

RECEIVED  
JAN 10 1954  
LIBRARY OF THE  
INDIAN CHEMICAL SOCIETY  
CALCUTTA

# JOURNAL OF THE INDIAN CHEMICAL SOCIETY



Published by The Indian Chemical Society  
10, Lawrence Road, Calcutta 20.





# Journal of the Indian Chemical Society

VOLUME LIX

NUMBER 7

JULY 1982

## CONTENTS

	<i>Pages</i>
Synthesis of Sulphur and Nitrogen Heterocycles Involving Rearrangement via Small Rings ..	815
B. D. TILAK	
FIR Studies of Copper(II) Monohaloacetates . Molecular Structure Based on Cu-O Vibrations	823
A. S. TYAGI and C. P. SRIVASTAVA	
Physicochemical Study of Some Transition Metal Complexes of Vanillin-sulphanilate	828
PURUSHOTTAM B. CHAKRAWARTI and PRAMILA KJANNA	
Studies on Some Polydentate Ligands. I	830
K. MUKKANTI, Y. K. BHON, K. B. PANDEYA and R. P. SINGH	
Equilibrium Study of the Mixed Complexes of Uranyl Ion with 3,5-Dinitrosalicylic as Primary and Some Substituted Carboxylic Acids as Secondary Ligands	833
D. N. SHELKE	
Studies on Hydrazones, Semicarbazones, Thiosemicarbazones and Oximes as Ligands. Part-III : Some Divalent Metal Complexes of Benzil Semicarbazone ...	836
R. C. MISRA, B. K. MOHAPATRA and D. PANDA	
Characterization of Alumina—A Versatile Catalyst	839
V. KRISHNASAMY and P. RATNASAMY	

**INDIAN CHEMICAL SOCIETY**  
**Dr. Acharya Prafulla Chandra Ray**  
**Calcutta 1900**

**Price of Publications :**

1. **Catalogue of Popular Chemical Standard Substances**  
Reprinted from Pure and Applied Chemistry, Vol. 20(1), 66-74 (1970)  
(With the kind permission of the International Union of Pure and Applied Chemistry.)  
Price : Rs. 4 (Inland, inclusive of postage)  
Rs. 8 (Foreign, inclusive of postage by Surface Mail)
  2. **Acharya Prafulla Chandra Ray : Life and Achievements**  
by Prof. N. R. Dhar :  
Price : Rs. 5 (Inland, inclusive of postage)  
Rs. 10 (Foreign, inclusive of postage by Surface Mail)
  3. **Reflections on Chemical Education** by Prof. N. R. Dhar :  
Price : Rs. 12.50 (Inland, inclusive of postage)  
Rs. 25.00 (Foreign, inclusive of postage by Surface Mail)
  4. **History of Chemistry in Ancient & Medieval India**  
Edited by Prof. P. Ray :  
Price : Rs. 30.00 (Inland, inclusive of postage)  
Rs. 75.00 (Foreign, inclusive of postage by Surface Mail)
  5. **Abstracts of XX-ICCC (held at Calcutta in December 1979)**  
Price : Inland : Rs. 325.00 (Inclusive of Regd. postage  
by Surface Mail)  
Foreign : Rs. 425.00 or U. S. \$ 50.00 (Inclusive of Regd.  
Air Mail postage).
  6. **Calcutta (A Tourist Guide Book)**  
Price : Inland : Rs. 15.00 (Inclusive of postage)  
Foreign : Rs. 25.00 (Inclusive of postage by Surface Mail)
- Annual Subscription (inclusive of postage) for the Journal of the Indian Chemical Society (for Non-Fellows) for 1982 :**  
Rs. 350.00 (Inland) ; Rs. 600.00 (Foreign)  
**Air Postage Extra.**
- Back Issues of the Journal of the Indian Chemical Society, and Indian Journal of Applied Chemistry (upto 1972 ; discontinued from January 1973) may be available, for which separate enquiries are to be made for availability and rates.**

**L. K. Ray**  
**Executive Secretary**

# Journal of the Indian Chemical Society

(62)

VOLUME LIX

NUMBER 7

JULY 1982

## CONTENTS

	<i>Pages</i>
Synthesis of Sulphur and Nitrogen Heterocyclics Involving Rearrangement via Small Rings ..	815
B. D. TILAK	
FIR Studies of Copper(II) Monohaloacetates . Molecular Structure Based on Cu-O Vibrations .	823
A. S. TYAGI and C. P. SRIVASTAVA	
Physicochemical Study of Some Transition Metal Complexes of Vanillin-sulphanilate .	828
PURUSHOTTAM B. CHAKRAWARTI and PRAMILA KHANNA	
Studies on Some Polydentate Ligands. I .	830
K. MUKKANTI, Y. K. BHOON, K. B. PANDEYA and R. P. SINGH	
Equilibrium Study of the Mixed Complexes of Uranyl Ion with 3,5-Dinitrosalicylic as Primary and Some Substituted Carboxylic Acids as Secondary Ligands ..	833
D. N. SHELKE	
Studies on Hydrazones, Semicarbazones, Thiosemicarbazones and Oximes as Ligands. Part-III : Some Divalent Metal Complexes of Benzil Semicarbazone ...	836
R. C. MISHRA, B. K. MOHAPATRA and D. PANDA	
Characterization of Alumina—A Versatile Catalyst	839
V. KRISHNASAMY and P. RATNASAMY	

	<i>Pages</i>
<b>Studies on the Suppression of Polarographic Maximum of Mn(II) by Some uni- and poly-valent Cations vis-a-vis Their Influence on the Kinetics of the Electrode Reaction of Mn(II)</b> ...	843
ASHOK KUMAR, KAILASH CHANDRA and MUKHTAR SINGH	
<b>Chemisorption Kinetic Studies of Oxygen on <math>V_2O_5</math>-<math>Ti_2O_3</math></b> ...	846
K. S. DE and K. GADGIL	
<b>Complexation of Salicylanilide with Some Metal Ions of Biological Interest</b> ...	853
R. SAHAI, S. AGRAWAL and S. S. S. KUSHWAHA	
<b>Melting Behaviour of Some Pure N-Acyl Amino Acids and Peptides</b> ...	856
VENKATARAMAN N. IYER, (Miss) GEETA N. SHETH and V. V. R. SUBRAHMANYAM	
<b>Properties of Pure Sodium Soaps of Saturated Fatty Acids</b> ...	860
(Miss) GEETA N. SHETH and V. V. R. SUBRAHMANYAM	
<b>Synthesis and Studies of Some New Phthal-as-Eins</b> ...	863
R. P. CHAMOLI, S. J. RAI and P. C. GUPTA	
<b>Synthesis of Some New Derivatives of Azlactone (Part I)</b> ...	867
M. A. EL-MAGHRABY and A. ABOU EL-ELA HASSAN	
<b>Synthesis of Pericarboxyl Lignans and Their Analogues</b> ...	869
P. W. AGNIHOTRI, V. R. PASARKAR and G. BAGAVANT	
<b>Synthesis of Aryloxy/Aryl Acetyl Thiosemicarbazides, Substituted 1,3,4-Oxadiazoles, 1,3,4-Thiadiazoles, 1,2,4-Triazoles and Related Compounds as Potential Fungicides</b> ...	877
R. S. SHARMA and S. C. BAHEL	
<b>Chemical Constituents of <i>Launaea nudicaulis</i> : C-13 Nuclear Magnetic Resonance Spectroscopy of Taraxasterenes and Pseudo-Taraxasterenes</b> ...	881
P. L. MAJUMDER and (Miss) SWAPNA LAHA	
<b>Study of Saponins from <i>Albizia lebbek</i> Benth Flowers</b> ...	884
I. P. VARSHNEY, D. C. JAIN and H. C. SRIVASTAVA	
<b>A New Reagent System for Photometric Analysis of Selenium in Complex Materials</b> ...	888
(Miss) A. BHATT and V. K. GUPTA	

# CONTENTS

## NOTES

	<i>Pages</i>
<b>Inorganic Coordination Complexes. Part-V : Complexes of Divalent Zinc, Cadmium and Mercury with Substituted Salicyl Hydrazines</b>	... 891
S. R. TEWARI, S. K. BAJPAL, S. K. MISRA, G. N. SHUKLA and V. N. MISRA	
<b>Spectral and Magnetic Studies of Some Mixed Ligand Complexes of High-Spin Cobalt(II)</b>	... 893
D. S. SANKHLA, R. C. MATHUR and SUDHINDRA N. MISRA	
<b>Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Chloro-2'-Methoxyaniline Complexes with La<sup>3+</sup>, Y<sup>3+</sup>, Nd<sup>3+</sup>, Dy<sup>3+</sup> and Gd<sup>3+</sup></b>	... 894
M. S. MAYADEO, S. S. PUROHIT and S. H. HUSSAIN	
<b>Polarographic Reduction of Uranyl(II) in Presence of Some Disubstituted Pyridines</b>	... 895
R. S. SINDHU, K. B. PANDEYA and R. P. SINGH	
<b>Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-Sulphamethoxazole Complexes with Cu<sup>2+</sup>, Ni<sup>2+</sup>, Co<sup>2+</sup>, Zn<sup>2+</sup> and Mg<sup>2+</sup></b>	... 896
M. S. MAYADEO and S. BHATTACHARJEE	
<b>Electrode Kinetics of the Polarographic Reduction of Ni(II) in the Presence of Increasing Concentrations of L-4-Hydroxyproline and L-Tryptophan</b>	... 897
J. C. KHATRI and MUKHTAR SINGH	
<b>Reactivity of Indian Rock Phosphates in Presence of Oxidative Degradation Products of Coal</b>	... 899
D. N. PATHAK	
<b>Triazolo [3,4-<i>b</i>] [1,3,4] thiadiazoles</b>	... 900
H. K. GAKHAR, ANJU JAIN and SHASHI BHUSHAN GUPTA	
<b>Synthesis and Antifungal Activity of Oxazolones</b>	... 901
M. R. MANRAO, R. C. SHARMA, B. S. DHIR and P. S. KALSI	
<b>Amoebicidal Testing of Drugs. Use of Goat Serum as a Substitute for Horse Serum for Growing <i>Entamoeba histolytica</i></b>	... 902
S. DUTTA, A. PAL, B. P. DEY and S. C. LAHIRI	
<b>Phytochemical Studies on <i>Eclipta alba</i></b>	... 905
B. C. SIKTORIA, S. J. SRIVASTAVA and G. S. NIRANJAN	
<b>Use of Potassium Bromate : Oxidation of Aldehydes</b>	... 905
HARAPRASAD SAMADDAR and AMALENDU BANERJEE	

# CONTENTS

	<b>Page</b>
<b>Potentiometric Determination of Niobium(V) in Presence of Tantalum in Non-Aqueous Media</b> ...	906
(Miss) PUSHPA SHARDA and G. C. SHIVAHARE	
<b>Determination of Equilibrium Constant of Ferric Formate Complex by Paper Electrophoresis</b> ...	907
H. G. MUKHERJEE and (Miss) ALOKA DEBI	
<b>Relative Stability of Formate Complexes by Paper Electrophoresis</b> ...	908
H. G. MUKHERJEE and (Miss) ALOKA DEBI	
<b>Solvent Extraction of Thorium with Liquid Cation Exchanger (Versatic 10)</b> ...	912
UDAY SANKAR RAY and SAGAR CHANDRA MODAK	

# AUTHOR INDEX

Agaihotri, P. W.	869	Mishra, R. C.	836
Agrawal, S.	853	Misra, S. K.	891
Bagavant, G.	869	Misra, Sudhindra N.	893
Babel, S. C.	877	Misra, V. N.	891
Bajpai, S. K.	891	Modak, Sagar Chandra	911
Banerjee, Amalendu	905	Mohapatra, B. K.	836
Bhatt, (Miss) A.	888	Mukherjee, H. G.	907,908
Bhattacharjee, S.	896	Mukkanti, K.	830
Bhoon, Y. K.	830		
Chakrawarti, Purushottam B.	828	Niranjan, G. S.	905
Chamoli, R. P.	863		
Chandra, Kailash	843	Pal, A.	902
De, K. S.	846	Panda, D.	836
Debi, (Miss) Alok	907,908	Pandeya, K. B.	830,895
Dey, B. P.	902	Pasarkar, V. R.	869
Dhir, B. S.	901	Pathak, D. N.	899
Dutta, S.	902	Purohit, S. S.	894
El-Maghraby, M. A.	867		
Gadgil, K.	846	Rai, S. J.	863
Gakhar, H. K.	900	Ratnasamy, P.	839
Gupta, P. C.	863	Ray, Uday Sankar	911
Gupta, Shashi Bhushan	900		
Gupta, V. K.	888	Sahai, R.	853
Hassan, A. Abou El-Ela	867	Samaddar, Haraprasad	905
Hussain, S. H.	894	Sankhla, D. S.	893
Iyer, Venkataraman N.	856	Sharda, (Miss) Pushpa	906
Jain, Anju	900	Sharma, R. C.	901
Jain, D. C.	884	Sharma, R. S.	877
Kahi, P. S.	901	Shelke, D. N.	833
Khanna, Pramila	828	Sheth, (Miss) Goeta N.	856,860
Khatr, J. C.	897	Shivahare, G. C.	906
Krishnasamy, V.	839	Shukla, G. N.	891
Kumar, Ashok	843	Sikroria, B. C.	905
Kushwaha, S. S. S.	853	Sindhu, R. S.	895
Laha, (Miss) Swapna	881	Singh, Mukhtar	843,897
Lahiri, S. C.	902	Singh, R. P.	830,895
Majumder, P. L.	881	Srivastava, C. P.	823
Manrao, M. R.	901	Srivastava, H. C.	884
Mathur, R. C.	893	Srivastava, S. J.	905
Mayadeo, M. S.	894,896	Subrahmanyam, V. V. R.	856,860
		Tewari, S. R.	891
		Tilak, B. D.	815
		Tyagi, A. S.	823
		Varshney, I. P.	884





# Journal of the Indian Chemical Society

VOLUME LIX

NUMBER 8

AUGUST 1982

## CONTENTS

	<i>Pages</i>
<b>Effect of Different Groups on Cyclopentadienyl Ring on the Stability of Titanium-Cyclopentadienyl Bond</b> ... ..	913
PURSHOTAM SONI, KAILASH CHANDRA, RAJENDRA K. SHARMA and BHAGAWAN S. GARG	
<b>Some Lanthanide-EDTA Ternary Complexes with Catechol, Resorcinol and Phloroglucinol</b> ... ..	916
S. N. LIMAYE and M. C. SAXENA	
<b>Metal Ion Interactions with the Constituents of Nucleic Acid. Part—1 : Metal-Adenine Complexes</b> ... ..	919
R. G. BHATTACHARYA and (Mrs.) I. BHADURI	
<b>Preparation and Characterization of Naphthoxides of Niobium(V) and Tantalum(V)</b> ... ..	922
K. C. MALHOTRA, (Miss) GESTA MATHUR, K. C. MAHAJAN and S. C. CHAUDHRY	
<b>Complexing Behaviour of N-Cyclo Hexyl Benzothiazole Sulphonamide with Cu(II), Mn(II), Ni(II), Co(II) and Fe(III)</b> ... ..	925
S. K. SRIVASTAVA, (Km.) ANITA VERMAN and (Km.) ACHLA GUPTA	
<b>Synthesis and Characterization of Complexes of Co(II), Cu(II), Cd(II), Mg(II) with Disubstituted Thioureas</b> ... ..	927
B. G. SAHA, R. P. BHATNAGAR and SAMIR K. BANERJI	
<b>Studies on Triortho-periodato Tetracobaltic(III) Acid. Part—II</b> ... ..	930
L. C. W. BAKER, H. G. MUKHERJEE and B. K. CHAUDHURI	
<b>Equilibrium and Formation Constants of Co(II), Ni(II) and Zn(II) Complexes of N-Benzoyl Phenyl Hydroxyl Amine in Various Mixed Aqueous Solvents</b> ... ..	934
A. E. CHAUDHURY and N. KOLB	

# CONTENTS

	Pages
Stability of Complexes of Co(II), Ni(II) and Cu(II) with Esters of Salicylic Acid ... ..	937
A GUPTA and B. S. PANNU	
Spectrophotometric Determination of Dissociation Constants of Violuric Acid and Stability Constant of its Cu(II) Complex ... ..	939
B. R. SINGH and R. GHOSH	
Molecular Complexes of Tetracycline and Oxytetracycline Drugs with Nucleic Acid Bases and Aromatic Amino Acids ... ..	941
J. LAHIRI and R. BASU	
Formation Constants of the Chelates of 2-Hydroxy-1-Naphthalidene- <i>ortho</i> -Fluoroaniline with Some Bivalent Metal Ions ... ..	949
M. S. MAYADBO, A. M. CHAUBAL and S. H. HUSSAIN	
Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-2',6'-Dimethylaniline Complexs with La <sup>3+</sup> , Y <sup>3+</sup> , Pr <sup>3+</sup> , Nd <sup>3+</sup> , Dy <sup>3+</sup> and Gd <sup>3+</sup> ... ..	952
M. S. MAYADBO, S. S. PUROHIT and S. H. HUSSAIN	
Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Hydroxyaniline Complexes with Mg <sup>2+</sup> , Co <sup>2+</sup> , Ni <sup>2+</sup> and Cu <sup>2+</sup> ... ..	955
M. S. MAYADBO and S. S. PUROHIT	
Studies on the Polarographic Reduction of Progesterone ... ..	958
(Miss) GUNJAN SRIVASTAVA and ARVIND KUMAR	
Polarographic Studies on the Effect of Some Ionic and Non-ionic Surfactants on the Kinetics of Irreversible Electrode Processes of Arylazopyrimidine and Arylazopyrazole .. ..	962
WAHID U. MALIK and RAJEEV JAIN	
4-(2-Pyridylazo) Resorcinol, A Sensitive Amperometric Reagent for Ultramicro Determination of Pr <sup>3+</sup> and Nd <sup>3+</sup> ... ..	965
S. C. LAVALLE and K. S. PITRE	
Structure of Faceted Naphthalene-Benzonic Acid Eutectic ... ..	968
P. S. BASSI, N. K. SHARMA and K. N. GOSWAMI	
Transformations of $\beta$ -Pinene over Platinum-Alumina Catalyst. Part—I : Influence of Contact Time, Temperature and Platinum Concentration ... ..	970
P. MATHUR, V. KRISHNASAMY and K. CHANDRASEKHARAN	

# CONTENTS

	<i>Pages</i>
<b>Aza Triterpenes—III : Action of Excess Hydrazoic Acid-Boron Trifluoride Etherate on 3-Oxo-Penta Cyclic Triterpenes</b> ... ..	975
T. SUNDARA RAMAIAH, S. K. RAMRAJ, CH. GOVARDHAN and V. VISHWANATH RAO	
<b>Synthesis of 3-Heteraryl Coumarins as Optical Brighteners</b> ... ..	977
D. ANNAPURNA, Y. D. REDDY and V. V. SOMAYAJULU	
<b>Free Acids in Lac Resin</b> ... ..	980
N. PRASAD, S. C. AGARWAL, J. N. CHATTERJEA and S. C. SENGUPTA	
<b>Paper Electrophoretic Separation and Estimation of the Constituents of Pyrolusite and Indian Coin (Cupro-nickel)</b> ... ..	984
H. G. MUKHERJEE and (Miss) ALOKA DEVI	
<b>NOTES</b>	
<b>Nickel(II) Complexes with Substituted Amino Benzothiazoles</b> ... ..	987
RAJENDRA P. MISRA and S. GURU	
<b>Complexes of Co(II), Ni(II), Cu(II), Zn(II), Cd(II) and Hg(II) with Chelating Bidentate Schiff's Base</b> ... ..	988
BEPIN B. MAHAPATRA, S. M. MAHAPATRA, S. K. PUJARI and A. CHIRANJEEVI	
<b>Binuclear Oxofluoro Complex of Quinquevalent Molybdenum</b> ... ..	990
M. C. CHAKRAVORTI, A. K. BERA and P. K. BHARADWAJ	
<b>Polymeric Metal Complexes of 5,5'-(<i>p</i>-phenylene-bisazo)-di-quinolin-8-ol</b> ... ..	991
VISHWANATH BANERJEE and ARUN K. DEY	
<b>Mixed Ligand Complexes of Zinc(II)</b> ... ..	992
P. C. PADHY and R. N. PATEL	
<b>Studies of ESR Spectra of Some Cu(II) Complexes</b> ... ..	994
NARAYAN S. BHAVE and R. B. KHARAT	
<b>Stability Constants and Thermodynamic Parameters of Neodymium(III) Complexes with Mandelic, Cinnamic and Phenylacetic Acids : A Polarographic Study</b> ... ..	996
FARID KHAN and A. V. MAHAJANI	

# CONTENTS

	Pages
<b>Studies on the Flow and Sedimentation Characteristics of Sodium Bentonite Suspensions in Presence of Electrolytes and Humic Acids</b> ... ..	998
K. D. GUPTA, SWAPAN NANDI, MUKHDEO and DIPAK GUHA	
<b>2-Aryl amino-4-[4'-(benzene sulphonamido)-phenyl]-thiazoles</b> ... ..	1000
V. H. PATIL and D. B. INGLE	
<b>Selective Methylation of Quercetin and Myricetin</b> ... ..	1001
LAL CHAND, R. MAURYA and A. B. RAY	
<b>Thiocarbamide as Dealkylating Agent : Debenzylation of Certain 2-S-Benzyl-1,5-diaryl-2,4-isodithiobiurets with Thiocarbamide</b> ... ..	1003
R. T. JADHAV and M. G. PARANJPE	
<b>Some Interesting Reactions of N-Phenyl-S-chloro isothiocarbamoyl Chloride</b> ... ..	1004
R. T. JADHAV and M. G. PARANJPE	
<b>Studies on 2-pyrazolin-5-one Derivatives</b> ... ..	1005
(Miss) P. MITRA, A. NAYAK and A. S. MITTRA	
<b>Flavonoids and other Constituents of <i>Indigofera hetrantha</i></b> ... ..	1007
ANILA THUSOO, NANCY RAINA and SHAKTI RAIS AHMED	
<b>Chemical Constituents of <i>Eucalyptus citriodora</i> Roots</b> ... ..	1008
RAMESHWAR DAYAL	
<b>Systematic Study of the Solvent Extraction of Metal-Tridentate Schiff Base Complexes</b> ... ..	1009
G. N. RAO and A. VARADARAJULU	
<b>Detection and Chromatographic Separation of Phenols on Papers Impregnated with Ferric Hydroxide</b> ... ..	1011
J. P. RAWAT, K. P. SINGH MUKTAWAT and ONKAR SINGH	
<b>Studies on 3-Oxo-Glutaric Acid Dianilide. Part—I : Acid-Base Properties</b> ... ..	1013
M. A. ZAYED, SALAH A. ABOU-TALEB and M. M. S. EL-MORSY	

# AUTHOR INDEX

Abou-Elsok, Salah A.	1018	Mahajan, K. C.	922
Agarwal, S. O.	980	Mahajani, A. V.	996
Ahmed, Shakti Bala	1007	Mahapatra, Bopin B.	988
Annapurna, D.	977	Mahapatra, S. M.	988
Baker, L. C. W.	980	Malhotra, K. O.	922
Banerji, Samir K.	927	Malik, Wahid U.	962
Banerji, Vishwanath	991	Mathur, (Miss) Geeta	922
Bassi, P. S.	908	Mathur, P.	970
Basu, R.	941	Maurya, R.	1001
Bera, A. K.	930	Maydeo, M. S.	949, 952, 955
Bhaduri, (Mrs.) I.	919	Misra, Rajendra P.	987
Bharadwaj, P. K.	980	Mitra, (Miss) P.	1006
Bhatnagar, R. P.	927	Mitra, A. S.	1005
Bhattacharyya, R. G.	919	Mukhdeo	988
Bhave, Namayan S.	994	Mukherjee, H. G.	980, 984
Chakravarti, M. C.	980	Nandi, Swapan	998
Chand, Lal	1001	Nayak, A.	1005
Chandra, Kailash	918	Padhy, P. C.	992
Chandrasekharan, K.	970	Panna, B. S.	987
Chatterjee, J. N.	980	Paranjpe, M. G.	1008, 1004
Chaubal, A. M.	949	Patel, R. N.	992
Chaudhry, S. C.	922	Patil, V. H.	1000
Chaudhuri, B. K.	980	Pitre, K. S.	986
Chaudhury, A. K.	984	Prasad, N.	980
Chiranjeevi, A.	988	Pujari, S. K.	988
Dayal, Ramachwar	1008	Purohit, S. S.	952, 955
Devi, (Miss) Aloka	994	Raina, Nancy	1007
Dey, Arun K.	991	Ramraj, S. K.	975
El-Moray, M. M. S.	1018	Rao, G. N.	1009
Garg, Bhagawan S.	918	Rawat, J. P.	1011
Ghosh, R.	989	Ray, A. B.	1001
Goswami, K. N.	968	Reddy, Y. D.	977
Govardhan, Ch.	976	Saha, B. G.	927
Guha, Dipak	998	Saxena, M. C.	916
Gupta, A.	987	Sengupta, S. C.	980
Gupta, (Km.) Achla	926	Sharma, N. K.	956
Gupta, K. D.	998	Sharma, Rajendra K.	918
Guru, S.	987	Singh, B. R.	989
Hussain, S. H.	919, 952	Singh, Onkar	1011
Ingle, D. B.	1000	Singh Muktawat, K. P.	1011
Jadhav, B. T.	1003, 1004	Somayajulu, V. V.	977
Jain, Rajeev	992	Soni, Purshotam	918
Khan, Farid	990	Srivastava, (Miss) Gunjan	958
Kharat, R. B.	994	Srivastava, S. K.	926
Kola, N.	984	Sundara Ramalaksh, T.	975
Krishnasamy, V.	970	Thussu, Anila	1007
Kumar, Arvind	968	Varadarajulu, A.	1009
Lahiri, J.	941	Verma, (Km.) Anita	925
Lavala, S. O.	985	Vishwanath Rao, V.	975
Lemaye, S. N.	916	Zayed, M. A.	1018





# Journal of the Indian Chemical Society

VOLUME LIX

NUMBER 9

SEPTEMBER 1982

## CONTENTS

	<i>Pages</i>
<b>Study of Transition and Non-Transition Metal Complexes with 3-Amino-2-Benzoylbenzofuran</b> ... ..	1017
N. V. HUGGI, M. B. HALLI and A. C. HIREMATH	
<b>Alkaline Earth Metal Complexes : Mixed Ligand Complexes of Some Organic Compounds of Magnesium with Nitrogen Donor Ligands</b> ... ..	1020
A. K. BANERJEE, SAILENDRA K. SINHA, MONOJIT K. GHOSH and S. K. ROY	
<b>Mixed Ligand Anionic Complexes of Cadmium(II)</b> ... ..	1022
BIPIN B. MAHAPATRA, D. PANDA, S. K. PUJARI and A. CHIRANJEEVI	
<b>Isolation, Characterisation and Antimicrobial Activity Studies of the Mixed Ligand Complexes of Cd(II) with 8-Hydroxy- quinoline and Various Salicylic Acids</b> ... ..	1024
Y. ANJANEYULU, R. PRABHAKARA RAO, R. Y. SWAMY, A. EKNATH and K. NARASIMHA RAO	
<b>Some Anionic Organotellurium Complexes</b> ... ..	1028
T. N. SRIVASTAVA, R. C. SRIVASTAVA and (Miss) M. SRIVASTAVA	
<b>Metal Derivatives of Organoantimony Compounds : Reactions of Anhydrous Chlorides of B(III), V(III) and Sn(IV) with Arylantimony Compounds</b> ... ..	1031
HEMANT K. SHARMA, S. N. DUBEY and D. M. PURI	
<b>A Study on Solid State Thermal Decomposition Characteristics of Some Metallo-organic Compounds. Part—I : Dehydration and Decarboxylation of Hydrated Calcium Salts of Pyridine Monocarboxylic Acids</b> ... ..	1034
S. GHOSH, S. K. RAY, P. K. RAY and T. K. BANDOPADHYAY	

# CONTENTS

Pages

<p><b>Stability Constants and Related Thermodynamic Functions of Some Rare-Earth Metal Complexes of Sodium 2-[4-Amino-3-(1,2,4-Triazolylazo)]Naphthol-4-Sulphonate</b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1038</p> <p style="text-align: center;">SURESH K. GARG, SUSHMITA MUKHERJEE, B. S. GARG and R. P. SINGH</p>
<p><b>Oxidation Studies. Part—XV : Ag(I)-Catalysis in Oxidation of Amines by Ce(IV) in Nitric Acid, A Kinetic Study</b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1040</p> <p style="text-align: center;">M. ANAND RAO, B. SETHURAM and T. NAVANEETH RAO</p>
<p><b>Studies in Triethylamine-Water. Part—IV : Predicting the Solubilities of Triethylamine and Water</b> .. ...</p> <p style="text-align: right; margin-right: 20px;">1044</p> <p style="text-align: center;">S. THANGAVEL and MATHEW J. MOOLEL</p>
<p><b>Studies on Electrolysis in a W-tube with Reference to Non-Faradaic Behaviour</b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1047</p> <p style="text-align: center;">SUBHALAKSHMI GHOSH and (Late) SANTI R. PALIT</p>
<p><b>Study of Dielectric Properties and Dipole Moments of Mn(II) Salts of Some Fatty Acids in Benzene Solutions</b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1050</p> <p style="text-align: center;">(Miss) LEEBA G. PARDESHI</p>
<p><b>Studies on the Interfacial Tension and Electrical Conductance of Oil/Water Emulsions Stabilized by Lignosulphonate of <i>Eucalyptus teriticornis</i></b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1053</p> <p style="text-align: center;">W. U. MALIK, S. K. SRIVASTAVA, TRILOK CHAND and A. K. JINDAL</p>
<p><b>Polarographic Studies on the Reduction of the Azomethine Bond in Aryl Thiosemicarbazides and the Determination of Hammett Parameters</b> . ...</p> <p style="text-align: right; margin-right: 20px;">1057</p> <p style="text-align: center;">WAHID U. MALIK, J. S. UPADHYAYA, RAJEEV JAIN and M. P. SHARMA</p>
<p><b>Polarographic Reduction of Some 5,6-Dimethylcyclohexane-2-Benzothiazolylhydrazono-1,3-Diones and its 2-Methyl, 4-Methyl, 4-Methoxy, 4-Ethoxy Derivatives</b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1060</p> <p style="text-align: center;">WAHID U. MALIK, (Miss) S. AGARWAL and RAJEEV JAIN</p>
<p><b>The Reaction of Potassium Permanganate with Potassium Ferrocyanide and Some Binary Mixtures in Presence of Fluoride Ions</b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1063</p> <p style="text-align: center;">H. A. DESSOKI, M. G. ALLAM and A. M. HAMMAM</p>
<p><b>Methylation of Phenol over Alumina in the Vapour Phase : Influence of Copper Sulphate</b> ... ..</p> <p style="text-align: right; margin-right: 20px;">1067</p> <p style="text-align: center;">V. KRISHNASAMY, T. V. SUBRAMANIAM and S. SOUNDARARAJAN</p>



# CONTENTS

	<i>Pages</i>
<b>Studies in Fluorinated 1,3-Diketones and Related Compounds.</b>	
<b>Part—XIV : Search for New NMR Shift Reagents</b> ... ..	1072
KRISHNA C. JOSHI, VIJAI N. PATHAK and (Miss) VINEETA GROVER	
<b>Synthesis of Some New Benzimidazoles as Antiamoebic Agents</b> ... ..	1074
VINAY S. MISRA, PRAMILLA SHAH and V. K. SAXENA	
<b>Synthesis of <math>\alpha</math>-Aminoadipic Acid</b> ... ..	1077
NASEEM H. KHAN, MOHD. ALI, H. PANDA and (Miss) RAKHSHINDA	
<b>High Content of Cholesterol in the Lipid of <i>Acacia farnesiana</i> Leaves</b> ... ..	1079
C. K. ANDHIWAL and KAMAL KISHORE	
<b>Amperometric Estimation of <math>\text{La}^{3+}</math> and <math>\text{Ce}^{3+}</math> with Cupferron using d.m.e.</b> ... ..	1081
K. S. PITRE and S. C. LAVALLE	
<b>Polarographic Determination of Stannous (tin) with Acrylic Acid</b> ...	1083
A. L. J. RAO and MAKHAN SINGH	
<b>Complex Formation of Vanadium(V) with Salicylhydroxamic Acid in MIBK : Photometric Methods of Determination of Vanadium in Alloy Steel and Ores</b> ... ..	1085
S. P. BAG, A. B. CHATTERJEE, A. K. CHAKRABARTI and P. R. CHAKRABORTY	

## NOTES

<b>Azo Complexes : Complexes of Alkali Metal Salts of Some Organic Acids with <i>o</i>-Hydroxybenzene-Azo-2-Naphthyl Amine</b> ... ..	1089
A. K. BANERJEE, TARKESHWAR SINGH and S. K. ROY	
<b>Interaction Products of Triphenylphosphine Oxide with Some Organotin Halides</b> ... ..	1090
K. K. BAJPAI and BEENA BAJPAI	
<b>Mixed Ligand Cobalt(III) Complexes Containing Benzotriazole or 5-Nitrobenzotriazole</b> ... ..	1092
L. K. MISHRA, HIMANSHU BHUSHAN and N. K. JHA	
<b>Mixed Ligand Complexes of <math>\text{Co(II)}</math>, <math>\text{Ni(II)}</math>, <math>\text{Cu(II)}</math> and <math>\text{Zn}</math> Salts with <i>o</i>-Hydroxy Propiophenone and Quinoline</b> ... ..	1094
R. N. ROY, S. B. MISHRA and B. K. MOHAPATRA	

# CONTENTS

	<i>Pages</i>
<b>Infrared Spectra and Thermal Studies of Some Reported Heteropoly Complexes</b> ... ..	1096
<b>S. K. ROY and P. P. JHA</b>	
<b>Potential Local Anaesthetic Agents. Part—III : Alkylaryl-amino- acetyl-2-aminothiazoles and Benzimidazoles</b> ... ..	1097
<b>J. S. UPADHYAYA, P. K. SRIVASTAVA and R. D. SHARMA (Late)</b>	
<b>Studies on Antitubercular Agents. Part—III : Preparation of Some p-(2,4-Diaryl-amino-6-S-Triazinyl-amino)-Benzaldehyde/ Acetophenone Thiosemicarbazones as Potential Tuberculostatic Agents</b> ... ..	1099
<b>N. A. LANGALIA and K. A. THAKER</b>	
<b>Studies on Antitubercular Agents. Preparation of 2-Arylamino-4- (4-Carboethoxyaniline)-6-Isonicotinylhydrazino-1,3,5-Triazine</b> ... ..	1101
<b>H. K. SHUKLA, N. A. LANGALIA, N. C. DESAI and K. A. THAKER</b>	
<b>Synthesis of Some New 1-Substituted 5-bromo-3-aryloxy acetyl hydrazono-2-indolinones as Potential Antibacterial Agents</b> ... ..	1102
<b>ANIL K. SEN GUPTA and ANITA RASTOGI</b>	
<b>Synthesis of Substituted 6-Pyrazolo and 6-Isoxazolo-Benzoxazoles and Their Physiological Activity</b> ... ..	1104
<b>M. SADASIVA SHANKAR, B. RAJESHWARA RAO, G. V. P. CHANDRA MOULI and Y. D. REDDY</b>	
<b>A Field Test for The Detection and Semiquantitative Determination of Sulphurdioxide in Air and Water</b> .. ...	1106
<b>(Miss) ABHA CHAUBE and V. K. GUPTA</b>	
<b>Spectrophotometric Determination of Aromatic Amines Using Catechol and Iodine</b> ... ..	1107
<b>C. S. PRAKASA SASTRY, B. G. RAO and K. V. S. S. MURTHY</b>	
<b>Spectrophotometric Determination of Palladium with Rubanic Acid in Presence of Piperidine, Quinoline, α-Picoline and Collidine</b> ... ..	1109
<b>M. B. SAHA and A. K. CHAKRABURTTY</b>	
<b>Oxalyldihydrazide : A New Reagent for Rapid Gravimetric Determination of Selenium</b> ... ..	1111
<b>ANIL K. BAVEJA and V. K. GUPTA</b>	
<b>Detection and Determination of Phosphate Using Monomethyl-p-Amidophenol as Reagent</b> ... ..	1113
<b>N. KRISHNA MURTY and A. V. SURVANARAYANA</b>	
<b>BOOK REVIEW</b>	1114

# AUTHOR INDEX

Agarwal, (Miss) S.	1080	Mouli, G. V. P. Chandra	1104
Ali, Mohd.	1077	Mukherjee, Sushmita	1088
Allam, M. G.	1088	Murthy, K. V. S. S.	1107
Andhiwal, O. K.	1079	Murty, N. Krishna	1118
Anjaneysulu, Y.	1024	Palit, (Late) Santi R.	1047
Bag, S. P.	1086	Panda, D.	1092
Bajpai, Beena	1090	Panda, H.	1077
Bajpai, K. K.	1090	Pardeshi, (Miss) Leela G	1080
Banerjee, A. K.	1020, 1089	Pathak, Vijai N.	1072
Bandyopadhyay, T. K	1094	Pitre, K. S.	1081
Baveja, Anil K.	1111	Pujari, S. K.	1022
Bhushan, Himanshu	1092	Puri, D. M.	1081
Chakrabarti, A. K	1085	Rakhshinda, (Miss)	1077
Chakraborty, P. R	1086	Rao, A. L. J.	1083
Chakraborty, A. K	1109	Rao, B. G	1107
Chand, Trilok	1053	Rao, B. Rajeshwara	1104
Chatterjee, A. B	1085	Rao, K. Narasimha	1024
Chauha, (Miss) Abha	1106	Rao, M. Anand	1040
Chiranjeevi, A.	1022	Rao, R. Prabhakara	1024
Desai, N. C	1101	Rao, T. Navaneeth	1040
Desoki, H. A.	1063	Rastogi, Anita	1102
Dubey, S. N.	1031	Rav P. K.	1084
Eknath, A.	1024	Ray, S. K.	1084
Garg, B. S.	1088	Reddy, Y. D.	1104
Garg, Suresh K	1088	Roy, B. N.	1094
Ghosh, Monjit K	1020	Roy, S. K.	1020, 1089, 1096
Ghosh, S.	1084	Saha, M. B.	1109
Ghosh, Subhalakshmi	1047	Sastry, C. S. Prakasa	1107
Grover, (Miss) Vineeta	1072	Saxena, V. K	1074
Gupta, V. K.	1106, 1111	Sen Gupta, Anil K.	1102
Halli, M. B.	1017	Sethuram, B.	1040
Hammam, A. M.	1063	Shah, Pramilla	1074
Hiremath, A. O.	1017	Shankar, M. Sadasiva	1104
Huggi, N. V.	1017	Sharma, Hemant K.	1081
Jain, Rajeev	1057, 1060	Sharma, M. P	1087
Jha, N. K.	1092	Sharma, (Late) R. D	1087
Jha, P. P.	1096	Shukla, H. K.	1101
Jindal, A. K.	1053	Singh, Makhan	1083
Joshi, Krishna C	1072	Singh, R. P.	1088
Khan, Naseem H.	1077	Singh, Tarkeshwar	1089
Kishore, Kamal	1079	Sinha, Sailendra K	1020
Krishnasamy, V.	1087	Soundararajan, S.	1067
Langalia, N. A.	1099, 1101	Srivastava, (Miss) M	1026
Lavale, S. C	1081	Srivastava, P. K.	1097
Malik, W. U.	1058	Srivastava, R. C.	1026
Malik, Wahid U.	1057, 1060	Srivastava, S. K.	1053
Mishra, L. K.	1092	Srivastava, T. N.	1028
Mishra, S. B.	1094	Subramaniam, T. V	1067
Misra, Vinay S.	1074	Suryanarayana, A. V	1118
Mahapatra, Bipin B.	1022	Swamy, R. Y.	1024
Mohapatra, B. K.	1094	Thaker, K. A.	1099, 1101
Moolal, Mathew J.	1044	Thangavel, S.	1044
		Upadhyaya, J. S.	1057, 1097



# Journal of the Indian Chemical Society

VOLUME LIX

NUMBER 10

OCTOBER 1982

## CONTENTS

	<i>Pages</i>
<b>Metal Complexes of Some Model Peptides. Part—I : Complex Formation of Cu(II) with N-Salicyloyl Glycine</b> ...	1117
G. N. MUKHERJEE, (Miss) S. SARKAR and S. K. CHATTERJEE	
<b>Stacked Ternary Complexes of Salicylanilide, Dithionon and Tryptophan with Co(II), Ni(II) and Cu(II)</b> ...	1121
R. SAHA, S. AGRAWAL and S. S. S. KUSHWAHA	
<b>Stabilisation of Molybdenyl Cations with 4,4'-Dimethyl 2,2'-Bipyridyl in Different Salt and Non-electrolytic Complexes</b> .. ...	1124
H. K. SAHA, S. S. MANDAL and P. C. GHORAI	
<b>Synthesis and Structural Studies of the Complexes of Zn(II), Ni(II), Cu(II) and Co(II) with 3-Aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazoles</b> . . . . .	1127
S. C. BAHTEL, B. L. DUBEY, N. NATH, A. TRIPATHI and J. K. SRIVASTAVA	
<b>Coordination Polymers of Terephthalaldehyde <i>bis</i>-(semicarbazone) with Some Bipositive Cations</b> ... ..	1130
BHAGWAT SINGH, P. L. MAURYA, B. V. AGARWALA and ARUN K. DEY	
<b>Stability and Related Thermodynamics of Chelation of Zn(II) with Thiodiacetic Acid (TDAA), Thiodipropionic Acid (TDPA), Iminodiacetic Acid (IDAA), Dithiodiacetic Acid (DTDAA) and Diglycollic Acid (DGA)</b> ... ..	1133
S. N. DUBEY, R. K. BAWEJA and D. M. PURI	
<b>Ion-exchange Equilibria of Na<sup>+</sup>-Ca<sup>2+</sup>/Cl<sup>-</sup> and Na<sup>+</sup>-Mg<sup>2+</sup>/Cl<sup>-</sup> from Concentrated Solution</b> ... ..	1136
L. D. DAVE and H. M. TRIVEDI	
<b>The Alkaline and Acid Hydrolysis of <i>n</i>-Butylacetate in Methanol-Water Mixtures</b> ... ..	1139
I. M. SIDAHMED, S. M. SALEM and F. M. ABDEL HALIM	

# CONTENTS

	Pages
Thermal Degradation of <i>p</i> -Anisic Acid-Formaldehyde Condensation Product	1145
RAMESH PATEL, RAJNI PATEL and KANTI PATEL	
Thermal Decomposition of Irradiated Strontium Nitrate	1147
S. M. K. NAIR, M. S. KRISHNAN and C. JAMES	
Isomerization of $\beta$ -Pinene in the Vapour Phase over Alumina Catalyst : Influence of Partial Pressure of Nitrogen and Pyridine	1151
V. KRISHNASAMY and P. RATNASAMY	
Vibrational Analysis of Glyoxal- $h_2$ - $d_2$ and $hd$	1155
A. NATARAJAN, P. KOLANDAIVELU and A. SAVARIANANDAM	
Behaviour of Vanadyl Porphyrin Complexes on TLC (Miss) S. CHAKRABORTY and V. K. BHATIA	1158
Kinetics of Chromic Acid Oxidation of Phenacyl Bromides ( $\omega$ -Bromoacetophenones)	1162
R. C. MOHAPATRA and N. C. KHANDUAL	
Synthesis of Some 3-Arylimino-5-( <i>N</i> -Methylanilino)- 1,2,4- $\Delta^4$ -Dithiazolines	1165
MOHAMMAD RAMZAN ALI and V. K. VERMA	
Preparation, Synthesis and Mass Spectral Studies of 3-( <i>p</i> -Nitrophenyl)-thiazolo-[2,3, <i>c</i> ][1,2,4]- triazepine Derivatives	1168
B. V. ALAKA, D. PATNAIK and M. K. ROUT	
Studies on Heterocyclic Compounds. Part—V : Synthesis and Antimicrobial Activities of <i>N</i> -Bridged Thiazole and Imidazole Derivatives	1170
S. N. DEHURI and A. NAYAK	
Synthesis of 3-( <i>p</i> -Fluoro)benzoylhydrazono-5-substituted- 2-indolinones as Potential Biologically Active Agents	1174
RAJENDRA S. VARMA and RAJNISH K. PANDEY	
Extraction and Spectrophotometric Determination of Vanadium(V) as Mixed Ligand Complexes of Various Hydroxy- amidines and Thiocyanate	1177
(Miss) ABHA RANI JHA and RAJENDRA KUMAR MISHRA	

# CONTENTS

	<i>Pages</i>
<b>NOTES</b>	
A Study of the Decomposition Patterns of Some Transition Metal Complexes Derived mainly from the Heterocyclic Ligands viz., Furan-2-carboxaldoxime and 3-Methyl-4-arylazopyrazole-5-one using Thermogravimetric Analysis ... ..	1180
(Mrs.) P. R. SHUKLA, CHANDRESHWARI SRIVASTAVA and V. K. SINGH	
Mixed Ligand Complexes of Zinc(II) with Dibasic Acids and Nitrogen Donor Ligands ... ..	1182
P. C. PADHY and R. N. PATEL	
Mixed Ligand Complexes of Cobalt(II) and Cadmium(II) with Oxine as Primary Ligand and Heterocyclic and Aromatic Amines as Secondary Ligands	1183
BIPIN B. MAHAPATRA and S. K. PUJARI	
Complexes of Cu(II), Ni(II), Cr(III), Mn(III) and Fe(III) with Schiff Base Derived from <i>Bis-p</i> (Aminophenyl) Sulphide and 2-Acetyl Thiophene Glyoxal ...	1184
H. S. VERMA, ANANG PAL, R. C. SAXENA and J. L. VATS	
Azo Complexes : Complexes of Alkali Metal Salts of Some Organic Acids with <i>o</i> -Hydroxybenzeneazo-2-Naphthol ... ..	1186
A. K. BANERJEE, TARKESHWAR SINGH and S. K. ROY	
Conductometric and Spectrometric Studies on Complexes of Ag(I) and Hg(II) Ions with N,N'-Diphenyl Thiourea	1187
B. SINGH, UMA SHANKAR PRASAD SHARMA and D. K. SHARMA	
Determination of Stability Constants of 2-Hydroxy-1-naphthalidene-sulphafurazole Complexes with La <sup>3+</sup> , Y <sup>3+</sup> , Pr <sup>3+</sup> , Nd <sup>3+</sup> , Gd <sup>3+</sup> , Dy <sup>3+</sup> .. ..	1189
M. S. MAYADEO and S. BHATTACHARJEE	
Conductance of KCl and NaCl in Sucrose + Water, Glucose + Water and Urea + Water Mixtures at Different Temperatures .. ..	1190
(Miss) S. MOHANTY and P. B. DAS	
Synthesis of Some 5-Arylazopyrimidine Derivatives ...	1192
V. K. MAHESH, VIRENDRA KUMAR and OM PRAKASH	
Search for New Hypoglycemic Agents. Part—VII : Coumarinylsulphonyl Ureas, Semicarbazides and Semicarbazones ... ..	1193
M. IMTIAZ HUSAIN, (Miss) KIRAN BALA GUPTA and R. C. SRIVASTAVA	

# CONTENTS

	<i>Pages</i>
Studies on Some Biologically Active Quinazolones. Synthesis of 2-phenoxyethyl-3-N-substituted Amino Carbonyl methyl-8-substituted 4(3H) quinazolones as Anticonvulsant Agents	1196
J. S. SHUKLA, SHRADHA SAXENA and RANJANA MISRA	
Synthesis of 1,2,4-Oxadiazolines Having Antifungal Activity	1197
MANGAT RAI and (Miss) BALJIT KAUR	
Chemical Examination of <i>Medicago sativa</i> Seeds	1198
S. P. SHRIVASTAVA and S. S. NIGAM	
Chemical Constituents of <i>Cephalotaxus griffithii</i>	1199
MOHD. KAMIL, NOOR AHMAD KHAN, IQBAL AHMAD, MOHD. ILYAS and WASIUR RAHMAN	
Selective Microgram Detection of Iron(III) on Ion Exchange Resin Beads	1200
SYED A. NABI, AHSAN R. SIDDIQUI, M. ATHAR and N. AHMAD	
Colorimetric Estimation of Ce(IV) by Phenothiazines	1201
R. T. SANE and A. B. AMBARDEKAR	
Spectrophotometric Determination of Ruthenium with Prochlorperazine Bismethanesulphonate	1201
H. SANKE GOWDA and A. THIMME GOWDA	
An Indirect Method for the Iodometric Microdetermination of Certain Organic Acids	1203
M. G. PATERIA and R. M. VERMA	
Obituary : Professor Priyadarshan Ray	1205
D. BANERJEA	





## INFORMATION FOR AUTHORS OF CONTRIBUTIONS AND PUBLISHERS OF BOOKS

1. Manuscripts for publication in the *Journal of the Indian Chemical Society* should be typed with double spacing on one side of good quality paper (Bond) with at least 3.5 cm margin on the left hand side and clear margin on all other sides; *the original and 2 carbon copies are to be submitted*. These should be addressed to the Honorary Editor, Indian Chemical Society, 92, Acharya Prafulla Chandra Road, Calcutta-700 009.

On the top right hand corner of the title page of the manuscript, the section (viz. Inorganic Chemistry, Physical Chemistry, Organic Chemistry, Analytical Chemistry, Biochemistry, Industrial Chemistry/Chemical Engineering, etc.) for which the communication is to be considered should be clearly indicated.

On receipt of a paper the author sending the paper shall be duly intimated of the Society's registration number for the manuscript which must be quoted by the author in all future correspondence on it to the Society. *All such future correspondence should be addressed to the Executive Editor.*

2. A paper will not be accepted for publication unless the author or at least one of the authors (in case of a contribution submitted jointly by more than one author) is a Fellow or a Member of the Indian Chemical Society of some category.

3. Original contributions to new chemical knowledge, both experimental and theoretical, in all the areas of Chemistry, are accepted for publication in the *Journal of the Indian Chemical Society*. Two types of contributions are considered for publication: *Articles* and *Notes*. Both categories should have sufficient information to permit repetition of the experimental work.

Contributions which have been published or accepted for publication in another journal or in any other freely available printed work will not be published in the *Journal of the Indian Chemical Society*. A declaration to that effect from the author must accompany a manuscript submitted for publication.

Authors are solely responsible for the factual accuracy of their contribution.

4. A prospective contributor should consult recent issues of this journal to get acquainted with its *contents* and *style*. Definitive accounts of significant completed studies presenting new important data or providing a fresh approach to an established subject should be submitted as *articles*. The presentation should be in a logical manner consistent with accuracy, clarity and brevity. The text should be divided into the following sections: (a) Introduction; (b) Experimental; (c) Results and Discussion; (d) References. Divisions within the sections should be indicated by sub-headings. Extensive review and unnecessary details of earlier work should be avoided. Well known or previously published procedures followed in the experimental work should only be referred to, omitting details. Important findings and results of much interest which may require priority in publication shall be considered for publication as *notes*.

Any portion of the text for which a special type of print is required must be indicated: *single underlining for italic type* and *double underlining for bold black type*.

The *title* of a contribution should tell accurately and clearly what the paper is about. The first letter of each noun and adjective in the title must be in *capital*. The title must be followed by the names of the authors and their addresses. The name of the senior author to whom correspondence may be made about the paper must be marked by an asterisk (\*). His present address, if different from that quoted as above, must be given in a foot-note.

Every article must be accompanied by an informative *abstract* that summarizes the principal findings of the work presented in the paper. Normally it should not be over 3 per cent of the length of the paper and should not exceed 250 words. It should be in a form that it may be used directly for publication in abstracting periodicals. This abstract should be typed before the main text and indented ca 2 cm to the right of it. *No such abstract is necessary for notes.*

5. The charge carried by an ion should be indicated in the following manner:  $\text{Na}^+$ ,  $\text{Cu}^{2+}$ ,  $\text{Co}(\text{NH}_3)_6^{3+}$ ,  $\text{Cl}^-$ ,  $\text{SO}_4^{2-}$ ,  $\text{Fe}(\text{CN})_6^{3-}$ , etc. Standard abbreviations should be used throughout the experimental section: e.g., m.p., b.p., sec, min, hr, mg, g, kg, mm, cm, cps, tlc, uv, ir, nm, etc. Analytical results should be reported in the form: (Found: N,.....; Cl, .....; Ni,..... Calcd. for.....; N, .. ; Cl,.....; Ni,..... %).

6. *Literature citations* should be numbered consecutively and these numbers are to appear as superscripts in appropriate positions in the text. Care must be exercised for uniformity in reference citations. "Ibid", "Idem", "et al", etc. should not be used. *Abbreviations for titles of journals must ordinarily conform to those used by the "Chemical Abstracts" published by the American Chemical Society (vide : "List of Periodical Abstracted")*. References to uncommon journals should also give corresponding references in *Chemical Abstract*. All the references must be typed in their serial order at the end of the text in the manuscript. The names (not surnames only) of all the authors should be given. A few sample citations are given below :

1. P. C. RAY, *J. Indian Chem. Soc.*, 1924, 1, 207.
2. R. J. KULA, D. T. SAWYER, S. I. CHAN and C. M. FINLEY, *J. Amer. Chem. Soc.*, 1963, 85, 2930.
3. C. S. GARNER and D. A. HOUSE in "Transition Metal Chemistry", (Ed.) R. L. CARLIN, Marcel Dekker, New York, 1970, Vol. 6, p. 59.

*Foot-notes* must be referred to in the text with suitable symbols such as \*, †, ‡, §, ¶, etc.

7. **Instructions for Diagrams and Figures** : The number of tables, diagrams and photographs should not be more than what is absolutely necessary, in view of the fact that the reproduction of such materials is very costly. If these exceed 20% of the pages of the text, authors may have to pay for the excess cost.

a. Figures should be numbered with Roman numerals and mentioned consecutively in the text indicating their respective locations. *All Figures must have legends and these should be typed out separately on a sheet of paper at the end of the main text of the manuscript. Legends should not duplicate information in the text.*

b. One set of the drawings should be made with India ink on tracing paper or good quality white drawing paper. *Graph paper should not be used.* Lines should contrast sharply with the back-ground. Most drawings should be planned for reproduction to a column width of 7.5 cm. Lettering should be large enough to be 1.5 mm high after reduction. Large drawings should be simplified for submitting with the manuscript, in a size which is reducible to not more than 16 cm × 22 cm. For satisfactory reproduction all drawings should be approximately twice the size in which they are to appear in the print. Use of legends in the body of the diagram must be reduced to the minimum. Free hand drawings and drawings unsuitable for block making cannot be accepted. If necessary the Editors may get the figures redrawn properly for which the actual cost is to be borne by the author(s). Structures and formulae which cannot be composed must also be submitted as suitable drawings for blockmaking.

c. If original tracings are not available, glossy prints of the tracings can be used if the back-ground is clear and the lines are distinct.

d. Photographs should be glossy black and white prints with sharp contrast. Paper clips mark the surface, and writing on the back of photos often punches through, spoiling the prints. *Photographs of equipment should be avoided.* Photomicrographs should be unmounted and should not be more than 7.5 cm wide.

8. *Reprints* shall be supplied only on receipt of payment of the usual charges, i.e., 50 reprints @ Rs. 15/- (U. S. \$ 5.00 for foreign) per page or part thereof, subject to a minimum charge of Rs. 35/- (U. S. \$ 12.50 for foreign). 100 reprints of 1-2 pages @ Rs. 50/- and for subsequent 2 pages or part thereof @ Rs. 40/-, next 100 reprints or part thereof at half the original rate. For foreign, 100 reprints @ U. S. \$ 8.00 per page or part thereof subject to a minimum U. S. \$ 20.00. Next 100 reprints or part thereof at half the original rate. *Additional postage is to be paid for Air Mail Charge. No free reprints are supplied and no such request can be entertained.* Reprint order form is sent to authors with the proof.

9. Books submitted for review in the *Journal of the Indian Chemical Society* must be sent in duplicate to the Honorary Editor, Indian Chemical Society, 92, Acharya Prafulla Chandra Road, Calcutta-700 009, so that one copy may be retained in the Library of the Indian Chemical Society, while the other copy may be retained by the reviewer for his personal use.

**In case of rejection of a paper, the opinion of the Honorary Editor shall ordinarily be treated as final,**

# AUTHOR INDEX

Agarwala, B. V.	1180	Nabi, Syed A.	1200
Agarwal, S.	1121	Nair, S. M. K.	1147
Ahmad, Iqbal	1199	Natarajan, A.	1155
Ahmad, N.	1200	Nath, N.	1127
Alaka, B. V.	1168	Nayak, A.	1170
Ali, Mohammad Ramzan	1165	Nigam, S. S.	1198
Ambardekar, A. B.	1201	Padhy, P. C.	1182
Athar, M.	1200	Pal, Anang	1184
Bahel, S. C.	1127	Pandey, Rajulsh K.	1174
Banerjee, D.	1205	Patel, Kanti	1145
Banerjee, A. K.	1186	Patel, R. N.	1182
Baweja, R. K.	1183	Patel, Rajni	1145
Bhatia, V. K.	1158	Patel, Ramesh	1145
Bhattacharjee, S.	1189	Pateria, M. G.	1203
Chakraborty, (Miss) S.	1158	Pattnaik, D.	1168
Chatterjee, S. K.	1117	Prakash, Om	1192
Das, P. B.	1190	Pujari, S. K.	1188
Dave, L. D.	1186	Puri, D. M.	1188
Dehuri, S. N.	1170	Rahman, Wasir	1199
Dey, Arun K.	1180	Rai, Mangat	1197
Dubey, B. L.	1127	Ramasamy, P.	1151
Dubey, S. N.	1183	Rout, M. K.	1168
Ghorai, P. C.	1124	Roy, S. K.	1186
Gowda, A. Thimme	1201	Saha, H. K.	1124
Gowda, H. Sanke	1201	Sahai R.	1127
Gupta, (Miss) Kiran Bela	1193	Salem, S. M.	1189
Halim, F. M. Abdel	1189	Sane, R. T.	1201
Hussain, M. Imtiaz	1193	Sarker, (Miss) S.	1117
Ilyas, Mohd.	1199	Savarinandam, A.	1155
James, C.	1147	Saxena, R. C.	1184
Jha, (Miss) Abha Rani	1177	Saxena, Shradha	1196
Kamli, Mohd.	1199	Sherma, D. K.	1187
Kaur, (Miss) Baljit	1197	Sharma, Uma Shanker Prasad	1187
Khan, Noor Ahmad	1199	Shrivastava, S. P.	1196
Khandwal, N. C.	1182	Shukla, J. S.	1196
Kolandaivelu, P.	1155	Shukla, (Mrs.) P. R.	1180
Krishnan, M. S.	1147	Siddiqui, J. M.	1199
Krishnasamy, V.	1151	Siddique, Ahsan R.	1200
Kumar, Virendra	1192	Singh, B.	1187
Kushwaha, S. S.	1121	Singh, Bhagwat	1190
Mahapatra, Bipin B.	1188	Singh, Tarkeshwar	1186
Mahesh, V. K.	1192	Singh, V. K.	1180
Mandal, S. S.	1124	Srivastava, Chandreshwari	1180
Maurya, P. L.	1180	Srivastava, J. K.	1197
Maydeo, M. S.	1189	Srivastava, R. C.	1193
Mishra, Rajendra Kumar	1177	Tripathi, A.	1127
Misra, Ranjana	1195	Trivedi, H. M.	1186
Mohanty, (Miss) S.	1190	Varma, Rajendra S.	1174
Mohapatra, R. C.	1192	Vat, J. L.	1184
Mukherjee, G. N.	1117	Verma, H. S.	1184
		Verma, R. M.	1203
		Verma, V. K.	1165



**J. Indian Chem. Soc.; Vol. LIX, No. 11-12, Pp. 1209—1494**

**November, December 1982**

**CODEN : JICSAH LIX, (11-12) (1982), 1209—1494**

**JOURNAL**

**OF THE**

**INDIAN**

**CHEMICAL**

**SOCIETY**

**PROFESSOR ARUN K. DEY 60TH BIRTHDAY COMMEMORATION ISSUE**



**Published by The Indian Chemical Society**

**92, Acharya Prafulla Chandra Road**

**Calcutta-700 009**



**Professor Arun Kumar Dey**

**M Sc , D Phil , D Sc , F N A Sc**

**Professor of Chemistry, University of Allahabad ; President, Section of Chemistry, 57th Indian Science Congress, 1970 ; General Secretary, Indian Science Congress Association, 1980-83 ; Vice-President, Indian Chemical Society, 1980 & 1981 ; Acharya P. C Ray Memorial Awardee**

# P R E F A C E

On the occasion of his sixtieth birthday, the former students, colleagues and associates in research of Professor Arun K. Dey felicitated him on 20th October 1982 in a function organised in the Vizianagaram Hall of the University of Allahabad. Professor U. N. Singh, Vice-Chancellor of the University presided and Professor S. Ghosh, former Head of the Department of Chemistry, Universities of Allahabad and Jabalpur, was the Chief Guest. A souvenir volume was presented to Professor Dey on behalf of the Felicitations Committee by Professor R. C. Kapoor of Jodhpur University. The Felicitations Committee is indebted to the Council of the Indian Chemical Society for dedicating this issue of the Journal of the Indian Chemical Society to Professor Arun K. Dey as a tribute to his services to the cause of Chemistry and Science Education in the country.

This special number of the journal contains invited articles from distinguished workers from various countries, and we are sincerely thankful to the authors for responding favourably to our invitation. We are grateful to Professor S. Ghosh, Professor R. D. Tiwari and Professor H. L. Nigam for their kindness in going through the manuscripts.

The Felicitations Committee deeply appreciate the active interest taken by Professor S. K. Talapatra, Honorary Secretary and the cooperation received from Dr. S. K. Roy, Executive Editor.

**R. Prasad**

*Chairman,*

*Prof. A. K. Dey*

*Felicitations Committee*

**Dr. A. K. Ghose**

**Dr. H. H. Misra**

**Dr. A. Mahan**

**Dr. V. S. Tripathi**

**Dr. M. C. Chattopadhyaya**

**B. V. Agarwala**

*Convener,*

*Prof. A. K. Dey*

*Felicitations Committee*

*Organising Secretaries,*

*Prof. A. K. Dey*

*Felicitations Committee*

# Journal of the Indian Chemical Society

VOLUME LIX

NUMBER 11, 12

NOVEMBER, DECEMBER 1982

## CONTENTS

	<i>Pages</i>
Training and Research in Analytical Chemistry · An Interdisciplinary Science ... R. C. MEHROTRA	1209
Teaching Microchemistry in Industry Versus Teaching in a University AL STEYERMARK	1213
Some Interesting Aspects of the Chemistry of Platinum JOHN C. BAILAR, JR.	1214
Intramolecular $\pi$ - $\pi$ Interactions in Metal "Capped" Porphyrins P. N. VENKATASUBRAMANIAN and F. BASOLO	1218
Chaotropic Ions and Acid Buffers as Eluents in Ligand Purification Using Semiautomated Affinity Chromatography R. PRASAD and S. T. NERENBERG	1220
Biochemical Fuel Cells GIRJESH GOVIL and ANIL SARAN	1226
Metal Ammine Formation in Solution. Part—XXIII : The Nickel(II)-Mono- and Diethanolamine Systems JANNIK BJERRUM and PREDRAG DJURDJEVIC	1229
The Rare Earths. Part—XCII : Chelating Tendencies of 1-Methoxy-2,4-pentanedione DEAN F. MARTIN, THERALD MOELLER and WILLIAM J. RANDALL	1232
Coordination of Al(III), Be(II) and Cu(II) Ions with 1,7-Dihydroxy- 4-sulfo-2-naphthoic and 3,5-Dihydroxy-7-sulfo-2-naphthoic Acids in Aqueous Sodium Perchlorate Medium LAURI H. J. LAJUNEN	1238
A New Parameter in Astatistical Stabilization of Ternary Complexes P. K. BHATTACHARYA and V. K. PATEL	1244



# CONTENTS

	<i>Pages</i>
<b>Compatibility of Nitrilotriacetic Acid and 3-Acetyl-4-Hydroxy-6-Methyl-2-Pyrone in the Coordination Sphere of Lanthanum Ions</b>	... 1247
R. K. KADIAN, B. S. GARG and R. P. SINGH	
<b>The Oxidation of Optically Active 3,4-Dihydroxyphenylalanine by Optically Active Cobalt(III) Complexes</b>	... 1250
YUZO YOSHIKAWA and KAZUO YAMASAKI	
<b>Optical Inversion of the <i>cis</i>(NO<sub>2</sub>), <i>trans</i>(N), <i>cis</i>(O)-bis(Aminocarboxylato)dinitrocobaltate(III) Ion</b>	... 1255
MILENKO B. ČELAP, LIJERKA J. ALJANČIĆ and TOMISLAV J. JANJIĆ	
<b>The Deuterium Isotope Effect on the Pfeiffer Effect in Optically Labile Coordination Compounds</b>	... 1259
STANLEY KIRSCHNER and JOANNE GABAY	
<b>Coordination Chemistry of Technetium as Related to Nuclear Medicine</b>	... 1262
S. C. SRIVASTAVA and P. RICHARDS	
<b>Mass Spectrometry of Transition Metal <math>\pi</math>-Complexes. Part—VII. A Study of the Behaviour of Some Ruthenocene Derivatives</b>	... 1270
REG DAVIS and DESMOND J. O'RFARDON	
<b>Molecular Orbital Study of [BFe(CO)<sub>5</sub>]<sup>+</sup>, B = (C<sub>5</sub>H<sub>5</sub>), (C<sub>5</sub>H<sub>7</sub>) and (C<sub>7</sub>H<sub>9</sub>)</b>	... 1273
D. A. BROWN, J. P. CHESTER and N. J. FITZPATRICK	
<b>NMR Spectroscopy of Oriented Organoselenium Compounds</b>	... 1276
C. L. KHETRAPAL	
<b>ESR Study of Cu(II)-N-Aryl Glycinates</b>	... 1280
L. J. BAI, Z. F. WANG and Y. T. CHEN	
<b>Infrared Spectra of Iron(II) Complexes with N,N-Dimethylformamide and N,N-Dimethylthioformamide</b>	1284
W. LINERT and V. GUTMANN	
<b>Synthesis and Characterisation of <math>\mu</math>-Oxobis[oxotetrachlororhenates (VI)]</b>	1287
V. YATIRAJAM and (Miss) M. LAKSHMI KANTAM	
<b>Synthesis of <i>p</i>-Phenylene-di-Acrylyl-Bis-N-Phenyl (PAPHA), Fumaryl-Bis-N-Phenyl (FPHA), Isophthalyl-Bis-N-Phenyl (IPHA) Hydroxamic Acids and Spectral and Magnetic Studies of their Polymers with Mn(II), Fe(II), Co(II), Ni(II), Cu(II) and Zn(II)</b>	... 1290
(Miss) N. R. GANDHI and K. N. MUNSHI	
<b>Anthranilic Acid Hydrazide Complexes of Aluminium(III) and Titanium(IV)</b>	... 1296
A. K. NARULA, B. SINGH and R. N. KAPOOR	

# CONTENTS

	<i>Pages</i>
<b>Determination of Zinc with Cupric Ion-Selective Electrode and its Analytical Application in Fertilizers</b>	... 1352
LILIANA ILCHEVA, MARIA POLIANOVA, VICTORIA ADEWUYI and PESHO BOZADZIEV	
<b>Floatable Ion Associates Formed in the System Iridium(III)-Tin(II)-Chloride-Basic Dye</b>	... 1354
Z MARCZENKO and K. KALINOWSKI	
<b>A Simple Deviation Function to Summarize Data in Solvent Mixtures. The Standard Oxidation Potential of the Silver Chloride Electrode in Water-Ethylene Glycol Mixtures</b>	... 1357
ERIK HOGFELD <sup>1</sup>	
<b>Alkaloids of <i>Mitragyna parvifolia</i> (Roxb) Korth. and their Transformation</b>	... 1360
A. CHATTERJEE, K. P. DHARA and J. BANERJI	
<b>Alkaloids of <i>Machilus glaucescens</i> Wight. Machigline, A New Phenolic Oxoaporphine Alkaloid</b>	... 1364
(MRS ) BANI TALAPATRA, SHYAMAPROSAD GOSWAMI, ARINDUM GHOSH and SUNIL K. TALAPATRA	
<b>Structure and Synthesis of Mukoline and Mukolidine, Two New Carbazole Alkaloids from <i>Murraya koenigii</i> Spreng.</b>	... 1369
SHYAMALI ROY, LINA BHATTACHARYYA and D. P. CHAKRABORTY	
<b>Synthesis of Pyrano/Pyrido Benzothiophene Derivatives. Part—I</b>	... 1372
J. N. CHATTERJEA and RADHIKA P. SAHAI	
<b>Some Aspects of the Chemistry of Fluorinated 1,3-Diketones</b>	... 1375
KRISHNA C. JOSHI	
<b>Restricted Rotation. Part—IV : Determination of Barrier to Rotation Around Some Crowded C-C and C-N Bonds by Dynamic Nuclear Magnetic Resonance</b>	... 1379
D. NASIPURI, N. P. DAW, S. BANERJEE and MITA DATTA GUPTA	
<b>Polymerization of Methacrylamide Initiated by Ceris Ion-Malic Acid Redox System</b>	... 1384
G. S. MISRA and J. I. KHATIB	
<b>Formylcamphor Condensed with Diamines : The Structure in Solution as Obtained from UV Absorption and Circular Dichroism Spectroscopy</b>	... 1387
HANS PETER JENSEN	
<b>Thermodynamics of Ferrous-1,10-Phenanthroline in <i>t</i>-Butanol-Water and Glycerol-Water Media at 25°</b>	... 1390
A. K. MANDAL, S. BANDYOPADHYAY and S. ADITYA	

# CONTENTS

	<i>Pages</i>
<b>Photocorrosion</b>	... 1393
<b>K. L. CHENG</b>	
<b>Spectrophotometric Study of the Reaction of Chromium(VI) with Fluphenazine Hydrochloride</b>	.. 1398
<b>H. SANKU GOWDA and J. B. RAO</b>	
<b>Spectral Studies of Polymeric Metal Complexes with Schiff Bases of Terephthalaldehyde and Hydrazides</b>	... 1400
<b>P. L. MAURYA, C. P. DUBE and B. V. AGARWALA</b>	
<b>Peptide Models for the Metal-Binding Sites of Proteins and Enzymes</b>	... 1403
<b>BIBUDHENDRA SARKAR</b>	
<b>Separation of Th(IV) in Aqueous Glycine Medium by Cation Exchange Chromatography</b>	... 1412
<b>LALIT C. T. EUSEBIUS, ASHOK MAHAN and ANIMESH K. GHOSH</b>	
<b>Effect of Substituents on the Relative Stabilities of Fe(III) Complexes of Substituted Salicylic Acids</b>	... 1416
<b>M. C. CHATTOPADHYAYA</b>	
<b>Computations of Apparent Formation Constants and Free Metal Ions in EGTA or EDTA Buffer Systems. Part—I : Effects of pH and Metal Concentration with Respect to Ligand</b>	.. 1419
<b>S. D. BISWAS and F. S. CHEBIB</b>	
<b>Fe(III), Co(III), Cu(II) and Ni(II) Derivatives of Some New Monothio-<math>\beta</math>-Diketones</b>	... 1424
<b>S. K. SAINI, V. D. GUPTA and R. C. MEHROTRA</b>	
<b>Formation Constants and Thermodynamic Parameters of 2-Amino-3-hydroxypyridine with Some Bivalent Metal Ions</b>	... 1427
<b>H. L. KALRA, J. S. MALIK and (Miss) VERSHA GERA</b>	
<b>Tetravalent Manganese as an Oxidising and Decomposing Agent</b>	... 1430
<b>S. B. RAO and B. R. SANT</b>	
<b>ERRATA</b>	... 1431
<b>INDEX</b>	... 1433



# AUTHOR INDEX

Adewuyi, Victoria	1352	Högfeldt, Erick	1357
Aditya, S.	1390	Iloheva, Lilliana	1352
Agarwal, Anita	1316	Janjić, Tomislav J.	1255
Agarwala, B. V.	1400	Jensen, Hans Peter	1387
Aljančić, Ljerka J.	1255	Joshi, Krishna C.	1375
Bahl, O. P.	1306	Kadian, R. K.	1247
Bai, L. J.	1280	Kalinowski, K.	1354
Bailar, Jr., John C.	1214	Kalra, H. L.	1427
Bandyopadhyay, S.	1390	Kantak, U. N.	1300
Banerjee, A. K.	1303	Kapoor, R. C.	1313
Banerjee, S.	1379	Kapoor, R. N.	1296
Banerji, J.	1360	Khatib, J. I	1384
Basolo, F.	1218	Khetrapal, C.L	1276
Bhattacharya, P. K.	1244	Khopkar, S. M	1346
Bhattacharyya, Lina	1369	Kiran, H. V.	1310
Bhushan, R.	1316	Korkisch, J	1331
Biswas, A. B.	1310	Kratzer, K.	1329
Bliswas, S. D.	1419	Krischner, Stanley	1259
Bjerrum, Jannik	1229	Lajunen, Lauri H. J.	1238
Bommannavar, A. S	1310	Lakshmi Kantam, (Miss) M.	1287
Bozadziev, Pesho	1352	Linert, W.	1284
Brown, D. A.	1273	Mahan, Ashok	1412
Ćelap, Milenko B.	1255	Malik, J. S.	1427
Chakrabarty, D. K.	1310	Malik, W. U	1316
Chakraborty, D. P.	1369	Mandal, A. K.	1390
Chatterjea, J. N.	1372	Manocha, L. M	1306
Chatterjee, A.	1360	Marczenko, Z.	1354
Chattopadhyaya, M. C.	1416	Martin, Dean F.	1232
Chebib, F. S.	1419	Mathur, K. C. K.	1313
Chen, Y. T.	1280	Mathur, R. B.	1306
Cheng, K. L.	1393	Maurya, P. L.	1400
Chester, J. P.	1273	Mehrotra, R. C.	1209, 1424
Datta Gupta, Mita	1379	Misra, G. S.	1384
Davis, Reg	1270	Moeller, Therald	1232
Daw, N. P.	1379	Munshi, K. N	1290
De, Anil K.	1334	Murty, M. V. N.	1343
Dhami, T. L.	1306	Narula, A. K	1296
Dhara, K. P.	1360	Nasipuri, D.	1379
Dju-djevic, Predrag	1229	Nerenberg, S. T.	1220
Dube, C. P.	1400	O'Reardon, Desmond J.	1270
Eusebius, Lalit C. T.	1412	Parhi, Narahari	1334
Fitzpatrick, N. J	1273	Patel, V. K.	1244
Gabay, Joanne	1259	Patil, S. R.	1300
Gaikwad, A. G.	1346	Pollanova, Maria	1352
Gandhi, (Miss) N. R.	1290	Prasad, Dharmbir	1303
Garg, B. S.	1247	Prasad, R.	1220
Gera, (Miss) Versha	1427	Prašilova', J.	1329
Ghose, Animesh K.	1412	Raj, J. B.	1398
Ghosh, Arindum	1364	Randall, William J.	1232
Goswami, Shyamaprosad	1364	Rao, S. B.	1430
Govil, Girjesh	1226		
Gowda, H. Sanke	1398		
Gupta, V. D.	1424		
Gutmann, V.	1284		

Rao, V. M.	1343	Singh, R. P.	1247
Ray, Uday S.	1334	Srivastava, S. C.	1262
Richards, P.	1262	Staniek, H.	1331
Roy, S. K.	1303	Stary', J.	1329
Roy, Shyamali	1369	Steffan, I	1331
		Steyermark, Al	1213
Sahal, Radhika P.	1372		
Saini, S. K	1424	Talapatra, (Mrs.) Bani	1364
Sant, B. R.	1430	Talapatra, Sunil K.	1364
Saran, Anil	1226	Tandon, S. N.	1338
Sarkar, Bibudhendra	1403	Thomas, J. D R.	1323
Sastri, M N	1343		
Sen, D. N.	1300	Venkatasubramanian, P. N.	1218
Seth, R. L.	1306		
Sindal, R. S.	1313	Wang, Z. F.	1280
Singh, B.	1296		
Singh, Devendra	1338	Yamasaki, Kazuo	1250
Singh, O. V.	1338	Yatirajam, V.	1287
		Yoshikawa, Yuzo	1250

# Synthesis of Sulphur and Nitrogen Heterocyclics Involving Rearrangement *Via* Small Rings\*

B. D. TILAK

Indian Institute of Education, Pune-411 029

IT is indeed a great honour to be called upon to deliver the Acharya Prafulla Chandra Ray Memorial Lecture (1978). I am grateful to the Indian Chemical Society for conferring on me this distinction.

Acharya Ray not only founded the Indian Chemical Society but was also the father of Indian Chemistry and Chemical Industry. I pay my humble homage to this great man to whom the nation owes so much.

In this lecture, I wish to briefly cover my work over the last twenty years, pertaining to the synthesis of sulphur and nitrogen heterocyclics, wherein we came across rearrangements which could be rationally explained by postulating the involvement of small (three or four membered) sulphur and nitrogen ring systems. In a few cases compounds representing these small ring systems were also isolated or

synthesised and then isomerized to five and six membered heterocyclics in a two step sequence.

The general method of synthesis of sulphur and nitrogen heterocyclics involved cyclodehydration of suitably substituted ketones or carbinols where the carbonyl and hydroxyl groups involved in the cyclodehydration reaction were removed from the hetero atom by one or two carbon atoms (*via* a methylene, dimethylene group or a double bond). The end products were the expected cyclodehydration products as well as the rearrangement products where the substituents attached to the carbonyl/hydroxyl group carrying carbon atoms and those attached to the carbon atoms linked directly to the hetero atom in the aliphatic chain were found to be interchanged. The general scheme of these reactions is shown in Chart 1. Synthesis of other sulphur/nitrogen heterocyclics arising out of the general schemes shown in Chart 1 are also described.

*Synthesis of 5-membered sulphur heterocyclics via thiiranium salts:*

Cyclodehydration of phenacyl phenyl sulphide 1 and its derivatives, (by treatment with PPA) was reported earlier<sup>1</sup> to give mostly 2-phenylthionaphthene 2. We however showed that the reaction gave both the 2-phenyl 2 (47%) as well as 3-phenylthionaphthene 3 (15%)<sup>2</sup>. Earlier reports<sup>1</sup> on cyclodehydration of phenacyl *p*-toluyl sulphide 4





CHART 2

\* Acharya Prafulla Chandra Ray Memorial Lecture (1978) delivered under the auspices of the Indian Chemical Society at Pune on 21st December, 1981.

were likewise revised by us<sup>8</sup> to show that the reaction gave both the expected 5-methyl-3-phenylthionaphthene 5 (25%) as well as the rearranged 5-methyl-2-phenylthionaphthene 6 (36%). The formation of the rearranged cyclodehydration products 2 and 6 in the above reactions was explained by us by postulating the intermediate formation of the three-membered sulphur heterocyclic intermediate, a thiiranium salt 7 which then ring expands in two alternative ways to yield the two sets of thionaphthenes 3, 5, (normal products) and 2, 6, (rearranged products)<sup>8</sup> (Chart 2).

Similarly, cyclodehydration of 2-thionaphthacyl phenyl sulphide 8 with  $P_2O_5$  or PPA gave both the normal cyclodehydration product 2,3'-dithionaphthyl 9 as well as 2,2'-dithionaphthyl 10<sup>8</sup> which probably arises by rearrangement *via* the relevant thiiranium salt reactive intermediate 11 (Chart 3).




Chart 3

Several more such rearrangements were also reported by us during the cyclodehydration of other




Chart 4

arylmethyl aryl sulphides<sup>4,7</sup>. Most of them led to two sets of arylthionaphthenes, one the normally expected cyclodehydration product and the other the rearrangement product (Chart 4). These rearrangements could also be explained on the basis of involvement of reactive thiiranium salts as reactive intermediates.

It is interesting to note that cyclodehydration of  $\alpha$ -phenylmercaptopropiophenone 26 with PPA gave only the normally expected 3-phenyl-2-methylthionaphthene 27 and the rearranged product 2-phenyl-3-methylthionaphthene 28 could not be traced<sup>4</sup>. However, in the light of more sophisticated techniques of analysis and separation now available it is desirable to re-examine these results (Chart 5).




Chart 5

The above rearrangements, observed during cyclodehydration of arylmethyl aryl sulphides, have also been found to occur in the acid catalysed cyclodehydration of arylmethyl aryl ethers and arylmethylarylamines (or secondary amines) 29 where also both the normally expected benzofurans and indoles 30 and the rearranged cyclodehydration products 31 are formed<sup>6,7</sup> (Chart 6). Several other rearrangement reactions in the synthesis of benzo-*b*-thiophenes during acid-catalysed cyclodehydrations of relevant keto-sulphides are also reported<sup>8</sup>. All these rearrangements probably occur through three-membered sulphur 7, oxygen (32,  $X_1 = -\overset{+}{O}=$ ) and nitrogen (32,  $X_1 = -\overset{+}{N}=$ ) heterocyclic rings (Charts 2, 6).




Chart 6

The involvement of a thiiranium salt 33 and N,N-dialkylaziridinium salt 34 is widely recognized in explaining the biological activity (as alkylating agents) of mustard gas and nitrogen mustards. We had also suggested the possible involvement of



thiiranium salts 35 and 36 to account for the carcinostatic activity found by us for thiodiglycol and thiodiglycollic acid<sup>9</sup> (Chart 7).




Chart 7

Acid catalysed cyclodehydration of  $\beta$ -hydroxyalkyl aryl sulphides 37 also gave both the normal 2,3-dihydrobenzo-*b*-thiophenes 38 as well as the rearranged thiophenes 39. Here also the rearrangement products are obviously formed *via* the reactive intermediate S-arylthiiranium salts 40 (Chart 8). In a few cases these reactive intermediates 40 were also isolated and then isomerized to the two sets of products 38 and 39<sup>10,11</sup>. The ratios of the normal and rearranged 2,3-dihydrobenzo-*b*-thiophenes and the proportion of *cis-trans* isomers obtained are also shown in Chart 8.




Chart 8

#### Synthesis of sulphur heterocyclics containing bridge-head sulphonium salt moiety :

Apart from the above thiiranium salts, we have also synthesised several five- and six-membered heterocyclic sulphonium salts, in some of which heterocyclic sulphur occupies a bridge-head position<sup>12-15</sup>. The synthesis of some of these sulphur and nitrogen heterocyclics involves rearrangement of incipient carbonium ions by 1,2-alkyl or proton shifts<sup>12-14</sup> (Chart 9).





Chart 9

#### Synthesis of six-membered sulphur heterocycles<sup>16</sup> via S-arylthiacyclobutanium and S-arylthiacyclobutenium salts :

Rearrangement reactions occurring through reactive three-membered heterocyclic intermediates described above were also observed during the synthesis of six-membered sulphur and nitrogen heterocyclic compounds through acid-catalysed cyclodehydration of appropriately substituted ketones and carbinols. Here also the rearrangement most probably occurs through reactive four-membered sulphur and nitrogen heterocyclic ring systems which then ring expand in two alternative ways to give the observed products. In several cases the relevant reactive four-membered sulphur and nitrogen heterocyclic compounds were also isolated and then isomerized to six-membered ring systems, the observed products of cyclodehydration reactions.


Thus, cyclodehydration of both  $\beta$ -phenylmercaptopropyl phenyl ketone 49 and  $\beta$ -phenyl- $\beta$ -phenylmercaptoethyl methyl ketone 50 gave a mixture of two sets of thianaphthalenium salts 51 and 52 and the thiachromans 53 and 54 in different proportions. The fact that *all* the four compounds are obtained starting from two *different* starting  $\beta$ -arylmercaptoethyl ketones, 49 and 50, goes to show that the cyclodehydration probably occurs through four-membered saturated (S-phenylthiacyclobutanium

salts 57, 58 or unsaturated (S-phenylthiacyclobutenium salts) 63, 64 sulphur ring systems as shown in the generalized scheme in Chart 10. The hydroxycyclobutanium salts 57, 58 are obviously unstable and readily yield S-phenylcyclobutenium salts 63, 64 which were isolated in several cases and then isomerized to the six-membered sulphur ring systems, the observed products of cyclodehydration of the  $\beta$ -arylmercaptoethyl ketones. Depending on the nature of substituents ( $R_1$ ,  $R_2$ ), 63 or 64 are more stable (in acidic solutions) and the less stable compound is slowly converted to the more stable thiacyclobutenium salt<sup>16-18</sup>. Consequently, the relative proportion of the normal as against the rearranged products in the above cyclodehydration reactions will depend on the nature of substituents  $R_1$  and  $R_2$  and the relative stability of the incipient carbonium ions involved in the cyclization step.




Proton abstraction from the yellow coloured thiacyclobutenium salts, 63 and 64, by treatment with sodium hydride, gave an identical olive green coloured neutral compound which is assigned a ylid (in preference to thiacyclobutadiene) structure as shown in Chart 10A. Reprotonation of the ylid yields the more stable of the two thiacyclobutenium salt 63 or 64<sup>17</sup>. Whereas these ylids could not be isolated and were unstable, several stable neutral sulphur heterocyclics, containing S(IV) atom, were prepared by us rather simply by thionation of appropriately substituted 1,8-dichloroanthraquinones and 1,4,5,8-tetrachloroanthraquinone. These are deeply coloured (red to green) quinonoid compo-

unds some of which are used commercially as vat dyes for cotton <sup>8A</sup> (Chart 10A).

**Chart 10A**

Cyclodehydration of  $\beta$ -arylmercaptomethylene ketones **65** by means of perchloric acid gave



### Chart 11

essentially the rearranged thianaphthalenium perchlorate 66 and only smaller amounts of the normal product 67. It seems likely that the rearranged products are formed through the intermediacy of reactive hydroxythiacyclobutenium perchlorates, 68, 69, which then lead to observed products 66, 67 (Chart 11)<sup>10</sup>. Several complex linear and angular polycyclic thianaphthalenium perchlorates were synthesised by this general method. In most cases cyclodehydration of the  $\beta$ -arylmercaptomethylene ketones gave only the rearranged thianaphthalenium perchlorates (Chart 11)<sup>10</sup>.

Cyclodehydration of 1-phenyl-1-phenylmercaptoethyl-3-butanol 71, obtained by  $\text{NaBH}_4$  reduction of  $\beta$ -phenyl- $\beta$ -phenylmercaptoethyl methyl ketone 70, by treatment with perchloric acid yields mostly the rearranged 2-methyl-4-phenylthiachroman<sup>18</sup> 72. The formation of the latter rearranged product is also explicable on the basis of intermediate involvement of 1-S-phenyl-1-thiocyclobutanium salt 73 (Chart 12). However, attempts to synthesise the latter compounds have not been successful so far.




Chart 12

#### Synthesis of quinolines via azetidines and azetines :

In analogy with the above acid catalysed cyclodehydration reactions, 1-arylamino-3-alkanols 74 gave both the normal 75 as well as the rearranged 76 tetrahydroquinolines<sup>20,21</sup>. The formation of the rearranged tetrahydroquinolines 76 is explicable by postulating the intermediate involvement of N-arylazetidines 77 which on ring expansion lead to 75 and/or 76 depending on the nature of substituents and their stereochemistry<sup>18</sup>. The relevant N-arylazetidines were also synthesised from the corresponding carbinols 74 by cyclodehydration with sulphuric acid<sup>22</sup> or better with triphenylphosphine dibromide in presence of triethylamine<sup>23</sup>. Stereospecific synthesis of the azetidines and their stereo-selective




Chart 13

conversion to *cis*- or *trans*-tetrahydroquinolines has also been achieved<sup>18</sup> (Chart 13).

Cyclodehydration of  $\beta$ -arylaminoethyl alkyl/cycloalkyl/aryl ketones 78 by treatment with fused zinc chloride and an arylamine hydrochloride in boiling ethanol gave a mixture of rearranged quinolines 79 and tetrahydroquinolines 80 along with the normal cyclodehydration products 81, 82. The formation of rearranged products is explicable by envisaging the intermediate formation of N-arylazetidines 83 or through the involvement of N-arylazetines<sup>18,24,25</sup>, 84, 85 as shown in Chart 14.





Chart 14

#### Cyclodehydration of $\beta$ -arylaminoethyl aryl



L = Leaving group e.g.  $\text{ArNH}_2$ ,  $\text{OH}$ , -Lactate,  $-\text{O}-\text{ZnCl}$

Chart 15

ketones **86** by treatment with PPA gave in most cases the relevant quinolines<sup>26</sup> **87**, whereas treatment of **86** with arylamine hydrochloride and fused zinc chloride in boiling ethanol, chloroacetic acid, lactic acid, ethanolic hydrochloric acid or perchloric acid gave the rearranged quinolines **88**. The rearrangement may be taking place through reactive intermediate azetines **89**, **90** (Chart 15) although other plausible mechanisms have also been suggested<sup>25</sup>. A large number of quinolines of the general formulae **87**, **88** have been synthesised by us<sup>25,26</sup> (Chart 16). Attempts to isolate or to synthesise N-arylazetines of the type **89**, **90**, however, proved unsuccessful. There is also no report in literature of the synthesis of N-arylazetines.




Chart 16

Several complex sulphur and nitrogen containing heterocyclic compounds were also synthesised by cyclodehydration of the relevant  $\beta$ -arylaminoethylene ketones where also the heterocyclics were obtained through rearrangement, possibly through the relevant azetines<sup>27-31</sup>. Some of these syntheses are shown in Chart 17 by way of illustration.

#### Synthesis of 3,4-dihydro-1,3,2-oxazaphosphorin-2-oxides and their rearrangement to quinolines:

In view of the synthesis of S-arylcyclobutenium perchlorates by interaction of  $\beta$ -arylmercaptoethyl alkyl (aryl) ketones with  $\text{POCl}_3/\text{HClO}_4$  discussed earlier,  $\beta$ -arylminoethyl aryl ketones **91** were treated with  $\text{POCl}_3$  and later (or simultaneously) with triethylamine. Instead of the expected azetines, **92**




Chart 17




Chart 18

2-chloro-3, 6-diaryl-3, 4-dihydro-1, 3, 2-oxazaphosphorin-2-oxides **93** were formed readily through intermediate phosphoramides **94**, which were also isolated in a few cases (Chart 18). Four compounds in this series **93** were found to be active against P388 lymphocytic leukemia<sup>22</sup>. Whereas tetrahydro-1,3,2-oxazaphosphorin-2-oxides (cyclophosphamides) are widely studied and some of them (e.g. Endoxan) are well known and widely used anti-leukemic agents, the 3,4-dihydro-1,3,2-oxazaphosphorin-2-oxides **93** represent new O,N,P, heterocyclic ring system. These compounds are very stable to heat, light, hydrolytic cleavage and dilute acids and alkali. The chlorine atom in **93** is, however, replaced by secondary alkylamino, azido, ethoxy and hydroxy (in the presence of phase transfer catalysts) groups to give 2-substituted-3,6-diaryl-3,4-dihydro-1,3,2-oxazaphosphorin-2-oxides **95**.

The oxazaphosphorin **96** was slowly converted on keeping to 7-methoxy-4-phenylquinoline **97** in high yield (90%). The transformation was rapid on photolysis, acid treatment or heating in benzene with or without Et<sub>3</sub>N. Some 7-methoxy-4-phenyl-1,2,3,4-tetrahydroquinoline **98** (yield 6%) was also formed. This transformation seems to be specific for **96** since other oxazaphosphorins **93**, **95** failed to give the corresponding quinoline derivatives (Chart 18). The mechanism of this facile conversion of **96** to **97** in high yield, even in *absence* of air, is under investigation.

#### Synthesis of azepines through nitrene insertion :

Thermal decomposition of *p*-toluenesulphonylazide **99** with benzenoid substrates containing electronegative substituents such as carbomethoxy, nitro, cyano, acetyl, dicarbomethoxy or dicarboethoxy groups yielded the azepines **104** and *p*-toluenesulphonamido derivatives **103**, of which the former are formed in greater (*albiet* low) yield<sup>23,24</sup>. The formation of azepines involves the addition of thermally generated (singlet) nitrene **100** across the double bond carrying the electro-negative substituent. Ring expansion of the resulting unstable aziridines **102** then yields the relevant azepines **104** (Chart 19).




Chart 19

Thermal interaction of **99** with dimethyl phthalate and anthraquinone gave the azepines **105** and **106** and 1-*p*-toluenesulphonamidoanthraquinone **107**<sup>25</sup> (Chart 20).




Chart 20

Although the yield of the above azepines were generally very low (5-20%), in view of the inaccessibility of these complex azepines by other methods, the present work may be of some interest.

#### Acknowledgement

The author records his thanks to his numerous research students and collaborators (listed in the references) but for whose dedication, devotion, hard and skilful work the above contributions, spread over the last twenty years, would not have been possible.

#### References

1. J. E. BANFIELD, W. DAVIES, N. W. GAMBLE and S. MIDDLETON, *J. Chem. Soc.*, 1956, 4791.
2. D. S. RAO and B. D. TILAK, *J. Sci. Industr. Res.*, 1959, **18B**, 77.
3. L. J. PANDYA, D. S. RAO and B. D. TILAK, *J. Sci. Industr. Res.*, 1959, **18B**, 516.
4. T. SRINIVASA MURTHY and B. D. TILAK, *J. Sci. Industr. Res.*, 1960, **19B**, 395.
5. T. SRINIVASA MURTHY, L. J. PANDYA and B. D. TILAK, *J. Sci. Industr. Res.*, 1961, **20B**, 169.
6. P. CAGNIANT and D. CAGNIANT in "Advances in Heterocyclic Chemistry", (Ed.) A. R. KATRITZKY and A. J. BOULTON, Academic Press, New York, 1975, Vol. 18, p. 368, 370.
7. P. K. BROWN in "Indoles—Part I", (Ed.) W. J. HOULIKANIN; "Heterocyclic Compounds Series", (Ed.) Arnold Weissburger, Wiley Interscience, New York, 1972, p. 317, 329, 336, 347, 350.
8. B. IDDON and R. M. SCROWSTON in "Advances in Heterocyclic Chemistry", (Ed.) A. R. KATRITZKY and A. J. BOULTON, Academic Press, New York, 1970, Vol. 11, p. 220.
9. B. D. TILAK, V. N. GOGTE, M. B. SAHASRABUDHE and R. N. GADEKAR in UGC Symposium on "Synthesis of Heterocyclic Compounds of Physiological Interest", Osmania University, 1964, 87.
10. H. M. MODAK, Ph.D. Thesis, Pune University, 1977.
11. V. N. GOGTE and H. M. MODAK in "New Trends in Heterocyclic Chemistry", (Ed.) R. B. MITRA, V. N. GOGTE, R. M. ACHISON, N. R. AYYANGAR and N. CROMWELL, Elsevier, Amsterdam-Oxford, New York, 1979, 142.

12. B. D. TILAK, R. B. MITRA and CHANDRALEKHA DESHPANDE, *Tetrahedron Lett.*, 1965, 3569.
13. A. S. JHINA and B. D. TILAK, unpublished work.
14. H. M. EL-NAMAKY, Ph.D. Thesis, Pune University, 1969.
15. A. R. ACHAREKAR, Ph.D. Thesis, Shivaji University, 1975.
16. R. S. DEVDHAR, V. N. GOGTE and B. D. TILAK, *Indian J. Chem.*, 1980, 19B, 1014.
17. R. S. DEVDHAR, V. N. GOGTE and B. D. TILAK, *Tetrahedron Lett.*, 1974, 3911.
18. B. D. TILAK and V. N. GOGTE, *Heterocycles*, 1977, 7, 1339.
- 18A. N. R. AYYANGAR, S. R. PURAO and B. D. TILAK, *Indian J. Chem.*, 1978, 16B, 673.
19. B. D. TILAK and S. L. JINDAL, *Indian J. Chem.*, 1969, 7, 737.
20. V. N. GOGTE, V. A. MUKHEDKAR, H. M. EL-NAMAKY, M. A. SALEMA and B. D. TILAK, *Indian J. Chem.*, 1974, 12, 1234.
21. V. N. GOGTE, S. B. KULKARNI and B. D. TILAK, *Indian J. Chem.*, 1977, 15B, 769.
22. V. N. GOGTE, H. M. EL-NAMAKY, M. A. SALEMA and B. D. TILAK, *Tetrahedron Lett.*, 1969, 3319.
23. V. N. GOGTE, S. B. KULKARNI and B. D. TILAK, *Tetrahedron Lett.*, 1973, 1867.
24. B. D. TILAK, T. RABINDRANATHAN and K. N. SUBBASWAMI, *Tetrahedron Lett.*, 1966, 1959.
25. B. D. TILAK, H. V. BERDE, V. N. GOGTE and T. RABINDRANATHAN, *Indian J. Chem.*, 1970, 8, 1.
26. HEMALATA BERDE, V. N. GOGTE, A. G. NAMJOSHI and B. D. TILAK, *Indian J. Chem.*, 1972, 10, 9.
27. V. N. GOGTE, K. A. R. SASTRY and B. D. TILAK, *Indian J. Chem.*, 1974, 12, 1147.
28. V. N. GOGTE, G. B. MULLICK and B. D. TILAK, *Indian J. Chem.*, 1974, 12, 1227.
29. H. V. BERDE, V. N. GOGTE and B. D. TILAK, *Indian J. Chem.*, 1972, 10, 332.
30. V. N. GOGTE, G. B. MULLICK and B. D. TILAK, *Indian J. Chem.*, 1974, 12, 1324.
31. Y. D. VANKAR, V. N. GOGTE and B. D. TILAK, *Indian J. Chem.*, 1977, 15B, 411.
32. B. D. TILAK, V. N. GOGTE and A. S. MODAK, *Indian J. Chem.*, 1981, 20B, 414.
33. N. R. AYYANGAR, M. V. PHATAK and B. D. TILAK, *J. Soc. Dyers & Col.*, 1979, 55.
34. N. R. AYYANGAR, M. V. PHATAK and A. K. PUROHIT, *Chem. & Industry*, 1979, 853.
35. A. K. PUROHIT, Ph.D. Thesis, Pune University, 1981.

# FIR Studies of Copper(II) Monohaloacetates : Molecular Structure Based on Cu-O Vibrations

A. S. TYAGI and C. P. SRIVASTAVA\*

Chemistry Department, Agra College, Agra-282 002

Manuscript received 19 October 1981, accepted 28 April 1982

FIR studies of copper(II) acetate monohydrate, fluoroacetate dihydrate, chloroacetate tetrahydrate and bromoacetate monohydrate have been made in crystalline state at room temperature and at low temperature. The number of Cu-O bands, active in IR, have been calculated theoretically for different possible moieties around Cu atom in the complexes and compared with the total number of bands actually observed in the spectra. A tentative assignment of Cu-O bands have been proposed. On the basis of shifting of Cu-O stretching bands, bridged cage type mode of coordination of the carboxylate ligand to the Cu atom and dimeric bridged cage structure of the complexes have been established.

THE mid infrared region of copper(II) monohaloacetates have been studied extensively and the work done upto 1978 has been reviewed by Nakamoto<sup>1</sup> and Catterick *et al*<sup>2</sup>. In most of these studies attention was focussed on the shifts of asymmetric and symmetric carboxylate stretching vibrations. Some earlier workers<sup>3-6</sup> assigned a series of bands in the frequency region 400-250  $\text{cm}^{-1}$  in copper(II) acetate complexes. However, no attempt has been made to establish or to support the molecular structures of these complexes based on Cu-O vibrations. In our earlier communication<sup>7</sup>, we established the dimeric bridged cage structure of some copper(II) *n*-alkanoates, including selection rules to calculate the Cu-O (carboxylate) vibrations in different possible moieties, comparing them with the total number of vibrations actually observed in the spectra of complexes and tentative assignments of Cu-O bands were also proposed, based on normal coordinate analysis. In the present communication an attempt has been made to establish the molecular structures of hydrated copper(II) fluoroacetate, chloroacetate and bromoacetate by studying Cu-O vibrations.

## Experimental

The complexes were synthesised by standard methods<sup>10</sup>. The FIR spectra were recorded in the region 400-80  $\text{cm}^{-1}$  with a Polytech FIR 30 Fourier spectrophotometer. The spectra were recorded at 298 and 77°K. The samples were prepared in wig-shaped polyethylene pellets, obtained by mixing 5.0 mg of a complex with 40 mg powdered polyethylene and pressing.

## Results and Discussions

The number of vibrations of the different possible moieties immediately around the Cu atom in the

studied complexes have been summarized in Table 1 which shows possible molecular structure, possible moieties around the Cu atom, point-group, type of fundamental vibrations allowed by selection rules and the total number of vibrations which should be active in the spectrum of the complex.

The total number of bands observed in the spectra of the complexes are shown in Table 2. The identification of the bands were made by comparing the spectra of copper(II) haloacetates with those of corresponding sodium salts except those which looked like mixed band, on the basis of increased intensity of the band. All the bands (stretch and bending) due to Cu-O vibrations are believed to lie in the range between 200-500  $\text{cm}^{-1}$ . However, to be sure that no relevant band had been overlooked, the supplementary bands below 200  $\text{cm}^{-1}$  were also looked for. No supplementary band was observed except in the case of  $\text{Cu}(\text{ClCH}_2\text{COO})_2 \cdot 4\text{H}_2\text{O}$ .

It is obvious from Table 2 that hydrated copper(II) monohaloacetates show, on the average, 4 bands which agree well with a pyramidal  $\text{CuO}_4$  moiety (Fig. 4.2) belonging to  $\text{C}_{4v}$  point group. We have no exact data about the coordination place of  $\text{H}_2\text{O}$  molecule in these complexes. It is, therefore, considered only tetravalent copper moieties showing the number of bands closest to the observed average 4 and at the maximum 6. Thus the monomeric and dimeric transplanar moieties,  $\text{CuO}_2\text{X}_2$  (Fig. 4.4), and the dimeric square planar structure having  $\text{CuO}_4$  and  $\text{CuX}_4$  moieties together (Fig. 4.3 and 4.8) need further consideration. To reach clearcut conclusions some other factors should also be taken into account. The monomeric *trans*-planar structure (Fig. 4.4) may not be accepted for the

\* Present Address : Education Officer, University Grants Commission, Bahadur Shah Zafar Marg, New Delhi-110 002.

following reasons :

1. It can not explain spin-spin transition i.e. the subnormal magnetic moment of copper(II) fluoroacetate dihydrate, chloroacetate tetrahydrate and bromoacetate monohydrate are 1.38, 1.45 and 1.48 B.M. respectively<sup>11,12</sup>.
2. The existence of band at 375 m $\mu$  in uv absorption spectra which is diagnostic of dimeric structure<sup>13</sup>.
3. The  $\Delta E$  (difference between asym. and sym. COO stretching bands) should be much higher, as infact, it has an asymmetrical oxygen and halogen linked bidentate structure, which means a monodentate structure of each COO group. The  $\Delta E$  values are 195, 205 and 202 cm<sup>-1</sup> for monofluoro, monochloro and monobromoacetates respectively, which are quite close to 184 cm<sup>-1</sup> for copper(II) acetate monohydrate<sup>14</sup>.

TABLE 1—CALCULATIONS OF CU-O VIBRATIONS IN DIFFERENT POSSIBLE MOIETIES

Molecular structure	Possible moiety	Structure	Figure No.	Point group	Types of vibrations allowed by selection rules	Total no. of active bands
Dimeric bridged cage type ; Cu atom bonded to oxygen <i>O' = HYDROXYL OXYGEN</i>	CuO <sub>2</sub>	Square pyramidal	4.1	C <sub>4v</sub>	3A <sub>1</sub> + 2B <sub>2</sub> + B <sub>2</sub> + 3E	6
	CuO <sub>4</sub>	Square pyramidal	4.2	C <sub>4v</sub>	2A <sub>1</sub> + 2B <sub>2</sub> + B <sub>2</sub> + 2E	4
	CuO <sub>4</sub>	Square planar	4.3	D <sub>4h</sub>	A <sub>1g</sub> + B <sub>1g</sub> + B <sub>2g</sub> + A <sub>2u</sub> + B <sub>2u</sub> + 2E <sub>u</sub>	3
Monomeric ; Cu atom bonded to oxygen and halogen (X). <i>X = HALOGEN</i>	CuO <sub>2</sub> X <sub>2</sub>	Trans-planar	4.4	D <sub>2h</sub>	2A <sub>g</sub> + B <sub>1g</sub> + 2B <sub>1u</sub> + 2B <sub>2u</sub> + 2B <sub>3u</sub>	6
	CuO <sub>2</sub> X <sub>2</sub>	Cis-planar	4.5	C <sub>2v</sub>	4A <sub>1</sub> + 3B <sub>2</sub> + A <sub>2</sub> + B <sub>1</sub>	8
	CuO <sub>2</sub> X <sub>2</sub>	Trans-pyramidal	4.6	C <sub>2v</sub>	4A <sub>1</sub> + 2B <sub>2</sub> + A <sub>2</sub> + 2B <sub>1</sub>	8
	CuO <sub>2</sub> X <sub>2</sub>	Cis-pyramidal	4.7	C <sub>i</sub>	5A' + 4A''	9
	CuO <sub>2</sub> X <sub>2</sub>	Square pyramidal	4.8	D <sub>4h</sub>	A <sub>1g</sub> + B <sub>1g</sub> + B <sub>2g</sub> + A <sub>2u</sub> + 2E <sub>u</sub>	3 + 3 = 6
Dimeric bridged cage type : Cu atom bonded to oxygen and halogen (X)	CuO <sub>2</sub> X <sub>2</sub>	Trans-planar	4.4	D <sub>2h</sub>	2A <sub>g</sub> + B <sub>1g</sub> + 2B <sub>1u</sub> + 2B <sub>2u</sub> + 2B <sub>3u</sub>	6
	CuO <sub>2</sub> X <sub>2</sub>	Cis-planar	4.5	C <sub>2v</sub>	4A <sub>1</sub> + 3B <sub>2</sub> + A <sub>2</sub> + B <sub>1</sub>	8
	CuO <sub>2</sub> X <sub>2</sub>	Square planar	4.3	D <sub>4h</sub>	A <sub>1g</sub> + B <sub>1g</sub> + B <sub>2g</sub> + A <sub>2u</sub> + 2E <sub>u</sub>	3 + 3 = 6
	CuO <sub>2</sub> X <sub>2</sub>	Trans-pyramidal	4.6	C <sub>2v</sub>	4A <sub>1</sub> + 2B <sub>2</sub> + A <sub>2</sub> + 2B <sub>1</sub>	8
	CuO <sub>2</sub> X <sub>2</sub>	Cis-pyramidal	4.7	C <sub>i</sub>	5A' + 4A''	9
	CuO <sub>2</sub> & CuX <sub>4</sub>	Square-pyramidal	4.8	D <sub>4h</sub>	2A <sub>1</sub> + 2B <sub>2</sub> + B <sub>2</sub> + 2E	4 + 4 = 8




Fig. 1. Dimeric structure

Monomeric ; Cu atom bonded to oxygen and halogen (X).

X = HALOGEN




Fig. 2. Monomeric structure

Dimeric bridged cage type : Cu atom bonded to oxygen and halogen (X)




Fig. 3. Dimeric structure

Vibrations in italics are active in infrared.

TABLE 2—TOTAL NUMBER OF CU-O BANDS OBSERVED IN THE SPECTRA OF COMPLEXES IN THE REGION 500-100 cm<sup>-1</sup>

Compound	Temp	Number of bands between 500-100 cm <sup>-1</sup>	Total number of bands observed
Cu(CH <sub>3</sub> COO) <sub>2</sub> ·H <sub>2</sub> O	RT	1vs + 3s + 1br sh + 1w	4-5
	LT	1vs + 3s + 2m	5-6
Cu(CH <sub>3</sub> FCOO) <sub>2</sub> ·2H <sub>2</sub> O	RT	2s + 2m + 1s mix + 1i	5-6
	LT	3s + 1m + 1s mix + 1mw	5-6
Cu(CH <sub>3</sub> ClCO) <sub>2</sub> ·4H <sub>2</sub> O	RT	1vs + 2s + 1m mix + 1vw	4-5
	LT	1vs + 2s + 1s mix + 1w	4-5
Cu(CH <sub>3</sub> BrCO) <sub>2</sub> ·H <sub>2</sub> O	RT	1vs + 1mw + 1vs mix + 2i	4-5
	LT	1vs + 2s + 1vs mix + 1m + 1vw	5-6

vs = very strong, s = strong, m = medium, mw = medium weak, vw = very weak, w = weak, br = broad, sh = shoulder, mix = mixture, RT = Room temp. (298°K), LT = Liquid nitrogen temp. (77°K).






Fig. 4.1 Moiety-CuO<sub>4</sub> square pyramidal point group-C<sub>4v</sub>.




Fig. 4.2 Moiety-CuO<sub>4</sub> square pyramidal point group-C<sub>4v</sub>.




Fig. 4.3 Moiety-CuO<sub>4</sub> square planar point group-D<sub>4h</sub>.




Fig. 4.4 Moiety-CuO<sub>2</sub>X<sub>2</sub> trans-planar point group-D<sub>2h</sub>.




Fig. 4.5 Moiety-CuO<sub>2</sub>X<sub>2</sub> cis-planar point group-C<sub>2v</sub>.




Fig. 4.6 Moiety-CuO<sub>2</sub>X<sub>2</sub> trans-pyramidal point group-C<sub>2v</sub>.




Fig. 4.7 Moiety-CuO<sub>2</sub>X<sub>2</sub> cis-pyramidal point group-C<sub>2</sub>.




Fig. 4.8 Moiety-CuX<sub>4</sub> square planar point group-D<sub>4h</sub>.




Fig. 4.9 Moiety-CuX<sub>4</sub> square pyramidal point group-C<sub>4v</sub>.

Fig. 4. Various possible moieties immediately around the copper(II) atom.

The dimeric moieties having *trans*-planar moiety, CuO<sub>2</sub>X<sub>2</sub>, (Fig. 4.4) belonging to D<sub>2h</sub> and square planar moieties, CuO<sub>4</sub> and CuX<sub>4</sub> (Fig. 4.2 and 4.8) having D<sub>4h</sub> point groups, do also not seem reasonable because of the following reasons :

1. If the molecule has D<sub>4h</sub> type structure, then all the stretching and bending vibrations will involve halogen (X) atoms except Cu-O stretching vibrations. Thus a bending  $\text{Cu} \begin{matrix} \text{O} \\ \diagup \diagdown \\ \text{X} \end{matrix}$  must be at lower frequency than the bending  $\text{Cu} \begin{matrix} \text{O} \\ \diagup \diagdown \\ \text{O} \end{matrix}$  because F, Cl, Br atoms are heavier than oxygen. In D<sub>4h</sub> symmetry, 3 vibrations would be due to CuO<sub>4</sub> moiety and 3 to CuX<sub>4</sub> moiety. Thus, 3 vibrations can be in the range of CuO<sub>4</sub> and 3 in the lower range of frequency.
2. The moiety D<sub>2h</sub> would imply that practically all the stretching vibrations should show their frequencies in the decreasing order Cu-O > Cu-F > Cu-Cl > Cu-Br. A similar trend should be obtained for bendings also. In D<sub>4h</sub> moiety 3 vibrations should remain fixed and another 3 of planar CuX<sub>4</sub> moiety should show low frequency shifts in the order F > Cl > Br.
3. Both of these moieties have bendings with only one COO oxygen atom, which should also give much higher  $\Delta E$  values than for bridged cage structures including CuO<sub>4</sub> moieties with bands due to the 2 oxygen atoms of each COO group.




Fig. 5. Comparative chart of copper(II) haloacetates.

A comparative chart of fir region 500-200  $\text{cm}^{-1}$  is presented in the Fig. 5. The arguments outlined above can be checked against the trend seen from this figure, taking  $(\text{CH}_3\text{COO})_2\text{Cu}\cdot\text{H}_2\text{O}$  as the reference.

For  $D_{4h}$  moiety, the vibrations should be shifted towards lower frequency in view of points 1 and 2. It is, however, found that monofluoro, monochloro and monobromo compounds have most of the bands shifted to higher frequencies in the sequence fluoro < chloro < bromoacetate. This contradicts the possibility of a dimeric moiety belonging to  $D_{4h}$  point group. This conclusion is also supported by  $\Delta E$  values<sup>14</sup>, which are in the range of dimeric bridged cage compounds. All these evidences discard a dimeric structure with local moiety having  $D_{4h}$  symmetry around Cu atom.

point for group, as  $\nu_a(\text{Cu-O}) > \nu_s(\text{Cu-O}) > \delta_a(\text{O-Cu-O}) > \delta_s(\text{O-Cu-O})$ .

In Fig. 5, we have presented the comparative chart of copper(II) fluoroacetate, chloroacetate and bromoacetate. The assignments of bands have been made by the proposed theoretical sequence and shown in Table 3. The bands at 364, 370 and 385  $\text{cm}^{-1}$  in the spectra of copper(II) fluoroacetate, chloroacetate and bromoacetate are assigned to  $\nu_a(\text{Cu-O})$  vibrations, whereas bands at 310, 317 and 330  $\text{cm}^{-1}$  are assigned to the  $\nu_s(\text{Cu-O})$  vibration for the respective compounds. Recently, Faniran *et al.*<sup>15</sup> have assigned the bands at 364 and 324  $\text{cm}^{-1}$  for  $\nu(\text{Cu-O})$  vibrations in copper(II) fluoroacetate. The bands at 385 and 330  $\text{cm}^{-1}$  were assigned to stretching modes of Cu-O band in the copper(II) chloroacetate.

TABLE 3—TENTATIVE ASSIGNMENT OF BANDS IN COPPER(II) MONOHALOACETATES

Assignments	$\text{Cu}(\text{FCH}_2\text{CO}_2)_2\cdot 2\text{H}_2\text{O}$	$\text{Cu}(\text{ClCH}_2\text{CO}_2)_2\cdot 4\text{H}_2\text{O}$	$\text{Cu}(\text{BrCH}_2\text{CO}_2)_2\cdot \text{H}_2\text{O}$
$\nu_a(\text{Cu-O})$	364 s	370 s	385 s
$\nu_s(\text{Cu-O})$	310 m	317 m	330 m
Ring deformation + $\delta_a(\text{O-Cu-O})$	288 s	276 s mix	269 vs
Ring deformation + $\delta_s(\text{O-Cu-O})$	248 m	257 m	248 m mix
Torsion	226 s br mix	233 w	226 w
Lattice vibrations	198 m	182 s	187 small
	170 mw	174 m	170 s

For  $D_{4h}$  symmetry, some vibrations should be at nearly fixed positions in monofluoro, monochloro and monobromo compounds and some should decrease in the order acetate > monofluoroacetate > monochloroacetate > monobromoacetate. However, we did not find either any fixed vibrations nor any band decreasing from acetate to monobromoacetate. These observations obviate the possibility of local  $D_{4h}$  symmetry. A similar conclusion is arrived for the point 3 due to low  $\Delta E$  values which are in the range for the dimeric cage compounds. It is thus concluded that the structure of hydrated copper(II) monohaloacetates should correspond to the  $\text{CuO}_4$  moiety with local  $C_{4v}$  symmetry (Fig. 4.2).

**Tentative assignment of bands:** It has been established that in copper(II) acetate monohydrate the moiety immediately around the copper atom is  $\text{CuO}_4$  in which the Cu atom is slightly above the plane of the four oxygen atoms making the square pyramidal structure. The four eventual oxygen atoms are at the corners of a square base and the fifth oxygen atom is coordinated to the Cu atom at the transaxial position. The fifth  $\text{O}^*$  atom is of different nature as is shown in Fig. 1. The Cu atom is linked to the other Cu atom by only a very weak  $\delta$ -interactions. No Cu-Cu bond has, therefore, been considered. The  $\text{CuO}_4$  moiety belongs to  $C_{4v}$  pointgroup. The fundamental vibrations and their sequence for the  $\text{CuO}_4$  moiety of the  $\text{Cu}(\text{CH}_3\text{COO})_2\cdot\text{H}_2\text{O}$  are:  $\nu_s(\text{Cu-O}^*) > \nu_a(\text{Cu-O}) > \nu_s(\text{Cu-O}) > \delta_a(\text{O-Cu-O}^*) > \delta_s(\text{O-Cu-O}) > \delta_s(\text{O-Cu-O})$ .

On the basis of similar grounds, we named the fundamental vibration and proposed their sequence for copper(II) monohaloacetate, belonging to  $C_{4v}$

It is obvious from Table 3, that both of  $\nu_a(\text{Cu-O})$  and  $\nu_s(\text{Cu-O})$  bands shifted to the higher frequency region in the sequence  $\text{Cu-BAC} > \text{Cu-CAC} > \text{Cu-FAC}$ ; where BAC stands for bromoacetate, CAC for chloroacetate and FAC for fluoroacetate. This sequence leads us to suggest that  $\nu(\text{Cu-O})$  vibrations decrease with an increase in electronegativity of the R group. This would indicate the weakening of Cu-O bond from bromoacetate to fluoroacetate. A similar behaviour was observed by Nakamoto *et al.*<sup>16</sup> for copper(II) acetyl acetonate and copper(II) hexafluoroacetylacetonate. They observed that substitution of  $\text{CF}_3$  for  $\text{CH}_3$  caused the Cu-O stretching band to shift to a lower frequency. Very recently, Faniran *et al.*<sup>15</sup> studying the mono-, di- and trifluoroacetate have pointed out that the Cu-O bond weakens with the increase in the electronegativity of R group. On the other hand the frequency separation of  $\nu(\text{Cu-O})$  vibration [ $\Delta\nu(\text{Cu-O})$ ] is found practically constant for the haloacetates (54, 53 and 55  $\text{cm}^{-1}$ ) for copper(II) fluoroacetate, chloroacetate and bromoacetate. The same trend was observed for the  $\Delta E(\nu_a, \text{COO} - \nu_s, \text{COO})$  in these complexes. Therefore, the dimeric bridged cage structure can be established for these complexes.

#### Acknowledgement

The authors thank the State Council of Science and Technology, U. P. for a grant to C. P. S. and a Cooperative Fellowship to A.S.T. The authors are also thankful to Prof. G. P. Vander Kelan, State University of Ghent, Belgium for recording the fir spectra of the complexes.

**References**

1. K. NAKAMOTO, "Infrared and Raman Spectra of Inorganic and Coordination Compounds", John Wiley & Sons, New York, 1978, p. 230.
2. J. CATTERICK and P. THORNTON, "Advances in Inorganic and Radio Chemistry", (Ed.) H. J. EMELEUS and A. G. SHARPE, Academic Press, New York, 1977, Vol. 20, p. 293.
3. J. A. FANIRAN and K. S. PATEL, *J. Inorg. Nuclear Chem.*, 1979, 41, 1495.
4. G. C. PERCY, *Spectrochim Acta*, 1976, 32A, 1287.
5. J. A. FANIRAN and K. S. PATEL, *J. Inorg. Nuclear Chem.*, 1974, 36, 2261.
6. A. B. P. LEVER and B. S. RAMASWAMI, *Cand. J. Chem.*, 1973, 51, 514.
7. A. H. HYENS, *J. Mol. Struct.*, 1972, 11, 93.
8. J. R. WASSON, C. I. SHYR and C. TRAPP, *Inorg. Chem.*, 1968, 7, 469.
9. A. S. TYAGI and C. P. SRIVASTAVA, *J. Indian Chem. Soc.*, 1981, 58, 1101.
10. A. S. TYAGI, Ph.D. Dissertation, Agra University, Agra, 1980.
11. M. KATO, H. B. JONASSEN and J. C. FANNING, *Chem Revs.*, 1964, 64, 99.
12. K. NAKAMOTO, *Inorg. Chem.*, 1973, 12, 2440.
13. M. MELNIK, *Acta Facul. Pharmace.*, 1974, 25, 37.
14. A. S. TYAGI and C. P. SRIVASTAVA, *J. Indian Chem. Soc.*, 1981, 58, 284.
15. K. NAKAMOTO, Y. MORIMOTO and A. E. MARTELL, *J. Phys. Chem.*, 1962, 66, 346.

# Physicochemical Study of Some Transition Metal Complexes of Vanillin-sulphanilate

PURUSHOTTAM B CHAKRAWARTI\* and PRAMILA KHANNA

Chemical Laboratories, M. L. B. College, Bhopal-462 002

Manuscript received 23 July 1981, revised 21 January 1982, accepted 1 May 1982

Transition metal complexes of a Schiff base, derived from vanillin and sulphonic acid (Van-Sul), have been prepared and characterised on the basis of elemental analysis, infrared and electronic spectra and magnetic susceptibility measurements. The magnetic and spectral data indicate them to be low spin octahedral complexes. Van-Sul molecules apparently act as the bidentate O-O donor.

SCHIFF bases containing two or more chromophoric groups separated by only one single bond (i.e. forming a conjugated system) are important not only for their analytical and physiological uses, but also for their interesting spectral and unusual magnetic and structural properties. In continuation of our studies<sup>1-3</sup> on transition metal complexes of Schiff bases derived from vanillin, we report here the results of our studies on the synthesis and characterisation of Fe(II), Co(II), Ni(II), Cu(II), Mn(II) and Fe(III) complexes of Van-Sul.

## Experimental

All the chemical used were AR or SM reagents.

**Preparation of Van-Sul:** On refluxing aqueous solutions of sulphanilic acid and vanillin (hot water) in equimolar ratio, yellow coloured Schiff base,  $C_8H_8(OH)(OCH_3)CH=NC_6H_4SO_3H$ , separated out, m.p. 272° with decomposition, soluble in alkali, alcohol and dioxan.

**Preparation of the metal complexes.** Metal complexes of the Schiff base were prepared by refluxing aqueous solutions of the metal salt and sodium salt of the Schiff base in 1 : 2 molar ratio for 2 to 3 hr. The metal salts used were  $CuSO_4 \cdot 5H_2O$ ,  $NiSO_4 \cdot 7H_2O$ ,  $MnSO_4 \cdot 7H_2O$ ,  $Fe(NH_4)_2(SO_4)_2 \cdot 6H_2O$ ,  $Fe(NO_3)_3 \cdot 9H_2O$  and  $CoSO_4 \cdot 7H_2O$ . Sodium salt of the Schiff base used was prepared by dissolving the Schiff base in the least quantity of a dilute solution of NaOH. The insoluble complexes that separated out on cooling, were filtered, washed, dried in vacuum and analysed for percentage of the metal, C, H, N and S microanalytically.

## Results and Discussion

The analytical data and conductometric study indicate 1 : 2 metal : ligand stoichiometry, with the molecular formula  $ML_2 \cdot 2H_2O$ , for all the complexes except the iron complex which was shown to have  $ML_2(OH) \cdot H_2O$  formula. The isolated complexes

were insoluble in common organic solvents and water and were infusible below 300°. The magnetic and spectral data indicate these complexes to be low spin ones in which Van-Sul molecules are attached with the metal ion through the phenolic and methoxy oxygen of the vanillin residue and imparting octahedral geometry to the complexes.

### Magnetic moments and electronic spectra :

**Mn(II)-Van-Sul:** The  $\mu_{eff}$  value (1.7 B.M.) obtained for the complex at room temperature (24°), is well within the range of low-spin octahedral stereochemistry. The electronic spectra of the complex exhibit only two bands at 18.5 kK and 23.2 kK. These low energy bands arising from the ground state  ${}^6T_{2g}(t_{2g}^5e_g^0)$  may be assigned to  ${}^6T_{2g}(I) \rightarrow {}^6A_{1g}(I)$  and  ${}^6T_{2g}(I) \rightarrow {}^6T_{1g}(I)$  transitions respectively, characteristic of octahedral geometry of Mn(II) complexes<sup>4</sup>.

**Iron complexes:** The magnetic moment value obtained for the Van-Sul complex isolated with the Fe(II) salt, is quite abnormal (2.0 B.M.) and is the same as obtained for Fe(III)-Van-Sul (1.97 B.M.). This indicates oxidation of Fe(II) into Fe(III) during isolation, as is also observed in the cases of Van-Hy<sup>3</sup> and Van-An<sup>3</sup> complexes of the salt. The  $\mu_{eff}$  value of 2.0 B.M. is well within the range reported for spin-paired octahedral complexes of Fe(III)<sup>5,6</sup>. Conclusion that Fe(II) is oxidised to Fe(III) is supported by the electronic and infrared spectra (discussed below) of the complex. The electronic spectra of the complex obtained with the Fe(II) salt show two bands at 17.2 and 20.0 kK which are quite analogous to the band obtained in case of Fe(III) complexes with octahedral stereochemistry<sup>7</sup>. These bands can be assigned to  ${}^6T_{2g} \rightarrow {}^6A_{1g}$  transitions of Fe(III) complexes in octahedral environment. This band in Fe(III) Van-Sul appears at 17.2 kK, in addition to a band at 13.7 kK for the  ${}^6T_{2g} \rightarrow {}^6A_{1g}$  transition. Since the complex isolated with the Fe(II) salt

\* To whom correspondence be made at 90/24, T. Nagar, Bhopal-462 005.

did not show any band in the regions 10.5 and 8.0 kK [characteristic of Fe(II) complexes in octahedral stereochemistry], it is clear in the light of the magnetic and spectral studies, that the two complexes of iron isolated in this study have Fe(III) in octahedral stereochemistry.

**Co(II)-Van-Sul :** The  $\mu_{eff}$  value (1.78 B.M.) of Co(II)-Van-Sul is characteristic of low-spin octahedral complexes of Co(II). The electronic spectra of the complex indicate two bands, one at 18.9 kK and the other at 20.48 kK and may be assigned to  ${}^4E_g(G) \rightarrow {}^4T_{1g}(G)$  and  ${}^4E_g(G) \rightarrow {}^4T_{1g}$  transitions respectively in octahedral field<sup>8</sup>.

**Ni(II)-Van-Sul :** The magnetic moment of the complex (3.2 B.M.) indicates it to be an octahedral complex<sup>9</sup>. However, the value is higher than that of a typical paramagnetic octahedral Ni(II) complex<sup>9</sup> and indicates large orbital contribution. The octahedral stereochemistry of the complex is also indicated by the two absorption bands seen in its electronic spectra for the transition  ${}^3A_{2g}(F) \rightarrow {}^3T_{1g}(F)$  (16.1 kK) and  ${}^3A_{2g}(F) \rightarrow {}^3T_{1g}(P)$  (28.5 kK).

**Cu(II)-Van-Sul :** The  $\mu_{eff}$  value obtained for the complex (1.85 B.M.) is greater than the spin only value (1.7 B.M.) and indicates orbital contribution and distortion of octahedral structure. This complex did not give any band in visible region as d-d transitions are obscured by the intense C.T. bands.

**IR spectra :** Infrared spectra of the complexes show that the bands due to  $\nu(OH)$ , appearing at 3440, 3180 and 2840  $cm^{-1}$  in the free ligand, fuse and become broad in the region 3600-2800  $cm^{-1}$ . The  $\nu(C-O)$  due to methoxy group, appearing in the region 1240-1290  $cm^{-1}$  in the free ligand, is lowered by 15-30  $cm^{-1}$  in the complexes while  $\nu(C-O)$  due to phenolic OH group is shifted to higher frequency by 10-20  $cm^{-1}$  in the complexes than in the free ligand. This shows that complexation take place through phenolic OH group with deprotonation<sup>10</sup> and oxygen of the methoxy group. The  $\nu(S-O)$ , and

symmetric and asymmetric  $\nu(SO_2)$  remain unchanged in the regions 1180, 980 and 1040  $cm^{-1}$ , respectively<sup>11</sup>. The coordinated water in the complexes is indicated by the presence of bands at  $\sim 3200$ , 1600 and 840  $cm^{-1}$ <sup>12,13</sup> while the M-O band appears at  $\sim 455$   $cm^{-1}$  in the complexes<sup>14</sup>.

#### Acknowledgements

Thanks of the authors are due to M/s Shree Synthetics, Ujjain. The authors also thank Prof. M. M. Bokadia, Head, School of Studies in Chemistry, Vikram University, Ujjain and Dr. C. S. Bhatnagar, Dept. of Physics, M. A. C. T., Bhopal for providing facilities and the U. G. C., New Delhi for the research grant to one of them (P. K.).

#### References

1. P. KHANNA and P. B. CHAKRAWARTI, *J. Indian Chem. Soc.*, 1980, 57, 586.
2. P. KHANNA and P. B. CHAKRAWARTI, *Bull. Chem. Soc., Japan*, (Communicated).
3. P. KHANNA and P. B. CHAKRAWARTI, *Aust. J. Chem.*, (Communicated).
4. T. M. DUNN, "Modern Coordination Chemistry", (Ed.) J. LEWIS and R. G. WILKINS, Inter Science, N. Y., 1960, p. 290.
5. E. KRONKHE, *Chem. Ber.*, 1950, 83, 35; 1953, 86, 1132; 1954, 87, 1126; 1955, 88, 863.
6. B. N. FIGGIS, *Trans. Faraday Soc.*, 1961, 57, 199.
7. C. J. BALLHAUSEN, "Introduction to Ligand Field Theory", McGraw Hill, N. Y., 1962.
8. F. A. COTTON and G. WILKINSON, "Advanced Inorganic Chemistry", Wiley Eastern, New Delhi, 1972, p. 881.
9. A. D. DAMODARAN, F. M. ICHAPORIA and G. S. RAO, *J. Indian Chem. Soc.*, 1968, 45, 690.
10. A. SYAMAL and V. D. GHANEKAR, *Indian J. Chem.*, 1978, 16A, 82.
11. C. NATRAJAN and P. R. ATHAPPAN, *Indian J. Chem.*, 1977, 15A, 1103.
12. FUJITA, K. NAKAMOTO and M. KABAYASHI, *J. Amer. Chem. Soc.*, 1956, 78, 3963.
13. STARTORI, FURLANI and DAMINI, "Chemistry of Coordination Compounds", Symp. Rome, Inter Science Publ., N. Y., 1954.
14. P. SINGH, V. SINGH, R. PAL and R. P. MAHESH, *J. Indian Chem. Soc.*, 1980, 57, 1954.

# Studies on Some Polydentate Ligands. I


K. MUKKANTI, Y. K. BHOON, K. B. PANDEYA and R. P. SINGH

Department of Chemistry, University of Delhi, Delhi-110 007

Manuscript received 4 April 1981, revised 26 October 1981, accepted 23 May 1982


Synthesis and characterisation of two new hexadentate ligands, 1,2-bis(*o*-1-methyltriazene-1-oxido-3-phenylthio)-ethane and 1,2-bis(*o*-1-ethyltriazene-1-oxido-3-phenylthio)-ethane and their chelates with some bivalent transition metal ions are described.

WE recently synthesised<sup>1</sup> two new hexadentate ligands, 1,2-bis(*o*-1-methyltriazene-1-oxido-3-phenoxy)ethane (DMTPE) and 1,2-bis(*o*-1-ethyltriazene-1-oxido-3-phenoxy)ethane (DETPE), and their metal chelates with Mn(II), Co(II), Ni(II) and Cu(II). In this communication we report the synthesis and chelating properties of the sulfur analogues of these ligands i.e., 1,2-bis(*o*-1-methyltriazene-1-oxido-3-phenylthio)ethane (DMTPTE), (Ia) and 1,2-bis(*o*-1-ethyltriazene-1-oxido-3-phenylthio)ethane (DETPTE), (Ib).



These two ligands act as hexadentate ligands utilising the two sulfur atoms, the two nitrogen atoms linked to the benzene ring and the two oxygen atoms, so that six-coordinate metal chelates of the type M(ligand-2H) are obtained with all the four metal ions, Mn(II), Co(II), Ni(II) and Cu(II).

The synthesis of the present ligands (I) has been achieved by introduction of triazene-1-oxido group in place of the amino group in the ligand (II)



The synthesis of the above quadridentate ligand (II) was reported by Unger<sup>2</sup> as early as in 1897. Dwyer<sup>3</sup> *et al* in 1967 studied the chelating properties of these ligands.

## Experimental

**Preparation of ligands:** The two ligands were synthesised by coupling the appropriate diazonium salts and substituted hydroxylamine in an acetate buffer at 0°. Details of preparations are as follows.

**1, 2-bis(*o*-1-methyltriazene-1-oxido-3-phenylthio)ethane (DMTPTE):** 1.75 g of 1,2-bis(*o*-aminophenylthio)ethane (II) was taken in 50% hydrochloric acid (4 ml HCl, 4 ml H<sub>2</sub>O) and diazotised by 1.15 g of sodium nitrite in 2 ml water. The temperature of the solution was maintained between 0-5°. This diazonium salt solution was added with stirring to 1.12 g of N-methylhydroxylamine hydrochloride in 50 ml of water, cooled to 0°. The pH of the reaction mixture was kept in the range 3-5 by slow and simultaneous addition of 7 g of sodium acetate in 20 ml of water. The solution was stirred for 10 more min. After the addition of diazonium salt solution was completed, a pale yellow precipitate separated out. This was filtered and recrystallised from alcohol to yield pale yellow needles. Analysis: C, 48.82; H, 5.42; N, 21.72; S, 16.01. C<sub>16</sub>H<sub>16</sub>N<sub>6</sub>O<sub>2</sub> requires C, 48.97; H, 5.14; N, 21.42; S, 16.34%; m.p. 169-70°.

**1, 2-bis(*o*-1-ethyltriazene-1-oxido-3-phenylthio)ethane (DETPTE):** The same procedure was used for the preparation of the DETPTE using N-ethylhydroxylamine hydrochloride as coupling agent. Analysis: C, 51.18; H, 5.63; N, 19.80; S, 15.72. C<sub>18</sub>H<sub>20</sub>N<sub>6</sub>O<sub>2</sub> requires C, 51.14; H, 5.75; N, 19.99; S, 15.25%; m.p. 171-73°.

## Preparation of the complexes:

**Manganese(II) complexes:** A solution of manganese acetate (1.2 g; 0.005 M) was added to ethanolic solution of ligand (2.0 g of DMTPE or 2.1 g of DETPTE; 0.005 M). The contents were refluxed for about half an hour and crystalline complexes separated out on concentration. The complexes were washed with hot water and finally with alcohol and dried in a vacuum desiccator over P<sub>2</sub>O<sub>5</sub>. They are insoluble in water and ethanol but soluble in acetone and chloroform.

**Cobalt(II) complexes:** Aqueous solution of cobalt acetate (1.3 g; 0.005 M) prepared in minimum volume of water was added to ethanolic solution of ligand (2.0 g of DMTPE or 2.1 g of DETPTE; 0.005 M). The contents were refluxed for about half an hour and red crystalline complexes separated out on concentration. The complexes were washed with hot water and finally with alcohol and dried in

a vacuum desiccator over  $P_4O_{10}$ . They are insoluble in water and ethanol but soluble in acetone and chloroform.

**Copper(II) complexes:** Alcoholic solution of copper(II) acetate (1.0 g; 0.005 M) was added to ethanolic solution of ligand (2.0 g of DMTPTTE or 2.1 g of DETPTE; 0.005 M). The contents were refluxed for about half an hour and on concentration, pale red crystalline complexes separated out. The complexes were washed with hot water and finally with alcohol and dried in a vacuum desiccator over  $P_4O_{10}$ . These complexes are insoluble in water and ethanol but soluble in acetone and chloroform.

**Nickel(II) complexes:** Aqueous solution of nickel chloride (1.2 g; 0.005 M) was added to ethanolic solution of ligand (2.0 g DMTPTTE or 2.1 g DETPTE; 0.005 M). The contents were refluxed for about half an hour and on concentration, green crystalline complexes separated out. The complexes were washed with hot water and finally with alcohol and dried in a vacuum desiccator over  $P_4O_{10}$ . Both the complexes are insoluble in water and ethanol but soluble in acetone and chloroform.


**Physical measurements:** NMR spectra were recorded on a Varian A-60 spectrometer. Tetramethylsilane was used as the internal standard and frequencies were measured by the side band technique.

Infrared spectra were taken in KBr pellets or in chloroform solutions on a Perkin Elmer 621 spectrophotometer.

The magnetic susceptibilities were measured on a Gouy balance, using  $Hg[Co(NCS)_4]$  as calibrant ( $\chi_0 = 16.46 \times 10^{-6}$  cgs). The diamagnetic corrections for the ligand atoms and cations were computed using Pascal's constants<sup>10</sup>.

## Results and Discussion

**Structure of the ligands:** The two tautomeric forms (IIIa) or (IIIb) are possible for the ligands under discussion. NMR spectra of the two ligands



(DMTPTE and DETPTE) in  $CDCl_3$  have a low field signal (-1.4 and -1.5 $\tau$ ), which is of the correct intensity to represent the N-H protons and confirms the existence of the molecule in (IIIb) form. If the ligands exist in (IIIa) form, there must be a singlet for O-H. This is usually located<sup>11</sup> at very low field ( $\sim -5\tau$ ) while N-H proton is very often found around -3 $\tau$ . The lowering in the position may be attributed to hydrogen bonding. But no O-H singlet is present in the spectra. So the structure of the ligands can be confirmed as (IIIb) and not as (IIIa).

This examination leads us to conclude that the corresponding compounds having  $R=CH_3$  or  $C_2H_5$ , are correctly formulated as 1,2-bis(o-1-alkyltriazeno-1-oxido-3-phenylthio)ethane (type IIIb).

Some representative nmr data for the ligands are shown in Table 1. The spectrum of DMTPTTE, taken in  $CDCl_3$ , gives rise to a singlet at 5.95 $\tau$  representing the two methyl groups. The ethylene group ( $-CH_2-CH_2-$ ) is found to give a singlet at 7.08 $\tau$ .


TABLE 1—PROTON RESONANCE FREQUENCIES OF THE LIGANDS IN  $CDCl_3$

Ligands	Group	Chemical shifts ppm ( $\tau$ )
DMTPTE	$NCH_3$	5.95
	$-CH_2-CH_2-$	7.08
	$-C_6H_5$ (aromatic protons)	2.40–3.10
	NH	-1.40
DETPTE	$NCH_2CH_3$ (due to $CH_3$ group)	8.45 (t, $J=7.5$ Hz)
	$NCH_2CH_3$ (due to $CH_2$ group)	5.80 (q, $J=7.5$ Hz)
	$-C_6H_5$ (aromatic protons)	2.30–2.55
	NH	-1.50
	$-CH_2-CH_2-$	7.06

The aromatic protons (in two benzene rings) appear as multiplets in the region 2.40 to 3.10 $\tau$ . The intensity ratio of the ethylene group and two methyl groups is 1.50.

Similarly, the nmr spectrum of DETPTE in  $CDCl_3$  has a low field signal (-1.50 $\tau$ ), which is assignable to the N-H protons. This compound gives rise to one singlet at 7.05 $\tau$  representing the ethylene group ( $-CH_2-CH_2-$ ). The two methylene groups of  $C_2H_5$  give one quartet in the region 5.50–5.90 $\tau$  ( $J=7.5$  Hz). These signals are assigned to  $-NCH_2-$  on the basis of their chemical shifts at higher field. The two methyl groups of  $C_2H_5$  give one triplet in the region 8.30–8.56 $\tau$  ( $J=7.5$  Hz). The aromatic protons in the two benzene rings give one multiplet in the region 2.30–2.55 $\tau$ .

**Structure of the complexes:** All the complexes have 1 : 1 metal : ligand composition. The triazene-1-oxide group is known to act as bidentate. The coordination ability of the thioetheral sulfur of the ligands is also well established<sup>12</sup>. The two ligands may, therefore, act as bidentate hexadentate ligands forming neutral six-coordinate complexes (IV).



The room temperature magnetic moment values (Table 2) for all the complexes are in conformity with such a structure in copper(II), nickel(II) and manganese(II). Complexes show normal magnetic

TABLE 2—ELEMENTAL ANALYSIS AND MAGNETIC PROPERTIES OF THE Mn(II), Co(II), Cu(II) AND Ni(II) CHELATES

	Colour	% C Found (Calcd.)	% H Found (Calcd.)	% N Found (Calcd.)	% S Found (Calcd.)	% M Found (Calcd.)	$\mu_{eff}$ (B.M.)
Mn(DMTPTE-2H)	Red	43.40 (43.14)	3.99 (4.07)	18.95 (18.87)	14.61 (14.39)	12.05 (12.35)	6.02
Co(DMTPTE-2H)	Red	42.99 (42.76)	4.06 (4.04)	18.57 (18.70)	14.02 (14.26)	13.40 (13.11)	4.50
Cu(DMTPTE-2H)	Brown	42.10 (42.32)	3.97 (3.99)	18.32 (18.51)	14.43 (14.13)	13.79 (13.99)	1.84
Ni(DMTPTE-2H)	Green	42.53 (42.78)	4.07 (4.04)	18.90 (18.71)	14.45 (14.27)	12.85 (13.07)	3.22
Mn(DETPTE-2H)	Red	45.25 (45.66)	4.62 (4.68)	17.51 (17.75)	13.69 (13.54)	11.28 (11.60)	6.11
Co(DETPTE-2H)	Brown	45.60 (45.28)	4.81 (4.64)	17.41 (17.60)	13.75 (13.43)	12.03 (12.34)	4.39
Cu(DETPTE-2H)	Brown	44.62 (44.84)	4.57 (4.60)	17.29 (17.43)	13.08 (13.30)	13.41 (13.18)	1.99
Ni(DETPTE-2H)	Green	45.02 (45.29)	4.56 (4.65)	17.85 (17.61)	13.59 (13.43)	12.61 (12.30)	3.11

moments corresponding to one, two and five unpaired spins, associated with expected orbital contributions.

In an octahedral crystal field, the magnetic moment<sup>21-22</sup> for high-spin cobalt(II) ( $S=3/2$ ) is expected to be 5.2 B.M. at 300 K. Low spin cobalt(II) complexes possess the electronic configuration  $t_{2g}^6 e_g^2$ . The magnetic moment is expected<sup>21-22</sup> to be temperature independent and fairly close to 1.9 B.M. However, cobalt(II) complexes can show magnetic moment at room temperature which is in between for the two spin-states and such intermediate values can arise due to any of the following mechanisms :

- (i) partial oxidation of cobalt(II) to cobalt(III),
- (ii) antiferromagnetic exchange interactions,
- (iii) equilibrium between the thermally accessible  $^4E_g$  and  $^4T_{2g}$  states i.e.,  $^4T_{2g} \rightleftharpoons ^4E_g$

The lowering in the magnetic moment in the cobalt(II) complexes under study as a result of partial oxidation of cobalt(II) to cobalt(III) is ruled out in view of the constancy in the magnitude of magnetic moment within the range of experimental error ( $\pm 0.02$ ) for the complexes obtained from three different preparations. The existence of exchange interactions with very bulky ligands of the type used in the present studies could also be ruled out and, therefore, the intermediate values of magnetic moments observed in the cobalt(II) complexes are possibly due to the equilibrium<sup>23-25</sup> between the thermally accessible  $^4T_{2g}$  and  $^4E_g$  states. Magnetic measurements at different temperature would have presented a clear picture of the facts.

Visible spectra of all the complexes contain a strong charge transfer absorption with a shoulder at  $\sim 19000 \text{ cm}^{-1}$ . This prevents appearance of any d-d bands.

#### Acknowledgement

Grateful thanks of the authors are due to the University Grants Commission, New Delhi for a Research Fellowship to one of them (K. M.).

#### References

1. SATYA PAL SINGH, Y. K. BHOON, K. B. PANDEYA and R. P. SINGH, *J. Indian Chem. Soc.*, (submitted).
2. O. UNGER, *Chem. Ber.*, 1897, 30, 607.
3. F. P. DWYER, N. S. GILL, S. C. GYARFAS and F. LIONS, *J. Amer. Chem. Soc.*, 1954, 76, 383.
4. A. CHAKRAWARTY, B. BEHERA and P. S. ZACHARIAS, *Inorg. Chim. Acta*, 1968, 2:1, 85.
5. B. BEHERA and P. S. ZACHARIAS, *Spectrochim. Acta*, 1971, 27(a), 2273.
6. P. S. ZACHARIAS and A. CHAKRAWARTY, *Inorg. Nuclear Chem. Lett.*, 1972, 8, 65.
7. P. S. ZACHARIAS, B. BEHERA and A. CHAKRAWARTY, Conference Report, XIV International Conference on Coordination Chemistry, Toronto, 1972.
8. P. S. ZACHARIAS and A. CHAKRAWARTY, *Inorg. Chim. Acta*, 1974, 11, 133.
9. P. S. ZACHARIAS and K. R. JOHNSON, *J. Inorg. Nuclear Chem.*, 1976, 38, 1957.
10. B. N. FIGGS and J. LEWIS, in "Modern Coordination Chemistry", (Ed.) J. LEWIS and R. G. WILKINS, Interscience, London, 1960, p. 403.
11. R. B. FLIPPEN and S. A. FRIEDBERG, *J. Appl. Phys.*, 1962, 31, 3385.
12. T. HASEDA, *J. Phys. Soc., Japan*, 1960, 15, 483.
13. B. C. GUHA, *Proc. Roy. Soc., (London)*, 1951, A206, 353.
14. L. C. JACKSON, *Phil. Trans. Roy. Soc., (London)*, 1923, A224, 1.
15. S. S. BHATNAGAR, M. L. KHANNA and M. B. NAVO, *Phil. Mag.*, 1938 25, 234.
16. R. C. PINK and R. C. HERRON, *J. Chem. Soc.*, 1956, 3948.
17. S. DATTA, *Phil. Mag.*, 1934, 17, 585.
18. R. B. JAMES, *Phys. Rev.*, 1935, 48, 78.
19. W. KLEMM and W. SHUTH, *Z. anorg. Chem.*, 1933, 210, 33.
20. B. N. FIGGIS and R. S. NYHOLM, *J. Chem. Soc.*, 1959, 338.
21. P. RAY and H. SAHU, *J. Indian Chem. Soc.*, 1946, 23, 161.
22. F. H. BURSTALL and R. S. NYHOLM, *J. Chem. Soc.*, 1952, 3570.
23. G. A. BARCLAY and R. S. NYHOLM, *Chem. Ind.*, 1953, 378.
24. R. C. STOUFFER, D. W. SMITH, E. A. CLEVINGER and T. E. NORRIS, *Inorg. Chem.*, 1966, 5, 1167.
25. I. M. STEWART, Ph.D. Thesis, Melbourne University, 1968.
26. C. M. HARRIS, T. N. LOCKYER, R. L. MARTIN, H. R. N. PATIL, E. SINN and I. M. STEWART, *Aust. J. Chem.*, 1969, 22, 2105.
27. D. BETTERIDGE and D. JOHN, *Analyst*, 1973, 98, 377.



# Equilibrium Study of the Mixed Complexes of Uranyl Ion with 3,5-Dinitrosalicylic as Primary and Some Substituted Carboxylic Acids as Secondary Ligands

D. N. SHELKE

Chemistry Department, Marathwada University, Aurangabad-431 004

Manuscript received 12 February 1981, revised 28 January 1982, accepted 1 May 1982

The stabilities of simple and mixed complexes of uranyl ion have been studied with 3,5-dinitrosalicylic acid as primary and malic, chlorosuccinic, dimercapto succinic, maleic, methylmalonic, dimethylmalonic, picolinic, dipicolinic or quinolinic acid as secondary ligands by pH metric method. Uranyl forms only 1:1 complex with maleic, chlorosuccinic and dimercapto succinic acid while 1:1 and 1:2 complexes are formed with all the other ligands. The relationship between complex stability and ligand basicity has been used to discuss the formation of mixed-ligand complexes.

THERE has been continuing interest over the years on mixed-ligand complexes of metal ions with biologically important ligands<sup>1-4</sup>. Considering the biological significance of uranyl compounds<sup>5-6</sup>, the ternary complexes of  $UO_2^{2+}$ -amino acids with some carboxylic acids have been studied<sup>7,8</sup>. As a part of systematic study of  $UO_2^{2+}$ -complexes with amino acids, pyridine carboxylic, thiodicarboxylic and simple dicarboxylic acids having 2 and 3 coordination sites, we had earlier reported the formation of series of complexes with these ligands<sup>9-12</sup>. We now report the mixed-ligand complex formation, occurring when uranyl ion is mixed with 3,5-dinitrosalicylic acid and other carboxylic acids. In addition, the present work was undertaken to examine the complexing ability of substituted succinic, malonic and pyridine carboxylic acids with  $UO_2^{2+}$ -3,5-dinitrosalicylic binary complexes and to discuss the preferential formation of ternary complexes over binary ones.

## Experimental

The ligands such as chlorosuccinic, dimercapto-succinic, methylmalonic, dimethylmalonic, picolinic, dipicolinic and quinolinic acids were obtained from Fluka (Germany). 3,5-Dinitrosalicylic, malic, maleic acids were B.D.H., AnalaR reagents. The purity of the ligands was checked by their melting points. Uranyl nitrate (B.D.H., AnalaR) was dissolved in perchloric acid to prepare stock solution. All solutions were prepared in glass distilled water. Details for the other chemicals and measurement of  $\mu$  are given in earlier papers<sup>11-14</sup>.

## Results and Discussion

The proton-ligand and metal-ligand stability constants of the simple complexes were calculated by Irving and Rossotti's method<sup>15</sup>. The mixed-

ligand stabilities and other equilibrium constants (Table 1) were evaluated by the method of Ramamoorthy and Manning<sup>17</sup> as outlined earlier<sup>18</sup>. The formation of simple and mixed species of uranyl complexes was the same and relevant equilibria were discussed earlier<sup>18,19</sup>. To illustrate the equilibrium concentrations in the systems containing 3,5-dinitrosalicylic and dicarboxylic acids, Fig. 1 shows the percentage distribution of the complexes formed in  $UO_2^{2+}$ -3,5-dinitrosalicylic-dipicolinic acid system as a function of pH.




Fig. 1. Distribution of various species present in ternary uranyl ion-3,5-dinitrosalicylic ( $H_2Y$ )-dipicolinic ( $H_2X$ ) acid system as a function of pH.  $M$  = uranyl ion free,  $MY$  = uranyl ion-3,5-dinitrosalicylic,  $MY_2$  = uranyl ion-(3,5-dinitrosalicylic)<sub>2</sub>,  $MX$  = uranyl ion-dipicolinic,  $MX_2$  = uranyl ion-(dipicolinic)<sub>2</sub>, and  $MXY$  = uranyl ion-dipicolinic-3,5-dinitrosalicylic acid.  $\mu = 0.1M$  ( $NaClO_4$ ), Temp.  $30 \pm 0.1^\circ$ .  $C_M = C_X = C_Y = 2.0 \times 10^{-3}M$ .

TABLE 1—LOGARITHMS OF EQUILIBRIUM CONSTANTS OF TERNARY COMPLEXES OF  $\text{UO}_2^{2+}$ -3,5-DINITROSALICYLIC\*\*  
(H<sub>2</sub>Y)-SECONDARY (H<sub>2</sub>X) LIGANDS

Secondary ligand/acids	Temp. 30°		$\mu = 0.1 \text{ M (NaClO}_4\text{)}$					$\Delta \log K$
	$\beta_{2Y}$	Standard deviations are given in parentheses	$K_{DXY}$	$K_{1YX}$	$K_{2XY}$	$K_{MX_1^*}$	$K_{MX_2^*}$	
Malic	10.37(3)	0.24	3.98	4.87	5.50	3.63	—	-1.52
Chlorosuccinic	8.70(1)	0.39 <sup>b</sup> 1.26 <sup>c</sup>	2.31	5.13	3.57	—	—	-1.25
Dimercaptosuccinic	8.41(3)	0.41 <sup>b</sup> -1.24 <sup>c</sup>	1.82	5.15	3.06	—	—	-1.24
Maleic	10.15(2)	0.26 <sup>b</sup> -1.39 <sup>c</sup>	3.76	5.00	5.15	—	—	-1.39
Methylmalonic	11.53(2)	0.50	5.14	4.83	6.70	4.22	—	-1.56
Dimethylmalonic	11.27(2)	0.52	4.88	4.95	6.32	4.05	—	-1.44
Picolinic	9.69(3)	0.04	3.30	5.23	4.46	3.75	—	-1.16
Quinolinic	9.80(3)	0.16	3.40	5.15	4.65 <sup>@</sup>	3.65 <sup>@</sup>	—	-1.25
Dipicolinic	11.48(4)	0.58	5.09	6.04	5.44	5.24	—	-0.35

a =  $\text{MX}_2 + \text{MY}_2 \rightleftharpoons 2\text{MXY}$ , b =  $\text{MX} + \text{MY}_2 \rightleftharpoons \text{MXY} + \text{MY}$  and c =  $\text{MX} + \text{MY} \rightleftharpoons \text{MXY} + \text{M}$

\*\*  $\log K_{MX_1} = 6.39$  and  $\log K_{MX_2} = 4.74$

\* ref. 11.

@ ref. 10.

In the system studied, all the ligands form 1 : 1 and 1 : 2 chelates except maleic, chlorosuccinic and dimercapto succinic acids. 3,5-Dinitrosalicylic acid can be considered as primary ligand and malic, maleic, chlorosuccinic, dimercaptosuccinic, methylmalonic, dimethylmalonic, picolinic, dipicolinic and quinolinic acids, which can respectively form seven, six, seven, seven, six, five, five and seven membered rings around the uranyl ion, as secondary ligands  $\Delta \log K$  values (Table 1) are negative for all the systems and indicate the preferential formation of ternary complexes over binary.

During the course of investigation, the order of  $\Delta \log K$  was reported<sup>10,11</sup> as carboxylic-carboxylic < carboxylic-phenolic < phenolic-phenolic acid systems. In the present work,  $\Delta \log K$  values are intermediate and are in agreement with earlier findings. Sigel<sup>12</sup> reported a method for the estimation of stability constants by the relation between ligand basicity and complex stability. The plots of  $\Delta \log K$  vs  $\Sigma pK$  gave an inverse as well as direct relationship between these two quantities for the mixed-ligand complexes of transition metal ions. These conclusions have been amply confirmed in subsequent studies involving dipeptides and amino acids in aqueous medium<sup>13</sup>. In the systems under investigation, the plot of  $\Delta \log K$  vs  $\Sigma pK$  (Fig. 2) gave direct relationship between these two quantities for closely related ligands. However, the point corresponding to dimethylmalonic acid as secondary ligand deviates from the straight line. The destabilized nature of the mixed-complex in this system is explained on the basis of steric hindrance due to the presence of two methyl groups and two nitro groups in dimethylmalonic acid and 3,5-dinitrosalicylic acid, respectively. In view of this, the higher value of mixed-ligand stability (Table 1) for methylmalonic

than that of dimethylmalonic acid system is also understandable.




Fig. 2. Relation between  $\Delta \log K$  and ligand stability for ternary complexes of  $\text{UO}_2^{2+}$ -3,5-dinitrosalicylic carboxylic acids. Carboxylic acids: 1) malic 2) chlorosuccinic, 3) dimercaptosuccinic, 4) maleic 5) methylmalonic, 6) dimethylmalonic, 7) picolinic 8) quinolinic.  $\mu = 0.1 \text{ M (NaClO}_4\text{)}$ ,  $t = 30^\circ$ .

$K_{DXY}$  values in most of the systems studied here are close to those predicted on statistical considerations. The value of 0.04 of  $K_{DXY}$  in 3,5-dinitrosalicylic-picolinic acid system indicates the equilibrium tendency of mixed-ligand formation by disproportionation reaction and dianion to bond 1 : 1  $\text{UO}_2^{2+}$  picolinate complex. The values -1.39 and +0.2 -1.26 and +0.39; -1.24 and +0.41 of  $K_{DXY}$  for both disproportionation reaction in the system corresponding to maleic, chlorosuccinic and dimercaptosuccinic acids as secondary ligands indicate the stabilized nature of 1 : 1  $\text{UO}_2^{2+}$ -3,5-dinitrosalicylate and ternary complex, respectively.

The formation of ternary complex is mainly dependent on ring size of the chelate which seems to offset the increasing basicity of the secondary ligands observed from the direct relationship between  $K_{XYZ}$  and the product of the acid dissociation constants for the closely related ligands. The inverse relationship between these two quantities is also reported in our studies on mixed-ligand complexes of uranyl ion involving pyridine carboxylic and dicarboxylic acids as ligands<sup>12,24</sup>.

The values of  $K_{XYZ}$  and  $K_{MX}$  (Table 1) indicate the formation of mixed complexes over the simple except for the systems involving maleic, chlorosuccinic and dimercaptosuccinic acids as secondary ligands. A comparison of  $K_{XYZ}$  and  $K_{MY}$ , especially in the systems involving methylmalonic, dimethylmalonic and dipicolinic acid as secondary ligands reveals the preferential formation of ternary complexes over binary ones.

The order of overall stabilities is methylmalonic > dipicolinic > dimethylmalonic > malic > maleic > quinolinic > picolinic > chlorosuccinic > dimercaptosuccinic, which is in accordance with the 1:1 binary stabilities. The plots of  $\beta_{XY}$  vs  $K_{MX}$  (Fig. 3) gave direct relationship. However, the point corresponding to dipicolinic acid complex deviates from the straight line.




Fig. 3. Relation between  $\beta_{XY}$  and  $\log K_{MX}$ , for ternary complexes of uranyl ion with 3,5-dinitrosalicylic and carboxylic acids. Carboxylic acids: 1) maleic, 2) chlorosuccinic, 3) dimercaptosuccinic, 4) maleic, 5) methylmalonic, 6) dimethylmalonic, 7) picolinic, 8) quinolinic, 9) dipicolinic.  $\mu = 0.1M$  ( $NaClO_4$ ),  $t = 30^\circ$ .

#### Acknowledgement

The author is grateful to Prof. S. S. Pawar, Head, Chemistry Department, for facilities. The Financial support from the U. G. C., New Delhi is also gratefully acknowledged.

#### References

1. J. V. RUND and K. G. CLAUS, *Inorg. Chem.*, 1969, 8, 59.
2. H. SIGEL, "Metal Ions in Biological Systems", Marcel Dekker Inc., New York, 1973, 2, 65; 1976, 5, 148, 250; 1979, 0, 8, 100, 146; 1979, 9, 95, 164.
3. A. GERGELY and I. NAGYPAL, *J. Chem. Soc., Dalton Transactions*, 1977, 1109.
4. G. BROOKES and L. D. PETIT, *J. Chem. Soc., Dalton Transactions*, 1977, 1918.
5. P. D. BOGER, "The Enzyme", Vol. 1, 3rd Edn., Academic Press, New York, 1970.
6. C. C. F. BLAKE, *Advan. Protein Chem.*, 1968, 23, 59.
7. P. V. SHELVARAJ and M. SANTAPPA, *J. Inorg. Nuclear Chem.*, 1976, 38, 837.
8. P. V. SHELVARAJ, Ph.D. Thesis, Madras University, Madras, 1974.
9. D. N. SHELKE and D. V. JAHAGIRDAR, *Indian J. Chem.*, 1978, 16A, 60.
10. D. N. SHELKE and D. V. JAHAGIRDAR, *J. Inorg. Nuclear Chem.*, 1979, 41, 929.
11. D. N. SHELKE, B. R. ARBAD and D. V. JAHAGIRDAR, *J. Indian Chem. Soc.*, 1979, 56, 947.
12. D. N. SHELKE and D. V. JAHAGIRDAR, *J. Indian Chem. Soc.*, 1980, 57, 596.
13. D. N. SHELKE and D. V. JAHAGIRDAR, *Acta Cincia Indica*, 1980, 6, 70.
14. D. N. SHELKE and D. V. JAHAGIRDAR, *Bull. Chem. Soc., Japan*, 1976, 42, 2142.
15. J. KIELLAND, *J. Amer. Chem. Soc.*, 1937, 59, 1675.
16. H. IRVING and H. ROSSOTTI, *J. Chem. Soc.*, 1953, 3397; 1954, 2904.
17. S. RAMAMOORTHY and P. G. MANNING, *J. Inorg. Nuclear Chem.*, 1972, 34, 1977.
18. D. N. SHELKE, *Inorg. Chim. Acta*, 1979, 32, L45.
19. D. N. SHELKE and D. V. JAHAGIRDAR, *J. Inorg. Nuclear Chem.*, 1979, 41, 925.
20. D. N. SHELKE and D. V. JAHAGIRDAR, *J. Inorg. Nuclear Chem.*, 1977, 39, 2223.
21. V. D. KHANOLKAR, D. V. JAHAGIRDAR and D. D. KHANOLKAR, *J. Inorg. Nuclear Chem.*, 1973, 35, 931.
22. H. SIGEL, *J. Inorg. Nuclear Chem.*, 1975, 37, 507.
23. D. N. SHELKE, B. R. ARBAD and D. V. JAHAGIRDAR, *Inorg. Chim. Acta*, 1980, 46, L17.
24. D. N. SHELKE and D. V. JAHAGIRDAR, *J. Inorg. Nuclear Chem.*, 1981, 43, 174.

# Studies on Hydrazones, Semicarbazones, Thiosemicarbazones and Oximes as Ligands. Part-III : Some Divalent Metal Complexes of Benzil Semicarbazone

R. C. MISHRA and B. K. MOHAPATRA\*

Department of Chemistry, B. J. B. College, Bhubaneswar-751 014

and

D. PANDA

Department of Chemistry, S. C. S. College, Puri


Manuscript received 14 May 1981, revised 2 February 1982, accepted 1 May 1982

A number of complexes of the composition  $MLX_2$  or  $ML_2X_2$ , where M is Mn(II), Co(II), Ni(II), Cu(II), Zn or Cd, X is  $Cl^-$ ,  $NCS^-$  or  $ClO_4^-$  and L is benzil semicarbazone have been synthesised and characterised on the basis of analysis, conductance, magnetic susceptibility, infrared and electronic spectral data.

IN the programme of preparing complexes of rare and higher coordination number<sup>1(a,b)</sup> ligands with divalent first transition series metal ions, we have been synthesising polydentate chelating ligands since such ligands dominate the area of higher coordination polyhedra in scope and numbers and also from the kinetic and thermodynamic stability point of view. The compact nature of polydentate Schiff bases particularly make them more effective in attaining high coordination structure. Complexation behaviour of bi-, tri- and tetradentate ligands has been reported earlier<sup>1-4</sup>. It was thought worthwhile to have a comparative study of the complexing abilities of hydrazones, semicarbazones, thiosemicarbazones and oximes towards the transition metal ions. As a part of this programme, complexes of benzil phenylhydrazine, 2,4-dinitrophenylhydrazine and oxime have been reported<sup>5-8</sup>. This communication describes some complexes of Mn(II), Co(II), Ni(II), Cu(II), Zn and Cd salts with benzil semicarbazone as the ligand.

## Experimental

Benzil semicarbazone  $C_6H_5-C(=O)-C(=O)-C_6H_5$



was prepared by a known method<sup>9</sup>. Analysis of the compound corresponds to benzil monosemicarbazone and its melting point is 242° (against 244°).

Ethanol solutions of different metal salts were reacted with the ligand in 1 : 2 proportion and the solution refluxed for 30 min to 1 hr. The solutions were concentrated by a rotary vacuum evaporator and kept standing in a refrigerator when crystalline compounds separated out. In some cases addition of petroleum ether was necessary for the isolation of the complexes. These were filtered under suction, washed with absolute ethanol followed by ether and dried in vacuum. Metal, halogen, thiocyanate and nitrogen were estimated as reported earlier<sup>9,10</sup>. Conductance was measured in 10<sup>-3</sup> acetone solution of the complexes using Toshniwal conductivity bridge. Magnetic susceptibility measurements were made over solid specimens by Gouy method. Infrared spectra were recorded on Perkin Elmer 621 spectrophotometer. Visible electronic spectra were recorded in 10<sup>-3</sup>M chloroform solution of the compounds using Hilger Watt Uvispek spectrophotometer. The relevant analytical data are presented in Table 1 and some of the spectral data in Table 2.

## Results and Discussion

Manganese, nickel and zinc complexes are of the composition  $MLX_2$ , whereas copper, cadmium and cobalt complexes are of the formula  $ML_2X_2$ . Manganese and zinc complexes are yellowish white, cadmium complexes are white, nickel complexes are deep yellow, copper complexes are light green and cobalt complexes are brown, orange or green in colour. Molar conductance values in acetone medium are low indicating non-electrolytic nature of the complexes, excepting cobalt and cadmium perchlorate complexes which are 1 : 2 electrolytes.

\* Author for correspondence.

TABLE 1—ANALYTICAL DATA OF BENZIL SEMICARBAZONE COMPLEXES

Compounds	$\lambda_{\text{max}}$ mhos. cm <sup>2</sup>	% Metal		% halogen, thiocyanate or nitrogen		$\mu_{\text{eff}}$ B.M.
		Found	Calcd.	Found	Calcd.	
1. MnLCl <sub>2</sub>	10.9	13.58	13.98	17.81	18.07	5.9
2. MnL(NCS) <sub>2</sub>	8.4	13.32	12.55	26.21	26.49	5.8
3. MnL(NO <sub>3</sub> ) <sub>2</sub>	10.2	12.15	12.32	15.54	15.70	5.8
4. MnL(ClO <sub>4</sub> ) <sub>2</sub>	10.5	10.36	10.55	7.78	8.06	5.9
5. CoL <sub>2</sub> Cl <sub>2</sub>	11.2	8.71	8.93	10.38	10.69	4.9
6. CoL <sub>2</sub> (SCN) <sub>2</sub>	9.8	8.14	8.31	16.21	16.36	5.1
7. CoL <sub>2</sub> (NO <sub>3</sub> ) <sub>2</sub>	7.9	8.05	8.22	15.45	15.62	5.0
8. [CoL <sub>2</sub> ](ClO <sub>4</sub> ) <sub>2</sub>	245	7.25	7.44	10.28	10.60	4.9
9. NiLCl <sub>2</sub>	10.2	14.51	14.30	17.59	17.90	Diamag.
10. NiL(SCN) <sub>2</sub>	11.4	13.08	13.29	26.02	26.26	"
11. NiL(NO <sub>3</sub> ) <sub>2</sub>	9.4	12.82	13.06	15.25	15.57	"
12. CuL <sub>2</sub> Cl <sub>2</sub>	11.5	9.21	9.50	10.43	10.62	1.78
13. CuL <sub>2</sub> (SCN) <sub>2</sub>	11.2	8.45	8.90	16.11	16.26	1.79
14. CuL <sub>2</sub> (NO <sub>3</sub> ) <sub>2</sub>	12.8	8.54	8.80	15.34	15.52	1.81
15. ZnLCl <sub>2</sub>	11.8	16.02	16.21	17.28	17.60	—
16. ZnL(SCN) <sub>2</sub>	12.5	14.25	14.58	25.48	25.87	—
17. ZnL(NO <sub>3</sub> ) <sub>2</sub>	10.8	14.16	14.33	15.21	15.34	—
18. CdL <sub>2</sub> Cl <sub>2</sub>	9.4	15.42	15.67	9.72	9.90	—
19. [CdL <sub>2</sub> ](ClO <sub>4</sub> ) <sub>2</sub>	242	13.12	13.30	9.75	9.94	—
20. [ZnL <sub>2</sub> ](ClO <sub>4</sub> ) <sub>2</sub>	235	7.85	8.19	10.35	10.52	—

L = Benzil semicarbazone

TABLE 2—SPECTRAL DATA OF SOME COMPLEXES

Compound No.	$\nu(\text{C}=\text{O})$	$\nu(\text{C}=\text{N})$	$\nu(\text{N}-\text{N})$	$\nu(\text{M}-\text{O})$	$\nu(\text{M}-\text{N})$	$\nu_{\text{max}}$ in kK ( $\epsilon$ )
1	1630	1580	1015	460	320	20.4(1), 22.0(2), 24.5(2)
4	1630	1585	1020	465	320	20.2(2), 22.2(2), 24.0(2)
5	1635	1580	1020	470	325	19.8(38), 20.1
8	1630	1590	1020	470	330	19.9(35), 20.4
9	1635	1585	1015	475	330	15.0(58)
12	1630	1580	1020	485	335	14.8(42)
16	1630	1580	1020	480	335	—
19	1635	1585	1015	485	340	—

Magnetic moment values of manganese complexes are in the range of 5.8–5.9 B.M. Cobalt complexes have moments in the range 4.9–5.1 B.M., suggesting an octahedral environment. Nickel complexes are diamagnetic and copper complexes have  $\mu_{\text{eff}}$  values in the range 1.78–1.82 B.M. Infrared spectra of benzil semicarbazone have main absorption bands at 3130, 1655, 1650, 1600 and 1000 cm<sup>-1</sup> assignable<sup>10</sup> to  $\nu(\text{N}-\text{H})$ ,  $\nu(\text{C}=\text{O})$ ,  $\nu(\text{C}=\text{N})$  and  $\nu(\text{N}-\text{N})$ , respectively.  $\nu(\text{N}-\text{H})$  in the complexes remains almost unaffected excepting in the chloro complexes where a lowering of the band occurs possibly due to hydrogen bonding with the anion.  $\nu(\text{C}=\text{O})$  is observed around 1630 cm<sup>-1</sup> along with a shoulder at 1645 cm<sup>-1</sup> probably indicating<sup>11</sup> the coordination through the oxygen atom of one of the carbonyl group, the other carbonyl remaining free.  $\nu(\text{C}=\text{N})$  in the complexes also shifts to lower frequency region and is observed around 1580 cm<sup>-1</sup> suggesting coordination through the azomethine nitrogen atom. This has been further substantiated by the observation<sup>12</sup> of  $\nu(\text{M}-\text{O})$  and  $\nu(\text{M}-\text{N})$  around 60–485 and 320–340 cm<sup>-1</sup> region. Thus, the ligand behaves as bidentate in all the cases excepting the cobalt perchlorate complex where only one carbonyl absorption is observed. Hence, the ligand in this complex coordinates through the oxygen atoms of both the carbonyl groups and the azomethine

nitrogen atom indicating the tridentate nature of the ligand.

In the thiocyanato complexes  $\nu(\text{C}\equiv\text{N})$  is found around 2090–2105 cm<sup>-1</sup> region, showing<sup>13</sup> the presence of terminal N-bonded thiocyanato group. Nitrate complexes have the  $\nu_1$  and  $\nu_4$  bands in the 1280 and 1410 cm<sup>-1</sup> region, respectively. The difference,  $\Delta\nu$ , is of the order of 130 cm<sup>-1</sup> suggestive<sup>14,15</sup> of monodentate nitrate coordination. In the cadmium, zinc and cobalt perchlorate complexes there is one broad absorption band at 1100 cm<sup>-1</sup> indicating<sup>16,17</sup> ionic perchlorate group in conformity with the molar conductance data suggestive of 1:2 electrolytic nature of the complexes.

In the visible electronic spectra of manganese complexes three absorption bands are observed around 20.0, 22.0 and 24.0 kK regions assignable<sup>18</sup> to  ${}^6\text{A}_1 \rightarrow {}^4\text{T}_1(\text{G})$ ,  $\rightarrow {}^4\text{T}_2(\text{G})$  and  $\rightarrow {}^4\text{A}_1(\text{G})$  transitions respectively. Extinction coefficient values are within 1 and 2. Thus, on the basis of the band positions and intensity, tetrahedral structure is presumed for these complexes. All the cobalt complexes give rise to one absorption band around 19–20 kK region with a shoulder on the high frequency side, attributable<sup>19</sup> to  ${}^4\text{T}_{1g}(\text{F}) \rightarrow {}^4\text{T}_{1g}(\text{P})$  transition, the shoulder may be the consequence of splitting due to spin orbit coupling. Lower energy

bands due to the transition  ${}^4T_{1g}(F) \rightarrow {}^4T_{2g}$ , could not be recorded due to limitations of the instrument. Hence, on the basis of the spectral bands, their intensity and magnetic moment values, a spin free octahedral stereochemistry is suggested for these complexes. Nickel complexes exhibit one absorption band around 14.5-15.0 kK region with extinction coefficient values round about sixty. A square planar configuration is assigned<sup>20</sup> to these complexes in conformity with the diamagnetic nature of the compounds. All the copper complexes exhibit one broad absorption band in the 14.8-15.5 kK regions indicating a distorted octahedral configuration<sup>21</sup>. On the basis of analysis, conductance and infrared spectral data, the zinc and cadmium complexes have presumably a tetrahedral environment around the metal ions. Thus in case of all the complexes possibly the ligand is bonded to the metal ions at site I and II excepting the cobalt perchlorate complex where the metal ion is bonded at site III in addition to site I and II.

#### References

- (a) V. ROMANO, M. CONSIGLIO, F. MAGGIO and T. PIZZINO, *Inorg. Nuclear Chem. Lett.*, 1978, 14, 135.  
(b) A. PASINI *et al.*, *Inorg. Nuclear Chem. Lett.*, 1977, 13, 511.  
(c) B. B. MOHAPATRA, S. GURU and B. K. MOHAPATRA, *Acta Chimica*, 1977, 94, 191.
- B. B. MOHAPATRA, S. GURU and B. K. MOHAPATRA, *J. Inorg. Nuclear Chem.*, 1977, 39, 2291.
- B. B. MOHAPATRA, S. GURU and B. K. MOHAPATRA, *J. Inorg. Nuclear Chem.*, 1978, 48, 1178.
- N. C. MISHRA, S. GURU and B. K. MOHAPATRA, *J. Indian Chem. Soc.*, 1979, 55, 829.
- C. D. RAO, S. GURU and B. K. MOHAPATRA, *J. Inorg. Nuclear Chem.*, 1980, 42, 1195.
- R. C. MISHRA, D. PANDA and B. K. MOHAPATRA, *J. Indian Chem. Soc.*, (Communicated).
- R. C. MISHRA, D. PANDA and B. K. MOHAPATRA, *Indian J. Chem.*, (Communicated).
- R. C. MISHRA, D. PANDA and B. K. MOHAPATRA, *J. Indian Chem. Soc.*, (Communicated).
- A. I. VOGEL, 'Practical Organic Chemistry', Longmans, London.
- R. M. SILVERSTEIN and G. C. BASLER, 'Spectrometric Identification of Organic Compounds', John Wiley, New York, 1963.
- Y. THAKUR and B. N. JHA, *J. Inorg. Nuclear Chem.*, 1980, 42, 449.
- J. R. FERRARO, 'Low Frequency Vibration of Inorganic and Coordination Compounds', Plenum Press, New York, 1971.
- A. TRAMER, *J. Chim. Phys.*, 1962, 59, 232.
- R. V. BIAGETTI, W. C. BOTJER and H. M. HAENDLER, *Inorg. Chem.*, 1965, 5, 379.
- A. B. P. LEVER, *Inorg. Chem.*, 1965, 4, 1042.
- G. DWYER, J. G. HARTLEY and L. M. VENANZI, *J. Chem. Soc.*, 1965, 1295.
- K. NAKAMOTO, 'Infrared Spectra of Inorganic and Coordination Compounds', Wiley, New York, 1963.
- B. N. FIGGIS, 'An Introduction to Ligand Fields', Wiley Eastern, New Delhi, 1967.
- A. B. P. LEVER, 'Inorganic Electronic Spectroscopy', Elsevier, Amsterdam, 1968.
- H. G. GRAY and C. J. BALLHAUBEN, *J. Amer. Chem. Soc.*, 1963, 85, 260.
- C. A. AGAMBER and K. G. ORREL, *J. Chem. Soc.*, 1969, 897.

# Characterization of Alumina—A Versatile Catalyst

V. KRISHNASAMY

Chemistry Section, A. C. College of Technology, Anna University, Madras-600 025

and

P. RATNASAMY

National Chemical Laboratory, Pune-411 008

Manuscript received 17 August 1981, revised 21 January 1982, accepted 28 April 1982

Different samples of alumina were prepared by impregnating pure alumina with potassium and fluoride ions and their heats of adsorption by adsorption of pyridine were determined by pulse flow technique in gas chromatograph in the temperature range 180-250°. The heats of adsorption decreased with addition of potassium and increased with addition of fluoride ions. Pure alumina had considerable total acidity; however, the Brønsted acidity was negligible.

Rate of dehydration of cyclohexanol was faster initially and decreased with increasing contact time. Cyclohexene, an intermediate registered a maximum at an intermediate contact time and then began to fall, while 1- and 3-methylcyclopentenes kept on increasing; the concentration of 1-methylcyclopentene was always higher than that of 3-methylcyclopentene. The dehydration of cyclohexanol followed a first order kinetics.

The mechanism of transformation of cyclohexanol over alumina has been explained in terms of both Brønsted and Lewis acid sites.

**A** LUMINA as catalyst or as catalyst support finds multiple uses in several important industrial processes like, dehydration, isomerization, cracking, polymerization, condensation and alkylation<sup>1</sup>. Alumina samples obtained from different sources are found to possess different activities<sup>2</sup>. The presence of acid sites over alumina has been acknowledged, though the nature of acidity, whether Brønsted or Lewis type has been a point of controversy<sup>3-5</sup>. Further, reactivity and selectivity of the catalytic alumina change with the impregnation of alkali or halide ions<sup>2,6</sup>.

An attempt has been made in the present work to correlate the activity of different alumina samples obtained by impregnation of pure alumina (from aluminium isopropoxide) with potassium and fluoride ions, with their heats of adsorption of pyridine, as it is a measure of the strength of acid sites. Cyclohexanol was chosen for this purpose because its transformation involves dehydration and skeletal and double bond isomerizations. Some of the steps are explained satisfactorily in terms of Lewis acid sites whose importance in bringing about various isomerization reactions has not been well recognised.

## Experimental

**Preparation of materials:** Alumina A, was prepared by hydrolysing aluminium isopropoxide with distilled water<sup>7</sup>. The precipitated aluminium hydroxide was filtered, washed thoroughly, cut into cakes and dried at 120° for 24 hr. The dried material was then activated at 500° in a stream of pure air for another 24 hr. The activated catalyst was crushed, powdered and sieved to 40-60 mesh size. A part of this material was used as such under the label catalyst A, and the rest was modified with potassium or fluoride ions.

Aluminas B and C were obtained by doping alumina A with potassium nitrate solution in water to give 0.9 and 2.2% by weight of K<sup>+</sup> as K<sub>2</sub>O in the catalyst, respectively. Alumina D was prepared by impregnating alumina A with hydrofluoric acid (40% solution, E. Merck) to give 5% by weight of HF in the catalyst. The samples were dried and activated as described earlier.

**Apparatus and procedure:** The surface area (BET), pore volume and average pore radius of the catalysts were determined by low temperature adsorption of nitrogen<sup>8</sup> and the results are presented in Table 1. The pulse flow technique of Eberly<sup>9,10</sup> was used to measure the heats of adsorption of pyridine on the various aluminas in the temperature range 180-250° and the results are given in Table 2. The total

TABLE 1—SURFACE PROPERTIES OF THE CATALYSTS SUCH AS SURFACE AREA, PORE VOLUME AND AVERAGE PORE RADIUS

Catalyst	$S_{BET}$ m <sup>2</sup> /g	$V_p$ ml/g	$r_A$
A	139	0.435	55
B	129	—	—
C	135	0.275	40
D	125	0.442	60

TABLE 2—HEATS OF ADSORPTION OF PYRIDINE (ACIDITY INDEX) AND ACTIVATION ENERGY

Catalyst	Heat of adsorption kcal/mole (acidity index)	Activation energy kcal/mole
A	17.6	1.20
B	9.2	1.06
C	6.2	0.70
D	22.9	0.70


acidity of aluminas A and D was determined by *n*-butylamine titration methods of Johnson<sup>11</sup> and are found to be 0.650 and 1.240 m mole/g, respectively. Brønsted acidity of alumina A was found to be only 0.02 m mole/g by potassium iodide-potassium iodate method<sup>12</sup>.

The reactions were carried out in a flow type fixed bed reactor. The operating variables, such as space velocity and particle size, were so chosen as to eliminate diffusion control on the reaction rate. The products were identified by Perkin-Elmer Infracord Model-137 and Perkin-Elmer Vapour Fractometer-154D and estimated using a 2 metre column of Bentone-34 in the Vapour Fractometer-154D.


### Results and Discussion

The heat of adsorption of pure alumina is found to decrease markedly from 17.6 kcal to 9.2 kcal by the addition of 0.9% by weight of potassium ions. When the doping increases to 2.2% the heat of adsorption falls still further to 6.2 kcal. On the other hand impregnation of alumina A with fluoride ions increases the heat of adsorption from 17.6 kcal to 22.9 kcal.

If the acidic sites on alumina are visualized as protons of the Al-O-H bond (Brønsted acid site), potassium, by replacing the protons in the hydroxyl group, reduces the concentration of Brønsted sites as shown below




Lewis acidity of the dehydrated alumina surface has been explained on the basis of incompletely coordinated aluminium atoms, and its formation is suggested to be as follows:



Introduction of potassium ions in the places of hydrogen during the preparation of the catalyst suppresses the formation of Lewis sites. This explains the lower heats of adsorption in the cases of aluminas B and C.

Hydrofluoric acid can enhance the acidic strength of the active sites in one or both of the following ways<sup>13</sup>:



In scheme A, the acidity of the proton is enhanced by the polarization induced in the adjacent bond by fluorine. In addition, the positive charge on the proton will be stabilized by the partial negative charge on fluorine. In scheme B, the fluorine attached to Al<sub>(2)</sub>, polarises the Al-O-Al bonds in the manner illustrated above and increases the Lewis acid strength of Al<sub>(1)</sub>.

The influence of contact time (W/F) on the rate of dehydration of cyclohexanol and the formation of products has been studied at 375° over alumina A and the results are illustrated in Fig. 1. The rate of dehydration is faster in the lower contact time regions. It decreases slowly and remains constant beyond 0.3 hr. The concentration of cyclohexene increases in the product, registers a maximum around 0.05 hr, and falls with further increase in contact time. Methylcyclopentenes begin to appear after 0.1 hr and keep on increasing; the concentration of 1-methylcyclopentene is always higher than that of 3-methylcyclopentene.




Fig. 1. Influence of contact time on the reactions of cyclohexanol; Catalyst Alumina A, Temp. 375°.

The effects of acidity index and temperature on the overall conversion of cyclohexanol are shown in Fig. 2. Increase in the acidity index of the catalyst and reaction temperature increases the conversion of cyclohexanol. However, at a fixed acidity index, more cyclohexanol reacted at higher temperature. Even though dehydration occurred over low acidity index alumina, it increased considerably with increasing acidity.

The extents of different reactions such as dehydration, skeletal isomerization and double bond isomerization as a function of acidity index are illustrated in Table 3. The most striking features of these results are the different rates at which the activity of aluminas in the various reactions are suppressed when its acidity is progressively reduced. The dehydration activity decreased steadily with increasing additions of potassium ions, while the skeletal and double bond isomerization activities fell






Fig. 2. Influence of acidity index and temp. on the conversion of cyclohexanol.

TABLE 3—COMPARISON OF DIFFERENT REACTIONS SUCH AS DEHYDRATION, SKELETAL ISOMERIZATION AND DOUBLE BOND ISOMERIZATION AS FUNCTION OF ACIDITY INDEX; . TEMP. 375°, CONTACT TIME 0.52 hr.

Acidity Index kcal/mole	6.2	9.2	17.6	22.9
Dehydration (mole %)	43.00	51.00	68.00	75.00
Skeletal isomerization (mole %)	0.00	4.00	55.00	55.00
Double bond isomerization (mole %)	0.00	0.00	20.00	20.00

sharply; the fall in the double bond isomerization activity is greater than that of skeletal isomerization activity.

The selectivity ratio (S R) of the catalyst as a function of acidity is given in Fig. 3. The concentration of cyclohexene drastically decreased with increasing acidity index of the catalyst while the concentration of methylcyclopentenes increased and consequently the selectivity ratio decreased.




Fig. 3. Influence of acidity index on the selectivity ratio.

The kinetics of dehydration of cyclohexanol over alumina A has been followed by plotting  $-\ln(1-X_A)$  (where  $X_A$  is the mole fraction of cyclohexanol disappeared) against contact time  $W/F$  at 375° (where  $W$  is the weight of the catalyst and  $F$  is the amount of cyclohexanol fed into the reactor per hour). The plot gives a straight line (Fig. 4) indicating that the reaction follows a first order kinetics. The rate constant calculated from the slope of the first order plot is  $2.065 \text{ hr}^{-1}$ . The variation of rate constant with temperature is illustrated in Fig. 5 and the energy of activation computed from the slopes of the Arrhenius plots are recorded in Table 2.




Fig. 4. First order plot; catalyst Alumina A, Temp. 375°.





Fig. 5. Arrhenius plots.

**Mechanism:** Both Dewing<sup>3</sup> and Pearson<sup>4</sup> claim to have detected the presence of Brönsted acid centres on alumina while Knözinger<sup>5</sup> has concluded that alumina possesses no such species. The presence of Lewis acid sites over alumina surfaces and also its importance in bringing about reactions, such as

different types of isomerizations of olefins<sup>1,4</sup> are well recognized. Further, determination of acidity of alumina shows that it possesses a very significant amount of total acidity. However, the presence of Brönsted acidity is much too small (vide Experimental). In view of the above, the mechanisms of reactions involving the transformation of cyclohexanol are explained both by Brönsted and Lewis acid sites.

The reaction of cyclohexanol is known to proceed by a consecutive reaction, in which cyclohexene, formed initially by dehydration of cyclohexanol, undergoes skeletal isomerization to 1-methylcyclopentene. This may subsequently isomerize to 3-methylcyclopentene by shifting of double bond.



The mechanism involves initial protonation of cyclohexanol, the proton coming from the Brönsted acid site of the catalyst, followed by dehydration

with the formation of a carbonium ion. Cyclohexene desorbs from the surface with simultaneous elimination of a proton. The cyclohexene adsorbs onto a Lewis acid site resulting in the formation of a carbonium ion which suffers skeletal isomerization involving a less stable primary carbonium ion, which rearranges to a more stable tertiary carbonium ion by 1,2-hydride shift. This then desorbs as 1-methylcyclopentene. The 1-methylcyclopentene is attacked by a proton leading to the formation of a tertiary carbonium ion, which changes to a secondary carbonium ion by 1,3-hydride shift. This eliminates a proton giving rise to 3-methylcyclopentene. The fact that 1,3-hydride shift is not so easy as the 1,2-hydride shift, accounts for the lower concentration of 3-methylcyclopentene.

#### References

1. A. S. RUSSEL, "Aluminium Properties", Aluminium Co. of America, Pittsburg, 1953, Technical Paper No. 10, p. 24.
2. H. PINES and W. O. HAAG, *J. Amer. Chem. Soc.*, 1960, **82**, 2471.
3. J. DEWING, G. T. MONKS and B. YOULL, *J. Catal.*, 1976, **44**, 226.
4. R. M. PEARSON, *J. Catal.*, 1977, **46**, 279; 1978, **53**, 173.
5. H. KNÖZINGER, *J. Catal.*, 1978, **53**, 171.
6. G. FEACHAM and H. T. S. SWALLOW, *J. Chem. Soc.*, 1948, 267.
7. H. PINES and W. O. HAAG, *J. Amer. Chem. Soc.*, 1961, **83**, 2847.
8. P. H. EMMETT, "Catalysis", Reinhold Publ. Co., N. Y., 1954, Vol. I, p. 31.
9. P. E. EBERLY, JR., *J. Phys. Chem.*, 1961, **65**, 1261.
10. P. E. EBERLY, JR. and C. N. KIMBERLIN, JR., *Trans. Faraday Soc.*, 1961, **57**, 1169.
11. O. JOHNSON, *J. Phys. Chem.*, 1955, **59**, 827.
12. S. P. WALVEKAR and A. B. HALGERI, *Indian J. Chem.*, 1973, **11**, 662.
13. H. P. BOCHM, *Angew. Chemie*, 1966, **56**, 533.
14. M. W. TAMELE, *Discuss. Faraday Soc.*, 1950, **8**, 270.

# Studies on the Suppression of Polarographic Maximum of Mn(II) by Some uni- and poly-valent Cations vis-a-vis Their Influence on the Kinetics of the Electrode Reaction of Mn(II)

ASHOK KUMAR\*, KAILASH CHANDRA and MUKHTAR SINGH

Department of Chemistry, Agra College, Agra-282 002

Manuscript received 13 July 1981, revised 17 March 1982, accepted 1 May 1982

Suppression of the polarographic maximum of Mn(II) in 0.05 M KCl, which falls in the category of the negative maximum of the first kind, has been attempted using some uni- and poly-valent metal cations, viz, Li<sup>+</sup>, Na<sup>+</sup>, K<sup>+</sup>, Ba<sup>2+</sup>, Sr<sup>2+</sup>, Ca<sup>2+</sup>, Mg<sup>2+</sup>, La<sup>3+</sup>, Nb<sup>5+</sup> and Pr<sup>3+</sup> as suppressors. The electrode reaction of Mn(II) has been found to be quasi-reversible in the presence of different amounts of these suppressors. The values of kinetic parameters ( $\alpha$  and  $k_{\text{f,h}}$ ) of quasi-reversible electrode reaction of Mn(II) have been calculated by Gellings' method. A decrease in the values of  $\alpha$  and  $k_{\text{f,h}}$  with increasing concentrations of uni- and poly-valent cations shows that the quasi-reversible electrode reaction of Mn(II) tends towards irreversibility. On the basis of molarity, the order of relative efficacies of metal cations in the suppression of the negative maximum of Mn(II) has been established as  $\text{M}^{3+} > \text{M}^{2+} > \text{M}^{+}$ .

LALE and Srivastava<sup>1-3</sup> reported that Mn(II) exhibited a negative maximum of first kind in KCl and attempted its suppression by some aliphatic alcohols and also by various cations. They reported that in the presence of Th<sup>4+</sup> ions, the maximum of Mn(II) is more exalted than suppressed. This observation contradicts the statement<sup>4</sup> that heavy metal cations suppress the maxima more readily than do those of light elements. The central idea of these studies has been to find the optimum concentration at which the maximum is just suppressed and then to formulate an order of efficacies on the molarity scale. Recently, Ram *et al*<sup>4</sup> have attempted the suppression of the maximum of Mn(II) by various ionic (both cationic and anionic) and non-ionic surfactants and compared their relative efficacies in the suppression of this maximum on the basis of their characteristic properties. In the present paper an attempt has been made to suppress the maximum of Mn(II) by some uni- and poly-valent cations and then to study the influence of these cations on the kinetics of the electrode reaction of Mn(II). The order of relative efficacies of uni- and poly-valent cations in the suppression of the maximum of Mn(II) has been established on the basis of molarity scale of concentration.

## Experimental

All the chemicals used were of reagent grade and their stock solutions were prepared in conductivity water. The concentration of Mn(II) (using MnCl<sub>2</sub>,

2H<sub>2</sub>O) was kept at  $1.0 \times 10^{-3}$  M in each case. 0.05 M KCl was used as the supporting electrolyte. The polarograms of the solutions were taken on a manual set-up<sup>5</sup>. Stock solutions (2 M) of Li, Na, K (as nitrates) and of Ba, Sr, Ca and Mg (0.1 M) (as nitrates) were prepared by direct weighing from A.R., B.D.H., samples. The concentrations of the rare earth cations (as nitrates) in their stock solutions were determined by standard methods<sup>6-7</sup>. Solutions of desired molarity were prepared from these stock solutions of known concentrations by dilution.

The experimental conditions such as the concentration of the depolarizer, the concentration of the supporting electrolyte (KCl), pH and the height of mercury column were adjusted in such a way as to obtain a sharp and well-defined maximum of Mn(II). These conditions were kept the same in all the cases throughout the study. Thus, the concentration of the depolarizer was kept at  $1.0 \times 10^{-3}$  M, that of the supporting electrolyte at 0.05 M, the pH of the medium at 6.0 (by adding very dilute solutions of HCl or NaOH) and the height of the mercury column ( $h_{\text{corr}}$ ) at 71.45 cm.

## Results and Discussion

The first kind polarographic maximum of Mn(II) under the chosen experimental conditions appears at -1.53V (vs S.C.E.). This lies well on the negative side of the electro-capillary curve and hence the maximum of Mn(II) is of negative polarity<sup>8</sup>. Representative Fig. 1 depicts the morphology of

\* Department of Chemistry, St. John's College, Agra.




Fig. 1. C-V curves of Mn(II) in the presence of increasing concentrations of  $Mg^{2+}$ .

1. 0.0 M, 2.  $0.7 \times 10^{-3}$  M, 3.  $1.1 \times 10^{-3}$  M, 4.  $1.2 \times 10^{-3}$  M, 5.  $2.8 \times 10^{-3}$  M, 6.  $4.0 \times 10^{-3}$  M.

C-V curves of Mn(II) in the presence of increasing concentrations of  $Mg^{2+}$ .

$E_{max}$  of Mn(II) gets shifted to positive potentials (Table 1) with increasing concentrations of uni- and poly-valent cations. The value of  $i_{max}$  decreases sharply before the suppression of the maximum, which indicates that the negative maximum of Mn(II) is susceptible to suppression by the requisite amounts of uni- and poly-valent cations. After the suppression of the maximum, Mn(II) yields, in each case, a well-defined wave which is diffusion-controlled.

TABLE 1—POLAROGRAPHIC CHARACTERISTICS AND KINETIC PARAMETERS FOR THE ELECTRODE REACTION OF Mn(II) IN THE PRESENCE OF INCREASING CONCENTRATIONS OF UNI- AND POLY-VALENT CATIONS AT  $25 \pm 0.1^\circ$ .  
 $h_{0.077} = 71.45$  cm;  $t = 3.1$  sec;  $m = 2.2$  mg/sec;  $m^{1/2}/t^{1/2} = 2.03$  mg<sup>1/2</sup>/s sec<sup>-1/2</sup> (IN 0.05 M KCl, OPEN CIRCUIT).

[Cation] M	$-E_{max}$ (S. C. E.)	$-E_{1/2}$ (S. C. E.)	$i_{max}$ $\mu A$	$i_d$ $\mu A$	Slope mV	$D \times 10^6$ cm <sup>2</sup> /sec	$\alpha$	$k_{s,h} (\times 10^4)$ cm/sec
0.0	1.53	—	15.71	—	—	—	—	—
$\times 10^1$				Li <sup>+</sup>				
0.8	1.52	—	14.73	—	—	—	—	—
1.6	1.51	—	8.90	—	—	—	—	—
2.0*	No max	1.489	—	7.51	41	6.85	0.80	8.62
11.6	"	1.493	—	5.70	47	3.95	0.75	5.13
				Na <sup>+</sup>				
0.6	1.52	—	14.32	—	—	—	—	—
0.7	1.51	—	7.78	—	—	—	—	—
0.8*	No max	1.489	—	7.64	40	7.11	0.80	7.22
3.2	"	1.492	—	5.84	44	4.15	0.72	1.55
				K <sup>+</sup>				
0.5	1.52	—	12.51	—	—	—	—	—
1.1	1.51	—	7.92	—	—	—	—	—
1.3*	No max	1.495	—	7.41	41	6.85	0.81	6.10
4.8	"	1.500	—	6.25	45	4.76	0.75	3.14
$\times 10^1$				Ba <sup>2+</sup>				
0.2	1.52	—	10.15	—	—	—	—	—
0.3	1.51	—	8.76	—	—	—	—	—
0.4*	No max	1.497	—	7.64	40	7.11	0.84	2.80
5.4	"	1.500	—	6.39	43	4.97	0.74	2.06
				Sr <sup>2+</sup>				
0.1	1.52	—	11.26	—	—	—	—	—
0.4	1.51	—	7.92	—	—	—	—	—
0.5*	No max	1.490	—	7.51	40	6.85	0.85	4.08
5.5	"	1.500	—	6.81	44	5.64	0.68	2.63
				Ca <sup>2+</sup>				
0.1	1.52	—	10.29	—	—	—	—	—
0.5	1.51	—	8.34	—	—	—	—	—
0.8*	No max	1.480	—	7.23	39	6.36	0.85	8.24
2.3	"	1.483	—	6.12	42	4.55	0.80	4.41
				Mg <sup>2+</sup>				
0.7	1.52	—	10.01	—	—	—	—	—
1.1	1.51	—	9.17	—	—	—	—	—
1.2*	No max	1.490	—	7.78	40	7.37	0.83	6.30
4.0	"	1.493	—	7.23	43	6.36	0.75	5.49
$\times 10^1$				La <sup>3+</sup>				
0.2	1.53	—	13.48	—	—	—	—	—
0.7	1.52	—	12.10	—	—	—	—	—
1.0	1.52	—	8.48	—	—	—	—	—
1.2*	No max	1.490	—	7.37	40	6.60	0.86	5.20
1.5	"	1.495	—	6.95	42	5.88	0.75	3.89
				Nb <sup>5+</sup>				
0.2	1.52	—	13.62	—	—	—	—	—
0.7	1.51	—	9.87	—	—	—	—	—
1.0*	No max	1.490	—	7.51	40	6.85	0.87	5.29
1.5	"	1.495	—	6.67	42	5.41	0.77	4.89
				Pr <sup>3+</sup>				
0.6	1.52	—	10.29	—	—	—	—	—
0.9	1.51	—	7.92	—	—	—	—	—
1.0*	No max	1.493	—	6.95	41	5.88	0.88	8.56
2.0	"	1.495	—	6.81	43	5.64	0.78	6.49

\* Concentration at which the maximum just disappears.

A perusal of slope values (Table 1) of log plots shows that the slope values of 2-electron reduction process of  $Mn(II)$  lie in the range 39-49 mV which indicates<sup>6-12</sup> that the polarographic reduction of  $Mn(II)$  is quasi-reversible in the presence of increasing amounts of uni- and poly-valent cations. The values of kinetic parameters ( $\alpha$  and  $k_{s,n}$ ) of the quasi-reversible electrode reaction of  $Mn(II)$  have been calculated by Gellings' method<sup>14</sup>. The values of  $k_{s,n}$  are of the magnitude of  $10^{-2}$  cm/sec which confirm<sup>10,12</sup> the quasi-reversible nature of the electrode reaction of  $Mn(II)$ . It is observed that the value of  $k_{s,n}$  decreases with increasing concentrations of uni- and poly-valent cations. This shows that the quasi-reversible electrode reaction of  $Mn(II)$  tends towards irreversibility with increasing concentrations of uni- and poly-valent cations. It is also evident from Table 1 that the value of  $\alpha$  decreases with increasing concentrations of the cations thereby showing that the quasi-reversible electrode reaction of  $Mn(II)$  tends towards irreversibility. The variations in the values of  $k_{s,n}$  and  $\alpha$  thus lead to the same conclusion. Further, a negative shift in  $E_{1/2}$  and a decrease in  $i_d$  with increasing concentrations of uni- and poly-valent cations lend support to the conclusion arrived at on the basis of the variations in the values of  $k_{s,n}$  and  $\alpha$ .

By comparing the concentrations (on the molarity scale) of the various uni- and poly-valent cations at the stage where the maximum gets just suppressed, the order for the relative efficacies of various uni- and poly-valent metal cations in the suppression of

negative maximum of  $Mn(II)$  has been established as  $M^{3+} > M^{2+} > M^+$ .

#### Acknowledgement

Financial assistance to one of the authors (A. K.) from U. G. C., New Delhi is gratefully acknowledged.

#### References

1. S. LAL and S. N. SRIVASTAVA, *Indian J. Chem.*, 1968, 6, 382.
2. S. LAL and S. N. SRIVASTAVA, *Indian J. Appl. Chem.*, 1969, 32, 287.
3. J. HEYROVSKY and J. KUTA, "Principles of Polarography", Academic Press, New York, 1966, p. 438.
4. G. RAM, M. C. DUBBY and M. SINGH, *Indian J. Chem.*, 1979, 17A, 452.
5. S. K. JHA, ASHOK KUMAR, (KM.) ANJU VARSHNEY, (KM.) KRISHNA and M. SINGH, *J. Indian Chem. Soc.*, 1979, 56, 1259.
6. I. M. KOLTHOFF and R. ELMQUIST, *J. Amer. Chem. Soc.*, 1931, 53, 1225, 1235.
7. G. SCHWARZENBACH, "Complexometric Titrations", Methuen & Co. Ltd., New York, 1969, p. 73.
8. J. HEYROVSKY and J. KUTA, "Principles of Polarography", Academic Press, New York, 1966, p. 437.
9. J. N. GAUR, D. S. JAIN and A. KUMAR, *Indian J. Chem.*, 1975, 13, 165.
10. P. S. VERMA, D. S. JAIN and J. N. GAUR, *Indian J. Chem.*, 1975, 13, 586.
11. S. S. SHARMA, S. K. JHA and M. SINGH, *Z. Naturforsch.*, 1977, 32B, 416.
12. S. S. SHARMA, S. K. JHA and M. SINGH, *Indian J. Chem.*, 1977, 15A, 923.
13. S. S. SHARMA and M. SINGH, *J. Indian Chem. Soc.*, 1980, 57, 21.
14. P. J. GELLINGS, *Z. Elektrochem. Ber. Bunsenges, Phys. Chem.*, 1962, 66, 477, 481, 799; 1963, 67, 167.
15. P. DELAHAY, *J. Amer. Chem. Soc.*, 1953, 75, 1430.
16. H. MATSUDA and Y. AYABE, *Z. Elektrochem.*, 1959, 63, 1164.

# Chemisorption Kinetic Studies of Oxygen on $V_2O_5$ - $Ti_2O_3$

K. S. DE\* and K. GADGIL

Centre of Energy Studies, Indian Institute of Technology, Hauz Khas, New Delhi-110 016

Manuscript received 15 June 1981, revised 25 March 1982, accepted 1 May 1982

From studies on the chemisorption of oxygen over  $V_2O_5$ - $Ti_2O_3$  mixture and  $V_2O_5$  separately, it was observed that the mixture exhibited higher activity. With the help of X-ray, DTA and magnetic measurement of the sample an attempt has been made to correlate the enhanced activity with the changed oxidation states. Elovich equation was found to be obeyed in all cases. Attempt has also been made to represent the probable mechanisms of the reaction.

**V**ANADIUM pentoxide is known as an important catalyst for oxidation reactions. Different investigations on the various aspects of  $V_2O_5$  like X-ray structure analysis, adsorption studies, thermal behaviour, catalytic activity etc. has established that the anomalous behaviour of  $V_2O_5$  is due probably to the peculiar geometry<sup>1,2,3</sup> as well as different composition of the oxide. The presence of lower valent states, either singly or in combination with  $V_2O_5$ , is responsible for catalytic reaction (oxidation)<sup>4</sup>. However, the existence of lower valent states and the presence of different phases with varying composition make it difficult to attribute the catalytic activity uniquely to any particular oxidation state.

Titanium sesquioxide,  $Ti_2O_3$ , isomorphous with  $V_2O_5$  and  $Cr_2O_3$  shows anomalous electrical and magnetic properties related in origin to  $V_2O_5$ . It has been observed from a study of the states of  $TiO_2$  heated in vacuum<sup>5</sup> that at 300° it is partially reduced to  $Ti^{3+}$  while on heating to 500° and above not only oxygen but also titanium enter gas phase and a compound,  $Ti_{1-x}O_{2-y}$ , where  $y > x$  is formed. This process can lead, on subsequent treatment of the  $TiO_2$  with oxygen, to the development of p-type semiconductivity, though  $V_2O_5$  normally exhibits n-type semi-conductivity. It is assumed that the change in the properties of  $TiO_2$ , when treated under various conditions, is caused by a shift of the reaction  $Ti^{3+} + O_2 = Ti^{4+}/O_2$ . Thus,  $Ti^{3+}$  defects





Fig. 1. Plot of  $\Delta p$  vs  $\log(t+k)$ .

\* Department of Chemistry, Indian Institute of Technology, Kharagpur, W. B.



appearing on  $TiO_2$  lattice must always be accompanied by the evolution of molecular oxygen which has been found to be true only at temperature of 500° and above.

TABLE 1—MODEL RESULTS OF ADSORPTION OF OXYGEN

Expt. No 7 $P_0 = 17.05$ cm of Hg $T = 300^\circ$		Expt. No. 10 $P_0 = 27.2$ cm of Hg $T = 300^\circ$		Expt. No. 8 $P_0 = 8.8$ cm of Hg $T = 350^\circ$	
Time (min)	$\Delta p$ (cm of Hg)	Time (min)	$\Delta p$ (cm of Hg)	Time (min)	$\Delta p$ (cm of Hg)
1	0.07	1	0.10	1	0.08
2	0.08	2	0.12	2	0.10
3	0.10	4	0.15	3	0.12
5	0.12	6	0.17	5	0.14
7	0.13	8	0.19	7	1.16
9	0.14	10	0.21	9	0.18
11	4.15	12	0.23	11	0.20
13	0.16	15	0.24	15	0.22
15	0.17	20	0.25	20	0.24
20	0.20	25	0.26	25	0.25
25	0.20	30	0.27	30	0.27
30	0.21	40	0.28	40	0.30
40	0.25	50	0.29	50	0.32
		60	0.32		

For the present investigation we have used the catalyst  $V_2O_5$  containing  $Ti_2O_3$  in 3 : 1 mole ratio prepared at high temperature. It is certain that  $Ti^{3+}$  in the mixture is converted to  $Ti^{4+}$  during its prepar-

ation. But heating the catalyst in vacuum would again lead to partial reduction and  $Ti^{3+}$  formation as in  $TiO_2$ . So,  $V_2O_5$  containing  $Ti_2O_3$  as prepared would act as if it is a mixture of  $V_2O_5$ - $TiO_2$ . We, thus, aimed to study the effect of incorporation on chemisorption and electrical conductivity studies of  $V_2O_5$  with  $Ti_2O_3$ .

**Preparation of sample :** The sample of  $V_2O_5$  was prepared as described earlier<sup>6</sup>. The sample of titanium sesquioxide used was prepared<sup>7</sup> by the reduction of  $TiO_2$  by passing pure, dry hydrogen with titanium tetrachloride at 750° for 48 hr.

The sample of vanadium pentoxide containing titanium sesquioxide,  $V_2O_5$ - $Ti_2O_3$ , was prepared by mixing  $V_2O_5$  and  $Ti_2O_3$  in 3 : 1 mole ratio respectively in a porcelain basin at 800°-1000° in nitrogen atmosphere. The resulting product, after cooling, was extracted with oxalic acid, evaporated and decomposed in vacuum. The particle size chosen was -120+140 B.S.S.

**Characterisation of the sample :** The sample of  $V_2O_5$  was analysed chemically by the method of Caderbank<sup>8</sup> and the sample of  $Ti_2O_3$  was analysed by both volumetric<sup>9</sup> and gravimetric methods. 1.1% of  $V^{4+}$  ions were present in the sample of  $V_2O_5$ . In the volumetric analysis of  $Ti_2O_3$ , calculation on the basis of the equation  $V^{3+} + Ti^{3+} \rightarrow V^{4+} + Ti^{4+}$  gave the % of  $Ti^{3+}$  in the prepared  $Ti_2O_3$  as 66%. A direct method for gravimetric analysis of the




Fig 3 DTA thermograms. Heating curve— — — — — Cooling curve— - - - -

TABLE 2—MODIFIED ELOVICH PARAMETERS

Expt. No	Temp.	Pressures (cm of Hg)	$\alpha$ ( $\text{cm}^{-1} \text{min}^{-1}$ )	k (min)	to (min)	$a^*(a)$ ( $\text{cm g min}^{-1}$ )	$\Delta P_0$ (cm)
7	300	17.05	9.979	7	3.860	0.01451	0.0597
15	325	17.05	7.757	7	1.063	0.01842	0.2431
11	350	17.05	7.119	7	58.880	0.02007	-0.2991
24	375	17.05	7.037	7	1.484	0.02031	0.1051
10	300	27.20	15.35	1	0.4861	0.06515	0.047
18	325	27.20	16.89	7	0.003303	0.008460	0.4534
20	350	27.20	15.35	1	0.05413	0.06515	0.195
25	375	27.20	8.011	7	-1.1719	0.01783	0.2167
8	350	8.80	8.80	7	3.394	0.01621	0.0818
22	375	8.80	9.234	7	1.452	0.01547	0.1663
21	350	13.00	21.18	7	0.03442	0.006743	0.2506
23	375	13.00	6.50	7	-1.4084	0.021984	0.2721

TABLE 3—VALUES OF  $\alpha_1$ ,  $\alpha_2$ ,  $\alpha_3$ , CALCULATED FROM  $\Delta P$  VS LOG  $t$  PLOTS

Expt. No.	Temp (°C)	Pressure (cm of Hg)	$\alpha_1$	$\alpha_2$	$\alpha_3$
7	300	17.05	40.64	12.62	—
15	325	17.05	26.90	10.40	—
11	350	17.05	33.91	10.80	—
24	375	17.05	40.68	9.003	—
10	300	27.20	21.08	—	—
18	325	27.20	49.73	—	—
20	350	27.20	30.11	7.754	—
25	375	27.20	30.11	15.25	—
8	350	8.80	24.73	11.74	—
22	375	8.80	21.08	5.27	—
21	350	13.00	31.62	—	—
23	375	13.00	24.84	9.003	6.39

sample,  $\text{Ti}_2\text{O}_3 + \frac{1}{2}\text{O}_2 \rightarrow \text{TiO}_2$  was done and the value obtained was 99% of the theoretical value.

It is known that  $\text{V}^{5+}$  is a strong oxidising agent and  $\text{Ti}^{3+}$  a very strong reducing agent. In the oxide obtained by heating a mixture of  $\text{V}_2\text{O}_5$  and  $\text{Ti}_2\text{O}_3$ , it is almost certain that  $\text{Ti}^{3+}$  has been completely oxidized to  $\text{Ti}^{4+}$  and simultaneously  $\text{V}^{5+}$  has been reduced to some other lower valent states. Thus no chemical analysis of the sample regarding the oxidation states of the vanadium in it was attempted.

X-ray powder photograph of the specimen was obtained using a 2865 mm dia camera (Philips model PW 1008) and chromium radiation ( $\lambda=2.291 \text{ \AA}$ ) in






Fig. 4. (a) Plot of  $\log(\text{rate}) \left[ \text{Log} \left( \frac{d\Delta P}{dt} \right) \right]$  vs  $1/T \times 10^3$ .

(b) Plot of activation energy (E) vs coverage ( $\Delta P$ ).

$\Delta P$  (1) —○...○  
 $\Delta P$  (2) —△...△  
 $\Delta P$  (3) —□...□  
 $\Delta P$  (4) —◇...◇




Fig. 5. Plot of  $\text{Log } a^*$  vs  $1/T \times 10^3$ .

Expt. 55-60 —△...△  
 Expt. 46-51 —○...○  
 Expt. 70-74 —□...□

the absence of any filter. Approximately 6 hr exposure was given at 25 KV and 10 MA. Results are given in Table 4.

TABLE 4—X-RAY ANALYSIS DATA

Sample (After preparation)		Sample (after O <sub>2</sub> kinetics)	
Intensity	d(Å)	Intensity	d(Å)
F (B)		VF (B)	1.383
M	1.685	F (D)	1.718
VF	2.242	VF	1.840
VF	2.479	F	2.269
F	3.152	VF	2.583
		F	3.00
		M	3.388
		M	3.534
		F	4.557
		VF	5.920

Magnetic susceptibility was determined by using a Guoy balance at a field strength of  $3.64 \times 10^5$  gauss. Standard DTA analysis was done using




Fig. 6. Plot of  $\alpha$  vs  $1/T$ .  
17 cm (pressure) —○—  
27.2 cm (pressure) —○—

$\gamma$ -alumina as the reference. Surface area measurement was done by conventional BET method using liquid nitrogen and the surface area before and after adsorption were found to be  $14.1 \text{ m}^2/\text{g}$  and  $20.2 \text{ m}^2/\text{g}$  respectively. Oxygen gas used was prepared following the procedure described earlier<sup>6</sup>.

## Experimental

The method for sample preparation and degassing and the form of the Elovich equation<sup>10,11</sup> applied has been described by De and Gadgil<sup>6</sup>. The kinetic measurements were carried out in the temperature range  $275^\circ$ – $375^\circ$  using oxygen.

Adsorption isotherms were obtained and isosteric heats of adsorption were calculated from the isotherms by the use of Clausius-Clapeyron equations :

$$\log (P_1/P_2)_\theta = \frac{\Delta H_2}{4.57} \left( \frac{1}{T_1} - \frac{1}{T_2} \right) \quad \dots (1)$$

where the terms have their usual significance. Isobars have also been plotted.

At temperatures  $300^\circ$  and  $325^\circ$  kinetics proceeds too slowly within the pressure range 4.7–13 cm of Hg. So kinetics was studied at pressures 17.02 and 27.2 cm of Hg. All other measurements were done between 4.7–27.2 cm of Hg.

## Results and Discussion

Chemisorption of oxygen does not proceed at low temperatures and pressures over this sample. Adsorption starts at  $300^\circ$  for an initial pressure of 17 cm and 27.2 cm of Hg, and for  $350^\circ$  and  $375^\circ$  at other lower initial pressures ; e. g.,  $P_0 = 13$  cm and 8 cm of Hg.

All the plots of  $\Delta p$  vs  $\log t$  are linear with discontinuities with one or two breaks. But by choosing a suitable value of 'k' they could be linearised with the exception of two expts. The plots of  $\alpha$  vs  $1/T$  do not show any regular variation with  $P_0 = 17$  cm.  $\alpha$  vs  $1/T$  plot is parabolic whereas with  $P_0 = 27.2$  cm the plot shows a maximum at  $325^\circ$ . So a change in the nature of active sites<sup>1,2</sup> occur at  $325^\circ$ , at least for  $P_0 = 27.2$  cm of Hg. Adsorption isotherm studies indicate the adsorption to be highest at  $325^\circ$  and was further supported by an endothermic peak in the DTA thermogram at  $325^\circ$  proving this to be a characteristic temperature of the catalyst in respect of its behaviour as an oxidation catalyst (for oxygen chemisorption).

The initial massive adsorption,  $a^*$ , increases with temperature for  $P_0 = 17$  cm, but for  $P_0 = 27.2$  cm at  $375^\circ$  there is some deviation in the trend of increase shown in the plot of  $\log a^*$  vs  $1/T$ . Activation energy was calculated using  $a^*$  ( $a_1$ ) with the help of the equation :

$$\log (\text{rate}) = \log \left( \frac{d\Delta p}{dt} \right) = \log a - \frac{\alpha}{2.303} \times \Delta P_0 \quad \dots (2)$$

It has been found to be 4.37 K cal/mole for  $P_0 = 17$  cm and 9.14 K cal/mole for  $P_0 = 27$  cm. Plot of

TABLE 5—ISOSTERIC HEAT OF ADSORPTION ( $\Delta H$ ) CALCULATED FROM THE ISOTHERMS

300°–350°		300°–375°		325°–350°		325°–375°		350°–375°	
V(cc)	(K. Cal) $\Delta H$	V(cc)	(K. Cal) $\Delta H$	V(cc)	(K. Cal) $\Delta H$	V(cc)	(K. Cal) $\Delta H$	V(cc)	(K. Cal) $\Delta H$
3.0	2.48	3.0	17.80	3.0	15.96	3.0	33.8	3.0	53.08
3.5	3.46	3.5	17.60	3.5	15.75	3.5	31.99	3.5	49.55
4.0	3.80	4.0	16.36	4.0	14.90	4.0	29.10	4.0	44.38
4.5	3.13	4.5	15.40	4.5	14.19	4.5	27.90	4.5	42.73
5.0	3.07	5.0	15.44	5.0	14.70	5.0	28.47	5.0	43.36
5.5	3.07	5.5	14.89	5.5	15.67	5.5	28.06	5.5	41.02
6.0	2.58	6.0	14.09	6.0	17.87	6.0	28.56	6.0	40.11


activation energy ( $E$ ) vs coverage ( $\Delta_p$ ) is not linear, but shows a maximum around  $\Delta_p = 0.03$  cm. The parameter ' $t_0$ ' which according to Low<sup>13</sup> indicates the time at which slow adsorption starts, has been found to be irregular in the present case and is probably of minor importance.

It is rather certain that during the preparation of the sample  $V_2O_5$ - $Ti_2O_3$ ,  $Ti^{3+}$  present would have been oxidized to  $Ti^{4+}$  with simultaneous conversion of  $V^{5+}$  to  $V^{4+}$  and possibly to other lower valent states. But from the study of the states of  $TiO_2$  heated in vacuum<sup>8</sup>, it has been shown that it is converted to an non-stoichiometric compound of the type  $Ti_{1-x}O_{2-y}$  (titanium and oxygen entering gas phase) and  $Ti^{3+}$  is formed. X-ray analysis data show two strong lines with those of  $TiO_2$  ( $Ti^{4+}$ ) supporting our view.

Magnetic susceptibility measurements give  $\mu_{eff}$  to be 3.67 B.M. as against 3.89 indicating the presence of 3 unpaired electrons.

After pretreatment and evacuation of catalyst, probable sites for attach may be  $Ti^{3+}$ ,  $V^{4+}$ ,  $V^{5+}$  and other lower valent states of vanadium. Oxygen may be adsorbed on these sites either as  $O^-$ ,  $O_2^-$  or  $O^-$  species. But at high temperatures, the formation of the species  $O_2^{2-}$ <sup>14</sup> is ruled out owing to the fact that physically adsorbed oxygen may be a weakly chemisorbed species like  $O_2^{2-}$ <sup>14</sup>. From the table of heat of adsorption for the temperature range 350°–375°,  $\Delta H$  varies from 53–40 K cal. It is highly probable that at this temperature oxygen will be adsorbed as  $O^-$ , forming higher oxides. It has also been observed that after the chemisorption of oxygen, the chemisorption of hydrogen on the same specimen is higher indicating the likely adsorption of  $O^-$  species.

From the X-ray spectroscopic data of the sample after oxygen chemisorption studies, a very strong line has been found to coincide with a very strong line of  $TiO_2$  (Rutile) indicating the formation of the higher oxide. The probable mode of adsorption may be :



The conductivity of the pelleted sample was measured both in vacuum and in oxygen atmosphere. The conductivity in oxygen atmosphere at 300° increased in the first minute from  $27.02 \times 10^{-4}$  ohm<sup>-1</sup> cm<sup>-1</sup> to  $78.15 \times 10^{-4}$  ohm<sup>-1</sup> cm<sup>-1</sup> and then decreased continuously. The reason for this increase is probably the adsorption of  $O^-$  species, because  $O^-$  species have a tendency to donate one electron to the conduction band forming uncharged ' $O$ ' species. This has also been proved by the work of Morrison<sup>15</sup>. Adsorption in the later stage may proceed as



leading to a decrease in the conductance. The  $O^-$  species may accept an electron from the F centre or from the conduction band to form  $O^-$  species. This  $O^-$  may fill up the lattice vacancies leading to the formation of  $TiO_2$  and higher oxides of vanadium. As has been stated, the adsorption of oxygen directly as  $O^-$  is also not unlikely. But whatever may be the case, it is almost certain that excess of  $O^-$  are created after oxygen adsorption.

#### Conclusion :

From previous work<sup>4</sup> the activity of  $V_2O_5$  has been attributed to the joint presence of  $V_2O_5$  and  $V_2O_4$ , involving a dynamic equilibrium between  $V_2O_5$  like structure and  $V_2O_4$  like structure. Some recent work on the oxidation involving  $V_2O_5$ <sup>16</sup> suggest that the presence of different lower valent states are responsible for catalytic reactions. We have deliberately added  $Ti_2O_3$ , introducing more of defect centres and our work seem to corroborate this view. From the work of Bhattacharyya *et al*<sup>17</sup> and our work<sup>4</sup>, the adsorption does not proceed at low temperatures, pressures and small amounts of sample. Comparison of the results show that the defects introduced play a definite role in the adsorption of oxygen facilitating oxidation reactions.

#### References

1. K. TARAMA, S. TERANISHI, S. YESHIDA and N. TAMURA, Proc. 3rd Intern. Cong. on Cat., 1964.
2. P. MARS and D. W. VAN KREVALEN, Chem. Engg. Sci. 3 (Special Supplement to the Proc. of the Conferences on Oxide Processes), 1954, 41.

3. V. A. IOFFEE and I. B. PATRINA, *Soviet Phys. Solid State*, 1964, 6, 10, 2227.
4. G. L. SIMARD, J. E. STEGER, R. J. ARNAT and L. A. SISOAL, *Ind. Engg. Chem.*, 1955, 47, 1424.
5. M. N. DANCHEVSKAYA, G. N. PANASYUK and E. N. FIGUREVENKAYA, *Kinetics and Catalysis*, 1969, 4, 19.
6. K. S. DE and K. GADGIL, *Proc. Indian Nat. Sci. Acad.*, 1975, 41A, 107.
7. FRIEDEL and GUERIN, *Ann. Chem.*, 1976, 8, 38.
8. P. H. CADERBEANK, *J. Appl. Chem.*, 1952, 2, 482.
9. MACCARDLE and SCHEFFER, *Anal. Chem.*, 1951, 23, 1169.
10. S. Z. REGINSKII and YA ZALDOVICH, *Acta Phys.*, 1934, 1, 449.
11. S. J. BLOVICH, *Zh. Fiz. Khim.*, 1947, 21, 919.
12. H. A. TAYLOR and N. THON, *J. Amer. Chem. Soc.*, 1952, 76, 4169.
13. J. J. D. LOW, *Chem. Rev.*, 1960, 60, 267.
14. F. F. VOL'KENSTEIN, "Electronic Theory of Catalysis on Semiconductors", Pergamon Press, 1968.
15. S. R. MORISON, *Adv. Cat.*, 1957, 9, 204.
16. YA. VOL'FROM, YA. V. V. ZNIGALL, E. F. TOTIKAYA and RAKESHA, *Kinetika i Katalis*, 1965, 6, 1.
17. S. K. BHATTACHARYYA and P. MOHANTY, Ph.D. Thesis submitted to I.I.T., Kharagpur (1968), Proc. 4th Int. Cong. Cat., Moscow.

## Complexation of Salicylanilide with Some Metal Ions of Biological Interest

R. SAHAI\*, S. AGRAWAL and S. S. S. KUSHWAHA

Department of Chemistry, V. S. S. D. College, Kanpur-208 002

Manuscript received 21 July 1980, revised 27 July 1981, accepted 1 May 1982

In order to examine complexation as a possible mode of action of some fungicides, the complexation of salicylanilide with a few metal ions of biological interest, such as, Fe(III), Co(II), Ni(II), Cu(II), Zn(II), Zr(IV), La(III) and Th(IV), has been studied potentiometrically using Calvin-Bjerrum titration technique as employed by Irving and Rossotti. Protonation constant of the ligand and stability constants of the respective metal complexes have been determined at constant temperature (25°) and ionic strength (0.1 M, KNO<sub>3</sub>) in 70% (v/v) dioxan-water medium. Complexes of salicylanilide with Fe(III), Ni(II) and Cu(II) have also been prepared and characterized on the basis of elemental analysis and IR spectral data. A possible mechanism of action of this fungicide has been discussed.

THE activity of various metal ions in biological systems has been explained on the basis of different complexed species formed in the living organisms<sup>1,2</sup>. Metal ions are found in several fungi<sup>3</sup> and are reported to play important role in different enzymatic reactions. A survey of literature reveals that the role of metal ions in fungicidal activity is rather unexplored. Salicylanilide is a potential fungicide<sup>4</sup> and its mode of action has been investigated only to the extent of some physiological<sup>5,6</sup> changes occurring in fungi but the structural features have not been considered. To explore this aspect of fungicidal activity, complexation of salicylanilide with some metal ions of biological interest, such as, Fe(III), Co(II), Ni(II), Cu(II), Zn(II), Zr(IV), La(III) and Th(IV) has been investigated in solution potentiometrically. The complexes of Fe(III), Ni(II) and Cu(II) with salicylanilide have also been isolated in solid state and studied to establish the site of interaction.

### Experimental

**Materials:** All the metal nitrates used were of AR grade and their solutions were prepared in carbonate free double distilled water. Salicylanilide was obtained from Fluka A.G. and weighed quantity of the anilide was dissolved in 70% (v/v) dioxan-water medium.

**Potentiometric measurements:** A Beckman pH meter with glass calomel electrode assembly was used for pH measurements. The following mixtures were prepared for each metal and titrated against standard alkali using Bjerrum-Calvin pH-titration technique:

- (a) 5 ml KNO<sub>3</sub> (1.0 M) + 10 ml HNO<sub>3</sub> (0.01 M),

- (b) 5 ml KNO<sub>3</sub> (1.0 M) + 10 ml HNO<sub>3</sub> (0.01 M) + 10 ml ligand (0.01 M),  
(c) 5 ml KNO<sub>3</sub> (1.0 M) + 10 ml HNO<sub>3</sub> (0.01 M) + 10 ml ligand (0.01 M) + 2 ml metal nitrate (0.01 M).

Total volume of each system was kept at 50 ml by appropriate addition of water and dioxan. Representative potentiometric titration curves are shown in Fig. 1




Fig. 1. Potentiometric titration curves A: Free acid; B: Ligand (L); C: Cu(II)-L; D: Ni(II)-L; E: Co(II)-L; F: Fe(III)-L; G: Th(IV)-L.

**Protonation constant:** The average number of protons associated with a ligand,  $\bar{n}_A$ , was calculated using the formula of Irving and Rossotti<sup>7</sup>

\* Author for correspondence.

$$\bar{n}_A = Y + \frac{(V_1 - V_2)(N^0 + E^0)}{(V_0 + V_1)T_L^0}$$

where  $V_1$  and  $V_2$  denote the volume of alkali required to reach the same pH in titrations of  $\text{HNO}_3$  and ligand, respectively,  $T_L^0$  the total concentration of ligand,  $Y$  the total number of dissociable protons attached to a ligand,  $N^0$  the normality of alkali,  $V_0$  total volume of mixture and  $E^0$  the initial concentration of free acid. Proton ligand formation curve, obtained by plotting  $\bar{n}_A$  values against pH values, was utilized to evaluate the protonation constant employing various computational methods<sup>4</sup>.

**Metal-ligand stability constants:** The average number of ligand associated with a metal ion,  $\bar{n}$ , and the free ligand exponent,  $pL$ , were calculated by using equations,

$$\bar{n} = \frac{(V_2 - V_1)(N^0 + E^0)}{(V_0 + V_1) \bar{n}_A T_L^0}$$

and

$$pL = \log_{10} \left[ \frac{\beta \left( \frac{1}{\text{Antilog } \beta} \right)^n}{T_L^0 - \bar{n} T_M^0} \cdot \frac{(V_0 + V_2)}{V_0} \right]$$

Metal ligand formation curves (Fig. 2) obtained by plotting  $\bar{n}$  against  $pL$  were utilized to calculate successive stability constants of metal complexes using Rossotti's computational techniques<sup>5</sup>.




Fig. 2 Metal ligand formation curves. A: Fe(III)-L; B: Co(II)-L; C: Ni(II)-L; D: Cu(II)-L; E: Zn(II)-L; F: Zr(IV)-L; G: La(III)-L; H: Th(IV)-L.

**General method of isolation of complexes:** Equimolar amounts of salicylanilide and nickel or cupric nitrate were dissolved in ethanol separately. The solution of salicylanilide was neutralized with equimolar solution of NaOH in ethanol and added to excess of metal nitrate solution with constant stirring. The precipitate was filtered, washed with hot benzene and dried. The Fe(III) complex was isolated by adding neutral solution of salicylanilide into excess ferric chloride solution in ethanol. The mixture was filtered and the filtrate was evaporated.

Residue was recrystallized from ethanol to give Fe(III) complex. Some analytical data of these complexes are given in Table 1.

TABLE 1—SOME ANALYTICAL DATA OF THE METAL COMPLEXES OF SALICYLANILIDE

Complex	Colour	% Found (Calcd.)			
		C	H	N	M
Fe[C <sub>10</sub> H <sub>11</sub> O <sub>2</sub> N] <sub>2</sub>	Violet	67.50 (67.30)	4.23 (4.33)	6.57 (6.69)	7.96 (8.09)
Ni[C <sub>10</sub> H <sub>11</sub> O <sub>2</sub> N] <sub>2</sub>	Green	64.27 (64.40)	4.02 (4.14)	5.71 (5.80)	12.28 (12.16)
Cu[C <sub>10</sub> H <sub>11</sub> O <sub>2</sub> N] <sub>2</sub>	Olive green	63.89 (64.0)	4.0 (4.10)	5.62 (5.74)	13.09 (13.02)

## Results and Discussion

Protonation constant (Table 2) of salicylanilide was obtained by plotting  $\bar{n}_A$  against corresponding pH values and interpolating at half  $\bar{n}_A$  value of the curve. Examination of representative titration

TABLE 2—STABILITY CONSTANTS OF THE COMPLEXES OF SOME METAL IONS WITH SALICYLANILIDE;  $\mu = 0.1 \text{ M (KNO}_3\text{)}$ ;  $t = 25^\circ$  (PROTONATION CONSTANT OF SALICYLANILIDE,  $pK_a = 9.68$ )

Metal Ion	$\log k_1$	$\log k_2$	$\log k_3$	$\log \beta$
Fe(III)	9.84	9.76	—	19.60
Co(II)	7.80	7.15	—	14.95
Ni(II)	7.70	7.58	—	15.28
Cu(II)	8.08	7.56	—	15.64
Zn(II)	6.78	5.84	—	12.62
Zr(IV)	8.50	7.58	5.30	21.38
La(III)	7.40	6.28	5.60	19.28
Th(IV)	9.00	8.20	6.65	23.85

curves (Fig. 1) shows that metal titration curves are well separated from the ligand titration curve. Metal-ligand formation curves for Co(II), Ni(II), Cu(II) and Zn(II) (Fig. 2, curves B, C, D and E, respectively) are complete at both ends. Hence values of  $\log k_1$  and  $\log k_2$  were obtained directly by interpolating at  $\bar{n} = 0.5$  and  $1.5$ , respectively. Due to symmetry of formation curves, it was also possible to determine the stability constant data by 'mid point' method. Formation curves of Fe(III), Zr(IV), La(III) and Th(IV) (Fig. 2, curves A, F, G and H, respectively) are, however, incomplete in lower half portions and thus the values of  $\log k_2$  and  $\log k_3$  were obtained at  $\bar{n} = 1.5$  and  $2.5$ , respectively, while those of  $\log k_1$  were obtained using the equation,

$$\log k_1 \cdot k_2 = 2pL \text{ (at } \bar{n} = 1.0 \text{)}$$

The calculated values of  $\log k_1$ ,  $\log k_2$  and  $\log k_3$ , alongwith the protonation constant ( $pK_a$ ) of salicylanilide have been reported in Table 2. The  $\log k_3$  values for Zr(IV) and Th(IV) could not be calculated due to limited accuracy of  $\bar{n}$  values. The general order of overall stability constant values have been found to be: Th(IV) > Zr(IV) > Fe(III) > La(III) > Cu(II) > Ni(II) > Co(II) > Zn(II) in which Fe(III), Cu(II), Ni(II) and Co(II) are according to Irving-Williams' sequence<sup>6</sup>.

In the absence of metal ion hydrolysis, proton release on complexation can be only from the ligand. If the solutions are not highly alkaline, the protonation equilibrium investigated is  $HL \rightleftharpoons H^+ + L^-$  and complex formation takes place through the displacement of phenolic hydrogen.

The analysis of representative species distribution curves of Cu(II) complex (Fig. 3) reveals that the concentration of species  $CuL^+$  increases rapidly, attains a limiting value ( $\approx 50\%$ ) at a pH of 5 and decreases beyond this pH, thereby increasing the concentration of  $CuL_2$ . It has been noted that at higher pH values, almost all Cu(II) complexes with salicylanilide in the form of  $CuL_2$  ( $\approx 100\%$ ). Similar observations have been obtained with systems of salicylanilide with other metal ions where substantial decrease in the concentrations of  $ML^+$  species increases the concentrations of  $ML_2$  species. The maximum concentrations of  $ML^+$  type of complexes for Co(II), Ni(II), Zn(II), Zr(IV), La(III) and Th(IV), were found to be 44, 48, 59, 58, 64 and 54%, respectively, whereas for  $ML_2$  type complexes were found to be 95, 95, 96, 87, 50 and 73%, respectively. The concentrations of  $ML_2$  type complexes of Zr(IV), La(III) and Th(IV) were observed to attain limiting values at 93, 95 and 92%, respectively. In all the cases, the concentration of each species tends to approach a limiting value and total concentration of metal, present in various species, was found to be nearly 100% at any pH.





Fig. 3. Species distribution curves [given as the percentage of total Cu(II) present] of several species present in binary system of Cu(II) and salicylanilide ( $C_M = 1 \times 10^{-3} M$  and  $C_L = 2 \times 10^{-3} M$ ).

**Nature of reaction leading to complex formation :** There are three possible binding sites in salicylanilide, two in amide group (one through its oxygen and the other through the nitrogen atom) and the third one through the phenolate oxygen. The negative shift observed in the N-H stretching frequency of ligand from  $3270 \text{ cm}^{-1}$  to  $3250$ ,  $3255$  and  $3260 \text{ cm}^{-1}$  for Fe(III), Ni(II) and Cu(II) complexes, respectively, has been interpreted as due to intramolecular hydrogen bonding between N-H group and phenolate oxygen bonded to metal

ion and not due to bonding with metal ion as the potentiometric determination of dissociation constant of salicylanilide has provided only one protonation constant (Table 2) due to phenolic group. Further, lowering of  $\nu C=O$  of salicylanilide from  $1620 \text{ cm}^{-1}$  to  $1600$ ,  $1600$  and  $1585 \text{ cm}^{-1}$  for Fe(III), Ni(II) and Cu(II) complexes, respectively, provides substantial evidence that the metal ions are coordinated through oxygen atom of amide group (Structure 1). These results are further supported from the work of Rao<sup>7</sup>, Bilger and Pechmeze<sup>8</sup> and Pannu and Chopra<sup>9</sup> on similar systems.



Structure-1

On the basis of present investigation, it has been observed that salicylanilide is capable of forming stable complexes with the metal ions which are found in conjugation with the enzymes where these metal ions may establish 'some sort of equilibrium' with fungicides. Thus, the growth inhibition of fungi may be due to removal of a metal ion from the enzyme to form its complex with fungicide, thereby disturbing the biological activity. Similar observation on dithiocarbamates has been recorded by Gokosyr<sup>10</sup>, Smale<sup>11</sup> and Kaars Sijpesteijn *et al*<sup>12</sup>. A detailed investigation of this mechanism is in progress.

#### Acknowledgement

The authors are grateful to Dr. J. B. Singh (G. S. V. M. Medical College, Kanpur) for experimental facility and Prof. P. R. Singh (I. I. T., Kanpur) for encouragement.

#### References

1. "Metal Ions in Biological Systems", (Ed.) H. Sigel, Marcel Dekker, N. Y., 1973.
2. C. H. KAUFFMANN, *Proc. Internat. Congr. Pl. Sci.*, 1929, 2, 1603.
3. M. M. ISHAK and A. A. SARAF, *Com. Gen. Pharmacol.*, 1970, 1, 201.
4. M. KOPLAY, C. K. R. KURKUR, K. W. LAM and D. R. SANDI, *Biochem.*, 1970, 9, 3599.
5. H. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1953, 3397; 1954, 2904.
6. H. IRVING and R. J. P. WILLIAMS, *Nature*, 1948, 162, 746.
7. C. N. R. RAO, "Chemical Application of Infrared Spectroscopy", Academic Press, London, 1963.
8. X. BILGER and J. PECHMEZE, *Chem. Abs.*, 1959, 53, 15097c.
9. B. S. PANNU and S. L. CHOPRA, *Indian J. Chem.*, 1975, 13, 732.
10. J. GOKOSYR, *Physiol. Pantarum*, 1955, 8, 719.
11. B. C. SMALE, *Dissertation Abs.*, 1958, 18, 374.
12. A. KAARS SIJPESTEIJN, M. J. JANSSEN and G. J. M. VANDERKERK, *Biochim. Biophys. Acta*, 1957, 23, 550.

## Melting Behaviour of Some Pure N-Acyl Amino Acids and Peptides

VENKATARAMAN N. IYER\*, (Miss) GBETA N. SHETH<sup>†</sup> and V. V. R. SUBRAHMANYAM

Department of Chemical Technology, University of Bombay, Bombay-400 019

Manuscript received 20 November 1981, accepted 28 April 1982

Fifty three *tlc* pure N-acyl amino acids were synthesized by Schotten-Baumann reaction from *glc* pure odd and even chain fatty acids and chromatographically homogeneous amino acids and a few N-acyl peptides were prepared through the carboxylic carbonic anhydride intermediates. The melting points are reported and discussed.

**N**-ACYL amino acids and peptides are finding use as surfactants and surfactant intermediates<sup>1</sup>.

The melting points of several even chain fatty acids derivatives were reported by earlier workers<sup>2-10</sup> and the m.p.s of only N-acylsarcosines of odd and even chain fatty acids were reported by Jungermann *et al*<sup>11</sup>. Systematic data on the effect of structure of these compounds on their melting behaviour are not available, and hence this investigation. The surfactant properties of the sodium salts of these acids are being communicated separately.

### Experimental

**Preparation of *glc* pure fatty acids :** *GLC* pure even chain fatty acids from decanoic to octadecanoic were prepared from commercially available fatty acids by ester fractionation and crystallisation technique<sup>3</sup>. Hendecanoic acid was prepared from laboratory hydrogenated methyl hendecanoate. Tri, penta and heptadecanoic acids were prepared through the nitrile route<sup>3,4</sup> from even chain fatty alcohols obtained by sodium reduction of the corresponding *glc* pure fatty acid esters.

**Preparation of N-acyl amino acids :** Fatty acid chlorides were prepared using thionyl chloride according to the procedure of Bauer<sup>5</sup> and further purified by vacuum distillation. These were condensed by Schotten-Baumann reaction with chromatographically homogeneous amino acids, viz, glycine (gly), DL-alanine (ala), DL-valine (val), L-leucine (leu), L-aspartic acid (asp) and L-lysine (lys). Pure sarcosine (sar),  $\epsilon$ -amino caproic acid and  $\omega$ -amino hendecanoic acid derivatives were also prepared to study the effect of structure on melting behaviour.

In general, appropriate acid chloride was added dropwise, with constant stirring, to an aqueous solution of sodium salt of amino acid (taken in 20% molar excess except for lysines where 3 moles of acid chloride per mole of amino acid was used) while maintaining the temperature at  $45 \pm 5^\circ$ ; the

pH of the reaction mixture being maintained at  $10 \pm 0.5$  by careful addition of 10% aqueous  $\text{NaOH}$  solution. The stirring was continued at the same temperature for 1 hr more after the addition was over, and the product was acidulated with 30% sulphuric acid. The separated N-acyl amino acid was taken in an appropriate solvent, washed free of mineral acid and repeatedly crystallised from appropriate solvent till completely free from fatty acids as adjudged by *tlc*.

Toluene was found to be suitable for extraction of N-acyl glycines, -alanines and -lysines, while hexane gave good results for -valines and -leucines; 95% ethanol was found to be good solvent for crystallisation for all these. For the N-acyl sarcosines, ethyl ether was used as extraction solvent and hexane as solvent for purification by crystallisation.

N-acyl aspartates were prepared in aqueous acetone according to Takehara *et al*<sup>6</sup> instead of plain aqueous media as for others.

**Preparation of N-acyl peptides :** N-acyl glyceryl glycines were prepared from 2,5-diketopiperazine<sup>7</sup> and acid chloride according to Koebner<sup>8</sup>. The others were prepared by an evolved procedure through the carboxylic carbonic anhydrides. The details of preparation of hendecanoyl glyceryl alanine are as follows.

N-hendecanoyl glycine was taken in tetrahydrofuran, and to it was added triethylamine in 20% molar excess; the contents were cooled to  $-5^\circ$  while stirring and ethyl chloroformate (again 20% molar excess) was added drop by drop while maintaining the temperature at  $5^\circ$ . After completion of addition, the mixture was stirred for another 10 min followed by addition of 10% aqueous solution of sodium salt of DL-alanine<sup>9</sup> (20% molar excess). The contents were then allowed to reach room temperature, further stirred for 30 min and acidified to a pH of 3.0. The precipitate formed was washed till free of mineral acid, and the N-hendecanoyl glyceryl alanine

Present address : \* Ahura Chemical Products Pvt. Ltd., Bombay-400 022

<sup>†</sup> S. I. E. S. College of Arts and Science, Bombay-400 022.



TABLE 1—MELTING POINTS OF PURE N-ACYL AMINO ACIDS

No. of atoms C-atoms in parent acid and its m.p. (in brackets)	Melting points, °C. (Figures in brackets are earlier reported values)						
	Amino acid						
	Glycine	DL-alanine	Sarcosine	DL-valine	L-leucine	L-aspartic acid	L-lysine
10 (36.5)	113	97	36.5 (37.5-38.5) <sup>1a</sup>	90	109 (109-109.5) <sup>1a</sup>	103	113
11 (28.0)	114	102	48.5 (49.4-50.2) <sup>1a</sup>	80.5	108 (108-109) <sup>1a</sup>	—	113
12 (44.1)	117 (117-118) <sup>6,10</sup>	104 (95-96) <sup>17</sup> (103-105) <sup>6,10,18</sup>	45.6 (45.2-45.8) <sup>1a</sup>	92 (91-92) <sup>14</sup>	107 (106-107) <sup>14</sup>	109 (107-109) <sup>6</sup>	117
13 (41.6)	118	107	58.6 (59.8-60) <sup>1a</sup>	82.6	103	—	—
14 (54.3)	121 (121-122) <sup>8</sup>	109	52.0 (51-52) <sup>1a</sup>	97.0	101	115	119
16 (62.8)	123* (121) <sup>10</sup>	114 (116-117) <sup>8</sup> (106) <sup>10</sup>	60.0 (65.5-66.5) <sup>1a</sup>	99.0 (95-98.5) <sup>1a</sup>	91.0 (88-89) <sup>1a</sup>	118	122 (121-122) <sup>1a</sup>
17 (61.1)	124	114	71.4 (71.4-71.9) <sup>1a</sup>	83.5	87.3	—	—
18 (69.5)	127 (125-127) <sup>11</sup> (123) <sup>1a</sup>	116 (115-117) <sup>11</sup> (108-110) <sup>1a</sup>	71.5 (65.6-66.5) <sup>1a</sup> (71.8-72) <sup>1a</sup>	100	65.0	119	—

\* m.p.s of linear N-acyl amino acids having a total 18 C-atoms are as follows :

Pentadecanoyl-β-alanine, 115°; dodecanoyl-ε-amino caproic acid, 86°; heptadecanoyl-11-amino hendecanoic acid, 98°.

was crystallized from tetrahydrofuran repeatedly till a product of constant m.p. was obtained.

N-hendecanoyl alanyl glycine was similarly prepared from N-hendecanoyl alanine and sodium glycinate; so also N-acyl glycyglycyl glycyglycines were prepared from N-acyl glycines with sodium salt of glycyglycine, and condensation of N-hexadecanoyl glycyglycine with sodium salt of glycyglycine gave N-hexadecanoyl glycyglycyl glycyglycine.

**Determination of melting points :** All the products were taken in closed capillary and their melting points were determined by the usual method.

#### Discussion

The determined acid values (not reported here) and also the determined nitrogen content of the peptides agree closely with theoretical values confirming the purity of products as tested by tlc. The m.p.s of thirty N-acyl amino acids are being reported for the first time; the m.p.s of others are closer to the values reported earlier with a few exceptions (Table 1). The m.p.s reported by Spivack and Kroll<sup>1a</sup> for stearic acid derivatives of glycine (123°), alanine (110°) and sarcosine (66.5°) are consistently lower than the present values (127, 116 and 71.5°, respectively). The present values, however, are nearer to the values reported by Fieser *et al.*<sup>11</sup> (stearoyl glycine 127° and stearoyl alanine

117°) and Jungermann *et al.*<sup>1a</sup> (stearoyl sarcosine, 72°). Koebner<sup>8</sup> reported a m.p. of 172° for hexadecanoyl glycyglycine which is lower than the value (179°) obtained in the present study by 7°; the m.p.s of the other acyl peptides are being reported for the first time (Table 2).

TABLE 2—MELTING POINTS OF N-ACYL PEPTIDES

Peptide	Melting point, °C	
	Acid	
	Hendecanoic	Hexadecanoic
gly. glycine	182	179*
gly. alanine	168	—
ala. glycine	141	—
gly. gly. glycine	211	208
gly. gly. gly. glycine	—	229

\* Reported m. p. is 172°; soon after melting all the compounds get darkened due to decomposition.

The effect of increasing the acyl chain length on m.p. of homologues varied from series to series. The N-acylated sarcosine series resembles the fatty acid series in alternation of m.p.s of odd and even

chain compounds, but the alternations are opposite. Alternation is apparent (Fig. 1) in valine series also, but here it is like that for fatty acids, i.e. the m.p. of even acyl chain compounds is higher than that of the odd acyl chain compounds having one carbon atom more. If the odd and even acyl chain compounds of valine and sarcosine are treated as separate series, the m.p.s increase as the series are ascended as in the case of fatty acids. Alternation is absent in the series of glycines, alanines, lysines and leucines; in the case of the first three series, m.p.s increase as the series are ascended, but they decrease in the case of N-acyl leucines, indicating that shorter acyl chain derivatives are packed more closely in solid state. This differential melting behaviour of homologues belonging to different series is, no doubt, due to the differences in structure of the amino acid present.




Fig. 1. Relations of No. of C-atoms in the N-acyl amino acids and their melting points. (gly, glycines; asp, aspartates; ala, alanines; val, valines; sar, sarcosines and leu, leucines)

Compared to parent fatty acids, N-acyl amino acids have higher m.p., the exceptions being decanoyl and tetradecanoyl sarcosines and N-octadecanoyl leucine (Table 1). The difference in m.p. of lower and higher homologues for the N-acyl amino acids is not much as compared to that of fatty acids except for sarcosine and leucine series which perhaps can again be attributed to structural differences of amino acids.

DL-alanines ( $\alpha$ -methyl glycines) do not show alternation in melting behaviour while the sarcosines (N-methyl glycines) do for any given acyl chain; the compounds in former series have higher m.p. than those of the latter even though their molecular weights are same.

The magnitude of substituent group at the  $\alpha$ -position of the glycines also plays an important role in the melting behaviour. For any given acyl chain, alanines ( $\alpha$ -methyl glycines) have higher m.p. than valines ( $\alpha$ -isopropyl glycines) which in turn melt

at a higher temperature than leucines ( $\alpha$ -isobutyl glycines). Further, as has already been mentioned, as the molecular weight is progressively increased, m.p. increases in alanine series, alternates in valine series and decreases in leucine series. Aspartates (decarboxylates) have m.p.s between those of the corresponding glycines and alanines. All these indicate that the substituent group plays an important role on the intramolecular interaction forces exerted by acyl chains, intermediate amido groups and terminal carboxyl groups of the compounds altering the packing of molecules in solid state. Two long acyl chains as in lysines (diacylated lysines) make the compounds behave like the corresponding glycines. Even though the molecular weights of compounds of the former series are nearly twice of the corresponding ones in the latter, their m.p.s are very close and in two cases they coincide (Table 1). That the position of the intermediate amido group also has a significant effect on the molecular packing in solid state is clear from a comparison of the melting points of four linear N-acyl amino acids having a molecular weight of 313 (having a total of 18 carbon atoms). N-hexadecanoyl glycine (m.p. 123°) has higher m.p. than N-pentadecanoyl alanine (m.p. 115°) which in turn melts higher than N-heptanoyl amino hendecanoic acid (m.p. 98°). These three compounds have 1, 2 and 10 methylene groups between the terminal carboxyl group and nitrogen atom. This indicates that m.p. decreases as the amido group moves away from the carboxyl group in the molecule but again increases when it is nearer to the other end of the molecule (N-dodecanoyl-amino caproic acid melts at 86°).

Incorporating glycine groups increases the m.p. The m.p. of N-hexadecanoyl glycine (123°) is almost twice that of palmitic acid (62.8°). Presence of additional amido groups in the former increases the m.p. further but not linearly (m.p.s of N-hexadecanoyl glycyl glycine, -glycyl glycyl glycine, -glycyl glycyl glycyl glycine are 179, 208 and 229°, respectively). Here also, like the leucines and unlike other acyl amino acid series, the hendecanoyl derivatives have higher m.p. than those of their corresponding higher homologues (hexadecanoyl derivatives) indicating the combined effect of acyl chain length and the polar part of the molecule on the melting behaviour.

In the peptides also, presence of substituted group (methyl) decreases the m.p. (Table 2); N-hendecanoyl glycyl glycine melts at a temperature (m.p. 182°) higher than that for hendecanoyl glycyl alanine (m.p. 168°) and hendecanoyl alanyl glycine (m.p. 141°). It is interesting to note that the sequence of amino acids in peptides has a profound effect on the molecular packing.

The length of the acyl chain as well as the structure of amino acid present in the compounds play an important role in the melting behaviour and in addition to these, the number and sequence of amino acids present have a profound effect on the molecular packing of N-acyl peptides.

References

1. J. D. SPIVACK, "Anionic Surfactant", Part II. (Ed.) W. H. LINFIELD, Marcel Dekker, Inc., 1976, p. 581.
2. Y. D. ARORA and V. V. R. SUBRAHMANYAM, *J. Oil Technol. Assocn. of India*, 1974, 6, 7.
3. "Organic Synthesis", Coll. Vol. II, (Ed.) A. H. BLATT, John Wiley and Sons, New York, 1961, p. 322.
4. R. A. LEVENE and F. A. TAYLOR, *J. Biol. Chem.*, 1924, 59, 905.
5. S. T. BAUER, *Oil and Soap*, 1946, 23, 1.
6. M. TAKEHARA, I. YOSHIMURA, K. TAKIZAWA and R. YOSHIDA, *J. Amer. Oil. Chem. Soc.*, 1972, 49, 157.
7. H. F. SCHOTT, J. B. LARKIN, L. B. ROCKLAND and M. S. DUNN, *J. Org. Chem.*, 1947, 12, 490.
8. A. KOEBNER, *J. Chem. Soc.*, 1941, 564.
9. G. IVALDI and L. ARRIGO, *Giorn. Biochem.*, 1961, 10, 549; *Chem. Abs.*, 1963, 58, 4643e.
10. S. BONDI, *Biochem. Z.*, 17, 543; *Chem. Abs.*, 1909, 3, 2014.
11. M. FIESER, L. F. FIESER, E. TOROMANOFF, Y. HIRAHITA, H. HEYMANN, M. TEFFT and S. BHATTACHARYA, *J. Amer. Chem. Soc.*, 1956, 78, 2825.
12. J. D. SPIVACK and H. KROLL (to Geigy Chem. Corp.), U. S. Pat., 2, 790, 778 (Apr. 1957); *Chem. Abs.*, 1957, 51, 11704h.
13. E. JUNGERMANN, J. F. GERECHT and I. J. KREMS, *J. Amer. Chem. Soc.*, 1956, 78, 172.
14. T. UEDA, S. KATO and S. TOYOSHIMA (to Dai-Nippon Pharmaceutical Co.), Jap. Pat., 8410 (Sep. 1957); *Chem. Abs.*, 1958, 52, 14669f.
15. R. YOSHIDA, I. YOSHIMURA, I. MAEDA, M. TAKEHARA and K. TAKIZAWA, Jap. Pat., 73, 35, 058 (Oct. 1973); *Chem. Abs.*, 1974, 80, 60208k.
16. T. TSUBONE, *Seikagaku*, 1963, 35, 67; *Chem. Abs.*, 1964, 61, 13407b.
17. M. NAUDET, *Bull. Soc. Chem. France*, 1950, 358; *Chem. Abs.*, 1950, 44, 8137c.
18. S. KANAO and T. TOYODA (to Nimoto Co.), Jap. Pat., 6713 (Oct. 1954); *Chem. Abs.*, 1969, 70, 38057g.

# Properties of Pure Sodium Soaps of Saturated Fatty Acids

(Miss) GEETA N. SHETH\* and V. V. R. SUBRAHMANYAM

Department of Chemical Technology, University of Bombay, Bombay-400 019

Manuscript received 20 November 1981, accepted 28 April 1982

Pure sodium salts of odd and even chain fatty acids ( $C_7$  to  $C_{19}$ ) were prepared and their properties and performance characteristics were evaluated.

The odd and even chain fatty acid soaps, in water, appear to behave as two separate surfactant series with respect to their solubility and critical micelle concentration; the higher soaps behave somewhat anomalously perhaps due to coiling of longer hydrophobic chains in aqueous solutions, while the lower soaps having very high CMC are ineffective as surfactants at the usual concentrations.

MANY reports have appeared on the properties of sodium soaps of fatty acids having even number of C-atoms originating from natural fatty oils<sup>1</sup>. Reports on some properties of odd chain fatty acid soaps have started appearing only recently<sup>2,3</sup>. Due to differences in test conditions of different workers, it is not possible to compare the properties of odd and even chain fatty acid salts at any given temperature. A detailed comparative study of the properties of sodium salts of fatty acids, from heptanoic to nonadecanoic, was, therefore, taken up.

## Experimental

**Preparation of sodium salts of pure fatty acids:** Four odd chain saturated fatty acids, viz. tri-, penta-, hepta- and nonadecanoic acids, were synthesized by the nitrile route<sup>4</sup>. GLC-pure methyl esters of even chain fatty acids were reduced to fatty alcohols by the sodium reduction method, which were then converted to iodides from which nitriles were prepared. The nitriles were hydrolysed by alcoholic NaOH and the soaps obtained were freed from unreacted impurities by repeated crystallizations from alcohol. All the other pure acids were prepared from the commercial fatty acids by the usual ester fractionation technique and, wherever necessary, by hydrogenation and/or solvent crystallization. The melting points of the glc and tlc pure fatty acids (purity of over 99.9%) agree closely with earlier reported values<sup>5,7</sup>. The relationship of m.p. with the number of C-atoms in the acids is shown in Fig. 1a. The pure fatty acids taken in alcohol were neutralised with alcoholic sodium hydroxide and the soaps were purified by recrystallization from alcohol, dried and stored in a desiccator.

**Evaluation of the properties and performance characteristics of soaps in water:** The pure soaps were evaluated by the methods described earlier<sup>8-10</sup>.

The temperature at which 1% aqueous soap solution becomes clear (K. P.) and the temperature at which clouding occurs while gradually cooling the clear solutions (C. P.) are given in Table 1 and represented in Fig. 1 (b and c). pH of 0.25% aqueous solutions, interfacial tension (I. T.) of 0.1% solutions against




Fig 1. Relationship of No. of C-atoms with (a) m.p. of fatty acids, (b) K.P. of fatty acid soaps and (c) C. P. of fatty acid soaps.

toluene and the minimum surface tension values (S. T.) attained by the soap solutions are given in Table 1. Critical micelle concentrations (CMC) of the soaps obtained by graphical methods from the S. T. and conductivity data of solutions varying in concentration are also given in Table 1. The relationship of log molar CMC (by conductivity method) and the number of C-atoms in soap is

\*Present address: Lecturer in Chemistry, S. I. E. S. College of Arts and Science, Bombay-400 022.

shown in Fig. 2. All the properties and performance characteristics of the soaps were evaluated, at 60°, in distilled water except the S. T. determinations which were in presence of added sodium meta silicate (5% based on soap).




Fig. 2. Relationship of log molar CMC of sodium salts and No. of C-atoms present.

of one C-atom to an even chain fatty acid soap (upto palmitate) means effective increase in the chain length by about 1.5 C-atoms from the solubility considerations, while for the odd chain soaps it means reducing effective chain length by less than one C-atom (about 0.5).

The pH of 0.25% solutions of different soaps progressively increases with increasing chain length (7.2 to 10.3 for decanoate to nonadecanoate) indicating the tendency of higher soaps for greater hydrolysis in distilled water. The same trend is observed (results not given) at different concentrations studied and also at 30°. The calculated maximum percentage hydrolysis for  $C_7$  and  $C_{19}$  soaps, at 60°, are  $1152 \times 10^{-4}$  and  $27.4 \times 10^{-4}$ , respectively, and the other soaps have values in-between, but the concentrations at which maximum percentage hydrolysis occurs differ for different soaps.

Sodium myristate is the best amongst the soaps in respect of I. T. lowering power. The ability, however, decreases when the series is either ascended or descended indicating the need for a proper HLB.

The need for optimum HLB is also apparent in the various performance characteristics of the soaps studied at 60° (but not reported in the table). In the wetting tests (canvas disc method<sup>10</sup> using 0.1% soap solutions) sodium laurate was found to be the best (wetting time of 31 sec) followed by hendecanoate (38 sec) and tridecanoate (60 sec),

TABLE 1—PROPERTIES OF AQUEOUS SOAP SOLUTIONS AT 60°

No. of Carbon atoms in soap	K. P. °C	C. P. °C	pH of 0.25% solution	I. T. of 0.1% soln. (dynes/cm)	Min. S. T. (dynes/cm)	CMC, m moles/l	
						S. T. method	Conductivity method
7	*	*	—	32	40	461	467
8	*	*	—	33	39	301	301
9	*	*	—	32	36	139	136
10	*	*	7.2	31	34	103	106
11	24.3	10.7	7.6	29	34	40	38
12	28.1	16.0	7.6	28	31	30	31
13	41.2	31.4	8.6	26	28	13	12
14	43.9	35.3	9.1	20	27	8	9
15	57.4	50.0	9.4	27	24	3.6	3.8
16	61.3	54.3	9.8	30	22	2.7	2.9
17	73.2	66.8	10.0	31	26	1.7	1.7
18	75.5	68.0	10.2	33	27	0.8	0.9
19	83.6	77.2	10.3	34	36	0.9	0.9

\* Clear at 0°

### Results and Discussion

The solubility of the soaps progressively decreases with the increase in their molecular weight as shown by the progressive changes of K. P. and C. P. (Table 1). However, when K. P. (Fig. 1b) and C. P. (Fig. 1c) are plotted against the number of C-atoms present in the soap, the points for odd and even chain acid soaps fall on two separate lines, as for the m.p. of fatty acids (Fig. 1a). The K. P. and C. P. lines of odd chain fatty acid salts are above those of the even chain, whereas the m.p. line of the odd chain fatty acids is below that of the even chain acids. The figure indicates that the addition

while the rest of the soaps are poor wetting agents under the test conditions. The 0.25% solutions of salts from heptanoate to decanoate do not foam in the Ross-Miles pour foam test<sup>11</sup> at 60° and hendecanoate gives poor unstable foam (only 55 mm). The other soaps, laurate to palmitate in distilled water, foam better than sodium lauryl alcohol sulphate (NaLAS) but again foaming ability decreases as the molecular weight increases. However, as adjudged by the foam height after 5 min, the stability of foam formed increases as the molecular weight increases. The deterative power (in the soiled cotton fabric-washing tests using Tergo-o-Meter<sup>9</sup>)

of higher soaps (tetradecanoate and above) is better than NaLAS, while the lower ones are poorer. The detergency of 0.25% soap solutions from heptanoate to hendecanoate are only 10-12% of that of sodium stearate. In general, the medium chain fatty acid soaps showed poor performance characteristics and are ineffective as surfactants at the tested concentrations (normally employed).

In all cases, the S. T. decreases with increase in the concentration till around the CMC of the soap, and the minimum values obtained are given in Table 1. The S. T. lowering power (effectiveness) is maximum for palmitate and pentadecanoate, amongst the soaps of even and odd series, respectively. The effectiveness decreases if the chain length is either increased or decreased, showing the need for optimum HLB for effective S. T. reduction.

CMC values of the soaps in distilled water obtained by the conductivity method are close to those obtained by the S. T. method (Table 1). They are also nearer to the values obtained by the pinacyanol chloride dye method (not reported).

The short chain fatty acid soaps (caprate and below) will be effective only at a very high concentration (as CMC of caprate is 2% by weight) which is not encountered in actual usage. The CMC, in general, decreases with increase in the chain length till stearate and there is no perceptible effect by further increase in the chain length by one more  $-\text{CH}_2$  group. When log molar CMC is plotted against the number of C-atoms in the soap molecules, a very interesting picture emerges (Fig. 2). Two separate straight lines are obtained for odd and even chain acid soaps upto palmitate, indicating that the odd and even chain soaps behave as two separate surfactant series. It is apparent from Fig. 2 that increasing the acyl chain of odd chain fatty acid

soap by one  $\text{CH}_2$  group (next higher even chain fatty acid soap) appears to increase the effective chain length (ECL) by only 0.6  $\text{CH}_2$  group till palmitate. Conversely, increase in one  $\text{CH}_2$  group in even chain fatty acid soap means increase in ECL by 1.4  $\text{CH}_2$  group. The anomalous solubility behaviour and CMC data may be due to the difference in intermolecular attraction forces between the acyl chains having odd and even number of C-atoms and/or due to the difference in arrangement of soap molecules in micelles. The CMC of the heptadecanoate falls on the line of even chain fatty acid soaps while nonadecanoate has CMC which is the same as that of the stearate. This behaviour of the higher soaps in water may be due to the coiling tendency of their long hydrophobic acyl chains as postulated by Mukerjee<sup>12</sup>.

#### References

1. J. G. KANE, "Soaps: Their Chemistry and Technology", Indian Central Oil Seeds Committee, Hyderabad, 1959.
2. O. KEIZO and I. YUKINORI, *Bull. Chem. Soc., Japan*, 1976, 49, 2683.
3. K. OGINO and F. TAKIGAMI, *J. Amer. Oil. Chem. Soc.*, 1979, 56, 880.
4. P. A. LEVENE and F. A. TAYLOR, *J. Biol. Chem.*, 1924, 59, 905.
5. F. FRANCIS and S. H. PIPER, *J. Amer. Chem. Soc.*, 1939, 61, 377.
6. H. A. SCHUETTE and H. A. VOGEL, *Oil and Soap*, 1939, 16, 209.
7. K. S. MARKLEY, "Fatty Acids", Interscience Pub., New York, 1967, p. 2588.
8. Y. D. ARORA and V. V. R. SUBRAHMANYAM, *J. Oil Technol. Assocn. of India*, 1974, 6, 7.
9. P. P. NAGARKAR and V. V. R. SUBRAHMANYAM, *J. Oil Technol. Assocn. of India*, 1975, 7, 33.
10. T. N. NANDAKUMAR and V. V. R. SUBRAHMANYAM, *J. Oil Technol. Assocn. of India*, 1979, 11, 31.
11. J. ROSS and G. D. MILES, *Oil and Soap*, 1941, 18, 99.
12. P. MUKERJEE, *Advan. Colloid Interface Sci.*, 1967, 1, 241.

# Synthesis and Studies of Some New Phthal-as-Eins


R. P. CHAMOLI\*, S. J. RAI† and P. C. GUPTA

Department of Chemistry, Allahabad University, Allahabad-211 002

Manuscript received 27 October 1979, accepted 14 September 1981

Condensation of two  $\gamma$ -keto acids, *o*-(*p*-methylbenzoyl)benzoic acid and *o*-(*p*-methylbenzoyl)tetrachlorobenzoic acid with phenols gives new series of phthal-as-eins. These dyes are substituted phthalides in which central carbon atom is attached to two different rings and hence they have been named as phthal-as-eins, 'as' representing unsymmetry and 'ein' the class of compound (phthal-ein). Absorption maxima of these new compounds have been found comparable to those of true phthal-eins.

**R**ING-chain tautomerism is encountered in various groups of compounds, e.g., carbohydrates, alkaloids, steroids and  $\gamma$ -keto acids. It has been generally observed that  $\gamma$ -keto acids exist mainly as lactol or as an equilibrium mixture of ring (II) and chain (I) tautomers<sup>1</sup>. The lactol form (II) gives well crystalline acetyl derivative<sup>2,4</sup> (III) which still retains cyclic structure. Many reactions of  $\gamma$ -keto acids such as formation of pseudo chlorides (IV)<sup>5</sup>, pseudo esters (V)<sup>6</sup> etc, have been explained on the basis of cyclization of acids to lactol IR<sup>7,8</sup>, Raman<sup>9</sup> and nmr<sup>10</sup> spectra have further confirmed the formation of cyclic isomers.



It has also been reported that ring tautomerism of  $\gamma$ -keto acids<sup>1,11</sup> is further exalted by changing R to larger alkyl or aryl groups. It increases further when hydrogen atoms on carbon atoms  $\alpha$  to carboxyl group are also changed to larger alkyl groups or  $\alpha,\beta$ -ethylenic bond<sup>12</sup>. In recent years Gupta *et al* reported the preparation of a large number of mixed phthal-eins and succineins<sup>13,20</sup>, by condensing various  $\gamma$ -keto acids with phenols. These workers proposed that  $\gamma$ -keto acids undergo condensation through their lactol form and hence the products possess cyclic lactonic structures. In continuation of this work, the present paper describes the synthesis of some new phthal-as-eins by condensing *o*-(*p*-methylbenzoyl)benzoic acid and *o*-(*p*-methylbenzoyl)tetrachlorobenzoic acid with various phenols.

## Experimental

All melting points are uncorrected. The absorption maxima (visible) have been measured using Beckman model DU spectrophotometer in absolute ethanol (neutral and alkaline media). IR spectra

were taken in KBr with a Perkin Elmer infracord. NMR spectra were recorded on Varian A-60 spectrophotometer using TMS as internal reference. For tlc, plates coated with alumina G-silica gel G (1 : 1) layers were run in ethyl acetate-methanol-5 N ammonia solution (60 : 30 : 10) and spots were developed with 5% aqueous NaOH.

*o*-(*p*-Methylbenzoyl)benzoic acid and *o*-(*p*-methylbenzoyl)tetrachlorobenzoic acid were prepared by reported procedure<sup>21</sup>. For preparation of acetyl derivative each acid was refluxed with acetic anhydride in presence of fused sodium acetate. The phenols (phenol, resorcinol, catechol, quinol, phloroglucinol and pyrogallol) were taken in slight excess of molecular proportion over the acid (VI). Conc. sulphuric acid (4-5 drops) was used as condensing agent throughout. Each dye, when tested was found free from sulphur. Analogous to phthal-eins<sup>22</sup>, the condensation is supposed to have taken place as shown in Chart 1.




Chart 1

- (VI-X)  $R'_1 = R'_2 = R'_3 = R'_4 = H$  or Cl  
(XI)  $R_1 = R_2 = R_3 = R_4 = H$ ,  $R_5 = OH$   
(XII)  $R_1 = R_2 = R_3 = H$ ,  $R_4 = R_5 = OH$   
(XIII)  $R_1 = R_2 = R_3 = H$ ,  $R_4 = R_5 = OH$   
(XIV)  $R_1 = R_2 = R_3 = H$ ,  $R_4 = R_5 = OH$   
(XV)  $R_1 = R_2 = H$ ,  $R_3 = R_4 = R_5 = OH$   
(XVI)  $R_1 = R_2 = H$ ,  $R_3 = R_4 = R_5 = OH$   
(XVII)  $R_1 = R_2 = R_3 = H$ ,  $R_4 = R_5 = OCOCH_3$   
(XVIII)  $R_1 = H$ ,  $R_2 = R_4 = Br$ ,  $R_3 = R_5 = OH$

Synthesis of *p*-methylphenyl resorcinol tetrachlorophthal-as-ein (XII ;  $R'_1 = R'_2 = R'_3 = R'_4 = Cl$ ) : An intimate mixture of acid (VI ;  $R'_1 = R'_2 = R'_3 = R'_4 = Cl$ )

\* Present address : Chemistry Department, Government Postgraduate College, Gopeshwar (Chamoli), U. P.

† Chemistry Department, Govt. P. G. College, Gyanpur (Varanasi), U.P.

TABLE 1—PREPARATION AND PROPERTIES OF PHTHAL-AS-EINS (X; R<sub>1</sub>' = R<sub>2</sub>' = R<sub>3</sub>' = R<sub>4</sub>' = H) AND TETRACHLOROPHTHAL-AS-EINS (X; R<sub>1</sub>' = R<sub>2</sub>' = R<sub>3</sub>' = R<sub>4</sub>' = Cl), RESPECTIVELY

Name of dye, (P = phthal-as-ein)	Condensation		Appearance microcrystalline. Colour	m. p. °C	Yield %	Analysis % Found (Calcd.)		
	Temp °C	Duration hr				C	H	Cl
XI (*) methylphenyl phenol P	150-160	8	yellowish white	165-166	84	79.96 (79.74)	5.28 (5.06)	
XII <i>p</i> -methylphenyl resorcinol P	130-140	3	yellowish brown	200-201	67	75.62 (75.90)	4.75 (4.93)	
XIII <i>p</i> -methylphenyl catechol P	125-130	2½	grey	172-173	61	75.71 (75.90)	5.20 (4.93)	
XIV <i>p</i> -methylphenyl quinol P	150-160	2½	brownish black	184-185	47	76.30 (75.90)	5.15 (4.93)	
XV <i>p</i> -methylphenyl phloroglucinol P	150-160	1½	brick red	212-213	60	72.69 (72.41)	4.81 (4.59)	
XVI <i>p</i> -methylphenyl pyrogallol P	130-140	1	dirty yellow	220-221	51	72.68 (72.41)	4.80 (4.59)	
XVII <i>p</i> -methylphenyl diacetylresorcinol P	130-140	3	colourless	115-116	52	77.26 (76.92)	5.01 (4.80)	
XVIII <i>p</i> -methylphenyl dibromoresorcinol P	130-140	1	brownish red	208-209	54	Br, 32.90 (32.65)		
XI (*) <i>p</i> -methylphenyl phenol tetrachloro P	180-190	6	light brown	229-230	47	55.75 (55.50)	2.31 (2.64)	31.01 (31.27)
XIII <i>p</i> -methylphenyl catechol tetrachloro P	210-220	1	grey	180-181	33	53.42 (53.61)	2.79 (2.55)	30.60 (30.21)
XIV <i>p</i> -methylphenyl quinol tetrachloro P	200-210	1	brown	160-161	33	53.40 (53.61)	2.81 (2.55)	30.52 (30.21)
XV <i>p</i> -methylphenyl phloroglucinol tetrachloro P	210-220	2	red brown	245-246	50	52.00 (51.85)	2.23 (2.46)	29.05 (29.21)
XVI <i>p</i> -methylphenyl pyrogallol tetrachloro P	210-220	½	blackish brown	240-241	51	51.64 (51.85)	2.30 (2.46)	29.56 (29.21)
XVII <i>p</i> -methylphenyl diacetylresorcinol tetrachloro P	130-140	4	yellowish white	140-141	68	54.45 (54.15)	2.59 (2.88)	25.42 (25.63)
XVIII <i>p</i> -methylphenyl dibromoresorcinol tetrachloro P	room temp	over night	brick red	260-261	69	Br, 25.86 (25.47)		

(\*) Excess phenol after condensation was removed by steam distillation.

(7.5 g) and resorcinol (2.0 g) was taken in a hard glass boiling tube and heated in an oil bath to 180°. Conc. sulphuric acid (5 drops) was added to the homogeneous contents and heating was continued between 180-190° for 1 hr to get a hard and brittle mass on cooling. The condensed mass was crushed, washed thoroughly with water to remove excess of resorcinol and extracted with 2% aqueous NaOH. The dye was precipitated from the red pink (green fluorescent) filtrate by adding hydrochloric acid gradually with stirring. The dye was filtered, washed with water and purified by repeated crystallization from rectified spirit, dried in an oven at 110° and finally over P<sub>2</sub>O<sub>5</sub> in a vacuum desiccator (yield 6.2 g; 60%).

The dye is yellow microcrystalline solid, m.p. 250-251°. The ethanolic solution is yellow with light green fluorescence which on addition of alkali changes to red-pink with intense green fluorescence. Found: C, 53.80; H, 2.67; Cl, 30.53; Mol. wt. 458 (Rast). Calcd. for C<sub>21</sub>H<sub>13</sub>O<sub>4</sub>Cl<sub>4</sub>; C, 53.61; H, 2.55; Cl, 30.21%; Mol. wt. 470.

**Paper chromatography of dyes (XI):** On Whatman No. 1 test paper, *n*-butanol-ammonia was allowed to run for 13 hr (descending) to give two pink spots of the dye (XI) and reference dye phenolphthalein. R<sub>f</sub>: dye XI (R<sub>1</sub>' = R<sub>2</sub>' = R<sub>3</sub>' = R<sub>4</sub>' = Cl), 0.89; phenolphthalein, 0.91 (lit.<sup>22</sup> R<sub>f</sub> 0.92).

**Acetylation of dyes (XII):** The dye (XII; R<sub>1</sub>' = R<sub>2</sub>' = R<sub>3</sub>' = R<sub>4</sub>' = Cl) (1.0 g) was refluxed with acetic anhydride (15.0 ml) and fused sodium acetate (3.0 g) at 130-140° for 4 hr to give yellowish white acetyl derivative (0.80 g), m.p. 140-141° (from acetic acid). Found: C, 54.45; H, 2.59; Cl, 25.42; Acetyl, 15.41. Calcd. for C<sub>23</sub>H<sub>15</sub>O<sub>4</sub>Cl<sub>4</sub> or C<sub>21</sub>H<sub>13</sub>O<sub>4</sub>Cl<sub>4</sub>·(COCH<sub>3</sub>)<sub>2</sub>; C, 54.15; H, 2.88; Cl, 25.63; Acetyl, 15.16%.

**Bromination of dyes (XII):** The dye (XII, R<sub>1</sub>' = R<sub>2</sub>' = R<sub>3</sub>' = R<sub>4</sub>' = Cl) (1.0 g) was dissolved in absolute ethanol and bromine (2 ml) was added to it drop by drop with shaking. The contents were left overnight at room temperature. The dibromo compound separated as brick red solid (0.9 g), m.p. 260° (from 80% ethanol). It dissolves in ethanol with pinkish red colour which is intensified on addition of alkali. Found: Br, 25.86. Calcd. for C<sub>21</sub>H<sub>10</sub>O<sub>4</sub>Cl<sub>4</sub>Br<sub>2</sub>; Br, 25.47%.

**Caustic potash treatment of dyes (XII):** The dye (XII: R<sub>1</sub>' = R<sub>2</sub>' = R<sub>3</sub>' = R<sub>4</sub>' = Cl) (1.0 g) was mixed with a paste of caustic potash pellets (10.0 g) in a platinum crucible and heated at about 250° for 3 hr until the pink colour of the dye completely disappeared. The contents were cooled and dissolved in water (50 ml) and filtered. The excess of alkali was just neutralized by dil. HCl when a yellowish brown residue (A) settled down. The residue was filtered



TABLE 2—ABSORPTION MAXIMA OF PHTHAL-AS-ETNS ( $X; R'_1 = R'_2 = R'_3 = R'_4 = H$ ) AND TETRACHLOROPHTHAL-AS-ETNS ( $X; R'_1 = R'_2 = R'_3 = R'_4 = Cl$ ), RESPECTIVELY. G. F. = GREEN FLUORESCENCE

Dye	Colour in ethanol		Colour with 2% NaOH	$\lambda_{max}$ (nm)		
	Neutral	Alkaline		Neutral	at pH	
XI	light yellow	light red	light red	500	530	9.0
XII	yellowish red (G. F.)	red	red	480	500	9.5
XIII	colourless	red	red	—	510	8.5
XIV	yellowish brown	brown	reddish brown	—	—	—
XV	yellow orange	red	red	420	460	9.0
XVI	yellow	brownish red	brownish red	—	—	—
XVII	light yellow	light yellow	light yellow	—	—	—
XVIII	light red	red	red	520	530	10.00
XI	light yellow	pink	pink	500	530	9.5
XII	yellow (light G. F.)	red pink (G. F.)	red pink (G. F.)	490	510	10.00
XIII	yellow	yellow brown	dark yellow brown	—	—	—
XIV	light yellow	light pink	light pink	—	520	9.00
XV	orange	brownish red	brownish red	450	—	—
XVI	yellow brown	green	dark green	—	—	—
XVII	light yellow	light yellow	colourless	—	—	—
XVIII	pinkish red	pinkish red	deep pink	520	530	10.00

TABLE 3—ABSORPTION MAXIMA OF SOME KNOWN PHTHALIETNS

Name of dye	Colour in ethanol		Colour with 2% NaOH	$\lambda_{max}$ (nm)		
	Neutral	Alkaline		Neutral	at pH	
Phenolphthalein	colourless	pink	pink	—	550	10.5
Fluorescein	yellow red	red (G. F.)	reddish pink (G. F.)	480	500	10.00
Eosin	light pink (G. F.)	orange pink (G. F.)	orange pink (G. F.)	530	530	9.5

and washed with water. The filtrate was further acidified by adding an excess of dil. HCl giving a white residue (B) which was also filtered and washed with water. The filtrate was extracted with ether and on evaporation of excess of solvent a brownish red residue (C) was obtained. Residues A, B and C, were identified as unreacted residual dye (XII), acid (VI) and resorcinol (XIX), respectively by direct comparison (m.m.p, co-tlc, co-ir) with their authentic samples.

### Results and Discussion

*o*-(*p*-Methylbenzoyl)benzoic acid ( $VI; R'_1 = R'_2 = R'_3 = R'_4 = H$ ) and *o*-(*p*-methylbenzoyl)tetrachlorobenzoic acid ( $VI; R'_1 = R'_2 = R'_3 = R'_4 = Cl$ ) have been found spectroscopically to exist as a mixture of ring and chain tautomers. IR spectra of the acids showed notable absorption bands at 1695-1690, 1670-1660, and 1760 (very feeble)  $cm^{-1}$  indicating the presence of carboxyl  $>C=O$ , diaryl ketonic  $>C=O$  and lactonic  $>C=O$ , respectively. Broad bands at 2700-2640 and 3460-3440  $cm^{-1}$  have been assigned to  $-OH$  of carboxyl and  $-OH$  of lactol form of the acids, respectively. The nmr spectra (DMSO- $d_6$ ) of these two acids showed the presence of a hydroxy proton of the lactol form (a broad singlet of low intensity at  $\tau$  4.7 and 4.5).

IR spectra of the acetyl derivatives of the acids showed a peak at 1780  $cm^{-1}$  due to lactonic  $>C=O$ . Other peaks at about 1755, 1235, 1200 and 1000  $cm^{-1}$  have been ascribed to  $OCOCH_3$  group. Peaks present in the ir spectra of acids at 3460-3440, 2700-2640, 1695-1690, 1670-1660  $cm^{-1}$  were found absent in the ir spectra of the corresponding acetyl derivatives. NMR spectra of acetyl derivatives did not

contain any signal at  $\tau$  4.7 and 4.5 (present in the nmr spectra of the acids), but there was a new signal at  $\tau$  7.5 (singlet, 3H) due to  $OCOCH_3$  group.

These spectral studies revealed that the acids are mixture of keto (VI) and lactol (VII) form and formation of acetyl derivatives takes place through the lactol form. Similarly, condensation of acids with phenols also occurs through the lactol form, and with excess of phenols the entire acid taken reacts as




Chart 2  
( $R'_1 = R'_2 = R'_3 = R'_4 = H - Cl$ )

lactol (VII) (Chart 1). The purity of the dyes has been confirmed by tlc and paper chromatography. The structures have been confirmed on the basis of elemental analysis, bromination, acetylation and KOH degradation studies (Chart 2). Formation of diacetyl derivatives (XVII) and dibromo derivatives (XVIII) support the presence of only one resorcinol molecule in the dyes (XII). KOH fusion of dyes (XI) yielded acids (VI) and resorcinol (XIX).

The absorption maxima of these phthal-as-eins are given in Table 2 and are comparable to those of known phthaleins prepared in similar manner (Table 3).

#### References

1. K. VON AUWERS and A. HEINKE, *Ber.*, 1919, 52, 584.
2. I. HEILBRON and H. M. BUNBURY, "Dictionary of Organic Compounds", Oxford University Press, New York, 1953, Vol. 3, p. 178.
3. S. GABRIEL, *Ber.*, 1881, 14, 919.
4. P. R. JONES and S. L. CONGDON, *J. Amer. Chem. Soc.*, 1959, 81, 4291.
5. R. C. MARTIN, *J. Amer. Chem. Soc.*, 1916, 38, 1142.
6. M. S. NEWMAN and C. D. MCCLEARY, *J. Amer. Chem. Soc.*, 1941, 63, 1537.
7. M. S. NEWMAN and C. W. MUTH, *J. Amer. Chem. Soc.*, 1951, 73, 4627.
8. P. M. MAGINNITY and T. G. GARR, *J. Amer. Chem. Soc.*, 1952, 74, 4958.
9. Y. K. SYRKIN, *Russ. Phys. Chem.*, 1943, 17, 347; *Chem. Abs.*, 1944, 38, 5701.
10. R. KUHN and H. SCHRETZMANN, *Chem. Ber.*, 1957, 90, 557.
11. S. DATT and J. F. THORPE, *J. Chem. Soc.*, 1924, 2524.
12. E. OTT, *Ann.*, 1912, 392, 245.
13. E. SINGH and P. C. GUPTA, *Ann. Chim.*, 1971, 6, 427.
14. E. SINGH and P. C. GUPTA, *Ann. Chim.*, 1972, 7, 359.
15. E. SINGH and P. C. GUPTA, *Z. Naturforsch.*, 1972, 27b, 405.
16. R. GOPAL, P. C. GUPTA and S. P. GARG, *J. Indian Chem. Soc.*, 1973, 50, 410.
17. R. GOPAL, P. C. GUPTA and S. P. GARG, *Z. Naturforsch.*, 1973, 28b, 468.
18. R. GOPAL, P. C. GUPTA and S. P. GARG, *Bull. Chem. Soc., Japan*, 1974, 47, 1789.
19. R. GOPAL, P. C. GUPTA and S. P. GARG, *Bull. Chem. Soc., Japan*, 1975, 48, 2227.
20. R. GOPAL, P. C. GUPTA and S. P. GARG, *Bull. Chem. Soc., Japan*, 1976, 49, 2077.
21. L. F. FISER, *Org. Synth.*, 1944, 1, 503.
22. M. M. BRUBACKER and R. ADAMS, *J. Amer. Chem. Soc.*, 1929, 49, 2279.
23. M. H. HUBACHER, *J. Amer. Chem. Soc.*, 1943, 65, 1655.

# Synthesis of Some New Derivatives of Azlactone (Part I)


M. A. EL-MAGHRABY and A. ABOU EL-ELA HASSAN

Chemistry Department, Aswan Faculty of Science, Aswan, Egypt

Manuscript received 19 June 1980, revised 15 December 1980, accepted 7 June 1982

Hippuric acid azlactone (I) was condensed with aldehydes to give the corresponding arylidino azlactones (II). Compounds (II) were reacted with hydrazine hydrate, phenylhydrazine and hydroxylamine to give the corresponding pyrazolines, phenylpyrazolines and isoxazolines, respectively.

IN view of bacteriostatic<sup>1,2</sup> and fungicidal activities of azlactone, we undertook the synthesis of a heterocyclic system containing an azlactone ring condensed with pyrazoline, N-phenyl pyrazoline, and isoxazolines hoping that these compounds might exhibit enhanced bacteriostatic activity. The hippuric acid azlactone (I) was condensed with aldehydes in presence of piperidine as a basic catalyst to give the corresponding arylidino azlactone (II).



The structure of compounds (II) was confirmed by elemental analysis and ir spectra, which showed a carbonyl stretching frequency at 1802 cm<sup>-1</sup>, characteristic for five-membered rings<sup>3</sup> and a band at 1640 cm<sup>-1</sup> for C=C<sup>4</sup>.

The additive property of the exocyclic C=C in compounds (II) conjugated with the carbonyl group prompted us to investigate their behaviour towards the action of hydrazine hydrate, phenyl hydrazine and hydroxylamine hydrochloride. Interaction of II with hydrazine hydrate under suitable condition gave a variety of pyrazolines. Hydrazine hydrate interacted with II in dioxan giving unstable pyrazolines but when these were treated with glacial acetic acid or when the reaction was carried out in presence of glacial acetic acid, the stable N-monoacetyl pyrazoline (III) was obtained.

The structure of compounds (III) has been established by elemental analysis and ir spectra which showed absorption bands at 1687-1613 cm<sup>-1</sup> (C=N) and at 1250-1227 cm<sup>-1</sup> (C-N) and the absence of the -NH stretching frequency.

Phenylhydrazine reacted with II in presence of a basic catalyst. The reaction was carried out in dioxan in presence of piperidine giving N-phenyl pyrazolines (IV).

The structure of compounds (IV) was established by elemental analysis and ir spectra which showed absorption bands at 1608-1592 cm<sup>-1</sup> (C=N) and at 1242-1220 cm<sup>-1</sup> (C-N). Compound (IV) proved to be stable on boiling with a mixture of acetic acid and conc. sulphuric acid at room temperature or on heating above its melting point which is the condition that causes the cyclization of phenylhydrazines to pyrazolines. The prepared pyrazoline gave a colour test characteristic for aryl pyrazolines<sup>5,6</sup>.

The isoxazoline (V) was obtained when a mixture of compound (II) and hydroxylamine in dioxan was refluxed in presence of NaOH. The structure of compounds (V) was established by elemental analysis and ir spectra which showed an absorption band at 1688-1612 cm<sup>-1</sup> (C=N).

The prepared compounds (III), (IV) and (V) were tested against two bacteria, *B. subtilis* and *E. coli*, and a fungus *Aspergillus*. It was found that the compounds were more active than the parent compound (II).




Fig. 1.

## Experimental

Infra red spectra were determined in KBr pellets on an Unicam Sp. 2006 Infrared spectrophotometer. Melting points are uncorrected. Hippuric acid and hippuric acid azlactone<sup>7</sup> were prepared by known methods.

TABLE 1—ARYLIDINE AZLACTONE (II)

Ar	Yield %	m. p. °C	M. F.	Analysis % Found (Calcd.)		
				C	H	N
C <sub>6</sub> H <sub>5</sub>	70	120-3	C <sub>16</sub> H <sub>11</sub> O <sub>3</sub> N	76.91 (77.10)	4.11 (4.42)	5.70 (5.62)
<i>p</i> -OHC <sub>6</sub> H <sub>4</sub>	73	127-9	C <sub>16</sub> H <sub>11</sub> O <sub>3</sub> N	72.15 (72.45)	4.18 (4.15)	5.14 (5.28)
<i>p</i> -NO <sub>2</sub> C <sub>6</sub> H <sub>4</sub>	75	132-5	C <sub>16</sub> H <sub>10</sub> O <sub>3</sub> N <sub>2</sub>	64.91 (65.31)	3.44 (3.40)	9.74 (9.52)
<i>o</i> -OHC <sub>6</sub> H <sub>4</sub>	71	137-9	C <sub>16</sub> H <sub>11</sub> O <sub>3</sub> N	72.05 (72.45)	4.20 (4.15)	5.20 (5.23)

TABLE 2—N-ACETYL PYRAZOLINE (III)

Ar	Yield %	m. p. °C	M. F.	Analysis % Found (Calcd.)		
				C	H	N
C <sub>6</sub> H <sub>5</sub>	50	160-3	C <sub>11</sub> H <sub>11</sub> O <sub>2</sub> N <sub>2</sub>	70.75 (70.82)	4.89 (4.92)	13.70 (13.77)
<i>p</i> -OHC <sub>6</sub> H <sub>4</sub>	55	158-9	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	67.00 (67.29)	4.70 (4.67)	12.95 (13.08)
<i>p</i> -NO <sub>2</sub> C <sub>6</sub> H <sub>4</sub>	60	164-6	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	61.69 (61.71)	4.05 (4.00)	16.02 (16.00)
<i>o</i> -OHC <sub>6</sub> H <sub>4</sub>	60	168-9	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	67.20 (67.29)	4.69 (4.67)	13.12 (13.08)

TABLE 3—PHENYL PYRAZOLINE (IV)

Ar	Yield %	m. p. °C	M. F.	Analysis % Found (Calcd.)		
				C	H	N
C <sub>6</sub> H <sub>5</sub>	59	140-4	C <sub>11</sub> H <sub>11</sub> ON <sub>2</sub>	77.80 (77.88)	5.05 (5.01)	12.29 (12.39)
<i>p</i> -OHC <sub>6</sub> H <sub>4</sub>	62	158-9	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	74.27 (74.37)	4.75 (4.79)	11.90 (11.83)
<i>p</i> -NO <sub>2</sub> C <sub>6</sub> H <sub>4</sub>	63	141-2	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	68.70 (68.75)	4.20 (4.17)	14.56 (14.58)
<i>o</i> -OHC <sub>6</sub> H <sub>4</sub>	60	160-2	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	74.31 (74.37)	4.80 (4.79)	11.80 (11.83)

TABLE 4—ISOXAZOLINE (V)

Ar	Yield %	m. p. °C	M. F.	Analysis % Found (Calcd.)		
				C	H	N
C <sub>6</sub> H <sub>5</sub>	65	170-3	C <sub>11</sub> H <sub>11</sub> O <sub>2</sub> N <sub>2</sub>	72.63 (72.73)	4.60 (4.55)	10.65 (10.61)
<i>p</i> -OHC <sub>6</sub> H <sub>4</sub>	60	167-3	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	68.51 (68.57)	4.30 (4.29)	10.01 (10.00)
<i>p</i> -NO <sub>2</sub> C <sub>6</sub> H <sub>4</sub>	63	175-7	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	60.20 (60.19)	3.50 (3.45)	13.20 (13.17)
<i>o</i> -OHC <sub>6</sub> H <sub>4</sub>	60	180-1	C <sub>11</sub> H <sub>10</sub> O <sub>2</sub> N <sub>2</sub>	68.49 (68.57)	4.25 (4.29)	10.01 (10.00)

TABLE 5—ANTIMICROBIAL ACTIVITY

Comp.	<i>B. subtilis</i>	<i>E. Coli</i>	<i>Aspergillus</i>
II	+	+	+ve
III	+++	++	+ve
IV	++	++	+ve
V	+++++	+++++	+ve

**Arylidine azlactone (II):** Equimolar amounts (0.1 mole) of hippuric acid azlactone and aromatic aldehyde were refluxed in dioxan (25 ml) containing piperidine (1 ml) for 1 to 3 hr. The reaction mixture was allowed to cool and arylidene azlactone was precipitated with petroleum ether (80-100). The product was filtered off, washed several times with petroleum ether and crystallized from ethanol. The results are given in Table 1.

**N-Acetyl pyrazoline (III):** A mixture of arylidene azlactone (II) (0.1 mole) hydrazine hydrate (0.1 mole) and a few drops of glacial acetic acid in dioxan (25 ml) was heated under reflux for 3 hr. The reaction mixture concentrated when the N-acetyl pyrazoline separated. It was filtered and recrystallized from benzene. The results are listed in Table 2.

**N-Phenyl pyrazoline (IV):** Equimolar amounts of arylidene azlactone (II) and phenyl hydrazine were refluxed in dioxan (30 ml) containing a few drops of piperidine for 3 hr. The reaction mixture was allowed to cool and the N-phenyl pyrazoline was precipitated with petroleum ether. The product was filtered washed several times with petroleum ether (80-100) and crystallized from the same solvent. The results are listed in Table 3.

**Isoxazoline (V):** A mixture of arylidene azlactone (II) (0.1 mole), hydroxylamine hydrochloride (0.1 mole) and a few pellets of NaOH in dioxan (30 ml) was heated under reflux for 3 hr. The reaction mixture was filtered and the precipitate washed thoroughly with dioxan. The isoxazoline was precipitated from the filtrate by ether. The product was filtered, washed several times with ether and recrystallized from the benzene. The results are listed in Table 4.

**Biological testing:** The bacteria used for testing were *B. subtilis* (gram positive) and *E. coli* (gram negative). The fungus used for testing was *Aspergillus*. The data are listed in Table 5.

#### References

1. A. A. MORTON, *Chem. Rev.*, 1944, 33, 1.
2. A. A. MORTON, *J. Amer. Chem. Soc.*, 1947, 69, 969.
3. L. Y. BELLAMY, "Infrared Spectra of Complex Molecules", Methuen and Co., 1959, p. 186.
4. L. Y. BELLAMY, "Infrared Spectra of Complex Molecules", Methuen and Co., 1959, p. 35.
5. B. H. Y. NICALET, *J. Amer. Chem. Soc.*, 1939, 57, 1098.
6. X. KNORR, *Ann.*, 1887, 238, 200.
7. KRAFFT, *Ber.*, 1882, 15, 1717.
8. BAUM, *J. Physical Chem.*, 1884, 9, 465.

# Synthesis of Pericarbonyl Lignans and Their Analogues

P. W. AGNIHOTRI, V. R. PASARKAR and G. BAGAVANT\*

Department of Chemistry, Nagpur University, Nagpur-440 010

Manuscript received 23 July 1981, revised 15 February 1982, accepted 7 June 1982

Perkin condensation of  $\beta$ -benzoylpropionic acid system (VI) and aryl aldehyde gave butenolide (VII) which led to  $\alpha$ -arylidene- $\beta$ -benzoylpropionic acid (IX). The latter, on formylation followed by cyclization afforded chloromethylnaphthoic acid (XV). Chloromethyl derivatives (XV) were subsequently converted into pericarbonyl lactones (XVI). This approach exemplifies a simple synthetic route to 1-aryl-2,3-naphthalide pericarbonyl lignans.

NATURAL products based on 2,3-dimethylphenyl-naphthalene constitute a distinct class of lignans.

More than 10 members, dehydropodophyllotoxin<sup>1a</sup>, diphyllin<sup>1b-1d</sup>, justicidin D<sup>1e</sup> (neojusticidin<sup>1f</sup>), justicidin E<sup>1g,h</sup>, taiwanin A<sup>1i</sup>, taiwanin C<sup>1m</sup> and helioxanthin<sup>1n</sup>, are now well characterized. All are lactones of either 1-phenyl-2-hydroxymethylnaphthalene-3-carboxylic acid (pericarbonyl lactone) (I) or 1-phenyl-3-hydroxymethylnaphthalene-2-carboxylic acid (perimethylene lactone) (II). Some of the aryl-naphthalide lignans were found to be physiologically active. Prominent among them are diphyllin<sup>a</sup> and justicidins A and B which are fish poisons, the latter being comparable to rotenone in toxicity in *Orizius latipes*<sup>a</sup>. Diphyllin completely inhibited DNA synthesis in Ehrlich carcinoma cells within a minute and partially inhibited RNA and protein formation<sup>a</sup>. The synthesis of some aryl-naphthalide lignans with pericarbonyl grouping is reported here.

An earlier attempt<sup>a</sup> to prepare the system of the type (I) by condensation of dimethylbenzoylsuccinate (III) and aryl aldehyde proceeded with the loss of carbomethoxy group leading to  $\alpha$ -arylidene- $\beta$ -benzoylpropionate (IV) which was later converted into pericarbonyl system (I).


To prepare pericarbonyl lactone (I) it was endeavoured to use  $\beta$ -aroylpropionic acid system (VI) which has two reactive methylene groups and a carboxy function capable of being handled to lead to the basic skeleton of lignan (VIII). A carbomethoxy group would yield part of furan ring adjacent to ring B and oxo group could be reduced.

Perkin condensation of  $\beta$ -benzoylpropionic acid (VI) with aryl aldehyde yielded butenolide of the type (VII) which finally led to  $\alpha$ -arylidene- $\beta$ -benzoylpropionic acid (IX). The butenolides (VII) were highly insoluble in most solvents, non-acidic to bicarbonate, but slowly dissolved in sodium hydroxide. Equivalent weight determination was not satisfactory (the products were highly insoluble and slight decomposition occurred). Using substituted benzoylpropionic acids and different aryl aldehydes, a number of butenolides were synthesized. These compounds showed an extended conjugation

at 400 nm in their ultraviolet spectra<sup>a</sup>. IR spectra of these compounds showed characteristic absorption at 1775 to 1760  $\text{cm}^{-1}$  (lactone carbonyl<sup>a</sup>) and nmr showed all protons in the expected region 6.58 to 7.58 $\delta$  (Table 1).

When the butenolide corresponding to benzaldehyde (VII;  $R_1=R_2=R'=H$ ) was treated with 30% sodium hydroxide with subsequent acidification, the products isolated were benzaldehyde and benzoic acid, respectively. A retro reaction occurred<sup>a</sup>. The butenolides (VII) were hence cleaved by refluxing in methanolic sodium carbonate (Borsche<sup>a</sup>), on acidification, afforded dark coloured mass which crystallized from aqueous alcohol to give  $\alpha$ -arylidene- $\beta$ -benzoylpropionic acids (IX). The IR spectra of IX showed a single absorption at 1681  $\text{cm}^{-1}$  (aryl conjugated carbonyl and  $\alpha,\beta$ -unsaturated acid<sup>10,11</sup>) (Table 2).

The stereochemistry of formation of  $\alpha$ -arylidene- $\beta$ -benzoylpropionic acids by Perkin condensation of  $\beta$ -benzoylpropionic acids with aryl aldehyde has E or *cis*  $\text{Ar/CH}_2\text{COPh}$  structure (X)<sup>a</sup>. The stereochemistry of the product would be controlled by the transition state in the Perkin reaction having the conformation with the bulky Ar and COOR groups *trans* which undergoes *trans* elimination of acetic acid to give the product (XI)<sup>10,11</sup>, with *cis* (E)  $\text{Ar/CH}_2\text{COPh}$  stereochemistry. Zimmerman orbital overlap theory<sup>12</sup> also leads to the same stereochemistry. For the overlap control, the carbonyl group must lie in the plane of the incipient double bond between the carbon 2 and 3. Out of the two transition states, (XII) and (XIII), which are possible in Perkin reaction (XII) would lead to *cis* (E)  $\text{Ar/CH}_2\text{COPh}$ . In the transition state (XII), the planarity which is necessary for orbital overlap is readily achieved as carbonyl group is unhindered. But in the case of (XIII), there is steric interaction of *cis* aryl/carbonyl groups which pushes the carbonyl group out of plane of the incipient double bond (XIIIa). So, the planarity is less readily achieved and consequently the overlap control is less. Thus the transition state (XII) is more favourable.




Scheme 1

$\alpha$ -Arylidene- $\beta$ -benzoylpropionic acid system (IX) thus obtained contained the required skeleton to prepare pericarboxyl lactone system. Elements of furan ring adjacent to ring B were introduced by formylation. Acid (IX) was treated with aqueous formaldehyde and potassium hydroxide to give the product which was identified as  $\alpha$ -arylidene- $\beta$ -methylene- $\beta$ -benzoylpropionic acid (XIV). [Kulkarni<sup>13,14</sup> observed that alkali concentration in the reaction play an important role in the formation of either mono or dicondensation product]. IR spectra of XIV showed a broad peak at  $1660\text{ cm}^{-1}$  for carboxyl and keto groups. In the nmr spectrum, two methylene protons appeared as a singlet at

$6.06\delta$ , and a singlet at  $7.85\delta$  was assigned for olefinic proton (Table 3).

To cyclize the  $\alpha$ -arylidene- $\beta$ -methylene- $\beta$ -benzoylpropionic acid system (XIV) to 1-phenyl-naphthalene system, it was treated with a mixture of acetic acid and conc. hydrochloric acid to give a product which was characterized as 1-phenyl-2-chloromethylnaphthalene-3-carboxylic acid (XV). IR spectra of chloromethyl derivatives (XV) showed a peak at  $1670\text{ cm}^{-1}$  for a carboxyl group. NMR spectra showed a singlet at  $5.08\delta$  for chloromethyl protons. The proton at  $C_8$  appeared as a singlet at  $6.68\delta$ . The proton at  $C_4$  showed a singlet at  $8.74\delta$ . A



Scheme 2

plet due to C<sub>3</sub> proton at 7.35δ is merged in aromatic pattern in the region 7.3-7.78δ (Table 4).

Chloromethyl derivatives (XV) were hydrolysed on heating with 10% aqueous sodium hydroxide. When they were treated with excess of hydrochloric acid and heated at 100° for 0.5 hr. After cooling, a solid was isolated and identified as 1-phenyl-2-benzoxymethylnaphthalene-3-carboxylic acid lactone (I). In ir spectra of XVI, absorption at 1760 cm<sup>-1</sup> indicated the presence of 5-membered lactone ring<sup>16</sup>. The nmr spectra are also consistent with structures assigned to them. 4-H proton resonance close to 8.38δ (compared to 7.7δ in retro one<sup>14</sup>) whilst methylene group of lactone<sup>17</sup> is shielded by ring current. This is seen by the chemical shift near 5.10δ in contrast to 5.40δ in retro lactone (Table 5).

#### Experimental

All melting points are uncorrected. The infrared spectra were run on Perkin-Elmer 237 grating spectrophotometer in nujol and uv on Beckmann DB-4 spectrophotometer in ethanol unless otherwise stated. Nmr spectra were measured at 60 MHz using tetrachloroform (CDCl<sub>3</sub>) as the solvent, the

chemical shifts are given in ppm using tetramethylsilane (TMS) as an internal standard.

1. *Perkin condensation of β-benzoylpropionic acid and veratraldehyde; α-(3,4-Dimethoxybenzylidene)-γ-phenyl-Δβ,γ-butenolide* (VIIa, R<sub>1</sub>=R<sub>2</sub>=OCH<sub>3</sub>, R'=H):

Veratraldehyde (4.2 g; 0.025 m) and β-benzoylpropionic acid (4.9 g; 0.025m) were refluxed for 3 hr in presence of acetic anhydride (7.5 ml) and a drop of pyridine. The hot reaction mixture was added to cold water (100 ml) and was warmed for a minute, cooled to 0°, filtered, washed with water, dried and crystallized from benzene to give α-(3,4-dimethoxybenzylidene)-γ-phenyl-Δβ,γ-butenolide (VIIa), m.p. 125° UV: λ<sub>max</sub><sup>EtOH</sup> 249 nm, log ε 4.21, 3.91 nm, log ε 4.21 and shoulder 406 nm, log ε 4.74. (Found: C, 73.56; H, 5.96. Calcd. for C<sub>15</sub>H<sub>14</sub>O<sub>4</sub>; C, 74.02; H, 5.23%. Table 1 presents the data for other butenolides (VIIa-VIIf).

2. *α-(3,4-Dimethoxybenzylidene)-β-benzoylpropionic acid* (IXa, R<sub>1</sub>=R<sub>2</sub>=OCH<sub>3</sub>, R'=H):

α-(3,4-Dimethoxybenzylidene)-γ-phenyl-Δβ,γ-butenolide (VIIa) (5 g) was refluxed with alcoholic sodium carbonate solution for 5 hr. The resulting mixture was cooled, filtered and acidified to congo

TABLE 1— $\alpha$ -ARYLIDENE- $\gamma$ -PHENYL- $\Delta\beta,\gamma$ -BUTENOLIDES (VII)  
Condensation of  $\beta$ -Aroylpropionic Acid with Aldehydes

Sl. No.	Aldehyde g	$\beta$ -Aroylpropionic acid g	Lactone Yield		m.p. °C	UV nm (log $\epsilon$ )	$\epsilon$ OH cm <sup>-1</sup>	IR cm <sup>-1</sup>	NMR $\delta$	Analysis %			
			g	%						Found		Calcd.	
1.	Veratraldehyde 8.3	$\beta$ -Benzoylpropionic acid 8.9	(VIIa) 14.1	73.3	125	249(4.21) 392(4.32) 406(4.24)	—	—	—	73.56	5.96	74.02	5.23
2	Veratraldehyde 8.3	4-Methoxybenzoylpropionic acid 10.4	(VIIb) 14.6	82.8	172	—	—	—	—	70.59	5.17	71.00	5.36
3a	Veratraldehyde 8.3	4-Methylbenzoylpropionic acid 9.6	(VIIc) 12.1	75.1	170	—	—	—	—	74.14	5.28	74.53	5.63
4.	Vanillin 7.1	$\beta$ -Benzoylpropionic acid 8.9	(VIId) 13.7	85.6	147	252 (4.18) 393 (4.26)	—	—	—	—	—	—	—
5.	Vanillin 7.1	4-Methoxybenzoylpropionic acid 10.4	(VIIe) 11.7	72.2	188	—	—	—	—	70.12	4.58	70.37	4.97
6.	Vanillin 7.1	4-Methylbenzoylpropionic acid 9.6	(VIIf) 13.1	85.0	156	—	—	—	—	74.22	4.95	74.01	5.23
7.	Vanillin 7.1	4-Isopropylbenzoylpropionic acid 11.0	(VIIg) 11.5	77.0	122	—	—	—	—	74.79	6.03	74.97	5.99
8.	Vanillin 7.1	4-Chlorobenzoylpropionic acid 10.6	(VIIh) 11.5	70.0	—	—	—	—	—	—	—	—	—
9.	Vanillin 7.1	4-Bromobenzoylpropionic acid 8.9	(VIIi) 13.2	63.2	128	—	—	—	—	—	—	—	—
10.	4-Methoxybenzaldehyde 6.8	$\beta$ -Benzoylpropionic acid 8.9	(VIIj) 13.2	84.1	169	245 (4.28) 290 (4.20) 402 (4.23)	1772 3.87 (s, 3H, OCH <sub>3</sub> ) 1762 7.11-7.06 (m, 9H aromatic), 6.92 (s, 2H, olefinic)	—	—	77.66	5.07	77.69	5.07
11.	3-Methoxybenzaldehyde 6.8	$\beta$ -Benzoylpropionic acid 10.4	(VIIk) 11.0	81.3	120	—	—	—	—	77.18	5.27	77.69	5.07
12.	3-Methoxybenzaldehyde 6.8	4-Methoxybenzoylpropionic acid 10.4	(VIIl) 12.1	71.4	135	—	—	—	—	—	—	—	—
13.	Piperonal 7.5	$\beta$ -Benzoylpropionic acid 8.9	(VIIm) 14.0	85.4	166	254 (4.12) 404 (4.46)	1772 6.03 (s, 2H, -OCH <sub>2</sub> O-) 1862 7.85-6.91 (m, 8H aromatic), 6.78 (s, 2H, olefinic)	—	—	73.48	4.59	73.97	4.14
14.	Piperonal 7.5	4-Methoxybenzoylpropionic acid 10.4	(VIIn) 12.1	76.1	115	—	—	—	—	71.65	4.54	70.80	4.38
15.	Piperonal 7.5	4-Methylbenzoylpropionic acid 9.6	(VIIo) 12.0	82.1	190	—	—	—	—	—	—	—	—

Contd. Table 1



Sl. No.	Aldehyde	$\beta$ -Aroyl-propionic acid	Lactone	Yield	m.p.	UV	$\epsilon_{10\text{M}}$	IR	NMR	(Contd. Table I)			
										Analysis %		Calcd.	
	g	g	g	%	°C	nm (log $\epsilon$ )		cm <sup>-1</sup>	$\delta$	Found	H	Found	H
16.	Piperonal 7.5	4-Ethyl-benzoyl-propionic acid 10.3	(VIIp) 10.0	65.4	137	—	—	—	—	74.59	4.75	74.99	5.04
17.	Piperonal 7.5	4-Isopropylbenzoyl-propionic acid 11.0	(VIIq) 14.3	85.1	114	—	—	—	—	75.25	5.67	75.44	5.43
18.	Piperonal 7.5	4-Chloro-benzoyl-propionic acid 10.6	(VIIr)	66.7	245	—	—	—	—	—	—	—	—

 TABLE 2— $\alpha$ -ARYLIDENE- $\beta$ -BENZOYLPROPIONIC ACID (IX)

Sl. No.	R	Eq. wt. Found	Eq. wt. Calcd.	m.p. °C	UV $\lambda_{\text{max}}$ nm (log $\epsilon$ )	IR cm <sup>-1</sup>	NMR $\delta$	Analysis %			
								Found	H	Calcd.	H
1	IXa : R <sub>1</sub> = R <sub>2</sub> = OCH <sub>3</sub> , R' = H	323	326	169	233(4.17) 274(3.99) 398(3.85)	1681	—	70.41	5.12	69.93	5.56
2.	IXb : R <sub>1</sub> = R <sub>2</sub> = R' = OCH <sub>3</sub>	349	356	192	—	1681	—	67.82	5.56	67.40	5.66
3.	IXc : R <sub>1</sub> = R <sub>2</sub> = OCH <sub>3</sub> , R' = CH <sub>3</sub>	338	340	196	—	1682	2.43 (s, 3H, -CH <sub>3</sub> ), 3.63 and 3.80 (s, 6H, 2-OCH <sub>3</sub> ), 4.23 (s, 2H, -CH <sub>2</sub> ), 6.83-7.97 (m, 7H, aromatic and olefinic protons)	69.67	5.35	70.56	5.92
4.	IXd : R <sub>1</sub> = OCH <sub>3</sub> , R <sub>2</sub> = OH, R' = H	317	312	207	233(4.39) 289(4.19)	—	—	69.63	4.92	69.23	5.16
5.	IXe : R <sub>1</sub> = OCH <sub>3</sub> , R <sub>2</sub> = OH, R' = OCH <sub>3</sub>	339	342	211	—	1682	3.68 and 3.95 (s, 6H, 2-OCH <sub>3</sub> ), 4.28 (s, 2H, -CH <sub>2</sub> ), 7.14 (s, 1H, -OH), 6.90-8.10 (m, 8H, olefinic and aromatic protons)	66.90	5.06	66.66	5.30
6.	IXf : R <sub>1</sub> = OCH <sub>3</sub> , R <sub>2</sub> = OH, R' = CH <sub>3</sub>	330	326	223	—	1681	—	70.41	5.25	69.93	5.56
7.	IXg : R <sub>1</sub> = OCH <sub>3</sub> , R <sub>2</sub> = OH, R' = $\begin{array}{c} \text{H} \\ \diagup \quad \diagdown \\ \text{C} \\ \diagdown \quad \diagup \\ \text{CH}_3 \end{array}$	348	354	163	—	1682	—	71.48	6.42	71.16	6.26
8.	IXh : R <sub>1</sub> = OCH <sub>3</sub> , R <sub>2</sub> = OH, R' = Cl	341	346.5	213	—	—	—	—	—	—	—
9.	IXi : R <sub>1</sub> = OCH <sub>3</sub> , R <sub>2</sub> = R' = H	293	296	177	245(4.28) 275(4.30) 296(4.05)	—	—	73.24	6.03	72.98	5.44
1.	IXk : R <sub>1</sub> = OCH <sub>3</sub> , R <sub>2</sub> = R' = H	291	296	145	—	—	—	—	—	—	—
2	IXl : R <sub>1</sub> , R <sub>2</sub> = -OCH <sub>2</sub> O-, R' = H	307	310	203	237(4.42)	1682	4.30 (s, 2H, -CH <sub>2</sub> ), 6.12 (s, 2H, -OCR <sub>2</sub> O-), 6.98-8.2 (m, 9H, aromatic protons)	70.41	4.96	69.68	4.55
3	IXm : R <sub>1</sub> , R <sub>2</sub> = -OCH <sub>2</sub> O-, R' = OCH <sub>3</sub>	335	340	—	—	—	—	66.75	4.32	67.06	4.74
4.	IXn : R <sub>1</sub> , R <sub>2</sub> = -OCH <sub>2</sub> O-, R' = CH <sub>3</sub>	320	324	196	—	—	—	69.92	4.78	70.37	4.97
5.	IXo : R <sub>1</sub> , R <sub>2</sub> = -OCH <sub>2</sub> O-, R' = C <sub>2</sub> H <sub>5</sub>	342	338	—	—	—	—	—	—	—	—
6.	IXp : R <sub>1</sub> , R <sub>2</sub> = -OCH <sub>2</sub> O-, R' = $\begin{array}{c} \text{H} \\ \diagup \quad \diagdown \\ \text{C} \\ \diagdown \quad \diagup \\ \text{CH}_3 \end{array}$	348	352	161	—	—	—	—	—	—	—
7.	IXq : R <sub>1</sub> , R <sub>2</sub> = -OCH <sub>2</sub> O-, R' = Cl	337	344.5	—	—	—	—	—	—	—	—
8.	IXr : R <sub>1</sub> = R' = OCH <sub>3</sub> , R <sub>2</sub> = H	—	326	142	—	—	—	—	—	—	—

TABLE 3—4-ARYLIDENE-β-METHYLENE-β-BENZOYLPROPIONIC ACIDS (XIV)

Sl. No.	R	Eq. wt Found	Eq. wt. Calcd.	m. p. °C	UV: $\lambda_{\text{max}}^{\text{EtOH}}$ nm (log $\epsilon$ )	IR: $\text{cm}^{-1}$	NMR $\delta$	Analysis %			
								Found		Calcd.	
								C	H	C	H
1.	XIVa: $R_1=R_2=\text{OCH}_3$ , $R'=H$	332	338	125	235 (4.21) 282 (4.08)	1660	3.82 and 3.90 (s, 6H, $2\text{-OCH}_3$ ), 6.06 (s, 2H, $-\text{C}=\text{CH}_2$ ), 6.8-8.0 (m, 9H, aromatic and olefinic protons)	70.65	5.02	71.00	5.36
2.	XIVe: $R_1=R_2=\text{OCH}_3$ , $R_3=\text{OH}$	348	354	201	—	1660	—	67.41	5.34	67.80	5.12
3.	XIVi: $R_1=\text{OCH}_3$ , $R_2=R_3=H$	302	308	170	—	—	—	73.68	5.31	74.02	5.23
4.	XIVj: $R_1=R_2=H$ , $R_3=\text{OCH}_3$	304	308	144	—	—	—	—	—	—	—
5.	XIVl: $R_1R_2=\text{OCH}_2\text{O}$ , $R'=H$	317	322	—	—	1650	5.99-6.02 (d, 2H $-\text{C}=\text{CH}_2$ ), 6.15 (s, 2H, $-\text{OCH}_2\text{O}-$ ), 6.93-8.0 (m, 9H, aromatic and olefinic protons)	71.24	4.09	70.80	4.38

TABLE 4—1-PHENYL-2-CHLOROETHYL-NAPHTHALENE-3 CARBOXYLIC ACIDS

Sl. No.	R	Eq. wt Found	Eq. wt. Calcd.	m. p. °C	UV: $\lambda_{\text{max}}^{\text{EtOH}}$ nm (log $\epsilon$ )	IR: $\text{cm}^{-1}$	NMR $\delta$	Analysis %			
								Found		Calcd.	
								C	H	C	H
1.	XVa: $R_1=R_2=\text{OCH}_3$ , $R'=H$	351	356.8	217	235 (4.21) 282 (4.08)	1670	3.74 and 4.07 (s, 6H, $2\text{-OCH}_3$ ), 5.08 (s, 2H, $-\text{CH}_2\text{-Cl}$ ), 6.68 (s, 1H, $\text{C}_8\text{-H}$ ), 7.35 (s, 1H, $\text{C}_6\text{-H}$ ), 7.45-7.68 (m, 5H, phenyl) and 8.74 (s, 1H, $\text{C}_4\text{-H}$ )	66.96	4.73	67.33	4.80
2.	XVb: $R_1=R_2=R_3=\text{OCH}_3$	380	386.8	179	—	1670	—	—	—	—	—
3.	XVc: $R_1=R_2=\text{OCH}_3$ , $R'=\text{CH}_3$	366	370.8	209	—	1671	—	67.79	5.01	68.02	5.16
4.	XVd: $R_1=\text{OCH}_3$ , $R_2=\text{OH}$ , $R'=H$	335	342.8	179	—	1670	—	—	—	—	—
5.	XVe: $R_1=R_2=\text{OCH}_3$ , $R_3=\text{OH}$	366	372.8	212	—	—	—	—	—	—	—
6.	XVf: $R_1=\text{OCH}_3$ , $R_2=\text{OH}$ , $R'=\text{CH}_3$	352	356.8	—	—	—	—	—	—	—	—
7.	XVg: $R_1=\text{OCH}_3$ , $R_2=\text{OH}$ , $R'=\text{C}(\text{H})\text{CH}_3$	380	384.8	196	—	1672	—	68.26	5.37	68.66	5.50
8.	XVh: $R_1=\text{OCH}_3$ , $R_2=R_3=H$	321	326.8	201	—	—	—	—	—	—	—
9.	XVi: $R_1=R_2=\text{OCH}_3$ , $R_3=H$	348	356.8	—	—	—	—	—	—	—	—
10.	XVm: $R_1R_2=\text{OCH}_2-$ , $R'=H$	336	340.8	241	—	—	—	67.32	3.41	66.96	3.84
11.	XVn: $R_1R_2=\text{OCH}_2\text{O}$ , $R'=\text{CH}_3$	351	354.8	245	—	1671	—	67.47	4.56	67.70	4.26
12.	XVo: $R_1R_2=\text{OCH}_2\text{O}$ , $R'=\text{C}(\text{H})\text{CH}_3$	376	382.8	229	—	—	—	68.77	4.69	69.01	5.00

TABLE 5—1-ARYL-2-HYDROXYMETHYLNAPHTHALENE-3-CARBOXYLIC ACID LACTONES

Sl. No.	R	m.p. °C	UV : $\lambda_{max}^{EIOH}$ nm (log $\epsilon$ )	IR $cm^{-1}$	NMR $\delta$	Found C	Found H	Analysis % Calcd. C	Analysis % Calcd. H
1. XVIa :	$R_1 = R_2 = OCH_3$ , $R' = H$	205	258 (4.69) 314 (4.02)	1760	3.85 and 4.06 (s, 6H, 2-OCH <sub>3</sub> ), 5.22 (s, 2H, lactone CH <sub>2</sub> ), 7.16 (s, 1H, C <sub>8</sub> -H), 7.37 (s, 1H, C <sub>6</sub> -H), 7.6 (br. s, 5H, phenyl) and 8.36 s, 1H, C <sub>4</sub> -H)	75.04	5.39	74.99	5.04
2. XVIb :	$R_1 = R_2 = R' = OCH_3$	230	—	1761	3.90, 4.01, 4.25 (s, 9H, 3-OCH <sub>3</sub> ), 5.30 (s, 2H, lactone CH <sub>2</sub> ), 7.1-7.7 (m, 6H, aromatic), 8.4 (s, 1H, C <sub>4</sub> -H)	72.37	4.86	72.00	5.18
3. XVIc :	$R_1 = R_2 = OCH_3$ , $R' = CH_3$	214	—	1762	2.50 (s, 3H, -CH <sub>3</sub> ), 3.86 and 4.08 (s, 6H, 2-OCH <sub>3</sub> ), 5.23 (s, 1H, lactone CH <sub>2</sub> ), 7.16-7.40 (m, 6H, aromatic), 8.33 (s, 1H, C <sub>4</sub> -H)	75.39	5.24	75.44	5.43
4. XVI d :	$R_1 = OCH_3$ , $R_2 = OH$ , $R' = OCH_3$	220	—	—	—	—	—	—	—
5. XVIe :	$R_1 = OCH_3$ , $R_2 = OH$ , $R' = CH_3$	241	—	1760	2.47 (s, 3H, -CH <sub>3</sub> ), 3.83 (s, 3H, -OCH <sub>3</sub> ), 5.20 (s, 2H, lactone CH <sub>2</sub> ), 7.04-7.30 (m, 7H and 1H, -OH aromatic) 8.25 (s, 1H, C <sub>4</sub> -H)	74.68	4.73	74.99	5.04
6. XVII :	$R_1 = OCH_3$ , $R_2 = OH$ , $R' = \begin{array}{c} H \\ \diagup \\ C \\ \diagdown \\ CH_3 \end{array}$	244	—	1762	—	76.06	5.45	75.83	5.79
7. XVIg :	$R_1 = OCH_3$ , $R_2 = H' = H$	172	—	—	3.97 (s, 3H, -OCH <sub>3</sub> ), 5.21 (s, 2H, lactone CH <sub>2</sub> ), 7.17-7.83 (m, 8H, aromatic), 8.33 (s, 1H, C <sub>4</sub> -H)	78.25	4.34	78.60	4.86
8. XVIIh :	$R_1, R_2 = OCH_2O-$ , $R' = H$	211	—	—	—	—	—	—	—
9. XVIIi :	$R_1, R_2 = OCH_2O-$ , $R' = CH_3$	171	—	1672	2.50 (s, 3H, -CH <sub>3</sub> ), 5.23 (s, 2H, lactone CH <sub>2</sub> ), 6.10 (s, 2H, -OCH <sub>2</sub> O-), 7.13-7.4 (d, 6H aromatic), 2.28 (s, 1H, C <sub>4</sub> -H)	75.19	4.23	75.46	4.43
10. XVIIj :	$R_1, R_2 = -OCH_2O-$ , $R' = \begin{array}{c} H \\ \diagup \\ C \\ \diagdown \\ CH_3 \end{array}$	241	—	—	—	76.73	4.87	76.29	5.24

red with HCl (3N). It gave a solid which was crystallized and identified as  $\alpha$ -(3,4-dimethoxybenzylidene)- $\beta$ -benzoylpropionic acid (4.6 g). Recrystallized from aqueous ethanol, m.p. 169°. Eq. wt. Found 324; Calcd. for C<sub>19</sub>H<sub>18</sub>O<sub>5</sub>; 326. IR :  $\nu_{CO}$  (nujol) 1650 cm<sup>-1</sup> ( $\alpha$ ,  $\beta$ -unsaturated ketone and carboxylic acid). (Found : C, 70.41; H, 5.12. Calcd. for C<sub>19</sub>H<sub>18</sub>O<sub>5</sub>; C, 69.92 H, 5.56%). Table 2 presents data for other acids (IXa-IXr).

3.  $\alpha$ -(3,4-Dimethoxybenzylidene)- $\beta$ -methylene- $\beta$ -benzoylpropionic acid (XIVa,  $R_1 = R_2 = OCH_3$ ,  $R' = H$ ):

To a solution of  $\alpha$ -(3,4-dimethoxybenzylidene)- $\beta$ -benzoylpropionic acid (IXa) in 10% aqueous sodium hydroxide (9 ml) was added 40% formalin solution (6 ml) and the reaction mixture was left overnight at room temperature. It was then cooled, acidified and extracted with benzene (3×50 ml) and dried (MgSO<sub>4</sub>). Evaporation of the solvent led to an orange gum (2.3 g) crystallized from benzene-petroleum ether (40-60) to give a solid, m.p. 125-126°, which was identified as  $\alpha$ -(3,4-dimethoxybenzylidene)- $\beta$ -methylene- $\beta$ -benzoylpropionic acid. UV :  $\lambda_{max}^{EIOH}$  235 nm (log  $\epsilon$  4.21) and 282 nm (log  $\epsilon$  4.08). IR :  $\nu_{CO}$  (nujol) 1660 cm<sup>-1</sup> (C=O and CO<sub>2</sub>H merged). NMR : (CDCl<sub>3</sub>)  $\delta$  3.82 and 3.90 (s, 6H, 2-OCH<sub>3</sub>), 6.06 (s, 2H, C=CH<sub>2</sub>), 6.8-8.0 (m, 9H,


aromatic and olefinic protons). Table 3 presents data for other methylenic compounds (XIVa-XIVi).

4. 1-Phenyl-2-chloromethyl-6,7-dimethoxynaphthalene-3-carboxylic acid (XVa,  $R_1 = R_2 = OCH_3$ ,  $R' = H$ ):

Conc. hydrochloric acid (50 ml) was gradually added to a cold solution of  $\alpha$ -(3,4-dimethoxybenzylidene)- $\beta$ -methylene- $\beta$ -benzoylpropionic acid (XIVa) (2.6 g) in glacial acetic acid (20 ml) and the mixture left overnight at room temperature. The yellow precipitate (2.2 g) formed was collected and crystallized from methanol to give a pale yellow solid, m.p. 217°, Eq. wt. Found 355; Calcd. for C<sub>20</sub>H<sub>17</sub>O<sub>4</sub>Cl; 356.5. UV :  $\lambda_{max}^{EIOH}$  252 (log  $\epsilon$  4.79) and 287 (log  $\epsilon$  3.93). IR :  $\nu_{CO}$  (KBr) 1670 cm<sup>-1</sup> (COOH gr). NMR : (CDCl<sub>3</sub>)  $\delta$  3.74 and 4.07 (s, 6H, 2-OCH<sub>3</sub>), 5.08 (s, 2H, -CH<sub>2</sub>Cl), 6.68 (s, 1H, C<sub>8</sub>-H), 7.35 (s, 1H, C<sub>6</sub>-H), 7.45-7.68 (m, 5H, phenyl) and 8.74 (s, 1H, C<sub>4</sub>-H). (Found : C, 66.96; H, 4.73. Calcd. for C<sub>20</sub>H<sub>17</sub>O<sub>4</sub>Cl; C, 67.33; H, 4.80%). Table 4 presents data for other chloromethyl derivatives (XVa-XVo).

5. 1-Phenyl-2-hydroxymethyl-6,7-dimethoxynaphthalene-3-carboxylic acid lactone (XVIa,  $R_1 = R_2 = OCH_3$ ,  $R' = H$ ):

The chloromethylnaphthoic acid (XVa) (2.0 g) was dissolved in 10% sodium hydroxide (15 ml) and



Scheme 3

heated at 100° for 1 hr. The mixture was cooled and washed with water to give a yellow solid (1.7 g). Crystallization from chloroform-methanol gave light yellow prisms, m.p. 205°, of 1-phenyl-2-hydroxymethyl-6,7-dimethoxynaphthalene-3-carboxylic acid lactone (XVIa). UV:  $\lambda_{max}^{EtOH}$  258 (log  $\epsilon$  4.69) and 314 nm (log  $\epsilon$  4.02). IR:  $\nu_{CO}$  (KBr) 1670  $cm^{-1}$  (lactone). NMR:  $CDCl_3$ ,  $\delta$  3.85 and 4.06 (s, 6H, 2-OCH<sub>3</sub>), 5.22 (s, 2H, lactone CH<sub>2</sub>), 7.16 (s, 1H, C<sub>8</sub>-H), 7.37 (s, 1H, C<sub>6</sub>-H), 7.16 (br, s, 5H phenyl) and 8.36 (s, 1H, C<sub>4</sub>-H). Table 5 presents data for other pericarboxyl lactones (XVIa-XVIj).

#### Acknowledgement

The authors thank Dr. P. A. Ganeshpure, Brandeis University, Waltham, U. S. A., and Dr. M. K. Gurjar, York University, Toronto, Canada for some of the spectral data and the Head of the Deptt. of Chemistry and the authorities of Central Instrumentation and Service Centre, Nagpur University, Nagpur for necessary facilities. Of the authors, (P. W. A.) thanks C. S. I. R., New Delhi

and (V. R. P.) thanks U. G. C., New Delhi for financial assistance.

#### References

- 1a. H. KOPOD and J. JORGENSEN, *Acta Chem. Scand.*, 1954, 8, 941, 1296; 1955, 9, 346.
- 1b. T. MURAKAMI and A. MATSUSHIMA, *Yakagaku Zasshi*, 1961, 81, 1596.
- 1c. T. R. GOVINDACHARI, S. S. SATHE, N. VISHWANATHAN, B. R. PAI and M. SHRINIVASAN, *Tetrahedron Lett.*, 1967, 3517.
- 1d. Z. HORII, K. OHKAWA, S. KIM and T. MOMOSE, *Chem. Comm.*, 1968, 653.
- 1e. K. MUNAKATA, S. MARUMO, K. OHTA and Y.-L. CHEN, *Tetrahedron Lett.*, 1967, 4167.
- 1f. K. OHTA and K. MUNAKATA, *Tetrahedron Lett.*, 1970, 923.
- 1g. M. OKIGAWA, T. MAEDA and N. KAWANO, *Chem. Pharm. Bull.*, 1970, 18, 862.
- 1h. K. WADA and K. MUNAKATA, *Tetrahedron Lett.*, 1970, 2017.
- 1i. R. D. HAWORTH and W. KELLY, *J. Chem. Soc.*, 1935, 745.
- 1j. Y.-T. LIN, T.-B. LO, K.-T. HANG and B. WEINSTEIN, *Tetrahedron Lett.*, 1967, 849.
- 1k. Z. HORII, M. TSUTSUCHI and T. MOMOSE, *Tetrahedron Lett.*, 1969, 1079.
- 1l. H. MACLEAN and B. L. MACDONALD, *Can. J. Chem.*, 1969, 47, 457.
- 1m. H. MACLEAN and B. F. MACDONALD, *Can. J. Chem.*, 1969, 47, 4495.
- 1n. R. S. BURDEN, L. CROMBIE and D. WHITING, *Tetrahedron Lett.*, 1968, 1035; *J. Chem. Soc. (C)*, 1969, 693.
2. T. MURAKAMI and A. MATSUSHIMA, *J. Pharm. Soc., Japan*, 1961, 81, 1596.
3. K. MUNAKATA, S. MARUMO, K. OHTA and Y.-L. CHEN, *Tetrahedron Lett.*, 1965, 4167.
4. A. G. GONZALEZ and V. DARIUM, *Planta Med.*, 1979, 36, 200; *Chem. Abs.*, 1979, 91, 186441.
5. P. A. GANESHPURE, Ph.D. Thesis, Nagpur University, 1977.
6. A. I. SCOTT, "Interpretation of the UV Spectra of Natural Products", Pergamon Press, London, 1969, p. 79.
7. C. N. R. RAO, "Chemical Applications of Infrared Spectroscopy", Academic Press, London, 1963, p. 193.
8. V. R. PASARKAR, Ph.D. Thesis, Nagpur University, 1977.
9. W. BORSCHKE, *Ber.*, 1904, 47, 1108.
10. N. H. CROMWELL and R. A. SETTERQUIST, *J. Amer. Chem. Soc.*, 1957, 79, 116.
11. E. L. ELIEL, "Stereochemistry of Carbon Compounds", McGraw Hill Book Company, Inc., New York, 1962, p. 92.
12. H. E. ZIMMERMAN and ABRAMIAN, *J. Amer. Chem. Soc.*, 1959, 81, 2086.
13. V. P. BARVE, A. B. KULKARNI and A. P. WAGH, *Indian J. Chem.*, 1976, 14B, 84.
14. A. P. WAGH and A. B. KULKARNI, *Indian J. Chem.*, 1975, 13B, 882.
15. R. D. HAWORTH and G. SHELDRIK, *J. Chem. Soc.*, 1935, 636.
16. A. S. R. ANJANEU, V. K. RAO, P. SATYANARAYANA and L. R. ROW, *Indian J. Chem.*, 1973, 11, 203.
17. S. GHOSAL, R. P. S. CHAUHAN and R. S. SHRIVASTAVA, *Phytochemistry*, 1974, 13, 1933.

# Synthesis of Aryloxy/Aryl Acetyl Thiosemicarbazides, Substituted 1,3,4-Oxadiazoles, 1,3,4-Thiadiazoles, 1,2,4-Triazoles and Related Compounds as Potential Fungicides

R. S. SHARMA and S. C. BAHEL\*

Chemistry Department, Gorakhpur University, Gorakhpur-273 001


Manuscript received 22 June 1981, accepted 28 April 1982

Twelve 1-aryloxy/aryl acetyl-4-aryl thiosemicarbazides, twelve 2-arylamino-5-aryloxy/aryl methyl-1,3,4-oxadiazoles, eleven 2-arylamino-5-aryloxy/aryl methyl-1,3,4-thiadiazoles, twelve 3-aryloxy/aryl methyl-4-aryl-5-mercapto-1,2,4-triazoles, three methyl-(3-aryloxymethyl-4-aryl-1,2,4-triazol-5-yl)-sulphides, three *bis*-(3-aryloxymethyl-4-aryl-1,2,4-triazol-5-yl)-disulphides and six *bis*-(3-aryloxy/aryl methyl-4-aryl-1,2,4-triazol-5-yl)-alkylene disulphides were prepared. Forty nine compounds have been screened against *A. niger* and *H. oryzae* and were found to possess moderate to fairly good antifungal activity.

**THIOSEMICARBAZIDES** have been reported to possess antifungal<sup>1,2</sup>, antibacterial<sup>3</sup> and anti-convulsant<sup>4</sup> properties. 2-Amino-5-substituted-1,3,4-oxadiazoles were prepared as antimitotic<sup>5</sup> and muscle relaxant and tranquilizing agents<sup>6</sup>. Substituted thiadiazoles are known to exhibit fungicidal<sup>7</sup>, bactericidal<sup>8</sup>, herbicidal<sup>9</sup> and insecticidal<sup>10</sup> activities.


Compounds containing triazole ring have shown good fungicidal<sup>11</sup>, bactericidal<sup>12</sup> and pesticidal<sup>13</sup> activities. Anticancer and antifungal activities have been displayed by some heterocyclic sulphides<sup>14</sup>. Further, sulphides have been found to be more active than parent mercapto compounds<sup>15</sup>. In view of these, the title compounds have been synthesised.

1-Aryloxy/aryl acetyl-4-aryl thiosemicarbazides (I) have been prepared by the reaction of aryloxy/aryl acetyl hydrazine<sup>16</sup> and aryl isothiocyanate. I was cyclised into 2-arylamino-5-aryloxy/aryl methyl-1,3,4-oxadiazoles (II) in the presence of mercuric oxide. Reaction of I with sulphuric acid gave 2-arylamino-5-aryloxy/aryl methyl-1,3,4-thiadiazoles (III).



3-Aryloxy/aryl methyl-4-aryl-5-mercapto-1, 2, 4-triazoles (IV) have been obtained by reacting aryloxy/aryl acetyl hydrazine<sup>16</sup> with aryl isothiocyanate in the presence of alkali. Reaction of IV with methyl iodide gave methyl triazolyl sulphides (V) whereas with bromine, *bis*-triazolyl disulphides (VI)

and with alkylene dihalide, *bis*-triazolyl alkylene disulphides (VII) were produced.



The compounds thus prepared are given in Tables 1-5 along with their antifungal data. Satisfactory N and S analyses results were found for all the compounds

## Experimental

All melting points are uncorrected.

**Aryloxy/aryl acetyl hydrazines:** These were prepared by the method of Conti<sup>16</sup>.

**1-Aryloxy/aryl acetyl-4-aryl thiosemicarbazides (I):** These were prepared by the method of Paul and Basu<sup>17</sup>.

**2-Arylamino-5-aryloxy/aryl methyl-1,3,4-oxadiazoles (II):** 1-Aryloxy/aryl acetyl-4-aryl thiosemicarbazide (0.01 M) was dissolved/suspended in methanol and mercuric oxide (0.011 M) was added to it. The contents were refluxed for 2 hr and the mixture filtered hot. The filtrate was evaporated and the solid obtained was recrystallised from aqueous ethanol.

**2-Arylamino-5-aryloxy/aryl methyl-1,3,4-thiadiazoles (III):** 1-Aryloxy/aryl acetyl-4-aryl thiosemicarbazide (0.01 M) was dissolved with cooling in conc. sulphuric acid (10 ml). The solution was kept at room temperature for 2 hr, stirred at intervals and then poured over crushed ice. It was stirred well and left as such for 1 hr. The residue was filtered, washed with water and recrystallised.

**3-Aryloxy/aryl methyl-4-aryl-5-mercapto-1,2,4-triazoles<sup>17</sup> (IV):** A mixture of aryloxy/aryl acetyl hydrazines (0.01 M) and aryl isothiocyanate (0.012 M) was refluxed in sodium hydroxide solu-


tion (20 ml, 8%) for 5 hr, cooled and poured into water. It was stirred and filtered. The filtrate on acidification yielded a solid which was filtered, washed and recrystallised from aqueous ethanol.

**Methyl-(3-aryloxymethyl-4-aryl-1,2,4-triazol-5-yl)-sulphides (V):** To a methanolic solution of 3-aryloxy methyl-4-aryl-5-mercapto-1,2,4-triazole (0.01 M), fused sodium acetate (2.0 g) and methyl iodide (0.01 M) were added. The contents were refluxed for 4 hr, cooled and poured into water. The solid separating out was filtered, washed and recrystallised.

TABLE 1—1-ARYLOXY/ARYL ACETYL-4-ARYL THIOSEMICARBAZIDES (I)

Compd. No.	R	R <sup>1</sup>	m.p. °C	Yield %	Fungicidal activity Conc. 10 ppm	
					<i>A. niger</i>	<i>H. oryzae</i>
1 <sup>a</sup>	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O-CH <sub>3</sub>	2-OCH <sub>3</sub>	180	94	24.4	25.1
2	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O-CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	174	98	18.7	21.3
3	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O-CH <sub>3</sub>	3,4-Cl <sub>2</sub>	190	85	27.1	27.9
4	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	2-OCH <sub>3</sub>	164	97	19.2	18.8
5	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	162	99	16.7	14.8
6	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-Cl <sub>2</sub>	172	72	21.6	23.4
7	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	2-OCH <sub>3</sub>	105	83	11.9	13.1
8	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	150	82	—	—
9	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-Cl <sub>2</sub>	140	76	14.4	16.8
10	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	2-OCH <sub>3</sub>	148	86	18.8	20.5
11	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	200	98	—	—
12 <sup>a</sup>	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-Cl <sub>2</sub>	150	74	22.4	24.1

IR spectral data  $\nu_{\max}$  in cm<sup>-1</sup>

		-CO.NH-	-C-O-C-	C-Cl	Orthodisubstituted benzene
a	1165	3400	1670	1060	760
b	1170	3400	1680	1225	Monosubstituted benzene
c	1175	3400	1655	1070	730
				1225	1,2,3,-Trisubstituted benzene

NMR spectral data

c Ar-H 2.1-3.2 $\tau$ , -CH<sub>3</sub>- 5.8 $\tau$ , -CH<sub>3</sub> 7.82 $\tau$ 

TABLE 2—2-ARYLAMINO-5-ARYLOXY/ARYL METHYL-1,3,4-OXADIAZOLES (II)

Compd. No.	R	R <sup>1</sup>	m.p. °C	Yield %	Fungicidal activity Conc. 10 ppm	
					<i>A. niger</i>	<i>H. oryzae</i>
13 <sup>d</sup>	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O-CH <sub>3</sub>	2-OCH <sub>3</sub>	171	54	33.9	35.7
14	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O-CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	194	70	22.8	27.8
15	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O-CH <sub>3</sub>	3,4-Cl <sub>2</sub>	145	51	36.7	39.1
16	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	2-OCH <sub>3</sub>	82	44	31.1	33.2
17	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	130	94	27.1	29.8
18	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-Cl <sub>2</sub>	179	76	32.0	35.1
19	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	2-OCH <sub>3</sub>	196	84	13.9	14.1
20	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	116	93	—	—
21 <sup>e</sup>	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-Cl <sub>2</sub>	125	83	16.8	16.9
22	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	2-OCH <sub>3</sub>	145	60	—	—
23	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	194	51	29.0	32.4
24	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-Cl <sub>2</sub>	155	54	35.2	38.0

IR spectral data  $\nu_{\max}$  in cm<sup>-1</sup>

	-C-O-C, C-O stretching	-NH	Conjugated cyclic -C=N	-C-O-C-	C-Cl
d	1115	3480	1570	1020	790
e	1110	3360	1570	1235	740
				1030	Monosubstituted benzene
				1250	720

TABLE 3—2-ARYLAMINO-5-ARYLOXY/ARYL METHYL-1,3,4-THIAZAZOLES (III)

Compd. No.	R	R <sup>1</sup>	m p. °C	Yield %	Fungicidal activity Conc 10 ppm	
					<i>A. niger</i>	<i>H. oryzae</i>
25	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O.CH <sub>3</sub>	2-OCH <sub>3</sub>	190 <sup>d</sup>	75	40.1	44.5
26	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O.CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	210	97	32.0	36.5
27 <sup>f</sup>	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>4</sub> -O.CH <sub>3</sub>	3,4-Cl <sub>2</sub>	218 <sup>d</sup>	98	45.8	48.2
28	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	200 <sup>d</sup>	90	30.5	34.1
29	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-Cl <sub>2</sub>	199 <sup>d</sup>	87	36.7	40.0
30	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	2-OCH <sub>3</sub>	252	97	15.2	16.1
31	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	200	95	—	—
32 <sup>g</sup>	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-Cl <sub>2</sub>	151	98	19.9	21.5
33	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	2-OCH <sub>3</sub>	208 <sup>d</sup>	57	—	—
34 <sup>h</sup>	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	221	95	32.2	35.0
35	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-Cl <sub>2</sub>	234 <sup>d</sup>	81	41.4	45.0
IR spectral data $\nu_{max}$ in cm <sup>-1</sup>						
	-NH	Conjugated cyclic -C = N-	-C=O-C-	C-Cl	1,2,3-Trisubstituted benzene	
f	3470	1605	1030 1250	750	—	
h	3440	1625	1035 1275	—	745	
NMR spectral data						
g	Ar-H 2.6-2.8 $\tau$ , -CH <sub>3</sub> - 5.8 $\tau$					

TABLE 4—3-ARYLOXY/ARYL METHYL-4-ARYL-5-MERCAPTO-1,2,4-TRIAZOLES (IV)

Compd. No.	R	R <sup>1</sup>	m.p. °C	Yield %	Fungicidal activity Conc 10 ppm		
					<i>A. niger</i>	<i>H. oryzae</i>	
36 <sup>d</sup>	4-Cl-3-CH <sub>3</sub> , C <sub>6</sub> H <sub>4</sub> -O CH <sub>3</sub>	2-OCH <sub>3</sub>	160	88	41.0	48.7	
37	4-Cl-3-CH <sub>3</sub> , C <sub>6</sub> H <sub>4</sub> -O CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	175	75	36.5	42.0	
38	4-Cl-3-CH <sub>3</sub> , C <sub>6</sub> H <sub>4</sub> -O CH <sub>3</sub>	3,4-Cl <sub>2</sub>	161	71	44.3	52.7	
39	2,4-(CH <sub>3</sub> ) <sub>2</sub> , C <sub>6</sub> H <sub>3</sub> -O CH <sub>3</sub>	2-OCH <sub>3</sub>	168	97	34.0	40.6	
40 <sup>d</sup>	2,4-(CH <sub>3</sub> ) <sub>2</sub> , C <sub>6</sub> H <sub>3</sub> -O CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	123	94	31.7	32.0	
41	2,4-(CH <sub>3</sub> ) <sub>2</sub> , C <sub>6</sub> H <sub>3</sub> -O CH <sub>3</sub>	3,4-Cl <sub>2</sub>	189	76	38.5	45.8	
42	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	2-OCH <sub>3</sub>	182	79	26.2	28.6	
43	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	110	78	—	—	
44 <sup>k</sup>	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-Cl <sub>2</sub>	154	67	28.7	36.0	
45	2,6-(CH <sub>3</sub> ) <sub>2</sub> , C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	2-OCH <sub>3</sub>	202	88	—	—	
46	2,6-(CH <sub>3</sub> ) <sub>2</sub> , C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	228	90	30.4	32.9	
47	2,6-(CH <sub>3</sub> ) <sub>2</sub> , C <sub>6</sub> H <sub>3</sub> -O-CH <sub>3</sub>	3,4-Cl <sub>2</sub>	222	67	37.8	44.2	
IR spectral data $\nu_{max}$ in cm <sup>-1</sup>							
	Secondary -NH	Conjugated cyclic -C=N-	-C=S	-C=O-C-	-SH	C-Cl	Orthodisubstituted benzene
i	3100	1600	1160	1040 1235	2580	690	750
j	3150	1500	1130	1035 1250	—	—	—
NMR spectral data							
k	Ar-H 2.6-3.0 $\tau$ , -CH <sub>3</sub> 5.8 $\tau$ , -SH 8.75 $\tau$						

Bis-(3-aryloxymethyl-4-aryl-1, 2, 4-triazol-5-yl)-disulphides (VI): To an ice cold methanolic solution of 3-aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazole (0.01 M), a cold methanolic solution of bromine (0.005 M) was added dropwise with swirling. It was kept as such for 2 hr and then evaporated. The residue obtained was washed successively with water, dilute sodium hydroxide and water and recrystallised.

Bis-(3-aryloxy/aryl methyl-4-aryl-1,2,4-triazol-5-yl)-alkylene disulphides (VII): A methanolic solution of 3-aryloxy/aryl-4-aryl-5-mercapto-1, 2, 4-triazole (0.01 M), methylene/ethylene dihalide (0.005 M) and fused sodium acetate (2.0 g) was refluxed gently for 1 hr, cooled and poured into water. The solid

obtained was filtered, washed and recrystallised from aqueous ethanol.

**Fungicidal screening:** The compounds were evaluated for their antifungal activity against *Aspergillus niger* and *Helminthosporium oryzae* by agar plate technique<sup>10, 11</sup> at three different concentrations viz., 1000, 100 and 10 ppm. Two commercial fungicides, BLITOX 50 WP and MEMCGE, were also tested under parallel conditions to compare the result. The number of replications in each case was three.

## Results and Discussion

The compounds screened possess moderate to fairly good antifungal activity against both the

TABLE 5—METHYL-(3-ARYLOXYMETHYL-4-ARYL-1,2,4-TRIAZOL-5-YL)-SULPHIDES (V)

Compd. No.	R	R <sup>1</sup>	m.p. °C	Yield %	Fungicidal activity Conc. 10 ppm	
					<i>A. niger</i>	<i>H. oryzae</i>
48	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	2-OCH <sub>3</sub>	63	86	39.8	42.7
49 <sup>l</sup>	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	Viscous liquid	67	—	—
50	2,6-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-Cl <sub>2</sub>	99	76	39.0	44.7
<i>Bis</i> -(3-Aryloxyethyl-4-aryl-1,2,4-Triazol-5-yl)-Disulphides (VI)						
51	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	2-OCH <sub>3</sub>	121	71	47.8	54.6
52 <sup>m</sup>	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	157	46	41.3	45.2
53	4-Cl-3-CH <sub>3</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-Cl <sub>2</sub>	160	50	50.6	56.9
<i>Bi</i> -(3-Aryloxy/Aryl Methyl-4-Aryl-1,2,5-Triazol-5-yl)-Alkylene Disulphides (VII)						
n = 1						
54 <sup>n</sup>	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	2-OCH <sub>3</sub>	169	91	44.0	46.8
55	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	109	91	36.5	38.7
56	2,4-(CH <sub>3</sub> ) <sub>2</sub> .C <sub>6</sub> H <sub>3</sub> -O.CH <sub>3</sub>	3,4-Cl <sub>2</sub>	205	85	48.5	53.3
n = 2						
57	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	2-OCH <sub>3</sub>	Semi solid	60	—	—
58	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-(CH <sub>3</sub> ) <sub>2</sub>	70	70	20.0	21.6
59	C <sub>6</sub> H <sub>5</sub> -CH <sub>3</sub>	3,4-Cl <sub>2</sub>	81	71	30.6	31.8
MEMEGE					83.4	75.8
BLITOX 50 WP					73.4	80.0
(Commercial fungicides)						
IR spectral data $\nu_{max}$ in cm <sup>-1</sup>						
	Conjugated cyclic -C=N-	-C-O-C-		1,2,3-Trisubstituted benzene		C-Cl
l	1480	1035		750		
		1265				
m	1480	1040		—		715
		1250				
n	1490	1040		Orthodisubstituted benzene		—
		1250		755		

fungi. In general, the presence of chlorine and/or methoxy group increases the antifungal activity of the compound. The thiadiazoles (III) are more active than the corresponding oxadiazoles (II) which are relatively more potent than the corresponding thiosemicarbazides (I). Further, the alkyl sulphides display nearly the same level of fungicidal activity as their parent triazoles whereas *bis*-triazolyl disulphides and *bis*-triazolyl methylene disulphides are better than their corresponding triazoles. The highest level of activity in each Table has been shown by compounds Nos 3, 15, 27, 38, 53 which contain 4-chloro-3-methylphenoxy and 3,4-dichlorophenyl moieties.

#### Acknowledgement

The authors thank Prof. R. P. Rastogi, Head, Chemistry Department, Gorakhpur University for the facilities. One of the authors (R. S. S.) is grateful to Board of Management, Y. D. Postgraduate College, Lakhimpur-Kheri for leave and to U. G. C., New Delhi for the award of a Teacher Fellowship.

#### References

- G. J. M. VANDER KERK, *Proc. Brit. Insect. Fungic. Conf.* (4th), 1967, 2, 562.
- R. B. PATHAK, (Miss) B. JAHAN and S. C. BAHEL, *J. Antibact. Antifung. Agents*, 1980, 8, 12.
- R. P. BHAMARIA, R. A. BELLARE and C. V. DELIWALA, *Indian J. Exp. Biol.*, 1968, 6, 62.
- ANIL K. SEN GUPTA, KAMALESH C. AGARWAL and M. MUSHTAQ, *Indian J. Chem.*, 1979, 17B, 184.
- D. GHIRAN, I. SCHWARTZ and I. SIMITI, *Pharmazie*, 1974, 22, 141; *Chem. Abs.*, 1975, 82, 43274c.
- J. J. PIALA and H. L. YALE, *U. S. Patent*, 3, 141, 022, 1964; *Chem. Abs.*, 1964, 61, 8317b.
- E. H. POMMER, H. HAGEN and H. FLEIZ, *Ger. Offen.*, 2, 526, 308, 1976; *Chem. Abs.*, 1977, 86, 140057z.
- F. RUSSO and M. SANTAGATI, *Farmaco Ed. Sci.*, 1976, 31, 41; *Chem. Abs.*, 1976, 84, 90090r.
- JOEL L. KIRKPATRICK, *U. S. Patent*, 4, 097, 263, 1978; *Chem. Abs.*, 1979, 90, 38928e.
- W. MAYER, B. BOEHNER and D. DAWES, *Ger. Offen.*, 2, 418, 363, 1974; *Chem. Abs.*, 1975, 82, 31328k.
- G. HEUBACH, B. SACHSE and H. BUERSTEL, *Ger. Offen.*, 2, 826, 760, 1980; *Chem. Abs.*, 1980, 92, 181200h.
- S. C. BENNUR, V. B. JIGAJINNI and V. V. BADIGER, *Rev. Roum. Chim.*, 1976, 21, 757; *Chem. Abs.*, 1976, 85, 94306j.
- M. A. WEBB and JOHN H. PARSONS, *Ger. Offen.*, 2, 653, 447, 1977; *Chem. Abs.*, 1977, 86, 117870w.
- C. R. MOLLER and V. BALIAH, *J. Amer. Chem. Soc.*, 1948, 70, 3853.
- K. C. JOSHI and A. B. SEN, *J. Sci. Food Agric.*, 1952, 11, 526.
- L. CLONT, *Bull. Sci. Fac. Chim. Ind. Bologna*, 1964, 22, 13; *Chem. Abs.*, 1964, 61, 4253e.
- B. K. PAUL and U. P. BASU, *J. Indian Chem. Soc.*, 1969, 46, 1121.
- J. G. HORSFALL, *Bot. Rev.*, 1945, 11, 357.
- U.S.D.A. Circular No. 198, 1931.



# Chemical Constituents of *Launaea nudicaulis*: C-13 Nuclear Magnetic Resonance Spectroscopy of Taraxasterenes and Pseudo-Taraxasterenes\*


P. L. MAJUMDER\* and (Miss) SWAPNA LAHA

Department of Chemistry, University College of Science, Calcutta-700 009

Manuscript received 13 July 1981, revised 4 February 1982, accepted 23 May 1982

Chemical investigation of *Launaea nudicaulis* yielded  $\beta$ -sitosterol, its acetate and taraxasterol.  $^{13}\text{C}$  NMR spectral analyses of taraxasteryl acetate (1b), pseudo-taraxasteryl acetate (1d) and  $3\beta$ -hydroxy-30-nor-taraxasteran-20-one (2) were made and the diagnostic features are discussed.

PROMPTED by the folk-lore associated with the medicinal properties<sup>1</sup> of *Launaea nudicaulis* (Compositae) we have made a systematic chemical investigation of the plant. This has resulted in the isolation of a triterpenoid and two steroidal constituents, which are identified as taraxasterol,  $\beta$ -sitosterol and its O-acetyl derivative, respectively. The identification is based on their physical constants, spectral data and comparison with authentic samples. In view of a number of recent publications<sup>2-5</sup> on  $^{13}\text{C}$  nmr spectral studies on several triterpenoid systems, viz.,  $\alpha$ - and  $\beta$ -amyryns<sup>2,3</sup>, 18,19-oleanenes<sup>4</sup>, lupanes<sup>5</sup> and hopanes<sup>5</sup>, the isolation of taraxasterol from *L. nudicaulis* in fairly good yield prompted us to carry out detailed  $^{13}\text{C}$  nmr spectral analyses of the triterpenoids of taraxasterene and pseudo-taraxasterene types. The present communication while briefly reporting the isolation of the chemical constituents of *L. nudicaulis*, primarily concerns with the results of the  $^{13}\text{C}$  nmr spectral analyses.



The compounds studied for the purpose are the acetyl derivatives of taraxasterol (1a) and pseudo-taraxasterol (1c) and the norketone (2). Pseudo-taraxasteryl acetate (1d) was obtained by treatment of taraxasterol with sulphuric acid followed by acetylation of the product, while the norketone was prepared by the action of  $\text{OsO}_4$  on taraxasteryl

acetate (1b) followed by periodate oxidation of the resultant 3,20,30-triol. The assignments of the carbon chemical shifts of 1b, 1d and 2 (Table 1) were based on off-resonance decoupling technique indicating substitution profile of carbon centres, functionality manipulation causing predictable shift variations, and comparison with the carbon chemical shifts of appropriate diterpenes<sup>6</sup> (for rings A and B) and triterpenoids<sup>2-5</sup>, viz.,  $\alpha$ - and  $\beta$ -amyryns<sup>2,3</sup> (for rings A and B), lupanes<sup>5</sup> and hopanes<sup>5</sup> (for rings A, B, C and part of D), having some commonness in the carbocyclic systems.

Comparison of the carbon chemical shifts of 1b, 1d and 2 with those of other triterpenoid systems has revealed several distinguishing features. Except the carbon atoms of rings A and B, the carbon chemical shifts of these compounds show practically very little resemblance to those of  $\alpha$ - and  $\beta$ -amyryns. This is primarily due to removal of the 12,13-double bond of the amyryns, introduction of the C/D-*trans*, a change over from D/E-*cis* to D/E-*trans* stereochemistry and the structural modification of ring E. This is reflected in the change of chemical shift of C-9 (upfield shift by  $\sim 3$  ppm) and carbons of C, D and E rings. The most significant is the extraordinary 9-11 ppm shielding of C-27, a characteristic feature also observed in 18,19-oleanenes, the lupanes<sup>5</sup> and the hopanes<sup>5</sup>. While in 18,19-oleanenes this upfield shift of C-27 is due to the removal of  $\delta$ -effect by C-19 and addition of a  $\gamma$ -effect by C-12, in the case of 1b, 1d and 2 as well as in lupanes and hopanes this may be attributed to the addition of a  $\gamma$ -effect by C-18 and the enhancement of  $\gamma$ -effect by C-12. In fact, the carbon chemical shifts of the compounds under investigation exhibit close resemblance to those of lupanes except C-17 and most of the ring E carbon atoms. The most striking is the chemical shift of C-17 which is shielded by  $\sim 8.5$  ppm compared to the lupanes. This may be attributed to the changed shielding parameters caused by the

\* A preliminary account of this work was presented in the "Symposium on Recent Trends in Organic Chemistry", Department of Pure Chemistry, University of Calcutta, 1979, Abstracts of Papers, P. 17, p.37.

replacement of the *trans*-hydrindane system (rings D and E) of lupanes by *trans*-decalin moiety in 1b (*trans*-octalin and a *trans*-decalone system in 1d and 2, respectively).

new members of the pentacyclic triterpenoids of the taraxasterane and pseudo-taraxasterane types.

### Experimental

**Isolation of 1a:** Air-dried powdered whole plant (1 Kg) of *L. nudicaulis* was successively extracted with petroleum ether (60-80°),  $\text{CHCl}_3$  and MeOH. Concentration of petrol extract deposited a white solid (yield 0.06%) which was filtered. The crude solid, on repeated crystallisation from MeOH- $\text{CHCl}_3$  (9 : 1) mixture, gave pure 1a, m.p. 221°,  $[\alpha]_D^{25} + 95.6^\circ$  ( $\text{CHCl}_3$ ); acetate (1b), m.p. 239-40°. The filtrate was chromatographed over silica gel using petrol and petrol-EtOAc mixture as eluents. The petrol-EtOAc (20 : 1) eluate on evaporation yielded a further quantity (0.15 g) of 1a. The petrol-EtOAc (10:1) eluate gave  $\beta$ -sitosterol acetate (yield 0.007%), m.p. 121°, crystallised also from MeOH- $\text{CHCl}_3$  mixture. Further washing the column with petrol-EtOAc (5 : 1) gave  $\beta$ -sitosterol (yield 0.01%), m.p. 136°; acetate, m.p. 121° (identical with the natural product). Chromatography of  $\text{CHCl}_3$  and MeOH extract furnished only traces of 1a and  $\beta$ -sitosterol.

**Isomerisation of 1a to 1c and acetylation of 1c to 1d:** 1a (0.2 g) was dissolved in a mixture of 10% ethanolic  $\text{H}_2\text{SO}_4$  (10 ml) and benzene (10 ml) and refluxed for 5 hr for the double bond isomerisation as reported<sup>7,8</sup> earlier. Solvent was removed under reduced pressure and the residue was diluted with water, extracted with ether, dried and evaporated. Repeated crystallisation of this solid (0.19 g) from MeOH- $\text{CHCl}_3$  gave pure 1c, m.p. 196°;  $M^+ 426$ ;  $\delta_{\text{CDCl}_3}^{13\text{C}}$  1.60, 3H, s and 5.18, 1H, m ( $\text{Me}-\text{C}=\text{CH}-\text{CH}_2-$ ). 1c was acetylated with  $\text{Ac}_2\text{O}/\text{Py}$  in the usual manner to give 1d, crystallised from MeOH- $\text{CHCl}_3$ , m.p. 228°,  $[\alpha]_D^{25} + 51.8^\circ$  ( $\text{CHCl}_3$ );  $\nu_{\text{max}}^{1735}$  and  $1250$  ( $\text{OAc}$ )  $\text{cm}^{-1}$ .

**Conversion of 1b to 2:** Following the method reported<sup>7</sup> earlier for structurally similar compound, 1b (1.9 g) dissolved in a mixture (1 : 1) of dry pyridine and  $\text{CHCl}_3$  (100 ml) was treated<sup>7</sup> with  $\text{OsO}_4$  (1 g) and the solution was kept at 20° for 7 days. The solvent was removed under reduced pressure and the dark brown mass was treated<sup>7</sup> with benzene (45 ml), MeOH (45 ml) and a mixture of KOH (10.5 g) and mannitol (10.5 g) in EtOH (45 ml) and water (28 ml), and refluxed for 3 hr. Removal of solvent under reduced pressure left a residue which was diluted with water, extracted with ether and dried. The ether extract, on evaporation, gave a solid which was chromatographed over silica gel. The petrol-EtOAc (1 : 1) eluate gave a crude mass of triol (0.75 g) which was dissolved in EtOH (320 ml) and treated<sup>7</sup> with a solution of sodium *meta*-periodate (0.55 g) in water (5 ml). The mixture was kept at 20° for 16 hr. EtOH was removed under reduced pressure and the residue was diluted with water, extracted with ether, dried and evaporated. The solid (0.47 g), on repeated crystallisation from petrol-EtOAc, gave pure 2, m.p. 260°. (Found: C, 81.2; H, 11.24.  $\text{C}_{30}\text{H}_{48}\text{O}_2$  requires C, 81.30; H, 11.21%).  $\delta_{\text{HCl}_3}^{13\text{C}}$  3380 (OH) and 1700

TABLE 1—CARBON CHEMICAL SHIFT<sup>a</sup> OF 1b, 1d AND 2

	1b	1d	2
C-1	38.7	38.4	38.7
C-2	23.5	23.6	27.3
C-3	80.7	80.8	78.8
C-4	37.6 <sup>b</sup>	37.7 <sup>b</sup>	38.9 <sup>b</sup>
C-5	55.3	55.3	55.3
C-6	18.0	18.1	18.2
C-7	33.8	34.2	33.9
C-8	40.7	41.0	40.8
C-9	50.2	50.2	50.3
C-10	36.9 <sup>b</sup>	36.9 <sup>b</sup>	37.0 <sup>b</sup>
C-11	21.3	21.5	21.1
C-12	25.4 <sup>c</sup>	26.9 <sup>c</sup>	25.6 <sup>c</sup>
C-13	38.3	39.1	37.5
C-14	41.8	42.1	41.7
C-15	26.5 <sup>c</sup>	27.5 <sup>c</sup>	26.5 <sup>c</sup>
C-16	39.2 <sup>d</sup>	36.2	36.0
C-17	34.3	34.1	34.1
C-18	48.5	48.6	49.8
C-19	38.2	42.2	46.0
C-20	154.2 <sup>e</sup>	139.6	218.0
C-21	25.3 <sup>e</sup>	118.8	33.1
C-22	39.0 <sup>d</sup>	36.6	36.3
C-23	27.7	27.8	27.9
C-24	16.1 <sup>e</sup>	16.2 <sup>d</sup>	16.8 <sup>d</sup>
C-25	15.7 <sup>e</sup>	15.9 <sup>d</sup>	15.8 <sup>d</sup>
C-26	16.1 <sup>e</sup>	16.2 <sup>d</sup>	16.2 <sup>d</sup>
C-27	14.5	14.6	14.5
C-28	25.0	21.6	21.8
C-29	19.3	17.6	15.3
C-30	107.0	22.4	
-OCOCH <sub>3</sub> <sup>f</sup>	170.5	170.6	
-OCOCH <sub>3</sub>	21.0	21.3	

<sup>a</sup>The  $\delta$  values are in ppm downfield from TMS ;  $\delta(\text{TMS}) = \delta(\text{CDCl}_3) + 76.9$  ppm.

b, c, d, e, f Values bearing the same superscript may be interchanged.

Other differences in the chemical shifts of the carbon sites of ring E between these compounds and the lupanes are in conformity with the structural variations of this part of their molecules. The chemical shift assignments for C-29 and C-28 in 1b are supported by functionality manipulation. Thus, replacement of the exocyclic methylene of 1b by a C-20 carbonyl function (as in 2), and the isomerisation of the 20,30-double bond to 20,21-position (1d) affect the chemical shifts of both C-29 and C-28, the latter then approaching the value of the corresponding carbon in the lupanes. The reverse assignments for these carbon sites in 1b would demand an improbable upfield shift (~10 ppm) of C-29 in 2. Furthermore, in view of the existence of a severe steric interaction<sup>7</sup> between the 29-methyl and the 12-methylene groups, the assigned chemical shift of C-29 appears more logical than otherwise. The differences in the carbon chemical shifts of 1b and 1d are only formal and are in accord with those expected from double bond isomerisation.

The results of these spectral analyses thus disclosed diagnostic features which would provide a method for future  $^{13}\text{C}$  nmr spectral recognition of

$(>C=O) \text{ cm}^{-1}$ ;  $\delta_{\text{CDCl}_3}^{\text{H}}$  3.15, 1H, m ( $-CH-OH$ ),  
 $\delta_{\text{CDCl}_3}^{\text{C}}$  2.40, 3H, m ( $\text{Me}-CH-C(=O)-CH_2-CH_2-$ ), 1.1, 3H,  
d, J 7 Hz ( $\text{Me}-CH-C(=O)-$ ), 0.71-1.0 ( $6-C-CH_3$ );  
m/e (relative abundance): 428 ( $M^+$ , 17.5), 410 (63.5), 395 (40.9), 367 (25.1), 341 (10.7), 328 (29.3), 259 (10.8), 207 (41), 189 (100), 136 (77.8), 135 (76.3), 123 (60.6), 121 (64.7), 109 (55.5), 95 (77.9), 81 (65.9), 69 (61.8), 55 (55.3) and 43 (45.7).

#### Acknowledgement

The authors are thankful to Dr. B. C. Das, Institut de Chimie des Substances Naturelles, C. N. R. S., Gif-Sur-Yvette, France, and Dr. G. F. Smith, The University of Manchester, U. K. for the mass spectra. The work was supported by U. G. C., New Delhi.

#### References

1. R. N. CHOPRA, S. L. NAYAR and I. C. CHOPRA, "Glossary of Indian Medicinal Plants", C.S.I.R., New Delhi, 1956.
2. S. A. KNIGHT, *Org. Magn. Reson.*, 1974, 6, 603, and references therein.
3. S. SEO, Y. TOMITA and K. TORI, *J. Chem. Soc., Chem. Commun.*, 1975, 954, and references therein.
4. P. L. MAJUMDER, R. N. MAITI, S. K. PANDA, D. MAL, M. S. RAJU and E. WENKERT, *J. Org. Chem.*, 1979, 44, 2811.
5. E. WENKERT, G. V. BADDELEY, I. R. BURFITT and L. N. MORENO, *Org. Magn. Reson.*, 1978, 11, 337.
- 6.a) E. WENKERT, B. L. BUCKWALTER, I. R. BURFITT, M. J. GAS'IC, H. E. GOTTLIEB, E. W. HAGAMAN, F. M. SCHELL and P. M. WOVKULICH, in "Topics in Carbon-13 NMR Spectroscopy", (Ed.) G. C. LEVY, Wiley-Interscience, New York, 1976, Vol. 2, p. 81, and references therein.
- b) B. L. BUCKWALTER, I. R. BURFITT, A. A. NAGEL, E. WENKERT and F. NÄF, *Helv. Chim. Acta*, 1975, 58, 1567.
7. T. R. AMES, J. L. BETON, A. BOWERS, T. G. HALSBALL and E. R. H. JONES, *J. Chem. Soc.*, 1954, 1905.
8. G. LARDELLI, Hs. K. KRÜSI, O. JEGGER and L. RUZICKA, *Helv. Chim. Acta*, 1948, 31, 1815.

# Study of Saponins from *Albizzia lebbek* Benth Flowers

I. P. VARSHNEY and D. C. JAIN

Department of Chemistry, University of Garhwal, Srinagar-Garhwal-246 174

and

H C SRIVASTAVA

Chemistry Division, Ahmedabad Textile Industry's Research Association, Ahmedabad-380 015

Manuscript received 27 January 1981, accepted 24 March 1982

*Albizzia lebbek* Benth flowers yield a number of saponins named as lebbekanin-D, F, G and H. They are all glycosides of echinocystic acid with varying sugars. On the basis of enzymatic, partial alkaline hydrolysis, methylation and periodate oxidation studies, partial structures have been assigned to these saponins.

*ALBIZZIA lebbek* Benth commonly known as *Siris* belongs to the family Leguminosae. Varshney *et al.*<sup>1-6</sup> have studied various parts of this tree and isolated eight new saponins named as lebbekanin A, B, C, D, E, F, G and H. The present paper describes the study of lebbekanin D, F, G and H, isolated from the flowers of this plant.

Air dried flowers, after defatting with light petroleum ether, were exhaustively extracted with ethanol. The ethanol extract on concentration and usual treatment<sup>1</sup> yielded a light brown substance which gave all the tests for triterpenic saponins.

The crude saponin was then separated into 4 pure saponins, lebbekanin D, F, G and H by repeated column chromatography on silica gel, lebbekanin D being the major part of the mixture.

**Study of lebbekanin D:** Lebbekanin D, m.p. 217-18°,  $[\alpha]_D^{25} -27.5^\circ$  (MeOH, c, 1%),  $R_f$  0.350 (chloroform : methanol : water 65 : 40 : 10), on acid hydrolysis with 2N aqueous sulphuric acid gave echinocystic acid (3 $\beta$ ,16  $\alpha$ -dihydroxy olean-12-ene-28 oic acid) (20.1%), and a mixture of five sugars, glucose, galactose, arabinose, xylose and rhamnose in the molar ratio 2 : 2 : 5 : 3 : 3.



Lebbekanin D on alkaline hydrolysis with 5% methanolic potassium hydroxide solution gave a prosapogenin-D<sub>1</sub> and an oligosaccharide-D<sub>1</sub> indicating the presence of ester linkage in the lebbekanin D (i.e. attachment of sugars at C-28 COOH group also). The attachment of sugars at C-16 OH group is not possible due to its strongly hindered position showing thereby that all the sugars are attached at C-3 OH and C-28 COOH groups. The oligosaccharide-D<sub>1</sub> on complete hydrolysis gave glucose, galactose and rhamnose in the molar ratio 1 : 1 : 3. The prosapogenin-D<sub>1</sub> on complete hydrolysis with 2N aqueous sulphuric acid gave four sugars, glucose, galactose, arabinose and xylose in the molar ratio 1 : 1 : 5 : 3 and echinocystic acid as genin.

Lebbekanin-D on mild alkaline hydrolysis with 2% methanolic KOH gave prosapogenin-D<sub>2</sub> and oligosaccharide-D<sub>2</sub>. Prosapogenin-D<sub>2</sub> on complete hydrolysis with 2N aqueous sulphuric acid gave same four sugars glucose, galactose, arabinose and xylose and a neutral genin, m.p. 210-13°,  $[\alpha]_D^{25} +36.9^\circ$  (EtOH, c, 1%),  $R_f$  0.726, in place of echinocystic acid, m.p. 308-8°,  $R_f$  0.414 (benzene : acetone 6 : 1) isolated by the hydrolysis of prosapogenin D<sub>1</sub>. Oligosaccharide D<sub>2</sub> on complete hydrolysis gave the same three sugars i.e., glucose, galactose and rhamnose.

The neutral genin thus obtained (m.p. 210-13°) gave positive tests for triterpenic sapogenins and a double bond. The spectral studies [ $IR_{max}^{KBr}$  : 1700-1720  $cm^{-1}$  (s) (COOCH<sub>3</sub>); nmr (CDCl<sub>3</sub>) : 3.8 (s) (3H; COOCH<sub>3</sub>), 5.5 (s) (1H; olefinic), 4.6 (s) (2H; OH)] showed it to be methyl ester of echinocystic acid. The above spectral data tally with the reported data<sup>9</sup> of methyl ester of echinocystic acid. The identity was also confirmed by co-tlc and m.m.p. with an authentic sample of the ester.

This led to the conclusion that glucose, galactose and rhamnose (1 : 1 : 3) are attached to C-28 COOH group as ester and when lebbekanin D is reacted with 2% methanolic KOH the sugars from the C-28 COOH group are knocked out and methyl group from methanol gets attached to COOH at C-28, giving methyl ester of echinocystic acid as neutral genin.

One strange thing is noted. When hydrolysis of lebbekanin-D is carried out with 5% methanolic KOH no methylation takes place at C-28 COOH group or if it takes place, the methyl group is knocked out by the strong concentration of KOH in alkaline hydrolysis and a potassium salt of echinocystic acid is formed. The 2% methanolic KOH, on the contrary, is not sufficient to remove the methyl group and formation of potassium salt of echinocystic acid is not possible (Fig. 1).



Prosapogenin-D<sub>1</sub> and oligosaccharide D<sub>1</sub>, obtained on 5% methanolic KOH hydrolysis were separated and their methylation, partial hydrolysis, enzymatic hydrolysis, periodate oxidation were carried out.

**Study of prosapogenin-D<sub>1</sub>:** Prosapogenin-D<sub>1</sub>, m.p. 205-8°,  $[\alpha]_D^{25}$  -24.3° (meOH c, 1%), R<sub>f</sub> 0.46 (chloroform, methanol : water 65 : 40 : 10), on acid hydrolysis with 2N aqueous sulphuric acid gave echinocystic acid and a mixture of four sugars, glucose, galactose, arabinose and xylose in molar ratio 1 : 1 : 5 : 3.

In order to find out the attachment and sequence of the sugars, prosapogenin-D<sub>1</sub> was methylated by Hakomori's method<sup>10</sup> followed by two Purdie methylation<sup>11</sup> in order to ensure complete methylation (checked by ir spectra). Fully methylated prosapogenin was subjected to methanolysis with 3% methanolic hydrogen chloride. The resulting methylglycoside of methylated sugars obtained were identified by glc on 8% OS-138 on chromosorb W column (NAW), relative retention times were determined taking methyl 2,3,4,6-tetra-O-Methyl  $\alpha$ -D glycosides as reference. Following methylglycosides of methylated sugars were tentatively identified :

- (i) Methyl-2,3,4-tri-O-methyl- $\beta$ -D-xyloside.
- (ii) Methyl-2,3,5-tri-O-methyl- $\alpha$ -L-arabinoside.
- (iii) Methyl-3,4-di-O-methyl- $\beta$ -D xyloside.
- (iv) Methyl-2,3,4,6-tetra-O-methyl- $\alpha$ -D-glucoside.
- (v) Methyl-3-O-methyl- $\alpha$ -L-arabinoside.
- (vi) Methyl-2-O-methyl- $\alpha$ -L-arabinoside.
- (vii) Methyl-2,3,6-tri-O-methyl- $\alpha$ -D-galactoside.

Prosapogenin-D<sub>1</sub> on partial hydrolysis with 0.1N aqueous sulphuric acid on water bath for 1 hr gave three sugars, glucose, arabinose and xylose but galactose was not liberated. This showed the back bone position of galactose. On partial hydrolysis for 1 hr three sugars, glucose, arabinose and xylose

were liberated. This indicates that these sugars were linked through weak linkages or had a terminal position in the sugar chain. Presence of methyl ethers of arabinose in methyl sugars shows that the branching is taking place through these molecule.

Prosapogenin-D<sub>1</sub> was treated with NaIO<sub>4</sub> (0.5M), oxidised prosapogenin was extracted with *n*-butanol and was hydrolysed. The hydrolysate showed the presence of only arabinose. It confirms that branching is taking place through arabinose and also support the methylation results.

**Study of oligosaccharide D<sub>1</sub>:** Oligosaccharide D<sub>1</sub> was completely methylated by Hakomori's method followed by one Purdie methylation. Complete methylation was checked by ir spectra. Methylated oligosaccharide was subjected to methanolysis in the usual manner. The methyl glycosides of methylated sugars obtained were identified by glc under similar conditions. Following methylglycosides of different methyl sugars were identified :

- (i) Methyl-2,3,4-tri-O-methyl- $\alpha$ -L-rhamnoside.
- (ii) Methyl-3,4-di-O-methyl- $\alpha$ -L-rhamnoside.
- (iii) Methyl-2,3,6-tri-O-methyl- $\alpha$ -D-glucoside.
- (iv) Methyl-2,3-di-O-methyl- $\alpha$ -D-galactoside.

Methylation results showed that the two rhamnose molecules have terminal positions whereas glucose, galactose and one rhamnose are present in the back bone position. Branching is taking place through galactose molecule as it comes as 2,3-di-O-methyl- $\alpha$ -D-galactose.

Enzymatic hydrolysis of lebbekanin-D with  $\beta$ -glucosidase did not liberate any sugar indicating the absence of  $\beta$ -glycosidic linkage in the glucose molecule.

Since the attachment of sugars at C-16 OH group is not possible due to its strongly hindered position, the only possibility that remains is of C-3 OH group

which is the usual position for the attachment of sugars in the case of triterpenic saponins. Thus, lebbekinin-D has two sugar chains, one attached to the C-28 COOH group and other at the C-3 OH group.

On the basis of above results partial structure of lebbekinin-D may be assigned as structure (I).

**Study of lebbekinin-F:** Lebbekinin F, m.p. 204-5°,  $[\alpha]_D^{40}$  (MeOH c, 1%),  $R_f$  0.453, on acid hydrolysis with 2N aqueous sulphuric acid gave an acid genin (24.5%). It has been identified as echinocystic acid by direct comparison.

The hydrolysate obtained was neutralized and deionised and on paper chromatography showed the presence of five sugars identified as glucose, arabinose, xylose, fucose and rhamnose present in the molar ratio 2 : 2 : 2 : 1 : 3.

Lebbekinin-F on alkaline hydrolysis with 5% methanolic/KOH on boiling water bath gave prosapogenin-F and oligosaccharide-F, indicating the presence of ester linkage in saponin i.e. attachment of sugars at C-28 COOH group.

Oligosaccharide-F on complete hydrolysis gave three sugars identified as glucose, xylose and rhamnose. Prosapogenin-F on complete hydrolysis gave five sugars glucose arabinose, xylose, fucose and rhamnose.

Lebbekinin-F on partial hydrolysis with 0.1N sulphuric acid for 1 hr gave four sugars, glucose, arabinose, xylose and rhamnose only. On enzymatic hydrolysis with  $\beta$ -glucosidase, it did not liberate any sugar indicating the absence of  $\beta$ -linkage.

Since the attachment of sugar at C-16 OH groups is not possible due to its strongly hindered position, all the sugars are attached at C-3 OH and C-28 COOH groups.

On the basis of above results lebbekinin-F has been assigned structure (II).




Fig. 2

- (I)  $R + R' = \text{Glu} : \text{gal} : \text{ara} : \text{xyl} : \text{rha}.$  (2 : 2 : 5 : 3 : 3)  
 $R = \text{Glu} : \text{gal} : \text{ara} : \text{xyl}$  (1 : 1 : 5 : 3)  
 $R' = \text{Glu} : \text{gal} : \text{rha}$  (1 : 1 : 3)
- (II)  $R + R' = \text{Glu} : \text{ara} : \text{xyl} : \text{fuc} : \text{rha}.$  (2 : 2 : 2 : 1 : 3)  
 $R = \text{Glu} : \text{ara} : \text{xyl} : \text{fuc} : \text{rha}$   
 $R' = \text{Glu} : \text{xyl} : \text{rha}.$
- (III)  $R + R' = \text{Glu} : \text{ara} : \text{xyl} : \text{fuc} : \text{rha}.$  (3 : 2 : 2 : 2 : 3)  
 $R = \text{Glu} : \text{ara} : \text{xyl} : \text{fuc} : \text{rha}$   
 $R' = \text{Glu} : \text{xyl} : \text{rha}.$
- (IV)  $R + R' = \text{Glu} : \text{gal} : \text{ara} : \text{xyl} : \text{rha}.$  (4 : 2 : 3 : 3 : 3)  
 $R = \text{Glu} : \text{gal} : \text{ara} : \text{xyl}$   
 $R' = \text{Glu} : \text{gal} : \text{rha}.$

**Study of lebbekinin-G:** Lebbekinin-G, m.p. 210-12°,  $[\alpha]_D^{38.5}$  (MeOH c, 1%),  $R_f$  0.390, on acid hydrolysis with 2N  $\text{H}_2\text{SO}_4$  gave an acid genin (18%) which was identified as echinocystic acid and five sugars glucose, arabinose, xylose, fucose and rhamnose present in the molar ratio 3 : 2 : 2 : 2 : 3.

Lebbekinin-G on alkaline hydrolysis with 5% methanolic KOH gave prosapogenin-G and oligosaccharide-G indicating the presence of ester linkage i.e. attachment of sugars at C-28 COOH group.

Oligosaccharide-G on complete hydrolysis gave three sugars glucose, xylose and rhamnose. Prosapogenin-G on complete hydrolysis gave five sugars, glucose, arabinose, xylose, fucose and rhamnose.

Lebbekinin-G on partial hydrolysis with 0.1N  $\text{H}_2\text{SO}_4$  gave glucose and rhamnose after 1 hr and glucose, arabinose, xylose and rhamnose after 2 hr while on enzymatic hydrolysis with  $\beta$ -glucosidase, did not liberate any sugar indicating the absence of  $\beta$ -linkage.

On the basis of above results lebbekinin-G has been assigned the structure (III).

**Study of lebbekinin H:** Lebbekinin-H, m.p. 220-22°,  $[\alpha]_D^{27.13}$  (MeOH c, 1%),  $R_f$  0.324, on acid hydrolysis with 2N  $\text{H}_2\text{SO}_4$  gave an acid genin (15.5%) identified as echinocystic acid and five sugars glucose, galactose, arabinose, xylose and rhamnose, present in the molar ratio 4 : 2 : 3 : 3 : 3.

Lebbekinin-H on alkaline hydrolysis with 5% methanolic KOH gave prosapogenin-H and oligosaccharide-H showing the presence of ester linkage in saponin i.e. attachment of sugars at C-28 COOH group.

Prosapogenin-H on complete hydrolysis gave four sugars glucose, galactose, arabinose and xylose while oligosaccharide-G gave three sugars glucose, galactose and rhamnose

Lebbekinin-H on partial hydrolysis with 0.1N  $\text{H}_2\text{SO}_4$  gave glucose and rhamnose after 1 hr. On enzymatic hydrolysis with  $\beta$ -glucosidase no sugar was liberated showing the absence of  $\beta$ -linkage.

On the basis of above results lebbekinin-H has been assigned the structure (IV)

#### Acknowledgement

Thanks of the authors are due to the Council of Scientific and Industrial Research, New Delhi for the award of a Senior Research Fellowship to one of them (D. C. J.).

#### References

1. I. P. VARSHNEY, *Indian J. Chem.*, 1969, 7, 446.
2. I. P. VARSHNEY, G. BADHWAR, H. C. SRIVASTAVA and T. N. KRISHNAMURTHY, *Planta Medica*, 1973, 24, 183.

**VARSHNEY, JAIN & SRIVASTAVA ; STUDY OF SAPONINS FROM *Albizia Lebbek* BENTH FLOWERS**

- I. P. VARSHNEY, G. HANDA (NEE' BADHWAR), H. C. SRIVASTAVA and T. N. KRISHNAMURTHY, *Indian J. Chem.*, 1973, 11, 1094.
- I. P. VARSHNEY and G. HANDA, (unpublished), Ph.D. thesis of Greta Handa, University of Indore, 1971.
- I. P. VARSHNEY, G. BADHWAR and RAJPAL, *J. Indian Chem. Soc.*, 1975, 52, 1202.
- I. P. VARSHNEY and M. S. Y. KHAN, *Cand. J. Chem.*, 1961, 39, 1721.
7. I. P. VARSHNEY, RAJPAL and P. VYAS, *J. Indian Chem. Soc.*, 1976, 53, 859.
8. I. P. VARSHNEY and D. C. JAIN, *Indian J. Chem.*, 1978, 16B, 1131.
9. G. K. JAIN, J. P. S. SARIN and N. M. KHANNA, *Indian J. Chem.*, 1977, 15B, 1139.
10. S. HAKOMORI, *J. Biochem. (Tokyo)*, 1964, 55, 205.
11. T. PURDIE and J. C. IRVINE, *J. Chem. Soc.*, 1903, 1021.

# A New Reagent System for Photometric Analysis of Selenium in Complex Materials

(Miss) A. BHATT and V. K. GUPTA\*

Department of Chemistry, Ravishankar University, Raipur-492 010

Manuscript received 22 June 1981, revised 11 December 1981, accepted 28 April 1982

A new reagent system consisting of 4-nitrophenyl hydrazine and 8-quinolinol is described for the photometric determination of selenium. 4-Nitrophenyl hydrazine is oxidised with selenious acid in 6 *M* hydrochloric acid to 4-nitrophenyl-diazonium chloride which is then coupled with 8-quinolinol to form an 'azoxine' dye. The dye gives intense purple colour in alkaline medium with an absorption maxima at 550 nm. The colour system obeys Beer's law in the range of 7-45  $\mu\text{g}$  Se/25 ml. The molar absorptivity and Sandell's sensitivity are  $3.2 \times 10^4 \text{ l. mole}^{-1} \text{ cm}^{-1}$  and  $0.0025 \mu\text{g/cm}^2$  respectively. The optimum reaction conditions and other analytical parameters are evaluated. The effect of various ions is discussed. The method is applied for detection and determination of selenium in complex materials such as cabbage leaf and cigarette paper.

**SELENIUM** and its compounds are of wide occurrence and known for their toxicity<sup>1</sup>. Selenium may be inhaled as fumes, dust or absorbed through skin and gastrointestinal tract. When taken into body, it is rapidly absorbed in blood and gets accumulated in lower kidney and muscle tissue. Several reports list selenium as a carcinogen<sup>2,3</sup>. Intoxication due to increased dietary intake of selenium has been reported to cause bad teeth, jaundice, chloasma, vertigo, chronic gastrointestinal disorder, dermatitis, hair loss, fatigue, etc<sup>4</sup>. Intake of selenium bearing plants causes chronic selenosis. It has been found that cruciferous plants accumulate much more selenium than other vegetables<sup>5</sup>. Selenium is also reported to be present in cigarette paper and tobacco<sup>6-8</sup>. These materials are largely consumed. Hence, sensitive methods are required for analysis of selenium in these materials.

Several analytical methods have been proposed for determination of selenium and they have been nicely reviewed<sup>9-11</sup>. Most popular spectrophotometric methods for determination of selenium are based on preparing sol of selenium and subsequent measurement of absorbance of the colloidal solution. Different reducing agents and stabilising agents have been proposed<sup>12</sup>. The methods are less sensitive and less specific. Other methods are based on the formation of complexes with *o*-diamines which form coloured or fluorescent selenol with selenious acid<sup>13,14</sup>. These methods lack sensitivity and selectivity. Some other methods make use of oxidising property of selenious acid<sup>15</sup>. The present investigation is based on oxidation of 4-nitrophenyl hydrazine to 4-nitrophenyl diazonium chloride with selenious acid in strong hydrochloric acid which is then coupled with 8-quinolinol in alkaline medium. The violet coloured dye is measured photometrically at 550 nm. The optimum reaction conditions and

other analytical parameters are evaluated. The method has been successfully used for the analysis of selenium in cigarette paper and cabbage leaves.

## Experimental

**Apparatus and reagents :** All spectrophotometric measurements were done at ECIL spectrophotometer model GS-865 and Carl Zeiss Spekol using 1 cm matched silica cells. An ECIL pH meter model 821 was used for pH measurements. A thermostated water bath was used for maintaining constant temperature.

The stock solution of selenium (1 mg/ml) was prepared by dissolving 0.22 g of sodium selenite in 100 ml distilled water. Working standards were prepared by appropriate dilution. 0.02% solution of 4-nitrophenyl hydrazine (4-NPH) in water and 0.2% solution of 8-quinolinol in 90% ethanol were used.

**Procedure :** An aliquot of sample solution (not more than 4 ml) containing 7-45  $\mu\text{g}$  of selenium was transferred to a test tube. To it was added 1 ml of 4-NPH and the acidity was maintained around 6*M*. The test tube was kept at  $60 \pm 2^\circ$  for 15 min in the thermostated water bath and the contents were transferred to a 50 ml beaker. To it was added 1 ml of the 8-quinolinol solution, 1 ml of 10% solution of disodium EDTA and 1 ml of 10% solution of sodium potassium tartrate and mixed well. The mixed solution was made alkaline by adding 5*M* sodium hydroxide solution drop by drop, cooling it simultaneously to  $25^\circ$  to prevent the decomposition of the dye by the heat produced during neutralisation. The violet dye was transferred into a 25 ml volumetric flask and diluted to the mark with distilled water. The absorbance of this solu-

\* Author for correspondence.




was measured at 550 nm and the amount of selenium was calculated from a calibration curve.

**Preparation of sample solution:** Into a 100 ml dahl flask 1 g of dried crushed cabbage leaf/rette paper from 5 cigarettes was taken and to it was added 15 ml concentrated nitric acid. The solution was heated till reduced to 2-3 ml. This procedure was repeated for 3-4 times to ensure complete decomposition. Then 5 ml of conc. hydrochloric acid was added and heated till 2-3 ml was left.

This procedure was also repeated 2-3 times to remove nitrous fumes. The digest was filtered, if necessary, and the volume was made up to 10 ml with distilled water. Selenium content was determined by the recommended procedure. Precaution must be taken to see that mixture does not dry up completely during digestion, otherwise there will be loss of selenium through volatilisation of oxides of selenium<sup>10</sup>. It was found that samples of cabbage had no selenium, therefore known amount of selenium was added to the sample before digestion. Selenium content was then determined by the recommended procedure. As concentrated nitric acid and hydrochloric acid was found to give nearly the same results, under the condition employed, the use of perchloric acid<sup>11,12</sup> was avoided for the reasons of safety. However, when perchloric acid was used, the results obtained were high, since chlorides interfere with this method.


#### Results and Discussion

**Spectral characteristics:** Absorption spectra of azoxine dye and azoxine dye are shown in Fig. 1. The graph shows  $\lambda_{max}$  at 550 nm. The reagent has negligible absorption at this wavelength. However, a reagent blank was used to compensate for any change in the colour of the reagent on storage.



Absorption spectra of azoxine dye and reagent blank in alkaline medium against water.  
A. Se = 30 µg/25 ml.  
B. Se = 20 µg/25 ml.  
C. Reagent blank.

**Reaction:** The reaction is given below. The ion B is identical with the reaction proposed by and Gupta<sup>10</sup>.



#### Effect of variables:

**Acidity:** The effect of acidity on oxidation of 4-NPH was studied by maintaining different molarities of hydrochloric acid ranging from 1 to 7 M and developing the colour by the recommended procedure. This revealed that at least 5 M hydrochloric acid was required for complete oxidation. Constant absorbance values were obtained when the acidity was above this. It was also found that wave length of maximum absorption remains constant in the range of acidity.

**Effect of time, temperature and reagent concentration:** The oxidation reaction is dependent on temperature. To determine the effect of temperature and time, the reaction was carried out at temperatures varying from 25 to 60°. The maximum time required for complete oxidation and stability of the diazonium chloride at respective temperature were evaluated by carrying out the oxidation reaction for different time and developing the colour. It was found that higher temperature accelerates the reaction, as the same intensity of colour is reached in 10 min at 60°, but in 45 min at 25°. However, the stability of diazonium chloride decreases at higher temperature. In this investigation the reaction was carried out at 60 ± 1° for 15 min.

The amount of reagent is not critical. For 7-45 µg of selenium per 25 ml, 1 ml of 4-NPH and 1 ml of 8-quinolinol gave reproducible results. At higher concentration 4-NPH itself gave colour with sodium hydroxide and it should be avoided.

**Effect of pH and stability of dye:** It was found that for coupling reaction pH 11 is required to attain maximum absorbance. This pH was attained with 5 M sodium hydroxide.

The dye was stable for 3-4 hr. Some turbidity was observed after this period.

**Beer's law, molar absorptivity and Sandell's sensitivity:** Beer's law was obeyed in the range of 7 to 45 µg/25 ml. The molar absorptivity and Sandell's sensitivity were  $3.2 \times 10^4 \text{ l. mole}^{-1} \text{ cm}^{-1}$  and 0.0025 µg/cm<sup>2</sup> respectively. The detection limit was 0.1 µg/ml. The standard deviation and relative standard deviation were ± 0.0026 and ± 0.814%, respectively.

**Validity of the method:** To check the validity of the method, 20 µg of selenium was determined in presence of known amounts of interferants. 100 fold excess of Br<sup>-</sup>, CN<sup>-</sup>, CNS<sup>-</sup>, CO<sub>3</sub><sup>2-</sup>, PO<sub>4</sub><sup>3-</sup>, SO<sub>4</sub><sup>2-</sup>, citrate and tartrate, 50 fold excess of Be<sup>2+</sup>, Ba<sup>2+</sup>(a), Co<sup>2+</sup>(a), Ca<sup>2+</sup>(a), Ni<sup>2+</sup>(a), Mg<sup>2+</sup>(a), Zn<sup>2+</sup>(a), Bi<sup>3+</sup>(b), Li<sup>+</sup>, K<sup>+</sup>, Pb<sup>2+</sup>(a), Al<sup>3+</sup>(a), 20 fold excess of Te<sup>4+</sup>, Hg<sup>2+</sup>(a) and 5 fold excess of Fe<sup>2+</sup>, Cr<sup>3+</sup> do not interfere. Many ions (marked by a and b) interfere by precipitation as hydroxide. These are masked with 1 ml of 10% disodium salt of EDTA (a) and

1 ml of 10% sodium potassium tartrate (b), respectively.  $\text{Cu}^{2+}$ , oxidants such as potassium permanganate, potassium dichromate,  $\text{Fe}^{3+}$  and reductants such as sulfide, thiosulphate,  $\text{Sn}^{2+}$  interfere. The interference of  $\text{Cu}^{2+}$  and  $\text{Fe}^{3+}$  can be eliminated by separating them as their cupferronates<sup>10</sup>.

The method was then successfully applied for the analysis of selenium in cabbage leaves (Table 1) and cigarette paper.

TABLE 1—DETERMINATION OF SELENIUM IN CABBAGE LEAVES

Selenium added μg	Selenium found <sup>a</sup> μg	Recovery %
40	39.00	97.50
20	19.50	97.50
10	9.70	97.00

<sup>a</sup>Average of three determinations.

Cigarette paper of different brands were found to contain different amounts of selenium. It was also found that the selenium content varied with different lot of the same brand. It was found that even one cigarette paper contained sufficient selenium to give positive test for selenium by this method.

The method is simple, sensitive, free from rigorous control of pH and can be compared favourably with other methods<sup>13-15</sup>. The coupling reagent 8-quinolinol used in proposed method is non-toxic as compared to  $\alpha$ -naphthylamine used in Kirkbright's method<sup>18</sup>. The method can be applied for the analysis of selenium in complex materials with reproducible results.

#### Acknowledgement

The authors thank Dr. S. G. Tandon, Head, Department of Chemistry, Ravishankar University, Raipur for facilities and the University Grants Commission, New Delhi for the award of Junior Fellowship to one of them (A. B.).

#### References

1. F. A. PATTY, "Industrial Hygiene and Toxicology", 2nd Ed., Interscience Publishers, New York, 1963, p. 889.
2. J. A. MILLER, N.A.S.-N.C.R. Publ. No. 1354, Washington D.C., 1966.
3. H. F. KRAGBILL, *Environ. Res.*, 1962, 2, 231.
4. M. I. SMITH, K. W. FRANKS and B. B. WESTFALL, *U. S. Public Health Rept.*, 1936, 51, 1496.
5. G. A. FLEMING, *Soil Sci.*, 1962, 94, 28.
6. R. A. NADKARNI, W. D. EHMAN, *Radiochem. Radioanal. Lett.*, 1969, 2, 161.
7. P. W. WEST, A. D. SHENDRIKAR, *Anal. Chim. Acta*, 1977, 82, 403.
8. a) P. W. WEST, S. L. SACHDEV and A. P. SHENDRIKAR, *Environ. Lett.*, 1972, 2, 225.  
b) A. K. BAVEJA and V. K. GUPTA, *Intern. J. Environ. Studies*, 1980, 16, 35.
9. D. F. BOLTS, "Colorimetric Determination of Non-metals", Interscience Publishers, New York, 1958, p. 315.
10. A. K. BABKO and A. T. PILIPENKO, "Photometric Analysis, Methods of Determination of Non-metals", Mir Publishers, Moscow, 1976, p. 315.
11. L. KLAYMAN and W. H. H. GUNTHER, "Organic Selenium Compounds: Their Chemistry and Biology", Wiley Interscience, New York, p. 1050.
12. V. I. MURASHOVA and S. G. SUSHKOVA, *Z. Anal. Khim.*, 1962, 24, 729.
13. E. M. DONALDSON, *Talanta*, 1977, 24, 441.
14. J. H. WATKINSON, *Anal. Chem.*, 1966, 38, 92.
15. G. H. KIRKBRIGHT and J. H. YOE, *Anal. Chem.*, 1963, 35, 808.
16. B. SIXTO, *Anal. Chem.*, 1978, 50, 649.
17. P. R. HADDAO and Z. E. SMYTHE, *Talanta*, 1974, 21, 859.
18. R. E. STANTON and A. J. McDONALD, *Analyst*, 1965, 90, 497.
19. J. NAIR and V. K. GUPTA, *Anal. Chim. Acta*, 1979, 111, 311.
20. M. F. FURMAN, W. B. MASON and J. S. PEKOLA, *Anal. Chem.*, 1949, 21, 1324.

# Notes

## Inorganic Coordination Complexes. Part-V. Complexes of Divalent Zinc, Cadmium and Mercury with Substituted Salicyl Hydrazines

S. R. TEWARI, S. K. BAJPAI\*, S. K. MISRA, G. N. SHUKLA  
and

V. N. MISRA

Chemistry Department, Lucknow University, Lucknow-226 007

Manuscript received 7 July 1980, revised 9 December 1981,  
accepted 1 May 1982

As a part of our studies on metal complexes<sup>1-6</sup>, we report here the reactions of divalent Zn, Cd and Hg with N-salicyl hydrazine (SH), N-N'-disalicyl hydrazine (DSH), N-acetyl-N'-salicyl hydrazine (ASH) and N-benzoyl-N'-salicyl hydrazine (BSH). Various substituted acyl hydrazines have been reported to coordinate through  $>C=O$  and  $-NH_2$  groups<sup>7-9</sup>, but the complexes of SH, DSH, ASH and BSH described here are of particular interest as  $-OH$  group formed by the enolization of these hydrazines provides an additional coordination site for various metal ions.

### Experimental

SH was prepared by the reaction of methyl salicylate and hydrazine hydrate<sup>10-11</sup>. ASH and BSH were obtained by acetylation and benzoilation of SH, whereas DSH was prepared by heating a mixture of methyl salicylate and SH. All ligands were further purified by repeated crystallization from hot ethanol. The complexes were prepared by the method described earlier<sup>4</sup>.


### Results and Discussions

The insolubility of the complexes under investigation in most of the organic solvents indicated their polymeric nature<sup>12</sup> (cf. I, II and III). The low molar conductance values of the complexes (varying from 0.6-1.0 mhos) in pyridine showed them to be non electrolytes. All the complexes are thermally stable, as they decompose above 200° without melting.


**1. SH and DSH complexes:** The ir spectra have been interpreted on the basis of published data<sup>13-15</sup>. On comparing the spectra of ligands with the spectra of the complexes, a considerable negative shift of 40-60  $cm^{-1}$  in  $C=O$  stretching frequency indicates the coordination of ligands through oxygen of  $C=O$  group. Coordination through nitrogen has been ruled out as  $\delta NH$  mode remains unaffected. However, the negative shift of 15-25  $cm^{-1}$  observed in the ring stretching vibrations and disappearance of OH frequency in the spectra of complexes confirm the coordination of ligand through oxygen atom of carbonyl group and oxygen of the phenolic group after deprotonation<sup>4</sup>. Similar ir spectral features have been observed with slight alteration in number,

position and intensity of bands in the DSH complexes.

The following polymeric structures, I and II, have been proposed for SH and DSH complexes, respectively.




I  
[M = Zn, Cd, Hg]



II  
[M = Zn, Cd, Hg]

**2. ASH and BSH complexes:** Ohta reported that acyl hydrazines show keto-enol tautomerism<sup>14</sup>. In view of this, ASH and BSH may exist as




The spectra of the complexes showed the negative shift of about 50  $cm^{-1}$  in the band around 3300  $cm^{-1}$  as compared to the spectra of the ligands showing involvement of NH group in complexation through nitrogen. An intense band in the region 1610-1670  $cm^{-1}$  in the spectrum of ligand has been assigned to the amide I ( $C=O$ ) mode. But in the complexes, a band is observed around 1600  $cm^{-1}$  which suggests that the amide I band of the ligand either suffers a negative shift or disappears due to formation of  $C=N$  as a results of enolization. This has been further substantiated by a band around 1500  $cm^{-1}$  due to involvement of NCO group in complexation<sup>15</sup>. The appropriate M-N and M-O frequencies are listed in Table I. Variation in M-N stretching frequencies of these complexes follows the "Irving Williams" order of stability of the bivalent metal complexes<sup>16</sup> i.e. Zn > Cd > Hg.

\*To whom all correspondence should be addressed.

TABLE 1—ANALYTICAL AND SPECTRAL DATA OF ZN, CD AND HG COMPLEXES OF SUBSTITUTED SALICYL HYDRAZINES  
(Values in parenthesis are calculated)

Compounds	m p./ Dec. Temp. °C	Colour	Metal %	C %	H %	N %	IR spectral data in cm <sup>-1</sup>			
							NH and OH	C=N, C=O	M-N	M-O
SH	144	White	—	55.02 (55.17)	5.15 (5.14)	18.20 (18.40)	3330m	1630s	—	—
Zn(SH-H) <sub>2</sub>	350	Dirty white	17.50 (17.71)	45.92 (45.77)	3.72 (3.81)	15.10 (15.25)	3275s	1580s	380m	430m
Cd(SH-H) <sub>2</sub>	250	Bright white	27.15 (27.05)	40.16 (40.57)	3.41 (3.38)	13.40 (13.52)	3280s	1575s	350m	440m
Hg(SH-H) <sub>2</sub>	200	White	39.68 (39.84)	33.10 (33.46)	2.62 (2.78)	11.20 (11.15)	3275s	1580s	320m	455m
DSH	302	Yellow	—	61.10 (61.25)	4.25 (4.38)	9.50 (9.69)	3300m	1610s	—	—
Zn(DSH-2H)	300	Light yellow	19.61 (19.40)	47.63 (47.32)	2.90 (2.81)	8.42 (8.35)	3100s	1560s	375m	435m
Cd(DSH-2H)	285	Yellow- ish white	29.45 (29.31)	43.43 (43.71)	2.58 (2.61)	7.30 (7.32)	3110s	1565s	340m	440m
Hg(DSH-2H)	248	Light yellow	42.35 (42.55)	35.28 (35.74)	2.01 (2.12)	5.81 (5.95)	3105s	1570s	325m	450m
ASH	183	White	—	55.86 (55.65)	5.15 (5.35)	14.70 (14.40)	3400s	1670s	—	—
Zn(ASH-2H)	400	White	25.10 (25.29)	42.21 (42.02)	3.21 (3.11)	10.75 (10.89)	3275s	1610s	370m	440m
Cd(ASH-2H)	350	White	36.68 (36.84)	35.31 (35.52)	2.52 (2.63)	9.10 (9.21)	3270s	1610s	345m	445m
Hg(ASH-2H)	200	White	51.15 (51.02)	29.35 (29.55)	2.10 (2.04)	7.05 (7.14)	3270s	1600s	320m	455m
BSH	280	White	—	65.75 (65.63)	4.96 (4.69)	10.70 (10.94)	3320s	1660s	—	—
Zn(BSH-2H)	400	Yellow- ish white	20.45 (20.37)	52.42 (52.66)	3.05 (3.13)	8.65 (8.77)	3280s	1600s	385m	435m
Cd(BSH-2H)	350	"	30.55 (30.60)	45.71 (45.90)	2.68 (2.73)	7.42 (7.65)	3285s	1605s	350m	445m
Hg(BSH-2H)	200	"	44.20 (44.05)	37.15 (37.00)	2.18 (2.20)	6.19 (6.16)	3280s	1600s	330m	450m

In view of the very poor solubility of these complexes in most of the organic solvents, the polymeric structure III may be proposed.



III  
[M = Zn, Cd, Hg & R = CH<sub>3</sub>, C<sub>6</sub>H<sub>5</sub>]

#### Acknowledgement

The authors are grateful to Prof. V. S. Misra, Head of Chemistry Department, Lucknow University and to Dr. D. Prakash, Senior Geo-chemist, Directorate of Geology and Mining, U. P., Lucknow for providing laboratory facilities.

#### References

1. S. K. BAJPAI, *J. Indian Chem. Soc.*, 1978, **55**, 973.
2. S. K. BAJPAI and D. PRAKASH, *J. Inorg. Nuclear Chem.*, 1979, **41**, 756.
3. S. K. BAJPAI, *Indian J. Chem.*, 1980, **19A**, 270.
4. V. N. MISRA and R. GOPAL, *Indian J. Chem.*, 1975, **13**, 186.
5. V. N. MISRA, K. K. NARANG and R. GOPAL, *Indian J. Chem.*, 1976, **14**, 364.
6. S. R. TEWARI, S. K. BAJPAI, V. N. MISRA and D. PRAKASH, *Mikrochimica Acta*, 1979, **9**, 397.
7. D. NICHOLLS, J. REED and A. ANAGNOSTOPOULOS, *Inorg. Chem. Acta Lett.*, 1979, **32**, 17.
8. R. M. ISSA, M. F. SHAZYL and M. F. ISKANDAR, *Z. anorg. allg. Chem.*, 1967, **354**, 90.
9. R. C. AGARWAL, B. N. YADAVA and T. PRASAD, *Indian J. Chem.*, 1972, **10**, 671.
10. B. PRAGAR, P. JACOBSON, P. SCHIMDT and O. STERN, "Beilsteins Handbuch der Organischen Chemie", 1927, **10**, 100.
11. S. WUOCHIN-HUA, G. R. ROSMAN, H. B. GRAY, G. S. HAMMOND and H. J. SCHUGAR, *Inorg. Chem.*, 1972, **11**, 990.
12. J. ZABICKY, "The Chemistry of Amides", Interscience Publisher, London, 1970, p. 556.
13. R. C. AGARWAL and K. K. NARANG, *Indian J. Chem.*, 1976, **14**, 64.
14. H. OHTA, *Bull. Chem. Soc., Japan*, 1958, **31**, 1056; 1960, **33**, 2.
15. M. MASHIMA, *Bull. Chem. Soc., Japan*, 1962, **35**, 332.
16. H. IRVING and R. P. WILLIAMS, *J. Chem. Soc.*, 1953, 3192.

## Spectral and Magnetic Studies of Some Mixed Ligand Complexes of High-Spin Cobalt(II)

D. S. SANKHLA, R. C. MATHUR\*  
and  
SUDHINDRA N. MISRA\*Department of Chemistry, University of Jodhpur,  
Jodhpur-342 001Manuscript received 23 April 1980, revised 15 May 1981,  
accepted 22 July 1981

**D**IVALENT cobalt complexes have tendency towards oxidation in presence of a variety of complexing agents<sup>1</sup>. The complexes synthesized in the present study have been found to be sufficiently stable and resistant to oxidation. In these ligand exchange reactions the comparatively weak bonded coordinated water molecules of the parent  $\beta$ -ketoester complexes of Co(II) are quantitatively replaced by thiourea. Since the solubility of these complexes in common organic solvents has been found to be very low, the diffuse reflectance has been carried out using lithium fluoride as diluent as well as reference.

## Experimental

Diaquo bis-(methylacetoacetato) and diaquo bis-(ethylacetoacetato) of Co(II) were prepared by known method<sup>2</sup>. The mixed ligand complexes were synthesized by adding an ethanolic solution of the second ligand viz. thiourea or phenylthiourea (0.02 mole) to an ethanolic solution of diaquo bis-(MeAA) Co(II) or diaquo bis-(EtAA) Co(II) (0.01 mole). The resulting reaction mixture was refluxed for one and half hour. The complex separated out on cooling, was filtered, washed with ethanol and ether and dried *in vacuo* over anhydrous calcium chloride.

Magnetic measurements were made on a Gouy magnetic balance at  $300 \pm 1^\circ\text{K}$ . The ir spectra of the complexes were recorded on a Perkin-Elmer 577 spectrophotometer in KBr phase while diffuse reflectance spectra were recorded on a VEB Carl Zeiss Jena VSU 2P spectrophotometer using the reflectance attachment o/r.

## Results and Discussion

The magnetic moment ( $\mu_{eff}$ ) for all the complexes ranges between 4.95-5.28 B.M. (Table 1)

indicating the complexes to be high-spin complexes with three unpaired electrons and having almost octahedral stereochemistry<sup>3,4</sup>. Absence of absorption band around  $3450\text{ cm}^{-1}$  in the mixed ligand complexes, discernible in parent complexes, show the replacement of two coordinated water molecules of parent complexes by two thiourea ligands. A considerable overlapping of bands due to coordinated  $\beta$ -ketoesters and the second ligand was observed. Definite shifts were observed in C-O, C-C and M-O stretching frequencies (Table 1) on coordination of thiourea ligands, because all the three bands are involved in the resonance system. The direction of these shifts cannot be correctly predicted since there will be a metal-ligand  $\pi$  bonding superimposed on a ligand-metal bond<sup>5</sup>. The shift of -NH absorption vibration of thiourea ligands towards higher and that of C=S band (around  $740\text{ cm}^{-1}$ ) towards lower frequency regions suggest the coordination of thiourea or substituted thiourea ligand to the metal through S-atom<sup>6,7</sup>.

In high-spin cobalt(II) complexes, the experimentally observed spin-allowed transitions in increasing order of energy are  ${}^4T_{1g}(F) \rightarrow {}^4T_{2g}$ ,  ${}^4T_{1g}(F) \rightarrow {}^4A_{2g}$  and  ${}^4T_{1g}(F) \rightarrow {}^4T_{1g}(P)$ , and are denoted as  $\nu_1$ ,  $\nu_2$  and  $\nu_3$ , respectively<sup>8</sup>. By using transitions  $\nu_1$  and  $\nu_2$ , and following weak field coupling scheme, the values for Racah interelectronic repulsion parameter, B, and crystal field splitting energy parameter,  $10 Dq$ , have been calculated<sup>9</sup> and are summarized in Table 1 along with experimentally observed transition energies. In the calculation of the different parameters the transition band  $\nu_3$  has not been used since it is a weak band due to two electron jump and hence its accurate location is difficult. The Jahn-Teller effect in the ground state  ${}^4T_{1g}(F)$  of octahedral  $d^7$  ion is expected to be weak and has not been considered here. The value of the free gaseous ion,  $972\text{ cm}^{-1}$ , is used to calculate the value for nephelauxetic ratio,  $\beta$ . The lower values for  $\beta$  in these mixed ligand complexes as compared to their respective parent complexes indicate the increase in covalency on further complexation. By using the modified Tanabe-Sugano diagram given by Lever<sup>10</sup>, the graphical values for parameters B and  $10 Dq$  have been deduced using transition energy ratio  $\nu_3/\nu_1$  (Table 1).

TABLE 1—EXPERIMENTALLY OBSERVED TRANSITION ENERGIES, VALUES OF VARIOUS PARAMETERS AND IR SPECTRAL DATA (IN  $\text{cm}^{-1}$ )

Complex	${}^4T_{1g}(F)$ $\downarrow$ ${}^4T_{2g}$	${}^4T_{1g}(F)$ $\downarrow$ ${}^4A_{2g}$	${}^4T_{1g}(F)$ $\downarrow$ ${}^4T_{1g}(P)$	B	10 Dq	B	10 Dq	$\nu_3/\nu_1$	$\beta$	$\nu(\text{C-O})$	$\nu(\text{C-C})$	$\nu(\text{M-O})$
						(Graph)	(Graph)					
Co(MeAA) <sub>2</sub> (H <sub>2</sub> O) <sub>2</sub>	8547	19801	21505	944.7	9759	954.5	9831	2.51	0.97	1620 s	1505 s	450 m
Co(MeAA) <sub>2</sub> (TU) <sub>2</sub>	8333	17842	20619	890.1	9397	902.7	9388	2.47	0.91	1630 s	1490 m	465 m
Co(MeAA) <sub>2</sub> (PTU) <sub>2</sub>	8474	18975	21276	933.8	9676	936.0	9640	2.51	0.96	1580 s	1485 s	468 w
Co(EtAA) <sub>2</sub> (H <sub>2</sub> O) <sub>2</sub>	8620	19607	21739	956.8	9853	928.6	9471	2.52	0.98	1626 s	1525 s	480 m
Co(EtAA) <sub>2</sub> (TU) <sub>2</sub>	8488	19157	20408	872.8	9660	871.7	9588	2.40	0.89	1630 s	1530 m	462 m
Co(EtAA) <sub>2</sub> (PTU) <sub>2</sub>	8605	18867	21276	924.5	9831	926.6	9636	2.47	0.95	1547 s	1532 m	468 m

MeAA = methylacetoacetate, EtAA = ethylacetoacetate; TU = thiourea; PTU = phenylthiourea.

\* Physics Division, Defence Laboratory, Jodhpur, India.

\* For correspondence.

Hay and Cauchley<sup>8</sup> have proposed the *trans* arrangement of the ligand for the  $\beta$ -ketoester derivatives of cobalt(II). Ballhausen *et al.*<sup>12</sup> have correlated this *trans* behaviour in cobalt(II) complexes with the width of the electronic absorption bands. The presence of narrow electronic bands was correlated to the *trans* configuration of the complexes. The electronic bands in these mixed ligand complexes also retain the same absorption pattern when the  $\text{Co}(\text{MeAA})_2(\text{H}_2\text{O})_2$  and  $\text{Co}(\text{EtAA})_2(\text{H}_2\text{O})_2$  react with thiourea and the observed bands are not broad. Thus, we can assume that the mixed ligand complexes derived from  $\beta$ -ketoesters of cobalt(II) have also the *trans* configuration with almost octahedral stereochemistry. Slight distortion may be due to the non-identical nature of the coordinating atoms.

#### Acknowledgement

The authors thank University Grants Commission, New Delhi for a grant to one of them (D. S. S.) and Prof. R. C. Kapoor for laboratory facilities.

#### References

1. R. L. CARLIN, "Transition Metal Chemistry", Marcel Dekker, Inc., New York, 1965, Vol. 1, p. 2
2. C. FERNELIUS and B. E. BRYANT, "Inorganic Synthesis", McGraw Hill, Inc., New York, 1957, Vol. 5, p. 105.
3. K. H. SHAW and G. J. SUTTON, *Aust. J. Chem.*, 1969, 22, 1841.
4. B. N. FIGGIS and J. LEWIS, *Prog. Inorg. Chem.*, John Wiley, New York, 1964, Vol. 6, p. 37.
5. R. W. HAY and B. P. CAUGHLEY, *Aust. J. Chem.*, 1967, 20, 1829.
6. R. A. BAILEY and T. R. PEARSON, *Can. J. Chem.*, 1968, 46, 3119.
7. G. F. SVATOS, C. CURRAN and J. V. QUAGLIANO, *J. Amer. Chem. Soc.*, 1955, 77, 6159.
8. J. LEWIS and R. G. WILKINS, "Modern Coordination Chemistry", New York, 1960, p. 290.
9. E. KONIG, *Structure and Bonding*, 1971, 9, 175.
10. A. B. P. LEVER, "Advances in Chemistry Series", 1966, 62, 430.
11. C. J. BALLHAUSEN and C. K. JORGENSEN, *Acta Chem. Scand.*, 1955, 9, 397.

#### Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Chloro-2'-Methoxyaniline Complexes with $\text{La}^{3+}$ , $\text{Y}^{3+}$ , $\text{Nd}^{3+}$ , $\text{Dy}^{3+}$ and $\text{Gd}^{3+}$

M. S. MAYADEO, S. S. PUROHIT and S. H. HUSSAIN

Department of Chemistry, Ramnarain Ruia College,  
Bombay-400 019

Manuscript received 23 March 1981, revised 13 January 1982,  
accepted 28 April 1982

It has been generally concluded from previous work<sup>1-4</sup> on the correlation between chelate stability and ionic radii that the stabilities of the tripositive lanthanide complexes should increase with decreasing cation radius or increasing atomic number. An examination of the stability constant data generally bears out this expectation but reveals

an anomalous behaviour in some instances. A large amount of work done relates to  $\text{O}^-$ ,  $\text{O}^-$  donors. However, complexes containing  $\text{O}^-$  and N functional groups (azomethines) have not been dealt with very extensively. This communication is a continuation of our work<sup>5</sup> on Schiff bases. The new Schiff base, 2-hydroxy-1-naphthalidene-4'-chloro-2'-methoxyaniline has been selected to study a correlation, if any, between the stability constants and the ionic potentials of the trivalent lanthanides.

#### Experimental

The ligand 2-hydroxy-1-naphthalidene-4'-chloro-2'-methoxyaniline was synthesised and repeatedly crystallised from alcohol to get an analytically pure sample with m.p. 271° (observed). All reagents were of A. R. grade and their solutions were made in purified dioxan<sup>6</sup> and double distilled  $\text{CO}_2$  free water. pH metric titrations of the following solutions, (i-iii) were carried out at  $25 \pm 0.1^\circ$  under nitrogen atmosphere. These solutions, with an initial volume of 40 ml, were titrated with a carbonate free standard sodium hydroxide solution (1.07 M) using a Corning Model 12 precision research pH meter having an accuracy of 0.005 pH unit with combined glass electrode and calomel reference electrode. The medium of titration was 75 : 25 (v/v) dioxan-water mixture. A constant ionic strength (0.1 M) was maintained by adding requisite amount of  $\text{NaClO}_4$ .

- (i) 5 ml (0.16 M)  $\text{HClO}_4$  + 5 ml (0.64 M)  $\text{NaClO}_4$  + 30 ml dioxan.
- (ii) 5 ml (0.16 M)  $\text{HClO}_4$  + 5 ml (0.64 M)  $\text{NaClO}_4$  + 49.84 mg reagent, accurately weighed to give 0.004 M reagent concentration in the final solution + 30 ml dioxan.
- (iii) 5 ml (0.64 M)  $\text{NaClO}_4$  + 5 ml metal salt (0.008 M) solution in (0.16 M)  $\text{HClO}_4$  + 49.84 mg reagent accurately weighed to give 0.004 M reagent concentration in the final solution + 30 ml of dioxan.

The experimental method of Irving and Rossotti<sup>7</sup> was applied to find out the values of  $\beta$  and  $pL$ . The titrations were performed in duplicate to test for reproducibility.

#### Results and Discussion

It may be pointed out here that the ligand used in this study did not undergo hydrolysis under the experimental conditions. This was indicated by rapid attainment of equilibrium during the titrations and by the absence of any significant change in pH even after 1 hr. The phenolic OH group of the ligand is deprotonated during complex formation.

From the titration curves of solutions (i) and (ii),  $\beta_A$  values at various 'B' values (pH meter readings), were calculated and a curve between 'B' and the corresponding  $\beta_A$  values was plotted. The value of  $pK_1^H$  was evaluated by half integral method as well as from the plot of  $\log(\beta_A/1-\beta_A)$  vs B. Both these values agree well.

From the titration curves of solutions (ii) and (iii),  $\bar{n}$  and  $pL$  values were calculated. The  $\bar{n}$  values were plotted against the corresponding  $pL$  values to get the formation curves of metal complex-ion equilibria. The  $pK_H^1$  of the ligand and  $\log K_1$  and  $\log K_2$  of the complexes of  $Y^{3+}$ ,  $La^{3+}$ ,  $Nd^{3+}$  and  $Gd^{3+}$  were evaluated by the half integral method. In the case of dysprosium and praseodymium metal systems, the differences between  $\log K_1$  and  $\log K_2$  values were found to be less than 1.78 log units and hence the same were evaluated by the least square method. The most representative values are recorded in Table 1. The order of stability of various metal chelates was found to be  $Y^{3+} > Gd^{3+} > Nd^{3+} > La^{3+} > Pr^{3+} > Dy^{3+}$ .

An attempt to interpret the stability data in terms of an entirely ionic type of bonding in these complexes was unsuccessful as the plot of  $Z^{3+}/r$  vs  $\log K_1$  values was not linear. The possibility of covalent interaction, however, cannot be completely excluded, as reported in the case of acetylacetonate chelates of rare earths<sup>8</sup>. The probable explanation of non-linearity could be that the assumption about ionic character of the metal-ligand bond, on which the linearity relation is based, is not valid. Other probable causes could be possibilities of higher coordination number of metal ion and steric factors.

TABLE 1—STEPWISE STABILITY CONSTANTS OF THE COMPLEXES OF 2'-HYDROXY-1-NAPHTHALIDENE-4'-CHLORO-2'-METHOXYANILINE WITH SOME TRIVALENT LANTHANIDES

	$t = 25 \pm 0.1^\circ$				$\mu = 0.1$ (NaClO <sub>4</sub> )			
Cations	H <sup>+</sup>	Y <sup>3+</sup>	La <sup>3+</sup>	Pr <sup>3+</sup>	Nd <sup>3+</sup>	Dy <sup>3+</sup>	Gd <sup>3+</sup>	
$\log K_1$	9.40	9.23	8.72	8.20	9.05	7.59	9.07	
$\log K_2$	—	7.08	6.10	6.73	7.05	6.28	6.78	

For proton association (H<sup>+</sup>),  $K_1$  corresponds to the species LH; while for metal ions,  $K_1$  and  $K_2$  correspond to the species ML<sub>1</sub> and ML<sub>2</sub>, respectively.

The standard deviation ranged from 0.05 to 0.1, the limits of error were  $\pm 0.06$ .

#### Acknowledgement

The authors record their sincere thanks to Dr. D. G. Vartak, B. A. R. C., Bombay, for valuable suggestions.

#### References

1. R. HARDER and S. CHABEREK, *J. Inorg. Nuclear Chem.*, 1959, 11, 197.
2. T. MOELLER and R. FERRUS, *J. Inorg. Nuclear Chem.*, 1961, 20, 261.
3. F. H. SPEDDING, J. E. POWELL and E. R. WHEELWRIGHT, *J. Amer. Chem. Soc.*, 1956, 78, 34.
4. T. MOELLER and L. C. THOMPSON, *J. Inorg. Nuclear Chem.*, 1962, 24, 499.
5. M. S. MAYADEO and S. S. PUROHIT, *J. Indian Chem. Soc.*, 1981, 58, 544.
6. A. I. VOGEL, "A Text Book of Practical Organic Chemistry", 3rd Ed., Longmans, p. 177.
7. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
8. T. D. MOELLER, *Chem. Rev.*, 1956, 65, 1.

#### Polarographic Reduction of Uranyl(II) in Presence of Some Disubstituted Pyridines

R. S. SINDHU, K. B. PANDEYA and R. P. SINGH

Department of Chemistry, University of Delhi, Delhi-110 007

Manuscript received 27 July 1981, accepted 2 February 1982

THE present paper describes the polarographic reduction of uranyl(II) in presence of some disubstituted pyridines, viz., 2,3-dihydropyridine (DPH), 2-amino-3-hydropyridine (AHP) and 3-hydropyridine-2-thiol (HPT). All the systems show diffusion controlled irreversible reduction waves. Kinetic parameters ( $\alpha n$  and  $k_p^0$ ) have been calculated and discussed. The ligands contain ideal sites for formation of sterically favoured five-membered ring and provide scope for comparison of donor properties of -OH, -NH<sub>2</sub> and -SH groups. Reactions of UO<sub>2</sub>(II) with these ligands have been studied earlier pH-metrically<sup>1-3</sup> wherein metal-ligand stability constants were determined.

#### Experimental

A D.C. manual polarograph with a scalamp galvanometer was used in all investigations. All potential measurements were made with reference to a saturated calomel electrode. The dropping mercury electrode had the characteristics,  $m^{2/3}t^{1/6} = 2.054 \text{ mg}^{2/3} \text{ sec}^{-1/6}$ ,  $h = 40 \text{ cm}$ ,  $t = 3.8 \text{ sec}$ . Purified nitrogen was passed through each solution to remove dissolved oxygen. All measurements were carried out at room temperature ( $30 \pm 0.1^\circ$ ).

Reagent grade chemicals were used. Solution of uranyl nitrate was prepared in double distilled water. Stock solutions of DPH and AHP (Aldrich Chemical Co., U.S.A.) were prepared in double distilled water and that of HPT (Fluka AG, Switzerland) in purified methanol. While UO<sub>2</sub>(II)-DHP and UO<sub>2</sub>(II)-AHP systems were studied in aqueous media, UO<sub>2</sub>(II)-HPT system was studied in 30% methanol medium owing to the limited solubility of the ligand in water. Sodium perchlorate was used as the supporting electrolyte and ionic strength was kept constant ( $\mu = 0.1$ ). Acetate buffer was used to maintain the pH. Gelatin (0.003%) was used as the maxima suppressor.

#### Results and Discussion

Well defined single cathodic waves were obtained in all the three cases.  $E_{s/4} - E_{1/4}$  values ( $69 \pm 1 \text{ mV}$ ) show irreversible nature of the systems and constant values of  $i_d/(h_{eff})^{1/2}$  show that the waves are diffusion controlled. Kinetic parameters have been calculated using Oldham and Parry method<sup>4</sup>. According to these authors the equation for an irreversible diffusion controlled wave (at  $30^\circ$ ) is

$$-E_d = -E_1 + \frac{0.060}{\alpha n} \log \left[ \frac{x(5.5-x)}{5(1-x)} \right] \quad \dots (1)$$

where  $x = \frac{i_E}{i_{lim}}$ ,  $i_E$  = current at potential  $E$  which is valid in the entire region  $0 \leq x \leq 1$ . The plots of  $E_{\frac{1}{2}}$  vs  $\log \left[ \frac{x(5.5-x)}{5(1-x)} \right]$  yield the values of  $\frac{0.060}{\alpha n}$  (slope) and  $-E_{\frac{1}{2}}$  (intercept). Also, for an irreversible wave the half wave potential is related to the rate constant for the electrode reduction by the expression,

$$E_{\frac{1}{2}} = E_0 + \frac{0.060}{\alpha n} \log \left[ 0.89 k_{f,h}^0 \sqrt{t/D} \right] \quad \dots (2)$$

where  $k_{f,h}^0$  is the formal rate constant at a reference potential  $E_0 = -0.2412$  volts vs S.C.E. and  $D$  and  $t$  have their usual significance. The reference potential in the present investigations has been chosen as the normal hydrogen electrode potential ( $-0.2412$  volts vs S.C.E.) and the values of  $D^{\frac{1}{2}}$  have been obtained using Ilkovic equation. Values of  $\alpha n$  and  $k_{f,h}^0$  have been calculated and presented in Table 1

TABLE 1—KINETIC PARAMETERS

ligand conc. (mM)	[UO <sub>2</sub> <sup>2+</sup> ] = 1 × 10 <sup>-4</sup> M			
	$-E_{\frac{1}{2}}$ (volts vs SCE)	$\alpha n$	$D^{\frac{1}{2}} \times 10^3$ (cm sec <sup>-1/2</sup> )	$k_{f,h}^0 \times 10^3$ (cm <sup>-1</sup> sec <sup>-1</sup> )
(a) System : UO <sub>2</sub> (II)-DHP, pH = 4.4				
2.0	0.460	0.750	2.33	2.71
4.0	0.480	0.742	2.19	1.54
6.0	0.488	0.740	2.03	1.16
8.0	0.492	0.739	1.95	1.01
(b) System : UO <sub>2</sub> (II)-AHP, pH = 4.4				
2.0	0.455	0.752	2.41	3.19
4.0	0.476	0.749	2.34	1.52
6.0	0.485	0.752	2.16	1.20
8.0	0.490	0.747	2.17	1.10
(c) System : UO <sub>2</sub> (II)-HPT, pH = 4.6				
2.0	0.463	0.747	2.18	1.74
4.0	0.481	0.741	2.11	1.46
6.0	0.490	0.740	2.03	1.10
8.0	0.493	0.740	1.86	1.02

A perusal of the results show that the  $k_{f,h}^0$  values for reduction of UO<sub>2</sub><sup>2+</sup> in presence of the same concentration of the ligands follow the order HPT < DHP < AHP. Since higher value of the rate constant signifies easier reduction and hence lower stability of the complex, the order of the strength of the metal ligand bond in the complexes of the three ligands appears to be HPT > DHP > AHP.

Uranyl ion falls in the category of hard acids (class 'a') for which the strength of the metal ligand bond should follow the O > N > S order of the donor atoms, so that the order of stability of the complexes formed with the three ligands under study should be DHP > AHP > HPT. For DHP and AHP, the studies were made under similar conditions (both in aqueous media) and the observed behaviour is as expected from theoretical considerations. Deviation in the behaviour of HPT may be because the study was made in 30% methanol medium which has a dielectric constant lower than that of water.

Vlcek<sup>2</sup> also approximated that a complex with a nonhomogeneous coordination sphere will be reduced more easily (i.e., the rate constant for reduction will be higher) than one with fully homogeneous coordination sphere. Consistent with the above, the rate constant for the reduction of the AHP complex is higher than that for the reduction of the DHP complex.

#### Acknowledgement

Grateful thanks of the authors are due to the Council of Scientific and Industrial Research, New Delhi for the award of a Research Fellowship to one of them (R. S. S.).

#### References

1. D. P. GOEL, Y. DUTY and R. P. SINGH, *J. Inorg. Nuclear Chem.*, 1970, 32, 3119.
2. D. P. GOEL, Ph.D. thesis, Delhi University, 1969.
3. V. KUSHWAHA, M. KATYAL and R. P. SINGH, *Talanta*, 1974, 21, 763.
4. K. B. OLDHAM and E. P. PARRY, *Anal. Chem.*, 1968, 40, 55.
5. A. A. VLCEK, *Progr. Inorg. Chem.*, 1963, 5, 364.

#### Determination of Stability Constants of 2-Hydroxy-1-naphthalidene-Sulphamethoxazole Complexes with Cu<sup>2+</sup>, Ni<sup>2+</sup>, Co<sup>2+</sup>, Zn<sup>2+</sup> and Mg<sup>2+</sup>

M. S. MAYADEO and S. BHATTACHARJEE

Department of Chemistry, Ramnarain Ruia College, Bombay-400 019

Manuscript received 31 July 1981, accepted 7 June 1982

IN the present investigation, potentiometric studies have been carried out on 2-hydroxy-1-naphthalidene-sulphamethoxazole and its complexes with some bivalent metal ions. The dissociation constants ( $pK_1$  and  $pK_2$ ) of the reagent and the formation constants ( $\log K_1$  and  $\log K_2$ ) of its metal chelates have been determined potentiometrically following the Calvin-Bjerrum pH titration technique as adopted by Irving and Rossotti<sup>1</sup>.

#### Experimental

The ligand 2-hydroxy-1-naphthalidene-sulphamethoxazole was prepared by refluxing equimolar quantities of 2-hydroxy-1-naphthaldehyde and the amine in alcohol-DMF mixture and was repeatedly crystallised to get an analytically pure compound, m.p 240° (observed). All the metal perchlorates used were prepared from metal salts and perchloric acid both of A. R. grade. These were standardised complexometrically by EDTA titrations<sup>2</sup>. Other experimental details were the same as in our earlier communication<sup>3</sup>.

#### Results and Discussion

It may be mentioned here that the ligand does not undergo hydrolysis under the experimental



conditions described. This was indicated by rapid attainment of equilibrium during the course of titration and by the absence of any significant drift in pH even after two hours. This was further confirmed by taking titration mixture from time to time.

In the ligand, it is the phenolic OH group that takes part in complex formation and the proton is replaced from it by the metal ion during chelation. As only one proton per ligand molecule is liberated, 'Y' the number of dissociable protons attached to each ligand molecule is one.

From the titration curves (Fig. 1),  $\bar{n}_A$  values at various B values (pH meter readings) were calculated and the formation curve (B vs  $\bar{n}_A$ ) was plotted. The  $pK_1^H$  corresponding to phenolic H was obtained by half integral method at  $\bar{n}_A=0.5$ . This was further corroborated by plotting the graph of  $\log (\bar{n}_A/1-\bar{n}_A)$  vs B.




Fig. 1. Titration curves of 2-hydroxy-1-naphthalidene-sulphamethoxazole.

From the titration curves,  $\bar{n}$  and  $pL$  values for metal-ligand systems were also determined. Values of  $\log K_1$  and  $\log K_2$  were determined from the curves  $\bar{n}$  vs  $pL$  by half integral method and the results were corroborated by plotting the graph of

$\left[ \log \frac{\bar{n}}{1-\bar{n}} \right]$  vs  $pL$ . As in the cases of  $Cu^{2+}$ ,  $Zn^{2+}$  and  $Mg^{2+}$  complexes the difference between  $\log K_1$  and  $\log K_2$  was found to be less than 1.78 log units, these were computed by the least square method, and the results are reported in Table 1.

TABLE 1—STEPWISE STABILITY CONSTANTS OF VARIOUS COMPLEXES\*

	$t = 25^\circ$			$\mu = 0.1$		
Cations	$H^+$	$Cu^{2+}$	$Zn^{2+}$	$Ni^{2+}$	$Co^{2+}$	$Mg^{2+}$
$\log K_1$	8.18	7.56	6.58	4.18	3.90	2.94
$\log K_2$	—	6.03	5.50	—	—	2.87

\* The order of stability of metal chelates is found to be  $Cu^{2+} > Zn^{2+} > Ni^{2+} > Co^{2+} > Mg^{2+}$ . This is in agreement with that of Irving and Williams<sup>4</sup>.

#### Acknowledgement

The authors record their sincere thanks to Dr. D. G. Vartak, B. A. R. C., Bombay for valuable suggestions.

#### References

1. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
2. H. A. FLASCHKA, "EDTA Titrations", Pergamon Press, Inc., N. Y., 1959.
3. M. S. MAYADEO and H. S. HUSSAIN, *J. Indian Chem. Soc.*, 1979, 56, 143.
4. H. IRVING and R. J. P. WILLIAMS, *J. Chem. Soc.*, 1953, 3192.

#### Electrode Kinetics of the Polarographic Reduction of Ni(II) in the Presence of Increasing Concentrations of L-4-Hydroxyproline and L-Tryptophan

J. C. KHATRI and MUKHTAR SINGH

Department of Chemistry, Agra College, Agra-282 002

Manuscript received 12 January 1981, revised 12 April 1982, accepted 7 June 1982

THOUGH a few polarographic data<sup>1,2</sup> on the electroreduction of Ni(II) in the presence of tryptophan are mentioned in literature, systematic and comprehensive studies on the electrode kinetics of this system are lacking. Besides, studies on the electrode kinetics of Ni(II) in the presence of L-4-hydroxyproline (LHP) have not been reported so far. The present paper aims at studying the influence of increasing concentrations of LHP and L-tryptophan on the kinetics of electrode reaction of Ni(II) under different conditions of pH.

#### Experimental

Solutions of  $Ni(NO_3)_2 \cdot 6H_2O$  and  $NaClO_4$  were prepared from reagent grade (A. R., B. D. H.) chemicals in conductivity water. L-4-Hydroxyproline (LHP) was a Fluka (Puriss, CHR) product, and L-tryptophan was a Reanal (Hungary) A. R. product and their aqueous solutions were used. The concentration of the depolarizer was kept at  $1 \times 10^{-3} M$  in each case and that of supporting electrolyte ( $NaClO_4$ ) at 0.1 M. Requisite amount of Triton X-100 was added to suppress the maximum.

Polarograms of the solutions were taken at  $25 \pm 0.1^\circ$  by a manual set up (Toshniwal polarograph, Model CLO2 in conjunction with a Toshniwal polyflex galvanometer, Model PL 50). Purified nitrogen gas was passed through the solutions to remove the dissolved oxygen. Saturated calomel electrode (S.C.E.) was used as a reference electrode. The number of electrons,  $n$ , involved in the reduction process was determined by millicoulometric method of DeVries and Kroon<sup>8</sup>. This gave the value of  $n$  equal to 2 in each case. Having known the value of  $n$ , the Ilkovic equation was used to calculate the value of  $D$  at different concentrations of LHP and L-tryptophan. The potential-dependent rate constant,  $k_{f,n}$ , was calculated by Koutecky's method<sup>4</sup>. The kinetic parameters,  $\alpha n_a$  and  $k_{f,n}^0$ , were calculated from the plots of  $\log k_{f,n}$  vs  $E_{a,e}$ . Throughout the measurements the current at the end of the drop (i.e. the maximum current) was recorded for the reasons given by Meites<sup>9</sup>.

The d.m.e. had the following capillary characteristics (in 0.1 M NaClO<sub>4</sub>, open circuit): (i) for Ni(II)-LHP system:  $m=2.46$  mg/sec;  $t=2.44$  sec;  $m^{2/3} t^{1/6}=2.11$  mg<sup>2/3</sup> sec<sup>-1/6</sup>;  $h_{0,orr}=61.8$  cm; (ii) for Ni(II)-L-tryptophan system:  $m=1.67$  mg/sec;  $t=4.04$  sec;  $m^{2/3} t^{1/6}=1.78$  mg<sup>2/3</sup> sec<sup>-1/6</sup>;  $h_{0,orr}=63.0$  cm.

## Results and Discussion

### (i) Ni(II)-L-hydroxyproline (LHP) system:

(a) At constant pH 4; Ni(II) gives a single well-defined diffusion-controlled wave in the absence of LHP. With the addition of  $2 \times 10^{-3} M$  LHP a second small wave appears at a more negative potential ( $-1.1$  V vs S.C.E.) whose half-wave potential is  $-1.22$  V (S.C.E.). On further increasing the concentration ( $6 \times 10^{-3} M - 4 \times 10^{-2} M$ ) the  $E_{1/2}$  of the second wave remains the same but at  $[LHP] \geq 6 \times 10^{-3} M$ , the  $E_{1/2}$  becomes  $-1.27$  V (S.C.E.). The wave-heights of both the waves are diffusion-controlled as revealed by the linearity of  $i_d$  vs  $h_{0,orr}$ , plots which pass through the origin. Analysis of these waves by log plots shows that both are irreversible. The more positive (first) wave may be attributed to aquo nickel ion and the second one to some complex species of nickel ion with LHP. This view is supported by the work of Pleticha<sup>6</sup> who obtained two waves for Ni(II) in the presence of histidine, D-arginine and methionine; the more positive wave was attributed by him to uncomplexed nickel. As pointed out above, at higher concentrations ( $> 6 \times 10^{-3} M$ ) of LHP the second wave is shifted to more negative potentials. A likely explanation of this may be that upto a certain concentration of LHP ( $4 \times 10^{-3} M$ ) only one form of Ni(II)-LHP complex is present as a result of interaction between LHP and Ni(II), but at higher concentrations ( $> 6 \times 10^{-3} M$ ) of LHP, a second species of complex is formed due to availability of excess ligand.

(b) At constant pH 8: In the absence of LHP, a single well-defined diffusion-controlled wave of aquo nickel ion is obtained. However, in the

presence of  $1 \times 10^{-3} M$  LHP two well-defined waves appear which are diffusion-controlled and irreversible.  $E_{1/2}$  of the first wave corresponds to the aquo nickel ion and that of the second more negative wave ( $E_{1/2} = -1.22$  V vs S.C.E.) corresponds to some complex species of Ni(II) with LHP. On further increasing the concentration of LHP ( $2 \times 10^{-3} - 8 \times 10^{-2} M$ ) the height of the first wave decreases while that of the second one increases thereby suggesting the participation of more and more nickel ion in the complex formation due to excess availability of the ligand. At still higher concentration of LHP ( $10 \times 10^{-3} M$ ), the first wave disappears and only the more negative second wave persists whose  $E_{1/2}$  is now shifted to more negative potential ( $-1.27$  V vs S.C.E.). On increasing the concentration of LHP beyond  $10 \times 10^{-3} M$ , the  $E_{1/2}$  of this wave records a negative shift. The fact that  $E_{1/2}$  of the second wave changes from  $-1.22$  V (upto  $8 \times 10^{-3} M$  LHP) to  $-1.27$  V (at  $10 \times 10^{-3} M$  LHP) and then to  $\approx 1.37$  V (at LHP concentration  $> 4 \times 10^{-2} M$ ) clearly shows the existence of consecutively formed complex species of Ni(II) with LHP.

(c) Influence of increasing concentrations of LHP on the kinetics of irreversible electrode reaction of Ni(II): On applying various tests of irreversibility<sup>7-10</sup> it has been ascertained that the well-established irreversible electrode reaction of Ni(II) remains the same at pH 4 and 8. As the wave-heights of the second wave at constant pH 4 are comparatively very small, an analysis of kinetic parameters for this wave to a greater degree of precision is not possible. Likewise, the analysis of kinetic data in respect of the first wave at constant pH 8 has not been taken up. Only the kinetic parameters at concentrations of LHP  $> 10 \times 10^{-3} M$ , where single wave appears, have been calculated at this pH.

At constant pH 4,  $\alpha n_a$  increases at lower concentrations ( $< 6 \times 10^{-3} M$ ) of LHP while at higher concentrations ( $> 10 \times 10^{-3} M$ ) it decreases. This shows that<sup>11-13</sup> the irreversible electrode reaction of Ni(II) becomes less irreversible at lower concentrations of LHP while it tends to become more irreversible at higher concentrations. An increase in the value of rate constant,  $k_{f,n}^0$  at lower concentrations of LHP and a decrease in its value at higher concentrations support the above conclusions. At constant pH 8,  $\alpha n_a$  and  $k_{f,n}^0$  decrease with increasing concentrations of LHP thereby showing that the irreversible electrode reaction of Ni(II) tends to become more irreversible in the presence of increasing concentrations of LHP.

(ii) Ni(II)-L-tryptophan system: Ni(II) yields a single well-defined diffusion-controlled and irreversible wave in the presence of increasing amounts of L-tryptophan under different conditions of pH, viz., constant pH 4 and 7. At constant pH 7, a sharp maximum appeared on the plateau of C-V curves which, however, disappeared on the addition of 0.002% Triton X-100.

On applying various tests of irreversibility, it has been ascertained that the well-established irrever-

sible electrode reaction of Ni(II) remains the same under both the two conditions of pH. Under the two conditions of pH the rate constant,  $k_f$ , decreases with increasing concentrations of tryptophan. It follows from this that the irreversible electrode reaction of Ni(II) is rendered increasingly more irreversible as the concentration of tryptophan is increased. The parameter  $\alpha n_a$  also decreases with increasing concentrations of tryptophan under different conditions of pH. The polarographic reduction of Ni(II) is a well-established 2-electron reduction process and therefore  $n_a$ , the number of electrons involved in the rate determining step, can either be 1 or 2. Since the decrease in  $\alpha n_a$  values is indiscrete and at no stage the two consecutive values differ by a factor of 2, the possibility of a decrease in the value of the product  $\alpha n_a$  due to a change in  $n_a$  may be ruled out. Thus it can be safely concluded that it is  $\alpha$  which is decreasing.  $\alpha$ , the transfer coefficient, signifies<sup>18</sup> the fraction of the applied voltage which favours the cathodic reaction,  $\text{Ni}^{2+} + 2e \rightarrow \text{Ni}$ . A decrease in the value of  $\alpha$  thus implies that the transfer of electron/electrons is made increasingly difficult. In other words, the electrode reaction of Ni(II) is rendered increasingly more irreversible as the concentration of L-tryptophan is increased. Thus, the variations in the values of both the kinetic parameters point to the same conclusion.

#### References

1. S. CHANDRA and S. N. SRIVASTAVA, *Indian J. Chem.*, 1969, 7, 829.
2. S. LAL and G. D. CHRISTAN, *J. Prakt. Chem.*, 1971, 313, 99.
3. T. DeVRIES and J. L. KROON, *J. Amer. Chem. Soc.*, 1953, 75, 2484.
4. J. KOUTECKY, *Chem. Listy*, 1953, 47, 323; *Colln. Czech. Chem. Commun.*, 1953, 18, 597; J. KOUTECKY and J. CIZEK, *Coll. Czech. Chem. Commun.*, 1956, 21, 836.
5. L. MEITES, "Polarographic Techniques", Interscience Publ., New York, 1965, p. 241.
6. R. PLETICHA, *Colln. Czech. Chem. Commun.*, 1950, 15, 807; *Chem. Listy*, 1951, 45, 185.
7. L. MEITES, "Polarographic Techniques", Interscience Publ., New York, 1965, p. 232.
8. R. GOTO and I. TACHI, *Proc. Intern. Polarogr. Congr.*, Prague, 1951, 1, 69.
9. P. DELAHAY, *J. Amer. Chem. Soc.*, 1951, 73, 4944.
10. P. KIVALO, K. B. OLDHAM and H. A. LAITINEN, *J. Amer. Chem. Soc.*, 1953, 75, 4148.
11. S. S. SHARMA, S. K. JHA and M. SINGH, *Indian J. Chem.*, 1977, 15A, 742.
12. S. S. SHARMA, S. K. JHA and M. SINGH, *Z. Naturforsch.*, 1977, 32b, 416.
13. S. K. JHA, S. JHA and S. N. SRIVASTAVA, *Z. Naturforsch.*, 1975, 30b, 859.

#### Reactivity of Indian Rock Phosphates in Presence of Oxidative Degradation Products of Coal

D. N. PATHAK

Department of Chemistry, Regional Institute of Technology,  
Jamshedpur-831 014

Manuscript received 1 November 1980, revised 20 October 1981  
accepted 28 April 1982

**T**HE oxidative degradation products of coal, obtained by the action of potassium permanganate in presence of rock phosphate in aqueous solution, increase the reactivity of rock phosphates

resulting in the dissolution of more phosphatic content in water.

A variety of oxidizing agents, mostly in acidic medium, were used in the past for controlled low temperature degradation of coal<sup>1</sup>. Later, oxidation of coal in alkaline medium using potassium permanganate was studied in detail<sup>2-6</sup>. The different parameters upon which the oxidative degradation of coal in alkaline medium is dependent was investigated very recently by Banerji<sup>7</sup>. Contradictory reports<sup>8,9</sup> on the reactivity of Indian rock phosphates posed a great problem of its utility to chemists all over the world. The work of Johnston<sup>10</sup> on the dissolution of insoluble phosphate in aqueous solutions of organic acids prompted the author to design the present investigation for determining the extent of reactivity by water soluble organic acids produced in the oxidative degradation of coal by potassium permanganate in presence of rock phosphates.

#### Experimental

Rock phosphates from Rajasthan, Uttar Pradesh and Bihar, obtained through Geological Survey of India, were powdered, sieved (100 mesh, B.S.S.) and analysed according to the procedure of Washington<sup>11</sup>.

A number of stoppered conical flasks were taken and 1g finely powdered sample of each rock phosphate, 0.5 g coal (dmf, 36 mesh BSS, C=80%) and 100 ml 0.1 N  $\text{KMnO}_4$  solution were added in each of the flasks. The flasks with their contents were kept agitated in a mechanical shaker at room temperature (27°). After definite intervals of time the solution of each flask was allowed to stand for some time, filtered and washed with water through a sintered glass crucible. Aliquot portions were utilized for determining  $\text{P}_2\text{O}_5$  and for measuring the extent of oxidative degradation<sup>12</sup>. A blank (mineral + water) estimation was also simultaneously carried out.

Phosphate was estimated volumetrically after precipitating with ammonium molybdate solution.

In order to measure the extent of oxidative degradation, a suitable portion of the aliquot was treated with solid KI and acidified with conc. HCl. The liberated iodine was titrated against a standard thiosulphate solution using starch as an indicator. Permanganate consumed by coal in different time intervals was calculated from the titre values.

#### Results and Discussion

The analysis (Table 1) shows that the rock phosphates contain varying amounts of  $\text{P}_2\text{O}_5$  (12 to 30%), magnesium and iron, suitable for healthy plant growth. It is interesting to record that all the rock phosphates are alkaline in aqueous solutions.

The experimental results (Tables 2 and 3) show that the release of phosphate from rock phosphates by water is not much. However, with water soluble aromatic polycarboxylic acids, produced as a result of degradation of coal by oxidizing action of alkaline

TABLE 1—COMPOSITION OF VARIOUS ROCK PHOSPHATES

Ingredients	RP	MNP	MPS	MGP	MVLP	MRP	I(B)RP
%							
Insoluble material	5.60	7.56	26.05	5.90	17.26	3.24	24.14
Al <sub>2</sub> O <sub>3</sub>	1.42	23.05	23.92	25.51	33.90	31.26	18.96
Fe <sub>2</sub> O <sub>3</sub>	0.28	0.25	0.24	0.25	0.32	0.96	12.17
CaO	44.98	32.15	17.00	16.45	15.50	11.38	9.81
MgO	0.08	0.09	0.06	0.05	0.05	0.04	0.35
P <sub>2</sub> O <sub>5</sub>	27.18	15.46	10.34	30.17	11.97	30.72	15.60

RP - Rajasthan Phosphate,  
MNP - Mussorie Nodular Phosphorite,  
MPS - Musorie Phosphorite Shale,  
MGP - Mussorie Granular Phosphorite,  
MRP - Mussorie Rock Phosphate,  
I(B)RP - Itagarh (Bihar) Rock Phosphate.

TABLE 2—RELEASE OF P<sub>2</sub>O<sub>5</sub> (G/L) FROM ROCK PHOSPHATES IN WATER AFTER 24 HR AT 27°

Period	RP	MNP	MPS	MGP	MVLP	MRP	I(B)RP
After 24 hr	0.0052	0.0045	0.0012	0.0040	0.0009	0.0033	0.0025

TABLE 3—RELEASE OF P<sub>2</sub>O<sub>5</sub> (G/L) FROM ROCK PHOSPHATES IN THE OXIDATIVE DEGRADATION OF COAL AT 27°

Period	RP	MNP	MPS	MGP	MVLP	MRP	I(B)RP
After 2 hr	0.0110	0.0076	0.0023	0.0071	0.0017	0.0063	0.0048
After 4 hr	0.0137	0.0099	0.0035	0.0090	0.0030	0.0077	0.0060
After 6 hr	0.0163	0.0115	0.0047	0.0105	0.0043	0.0091	0.0077
After 8 hr	0.0223	0.0158	0.0083	0.0145	0.0075	0.0128	0.0115

permanganate in aqueous solution, the release increases to a marked extent. The colour of permanganate changes gradually from brown to colourless at the end of 8 hr showing thereby that the reduction occurs in a step wise process.



According to Banerjee<sup>7</sup>, for a typical low rank coal (C=79.2%), the optimum volume and concentration of permanganate solution for complete oxidation, i.e. when no coal particle is left over as residue, are  $20.2 \times 10^{-3}$  mole/litre and 225 ml/g of coal (dmf), respectively. The release of P<sub>2</sub>O<sub>5</sub> from various rock phosphates shows a progressive increase with lapse of time. This is because of the fact that degradation of coal, which continues upto above 8 hr, produces more and more water soluble organic acids which help in the dissolution of increasing amount of phosphatic content.

During the course of this investigation it was noticed that after a few hours the solutions in all the systems became colloidal. This is because of the formation of finely divided hydrated manganese oxide as a result of the reduction of permanganate and intermediate formation of humic acid on account of degradation of coal. With lapse of time, further degradation of humic acid into benzene carboxylic acids occurs and the solution becomes clear.

Thus, the reactivity of Indian rock phosphates increases to an appreciable extent by the permanganate oxidation of coal.

## References

1. H. C. HOWARD and H. H. LOWRY (Ed.), "Chemistry of Coal Utilization", John Wiley & Sons, Inc., New York, 1945, pp. 358-72. Example cited in *Ind. Eng. Chem*, 1952, 44, 2784.
2. F. FISCHER and H. SCHARADER, *Gessam Abh. Kohle*, 1920, 5, 200.
3. W. A. BONE, L. HORTON and S. G. WARD, *Proc. Roy. Soc., London*, 1930, 127A, 480.
4. W. A. BONE, L. G. E. PARSONS, R. A. SHAPIRO and G. M. GROOCCOCK, *Proc. Roy. Soc., London*, 1935, 148A, 492.
5. W. A. BONE and R. QUARENDON, *Proc. Roy. Soc., London*, 1926, 110A, 537.
6. W. A. BONE and B. J. A. BARD, *Proc. Roy. Soc., London*, 1937, 162A, 495.
7. A. BANERJEE, *Indian J. Tech.*, 1980, 18, 153.
8. B. DAS, *J. Indian Chem. Soc.*, 1976, 53, 623.
9. D. C. GAMI, J. A. SANOHANIA and S. L. AGARWAL, Example cited in *Indian J. Tech.*, 1979, 17, 65.
10. H. W. JOHNSTON, *New Zealand J. Sci.*, 1959, 2, 109.
11. H. S. WASHINGTON, "Chemical Analysis of Rocks", John Wiley & Sons, Inc., New York, 10th Edn., 1930.
12. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", Longmans Green & Co., London, 3rd Edn., 1961.

## Triazolo [3, 4-b] [1, 3, 4] thiadiazoles

H. K. GAKHAR, ANJU JAIN

and

SHASHI BHUSHAN GUPTA


Chemistry Department, Panjab University,  
Chandigarh-160 014Manuscript received: 29 September 1981,  
accepted 11 March 1982

LITERATURE records<sup>1-3</sup> the synthesis of some *s*-triazolo [3, 4-b] [1, 3, 4] thiadiazoles. One such synthesis is by George *et al*<sup>4</sup> but the yields recorded are low. We report here the synthesis of some new *s*-triazolo [3, 4-b] [1, 3, 4] thiadiazoles by the modification of the above procedure, where very good yields of the compounds were obtained.

The compounds have been prepared by the condensation of 4-amino-5-mercapto-3-methyl-*s*-triazole (I) with various aldehydes in the presence of sodium acetate. The structure (III) for these compounds finds support from analysis and pmr data. PMR\* of IIIa in CDCl<sub>3</sub>-DMSO-d<sub>6</sub> showed a doublet (3H) at 2.37 assignable to three methyl protons at position 6. It also showed a singlet (3H) at 3.20 assignable to three protons of methyl group at position 3. The signals due to one proton attached to C<sub>5</sub> and one proton attached to nitrogen overlapped and gave a broad signal at 5.20.

\*Chemical shifts in  $\delta$  (ppm).

Structure III finds further support from its insolubility in dil. NaOH solution.



- a, R = CH<sub>3</sub> -  
 b, R = C<sub>6</sub>H<sub>5</sub> -  
 c, R = C<sub>6</sub>H<sub>4</sub>NO<sub>2</sub> - (3')  
 d, R = CH<sub>3</sub>O, C<sub>6</sub>H<sub>4</sub> - (3', 4')  
 e, R = CH<sub>3</sub>O, C<sub>6</sub>H<sub>4</sub>.NH<sub>2</sub> - (3', 4', 6')

### Experimental

Melting points were taken in open glass capillaries in liquid paraffin bath and are uncorrected. PMR spectra were recorded on Varian 360 60 MHz spectrometer. Purity of the compounds was checked by tlc on silica gel.

**4-Amino-5-mercapto-3-methyl-s-triazole (I):** It was prepared starting from thio-carbohydrazide<sup>8</sup> and excess of acetic acid according to the procedure described by Saikachi and Kanaoka<sup>9</sup>.

**3,6-Dimethyl-5,6-dihydro-s-triazolo [3,4-b] [1,3,4] thiadiazole:** A slow stream of dry hydrochloric acid gas was passed through a chilled ethereal suspension (20 ml) of 4-amino-5-mercapto-3-methyl-s-triazole (1.3 g; 0.01 mole) till it was saturated. Ether was decanted off completely and the residue was suspended in absolute ethanol (40 ml). To this, fused sodium acetate (0.90 g; 0.011 mole) and freshly distilled acetaldehyde (2.2 g; 0.05 mole) were added. The contents were refluxed over a steam bath under nitrogen atmosphere. The suspension started dissolving and a new solid separated out. Refluxing was continued for 4 hr when it was cooled. The separated solid was collected under suction and washed with water. Crystallisation from ethanol gave faint cream coloured long plates, m.p. 211°, yield 1.0 g (65%).

TABLE 1—METHYL-5,6-DIHYDRO-S-TRIAZOLO [3, 4-b] [1, 3, 4] THIADIAZOLES WITH SUBSTITUTIONS IN POSITION 6.

Sl. No.	R	Time taken for the reaction (hr)	m.p. °C	Yield %
a	CH <sub>3</sub>	4	211	65
b	C <sub>6</sub> H <sub>5</sub>	4	203	75
c	C <sub>6</sub> H <sub>4</sub> NO <sub>2</sub> -(3')	8	227	60
d	CH <sub>3</sub> O, C <sub>6</sub> H <sub>4</sub> -(3', 4')	4	219	68
e	CH <sub>3</sub> O, C <sub>6</sub> H <sub>4</sub> .NH <sub>2</sub> -(3', 4', 6')	6	300	55

All the compounds were crystallised from ethanol. All compounds give consistent C, H and N analysis.

Similarly, other aldehydes, namely benzaldehyde, *m*-nitrobenzaldehyde, piperonal and *o*-amino piperonal were condensed with 4-amino-5-mercapto-3-methyl-s-triazole. The yield of these products, their m. p. and time required for the reaction are tabulated in Table 1. All the compounds were crystallised from ethanol. They also gave consistent carbon, hydrogen and nitrogen analysis.

### Acknowledgement

The authors are thankful to Prof. M. L. Lakhanpal, Chairman, Chemistry Department, Panjab University for the facilities, Mr L. K. Khullar for elemental analysis and Mr. Avtar Singh for the pmr spectrum of the compound.

### References

1. M. KANAOKA, *J. Pharm. Soc., Japan*, 1956, 76, 1133.
2. K. T. POTTS and R. M. HUSCKY, *J. Org. Chem.*, 1966, 31, 3528.
3. M. KANAOKA, *Chem. Pharm. Bull., Tokyo*, 1957, 5, 385.
4. T. GEORGE, R. TAHILRAMANI and D. A. DABHOLKAR, *Indian J. Chem.*, 1969, 7, 959.
5. L. F. AUDRIETH, E. S. SCOTT and P. S. KIPPUR, *J. Org. Chem.*, 1954, 19, 733.
6. H. SAIKACHI and M. KANAOKA, *Yakugaku Zasshi*, 1962, 82, 683; *Chem. Abs.*, 1963, 58, 4543

### Synthesis and Antifungal Activity of Oxazolones

M. R. MANRAO\*, R. C. SHARMA, B. S. DHIR  
 and  
 P. S. KALSI

Department of Chemistry, Punjab Agricultural University,  
 Ludhiana-141 004

Manuscript received 5 February 1981,  
 revised 22 December 1981, accepted 11 March 1982.

**4-(2-Chlorophenylhydrazono)-3-methyl-5-isoxazolone** is the only compound in the oxazolone and isoxazolone family of compounds which has been used against fungus<sup>1</sup>. During our work on the synthesis and activity studies of some new heterocyclic compounds, we found that 2-phenyl-4-( $\alpha$ -methylbenzal)-5-oxazolones are quite active against fungus. This paper describes synthesis of some oxazolones and their activity against the fungi *Alternaria solani*, *Colletotrichum capsici* and *Choanephora cucurbitarum*.

**2-Phenyl-4-( $\alpha$ -methylbenzal)-5-oxazolones (III)** have been prepared by the reaction of azlactone, prepared *in situ* by the action of acetic anhydride on hippuric acid in presence of sodium acetate, with  $\alpha$ -methylbenzalbenzylamines. The products are obtained probably by the elimination of benzylamine from the addition products of azlactone with corresponding imines. First step in the mechanism<sup>2,3</sup> is the abstraction of a proton from the active methylene function of azlactone to give an enolate which undergoes electrophilic addition with the imines to yield unstable addition product (II). Subsequent

elimination of benzylamine in presence of base affords III as shown in Chart 1.




Chart 1

The oxazolone structure assigned to these products has support from elemental analysis, ir, nmr and mass spectra. IR spectrum of IIIa showed bands at 1750 and 1670  $\text{cm}^{-1}$  indicative of carbonyl group and C=N linkage, respectively. NMR spectrum of IIIb showed three methyl protons as a singlet at 7.7  $\tau$  and nine aromatic protons as a multiplet between 2.2 to 2.8  $\tau$ . In mass spectra, molecular ion peaks constituted the base peaks. Mass and nmr spectra further indicated that acylation of OH and  $\text{NH}_2$  groups also took place under the reaction conditions.

The products (Table 1) are found to be identical (m.m.p.) with the authentic samples of the respective oxazolones synthesized by an unambiguous route<sup>4</sup>.

TABLE 1—2-PHENYL-4-( $\alpha$ -METHYLBENZYL)-5-OXAZOLONES (III)

Compound	R	m.p. <sup>a</sup> °C	Yield %
IIIa	<i>p</i> -OC <sub>6</sub> H <sub>5</sub>	37	70
IIIb	<i>p</i> -Cl	250	80
IIIc	<i>p</i> -OCOCH <sub>3</sub>	100	75
IIId	<i>m</i> -NO <sub>2</sub>	70	80
IIIe	<i>p</i> -CH <sub>3</sub>	167	80
IIIf	<i>p</i> -NHCOCH <sub>3</sub>	143	75
IIIg	<i>o,p</i> -Br <sub>2</sub>	138	70
IIIh	<i>o,p</i> -(OCOCH <sub>3</sub> ) <sub>2</sub>	153	70

<sup>a</sup>All melting points are uncorrected.

All the compounds gave satisfactory elemental analysis.

The above oxazolones (IIIa-IIIh) along with 2-phenyl-4-( $\alpha$ -methylbenzal)-5-oxazolone (IIIi) and 2-phenyl-4-( $\alpha$ -methyl-*p*-bromobenzal)-5-oxazolone (IIIj) were tested for their antifungal activity against *Alternaria solani*, *Colletotrichum capsici* and *Choanephora cucurbitarum* by poisoned food technique. For each compound three concentrations viz. 1000, 500 and 250 ppm were tried. Compounds IIIb, IIId, IIIf, IIIg and IIIh completely inhibited all the three fungi at 1000 ppm. The other five compounds were not so effective even at 1000 ppm. A detailed study of the structure activity relationship showed that the presence of Cl, NO<sub>2</sub> and NHCOCH<sub>3</sub> groups in phenyl ring of oxazolone increased the activity of unsubstituted oxazolone IIIi. Another interesting feature of the study was that while the presence of one Br or OCOCH<sub>3</sub> in the phenyl ring had little effect on the activity, presence of two Br or two OCOCH<sub>3</sub> in the phenyl ring (IIIg and IIIh) made these oxazolones the most effective.

### Experimental

**Reaction of azlactone with  $\alpha$ -methyl-*p*-chlorobenzal-benzylamine:** Hippuric acid (1.8 g) and  $\alpha$ -methyl-*p*-chlorobenzalbenzylamine (0.01 mole) were dissolved in dry benzene (50 ml). Acetic anhydride (1.2 ml) and sodium acetate (0.5 g) were added to the solution. The mixture was just heated to get a clear solution and left at room temperature for 2 days. During this period most of the product precipitated which was filtered off. The mother liquor on concentration gave more of the product. The product was recrystallized from hot benzene, m.p. 250° (yield 80%). Other oxazolones were synthesized in similar manner.

### References

- G. S. HARTLEY and T. F. WEST, "Chemicals for Pest Control", Pergamon, Oxford, 1969, p. 288.
- M. RAI and A. SINGH, *Indian J. Chem.*, 1976, 14B, 377.
- S. KUMAR, M. RAI, K. KRISHAN and A. SINGH, *Chem. Ind.*, 1979, 211; *J. Indian Chem. Soc.*, 1979, 56, 432.
- A. H. BLATT, "Organic Synthesis", Coll. Vol. II, John Wiley, New York, 1961, 55.

### Amoebicidal Testing of Drugs—Use of Goat Serum as a Substitute for Horse Serum for Growing *Entamoeba histolytica*

S. DUTTA, A. PAL, B. P. DEY and S. C. LAHIRI

Department of Chemistry, University of Kalyani,  
Kalyani-741 235

Manuscript received 30 June 1981, revised 15 December 1981,  
accepted 11 March 1982

**A**MOEBIASIS is one of the most prevalent diseases in tropical countries like India. Unfortunately, even today, the disease is not diagnosed adequately and critically though prolonged amoebiasis causes ulcerations, hepatic complications, liver

shades and other associated diseases. It is, however, well established that an ideal antiamoebic agent should be capable of eradicating the causative organism *Entamoeba histolytica* both from the bowel and from extra intestinal sites at non-toxic doses<sup>1,2</sup>. Though a number of useful drugs have been synthesised, they are not found to be universally effective or ideal and are usually associated with side effects. Moreover, need for drugs with sustained prophylactic actions are widely felt<sup>2</sup>. But no single preparation satisfy all these requirements.

In our attempt to study the synthesis of new antiamoebic drugs based on the physico-chemical properties of different known antiamoebic drugs and their biological properties, it has been found necessary to screen the different antiamoebic agents in the laboratory by proper *in vitro* testing.

*E. histolytica* is generally grown in Boeck and Drbohlav medium consisting of egg slant of horse serum overlay with bacteria plus rice starch. In view of high cost of horse serum and the difficulty in obtaining its regular supply, Dutta<sup>3</sup> used bovine serum as a substitute for growing *E. histolytica*. However, availability of goat serum is comparatively easy in Kalyani and we prefer to use goat serum as a substitute for horse serum.

We report in this communication our attempt to use goat serum as a substitute for horse serum or bovine serum for growing *E. histolytica*, and to standardize and test the method by using some known antiamoebicides and screen a few unknown compounds. Study of amoebicidal properties of drugs in different media would be helpful in comparing amoebicidal action of antiamoebic drugs against axenically grown *E. histolytica* and in different medium using horse, bovine or goat serum.

## Experimental





**Preparation of serum:** For the preparation of serum and screening of drugs, we followed the same procedure as reported by Dutta *et al.*<sup>3</sup>. Fresh goat blood was collected from Kalyani market in a thermoflask. The serum was decanted, centrifuged at 2000 rpm for about half an hour and filtered through sintered glass filter. The filtered serum was taken in a clean dry sterilised conical flask, inactivated in a thermostat at 56° for about 1 hr and stored at 4°. The stored serum was diluted eight fold with 0.85% normal saline in M/40 phosphate buffer (pH=7.0) before use.

**Technique of cultivation:** A series of test tubes and Erlenmeyer flasks were thoroughly cleaned, dried, plugged with cotton and sterilised at 150° for 1 hr in an air-oven. 8 eggs (Hen) were thoroughly cleansed with detergent and subsequently sterilized with alcohol. The eggs were broken and the contents emulsified with M/40 phosphate buffer and filtered through a sintered glass filter. Different strains of *E. histolytica* were grown in the flasks with diluted goat serum, mixed bacterial flora and rice starch at 37°. Sub-cultures were made every

48 hr. 5 ml of emulsified egg solution was poured in each of the sterilised test tubes placed at an angle of 45° and heated at 80° for 1 hr in an air-oven. The heating was repeated thrice in succession. The appearance of turbidity in the contents of the medium indicated lack of proper sterilization and caused immediate rejection. *E. histolytica* was cultured in these test tubes. 0.2% solutions of acriflavim and gentian violet were used to prevent overgrowth of fungal and bacterial flora.

**Isolation of strain of *E. histolytica*:** LD strain of *E. histolytica* was isolated from fresh stool samples collected from Usha 'X'-ray clinic, P. O. Ranaghat, Nadia. Both trophozoite and cystic forms of *E. histolytica* were present. The sample was washed with 0.85% NaCl solution and transferred into goat serum medium. This was repeated several times and the contents were examined under the microscope (10X-90X). Trophozoite form of *E. histolytica* was collected in this way and preserved. Strain collected from the School of Tropical Medicine, Calcutta, was also used.

TABLE 1—*In vitro* ACTIVITIES OF AMOEBICIDAL DRUGS

Drugs	Amoebicidal concentration ( $\mu$ g/ml) 48 hr
Enterokinol	62.5
Enterovioform	62.5
Dilidoquinol	500.00
Chloroquine-phosphate	500.00
Metronidazole	7.81
5-Chloro-7-nitro-8-hydroxy quinoline <sup>+</sup>	15.6
	
Emetine hydrochloride	7.81
Glycobiarsol	500.00
Furanidazole	62.5
Clephamide	62.5
6-Amino-5-spiro-(4,5)-decane/hydrochloride <sup>+</sup>	15.6
	
1-n-Butyl-3,4-dimethoxy-5-amino-5,6,7,8,9-pentahydro-benzocyclo heptene/hydrochloride <sup>+</sup>	62.5
	
1-n-Butyl-3,4-dimethoxy-5-dimethyl amino-5,6,7,8,9-pentahydro-benzocyclo heptene/hydrochloride <sup>+</sup>	250.00
	

<sup>+</sup> The compounds were synthesised by Prof. B. C. Pathak *et al.*, Department of Applied Chemistry, University of Calcutta. The other drugs were procured from The Central Drug Laboratory, Calcutta and from Prof. B. C. Pathak.

TABLE 2—COMPARISON OF AMOEBCIDAL ACTIVITIES ( $\mu\text{g/ml}$ ) REPORTED BY VARIOUS WORKERS

	Philips <sup>a</sup>	Nakamura and Anderson <sup>a</sup>	Bradner and Rawson <sup>a</sup>	Diamond and Bartgis <sup>10</sup>	Dutta and Yadava <sup>a</sup>	Present study
Strain of <i>E. histolytica</i>	F-22	F-22	F-22	F-22	NIH 200	LD 1
Period of incubation with drug	48 and 72 hr	48 hr	48 hr	72 hr	72 hr	48 and 72 hr
Emetine-hydrochloride	5	10	31.2	6	11.7	7.8 <sup>a</sup> (3.9-7.8 <sup>a</sup> )
Metronidazole	—	—	—	0.75-1.5	3.9	3.9-7.8 <sup>a</sup>
Enterovioform	—	40-50	125	—	31.2	62.5
Chloroquine phosphate	—	—	—	—	1000	500
Diiodoquine	—	200	1000	—	375	500

<sup>a</sup>Upper limit (3.9-7.8<sup>a</sup>—activity is observed within these limits)

**Examination and sub-culture of *E. histolytica*:** Four day old cultures were examined under an inverted microscope (10X ocular and 20X objective) and the tubes showing  $20-30 \times 10^4$  amoebae/ml were used as seed for sub-culturing fresh tubes. For sub-culture, 0.2 ml of this amoebic suspension was inoculated into each tube containing 8.8 ml of the medium and the cultures were incubated vertically at 37°.

**Drug testing:** Most of the drugs are insoluble in water. Some of the drugs are dissolved in a little DMF solution. In general, fine suspensions of drug were made by adding gum acacia. 1 ml of drug suspension in normal saline (10 mg/ml) was added to each culture tube containing 9 ml inoculated medium (8.8 ml medium+0.2 ml inoculum) in duplicate to give a drug concentration of 1000  $\mu\text{g/ml}$  per tube. Each tube contained  $23.75 \times 10^4$  amoebae/ml. Successive two-fold serial dilutions (eight) of the drug in sterile normal saline was added in subsequent duplicate tubes. Strict aseptic conditions were maintained. Drug suspensions were sterilized by autoclaving at 10 lb/sq inch for 15 min at 120°. The tests were run for 72 hr (though 48 hr are sufficient) and incubation was carried out at 37°. Amoebicidal end point was examined on the basis of presence or absence of living amoebae by direct observation under a microscope and by sub-culture.

The operations were repeated to examine the reproducibility of the results. The results of some known and unknown drugs are recorded in Table 1.

*In vitro* activities of antiamoebic drugs against *E. histolytica* have been widely reported<sup>4, 10</sup>. Variations of end points depending on conditions are also noted.

#### Discussions

The results presented in the Table 1 and Table 2 show that goat serum can be successfully utilised instead of horse serum for the culture of *E. histolytica*. The results also show that all the unknown compounds particularly spiroamino

hydrochloride and 5-chloro-7-nitro-hydrooxyquinoline can be successfully used as antiamoebic drugs. Spiroamino hydrochloride and its derivatives should receive special attention as amoebicidal properties of these compounds are not yet reported.

It will be quite pertinent to compare some of results with those reported earlier (Table 2). Slight variations in results appear reasonable in view of different strains and culture media. Furthermore, insolubility of the drugs poses a big problem and variations of minimum inhibitory concentration (MIC) appear natural. We have reported the upper limits of MIC taking into consideration all these limitations.

#### Acknowledgement

One of the authors (A. P.) thanks U. G. C., New Delhi for a Research Fellowship. The authors are thankful to Dr T. N. Ghosh (School of Tropical Medicine, Calcutta) and Dr. D. P. Halder, Kalyani University for valuable suggestions and to Prof. B. C. Pathak and his associates, particularly Dr. R. Mukherjee, for supplying the unknown compounds.

#### References

1. E. F. ELSLAGER, in "Medicinal Chemistry", (Ed.) A. BURGER, 3rd Ed, Part-I, Wiley Interscience, 1970, Chapter 21.
2. R. F. DOERGE, in "Text Book of Organic Medicinal and Pharmaceutical Chemistry", (Ed.) C. O. WILSON, O. GISVOLD and R. F. DOERGE, 6th Ed., J. B. Lippincott Company, Philadelphia and Toronto, 1971, Chapter 9.
3. G. P. DUTTA, *Indian J. Microbiology*, 1966, 6, 83.
4. G. P. DUTTA and J. N. S. YADAVA, *Indian J. Med. Res.*, 1972, 60, 1156.
5. J. N. S. YADAVA and G. P. DUTTA, *Indian J. Med. Res.*, 1973, 61, 921.
6. G. WOOLFE, in "Experimental Chemotherapy" I, (Ed.) R. J. SCHNITZER and F. HAWKING, Academic Press, New York, 1963, p. 355.
7. B. P. PHILLIPS, *Amer. J. Trop. Med.*, 1951, 31, 561.
8. M. NAKAMURA and H. H. ANDERSON, *Exp. Parasitol.*, 1951, 1, 66.
9. W. T. BRADNER and G. W. RAWSON, *Science*, 1951, 113, 674.
10. L. S. DIAMOND and I. L. BARTGIS, *Arch. Invest. Med. (Mex.)*, 1971, 2, (Suppl.), 339.



# Phytochemical Studies on *Eclipta alba*

B. C. SIKRORIA, S. J. SRIVASTAVA and  
G. S. NIRANJAN\*

Department of Chemistry, D. V. (P. G.) College,  
Orai-285 001, U. P.

Manuscript received 25 August 1981, revised 8 February 1982,  
accepted 11 March 1982

**ECLIPTA alba** (Compositae), popularly known as 'Bringraj' is an annual herb, growing in moist environment all over India. It is reputed for its high medicinal values<sup>1</sup>. A perusal of literature revealed that the leaves and stems of the plant have been examined chemically<sup>2-7</sup> but no phytochemical study of the roots of this plant seems to have been done. A systematic study of this part was therefore undertaken and the results are reported here.

The dried and crushed roots (2 Kg) were extracted exhaustively with hot petroleum ether (60-80°) and ethanol successively. The concentrated petroleum ether extract was saponified with 0.5 N KOH. It yielded an unsaponifiable matter which was extracted with ether. The aqueous layer had some insoluble floating material which was separated and dissolved in chloroform. Chloroform was distilled off under reduced pressure to give a cream coloured solid which on column chromatography over silica gel afforded compound (A) and (B). The concentrated ether extract was chromatographed with petroleum ether : ether (1 : 4) to give compound (C). After refluxing with benzene the concentrated ethanolic extract of the root was chromatographed over silica gel to give compound (D).

**Compound (A)** : Elution with petroleum ether : benzene (1 : 1) yielded a white compound, m.p. 86-87°,  $C_{31}H_{64}O$ ;  $\nu_{max}^{KBr}$   $cm^{-1}$  3289, 775 and 772, mass spectrum,  $m/e$  434 [ $M^+ - H_2O$ ], 406 [ $M^+ - H_2O - C_2H_5$ ] and 31 ( $-CH_2OH$ ).

It was characterised as hentricontan-ol<sup>8</sup> by co-tlc and m.m.p. with an authentic sample and by preparing its acetate, m.p. 69-70°, iodide, m.p. 69° and hentricantanoic acid, m.p. 98°.

**Compound (B)** : Elution with ethanol : benzene (1 : 1) afforded a white solid compound, m.p. 78-79°,  $C_{32}H_{66}O$ ,  $\nu_{max}^{KBr}$   $cm^{-1}$  3440, 1100, 765 and 720. It formed an acetate, m.p. 44-45°. It was identified as heptacosanol-14 by co-tlc and m.m.p. with an authentic sample.

**Compound (C)** : Elution with petroleum ether : ether (1 : 4) gave colourless needles, m.p. 166-68°,  $C_{30}H_{60}O$ , [ $\alpha$ ]<sub>D</sub><sup>25</sup> +46°;  $\nu_{max}^{KBr}$   $cm^{-1}$  3510, 1650, 995, 845 and 800. It responded to all the tests for a sterol. It formed an acetate, m.p. 141-43° and benzoate m.p. 158-60°. The identity of this compound with stigmasterol was established by m.m.p. and co-tlc with an authentic sample.

**Compound (D)** : Elution of the column with petroleum ether : benzene (1 : 3) afforded a white crystalline compound, m.p. 196-98°,  $C_{30}H_{50}O$ , [ $M^+$  426],

[ $\alpha$ ]<sub>D</sub><sup>25</sup> +84°. It gave LB tests and Nollers reaction for triterpenoids. IR,  $\nu_{max}^{KBr}$   $cm^{-1}$  3200, 1653, 1470, 1000 and 828; acetate, m.p. 237-39° and benzoate, m.p. 233-35°. The identity of the compound was established by m.m.p. and co-tlc with an authentic sample.

## Acknowledgement

The authors are thankful to Dr. P. C. Gupta, University of Allahabad, Allahabad for providing the authentic samples and Director, C.D.R.I., Lucknow, for spectroscopy. The authors are also grateful to the U.G.C. (B.C.S.) and C.S.I.R. (S.J.S.) for the award of Junior Research Fellowship.

## References

1. J. F. DASTUR, "Medicinal Plants of India and Pakistan", D. B. Taraporevala Sons and Co. Private Ltd, Bombay, p. 77
2. T. R. GOVINDACHARI, K. NAGRAJAN and B. R. PURI, *J. Sci. Ind. Research*, 1956, 158, 664.
3. F. BOHLMANN, K. M. KLEINE and C. ARNDT, *Chem. Ber.*, 1964, 97, 2125.
4. N. R. KRISHNASWAMI, T. R. SESHADRI and B. R. SHARMA, *Tetrahedron Lett.*, 1966, 35, 4227.
5. K. K. BHARGAVA, N. R. KRISHNASWAMI, T. R. SESHADRI and P. TIRUVENKATA, *Indian J. Chem.*, 1970, 8, 664.
6. K. K. BHARGAVA, N. R. KRISHNASWAMI and T. R. SESHADRI, *Indian J. Chem.*, 1972, 10, 810.
7. S. N. PAL and M. NARASIMHAN, *J. Indian Chem. Soc.*, 1943, 20, 181.
8. H. BUDZIKIEWICZ, C. DJERASSI and H. WILLIAMS, "Mass Spectrometry of Organic Compounds", Holden-Day, Inc., London, 1967, p. 99.
9. I. HEILBRON, H. M. BUNBURY, A. H. COOK and E. R. H. JONES, "Dictionary of Organic Compounds", Eyre and Spottiswoode, London, 1953, Vol. IV, p. 538.

## Use of Potassium Bromate : Oxidation of Aldehydes

HARAPRASAD SAMADDAR

Chemistry Department, Ramakrishna Mission Residential College, Narendrapur, 24-Parganas, West Bengal

and

AMALENDU BANERJEE

Chemistry Department, Jadavpur University,  
Calcutta-700 032

Manuscript received 2 June 1981, revised 21 December 1982,  
accepted 7 June 1982

**BENZALDEHYDE** was oxidised to benzoic acid with potassium bromate under acidic condition in this laboratory<sup>1</sup>. The established optimum condition has been utilised for the oxidation of *o*-, *m*-, *p*-nitrobenzaldehydes, *o*-, *m*-, *p*-chlorobenzaldehydes, *o*-, *m*- and *p*-methoxybenzaldehydes to furnish the corresponding substituted benzoic acids in almost quantitative yield. Only *o*- and *m*-methoxybenzoic acids were found to undergo bromination to some extent during oxidation in acetic acid. This

difficulty has been overcome by using acetone as the bromine scavenger. But salicylaldehyde and vanillin could not be oxidised to the corresponding acids under similar experimental condition showing that phenolic aldehydes are unsuitable for bromate oxidation. Cinnamaldehyde produced cinnamic acid in moderate yield indicating that the double bond remained unaffected by bromate. Citral, on the other hand, failed to produce the desired acid and butyraldehyde furnished impure butyric acid. Bromine was evolved in each case. It appeared that aliphatic aldehydes were difficult to oxidise. It was also observed that the use of dilute sulphuric acid during the bromate oxidation of substituted benzaldehydes holding ring-activators favoured the introduction of bromine atom in the ring in a regioselective manner, the electron attracting groups accelerated the rate of oxidation while the electron releasing groups retarded it. From the kinetic study<sup>8</sup> carried out in dilute acetic acid solution, it has been found that the rate of oxidation of the aldehyde at temperature ranging from 40 to 60° is dependent on the substrate and acetic acid but not on the oxidant. The oxidation of other classes of organic compounds is under investigation.

### Experimental<sup>1</sup>

**General procedure:** A mixture of weighed amount of substituted benzaldehyde and half its weight of potassium bromate in acetic acid (15 ml per g of starting aldehyde) was heated under reflux for 15 min. Bromine evolved which escaped the reaction mixture. The latter was cooled, poured onto water, saturated with sodium chloride and extracted thrice with chloroform. The organic layer was extracted with saturated sodium bicarbonate solution, washed with water and dried over anhydrous sodium sulphate. On removal of the solvent no starting material was obtained excepting cinnamaldehyde, salicylaldehyde and citral. The alkaline extract was acidified with dilute sulphuric acid (congo red) and the precipitated organic acid was extracted thoroughly with either chloroform or ether. The organic layer was washed with small amount of water, dried and the solvent removed to furnish the desired acids which were crystallised, if required, for further purification. The results are presented in the order: derived acid (% yield), melting point<sup>2,3</sup>, spectral data and/or other supporting evidence and [Remarks if any]. The ir spectra were taken in Perkin-Elmer Model 597 Infrared grating spectrophotometer. The m.m.p. of each solid product with authentic specimen remained undepressed. (a) 2-Nitrobenzoic acid (95%), 142°<sup>2,3</sup>. (b) 3-Nitrobenzoic acid (99%), 136°<sup>2,3</sup>, N.E. 165±5 [no bromination during oxidation if 4 N sulphuric acid is used]. (c) 4-Nitrobenzoic acid (99%), 241°<sup>2,3</sup>. (d) 2-Chlorobenzoic acid (90%), 137°<sup>2,3</sup>. (e) 3-Chlorobenzoic acid (85%), 157°<sup>2,3</sup>, N.E. 152±5. (f) 4-Chlorobenzoic acid (90%), 237°<sup>2,3</sup>. (g) 2-Methoxybenzoic acid (72%), 101°<sup>2,3</sup>,  $\nu_{\text{max}}^{\text{KBr}}$  1690, 1610, 1590, 1470, 1430, 1310, 1295, 1230, 1045, 935, 910, 805 and 760 cm<sup>-1</sup>; N.E. 150±5, [5 ml of acetone was used per g of 2-methoxybenzaldehyde

during oxidation, otherwise brominated product, m.p. 120-135° was obtained]. (h) 3-Methoxybenzoic acid (55%), 105-107°<sup>2,3</sup>,  $\nu_{\text{max}}^{\text{KBr}}$  1693, 1607, 1586, 1462, 1379, 1310, 1291, 1230, 1121, 1105, 1049, 1043, 936, 908, 891, 869, 810, 755, 679 and 665 cm<sup>-1</sup>; [acetone was used during oxidation as in (g)]. (i) 4-Methoxybenzoic acid (90%), 182°<sup>2,3</sup>,  $\nu_{\text{max}}^{\text{KBr}}$  1680, 1605, 1580, 1515, 1425, 1305, 1260, 1180, 1170, 1132, 1108, 1025, 925, 895, 825, 775, 698, 635, 615, 605 and 540 cm<sup>-1</sup>; N.E. 151±5, [mineral acid induced bromination during oxidation]. (j) Cinnamic acid (40%), 131°<sup>2,3</sup> [recovered cinnamaldehyde, 55%, b.p. 210-220°]. (k) Butyric acid (55%), b.p. 130-140°/water aspirator [contained traces of bromo-compound].

### Acknowledgement

The authors are thankful to Prof. (Mrs.) K. K. Rohatgi-Mukherjee, Head of the Department of Chemistry, Jadavpur University, for laboratory facilities and to Dr. R. G. Bhattacharyya for the ir spectra of some of the compounds.

### References

1. A. BANERJEE, S. BANERJEE and H. SAMADDAR, *J. Indian Chem. Soc.*, 1979, 56, 988.
2. K. K. SENGUPTA, H. SAMADDAR, A. BANERJEE and P. K. SEN, *J. Org. Chem.*, (To be published).
3. I. HEILBRON in "Dictionary of Organic Compounds", Eyre and Spottiswoode Publishers Ltd., London, 1965. (a) Vol. IV, p. 2435, (b) Vol. IV, p. 2436, (c) Vol. II, p. 601, (d) Vol. II, p. 602, (e) Vol. IV, p. 2103, (f) Vol. I, p. 248, (g) Vol. II, p. 710.

### Potentiometric Determination of Niobium(V) in Presence of Tantalum in Non-Aqueous Media<sup>1</sup>

(Miss) PUSHPA SHARDA and G. C. SHIVAHARE

Department of Chemistry, University of Rajasthan,  
Jaipur-302 004

Manuscript received 15 May 1981, revised 31 December 1981,  
accepted 11 March 1982

**NI OBIUM** salts hydrolyse easily in aqueous media and their direct estimation in such media presents some difficulty. Many niobium compounds are soluble in non-aqueous media but their estimation by usual methods takes time. Estimation of niobium or tantalum in the presence of each other is also considered difficult.

Bismuth has been estimated using 5-mercapto-3-phenyl-1,2-thio-1,3,4-thio-diazolone-2-phenyldithio-diazolone (MPTTPT) in acid medium when a reddish-coloured precipitate is obtained. Bismuth has also been detected and estimated colorimetrically using this reagent. The reagent also forms yellow precipitates with gold, mercury, lead, silver, platinum, arsenic and antimony; white with cadmium, zinc; brown with copper; brick red with tin and red with palladium<sup>1,2</sup>.

The authors earlier reported the gravimetric estimation of niobium using the reagent in aqueous media<sup>2</sup>. No reference has been found in literature regarding the use of this reagent in electrometric methods.

### Experimental

E.M.F. measurements were made with a digital pH meter (ECL Model PH 5651) having a single glass-calomel electrode assembly.

**Preparation of niobium solution :** Requisite quantity of niobium pentachloride (Fluka) was dissolved in absolute alcohol. Care was taken to avoid moisture while weighing.

**Preparation of the reagent :** The reagent was prepared by the described method<sup>4</sup>. The compound is fine white needles, m. p. 259° and is soluble in water and warm alcohol.

MPTTPT was dissolved in slightly warm absolute alcohol. The strength of the reagent solution was kept the same as that of the niobium pentachloride solution.

5 ml of niobium pentachloride solution was taken in the cell every time and the titrant (MPTTPT reagent) solution added from a microburette. Direct and reverse titrations were performed. Several such experiments were performed using 0.01M, 0.005M and 0.004M solutions of niobium pentachloride. In all the titrations, sharp change was noticed at the equivalence point after which the potential became steady again. The end-point was obtained from the maximum of  $\Delta E/\Delta V$  and corresponds to 1 : 1 complex.

It is noteworthy that tantalum does not interfere in the estimation of niobium by this method. The method described above is rapid and accurate for the estimation of such compounds of niobium which get hydrolysed in aqueous media but are soluble in absolute alcohol.

### References

1. A. K. MAJUMDAR, *J. Indian Chem. Soc.*, 1944, 21, 347.
2. J. V. DUBSKY and J. TRTILEK, *Chem. Obozr.*, 1934, 9, 203; *Chem. Abs.*, 1935, 29, 2876.
3. PUSHPA SHARDA and G. C. SHIVAHARE, Paper presented at the session of the Indian Science Congress Association, 1980.
4. M. BUSCH, *Ber.*, 1894, 27, 2510.

### Determination of Equilibrium Constant of Ferric Formate Complex by Paper Electrophoresis

H. G. MUKHERJEE\* and (Miss) ALOKA DEBI

Pure Chemistry Department, University College of Science, Calcutta-700 009

Manuscript received 25 September 1980, revised 8 September 1981, accepted 11 March 1982

**P**APER electrophoresis has been applied to the study of metal complexes in solution. Attempts have also been made to determine the stability constants of the complex species<sup>1-10</sup>.

As far as we are aware the stability constant has not been determined from the eluate of the cationic and anionic species of the migrant obtained after paper electrophoresis. In the present study, an attempt has been made to determine the equilibrium constant of the Fe(III)-formate system by paper electrophoresis.

### Experimental

**Preparation of migrant solution :**  $\text{FeCl}_3 \cdot 6\text{H}_2\text{O}$  (1.0100 g) was dissolved in 30 ml water with addition of a few drops of hydrochloric acid. The solution was filtered and the volume made up to 50 ml.

**Preparation of the background electrolyte :** Stock solutions of 2M formic acid, 2M sodium formate and 1M sodium nitrate were prepared. The background electrolyte consisted of a mixture containing 25 ml 2M sodium formate, 25 ml 2M formic acid and 50 ml 1M sodium nitrate per 100 ml solution. Sodium nitrate was used to attain the desired ionic strength. Formate concentration was fixed, ionic strength was 1.0 and the pH of the electrolyte was 3.75.

**Instrument :** Wieland and Fischer type horizontal set was used<sup>11</sup>. The apparatus used was the cassette type and chromatograms could be run simultaneously on six paper strips. High voltage electrophoresis was carried out for 20 min at 400 volts and at 30°. Whatman No. 1 paper strips (3 × 40 cm) were used with an applied voltage gradient of 8 volt/cm.

pH measurements were made with an Elico Model LI-10 pH meter using a glass-calomel electrode assembly.

**Procedure :** The midpoint of each paper strip was marked and moistened with the background electrolyte and a spot of the metal solution was applied on it. The electrophoretic migration of the metal spots of different volume on the paper was observed. After electrophoresis, the spots of Fe(III) were developed with yellow ammonium sulphide. Two species were obtained in each case, one moved towards the anode and the other towards the cathode. The distances of the leading and tailing edges of the spots from the marked centre were measured. Portions of the paper containing the ions were cutout from the dried undeveloped electrophoregram after matching the positions of the ions with a developed electrophoregram subjected to identical electrophoretic conditions and environment. The paper portions containing the ions were treated with 0.8 N  $\text{H}_2\text{SO}_4$  to extract the ion. The extracts derived out of the strips through washings were taken in a 25 ml volumetric flask and the volume made upto the mark with 0.8 N  $\text{H}_2\text{SO}_4$ . Similarly, blank solutions were prepared. The absorbance of the eluted iron solution was measured against these blanks at 305 m $\mu$  (Table 1).

In both the anionic and cationic species the metal ion Fe(III) present in each case was calculated

using the equation,

$$C = \frac{A}{\epsilon} = \frac{\text{Absorbance}}{\text{Extinction coefficient}}$$

where C = concentration in molarity,  $\epsilon = 2180^{12}$ .

TABLE 1

Migrant FeCl <sub>3</sub>	A	
	anionic species	cationic species
0.04 ml	0.02	0.002
	0.033	0.005
	0.021	0.002
0.08 ml	0.062	0.01
	0.064	0.01
	0.058	0.01
0.12 ml	0.210	0.017
	0.088	0.015

With these concentrations of anionic and cationic species the equilibrium constant K was calculated in each case using the equation

$$K = \frac{[\text{Fe}(\text{OOCH})_3]^{3-}}{[\text{Fe}^{3+}][\text{HCOO}^-]^3}$$

The equilibrium constant K and its logarithm are shown in Table 2.

TABLE 2

Migrant FeCl <sub>3</sub>	K	log K	Mean log K	log K from literature (e.m.f. method)
0.04 ml	640	2.81		
	704	2.85		
	672	2.83		
0.08 ml	640	2.81	2.83	3.1
	661	2.82		
	619	2.79		
0.12 ml	790	2.90		
	625	2.80		

### Discussion

In the presence of an excess of formate ion, the positive metal ion is complexed to form  $[\text{Fe}(\text{OOCH})_3]^{3-}$  when the background electrolytes used are 25 ml 2M HCOONa, 1-15 ml 2M HCOOH, 50 ml 1M NaNO<sub>3</sub> and 24-10 ml water at the pH range 5.15 to 3.97.



But when the background electrolyte used is 25 ml 2M HCOONa, 25 ml 2M HCOOH, 50 ml 1M NaNO<sub>3</sub> at pH 3.75, the positive metal ion forms both the anionic and cationic species.

Electrophoretic study reports that most of the metal ion is complexed to form  $[\text{Fe}(\text{OOCH})_3]^{3-}$  and a trace amount of metal ion moves as a simple cation. So there must exist an equilibrium



$$K = \frac{[\text{Fe}(\text{OOCH})_3]^{3-}}{[\text{Fe}^{3+}][\text{HCOO}^-]^3}$$

where K is the equilibrium constant.

**Conclusion:** Paper electrophoresis technique is limited to charged species, and the precision of the method is not as high as that of other physicochemi-

cal methods. Nevertheless, it is of interest in the metal-ligand system in solution since complex formation is widely used in effecting separations of metal ions.

### Acknowledgement

The authors record their sincere thanks to Professor N. N. Ghosh, Pure Chemistry Department, Calcutta University for valuable suggestions and to Dr. G. N. Mukherjee, Pure Chemistry Department, Calcutta University for encouragement.

### References

1. J. BIERNAT, *Rocz. Chem.*, 1964, **38**, 343.
2. V. JOKL, *J. Chromatogr.*, 1964, **14**, 71.
3. B. HURNIK, *Rocz. Chem.*, 1965, **39**, 137.
4. J. KOZAK, *Acta Fac. Rerum Natur. Univ. Comenianae Chem.*, 1971, 23.
5. H. KOCH and M. IOVCHEV, *Isotopenpraxis*, 1971, **7**, 401.
6. E. LARSEN and J. ERIKSEN, *J. Chem. Educ.*, 1975, **52**, 122.
7. P. C. YADAVA, A. K. GHOSH, K. L. YADAVA and A. K. DEY, Private communication.
8. G. MARCU and M. TOMUS, *Analysis*, 1972, **1**, 43.
9. B. KOZJAK, Z. MARINIC, Z. KONARD, L. MUSANI MARAZOVIC and Z. PUCAR, *J. Chromatogr.*, 1977, **132**, 323.
- 10a. CZAKIS SULIKOWSKA, *Zesz. Nauk, Politech. Lodz. Chem.*, 1965, 23.
- 10b. P. C. YADAVA, A. K. GHOSH, K. L. YADAVA and A. K. DEY, *J. Chromatogr.*, 1976, **119**, 563.
11. T. WIELAND and E. FISCHER, *Naturwiss.*, 1948, **35**, 29.
12. R. H. SCHULER and A. O. ALLEN, *J. Chem. Phys.*, 1956, **24**, 56.

### Relative Stability of Formate Complexes by Paper Electrophoresis

H. G. MUKHERJEE and (Miss) ALOKA DEBI

Pure Chemistry Department, University College of Science,  
Calcutta-700 009

Manuscript received 30 March 1981, revised 23 November, 1981,  
accepted 11 March 1982

**S**TUDIES on the relative stabilities of various inorganic compounds have been reported earlier<sup>1-5</sup>. While the oxalate, citrate, tartrate and malate complexes have been investigated, none of these studies relates to the relative stability of the formate complexes. It was therefore decided to study the relative stability of formate complexes of Fe(III), Cu(II), Ni(II) and Co(II) by paper electrophoresis.

### Experimental

**Migrants:** 2% solution of CuSO<sub>4</sub>.5H<sub>2</sub>O, FeCl<sub>3</sub>.6H<sub>2</sub>O, CoCl<sub>2</sub>.6H<sub>2</sub>O and NiCl<sub>2</sub>.6H<sub>2</sub>O were used as migrants.

**Electrolytes:** Stock solutions of 2M sodium formate, 2M formic acid and 1M sodium nitrate were prepared. Sodium nitrate was used to attain the desired ionic strength.

# NOTES

**Procedure:** Whatman No. 1 (1 cm × 34 cm) paper strips were taken. The electrophoretic movement of a drop of migrant under the potential difference of 220 volts for 45 min in different carrier electrolytes are recorded in Tables 1 to 3.

It appears from Table 1 that Fe(III) and Cu(II) migrate towards the anode at high concentration (1M-0.4M) of Na-formate when pH of the carrier electrolyte is 8.9-8.7 and ionic strength is constant while Co(II) and Ni(II) ions migrate towards the cathode. It means that Fe(III) and Cu(II) ions form anionic complexes with the carrier electrolyte and Co(II) and Ni(II) do not form such complexes.

But at low concentration of sodium formate as electrolyte (0.25 M and below), Fe(III) is precipitated at the point of application, Cu(II) moves towards the cathode i.e. Cu(II) forms cationic species with the background electrolyte while Co(II) and Ni(II) behave as before.

From the resulting data, formation of M-formate and M'-formate complex, where M=Ni(II), Co(II) and M'=Fe(III), Cu(II) is inferred. The data shows that Fe(III)-formate complex is more stable than Cu(II)-formate complex. Therefore, the relative stability of Fe(III)-formate complex is higher than that of Cu(II)-formate complex.

TABLE 1

Carrier electrolyte	Distance migrated in cm ( '+' anionic movement ; '-' cationic movement)			
	Fe(III)	Cu(II)	Ni(II)	Co(II)
(1) 50 ml 2M Na-formate + 50 ml water *(1M), pH = 8.9	+0.2 to +0.9	+0.5 to +2.1	-0.7 to -2.8	-0.8 to -2.4
(2) 25 ml 2M Na-formate + 25 ml water + 50 ml 1M NaNO <sub>3</sub> *(0.5M), pH = 8.72	+0.2 to +0.5	+0.3 to +2	Cationic	Cationic
(3) 20 ml 2M Na-formate + 20 ml water + 60 ml 1M NaNO <sub>3</sub> *(0.4M), pH = 8.70	0 to +0.4	+1.1 to -0.5	Cationic	Cationic
(4) 12.5 ml 2M Na-formate + 12.5 ml water + 75 ml 1M NaNO <sub>3</sub> *(0.25M), pH = 8.60	ppt at the point of application	-1.1 to -2.7	Cationic	Cationic
(5) 5 ml 2M Na-formate + 5 ml water + 90 ml 1M NaNO <sub>3</sub> *(0.1M), pH = 8.4	ppt at the point of application	-1.8 to -3.2	Cationic	Cationic

pH (8.9-8.4), ionic strength constant, Na-formate variable.  
\*Conc. of formate in the solution and pH.

TABLE 2

Carrier electrolyte	Distance migrated in cm ( '+' anionic movement ; '-' cationic movement)			
	Fe(III)	Cu(II)	Ni(II)	Co(II)
(1) 50 ml 2M HCOONa + 50 ml 2M HCOOH *(1M)	+1.9 to +3.3	+2.4 to +5.3	Cationic	Cationic
(2) 25 ml 2M HCOONa + 25 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> *(0.5M)	+1.2 to +2.6	+1.2 to -0.5	Cationic	Cationic
(3) 20 ml 2M HCOONa + 20 ml 2M HCOOH + 60 ml 1M NaNO <sub>3</sub> *(0.4M)	+1.1 to +2.3	-0.3 to -1.9	Cationic	Cationic
(4) 12.5 ml 2M HCOONa + 12.5 ml 2M HCOOH + 75 ml 1M NaNO <sub>3</sub> *(0.25M)	+0.6 to +1.9	-1.6 to -2.7	Cationic	Cationic
(5) 10 ml 2M HCOONa + 10 ml 2M HCOOH + 80 ml 1M NaNO <sub>3</sub> *(0.2M)	+0.4 to +2	-1.9 to -3.2	Cationic	Cationic
(6) 5 ml 2M HCOONa + 5 ml 2M HCOOH + 90 ml 1M NaNO <sub>3</sub> *(0.1M)	-0.1 to -1 (having a tendency to precipitate)	-2.4 to -3.8	Cationic	Cationic

pH = constant, ionic strength = 1, formate variable.  
\*Concentration of formate ion in solution.

TABLE 3

Carrier electrolyte	Distance migrated in cm ('+' anionic movement; '-' cationic movement)			
	Fe(III)	Cu(II)	Ni(II)	Co(II)
(1) 25 ml 2M HCOONa + 1 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> + 24 ml water (pH = 5.15)	+1.8 to +3.9	+2.4 to +5.6	Cationic	Cationic
(2) 25 ml 2M HCOONa + 2.5 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> + 22.5 ml water (pH = 4.75)	+0.8 to +1.9	+2.6 to +4.6	Cationic	Cationic
(3) 25 ml 2M HCOONa + 5 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> + 20 ml water (pH = 4.45)	+0.5 to +2.1	+2.1 to +3.7	Cationic	Cationic
(4) 25 ml 2M HCOONa + 10 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> + 15 ml water (pH = 4.15)	+0.5 to +1.6	-0.6 to -1.9	Cationic	Cationic
(5) 25 ml 2M HCOONa + 15 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> + 10 ml water (pH = 3.97)	+0.2 to +1.1	-0.9 to -2.6	Cationic	Cationic
(6) 25 ml 2M HCOONa + 20 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> + 5 ml water (pH = 3.85)	+0.1 to +1.1 and -0.8 to -1.6	-1.1 to -2.6	Cationic	Cationic
(7) 25 ml 2M HCOONa + 2 ml 2M HCOOH + 50 ml 1M NaNO <sub>3</sub> + (pH = 3.75)	+0.1 to 1 and -1.9 to -2.7	-1 to -3.1	Cationic	Cationic

(Formate concentration and ionic strength constant, pH is variable)

All electrolytes in Table 2 have the same pH and it will be equal to the  $pK_a$  of formic acid because of the same concentration of salt and acid. Hence, pH is 3.75 in all the cases and

$$[H^+] = 18 \times 10^{-4} \text{ g-ion/litre}$$

Concentration of  $H^+$  is essential to calculate the ionic strength of the electrolyte because formic acid is a weak acid as it does not undergo complete dissociation.

Table 2 shows that Fe(III) ion behaves as an anionic complex throughout the concentration range (1M to 0.2M) of sodium formate when the pH and the ionic strength of the carrier electrolyte are constant. But at low concentration (0.1M) of Na-formate, Fe(III) moves towards the cathode. Cu(II) forms anionic complex when concentration of sodium formate is high (1M to 0.5M) but below this concentration Cu(II) forms cationic species with carrier electrolyte under the same condition. In the case of Ni(II) and Co(II), both the ions move as cationic species throughout the experiment. Hence it can be concluded that the relative stability of Fe(III)-formate complex is more than that of Cu(II)-formate complex.

Table 3 indicates that Fe(III) forms anionic complex with the carrier electrolyte throughout the experiment (pH 5.15-3.75) but at pH 3.85 and 3.75, Fe(III) forms both anionic and cationic

species when ionic strength of the electrolyte and Na-formate concentration are constant. Cu(II) forms anionic formate complex at pH 5.15-4.45 and forms cationic species at pH 4.15-3.75. In the case of Ni(II) and Co(II) both the ions move towards the cathode throughout the experiment.

From the experimental data it can be said that the Fe(III)-formate complex is very stable but Cu(II) formate complex is not so stable. So the relative stability of Fe(III)-formate complex is higher than that of Cu(II)-formate complex.

#### Acknowledgement

The authors are thankful to Professor N. N. Ghosh and Dr. G. N. Mukherjee, Pure Chemistry Department, Calcutta University for their valuable advice.

#### References

1. B. HURNIK, *Rocz. Chem.*, 1965, 39, 137.
2. B. HURNIK, *Theory and Struct. of Complex Compds.*, Symp. Wroclaw, Poland, 1962, 693.
3. D. S. GAIBAKYAN, Z. Z. TERMENZHYAM and V. M. TARAYAN, *Arm. Khim.*, 1970, 23, 128.
4. V. V. GRIGOREVA and S. M. TRIMBLER, *Zh. Neorg. Khim.*, 1968, 13, 498.
5. M. NELSON PEGG and E. ST. CLAIR GANTZ, *Proc. Indiana Acad. Sci.*, 1947, 57, 101.

# Solvent Extraction of Thorium with Liquid Cation Exchanger (Versatic 10)\*\*

UDAY SANKAR RAY\* and SAGAR CHANDRA MODAK

Department of Chemistry, Visva Bharati, Santiniketan,  
West Bengal

Manuscript received 20 September 1980, revised 19 December  
1981, accepted 11 March 1982

THE synthetic carboxylic acids, Versatic 911 and Versatic 10, have been shown to be a promising extractant for large scale processing of transition metals<sup>1</sup>. A number of papers have appeared on the extraction of metals with versatic acids<sup>2-5</sup> and the composition of the extracted species has also been investigated<sup>4-6</sup>. Flett<sup>7</sup> reported its use for the extraction of metal in commercial plant. This communication reports the extraction of thorium(IV) and determination of probable composition of the extracted species using Versatic 10 in benzene as extractant. Quantitative extraction from 0.1 M acetate solution was achieved in the pH range 4.0-5.2. Thorium was separated from most of the rare earth elements, having separation factor,  $D_{Th}/D_{RE}$ , in the order of  $10^4$ . The probable composition of the extracted species  $ThR_4 \cdot 2RH$  ( $RH = \text{Versatic 10}$ ) was deduced from the extraction data.

## Experimental

**Apparatus and reagents:** Elico pH meter (Elico, Model LI-10, Hyderabad, India) was used for measurement of pH.

Versatic 10 (Shell Chemical Co., London), a mixture of branched  $C_{10}$  isomeric tertiary mono-carboxylic acids<sup>8</sup>, was used in conjunction with benzene, without further purification. The purity and concentration of Versatic 10 was 99% and 5.28 M, respectively.

Thorium acetate solution (1.04 mg/ml) was prepared by dissolving 3.8 g  $Th(NO_3)_4 \cdot 6H_2O$  (E. Merck) in deionized water followed by precipitation of the metal hydroxide and subsequent dissolution in 0.2 M acetic acid. The solution was standardised by complexometric titration with EDTA (disodium salt) using xylenol orange indicator. All other chemicals and solvents were of analytical grade.

**Extraction procedure:** The aqueous phase (20 ml) containing  $2.2 \times 10^{-3}$  M thorium was equilibrated with 10 ml of 0.88 M Versatic 10 in benzene for 5 min. Distribution ratio reached a constant value within 2 min of shaking, so contact time of 5 min was used in all the experiments. NaOH solution was used for adjustment of pH. All the extraction experiments were carried out at  $30 \pm 1^\circ$  and the ionic strength was maintained at 0.1 M with acetic acid. The two layers were allowed to settle for 5 min.

The aqueous phase separated and the equilibrium pH measured. The aqueous phase was washed with 5 ml benzene to remove entrained solvent and the benzene extract was mixed with the separated organic phase. The amount of thorium present in the aqueous phase was estimated by titration with EDTA. The metal ion from the organic phase was stripped with 2N  $HNO_3$  (20 ml) and the acid extract was washed with 5 ml benzene to remove the entrained solvent present. The amount of thorium extracted was estimated by titrating the acid extract with EDTA.

## Results and Discussion

The extraction of thorium(IV) from 0.1 M acetate solution with Versatic 10 was performed at various pH. With constant extractant concentration (0.88M) and constant metal concentration ( $2.2 \times 10^{-3}$  M) extraction of thorium increased with increased pH and became quantitative at pH 4-5.2. The optimum pH range for quantitative extraction is 4-5.2. The equilibration time was determined by varying the contact time from 0.5 min to 10 min. The distribution ratio, D, reached a constant value within 2 min and back extraction was completed within 5 min. However, contact time and stripping time was kept at 5 min in all the experiments. Various diluents, viz., benzene, toluene, xylene, carbon tetrachloride, diisopropyl ether, chloroform and butanol were tried on the extraction of thorium under the optimum conditions. Quantitative extraction of thorium was achieved in all the cases except diisopropyl ether. In case of diisopropyl ether emulsion formation took place. Some saturation experiments were undertaken at pH 4.9 to examine the practical applicability of the proposed method for large scale extraction of thorium. 25 g/l of thorium could be extracted (94.5%) in a single step at pH 4.9. Further increase of thorium in the aqueous phase leads to difficulty in phase separation.

**Probable extraction mechanism:** The acetate ion dependency on extraction was investigated by performing the extraction at constant pH, constant metal ion concentration ( $2.2 \times 10^{-3}$  M) and constant Versatic 10 concentration (0.88M). Results show that increase of acetate ion in the aqueous phase leads to reduced extraction. This was probably due to formation of less extractable thorium acetate complexes in the aqueous phase. The plot of  $\log D$  against  $\log [\text{acetate}]$  was linear with a slope of  $-4.1$ , indicating the release of four acetate ions in the extraction process. The plot of  $\log D$  against  $\log [\text{Versatic 10}]$  was linear with a slope of 2.9. Versatic acids are known to exist as dimer in nonpolar solvent such as benzene<sup>9</sup>. The probable extraction mechanism, can therefore be expressed as:



where  $R_2H_2$  represents the dimeric form of Versatic 10 in benzene and the barred species are in the organic phase.

\*\*Paper presented at the Convention of Chemist, Kurukshetra University, 1979.

**Extractive separations:**  $Mg^{2+}$ ,  $Ca^{2+}$ ,  $Sr^{2+}$ ,  $Ba^{2+}$ ,  $Zn^{2+}$ ,  $Cd^{2+}$ ,  $La^{3+}$ ,  $Pr^{3+}$ ,  $Nd^{3+}$ ,  $Sm^{3+}$ ,  $Gd^{3+}$ ,  $Tb^{3+}$ ,  $Dy^{3+}$  and  $Hg^{2+}$  did not interfere in the extraction of thorium(IV). In all these cases, separations were achieved simply by controlling the pH (pH=4.6) of the aqueous phase during extraction. Separation factor,  $D_{Th}/D_M$ , in the order of  $10^4$  was achieved in all these cases. Only in the case of mercury, two consecutive equilibrations were required at pH 4.3. The interfering ions were  $Ce^{4+}$ ,  $Pb^{2+}$  and  $U^{6+}$ . In order to assess the possible analytical applications, the proposed method was applied for the extraction of thorium(IV) from several synthetic mixtures prepared by mixing 5 mg of each metal [Th(IV) + Ca(II) + Ba(II); Th(IV) + La(III) + Pr(III) + Nd(III); Th(IV) + Sm(III) + Gd(III) + Tb(III); Th(IV) + Zn(II) + Cd(II) + Hg(II)]. In most of the cases quantitative recovery of thorium was achieved. Extraction experiments were carried out at pH 4.6 using 0.88 M Versatic 10 (10 ml) in benzene.

#### Acknowledgement

Financial support from U. G. C., New Delhi is gratefully acknowledged. The authors are thankful to Prof. A. K. De, for encouragement.

#### References

1. D. S. FLETT and M. J. JAYCOCK, "Ion Exchange and Solvent Extraction", Marcel Dekker, New York, 1973, Vol. 3, Chap. 1.
2. U. S. RAY and S. C. MODAK, *Sep. Sci. and Tech.*, 1981, 16, 87.
3. U. S. RAY and S. C. MODAK, *J. Indian Chem. Soc.*, 1981, 58, 38.
4. L. M. GINDIN *et al.*, *J. Inorg. Chem.*, 1960, 5, 1146.
5. A. W. ASHBROOK, *J. Inorg. Nuclear Chem.*, 1972, 34, 1721.
6. J. SHIBATA and S. NISHIMURA, *Trans. Japan Inst. Metal*, 1977, 18, 794.
7. D. S. FLETT, *Trans. Min. Metal*, 1974, 83, C30.
8. J. SHIBATA and S. NISHIMURA, *Nippon Kinzoku Gakkagishi*, 1975, 39, 206, 767.
9. H. GREEN, *Talanta*, 1973, 20, 158.



# Effect of Different Groups on Cyclopentadienyl Ring on the Stability of Titanium-Cyclopentadienyl Bond

PURSHOTAM SONI, KAILASH CHANDRA, RAJENDRA K. SHARMA and BHAGAWAN S. GARG\*

Department of Chemistry, University of Delhi, Delhi-110 007

Manuscript received 26 December 1980, revised 19 October 1981, accepted 23 May 1982

Reactions of  $\text{ABTiCl}_2$  (A = cyclopentadienyl and B = methylcyclopentadienyl or indenyl) with sodium salts of dithiocarbamic acids,  $\text{Na}(\text{S}_2\text{CNRR}')$  ( $\text{R}=\text{R}'=\text{CH}_3$ ,  $\text{C}_6\text{H}_5$ ,  $i\text{-C}_4\text{H}_7$ ; or  $\text{R}=\text{CH}_3$ ,  $\text{R}'=\text{C}_6\text{H}_5$ ) have been carried out in the molar ratio of 1 : 3. It was found that in case of  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$ , the cyclopentadienyl ring was knocked off resulting in the formation of  $(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)\text{Ti}(\text{S}_2\text{CNRR}')$ , whereas, in case of  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-C}_6\text{H}_4)]\text{TiCl}_2$ , the indenyl ring was knocked off resulting in the formation of  $(\eta^5\text{-C}_6\text{H}_4)\text{Ti}(\text{S}_2\text{CNRR}')$ . A suitable explanation for this observation has been proposed.

SUBSTITUTION on Cp ring affects the stability of titanium-cyclopentadienyl bond i.e., in case of  $(\eta^5\text{-C}_5\text{H}_5)\text{TiCl}_2$ , cyclopentadienyl ring is lost by alkaline hydrolysis, whereas  $[(\eta^5\text{-CH}_3)_2\text{C}_5\text{H}_3]\text{TiCl}_2$  is converted only to  $[(\eta^5\text{-CH}_3)_2\text{C}_5\text{H}_3]\text{Ti}(\text{OH})_2$ . In the other case, unlike  $(\eta^5\text{-Cp})_2\text{Ti}(\text{CH}_3)_2$ , the yellow pentane solutions of  $[(\eta^5\text{-CH}_3)_2\text{C}_5\text{H}_3]\text{Ti}(\text{CH}_3)_2$  were found to show no reactivity towards  $\text{H}_2$  even at 100 atm pressure<sup>1</sup>. Recently, it has been established that in the reaction of  $(\eta^5\text{-C}_5\text{H}_5)_2\text{MCl}_2$  or  $(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)_2\text{MCl}_2$  ( $\text{M}=\text{Ti, Zr or Hf}$ ), with sodium dithiocarbamates in the ratio of 1 : 3, one cyclopentadienyl or methylcyclopentadienyl ring is knocked off resulting in the formation of  $(\eta^5\text{-C}_5\text{H}_5)\text{M}(\text{DTC})_2$  or  $(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)\text{M}(\text{DTC})_2$ <sup>2,3</sup>.

In the present communication reactions of  $\text{ABTiCl}_2$ , [ $\text{A}=\eta^5\text{-C}_5\text{H}_5$ ,  $\text{B}=\eta^5\text{-CH}_3\text{C}_5\text{H}_4$  or  $\eta^5\text{-C}_6\text{H}_4$  (indenyl)], with  $\text{Na}(\text{S}_2\text{CNRR}')$ , ( $\text{R}=\text{R}'=\text{CH}_3$ ,  $\text{C}_6\text{H}_5$ ,  $i\text{-C}_4\text{H}_7$ ; or  $\text{R}=\text{CH}_3$ ,  $\text{R}'=\text{C}_6\text{H}_5$ ), have been studied with a view to ascertain the effect of the different groups present on cyclopentadienyl ring on the stability of titanium-cyclopentadienyl bond. In the case of  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$ , cyclopentadienyl ring is knocked off indicating that the  $-\text{CH}_3$  group present on the cyclopentadienyl ring imparts stability to titanium-cyclopentadienyl bond, whereas in the case of  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-C}_6\text{H}_4)]\text{TiCl}_2$ , indenyl ring is knocked off thereby indicating that the presence of phenyl ring fused to cyclopentadienyl ring (in indenyl) makes the titanium-cyclopentadienyl bond fragile.

## Experimental

**Reagents and general techniques:**  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$  was prepared by the reaction of  $\eta^5\text{-CpTiCl}_2$  and  $(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)\text{Ti}$  (I) in 1 : 1 molar ratio in THF.  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-C}_6\text{H}_4)]\text{TiCl}_2$  was prepared by the reaction of  $\eta^5\text{-CpTiCl}_2$  and sodium indenide in 1 : 1 molar ratio in THF<sup>4,5</sup>. Sodium salts of dithiocarbamic acids were prepared

as described by Kloppe and Kerk<sup>1,4</sup> and dried before use. All the organic solvents used were predried and well purified.

### Preparation of the complexes :

[A] **Reaction of sodium salt of N,N-dimethyl-dithiocarbamic acid on  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$ :**  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$  (0.2630 g; 0.001 mole) was refluxed with  $\text{Na}[\text{S}_2\text{CN}(\text{CH}_3)_2]$  (0.4290 g; 0.003 mole) in  $\text{CH}_2\text{Cl}_2$  (50 ml) for 10 hr. The reaction mixture was cooled and filtered. The volume of the filtrate was reduced to ~10 ml *in vacuo* and petroleum ether (60-80°) was added dropwise to precipitate the complex. The precipitate was filtered, dried and recrystallized from 1 : 1 mixture of dichloromethane and petroleum ether to isolate the yellow orange product,  $(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{CH}_3)_2]_2$  in > 90% yield. Reactions of  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$  with other dithiocarbamates, i.e.,  $\text{Na}(\text{S}_2\text{CNRR}')$ , ( $\text{R}=\text{R}'=\text{C}_6\text{H}_5$ ,  $i\text{-C}_4\text{H}_7$ ; or  $\text{R}=\text{CH}_3$ ,  $\text{R}'=\text{C}_6\text{H}_5$ ), in 1 : 3 molar ratio were carried out in similar manner and yielded corresponding mono(methylcyclopentadienyl) trisdithiocarbamatotitanium (IV) complexes in > 90% yield.

[B] **Reaction of sodium salt of N,N-disubstituted dithiocarbamic acid on  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-C}_6\text{H}_4)]\text{TiCl}_2$ :** Reactions of  $[(\eta^5\text{-C}_5\text{H}_5)(\eta^5\text{-C}_6\text{H}_4)]\text{TiCl}_2$  with  $\text{Na}(\text{S}_2\text{CNRR}')$ , ( $\text{R}=\text{R}'=\text{CH}_3$ ,  $\text{C}_6\text{H}_5$ ,  $i\text{-C}_4\text{H}_7$ ; or  $\text{R}=\text{CH}_3$ ,  $\text{R}'=\text{C}_6\text{H}_5$ ), in 1 : 3 molar ratio were also carried out in the manner as described in [A] to yield the respective mono(cyclopentadienyl) trisdithiocarbamatotitanium (IV) complexes in > 90% yield.

**Physico-chemical measurements:** The ir spectra in the region 4000-250  $\text{cm}^{-1}$  were recorded on Perkin-Elmer 621 grating spectrophotometer. The  $^1\text{H}$  nmr spectra were recorded at ambient temperature ~30° in  $\text{CDCl}_3$  on a Varian A-60 NMR spectrometer at a sweep width of 500 Hz using TMS as an internal standard. Molecular weight of

\* Author for correspondence.

TABLE 1—PHYSICAL DATA FOR  $(\eta^5\text{-OH}_2\text{C}_6\text{H}_4)\text{Ti}(\text{S}_2\text{CNRR}')_2$  AND  $(\eta^5\text{-C}_6\text{H}_5)\text{Ti}(\text{S}_2\text{CNRR}')_2$

Complex	Molar conductivity $\text{ohm}^{-1}\text{cm}^2\text{mole}^{-1}$	Concentration mM	Molecular weight Found (Calcd.)	Analysis % Found (Calcd.)				m.p. and colour
				C	H	N	Ti	
$(\eta^5\text{-OH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{OH})_2]_2$	0.22	0.5	490 (487)	40.1 (37.0)	5.2 (5.1)	8.5 (8.6)	9.8 (9.9)	160° Yellow
$(\eta^5\text{-OH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{O}_2\text{H})_2]_2$	0.20	0.5	565 (571)	43.8 (44.1)	6.4 (6.5)	7.2 (7.3)	8.1 (8.4)	158° Yellow
$(\eta^5\text{-OH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{i-C}_4\text{H}_7)_2]_2$	0.23	0.4	680 (655)	48.9 (49.5)	7.6 (7.5)	6.2 (6.4)	7.4 (7.3)	170° Yellow orange
$(\eta^5\text{-OH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{OH})_2(\text{O}_2\text{H})]_2$	0.25	0.5	690 (673)	54.2 (53.5)	4.5 (4.6)	6.5 (6.2)	7.8 (7.1)	90° Orange yellow
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{OH})_2]_2$	0.22	0.5	431 (473)	35.2 (35.5)	4.7 (4.86)	8.7 (8.88)	10.3 (10.15)	240° Yellow orange
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{O}_2\text{H})_2]_2$	0.21	0.5	512 (557)	49.2 (43.09)	6.1 (6.28)	7.2 (7.54)	8.8 (8.62)	250° Yellow orange
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{i-C}_4\text{H}_7)_2]_2$	0.21	0.5	655 (641)	49.1 (48.7)	7.4 (7.3)	6.7 (6.5)	7.3 (7.5)	149° Orange yellow
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{OH})_2(\text{O}_2\text{H})]_2$	0.20	0.5	668 (659)	53.5 (52.8)	4.3 (4.4)	6.5 (6.37)	7.4 (7.28)	101° Orange

TABLE 2—PROTON CHEMICAL SHIFT ( $\tau$  VALUES IN ppm) AT  $\sim 80^\circ$  IN  $\text{ODCl}_3$


Complex	$\text{CH}_2\text{C}_6\text{H}_4$ or $\text{C}_6\text{H}_5$ ring protons	$\text{OH}_2$ protons of $\text{CH}_2\text{C}_6\text{H}_4$	$(\text{S}_2\text{CNRR}')_2$ protons		$-\text{CH}_2$ protons	$-\text{CH}_2$ protons
			$-\text{C}_6\text{H}_5$ protons	$\rightarrow\text{CH}$ protons		
$(\eta^5\text{-CH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{OH})_2]_2$	4.48(t), 4.00(t)	7.75	—	—	—	6.76(d) (5:1)
$(\eta^5\text{-CH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{O}_2\text{H}_2)_2]_2$	4.53(t), 4.1(t)	7.80	—	—	6.325(q)	8.33(t)
$(\eta^5\text{-CH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{i-C}_4\text{H}_7)_2]_2$	4.48(t), 4.05(t)	7.77	—	5.28(m)	—	A 8.66(d) (2:1)      B 8.61(d) (2:1)
$(\eta^5\text{-CH}_2\text{C}_6\text{H}_4)\text{Ti}[\text{S}_2\text{CN}(\text{OH})_2(\text{O}_2\text{H}_2)]_2$	4.55(t), 4.17(t)	7.85	2.89(d) (2:1)	—	—	6.51(d) (2:1)
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{OH})_2]_2$	4.1	—	—	—	—	6.76(d) (5:1)
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{O}_2\text{H}_2)_2]_2$	3.78	—	—	—	6.975(q)	8.53(t)
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{i-C}_4\text{H}_7)_2]_2$	4.05	—	—	5.52(m)	—	A 8.64(d) (2:1)      B 8.57(d) (2:1)
$(\eta^5\text{-C}_6\text{H}_5)\text{Ti}[\text{S}_2\text{CN}(\text{CH}_3)(\text{O}_2\text{H}_2)]_2$	3.73	—	2.59(d) (2:1)	—	—	7.975(d) (2:1)

m = multiplet, q = quartet, t = triplet, d = doublet, A and B are the two doublets of equal intensity.

the complexes were determined on Gallenkamp ebullioscope in benzene and conductivity measurements were carried out in nitrobenzene using Elico CM82T conductivity bridge.

## Results and Discussion

The reactions of  $(\eta^5\text{-C}_6\text{H}_5)(\eta^5\text{-CH}_2\text{C}_6\text{H}_4)\text{TiCl}_2$  or  $(\eta^5\text{-C}_6\text{H}_5)(\eta^5\text{-C}_6\text{H}_7)\text{TiCl}_2$  with  $\text{Na}(\text{S}_2\text{CNRR}')$  ( $\text{R}=\text{R}'=\text{CH}_3$ ,  $\text{C}_6\text{H}_5$ ,  $\text{i-C}_4\text{H}_7$ ; or  $\text{R}=\text{CH}_3$  and  $\text{R}'=\text{C}_6\text{H}_5$ ) in 1:3 molar ratio have been studied in nonaqueous medium. These reactions may be represented as:



These complexes are yellow orange to orange in colour and are insoluble in  $\text{H}_2\text{O}$  and petroleum ether but are highly soluble in  $\text{CHCl}_3$ ,  $\text{CH}_2\text{Cl}_2$ ,  $\text{C}_6\text{H}_6$ ,  $\text{CS}_2$ ,  $\text{CH}_3\text{COCH}_3$  and THF. They are thermally stable but slowly hydrolyse on exposure to moist air. The conductivity measurements in nitrobenzene and molecular weight determinations in benzene indicate that the complexes are non-electrolytic monomers. Physical data for these complexes are given in Table 1. These complexes have also been prepared previously by the reaction of  $(\eta^5\text{-CH}_2\text{C}_6\text{H}_4)_2\text{TiCl}_2$  or  $(\eta^5\text{-C}_6\text{H}_5)_2\text{TiCl}_2$  and  $\text{Na}(\text{S}_2\text{CNRR}')^{+10}$ .

**Infrared spectra:** The ir spectrum of each of these complexes shows only one  $\nu\text{C}\equiv\text{N}$  at  $\sim 1505\text{ cm}^{-1}$  and only one  $\nu\text{C}\equiv\text{S}$  at  $\sim 1000\text{ cm}^{-1}$ . The pentahapto cyclopentadienyl ring in the complexes  $(\eta^5\text{-C}_6\text{H}_5)\text{Ti}(\text{S}_2\text{CNRR}')_2$  is identified by the characteristic ir bands viz., C-H stretching at  $\sim 2925\text{ cm}^{-1}$ ,

C—C stretching at  $\sim 1430\text{ cm}^{-1}$ , symmetric ring breathing at  $\sim 1120\text{ cm}^{-1}$ , C—H asymmetric in plane deformation at  $\sim 1010\text{ cm}^{-1}$  and C—H out of plane deformation at  $\sim 845$ ,  $\sim 800\text{ cm}^{-1}$ . The presence of pentahapto methylcyclopentadienyl ring in the complexes  $(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)\text{Ti}(\text{S}_2\text{CNRR}')_2$  is identified by the characteristic ir bands viz., C—H stretching (ring) at  $\sim 3100\text{ cm}^{-1}$ , C—C stretching at  $\sim 1435\text{ cm}^{-1}$ , symmetrical ring breathing  $\sim 1125\text{ cm}^{-1}$ , C—H asymmetric in plane deformation at  $\sim 1035\text{ cm}^{-1}$  and C—H out of plane deformation at  $\sim 865$ ,  $\sim 825\text{ cm}^{-1}$ .

The ir data for these complexes are similar to those already prepared<sup>6-10</sup>. Therefore, the dithiocarbamate ligands in these complexes are bidentate and a coordination number of 'seven' may be assigned to titanium as already discussed<sup>6-10</sup>.

<sup>1</sup>H nmr spectra : The <sup>1</sup>H nmr data for these complexes are given in Table 2 and are similar to those already reported<sup>6-10</sup>. Therefore, these complexes are stereochemically rigid heptacoordinate chelates which assume different geometries<sup>6-10</sup>.

*Effect of the different groups present on the cyclopentadienyl ring on the stability of titanium-cyclopentadienyl ring :* The reactions of  $[(\eta^5\text{-C}_6\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$  or  $[(\eta^5\text{-C}_6\text{H}_5)(\eta^5\text{-C}_6\text{H}_7)]\text{TiCl}_2$  with sodium salts of N,N-disubstituted dithiocarbamic acids in 1 : 3 molar ratio yield trisdithiocarbamate complexes and one ring out of the two attached to titanium is knocked off. Naturally, the one having weaker titanium ring bond will be knocked off leaving the other ring having comparatively stronger bond with titanium.

In the case of the reaction of  $[(\eta^5\text{-C}_6\text{H}_5)(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)]\text{TiCl}_2$  with sodium dithiocarbamate, the cyclopentadienyl ring is knocked off. It clearly indicates that  $(\eta^5\text{-CH}_3\text{C}_5\text{H}_4)\text{-Ti}$  bond is stronger than  $(\eta^5\text{-C}_6\text{H}_5)\text{-Ti}$  bond. In fact, the electron releasing property of the methyl group present on the cyclopentadienyl ring in methylcyclopentadienyl group increases the electron density in the ring, imparting thereby additional stability to the titanium-methylcyclopentadienyl bond. Thus, as compared to titanium-methylcyclopentadienyl bond, titanium-cyclopentadienyl bond becomes relatively fragile and can be knocked off by dithiocarbamate ligand.

On the other hand in the case of the reaction of  $[(\eta^5\text{-C}_6\text{H}_5)(\eta^5\text{-C}_6\text{H}_7)]\text{TiCl}_2$  with sodium dithiocarbamates, the indenyl ring is knocked off. It indicates

that  $(\eta^5\text{-C}_6\text{H}_7)\text{-Ti}$  bond is weaker than  $(\eta^5\text{-C}_6\text{H}_5)\text{-Ti}$  bond. In fact the electron withdrawing property of  $\text{C}_6\text{H}_5$  ring fused to cyclopentadienyl ring (in indenyl ring) decreases the electron density of the cyclopentadienyl ring of the indenyl group. Thus,  $(\eta^5\text{-C}_6\text{H}_7)\text{-Ti}$  bond becomes weaker as compared to  $(\eta^5\text{-C}_6\text{H}_5)\text{-Ti}$  bond. Therefore, preferential removal of indenyl ring by dithiocarbamate ligand takes place during the formation of trisdithiocarbamate complexes.

It is, therefore, concluded that the electron releasing groups present on cyclopentadienyl ring increases the stability of titanium-cyclopentadienyl bond whereas the presence of electron withdrawing groups on cyclopentadienyl ring makes the titanium-cyclopentadienyl bond fragile and exchangeable. The order of stability is  $\eta^5\text{-CH}_3\text{C}_5\text{H}_4\text{-Ti} > \eta^5\text{-C}_6\text{H}_5\text{-Ti} > \eta^5\text{-C}_6\text{H}_7\text{-Ti}$ . During the reaction with DTC, one ring always remains attached with titanium. The fact has been ascertained through <sup>1</sup>H nmr spectra of the resultant products.

#### Acknowledgement

One of the authors (K. C.) is thankful to the University Grants Commission, New Delhi for the award of a Teacher Fellowship under Faculty Improvement Programme.

#### References

1. H. ROHL, E. LANGE, T. GOSSL and G. ROTH, *Angew. Chem., Int. Ed.*, 1962, 1, 117.
2. J. E. BERCAW, R. H. MARVICH, L. G. BELL and H. H. BRINTZINGER, *J. Amer. Chem. Soc.*, 1972, 94, 1219.
3. A. H. BRUDER, R. C. FAY, D. F. LEWIS and A. A. SAYLER, *J. Amer. Chem. Soc.*, 1976, 98, 6992.
4. V. K. JAIN, B. S. GARG and R. P. SINGH, *Aust. J. Chem.*, 1977, 30, 2545.
5. W. L. STEFFEN, H. K. CHUN and R. C. FAY, *Inorg. Chem.*, 1978, 17, 3498.
6. K. CHANDRA, Ph.D. Thesis, University of Delhi, 1980.
7. P. SONI, Ph.D. Thesis, University of Delhi, 1980.
8. K. CHANDRA, R. K. SHARMA, B. S. GARG and R. P. SINGH, *Trans. Metal Chem.*, 1980, 5, 209.
9. K. CHANDRA, R. K. TULI, B. S. GARG and R. P. SINGH, *J. Inorg. Nuclear Chem.*, 1981, 43, 29.
10. K. CHANDRA, R. K. SHARMA, B. S. GARG and R. P. SINGH, *J. Inorg. Nuclear Chem.*, 1981, 43, 663.
11. P. SONI, R. K. TULI, K. CHANDRA, R. K. SHARMA and B. S. GARG, *J. Inorg. Nuclear Chem.*, 1980, 42, 1978.
12. R. K. TULI, P. SONI, K. CHANDRA, R. K. SHARMA and B. S. GARG, *Trans. Metal Chem.*, 1980, 5, 145.
13. E. SAMUEL, *J. Organometal. Chem.*, 1968, 19, 87.
14. H. L. KLOPPING and G. J. M. VANDERKREEK, *Recl. Trav. Chim. Pays-Bas*, 1961, 70, 917.

# Some Lanthanide-EDTA Ternary Complexes with Catechol, Resorcinol and Phloroglucinol

S. N. LIMAYE and M. C. SAXENA\*

Department of Chemistry, University of Sagar, Sagar-470 008

Manuscript received 18 June 1981, revised 12 February 1982, accepted 8 July 1982

The proton-ligand stability constants of catechol, resorcinol and phloroglucinol and the metal-ligand stability constants of the 1 : 1 binary complexes, ML ( $M = La^{3+}$ ,  $Ce^{3+}$ ,  $Pr^{3+}$ ,  $Nd^{3+}$  or  $Sm^{3+}$  and  $L = cat, res$  or  $phl$ ) and 1 : 1 : 1 ternary complexes, MAL ( $M = La^{3+}, Ce^{3+}, Pr^{3+}, Nd^{3+}$  or  $Sm^{3+}$ ;  $A = edta$ ;  $L = cat, res$  or  $phl$ ) have been determined at 28° and  $\mu = 0.2M$  ( $NaClO_4$ ) using Irving-Rossotti pH-titration technique. The stability constant values have been found to lie in the order  $\log K_{MA}^M \gg \log K_{ML}^M > \log K_{MAL}^{MA}$ . The  $\Delta F$  and  $\Delta \log K$  values have been calculated. The stability of the complexes ML as well as MAL is found to be in the sequence  $cat > res > phl$  with respect to the secondary ligands, and  $La^{3+} < Ce^{3+} < Pr^{3+} < Nd^{3+} < Sm^{3+}$  with respect to the metal ions.

Validity of Born's relation has been tested for the ternary complexes MAL. The  $\log K_{MAL}^{MA}$  values have been correlated with the standard entropies, standard electrode-potentials and ionic potentials of the lanthanides.

The  $\log K_{MAL}^{MA}$  vs  $\log K_{ML}^M$  or  $\log K_{MA}^M$  plots are found to be linear. Comparison of the experimental values of  $\log K_{MAL}^{MA}$  for catechol with the literature values for some corresponding edta and nta ternary lanthanide complexes reveals the stability sequence  $nta > edta > cat$ .

**STABILITY** constants of 1 : 1 : 1 ternary complexes of the type  $[M(II)-edta-cat]^+$ , where  $M(II) = Ni^{2+}$ ,  $Cu^{2+}$ ,  $Zn^{2+}$  or  $Cd^{2+}$ ,  $[Ni(II)-o-phen-cat]^+$ ,  $[Ni(II)-dipy-cat]^+$  and  $[M(III)-A-cat]^+$ , where  $M(III) = La^{3+}, Pr^{3+}$  or  $Nd^{3+}$  and  $A = edta$  or  $nta$ , have been determined by earlier workers. Stability constants of binary lanthanide-catechol chelates have also been reported recently<sup>1</sup>.

The present work deals with the determination of the stability constants of 1 : 1 binary and 1 : 1 : 1 ternary lanthanide complexes using edta as a primary ligand and catechol (cat), resorcinol (res) or phloroglucinol (phl) as a secondary ligand. Some stability correlations have also been attempted.

## Experimental

Standard solutions of catechol, resorcinol and phloroglucinol were prepared in double distilled water by direct weighing. The lanthanide solutions were prepared by dissolving the nitrates of  $La(III)$ ,  $Ce(III)$  and  $Sm(III)$  in water.  $Pr(III)$  and  $Nd(III)$  oxides were dissolved in minimum quantity of perchloric acid, excess of which was carefully evaporated and checked before-hand so as to eliminate the possibility of any extra acid in the metal ion solution. EDTA was used as its disodium salt, the two remaining protons were also taken care of.

The usual titration sets i.e. (i) acid, (ii) acid + secondary ligand (L), (iii) acid + L + metal ion (M)

for the binary complexes; and (i) acid + primary ligand (A) + M, (ii) acid + L, (iii) acid + M + A + L for the ternary complexes were prepared. The ionic strength was maintained at  $\mu = 0.2M$  ( $NaClO_4$ ). Dilute solutions ( $10^{-3}M$ ) were used to avoid the possibility of formation of polynuclear species. The sets were titrated pH metrically against 0.2M carbonate free NaOH, at 28° using Irving-Rossotti titration technique<sup>2</sup>.

A digital pH-meter (model Elico-LI-120) was used. Reproducible pH readings were used for calculations. Plots of pH vs alkali added for 1 : 1 binary complexes of  $La(III)$  with cat, res and phl and those for the corresponding 1 : 1 : 1 ternary complexes were worked out.

## Results and Discussion

The calculated values of proton-ligand stability constants  $\log K_1^H$  and  $\log K_2^H$  of the secondary ligands are recorded in Table 1. The metal-ligand stability constants of 1 : 1 binary complexes with

TABLE 1—PROTON-LIGAND STABILITY CONSTANTS OF THE SECONDARY LIGANDS

Ionic strength  $\mu = 0.2M$  ( $NaClO_4$ ), Temp. = 28°

Ligand	$\log K_1^H$	$\log K_2^H$	$\log \beta$
Catechol	9.20	11.70	20.90
Resorcinol	9.07	11.07	20.14
Phloroglucinol	8.90	9.76	18.66

TABLE 2—METAL-LIGAND STABILITY CONSTANTS OF 1:1 BINARY AND 1:1:1 TERNARY LANTHANIDE COMPLEXES

Metal ion	$\log K_{MA}^M$	Catechol				Resorcinol				Phloroglucinol			
		$\log K_{ML}^M$	$\log K_{MAL}^{MA}$	$-\Delta \log K$	$-\Delta F^*$	$\log K_{ML}^M$	$\log K_{MAL}^{MA}$	$-\Delta \log K$	$-\Delta F^*$	$\log K_{ML}^M$	$\log K_{MAL}^{MA}$	$-\Delta \log K$	$-\Delta F^*$
La <sup>3+</sup>	9.31	8.55 ( $\pm 0.03$ )	6.20 ( $\pm 0.08$ )	2.35	8.59	4.45 ( $\pm 0.03$ )	2.10 ( $\pm 0.04$ )	2.35	2.91	3.50 ( $\pm 0.02$ )	2.20 ( $\pm 0.03$ )	1.30	3.05
Ce <sup>3+</sup>	9.02	8.65 ( $\pm 0.04$ )	6.50 ( $\pm 0.02$ )	2.15	9.01	4.55 ( $\pm 0.02$ )	2.20 ( $\pm 0.04$ )	2.35	9.05	3.75 ( $\pm 0.04$ )	2.40 ( $\pm 0.03$ )	1.35	3.33
Pr <sup>3+</sup>	9.96	8.90 ( $\pm 0.04$ )	6.70 ( $\pm 0.03$ )	2.20	9.29	5.05 ( $\pm 0.04$ )	2.35 ( $\pm 0.03$ )	2.70	8.36	3.90 ( $\pm 0.03$ )	2.50 ( $\pm 0.05$ )	1.40	3.47
Nd <sup>3+</sup>	10.56	9.10 ( $\pm 0.07$ )	7.00 ( $\pm 0.05$ )	2.10	9.70	5.35 ( $\pm 0.07$ )	2.50 ( $\pm 0.05$ )	2.85	3.47	4.00 ( $\pm 0.07$ )	2.60 ( $\pm 0.02$ )	1.40	3.60
Sm <sup>3+</sup>	11.02	9.20 ( $\pm 0.03$ )	7.45 ( $\pm 0.05$ )	1.75	10.32	5.95 ( $\pm 0.03$ )	3.05 ( $\pm 0.03$ )	2.90	4.23	4.20 ( $\pm 0.02$ )	2.70 ( $\pm 0.02$ )	1.50	3.74

\*  $-\Delta F = K \text{ cal mole}^{-1}$ .

A ( $\log K_{MA}^M$ ) and L ( $\log K_{ML}^M$ ) and of 1:1:1 ternary complexes ( $\log K_{MAL}^{MA}$ ) along with their standard deviations (in parentheses) are shown in Table 2. The  $\Delta \log K$  values i.e.  $\log K_{MAL}^{MA} - \log K_{ML}^M$  and the  $\Delta F$  values for the ternary complexes ( $\Delta F = -RT \log K_{MAL}^{MA}$ ) are also included in this table.

It was observed from the pH plots that the separation of secondary ligand curve from the acid curve took place at  $pH \approx 7$  due to ionisation of the phenolic group in the relatively higher pH range. The values of  $\bar{n}_H$  obtained in the range  $0 < \bar{n}_H < 2$  have been used to calculate  $\log K_1^H$  and  $\log K_2^H$  for cat, res and phl. The values are in good agreement with those reported in literature<sup>7,8</sup>. The higher value of  $\log K_2^H$  over that of  $\log K_1^H$  may be due to lowering of the inductive effect in the second step of ionisation<sup>9</sup> and also hydrogen bonding<sup>10</sup>. The observed sequence of ligand basicity, cat > res > phl, is expected due to a greater proximity of the phenolic groups in catechol.

It was found that the binary complex curve practically overlapped the ligand curve in the lower buffer region, which minimised the possibility of formation of any protonated species<sup>11</sup>. The separation of the two curves occurred at  $pH \approx 5.5$  to 6.0 indicating complexation. The  $\bar{n}$  values have been calculated in the pH range where no precipitation was observed. The ternary complex curve separated at lower pH region from the curves of the primary complex and the secondary ligand indicating the formation of the ternary complex. This has been further confirmed by the non-superimposable<sup>12</sup> nature of the theoretical composite curve on the experimental curve of ternary complex. The ternary complex is obviously formed according to the scheme:  $M + A \rightleftharpoons MA$ ;  $MA + L \rightleftharpoons MAL$ .

A perusal of the values of stability constants (Table 2) shows that the general order is  $\log K_{MA}^M \gg \log K_{ML}^M > \log K_{MAL}^{MA}$ . The much higher value of  $\log K_{MA}^M$  over that of  $\log K_{ML}^M$  eliminates

the possibility of ligand displacement,  $MA + L \rightleftharpoons ML + A$ , in the ternary systems. Any disproportionation of the ternary complex MAL is also discounted as the hexadentate nature of edta will not favour the formation of the species  $MA_2^{13}$ . The lower values of  $\log K_{MAL}^{MA}$  may be due to coulombic repulsion between the negatively charged primary complex MA,  $[Ln-edta]^-$ , and the incoming secondary ligand ( $L^-$  or  $L^{2-}$ ). Steric repulsions and statistical considerations are also expected to contribute towards the lowering of  $\log K_{MAL}^{MA}$  value as compared to  $\log K_{ML}^M$ . The  $\Delta \log K$  values are consequently negative.

Calculation of % ionisation<sup>14</sup> reveals that the second phenolic-OH in res and phl is very little ionised (res; 0.09-2.4%; phl; 0.2-24%) in the pH range used for calculations. It, therefore, appears reasonable to use only the  $\log K_1^H$  value in these two cases for calculating the stability constants. The sequence of stability with respect to the secondary ligands for binary as well as ternary complexes has been found to be cat > res > phl, which is the order of ligand basicities. The variation of  $\log K_{MAL}^{MA}$  for the lanthanides shows the expected trend  $La^{3+} < Ce^{3+} < Pr^{3+} < Nd^{3+} < Sm^{3+}$ , which is the order of decreasing ionic radii of the metal ions. The relative complexing tendencies as measured by  $K_{MA}^M/K_{ML}^M$  are found to lie in the sequence phl > res > cat; the variations in numerical values being large e.g.,  $10^6$  to  $10^2$  for the  $La^{3+}$  complexes.

Unlike the '3d'-elements, the lanthanides are highly electropositive with large ionic radii and their 4f<sup>n</sup> electrons are well shielded by the outer lying 5s and 5p orbitals from ligand perturbations. The metal-ligand bond should, therefore, be ionic with a minimal covalent contribution, if at all. Born relation<sup>15</sup>  $E = z^2/2r(1-1/D)$  (where  $E$  = energy of complexation,  $z$  = charge and  $r$  = ionic radius of the metal ion) has been tested for the present series of ternary complexes. Plots of  $\log K_{MAL}^{MA}$  vs  $z^2/r$  were found to be curved, which may be due to partial covalent nature<sup>16</sup> of the bond and varying degrees of stabilisation caused by the ligand field. Similar

observations<sup>17-19</sup> have been noted for some other lanthanide complexes.

The  $\log K_{MAL}^{MA}$  values were plotted against  $\log K_{MA}^M$  and  $\log K_{ML}^M$  and produced almost linear plots indicating similarity in bonding in the binary and ternary complexes. Slight deviations from linearity may be due to additional steric effects involved in the formation of the ternary complexes.

The variation of  $\log K_{MAL}^{MA}$  with the standard entropies,  $S^\circ$ , of the lanthanides<sup>20</sup> showed a linear increase in the stability constant with  $S^\circ$  indicating that the changes in free energy during complexation are essentially changes in entropy. A similar trend has been observed for the 1:1 Ln-edta complexes by Foreman and Smith<sup>21</sup>. The stability constants of the ternary complexes increased regularly with increase in the ionic potentials of the lanthanides. This trend is expected in view of the decreasing ionic radii of trivalent lanthanide cations. Standard electrode potentials,  $E^\circ$ , of the lanthanides plotted against the stability constants yielded a linear plot. The free energy corresponding to the standard electrode potential comprises mainly the heat of formation of the bare  $Ln^{3+}$  ion and its heat of hydration. The latter being the heat of ligation of water molecules, one may expect a gradual increase in  $\log K_{MAL}^{MA}$  value with decrease in the numerical value of  $E^\circ$  (with increasing value of  $4f^n$ ) for the lanthanides.

It is interesting to note an expected trend between our values of  $\log K_{MAL}^{MA}$  and the reported values for similar ternary systems as shown below :

System	$\log K_{MAL}^{MA}$			Reference
	$La^{3+}$	$Pr^{3+}$	$Nd^{3+}$	
Ln-edta-cat	4.83	5.69	6.10	4
Ln-edta-cat	6.20	6.70	7.00	Present work
Ln-nta-oat	6.90	6.98	7.86	4

The increase in  $\log K_{MAL}^{MA}$  values in the order  $cdta < edta < nta$  may be due to (i) greater coulombic repulsion in the case of  $cdta$  and  $edta$  between the primary and secondary ligands than in the case of  $nta$ , (ii) availability of more coordination sites for the secondary ligand in the case of  $nta$  than for  $cdta$  and  $edta$  and (iii) between  $edta$  and  $cdta$ , greater loss of conformational freedom in the case of  $cdta$ .

The only comparable values of  $\log K_{MAL}^{MA}$  for the '3d'-elements as reported by Bhattacharya *et al.*<sup>1</sup> are  $[Ni(II)-edta-cat]$ , 4.44;  $[Cu(II)-edta-cat]$ , 7.01 and  $[Zn(II)-edta-cat]$ , 3.73. The higher value for the  $Cu(II)$  complex may be attributed chiefly to Jahn Teller distortion resulting in increased binding energy.

#### Acknowledgement

The authors are thankful to Prof. A. V. Mahajani, Head, Department of Chemistry, University of Saugar for laboratory facilities. One of the authors (S. N. L.) is thankful to the U. G. C., New Delhi for a Senior Research Fellowship.

#### References

1. I. P. MAVANI, G. R. JEJURKAR and P. K. BHATTACHARYA, *Bull. Chem. Soc., Japan*, 1974, 47, 1290.
2. D. O. PATEL and P. K. BHATTACHARYA, *J. Inorg. Nuclear Chem.*, 1971, 33, 529.
3. J. D. JOSHI, G. R. JEJURKAR and P. K. BHATTACHARYA, *Indian J. Chem.*, 1978, 17, 940.
4. H. B. RANA and J. P. TANDON, *J. Indian Chem. Soc.*, 1976, 53, 128; *Indian J. Chem.*, 1976, 14A, 914.
5. B. C. BHUYAN and S. N. DUBEY, *J. Indian Chem. Soc.*, 1981, 58, 618.
6. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1953, 3897, 1954, 2904.
7. S. D. MAKHIJANI and S. P. SEHGAL, *J. Indian Chem. Soc.*, 1976, 53, 565.
8. S. S. SANDHU, R. S. SANDHU, J. N. KUMARIA, JASBIR SINGH and N. S. SEKHON, *J. Indian Chem. Soc.*, 1976, 53, 114.
9. PETER SYKES, "A Guide Book to Mechanism in Organic Chemistry", Oriental Longman Ltd., 1970, p. 46.
10. E. A. BRAUDE and F. O. NOCHOD, "Determination of Organic Structures by Physical Methods", Academic Press, N. Y., 1955, p. 629.
11. S. P. TRIPATHI, G. K. CHATURVEDI and R. C. SHARMA, *J. Indian Chem. Soc.*, 1981, 58, 848.
12. G. H. CARREY and A. E. MARTELL, *J. Amer. Chem. Soc.*, 1967, 89, 2859.
13. L. O. THOMPSON and J. A. LORASS, *Inorg. Chem.*, 1968, 7, 89.
14. A. ALBERT and E. P. SARJEANT, "Ionization Constants of Acids and Bases", John Wiley and Sons, Inc., New York, 1962, p. 9.
15. T. D. MOELLER, *Chem. Rev.*, 1955, 65, 1.
16. F. J. SPEDDING, D. E. POWELL and E. J. WHEELRIGHT, *J. Amer. Chem. Soc.*, 1956, 78, 84.
17. L. K. A. SHARLEY and T. RANDALL, *Discuss. Faraday Soc.*, 1958, 26, 157.
18. G. P. SENGUPTA and C. R. BERA, *J. Indian Chem. Soc.*, 1980, 57, 558.
19. M. S. MAYADRO and S. S. PURONIT, *J. Indian Chem. Soc.*, 1980, 57, 1047.
20. F. D. DYER and D. P. MOELLER, "Chelating Agents and Metal Chelates", Academic Press, 1964, p. 292.
21. J. K. FOREMAN and T. D. SMITH, *J. Amer. Chem. Soc.*, 1967, 79, 1752.

# Metal Ion Interactions with the Constituents of Nucleic Acid. Part-I : Metal-Adenine Complexes

R. G. BHATTACHARYA and (Mrs.) I. BHADURI

Department of Chemistry, Jadavpur University, Calcutta-700 082

Manuscript received 10 September 1979, revised 9 February 1982, accepted 28 May 1982

Metal-adenine complexes of the type  $[Cd(AdH)_2Cl_2]$ ,  $[Hg_2Cl_2(Ad)_2(AdH)_2]$ ,  $[Pd_2Cl_2(Ad)_2(AdH)_2] \cdot 2H_2O$  and  $[UO_2(Ad)_2(H_2O)_2] \cdot H_2O$  have been isolated and characterised by analytical, infrared and TGA data. The AdH (neutral adenine) is probably unidentate in the Cd complex whereas in the Hg and Pd complexes, it functions probably as a bidentate bridging ligand, linking two metal ions. In the case of the Pd complex, Ad coordinates through C(6) NH<sub>2</sub> and N(7) but in all other cases possibly through N(3) and N(9) atoms.

THE biologically important intermolecular transfer of a phosphoryl group of adenosine triphosphate is an enzymic process with an absolute metal ion requirement. The non-enzymic transphosphorylation occurring between ATP and orthophosphate ion is also catalysed by bivalent metal ions, notably  $Mn^{2+}$ ,  $Ca^{2+}$  and  $Cd^{2+}$ . In a recent publication<sup>1</sup> we described the synthesis and characterisation of some metal-ATP complexes with particular emphasis on the binding sites. Adenine, one of the constituent bases of nucleic acids and the constituent base of ATP, is known<sup>2</sup> to enter into metal coordination either as a neutral molecule, AdH, or as a mono-anion, Ad<sup>-</sup> [by the deprotonation of N(9) i.e. the imino nitrogen]. In acid medium the base also coordinates as adeninium cation, AdH<sup>+</sup>, where apart from N(9) [where one proton normally resides in free neutral adenine but if this nitrogen is linked with metal on coordination, the proton shifts to N(7)<sup>3</sup>], N(1) is also protonated<sup>4,5</sup>.

The earlier work<sup>6,7</sup> regarding the preparation of the Au(III) adenine complex in dil HCl medium probably involves adenine in the form of the cation AdH<sup>+</sup>. Only comparatively recently the Cu(II), Zn(II) and Pt(II) complexes with adenine have been isolated and their structures studied<sup>8-10</sup>. In this paper, we report the complexes of adenine with Cd(II), Hg(II), Pd(II) and  $UO_2(II)$ .

## Experimental

**Preparation of the complexes:** The Cd(II), Hg(II) and Pd(II) complexes are prepared by adding an aqueous solution of adenine in twice molar proportion to the respective metal chloride solution in water (aqueous NaCl in the case of  $PdCl_2$ ). The precipitated solids (the pH of the medium after the precipitation of the complexes remains at 5) were washed with hot water, ethanol and ether and dried in vacuum.

In the case of dioxouranium(VI) complex, the aqueous solution of  $UO_2(NO_3)_2 \cdot 6H_2O$  and adenine

were mixed in 1 : 2 molar ratio but the resultant solution was clear. The pH was raised to 5 by adding NaOH solution and the precipitated solid was washed and dried as in the other cases.

The compounds are insoluble in water as well as in all organic solvents.

**Materials and methods:** All chemicals used were of analytical grade. The infrared spectra ( $4000-200\text{ cm}^{-1}$ ) as CsI pellets were recorded in a Perkin-Elmer Model 597 IR spectrophotometer. The water content and the decomposition temperatures were followed from the TGA curves<sup>11</sup>.

## Results and Discussion

The composition of the complexes and their analytical data are recorded in Table I. The composition of the complexes, suggested on the basis of their analytical data is further corroborated by their infrared vibrational frequencies. In molecules like adenine, the intensity of the  $\nu NH_2$  bands ( $\sim 3300\text{ cm}^{-1}$ ) is expected<sup>12</sup> to be not much greater than that of the  $\nu NH$  ( $\sim 3150\text{ cm}^{-1}$ ). The position and relative intensities of the infrared bands may therefore be considered here as reasonable guide in deciding ligand type (neutral, anionic or cationic) and the probable binding sites. Making proper allowance for any intermolecular hydrogen bonding (specially in the free adenine molecule) and roughly analysing the overlapping  $NH_2$  and  $NH$  bands as per Gaussian method, it appears that in adenine (3250, 3050) the intensity of the said bands are in the ratio 1 : 1 and so also in the Cd compound (3300, 3135), but in the Hg compound (3325, 3050) the intensity of the former band is roughly double of that of the latter. These observations support the suggested compositions. Strong water absorption of the uranium compound as well as the medium intensity broad water band in the palladium complex frustrate such an attempt.

Comparing the positions of the four  $\delta NH_2$  bands<sup>13</sup> in free adenine [1675 (s), symmetric in

TABLE 1—THE COMPOSITION, COLOUR, ANALYTICAL AND THE INFRARED DATA OF THE COMPLEXES

Compounds	Colour	Analysis%				(M-Cl)* cm <sup>-1</sup>	(M-N)† cm <sup>-1</sup>
		M Found (Calcd.)	N Found (Calcd.)	Cl Found (Calcd.)	H <sub>2</sub> O Found (Calcd.)		
CdCl <sub>2</sub> (AdH) <sub>2</sub>	White	25.1 (24.8)	31.4 (30.9)	16.2 (15.7)	—	340	542
Hg <sub>2</sub> Cl <sub>2</sub> (AdH)(Ad) <sub>2</sub>	White	45.1 (45.8)	24.0 (24.0)	9.2 (8.1)	—	338	545
Pd <sub>2</sub> Cl <sub>2</sub> (AdH)(Ad) <sub>2</sub> ·2H <sub>2</sub> O	Yellow	29.4 (29.7)	28.8 (29.0)	10.4 (9.8)	4.7 (5.0)	325	445
UO <sub>2</sub> (Ad) <sub>2</sub> ·8H <sub>2</sub> O	Yellow	39.6 (40.1)	23.9 (23.6)	—	9.4 (9.1)	—	400

\* Ref. 14c-16, † Ref. 14a-18.

plane; 1250 (m), asymmetric out of plane; 910 (m), symmetric out of plane and 718 (m); asymmetric in plane deformation] and metal bound adenine (bands almost retain their positions), it is clear that




Fig. 1. The infrared spectra of (1) Cd complex, (2) Hg complex, (3) Pd complex and (4) UO<sub>2</sub> complex.

unlike the ATP complexes\* [the bands described\* as  $\nu(\text{CN})$  should be the symmetric in plane deformation of the  $\text{NH}_2$  group in ATP and its complexes; other  $\delta\text{NH}_2$  bands are also there] the bands here do not undergo red shift (rather slightly blue shifted) on complexation, excepting in the case of Pd(II) complex, where it does [1645 (s), 1218 (m); 910  $\text{cm}^{-1}$  band not observed]. This observation excludes the possibility of coordination through the C(6)  $\text{NH}_2$  group in all the cases except that of the Pd(II), where the coordination definitely occurs through the said  $\text{NH}_2$  group (see Fig. 1 for comparison). Modelling<sup>18</sup> indicates that involvement of the  $\text{NH}_2$  group in coordination almost commits the participation of the N(7) of adenine. It may, therefore, be concluded that in the Pd(II) complex, Ad functions as a bidentate ligand linking through C(6)  $\text{NH}_2$  and the N( ). Since in the said complex only a single type of  $\text{NH}_2$  group is found from the ir data, the AdH probably functions as a bridging ligand between two Pd(II) groups—one linked to N(7) and the other to C(6)  $\text{NH}_2$  group (Fig. 2A). This contention is also supported by the  $\nu(\text{Pd}-\text{Cl})$  vibration (325  $\text{cm}^{-1}$ ) which indicates that chloride is present as a terminal ligand and not a bridging one<sup>14c</sup>. Similarly, in the Cd and Hg complexes the  $\nu(\text{M}-\text{Cl})$  band (Table 1) is indicative of terminal chloride ligands. No other band at still lower wave number regions is present in any of the cases (Fig. 1) thereby ruling out the possibility of a bridging M-Cl bond (see also refs. 15 and 16). It may also be quite pertinent to mention here that  $[\text{Cu}_2\text{Ad}_2]$  (prepared by the method of Weiss and Venner<sup>8</sup> and ir spectra recorded by us for comparison) complex is ir transparent in the region 400-200  $\text{cm}^{-1}$ . However, in the Pd complex, as expected, the ring vibrations<sup>11</sup> of the purine ring is only very slightly modified after the involvement of the N(7) during metallation. In fact, the ring vibrations in the other cases ( $\text{Cd}^{2+}$ ,  $\text{Hg}^{2+}$  and  $\text{UO}_2^{2+}$ ) are a bit more modified. Based on these observations, and also the fact that in the latter two cases the  $\text{NH}_2$  group remains free, it may be presumed that Ad<sup>-</sup> in these cases functions as a bidentate ligand linking through N(3) and N(9) (Figs. 2B and 2C) as was confirmed in the case of Cu(II) by X-ray crystallography<sup>9</sup>. In the Hg(II)



complex, AdH probably acts as a bridging group linking through two Hg(II) ions, one with N(3) and the other with N(9), since here also only one type of  $\text{NH}_2$  mode is present and the possibility of chlorine bridging is excluded from the far ir spectroscopy. Since the Cd(II) complex should be 4-coordinated, the AdH groups probably act here as a unidentate ligand linking through the N(9) (Fig. 2D), a site which might be preferred to N(3) (compare the nucleoside formation by linking through sugars at this point).

After a thorough comparison of the ir bands of adenine with those of the complexes, the  $\nu(\text{U}-\text{N})$  is assigned<sup>17</sup> at 400 while the  $\nu(\text{Pd}-\text{N})$  band at




Fig. 2. The most probable structures of (A) Pd complex, (B) Hg complex, (C)  $\text{UO}_2$  complex and (D) Cd complex.

$445^{14a}$  and the  $\nu(\text{Cd}/\text{Hg}-\text{N})$  bands in the vicinity of  $540\text{ cm}^{-1}$  (Table I). The Cd and Hg-N vibrations at higher wave numbers are also corroborated by earlier work on the N-chelates<sup>14a</sup>. The  $\text{UO}_2^{2+}$  complex contains two other bands, one at  $320$  and the other at  $260\text{ cm}^{-1}$ . The latter band is assigned to the  $\nu_2$  (bending vibration)<sup>18,20</sup> of the  $\text{UO}_2^{2+}$  ion while the former is assignable to the  $\nu(\text{U}-\text{O})$  band arising out of the water ligands<sup>14b,20-22</sup>.

TGA curves show that the water molecules in the Pd(II) complex and one of the water molecules in the  $\text{UO}_2^{2+}$  complex are lost well below  $100^\circ$  indicating that they are only weakly held in the lattice. Other water molecules present in the appropriate cases are lost just below  $150^\circ$  showing that they are coordinated. (However the  $\delta\text{H}_2\text{O}$  bands are entrapped within the strong  $\delta\text{NH}_2$  absorption). All these confirm the suggested structures (Fig. 2).

The compounds are insoluble and the possibility of molecular polymerisation could not be ruled out. Also, the insolubility of the complexes even in DMSO did not permit any NMR work which would have been more conclusive. They are prepared under such a condition that isolation of good crystals are impossible. So, presently, our knowledge should remain limited to the formulation of the most probable structures (Fig. 2A-2D).

#### Acknowledgement

The authors are grateful to the Council for Scientific and Industrial Research, New Delhi for financial support and a Research Fellowship to one of them (I. B.). The authors also thank the Alexander von Humboldt Foundation (F. R. G.) for the donation (to R. G. B.) of the Infrared spectrophotometer used in this investigation.

#### References

1. J. N. LOWENSTEIN, *Biochem. J.*, 1958, **70**, 222.
2. R. G. BHATTACHARYYA and I. BHADURI, *J. Inorg. Nuclear Chem.*, 1978, **40**, 788.
3. D. J. HODGSON, *Prog. Inorg. Chem.*, 1977, **23**, 211.
4. J. J. CHRISTENSEN, J. H. RYTTING and R. M. IZAT, *Biochem.*, 1970, **6**, 4907; M. J. MCCALL and M. TAYLOR, *Biochem. Biophys. Acta*, 1975, **390**, 187.
5. W. COCHRAN, *Acta Cryst.*, 1951, **4**, 81; P. D. MEESTER and A. C. SKAPSKI, *J. Chem. Soc., Dalton Trans.*, 1959, 1598.
6. E. SLETTEN, *J. U. S. Chem. Commun.*, 1967, 1119.
7. H. HOLZ and H. MÜLLER, *Arch. Exp. Pathol. Pharmacol.*, 1974, **30**, 105.
8. R. WEISS and H. VERNER, *Z. Phys. Chem. (Lpz)*, 1966, **34**, 122; P. D. MEESTER, D. M. L. GOODGAN, A. C. SKAPSKI and Z. WARNER, *Biochem. Biophys. Acta*, 1973, **324**, 301; I. J. KISTENMACHER, *Acta Cryst.*, 1978, **B29**, 1974; M. J. MCCALL and M. TAYLOR, *Acta Cryst.*, 1976, **B32**, 1687.
9. P. D. MEESTER and A. C. SKAPSKI, *J. Chem. Soc. (A)*, 1971, 2167; A. TERZIS, A. L. BEAUCHAMP and RIVEST, *Inorg. Chem.*, 1973, **12**, 1116.
10. I. SRINIVASAN and M. TAYLOR, *J. C. S. Chem. Commun.*, 1970, 1668; M. R. TAYLOR, *Acta Cryst.*, 1973, **B29**, 86; A. TERZIS, N. HADJILIAS, R. RIVEST and THEOPHANIDES, *Inorg. Chim. Acta*, 1975, **17**, 45.
11. L. J. BELLAMY, "The Infrared Spectra of Complex Molecules", Chapman and Hall, London, 1975.
12. A. N. SPEKA, C. M. MIEULSKI, F. J. IACONIANI, L. PYTLEWSKI and N. M. KARAYANNIS, *Inorg. Chim. Acta*, 1979, **37**, L551 and references therein.
13. "Frame-work Molecular Model", Prentice-Hall, Englewood Cliffs, N. Y., U. S. A.
14. K. NAKAMOTO, "Infrared and Raman Spectra of Inorganic and Coordination Compounds", Wiley, New York, 1979, p. (a) 197-216, (b) 226-229 and (c) 817-823.
15. R. J. GOODFELLOW, P. L. GOGGIN and I. M. VENNA, *J. Chem. Soc., A*, 1967, 1897.
16. M. GOLDSTEIN and W. D. UNSWORTH, *Inorg. Chim. Acta*, 1970, **4**, 342.
17. P. THOMAS, *Z. Chem.*, 1977, **17**, 74.
18. T. ITAMOTO and D. F. SHRIVER, *Inorg. Chem.*, 1971, **10**, 2428.
19. S. P. MCGLYNN, J. K. SMITH and W. C. NEELEY, *J. Chem. Phys.*, 1961, **35**, 105.
20. K. ONWADA, *J. Coord. Chem.*, 1976, **6**, 75.
21. J. I. BULLOCK and F. W. PARRETT, *Canad. J. Chem.*, 1970, **48**, 8095.
22. I. NAKAGAWA and T. SHIMANOUCHI, *Spectrochim. Acta*, 1964, **20**, 429.
23. L. CATALINI, U. CROATTO, S. DREOTTO and TONDEUO, *Inorg. Chim. Acta Rev.*, 1971, **5**, 19; references therein.

## Preparation and Characterization of Naphthoxides of Niobium(V) and Tantalum(V)

K. C. MALHOTRA, (Miss) GEETA MATHUR, K. C. MAHAJAN and S. C. CHAUDHRY

Department of Chemistry, Himachal Pradesh University, Simla-171 005

Manuscript received 17 February 1981, revised 9 December 1981, accepted 8 July 1982

Compounds of composition  $MCl_n(ONp)_{4-n}$ , where  $M = Nb$  or  $Ta$ ,  $ONp$  = anion of  $\beta$ -naphthol and  $n = 0$  to  $4$ , have been prepared by digesting pentachlorides of the metals with  $\beta$ -naphthol in appropriate molar ratios in carbon tetrachloride. Their structures have been elucidated from elemental analysis, conductance, magnetic susceptibility, infrared and TGA studies.

COMPARED to alkoxides, very little work has been carried out on the synthesis of metal phenoxides and naphthoxides, inspite of their utility as catalysts in many industries<sup>1</sup>. Prasad and coworkers<sup>2</sup> isolated two series of compounds of anhydrous aluminium chloride with  $\beta$ -naphthol. Halides of titanium(IV) and zirconium(IV) are known to react with phenols and naphthols to form the corresponding derivatives but their structural information is lacking<sup>3</sup>. Reaction of selenium dithiocyanate with naphthols has been found to be useful for introducing SCN group into organic compounds<sup>4</sup>. Naphthols have been reported to be most effective and convenient amongst the phenols for the separation of ruthenium from uranium<sup>5</sup>. Naphthoxides of beryllium(II) and tungsten(V) have been isolated by reacting their halides with  $\beta$ -naphthol<sup>6</sup>. It is, therefore, of interest to isolate and characterise naphthoxides of transition metals. In the present communication, we report the preparation of naphthoxides of niobium(V) and tantalum(V) and propose a possible structure on the basis of elemental analysis, molar conductance, TGA, magnetic and infrared spectral studies.

### Experimental

Naphthol (A.R.) was purified by crystallisation from dry benzene. Pentachlorides of niobium and tantalum, were Fluka, analytical grade, and were used without further purification. All the organic solvents were of AnalaR grade. They were further dried by appropriate drying agents and fractionally distilled.

Compounds of composition  $MCl_4(ONp)$ ,  $MCl_3(ONp)_2$  and  $MCl_2(ONp)_3$ , where  $M$  stands for niobium or tantalum and  $ONp$  stands for the anion of  $\beta$ -naphthol, were obtained by mixing corresponding pentachlorides with  $\beta$ -naphthol in exact 1 : 1, 1 : 2 and 1 : 3 molar ratio in dry carbon tetrachloride and continuous stirring at room temperature till there was no evolution of HCl gas. But in case of compounds of composition  $MCl(ONp)_4$  and  $M(ONp)_5$ , the corresponding

mixture solutions were heated occasionally (not more than 60°). To ensure complete substitution by naphthoxy groups in the last compound,  $\beta$ -naphthol in 1 : 5 molar ratio was taken in a little excess and digested till there was no evolution of HCl gas. The compounds so obtained were filtered, washed repeatedly with dry benzene and finally dried under vacuum.

Niobium and tantalum were estimated as their pentoxides and chlorine by Volhard's method. Infrared spectra of the complexes were recorded on a double grating infrared spectrophotometer, Perkin-Elmer 337 and 621, in KBr pellets. Molar conductance values of  $10^{-3}M$  solutions of these compounds in nitrobenzene were determined using a cell of cell constant  $0.384$  at  $25 \pm 0.1^\circ$  with a Toshniwal conductivity bridge, CLO1/01A Sr. No. 447. Thermogravimetric analysis was carried out on a Stanton thermogravimetric balance, model AD-2 at a heating rate of  $5^\circ/\text{min}$ . Magnetic susceptibility measurements were made on a Guoy's balance at room temperature.

### Results and Discussion

The reactions of pentachlorides of niobium and tantalum with  $\beta$ -naphthol in carbon tetrachloride were found to be slow but became facile on digestion. All attempts to isolate a solvate of  $\beta$ -naphthol with pentachlorides of niobium and tantalum at room temperature were unsuccessful, possibly because of the greater lability of the proton of naphthol. The niobium compounds gave dull orange crystals whereas, the tantalum compounds were sulphur yellow in colour. Stoichiometric composition of these compounds was established by elemental analysis and results are reported in Table I. All these compounds are moisture sensitive and change their colour on exposure but are sufficiently stable in dry air. They are insoluble in most organic solvents except slight solubility in nitrobenzene and dimethylformamide. Molar conductance values of  $10^{-3}M$  solutions in nitrobenzene (Table I) suggest that the compounds are non-ionic.

TABLE 1—ANALYTICAL DATA OF THE ISOLATED NIOBIUM AND TANTALUM COMPLEXES

Compound	Colour	Elemental analysis				Molar conductance in nitrobenzene (ohm <sup>-1</sup> cm <sup>2</sup> mole <sup>-1</sup> )
		% Found		% Req'd.		
		M	Cl	M	Cl	
Nb(ONp) <sub>3</sub>	Brick red	10.80	—	11.50	—	18*
NbCl(ONp) <sub>3</sub>	Light brick red	13.00	4.95	13.82	5.07	2
NbCl <sub>2</sub> (ONp) <sub>2</sub>	Deep orange	14.28	11.25	15.70	12.00	3
NbCl <sub>3</sub> (ONp)	Orange	18.88	21.28	19.15	21.97	2
NbCl <sub>4</sub> (ONp)	Orange	25.02	26.82	24.16	27.05	16*
Ta(ONp) <sub>3</sub>	Dull yellow	20.00	—	20.20	—	10*
TaCl(ONp) <sub>3</sub>	Deep yellow	21.82	4.08	22.90	4.50	2
TaCl <sub>2</sub> (ONp) <sub>2</sub>	Sulphur yellow	25.89	9.72	26.60	10.40	2
TaCl <sub>3</sub> (ONp)	Yellow	30.74	17.81	31.20	18.60	11*
TaCl <sub>4</sub> (ONp)	Yellow	37.25	29.31	38.80	30.40	2

\* In dimethylformamide.

in nature. Molecular weight determinations could not be carried out because the compounds are insoluble in solvents suitable for cryoscopy. They are diamagnetic, excluding thereby the possibility of any reduction of the metal to the lower oxidation state.


Infrared spectra of these compounds show a significant change in the spectrum of the pure ligand on complex formation. The broad band in the region 3360-3460 cm<sup>-1</sup>, assigned to hydrogen bonded phenolic hydroxyl group in  $\beta$ -naphthol<sup>7</sup>, is altogether missing in all the compounds. This indicates that there is no phenolic hydroxyl group present in these compounds, which is also supported by the observation that hydrogen chloride gas was liberated during the course of their preparation. A perusal of the spectra of these compounds suggests that the changes in various bands are similar to the ones observed for various aromatic tertiary bases upon complex formation with metal<sup>7</sup> and non-metal halides<sup>8</sup>. The sharp bands at 3052 and 3074 cm<sup>-1</sup> assigned to  $\nu$ (C-H) in  $\beta$ -naphthol are observed at the same positions in the compounds. Furthermore, the most important and strong band at 1260 cm<sup>-1</sup> in pure  $\beta$ -naphthol<sup>8</sup> due to  $\nu$ (C-O) stretching mode, shifts to lower spectral regions by about 40-50 cm<sup>-1</sup> in the spectra of these compounds. This shift may be attributed to the drainage of electrons from the ring to the metal through C-O bond. The important bands are given in Table 2.

TABLE 2—PRINCIPAL INFRA RED BANDS (cm<sup>-1</sup>) OF THE NIOBIUM(V) AND TANTALUM(V) COMPLEXES

Compound	$\nu$ (O-H)	$\nu$ (O-C)	$\nu$ (M-O)	$\nu$ (M-Cl)
NpOH	3400	1260	—	—
Nb(ONp) <sub>3</sub>	—	1190	540, 580	—
NbCl(ONp) <sub>3</sub>	—	1290	546, 578	849
NbCl <sub>2</sub> (ONp) <sub>2</sub>	—	1210	548, 570	852
NbCl <sub>3</sub> (ONp)	—	1198	542, 568	848
NbCl <sub>4</sub> (ONp)	—	1204	540	840
Ta(ONp) <sub>3</sub>	—	1210	502, 545	—
TaCl(ONp) <sub>3</sub>	—	1215	518, 548	838
TaCl <sub>2</sub> (ONp) <sub>2</sub>	—	1198	510, 550	842
TaCl <sub>3</sub> (ONp)	—	1220	498, 552	838
TaCl <sub>4</sub> (ONp)	—	1202	506	836


Metal coordination to the ligand has been further confirmed by the appearance of new bands (not present in the pure ligand) in the lower wave number region. Intense bands around 570-580 cm<sup>-1</sup> in case of niobium and around 540-550 cm<sup>-1</sup> in case of tantalum compounds may be assigned to ir active terminal  $\nu$ (M-O) stretching modes. Such type of bands, assigned to terminal M-O bonds in the alkoxides of these metals, have also been reported earlier in the same region<sup>10,11</sup>. It is interesting to note that in these compounds no band around 900-930 cm<sup>-1</sup>, which could be assigned to Nb=O or Ta=O stretching modes<sup>12</sup>, has been observed suggesting that no oxygen abstraction occurs in these compounds.

In the case of the compound of composition NbCl<sub>4</sub>(ONp), an intense and sharp band at 540 cm<sup>-1</sup> has also been observed. Since this band is well below the range 570-580 cm<sup>-1</sup> observed for terminal  $\nu$ (Nb-O) stretching mode<sup>11</sup>, it may be

attributed to bridging Nb  Nb mode. This assignment is quite in agreement with earlier observations<sup>11,13</sup>. Furthermore, a sharp intense band at 340 cm<sup>-1</sup> assigned to  $\nu$ (Nb-Cl) stretching vibrations is observed which is in agreement with the assignments of Djordjevic<sup>14</sup> and with the reported  $\nu$ (Nb-Cl) vibrations for octahedral complexes<sup>15</sup>. No band that could be assigned to bridging chlorine, which is expected to fall below 330 cm<sup>-1</sup><sup>13</sup>, has been observed. Based upon ir spectral data and insolubility in various solvents, a possible dimeric structure via bridging through naphthoxy groups may be proposed. Similar observations have been made in case of tantalum compounds. These propositions also find support from previous work on the alkoxides and phenoxides of niobium and tantalum<sup>16-18</sup>.

Thermal mode of decomposition and relative strength of bonds in these naphthoxides have been inferred from the weight changes noted from thermograms. In the case of the compound NbCl<sub>4</sub>(ONp), a molecule of chloronaphthalene is lost at ~158° leaving behind niobium oxytrichloride, which decomposes further via dioxymonochloride (NbO<sub>2</sub>Cl) formation at ~260° followed by

subsequent disproportionation to the pentoxide and pentachloride<sup>10</sup> at about 600°. However, in case of fully substituted naphthoxide, i.e. Nb(ONp)<sub>5</sub>, the major intermediate products are dinaphthyl ether and niobiumoxytrinaphthoxides as shown below :



The final product in all the naphthoxides has been found to be M<sub>2</sub>O<sub>5</sub>. Formation of these intermediates is supported by the earlier reports on the mode of decompositions of alkali metal<sup>20</sup> and transition metal phenoxides<sup>21</sup>. It can thus be concluded that these naphthoxides have sufficient thermal stability because of their polymeric structure.

#### Acknowledgement

Thanks of the authors are due to Professor O. P. Vig, Panjab University, Chandigarh, and Professor O. P. Malhotra, B. H. U., Varanasi for facilities for infrared, TGA and magnetic measurements.

#### References

1. K. TANIUCHI and T. ARAKAWA, Japan Kokai, 1971, 73, 10,046.
2. S. PRASAD and K. N. UPADHYAYA, *J. Indian Chem. Soc.*, 1969, 36, 772.
3. H. J. EMELEUS and G. S. RAO, *J. Chem. Soc.*, 1958, 4245.
4. S. M. ORLBERG and P. A. VANDER MEULEN, *J. Amer. Chem. Soc.*, 1958, 75, 997.
5. O. KOMENY, *Chem. Commun.*, 1962, 27, 2596.
6. N. YA. TUROVA, A. V. NOVOSELOVA, K. N. SEMENENKO and R. I. SAVOSTYANOVA, *Zhur. Neorg. Khim.*, 1959, 4, 549, *Chem. Abs.*, 1959, 53, 21317.
7. N. N. GREENWOOD and K. WADE, *J. Chem. Soc.*, 1960, 1180.
8. T. TANAKA, V. MATSUMURA, R. OKAWARA, Y. MUYA and S. KINUMARKI, *Bull. Chem. Soc., Japan*, 1968, 41, 1497.
9. A. H. SYZMANSKI, "Interpreted Infra Red Spectra", Plenum Press, Data Division, 1964, Vol. 8, p. 43.
10. C. G. BARRACLOUGH, D. C. BRADLEY, J. LEWIS and I. M. THOMAS, *J. Chem. Soc.*, 1961, 2801.
11. D. C. BRADLEY and A. M. WESTLAKE, "Proceedings of the Thany Symposium", Hungarian Academy of Sciences, Budapest, 1965, 309.
12. C. G. BARRACLOUGH, J. LEWIS and R. S. NYHOLM, *J. Chem. Soc.*, 1959, 3552.
13. R. J. H. CLARK, *Spectrochim. Acta*, 1965, 21, 955.
14. G. DJORDJEVIC, *Spectrochim. Acta*, 1965, 21, 301.
15. D. M. ADAM, J. OHATT, J. M. DAVIDSON and J. GERRATT, *J. Chem. Soc.*, 1963, 2189.
16. D. C. BRADLEY, "Advances in Inorganic and Radiation Chemistry", 1972, Vol. 15, p. 259.
17. L. KOLDITZ and M. SCHONBERG, *Z. Chem.*, 1965, 5, 849.
18. K. C. MALHOTRA, U. K. BANERJEE and S. C. CHAUDHRY, *J. Indian Chem. Soc.*, 1980, 57, 868.
19. F. FAIRBROTHER, "The Chemistry of Niobium and Tantalum", Elsevier Pub. Company, Amsterdam, 1967, p. 102.
20. F. FISCHER and U. EHRHARDT, *Ges. Abhandl. Konnigs Kohle*, 1919, 4, 287, *Chem. Abs.*, 1921, 15, 8635.
21. U. K. BANERJEE, Ph.D. Thesis, H. P. University, Simla, 1980.

# Complexing Behaviour of N-Cyclo Hexyl Benzothiazole Sulphonamide with Cu(II), Mn(II), Ni(II), Co(II) and Fe(III)

S. K. SRIVASTAVA\*, (KM.) ANITA VERMAN and (KM.) ACHLA GUPTA

Department of Chemistry, D. N. College, Meerut-250 002

Manuscript received 18 June 1981, revised 17 December 1981, accepted 23 May 1982

Metal complexes of the type  $ML_2X_2$  and  $M/L_2X_2$ , [M = Cu(II), Mn(II), Ni(II) or Co(II); M' = Fe(III); X = Cl<sup>-</sup>, CH<sub>3</sub>COO<sup>-</sup>, NO<sub>3</sub><sup>-</sup> or C<sub>6</sub>H<sub>5</sub>(NO<sub>2</sub>)<sub>2</sub>O<sup>-</sup> and L = N-cyclo hexyl benzothiazole sulphonamide] have been synthesized and characterized on the basis of elemental analysis, magnetic susceptibility measurements and spectral studies. The ligand behave as a bidentate chelating agent in all the complexes. All the complexes exhibit octahedral stereochemistry. They were screened for fungicidal activity against *Drechlera tetramera*, *Alternaria alternata* and *Fusarium oxysporum*.

THERE has been considerable interest in recent years in the study of complexes with benzothiazole, imidazole and thiazole ligands<sup>1-4</sup>. A perusal of literature shows that no work on transition metal complexes of N-cyclo hexyl benzothiazole sulphonamide has been carried out. We report here the preparation and characterisation of Cu(II), Mn(II), Ni(II), Co(II) and Fe(III) complexes with N-cyclo hexyl benzothiazole sulphonamide. The newly synthesized complexes were also screened against different fungi.

**Material and methods:** All the chemicals used were either C. P. or A. R. grade. The ligand was used after recrystallisation.

**Preparation of metal complexes:** An alcoholic solution of the appropriate metal salt (1 mole) was refluxed with an alcoholic solution of the ligand (2 mole) for 0.5 hr. The reaction mixture was concentrated to half its volume. Solid complex separated out on cooling which was filtered, washed successively with ethanol and ether and dried *in vacuo*.

The analysis of metal, sulphur and nitrogen were carried out by standard methods. IR spectra of the ligand and complexes were recorded on a Beckmann spectrophotometer model IR-20 in the range 4000-200 cm<sup>-1</sup>. Magnetic susceptibility measurements of complexes were done by Gouy's method at room temp. using mercury tetrathiocyanato cobaltate as calibrant. The results are given in Table I.

All the complexes and ligands were screened for their fungicidal activity using three different fungi by growth method.

## Results and Discussion

On comparing the infrared spectra of the ligand with those of the complexes, it was found that the positions of most of the bands had shifted. The

TABLE I—ELEMENTAL ANALYSIS AND MAGNETIC SUSCEPTIBILITY DATA

Complex	%N Found (Calcd.)	%S Found (Calcd.)	%M Found (Calcd.)	Magnetic susceptibility B. M.
L	9.50 (9.45)	21.50 (21.52)	—	—
(CuL <sub>2</sub> )(NO <sub>3</sub> ) <sub>2</sub>	10.88 (10.90)	16.58 (16.54)	8.20 (8.15)	1.85
(MnL <sub>2</sub> )(NO <sub>3</sub> ) <sub>2</sub>	10.91 (10.89)	16.55 (16.60)	7.08 (7.18)	6.00
(NiL <sub>2</sub> )(NO <sub>3</sub> ) <sub>2</sub>	10.86 (10.84)	16.60 (16.54)	7.52 (7.57)	3.16
(CoL <sub>2</sub> )(NO <sub>3</sub> ) <sub>2</sub>	10.88 (10.88)	16.55 (16.51)	7.68 (7.61)	4.95
(FeL <sub>2</sub> )(NO <sub>3</sub> ) <sub>2</sub>	11.17 (11.24)	16.92 (16.99)	5.00 (4.98)	5.89
(CuL <sub>2</sub> )(OAc) <sub>2</sub>	7.29 (7.28)	16.60 (16.54)	8.15 (8.21)	1.87
(MnL <sub>2</sub> )(OAc) <sub>2</sub>	7.42 (7.59)	16.75 (16.70)	7.12 (7.18)	5.87
(NiL <sub>2</sub> )(OAc) <sub>2</sub>	7.92 (7.28)	16.70 (16.65)	7.61 (7.68)	3.19
(CoL <sub>2</sub> )(OAc) <sub>2</sub>	7.91 (7.28)	16.66 (16.64)	7.65 (7.67)	4.92
(FeL <sub>2</sub> )(OAc) <sub>2</sub>	7.42 (7.40)	17.08 (17.13)	5.02 (4.97)	5.94
(CuL <sub>2</sub> )(Cl) <sub>2</sub>	7.72 (7.70)	17.66 (17.61)	8.80 (8.74)	1.86
(MnL <sub>2</sub> )(Cl) <sub>2</sub>	7.82 (7.79)	17.85 (17.82)	7.62 (7.66)	5.90
(NiL <sub>2</sub> )(Cl) <sub>2</sub>	7.77 (7.76)	17.80 (17.78)	8.11 (8.18)	3.18
(CoL <sub>2</sub> )(Cl) <sub>2</sub>	7.79 (7.76)	17.68 (17.72)	8.19 (8.17)	5.08
(FeL <sub>2</sub> )(Cl) <sub>2</sub>	7.92 (7.99)	18.32 (18.28)	5.86 (5.81)	5.99
(CuL <sub>2</sub> )[C <sub>6</sub> H <sub>5</sub> (NO <sub>2</sub> ) <sub>2</sub> O] <sub>2</sub>	12.81 (12.59)	11.48 (11.51)	5.80 (5.71)	1.88
(MnL <sub>2</sub> )[C <sub>6</sub> H <sub>5</sub> (NO <sub>2</sub> ) <sub>2</sub> O] <sub>2</sub>	12.55 (12.59)	11.65 (11.60)	4.90 (4.98)	5.88
(NiL <sub>2</sub> )[C <sub>6</sub> H <sub>5</sub> (NO <sub>2</sub> ) <sub>2</sub> O] <sub>2</sub>	12.58 (12.55)	11.60 (11.56)	5.25 (5.20)	3.20
(CoL <sub>2</sub> )[C <sub>6</sub> H <sub>5</sub> (NO <sub>2</sub> ) <sub>2</sub> O] <sub>2</sub>	12.60 (12.64)	11.54 (11.56)	5.35 (5.32)	4.98
(FeL <sub>2</sub> )[C <sub>6</sub> H <sub>5</sub> (NO <sub>2</sub> ) <sub>2</sub> O] <sub>2</sub>	12.98 (12.90)	11.80 (11.78)	3.40 (3.42)	5.90

L = C<sub>12</sub>H<sub>16</sub>N<sub>2</sub>S<sub>2</sub>O<sub>2</sub>

\* Author for correspondence.

bands for sulphonamide group observed at 1305 and 1180  $\text{cm}^{-1}$  in the ligand were shifted to 1325-1315 and 1170-1150  $\text{cm}^{-1}$ , respectively.  $\nu_{\text{C-S}}$  observed at 640  $\text{cm}^{-1}$  in the ligand was shifted to a position below 600  $\text{cm}^{-1}$  in the spectra of the complexes. In all the complexes a new band appeared around 500  $\text{cm}^{-1}$  which is assigned to M-N band. These evidences clearly show that complexation is taking place through the S of thiazole ring and N of sulphonamide group.

The asymmetric and symmetric C=O stretching frequencies of acetate ion expected at 1578 and 1425  $\text{cm}^{-1}$ , respectively are observed around 1550-1530 and 1450-1435  $\text{cm}^{-1}$ , respectively in acetato complexes. The changes in these modes on complexation suggest that acetate group behaves as a unidentate ligand in all the acetato complexes<sup>4</sup>.

The magnetic moment values of the Cu(II) complexes are in the range of 1.84-1.88 B. M. The  $\mu_{\text{eff}}$  values of the complexes suggest an octahedral or distorted octahedral stereochemistry<sup>6</sup>. All the copper complexes show an electronic spectral band in the region 13000-16000  $\text{cm}^{-1}$  which may be assigned to the transition  ${}^3E_g \rightarrow {}^3T_{2g}$  characteristic of distorted octahedral Cu(II) complexes<sup>7</sup>.

The magnetic moment values of Co(II) complexes lie in the range 4.90-5.1 B. M. which is characteristic of high spin octahedral complexes. The electronic spectra of Co(II) complexes show two absorption bands at 8870 and 20000  $\text{cm}^{-1}$ . The first band may be identified with the transition  ${}^4T_{1g}(F) \rightarrow {}^4T_{2g}$  and the second band may be due to the transition  ${}^4T_{1g}(F) \rightarrow {}^4T_{1g}(P)$ . The absorption bands in the electronic spectra of Co(II) complexes are approximately similar to those reported for octahedral complexes<sup>8-11</sup>.


The magnetic moment values of Ni(II) complexes are in the region 3.16-3.20 B. M. which show the presence of two unpaired electron. The values are typical of octahedral Ni(II) complexes. The electronic spectra of Ni(II) complexes show bands around 9300  $\text{cm}^{-1}$ , 15750  $\text{cm}^{-1}$  and 25974  $\text{cm}^{-1}$ , characteristic of octahedral Ni(II) ion. These bands may be assigned to  ${}^3A_{2g} \rightarrow {}^3T_{2g}(\nu_1)$ ,  ${}^3A_{2g} \rightarrow {}^3T_{1g}(F)(\nu_2)$  and  ${}^3A_{2g} \rightarrow {}^3T_{1g}(P)(\nu_3)$ , respectively.

The observed magnetic moment values of Fe(III) complexes are in the region 5.88-6.00 B. M. and support the octahedral stereochemistry of Fe(III)

complexes. The electronic spectra of Fe(III) complexes show a weak band around 9200  $\text{cm}^{-1}$  assignable to  ${}^6T_{2g} \rightarrow {}^6E_g$  which is characteristic of high spin octahedral Fe(III).

Magnetic susceptibility measurements of the Mn(II) complexes at room temp. suggest that Mn(II) complexes are high spin and display magnetic moment values in the range 5.85-6.00 B. M. expected for five unpaired electrons in a weak octahedral field. The electronic spectra of Mn(II) complexes show four bands at 19800, 23000, 29000 and 34000  $\text{cm}^{-1}$ . These bands may be assigned to the transition  ${}^6A_{1g} \rightarrow {}^6T_{1g}(G)$ ,  ${}^6A_{1g} \rightarrow {}^6T_{2g}(G)$ ,  ${}^6A_{1g} \rightarrow {}^6T_{2g}(D)$  and  ${}^6A_{1g} \rightarrow {}^6T_{1g}(P)$ . The magnetic moment value and electronic spectra support the octahedral configuration.

**Fungicidal screening:** All the complexes exhibited significant fungitoxicity at 500, 200 and 100 ppm, the inhibition ranging from 60 to 88%, 31 to 60% and 24 to 35%, respectively. The toxicity of metal chelates in the descending order is as follows



#### Acknowledgement

The authors thank Dr. S. P. Gupta Principal D. N. College, Meerut for necessary facilities. They are also grateful to C. S. I. R., New Delhi for the award of Junior Research Fellowship to one of them (A. G.).

#### References

1. W. J. EILBECK, F. HOLMES and A. E. UNDERHILL, *J. Chem. Soc. A*, 1967, 757.
2. E. J. DUFF, M. N. HUGHES and K. J. BUTT, *J. Chem. Soc. A*, 1968, 2845.
3. M. N. C. CHAN, N. A. GOODGAME and M. J. WENZEL, *J. Chem. Soc. A*, 1968, 2409.
4. R. A. FORD, G. HALEYARD and A. E. UNDERHILL, *Inorg. Nuclear Chem. Lett.*, 1968, 4, 507.
5. K. NAKAMOTO, J. FUJITA, S. TANAKA and M. KOBAYASHI, *J. Amer. Chem. Soc.*, 1957, 79, 4904.
6. R. S. NYHOLM and J. LEWIS, "Progress of Inorganic Chemistry", (Ed) F. A. COTTON, Vol. 6, p. 41.
7. A. B. P. LEVER, "Inorganic Electronic Spectroscopy" Elsevier, Amsterdam, 1968.
8. W. J. EILBECK, F. HOLMES and A. E. UNDERHILL, *J. Chem. Soc. A*, 1968, 1189.
9. W. J. EILBECK, F. HOLMES, C. E. TAYLOR and A. E. UNDERHILL, *J. Chem. Soc. A*, 1968, 1189.
10. R. L. CARLIN, *Trans. Metal Chem.*, 1968, 1, 8.
11. G. DEVOTO, G. PONTICELLI and C. PRETI, *J. Inorg. Nuclear Chem.*, 1975, 37, 1693.

# Synthesis and Characterization of Complexes of Co(II), Cu(II), Cd(II), Mg(II) with Disubstituted Thioureas

B. G. SAHA, R. P. BHATNAGAR and SAMIR K. BANERJI

Chemistry Group, Birla Institute of Technology and Science, Pilani-333 081

Manuscript received 16 December 1980, revised 29 September 1981, accepted 23 May 1982

N-2-(6-methyl substituted pyridyl)-N'-substituted thioureas, N-2 (5-chloro substituted pyridyl)-N'-substituted thiourea and N-4-naphthyl-N'-substituted thiourea and their Co(II), Cu(II), Cd(II) and Hg(II) complexes were synthesized and characterized by elemental analysis. (The metals were estimated by atomic absorption spectrophotometer). Molar conductance, IR, UV and magnetic measurements were made.

**TRANSITION** metal complexes of substituted thioureas have been studied by several workers<sup>1-5</sup> but no work has been reported on Co(II), Cu(II), Cd(II), Hg(II) chloride complexes of N-2-(6-methyl substituted pyridyl)-N'-substituted thioureas, N-2-(5-chloro substituted pyridyl)-N'-substituted thiourea and N-4-naphthyl-N'-substituted thiourea. The present communication reports an attempt to study the Co(II), Cu(II), Cd(II) and Hg(II) complexes of these disubstituted thioureas.

## Experimental

**Chemicals** All chemicals used were of B. D. H. 'AnalaR', E Merck 'GR' quality. 6-Methyl-2-amino-pyridine and 4-naphthyl amine used were obtained from Sigma R Chemicals and Riedel-Haen, respectively.

**Apparatus:** Atomic absorption studies were performed on Perkin-Elmer-306, atomic absorption spectrophotometer. Melting points were recorded in capillary melting point apparatus (Arthur H. Thomas Co.). Conductance measurements were taken on a conductivity meter (Toshniwal, India) with dipping electrode cell. IR spectra were recorded on model 577 Perkin-Elmer IR spectrophotometer in nujol mull and UV spectra on Hitachi spectrophotometer, model 139. Magnetic measurements were performed on Gouy's balance.

**Synthesis of mustard oil (isothiocyanate):** Synthesis of phenyl isothiocyanate was done by the method described by Vogel<sup>7</sup>. Allyl isothiocyanate and methyl isothiocyanate were synthesized by similar method except that the amines used were allyl amine and methyl amine respectively in place of aniline.


**Synthesis of 5-chloro-2-amino-pyridine:** The compound was prepared by the method described by Shozo Shibata *et al*<sup>8</sup>.

**Synthesis of N-2-(6-methyl substituted pyridyl)-N'-substituted thioureas, N-2-(5-chloro substituted pyridyl)-N'-substituted thiourea and N-4-naphthyl-N'-substituted thiourea:** Equimolar amounts of amino compounds and mustard oil (isothiocyanate) were



taken in ethanol. The mixture was refluxed for about 1-2 hr. The solution was then kept in ice-cold water for some time when substituted thiourea precipitated out as fine crystals. The precipitate was filtered and washed with ethanol and finally recrystallised from ethanol and dried in a vacuum desiccator.

In the case of 2-amino-5-chloro-pyridine, the substituted thiourea was subjected to charcoal treatment in benzene to remove the colouring material and finally recrystallised from C<sub>6</sub>H<sub>6</sub> and dried in a vacuum desiccator.

The formation of the substituted thioureas can be represented by the following equations



and



**Preparation of complexes.** 0.01 Mole of CoCl<sub>2</sub>, 6H<sub>2</sub>O, CuCl<sub>2</sub>, 2H<sub>2</sub>O, HgCl<sub>2</sub> (all B. D. H. "AnalaR") or CdCl<sub>2</sub> (E Merck 'GR') in *n*-butanol or ethyl alcohol was added slowly to a hot solution of 0.025 mole of the ligand in the same solvent. In the case of Co(II), the reaction mixture was refluxed for 30 to 60 min. Later, 50 to 60% solvent was evaporated. The crystallization was achieved by keeping this concentrated solution in ice-cold water for some time. Blue or bluish green crystals separated out.

Copper(II) complexes immediately precipitated out as white crystals from ethanol solution which suggests that copper(II) gets reduced to copper(I) state. In the case of mercury(II), no precipitation was obtained till the concentration ratio of metal/

ligand was raised to 1 : 1. This metal/ligand ratio resulted only in milky coloured reaction mixture which gave white crystals when kept for some time. Excess of metal chloride immediately gave white precipitate.

Cadmium(II) complexes required more vigorous condition such as metal/ligand ratio of 1 : 1 with continuous stirring in hot condition for 30-60 min followed by a precipitation time of 10-12 hr at low temperature. The complexes thus obtained were white in colour.

These complexes could not be recrystallised either from *n*-butanol or ethanol. Therefore, to ensure purity, they were washed several times with the solvent followed by 2 or 3 washings with ether (10 ml each time) and dried in vacuum.

### Results and Discussion

The elemental analysis of these complexes indicates that they are formed in 1 : 2 (M : L) ratio (where L = substituted thiourea) except when N-allyl-N'- $\alpha$ -naphthyl thiourea is used as ligand, in which case they are in 1 : 1 (M : L) ratio. The melting points range from 152°-260° with decomposition.

The molar conductance of these complexes in DMF were found to be quite low. 1 : 1 Electrolytes generally have conductance in the range 70-110 mhos<sup>2</sup>, showing the non-electrolytic nature of the complexes. Thus, the chlorine atoms can be considered to be coordinated to the metal ion and are not present as chloride ions. The values obtained in the present work are indicative of an octahedral geometry for these Co(II) complexes. Complexes of the other metals are diamagnetic in nature.

The uv spectra (CHCl<sub>3</sub>) of these complexes exhibited two intense absorption maxima in the region of 260-280 nm and 300-310 nm, (except in the case of N-allyl-N'- $\alpha$ -naphthyl thiourea which showed only one thiocarbonyl  $\pi$ - $\pi^*$  transition). These transition bands have been assigned to thiocarbonyl  $\pi$ - $\pi^*$  and pyridyl  $\pi$ - $\pi^*$  transitions<sup>6,10</sup>.

All the uv spectra of the complexes were compared with uv spectra of ligands. The absorption maxima showed an erratic shift to lower or higher wave length of about 10 nm or in some cases no shift in any appreciable amount in wave length. The intensity of the absorption of complexes was higher than that of ligands. Out of the two absorption maxima, the  $\pi$ - $\pi^*$  transition of thiocarbonyl (C=S) showed strongest interaction in metal complexes when compared with ligands.

The ir spectra of the ligands are complex and only the peaks which can be assigned with reasonable certainty are presented. From the point of view of ascertaining the donor sites of the ligands the following peaks are important:  $\nu(\text{C}=\text{C}+\text{C}=\text{N})$  (1630-1590 cm<sup>-1</sup>)<sup>1-4</sup>;  $\nu(\text{NCN})+\nu(\text{NCN}+\text{C}=\text{S})$

(1060-1010 cm<sup>-1</sup>)<sup>1-4,11</sup> and  $\nu(\text{C}=\text{S})$  (741-722 cm<sup>-1</sup>)<sup>1-4,12</sup>. The  $\nu(\text{C}=\text{C}+\text{C}=\text{N})$  band at 1630-1590 cm<sup>-1</sup> has been reported to be shifted in the case of coordinated pyridyl nitrogen<sup>12</sup>. The behaviour of this band is of considerable importance in deciding whether the heterocyclic nitrogen is involved in the coordination with metal. In the case of the present complexes, this band shifted to higher or lower frequencies in an irregular fashion thereby precluding any unambiguous assertion of metal ligand bonding through the pyridyl nitrogen (except for N-allyl-N'- $\alpha$ -naphthyl thiourea).


The band appearing at 1060-1010 cm<sup>-1</sup> in the ligand and assigned to  $\nu(\text{C}=\text{C}+\text{C}=\text{S})$  mode, was reduced in its intensity or shifted to lower frequencies in most of the spectra of the complexes.

The mode  $\nu(\text{C}=\text{S})$ , occurring at 741-722 cm<sup>-1</sup>, was shifted to slight higher frequencies in metal complexes in the case of 6-methyl-pyridyl substituted thiourea ligands, while in the other complexes it was found to be reduced in intensity or shifted to lower frequencies. The shift to slight higher frequencies may be accounted for substitution effect in 6-position of pyridyl ring.

The shifting of the bands assigned to  $\nu(\text{NCN}+\text{C}=\text{S})$  and  $\nu(\text{C}=\text{S})$  mode to lower frequency (in some cases change to higher frequencies) or reduction of their intensities in metal complexes may be due to the sulphur metal coordination bond formation<sup>1-4</sup>.

One more possible site for the coordination between metal and ligand may be one of the nitrogens of substituted thiourea unit. If this nitrogen and sulphur act as donors, a four membered chelate ring would be formed which is quite unstable in comparison to the 6-membered chelate ring formed by the donation of electrons from the nitrogen of pyridine ring and the thiocarbonyl sulphur.

From these studies of eighteen complexes of Co(II), Cu(II), Cd(II) and Hg(II), it can be reasonably concluded that complexes formed are non-electrolytes with 1 : 2 metal to ligand ratio except in the case of N-allyl-N'- $\alpha$ -naphthyl thiourea where the ratio is 1 : 1. The chlorine in the complexes appears to be present in the inner sphere of the complexes. On the basis of these measurements, the following structures of the complex can be assigned.





### Acknowledgement

The authors are thankful to the Birla Institute of Technology & Science authorities for laboratory facilities and to the University Grants Commission, New Delhi for financial assistance. One of them (B. G. S.) is thankful to the U. G. C., New Delhi for a Junior Research Fellowship.

### References

1. B. C. KASAP, A. D. TANEJA and SAMIR K. BANERJI, *J. Inorg. Nuclear Chem.*, 1975, 37, 1542.
2. B. C. KASAP, A. D. TANEJA and SAMIR K. BANERJI, *J. Inorg. Nuclear Chem.*, 1975, 37, 612.
3. B. C. KASAP, SAMIR K. BANERJI and A. D. TANEJA, *Curr. Sci.*, 1976, 45, 81.
4. G. S. G. PRASAD and SAMIR K. BANERJI, *J. Inorg. Nuclear Chem.*, 1976, 38, 1857.
5. P. K. MANDAL, *Indian J. Chem.*, 1974, 12, 845.
6. SHOZO SHIBATA, FURA KAWA, MASEMICH, KAWATA EIJIRO and GUTOM KAZUO, *Anal. Chim. Acta*, 1970, 50, 489.
7. A. I. VOGEL, "A Text Book of Practical Organic Chemistry" Longman, London, 1962.
8. A. SVAMAL, *J. Indian Chem. Soc.*, 1968, 45, 904.
9. A. DUTTA AHMED and P. K. MANDAL, *J. Inorg. Nuclear Chem.*, 1967, 29, 2347.
10. R. M. SILVERSTEIN, C. G. BASSLER and T. C. MORRIL, "Spectrophotometry of Organic Compounds", 3rd Ed., John Wiley and Sons, Inc., New York.
11. A. YAMAGUCHI, R. B. PENLAND, S. MIZUSHIMA, T. L. LOWR, C. CURRAN and J. V. QUAGLINO, *J. Amer. Chem. Soc.*, 1968, 80, 527.
12. K. SWAMINATHAN and H. M. N. H. IRVING, *J. Inorg. Nuclear Chem.*, 1964, 26, 1261.
13. D. BANERJEE and I. P. SINGH, *Indian J. Chem.*, 1968, 6, 84.

# Studies on Triortho-periodato Tetracobaltic(III) Acid. Part—II

L. C. W. BAKER

Georgetown University, Washington DC. U.S.A.

and

H. G. MUKHERJEE\* and B. K. CHAUDHURI

Pure Chemistry Department, Calcutta University, Calcutta-700 009

Manuscript received 29 September 1981, revised 24 February 1982, accepted 1 May 1982

The compound  $H_2[Co_4I_2O_{24}H_{12}].6H_2O$  has been prepared following two known methods—one is an alkaline method and the other is an acid method. TGA, ir and electronic spectra and powder X-ray studies have been made to throw light on its structure.

In one of our previous communications<sup>1</sup>, we discussed some of the properties of the interesting compound, triortho-periodatotetracobaltic(III) acid. We have now carried out thermal, spectral and powder X-ray studies of this compound. The compound has further been prepared following two known methods, the alkaline<sup>2</sup> and the acid methods<sup>3</sup>. The composition of the compound has been formulated as  $H_2[Co_4I_2O_{24}H_{12}].6H_2O$ . Analyses have confirmed that the composition is independent of the method of preparation. Powder X-ray study has confirmed the similarity of the crystalline nature of the compound prepared by either of the methods.

## Experimental

In the alkaline method<sup>2</sup>, the compound  $Na_2H_2Co(IO_6)_2.xH_2O$  was prepared and its saturated aqueous solution was made approximately 2M with  $HClO_4$ . This was allowed to stand for several days when a dark green crystalline solid precipitated. The crystals were dissolved in minimum amount of water and reprecipitated by making the solution 2M in  $HClO_4$ . After 2 such precipitations, the crystals were collected and analysed.

In the acid method<sup>3</sup>, the compound,  $Na_2[Co(III)-(CO_3)_2].3H_2O$ , was prepared and dissolved in appropriate amount of  $HClO_4$ . A known amount of sodium metaperiodate was added to this solution. The green crystalline product obtained was collected from 2M  $HClO_4$  as above. After 2 such precipitations the crystals were collected and analysed.

**Thermal analysis:** The thermograph was recorded with a Paulik-Paulik Erdey type MOM model OD-102. The derivatograph was obtained at a rate of 3°/min from room temp. to 750° using platinum crucible and samples of 150 mesh. Both

DTA and DTG were recorded with the same instrument. The peaks obtained were endothermic in nature (Fig. 1). Results are shown in Table 1.

It appears from Fig. 1 that the first step of decomposition is the elimination of water molecules. The elimination takes place via thermally unstable intermediate ( $\Delta H = 3.91$  K cal/mole). A slow phase transition has been observed in the range 270-310°. The final decomposition product is  $Co_2O_4$ .

**Spectral study:** Electronic spectra, both in visible and ultra violet regions, were recorded in a Hilger spectrophotometer. The results are tabulated in Table 1. The acid shows 4 bands of which 3 are in the visible to near uv region. The weak band at  $22.7 \times 10^3$   $cm^{-1}$ , which appears as a shoulder on the strong charge transfer band, is assigned to the "polynuclear band" due to a charge transfer

transition<sup>4</sup> in the group  $Co \begin{array}{c} O \\ \diagup \quad \diagdown \\ O \end{array} Co$ . The first

band, which appears at  $16.5 \times 10^3$   $cm^{-1}$ , agrees well with the behaviour of several  $Co(O)_6$  type complexes<sup>5</sup> showing octahedral coordination round cobalt atoms. The band with high extinction coefficient in the near ultra violet region may also originate from charge transfer region. The maxima with high extinction coefficient in the ultra violet region is a charge transfer band characteristic of  $IO_6^{5-}$  species. From his studies on lithium orthoperiodate, Hauck<sup>6</sup> concluded that orthoperiodates give two bands, one in the uv and the other in the near uv region. This is also in agreement with our observation.

From the energies of the visible absorption bands for the heteropoly acid, one calculates the value of the Racah parameter B to be 387  $cm^{-1}$  (the band separation is 16B). This is very small

\* For correspondence.



 Fig. 1. Thermal decomposition of  $H_2[Co_4I_4O_{14}H_{12}] \cdot 6H_2O$ .

 TABLE I—DATA OF THERMAL DECOMPOSITION AND SPECTRA  
THERMAL DECOMPOSITION OF  $H_2[Co_4I_4O_{14}H_{12}] \cdot 6H_2O$ 


	Total wt. loss		Temp. °C	
	Obsd.	Calcd.	TGA	DTG (Peak temp.)
$H_2[Co_4I_4O_{14}H_{12}] \cdot 6H_2O \rightarrow H_2Co_4I_4O_{14}H_{12} + 6H_2O$	110	108	50-160	140
$H_2Co_4I_4O_{14}H_{12} \rightarrow H_2Co_4I_4O_{14}$	218	216	165-215	180
$H_2Co_4I_4O_{14} \rightarrow Co_4I_4O_{14} + \frac{1}{2}H_2O + \frac{1}{2}[O]$	301.5	299	225-340	
$Co_4I_4O_{14} \rightarrow \frac{1}{2}Co_2O_4 + \frac{1}{2}[O] + \frac{1}{2}I_2$	808	803	350-500	
$Co_2O_4$			500-750	

## Spectral Data

$\nu$ in $cm^{-1}$	$\epsilon$
$16.5 \times 10^3$	(410)
$32.7 \times 10^3$	(426)
$27.4 \times 10^3$	(2454)
$44.4 \times 10^3$	(4507)

compared to the values for typical cobalt(III) complexes,  $510\text{ cm}^{-1}$  for  $[Co(H_2O)_6]^{3+}$ , indicating that the interaction repulsion of the 'd' electrons is much reduced, presumably by covalency<sup>7</sup>.

**Infrared study:** Infrared spectra were recorded in Perkin-Elmer model 621 and in Unicam SP 1000 Infrared spectrophotometer in CsI/Nujol phase and are shown in Fig. 2.


 Fig. 2. Infrared spectra of  $H_2[Co_4I_4O_{14}H_{12}] \cdot 6H_2O$ .

The broad band in the range  $3600-2800\text{ cm}^{-1}$  is due to stretching O-H vibration. The broadening may be due to strong hydrogen bonding of the type O-H.....O bridge. The bridge is comparatively short as relatively broad absorption has shifted

towards lower wave number<sup>8</sup>. Deformation  $H_2O$  vibration has been observed at  $1590-1580\text{ cm}^{-1}$  with the acid. Deformation -OH vibrations bonded to iodine appear as several peaks between  $1300-1000\text{ cm}^{-1}$ , the overtones of which appear as shoulder at  $2260\text{ cm}^{-1}$ . The band at  $935\text{ cm}^{-1}$  may be due to coordinated water molecules. Stretching IO-(H) vibration appears at  $630-670\text{ cm}^{-1}$  and that of IO vibration between  $530$  and  $790\text{ cm}^{-1}$ . Deformation OIO vibrations appear as multiple peaks at  $480-230\text{ cm}^{-1}$ . Co-O vibrations may be present in this region. Large number of bands in this region may be due to distortion of the octahedral  $IO_4$  group<sup>9-12</sup>.

**X-ray powder photography:** X-ray powder photography has been taken with cobalt  $K_\alpha$  radiation in a Rigaku camera at  $20^\circ$ . Number of lines obtained are of little importance for any proper indexing, so that parameters of the unit cell could not be carried out by this method. The results (Table 2) show that the spacings are exactly equal for the complex periodic acid obtained from the two different methods. This indicates the similarity of their crystalline nature. Crystals of the heteropolyacid, obtained by both the methods, appear identical under microscope.

TABLE 2—POWDER X-RAY RESULTS

Compound $H_2[Co_4I_2O_{14}H_{12}].6H_2O$			
Obtained by the acid method		Obtained by the alkaline method	
d in Å	Intensity	d in Å	Intensity
8.6286	m	8.6286	m
7.5222	s,b	7.5222	s,b
6.4751	m,b	6.4751	m,b
5.1920	w	5.1920	w
4.9455	s,b	4.9455	s,b
4.6213	w	4.6213	w
4.4257	w	4.4257	w
4.1654	w	4.1654	w
3.8624	w	3.8624	w
3.4881	w	3.4881	w
3.1699	vw,b	3.1699	vw,b
2.9164	vw,b	2.9164	vw,b
2.7684	vvw	2.7684	vvw
2.7008	vvw	2.7008	vvw
2.5153	s,b	2.5153	s,b
2.1421	s	2.1421	s
2.0656	w	2.0656	w
1.9927	m	1.9927	m
1.8800	w	1.8800	w
1.7367	w	1.7367	w
1.6711	vw	1.6711	vw
1.6004	vvw	1.6004	vvw
1.5657	vvw	1.5657	vvw
1.4544	vvw	1.4544	vvw
1.4268	vvw	1.4268	vvw
1.3756	vvw	1.3756	vvw

vvw = very very weak, vw = very weak, m = medium, s = strong, w = weak, b = broad.

## Results and Discussions

Chemical and thermal analyses show that the complex polynuclear acids prepared by the above two methods are the same and have the general composition  $H_2[Co_4I_2O_{14}H_{12}].6H_2O$ , which has a formula weight of 1124. X-ray powder photography established the similarity of their crystalline nature. The compound is stable in the solid state. The aqueous solution of the compound decomposes on standing. It has been shown by potentiometric titration that the acid is tribasic with virtually identical  $pK$  values ( $pK \sim 1.5$ ) and the acid equivalent is 375.

It has been observed that though the compound  $H_2[Co_4I_2O_{14}H_{12}].6H_2O$  is obtained from  $Na_2H_2Co(IO_6)_2.xH_2O$  by acidification, the reverse reaction i.e. formation of the sodium salt cannot be accomplished by neutralising the above acid with NaOH, probably due to decomposition. It has also been observed that the sodium complex can be obtained by the alkaline method<sup>2</sup>, whereas the condensed form of the complex, i.e. polynuclear acid, is obtained by the acid method<sup>2</sup>.

Nyman and Plane<sup>12</sup> proposed two structures for the condensed compound, one chain and the other hexol like. The two have a notable difference in the number of water molecules, viz. 12 for the former and 6 for the latter. The latter structure is based on the Anderson model<sup>13</sup> where one cobalt atom takes the centre of a hexagon and the three iodine and other three cobalt atoms occupy six

corners, in alternate positions, in six other hexagons. These seven octahedra are condensed by edge sharing into a flat aggregate. The compound may be formulated as  $[Co\{(OH)_2Co(IO_6)_2\}_2]^{2-}$ , should be optically active and be resolved into enantiomorphs. Although cobalt(III) compounds are inert and optical resolution of this acid was unsuccessful, some of its derivatives, e.g. L-alanine $[Co_4I_2O_{14}-(OH)_2(L-ala)]^{4-}$ , have been separated by Ama *et al*<sup>14</sup> into optical isomers and their O.R.D., C.D. recorded. These authors also prepared some other derivatives, e.g.  $[Co_4I_2O_{14}(NH_3)_6]^{2-}$  and  $[Co_4I_2O_{14}(en)_3]^{2-}$ , showing the complex species to contain six water molecules. Formation of 'en' complex further indicated that every two of the six water molecules take a *cis*-position to each other and this, in all probability, around each outer three cobalt atoms. All these facts suggest a hexol like structure. Our studies also reveal that the first structure of Nyman and Plane is not correct. The structure, as proposed, is not symmetric. No reason has been advanced for the different number of water molecules attached to cobalt atoms. It cannot also satisfy other experimental observations.

Electronic absorption spectra speak of the octahedral geometry round iodine and cobalt atoms. Thermal studies reveal that the twelve water molecules are linked differently to the compound in groups of six. Of these, first six molecules are lattice water, and the other six are coordinated water attached to the three outer cobalt atoms in pairs of two, that take *cis*-positions to each other. Spectral data reveal that both cobalt and iodine atoms are in octahedral environments. Racah parameter shows covalency in the solid. There is still no evidence for metal interaction in the heteropoly acid. The dark colour of the complex is due to intense electron transfer absorption in the near uv region and may also originate from distortion in the octahedral symmetry around cobalt and iodine atoms. High intensities of the electronic band may be attributed to some sort of  $\pi$  bonding. The intensities of the bands are high, typical of octahedral cobalt(III) complexes. Conductivity measurement<sup>1</sup> cannot ascertain classification of the acid to  $H_2A$  ( $A = Co_4I_2O_{14}H_{12}$ ) type. But similar measurement on the sodium salt of the heteropoly acid,  $Na_2[Co_4I_2O_{14}H_{12}].11H_2O$ , has confirmed the presence of four ions (molar conductivity 330 mhos  $cm^2$  mole<sup>-1</sup>).

Considering all these facts, our suggestion is that the complex acid molecule possesses identical structure of  $[Cr^{3+}(OH)_2Mo^{6+}O_4]^{3-}$  put forward by Perloff<sup>15</sup> where all cobalt and iodine atoms are octahedrally arranged by edge sharing through oxygen (Fig. 3). The periodate complexes are probably H-bonded together *via* Co-O-I attachments between adjacent complexes, as has been observed in the above Cr complexes where the Cr complexes, although weakly H-bonded together *via* waters of crystallisation, are directly attached to each other only *via* two weak Cr-O-H...OMo H bonds per




Fig. 3. Probable structure of  $H_3[Co_4I_2O_{22}H_{12}].6H_2O$ .

complex since the peripheral Os lack H atoms. This will give slightly elongated exterior Co-O distances. A shorter I-O distance is also presumed. Distortion from the idealised octahedral symmetry may be there due to different I-O and Co-O bond lengths. This arrangement, however, cannot explain the presence of I-OH bond, seem to be present from infrared study. NMR studies show absence of metal hydrogen bond. The compound has been shown to be monomeric from cryoscopic study in fused  $Na_2SO_4.10H_2O^{17}$ .

#### Acknowledgement

The authors acknowledge the help of Dr. D. R. Das Gupta, Mineral Physics Department, Geological Survey of India, Calcutta and Prof. A. K. Saha, Geology Department, Presidency College, Calcutta, for taking X-ray photograph and of Prof. O. P. Vig,

Chemistry Department, Punjab University, Chandigarh for recording far infrared spectra. One of the authors (B. K. C) is the recipient of a grant from U. G. C., New Delhi.

#### References

1. L. C. W. BAKER, H. G. MUKHERJEE and B. K. CHAUDHURI, *J. Indian Chem. Soc.*, 1980, **57**, 16.
2. C. J. NYMAN and R. A. PLANN, *J. Amer. Chem. Soc.*, 1961, **83**, 2617.
3. S. YOUNG TYRES, JR. (Ed.), "Inorganic Synthesis", McGraw Hill Book Company, Inc., New York, 1967, Vol 9, p. 142.
4. Y. SASAKI, J. FUJITA and K. SAITO, *Bull. Chem. Soc., Japan*, 1969, **42**, 146.
5. N. MATSUOKA, *Bull. Chem. Soc., Japan*, 1967, **40**, 1868.
6. J. HAUCK, *Z. Naturforsch.*, 1969, **B24**, 1849.
7. R. L. CARLIN and F. CANZIANI, *J. Chem. Phys.*, 1964, **40**, 371.
8. A. H. J. LOKIO and J. R. KYRKI, *Soumen Kemistilehti*, 1971, **B44**, 340.
9. A. H. J. LOKIO and J. R. KYRKI, *Soumen Kemistilehti*, 1973, **B46**, 206.
10. H. SIEBERT and G. WIEGHARDT, *Spectrochim. Acta*, 1971, **27A**, 1907.
11. F. PETRE, J. HRADILOVA and B. HAJEK, *J. Inorg. Nuclear Chem.*, 1970, **32**, 1485.
12. B. HAJEK and J. HRADILOVA, *Coll. Czech. Chem. Comm.*, 1971, **36**, 8765.
13. C. J. NYMAN and R. A. PLANN, *J. Amer. Chem. Soc.*, 1961, **83**, 2617.
14. J. S. ANDERSON, *Nature*, 1967, **140**, 850.
15. T. AMA, J. HIDAKA and Y. SHIMURA, *Bull. Chem. Soc., Japan*, 1978, **46**, 2145.
16. A. PERLOFF, *Inorg. Chem.*, 1970, **9**, 2228.
17. O. W. ROLLINS and L. C. W. BAKER, *Inorg. Chem.*, 1969, **8**, 397.

# Equilibrium and Formation Constants of Co(II), Ni(II) and Zn(II) Complexes of N-Benzoyl Phenyl Hydroxyl Amine in Various Mixed Aqueous Solvents

A. K. CHAUDHURY\* and N. KOLE

Chemistry Department, University of Burdwan, Burdwan-718 104, West Bengal

Manuscript received 5 June 1981, accepted 28 May 1982

The equilibrium constants  $\beta = [ML][H]/[M][HL]$ , where  $M = \text{Co(II)}$ ,  $\text{Ni(II)}$  or  $\text{Zn(II)}$ ;  $HL = \text{N-benzoyl phenyl hydroxyl amine (NBPHA)}$  and formation constant  $\beta' = [ML]/[M][L]$  have been determined in five different mixed aqueous solvents namely, dioxane-water, isopropanol-water, acetone-water, ethanol-water and methanol-water in 75% v/v compositions. The order of equilibrium constants ( $\log \beta_n$ ) are found to have no relation with 1/e sequence of the media, but is almost the same for different metal ions. The formation constants ( $\log \beta'_n$ ), however, are in a sequence similar to 1/e sequence, with a few exceptions. In all the solvents the order of stability is  $\text{Co(II)} > \text{Ni(II)} < \text{Cu(II)} > \text{Zn(II)}$ . The anomalous position of  $\text{Co(II)}$  is attributed to Jahn Teller type of distortion.

In a previous communication<sup>1</sup> we reported in detail the interaction of  $\text{Cu(II)}$ -NBPHA complex system in various mixed aqueous solvents. The study has been extended to other metallic central ions e.g.  $\text{Co(II)}$ ,  $\text{Ni(II)}$  and  $\text{Zn(II)}$  and the findings are presented here. The physical properties of  $\text{Mn(II)}$ ,  $\text{Co(II)}$ ,  $\text{Ni(II)}$ ,  $\text{Cu(II)}$  or  $\text{Zn(II)}$  complexes of NBPHA were studied and their stability constants determined in 50% v/v dioxane-water by Bag and Lahiri<sup>2</sup>. Shome *et al.*<sup>3</sup> reported the stabilities of  $\text{Al}^{3+}$ ,  $\text{Ga}^{3+}$ ,  $\text{In}^{3+}$ ,  $\text{Sc}^{3+}$ ,  $\text{Y}^{3+}$  and  $\text{La}^{3+}$  complexes of NBPHA in 50% dioxane-water.


In the present work equilibrium constants for the reactions  $\text{M}^{2+} + \text{HL} = \text{ML}^+ + \text{H}^+$  etc., where  $M = \text{Co(II)}$ ,  $\text{Ni(II)}$  or  $\text{Zn(II)}$  and  $\text{HL} = \text{NBPHA}$ , and formation constants for the reaction  $\text{M}^{2+} + \text{L}^- = \text{ML}^+$  etc. have been determined in five different mixed aqueous solvents in 75% v/v composition. This high volume per cent composition was maintained to cope with the solubility difficulties, considering all the solvents. The object of the present study was to investigate the solvent effects on the stability of complexes of a series of metal ions and variation of formation and equilibrium constant of a metal complex with the variation of the nature of the solvent media.

## Experimental

All reagents were of A. R. or G. R. grade. The composition of the experimental solutions were described in an earlier paper<sup>4</sup>. The titrations were carried out in 75% v/v dioxane-water (D-W), isopropanol-water (I-W), acetone-water (A-W), ethanol-water (E-W) and methanol-water (M-W) at  $30 \pm 0.1^\circ$ . The ionic strength was maintained constant at 0.1 M with  $\text{NaClO}_4$ . The pH measurements were made with a bench model Cambridge

pH meter using glass electrodes. True  $[\text{H}^+]$  concentration was measured as before<sup>4</sup>.

The equilibrium constants,  $\beta_1$  and  $\beta_2$ , for the reactions



were calculated as reported earlier<sup>1,4,5</sup>. The formation constants,  $\beta'_1$  and  $\beta'_2$ , were also calculated by the earlier reported method<sup>1,4,5</sup> using the relations

$$\begin{aligned} \log \beta_1 &= \log \beta'_1 - \log {}^pK_1^{\text{H}} \\ \log \beta_2 &= \log \beta'_2 - 2 \log {}^pK_1^{\text{H}} \end{aligned} \quad (2)$$

The computation was done in BURROUGHS 6700 system as described before<sup>4</sup>.

## Results and Discussion

$\log \beta_1$ ,  $\log \beta_2$ ,  $\log \beta'_1$  and  $\log \beta'_2$  and  ${}^pK_1^{\text{H}}$  values for  $\text{Co(II)}$ ,  $\text{Ni(II)}$  and  $\text{Zn(II)}$  are set out in Table 1. Values of  $\text{Cu(II)}$  are taken from the previous paper<sup>1</sup> for comparison.

In 75% v/v solvent compositions the sequence of 1/e values is  $\text{D-W} > \text{I-W} > \text{A-W} > \text{E-W} > \text{M-W}$ . The values of  $\log {}^pK_1^{\text{H}}$  have the sequence  $\text{A-W} > \text{D-W} > \text{I-W} > \text{E-W} > \text{M-W}$ ,  $\log \beta_1$ ,  $\log \beta_2$ ,  $\log \beta'_1$  and  $\log \beta'_2$  have the following sequences for the different metal ions:

Cobalt(II):



TABLE I—EQUILIBRIUM AND FORMATION CONSTANTS OF Co(II), Ni(II), Zn(II) AND Cu(II) COMPLEXES OF NBPFA IN DIFFERENT MIXED AQUEOUS SOLVENTS AT  $30 \pm 0.1^\circ$  AND 0.1M IONIC STRENGTH

Solvent composition	$1/\epsilon$	Mole fraction	$\log {}^pK_1^H$	Metal ions	Equilibrium constants		Formation constants	
					$\log \beta_1$	$\log \beta_2$	$\log \beta'_1$	$\log \beta'_2$
75% D-W	0.0899	0.388	$10.59 \pm 0.01$	Co(II)	$-3.99 \pm 0.003$	$-7.77 \pm 0.001$	$7.80 \pm 0.012$	$18.41 \pm 0.021$
				Ni(II)	$-3.41 \pm 0.004$	$-8.15 \pm 0.004$	$7.18 \pm 0.014$	$18.08 \pm 0.024$
				Zn(II)	$-3.08 \pm 0.003$	$-7.35 \pm 0.003$	$7.56 \pm 0.012$	$18.98 \pm 0.022$
				*Cu(II)	$-0.96 \pm 0.004$	$-1.58 \pm 0.004$	$10.38 \pm 0.014$	$19.60 \pm 0.024$
75% I-W	0.0859	0.415	$9.88 \pm 0.01$	Co(II)	$-3.06 \pm 0.014$	$-6.87 \pm 0.01$	$6.77 \pm 0.024$	$12.99 \pm 0.08$
				Ni(II)	$-3.08 \pm 0.011$	$-6.81 \pm 0.008$	$6.75 \pm 0.021$	$12.85 \pm 0.028$
				Zn(II)	$-2.98 \pm 0.02$	$-6.45 \pm 0.01$	$6.90 \pm 0.03$	$12.21 \pm 0.03$
				*Cu(II)	$-0.08 \pm 0.02$	$-1.44 \pm 0.01$	$9.75 \pm 0.03$	$18.22 \pm 0.03$
75% A-W	0.0289	0.422	$10.67 \pm 0.01$	Co(II)	$-3.51 \pm 0.006$	$-7.94 \pm 0.004$	$7.16 \pm 0.016$	$18.40 \pm 0.024$
				Ni(II)	$-3.58 \pm 0.003$	$-8.36 \pm 0.003$	$7.09 \pm 0.013$	$12.98 \pm 0.028$
				Zn(II)	$-3.46 \pm 0.015$	$-7.43 \pm 0.007$	$7.21 \pm 0.026$	$18.91 \pm 0.027$
				*Cu(II)	$-0.48 \pm 0.03$	$-2.00 \pm 0.02$	$10.24 \pm 0.04$	$19.84 \pm 0.04$
75% E-W	0.0271	0.479	$9.74 \pm 0.01$	Co(II)	$-2.92 \pm 0.01$	$-6.87 \pm 0.005$	$6.82 \pm 0.02$	$12.61 \pm 0.025$
				Ni(II)	$-3.02 \pm 0.007$	$-7.05 \pm 0.004$	$6.73 \pm 0.017$	$12.48 \pm 0.024$
				Zn(II)	$-2.75 \pm 0.007$	$-6.45 \pm 0.006$	$6.99 \pm 0.017$	$18.08 \pm 0.026$
				*Cu(II)	$-0.27 \pm 0.01$	$-1.46 \pm 0.01$	$9.47 \pm 0.02$	$18.02 \pm 0.03$
75% M-W	0.0280	0.573	$9.57 \pm 0.01$	Co(II)	$-3.18 \pm 0.007$	$-7.57 \pm 0.06$	$6.89 \pm 0.017$	$11.57 \pm 0.026$
				Ni(II)	$-3.21 \pm 0.008$	$-7.86 \pm 0.005$	$6.36 \pm 0.018$	$11.38 \pm 0.025$
				Zn(II)	$-3.12 \pm 0.006$	$-7.28 \pm 0.004$	$6.48 \pm 0.016$	$11.91 \pm 0.024$
				*Cu(II)	$-0.27 \pm 0.01$	$-1.62 \pm 0.01$	$9.30 \pm 0.03$	$17.52 \pm 0.03$

\* The values were reported earlier<sup>1</sup>.

## Nickel(II) :

$\log \beta_1$ —E-W>I-W>M-W>D-W>A-W  
 $\log \beta_2$ —I-W>E-W>M-W>D-W>A-W  
 $\log \beta'_1$ —D-W>A-W>I-W>E-W>M-W  
 $\log \beta'_2$ —D-W>A-W>I-W>E-W>M-W

## Zinc(II) :

$\log \beta_1$ —E-W>I-W>D-W>M-W>A-W  
 $\log \beta_2$ —E-W>I-W>M-W>D-W>A-W  
 $\log \beta'_1$ —D-W>A-W>E-W>I-W>M-W  
 $\log \beta'_2$ —D-W>A-W>I-W>E-W>M-W

## Copper(II) :

$\log \beta_1$ —I-W>D-W=E-W=M-W>A-W  
 $\log \beta_2$ —I-W>E-W>D-W>M-W>A-W  
 $\log \beta'_1$ —D-W>A-W>I-W>E-W>M-W  
 $\log \beta'_2$ —D-W>A-W>I-W>E-W>M-W

The sequence of  ${}^pK_1^H$  is explained<sup>1</sup> as follows. Weak proton solvation of acetone puts acetone on the top. Although D-W has low dielectric constant, larger proton solvation by dioxane-water and also by the cosolvent removes dioxane from the first place to the second. The alcoholic solvents are in the sequence of their  $1/\epsilon$  values. In addition, they are stronger proton solvating. That acetone water has a tendency to go higher up in the series is evident from the fact that in 75% v/v composition, although the mole fraction of A-W is a bit greater than that of D-W or I-W, it is much less than that of E-W or M-W. The difference between A-W and E-W is also very large although the difference in  $1/\epsilon$  for these two compositions is quite small.

The equilibrium constants,  $\log \beta_1$  and  $\log \beta_2$ , show random deviation from  $1/\epsilon$  sequence. But one thing is remarkable. The sequences are almost unaltered by the different metal ions. Acetone-water generally has the lowest value since the cosolvent here has the least tendency to solvate proton. Alcohols go up in the sequence as they solvate protons comparatively to a larger extent.

The formation constants,  $\log \beta'_1$  and  $\log \beta'_2$ , however have some correlation with the  $1/\epsilon$  sequence in the different solvents, because proton solvation may not have here any direct influence. The order for  $\log \beta'_1$  is less regular but  $\log \beta'_2$  has become almost similar to the  $1/\epsilon$  sequence, only that acetone-water and isopropanol-water have exchanged places. Here again, it may be noted that the nature of the metal ions has little effect on the order.

In every solvent-water system the stability sequence for metal ions is observed to be Co(II) > Ni(II) < Cu(II) > Zn(II). Co(II) is thus found to deviate from Irving and Williams' order. The entropy factor is likely to be similar in these systems. So it appears that it may be an evidence of Jahn Teller type of distortion for  $t_{2g}^5 e_g^3$  set in high spin Co(II) ion ( $t_{2g}^5 e_g^3$ ). This may be the reason for slightly higher stability of Co(II). Higher L.F.S.E. effect of NBPFA ligand may also be a contributory factor to this.

## Acknowledgement

The authors are grateful to University Grants Commission, New Delhi for the grant of a Teacher Fellowship to one of them (N. K.).

References

1. A. K. CHAUDHURY and N. KOLE, *J. Indian Chem. Soc.*, 1981, 58, 868.
2. S. P. BAG and S. LAHIRI, *J. Inorg Nuclear Chem.*, 1976, 38, 1611.
3. S. C. SHOME, M. R. SENGUPTA and H. R. DAS, *J. Inorg. Nuclear Chem.*, 1972, 34, 860.
4. A. K. CHAUDHURY, N. KOLE and S. P. GHOSH, *J. Indian Chem. Soc.*, 1981, 58, 248.
5. A. K. CHAUDHURY, *J. Indian Chem. Soc.*, 1976, 53, 1286.



# Stability of Complexes of Co(II), Ni(II) and Cu(II) with Esters of Salicylic Acid

A. GUPTA and B. S. PANNU

Department of Chemistry, Punjab Agricultural University, Ludhiana-141 004

Manuscript received 6 February 1981, revised 30 December 1981, accepted 23 May 1982

The stepwise stability constants of complexes of Co(II), Ni(II) or Cu(II) with methylsalicylate, ethylsalicylate or phenylsalicylate have been determined. The effect of temperature and ionic strength has been studied. The thermodynamic stability constants are obtained at 25°. The stability order is Cu(II) > Ni(II) > Co(II) and methylsalicylate > ethylsalicylate > phenylsalicylate. The higher values of stability constants suggest that the complexes are chelate in nature.

THE stabilities of the chelates of methylsalicylate with some metal ions of the first transition series in aqueous solutions were reported by Perrin<sup>1</sup>. The stabilities of ethylsalicylate complexes of Cu(II), Ni(II), Zn(II) and Hg(II) are known in literature<sup>2</sup>. The stabilities and thermodynamic functions of the complexes of Mn(II), Zn(II), Cd(II) and Hg(II) with esters of salicylic acid have been published from our laboratory<sup>3,4</sup>. A systematic study of the stabilities of the complexes of Co(II), Ni(II) or Cu(II) with methylsalicylate, ethylsalicylate or phenylsalicylate is reported in this paper.

## Experimental

Bjerrum Calvin pH titration technique<sup>5,6</sup>, as modified by Irving and Rossotti<sup>7</sup>, has been used for investigations. The stability constants of the complexes have been determined at 25° and various ionic strengths viz. 0.05 M, 0.075 M, 0.10 M and at 35° with an ionic strength of 0.05 M in aqueous ethanol 50 : 50 (v/v). The ionic strength was adjusted by adding NaClO<sub>4</sub> solution as an inert electrolyte. In order to fulfil the condition of maximum coordination number, metal to ligand ratio was kept at 1 : 5. Since the titrations were carried out in aqueous ethanol system appropriate corrections were applied to the measurements to get the actual pH<sup>8</sup>. The following three solutions were titrated against a standard alkali (0.1 M KOH).

- (A) 2.0 ml of 0.05 M HClO<sub>4</sub>
- (B) A+2.0 ml of 0.05 M ligand
- (C) B+2.0 ml of 0.01 M metal ion.

The initial volume in each case was 20 ml containing aqueous ethanol system 50 : 50 (v/v). The titrations were carried at 25 ± 0.1° and 35 ± 0.1° in a constant temperature bath.

## Results and Discussion

The esters of salicylic acid are weak acids due to the OH group. The values of  $\beta_A$ ,  $K_H^*$ ,  $\bar{n}$  and  $pL$

were calculated by the usual relationships<sup>9</sup>. The formation curves were obtained by plotting  $\bar{n}$  against  $pL$ . The value of  $\bar{n}$  does not go beyond 2 in any case for the metal complexes. This indicates the formation of 1 : 1 and 1 : 2 complexes. The

TABLE 1—STABILITY CONSTANTS OF METAL COMPLEXES OF ESTERS OF SALICYLIC ACID IN ALCOHOL : WATER SYSTEM 50 : 50 (v/v) AT 25°

Ester	Metal ion	Ionic strength M	log K <sub>1</sub>	log K <sub>2</sub>
Methyl salicylate	Co(II)	0.000	5.70	4.50
		0.050	4.95	3.83
		0.075	4.80	3.72
		0.100	4.70	3.63
		0.050*	5.82	4.82
	Ni(II)	0.000	5.80	4.60
		0.050	5.30	3.85
		0.075	5.20	3.75
		0.100	4.90	3.65
		0.050*	5.75	4.89
	Cu(II)	0.000	14.62	13.00
		0.050	9.87	8.50
		0.075	8.25	7.45
		0.100	7.00	6.87
		0.050*	7.43	7.00
Ethyl salicylate	Co(II)	0.000	5.60	4.40
		0.050	4.90	3.80
		0.050*	5.14	4.50
	Ni(II)	0.000	6.40	4.50
		0.050	5.15	3.82
		0.050*	5.17	4.77
	Cu(II)	0.000	8.90	8.10
		0.050	6.90	6.40
		0.050*	6.70	6.30
Phenyl salicylate	Co(II)	0.000	5.00	4.30
		0.050	4.55	3.80
		0.050*	4.60	3.87
	Ni(II)	0.000	5.60	4.40
		0.050	4.87	3.80
		0.050*	4.90	4.35
	Cu(II)	0.000	7.70	7.30
		0.050	6.55	6.05
		0.050*	6.80	5.75

\* at 30°.

stability constants for the complexes were obtained by half  $\bar{n}$  method and linear extrapolation method<sup>9</sup>. The values obtained by both the methods are in good agreement. The average values at different temperatures and ionic strengths are given in Table 1. The thermodynamic stability constants at 25° were obtained by plotting  $\log K_n$  values against  $\sqrt{\mu}$  and extrapolating to zero ionic strength. These are also given in Table 1.

A perusal of the values of the stability constants shows that there exists the stability order  $\text{Cu(II)} > \text{Ni(II)} > \text{Co(II)}$  with regards to the nature of the metal ions. This sequence of stability constants agrees with the Irving-Williams natural order<sup>10</sup> and other orders confirmed by several workers<sup>11,12</sup>.

Regarding the nature of the ligands, the stability order of the complexes is methylsalicylate > ethylsalicylate > phenylsalicylate. The value of  $\log K_1^H$  (the proton-ligand stability constant) has been found to decrease on increasing the bulk of the group R in  $\text{R-OOCC}_6\text{H}_4\text{OH}$ . This explains the descending stability order of the complexes with increasing bulk of R in the esters. A comparison of the stabilities at 25° and 35° shows that the effect of rise of temperature on the stability of the complexes becomes less and less pronounced in going from methylsalicylate through ethylsalicylate to phenylsalicylate.

Another important factor influencing the stability is ionic strength of the medium. It is apparent from the stabilities at 25° with different ionic strengths (Table 1); the stabilities record a decrease with an increase of ionic strength. This is in accordance with the earlier conclusions of Debye<sup>13</sup>. In media of higher ionic strength the metal ions are shielded from the ligands by the other ions present. This results in low rates of combination of the metal ions with the ligands.

#### References

1. D. D. PERLIN, *Nature*, 1958, 182, 741.
2. K. E. JABALPURWALA, K. A. VENKATACHALAM and M. B. KABADI, *J. Inorg. Nuclear Chem.*, 1964, 26, 1027.
3. A. GUPTA and B. S. PANNU, *Thermochim. Acta*, 1979, 31, 101.
4. AMRITVIR and B. S. PANNU, *Thermochim. Acta*, 1980, 37, 253.
5. J. BJERRUM, "Metal Ammine Formation in Aqueous Solution", P. Haase and Sons, Copenhagen, 1941.
6. M. CALVIN and K. W. WILLSON, *J. Amer. Chem. Soc.*, 1945, 67, 2008.
7. H. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
8. L. G. VAN UITERT and C. G. HAAS, *J. Amer. Chem. Soc.*, 1953, 75, 451.
9. H. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1953, 8397.
10. H. IRVING and R. J. P. WILLIAMS, *Nature*, 1948, 162, 746.
11. J. W. MELLOR and G. F. MALEV, *Nature*, 1947, 159, 370.
12. G. A. CARLSON, J. P. McREYNOLDS and F. H. VERHOEF, *J. Amer. Chem. Soc.*, 1945, 67, 1884.
13. P. DEBYE, *Trans. Electrochem. Soc.*, 1942, 82, 7.

# Spectrophotometric Determination of Dissociation Constants of Violuric Acid and Stability Constant of its Cu(II) Complex

B. R. SINGH\* and R. GHOSH\*\*

Chemistry Department, University of Roorkee, Roorkee-247 672

Manuscript received 2 December 1980, revised 18 January 1982, accepted 23 May 1982

Spectrophotometric studies of Cu(II)-violuric acid system indicate the presence of 1 : 2 complex in the pH range 4.0-6.5. The apparent equilibrium constant ( $K_1$ ) has been determined by general absorbance-extinction-concentration scheme. The thermodynamic values of the first and second dissociation constants of the ligand have been determined while the third dissociation constant has been determined at  $I=1.0$ . The effects of pH stress and buffer compositions on the dissociations have also been investigated. The stability constant of the complex is found to be 14.60 at pH 5.5 and  $I=0.10$ .

THE coordinative interactions of substituted barbituric moieties are of great importance in elucidating various enzymatic and drug actions. Isonitroso barbituric acid or violuric acid forms chelates with different metal ions<sup>1-4</sup>. Apart from this analytical potentiality, no systematic work has been done on this acid and as such it was decided to make a thorough study of its chelation to Cu(II). As a knowledge of dissociation constants of the acid is required, these have also been determined by spectrophotometric technique.

## Experimental

Violuric acid (VA) of E. Merck chromatographic grade was used without further purification. Carbonate-free NaOH and HClO<sub>4</sub> (A. R., E. Merck) solutions were used for adjusting the pH to the desired value. Other chemicals used were of AnalaR grade. All studies were made in conductivity water.

The pH was measured with an ELICO-pH meter (India) fitted with glass and saturated calomel electrodes. The uv absorption spectra of VA at various pH values were recorded on Carl-Zeiss Specord recording spectrophotometer. The visible spectra of the complex were measured with Bausch and Lomb Spectronic-20. All absorbance measurements were taken with 1 cm cells at room temperature ( $25 \pm 0.5^\circ$ ).

For studies of dissociation, a solution of  $2.0 \times 10^{-3}$  M violuric acid at an ionic strength of 0.10 was used; some measurements were taken at variable ionic strength ranging from 0.02 to 0.35. For determining  $pK_a$ , the ionic strength had to be maintained, of necessity, at 1.0. For studies on the Cu(II) complex, concentrations were varied at a fixed M/L (1 : 2) ratio and constant ionic strength (0.10).

## Results and Discussions

The spectra of violuric acid (VA) in solution strongly depend on the pH of the media indicating successive deprotonation equilibria. The significant bands of VA are at 252 nm in strongly acid solution (pH 1.25) and at 220 nm and 312 nm in the alkaline medium (pH 8.0). Beyond pH 10.0, the absorption occurs at 325 nm with an isosbestic point at 318 nm. In a more basic medium (pH 13.50), the characteristic peak is at 310 nm. Interpreting the spectral behaviour in terms of three successive dissociation equilibria, the molecular acid  $H_3L$  would correspond to pH 2.50, the monoanion,  $H_2L^-$ , would be present around a pH 8.0 and the dianion,  $HL^{2-}$ , at about a pH of 12, respectively. To identify fully ionized VA i.e.,  $L^{3-}$ , the spectrum of VA in 2 M NaOH was recorded and a graphical estimation<sup>5</sup> was also made. The extinction values obtained by the two methods agreed well.

The dissociation constants,  $K_c$ , have been calculated by the equations reported in the literature<sup>6</sup>. The  $K_{c1}$  and  $K_{c2}$  values were determined at several ionic strengths. The thermodynamic  $pK_1$  and  $pK_2$  values were determined by extrapolation method. The average values of the stepwise dissociation constants determined at several analytical wave lengths<sup>7</sup> are  $K_{c1} = 5.88 \times 10^{-4}$  ( $I=0.10$ ),  $K_{c2} = 1.38 \times 10^{-10}$  ( $I=0.10$ ) and  $K_{c3} = 2.81 \times 10^{-14}$  ( $I=1.0$ ).

**Determination of the stability constant of Cu(II)-VA complex :** In presence of a large excess of Cu(II) ions, VA shows maximum absorbance at  $\lambda = 420$  nm in the pH range 4.2 to 6.5. For solutions above pH 7.0, the absorption maximum shifts towards shorter wavelength and an isosbestic point is observed at 412 nm. This indicates that only one complex is formed between pH 4.2 and 6.5 but formation of more than one complex may be

\* Present address : Department of Chemistry, Bahu Jain College, Najibabad-266 768, Bijnor (U. P.).

\*\* Present address : Department of Chemistry, Indian Institute of Technology, Kharagpur-721 303.

involved at pH above 6.5. The 1 : 2 composition of the complex was determined by Job's method<sup>7</sup>.

The reaction scheme



is proposed to represent the interactions of  $\text{Cu}^{2+}$  ions added to a solution of VA in the pH range 4.5 to 6.5. At constant pH the apparent equilibrium constant  $K_1^{\text{app}}$  is then given by

$$K_1^{\text{app}} = \frac{[\text{Cu}(\text{HL})_2^{2-}]}{\{M^0 - [\text{Cu}(\text{HL})_2^{2-}]\}\{L^0 - [\text{Cu}(\text{HL})_2^{2-}]\}^2} \quad (2)$$

where  $M^0$  and  $L^0$  are analytical concentrations of metal ion and ligand, respectively.

The stability constant (concentration quotient) of 1 : 2 complex is defined as

$$K_1 = K_1^{\text{app}} \phi \quad \dots (3)$$

where  $\phi = \left[1 + \frac{[\text{H}]}{K_{c_1}} + \frac{[\text{H}]^2}{K_{c_1}K_{c_2}}\right]$ , and

$K_{c_1}$  and  $K_{c_2}$  are the first and second concentration dissociation constants of VA. Knowing  $K_1^{\text{app}}$  and  $\phi$  at a definite pH, the stability constant of the complex can be calculated from equation 3. As the  $\text{Cu}(\text{II})$  ion and VA do not absorb in the region of  $\lambda_{\text{max}} = 420 \text{ nm}$  of the complex, the extinction coefficient ( $\epsilon$ ) of the complex is found to be  $0.28 \times 10^4$  at  $\text{pH } 5.50 \pm 0.05$  and  $I = 0.1 \text{ M}$ . The apparent equilibrium constant,  $K_1^{\text{app}}$ , determined by general absorbance extinction concentration scheme and the stability constant,  $K_1$ , calculated from equation 3 are  $\log K_1^{\text{app}} = 7.15$  and  $\log K_1 = 14.60$ , respectively at  $\text{pH } 5.50 \pm 0.05$  and  $I = 0.1 \text{ M}$ .

The effect of pH on the apparent equilibrium constant,  $K_1^{\text{app}}$ , of the complex has been studied. The  $K_1^{\text{app}}$  values were found to show no appreciable change in the pH range 4.2-6.5. A sudden lowering of the  $K_1^{\text{app}}$  values above pH 7.0 may be due to the hydrolysis of unreacted  $\text{Cu}(\text{II})$  ions and/or formation of other species. A linear plot of  $\log K_1$  versus pH with slope of 1.0 suggests that the dissociation of the second proton from VA, occurring in this pH range, accompanies the association of the dianion with  $\text{Cu}(\text{II})$  ion. This is an evidence adduced in favour of the reaction scheme (1).

#### Acknowledgements

The authors express their gratitude to the University of Roorkee for facilities and to the U. G. C., New Delhi for awarding a Fellowship to one of them (B. R. S.).

#### References

1. P. A. LEHRMAKERS and W. A. HOFFMANN, *J. Amer. Chem. Soc.*, 1968, **90**, 5668.
2. H. MICHELLE, *Acta Crystallogr. B*, 1968, **28**, 228.
3. J. MORATAL and J. FAUS, *Inorg. Chim. Acta*, 1977, **25**,  $L_1-L_2$ .
4. C. BREMARD, M. MULLER, G. NOUROGROCKI and S. SORUR, *J. Chem. Soc., Dalton Trans.*, 1977, **23**, 2307.
5. A. ALBERT and E. P. SERJEANT, "Ionization Constants of Acids and Bases", Methuen & Co. Ltd., London, 1962, p. 84.
6. M. C. GHATTOFADHYAYA and R. S. SINGH, *Indian J. Chem.*, 1972, **10**, 850.
7. P. JOB, *Compt. Rend.*, 1925, **180**, 928.

# Molecular Complexes of Tetracycline and Oxytetracycline Drugs with Nucleic Acid Bases and Aromatic Amino Acids

J. LAHIRI and R. BASU\*

Department of Physical Chemistry, University College of Science, Calcutta-700 009

Manuscript received 28 August 1981, revised 20 May 1982, accepted 8 June 1982

Spectral studies are made on tetracycline and oxytetracycline drugs with purines, pyrimidines and amino acids.  $h\nu_{\max}$  vs HFMO (highest filled  $\pi$ -molecular orbital) plots give different stabilization energies for purines, pyrimidines and amino acids. Oxytetracycline gives stronger complexes with purines, pyrimidines and amino acids than the tetracycline. The thermodynamic functions,  $\Delta G^\circ$ ,  $\Delta H^\circ$  and  $\Delta S^\circ$ , have been calculated from the spectral data. Reasonable linear relationships have been found between  $\Delta H^\circ$  and  $\Delta S^\circ$  or  $\Delta G^\circ$  and  $\Delta H^\circ$  for these systems. The contribution of the dative bond wave function has been calculated for each complex in the ground state indicating the formation of charge-transfer complex of the order of 6-14%.

THE action of antibiotics<sup>1</sup> upon microorganisms may be either bacteriostatic or bactericidal.

The mechanism through which the antibiotics act upon microorganisms is not fully clear. It is generally believed that the bacteriostatic effects arise from the interaction of antibiotics with bacterial enzymes, while the bactericidal effects originate in the interaction of antibiotics with cell nuclei. Molecular biologists have theorized that this interaction is due to complex formation between antibiotics and proteins on one hand and nucleic acids on the other, thereby suppressing the normal biological activity of proteins and nucleic acids. Some experimental support for this theory can be provided if the existence of molecular complexes of antibiotics with nucleic acids could be demonstrated by physical measurements. With this object in view systems containing antibiotics tetracycline and oxytetracycline, with purines, pyrimidines and amino acids in dimethyl sulphoxide (DMSO) and dimethyl formamide (DMF) were studied and the results are reported here. Similar studies were made in water, ethylene glycol and propylene glycol where the interaction was shown to be of charge-transfer type<sup>2</sup>.

Since tetracycline and oxytetracycline have intense absorption bands in the near ultraviolet region at 363 nm and 365 nm, respectively optical methods may be used conveniently for the study of molecular complexes in these systems. We have used four aromatic amino acids phenyl alanine tryptophan, tyrosine and histidine; four purines adenine, guanine, xanthine and hypoxanthine and three pyrimidines cytosine, thymine and uracil in the present investigation.

## Experimental

All the purines, pyrimidines and amino acids used are products of E. Merck, Darmstadt, B. D. H., England and Loba Chemical, Austria. They were

of A. R. grade and used without further purification. The solvents used were of E. Merck quality. They were carefully dried and freshly distilled just before the experiments. Since traces of moisture in the solvents give completely erratic results, particular care was taken about the purification of the solvents. Tetracycline and oxytetracycline were obtained from Sigma Company, St. Louis, U. S. A. and used directly without further purification.

All spectral data were taken in Beckman model DU spectrophotometer provided with a thermostatic arrangement, using matched pairs of stoppered silica cells. Measurements with strongly absorbing systems were made in 1 cm cells whereas 10 cm cells were used when the intensity of absorption was low. Measurements were made at four different temperatures namely 23, 40, 50 and 60°. The thermostatic arrangements were kept under such control that the variation of temperature did not exceed  $\pm 1^\circ$ .

The concentrations of the donors were  $10^{-3}$  mole/litre and those of drugs were  $10^{-4}$  mole/litre.

## Results and Discussions

The absorption spectra of tetracycline and adenine-tetracycline mixture in DMSO is given in Fig. 1. The tetracycline shows a peak at 363 nm, while adenine-tetracycline mixture shows two peaks at 363 nm and 376 nm. Adenine itself, in DMSO, has no absorption band in this region. As the adenine concentration is increased at a fixed tetracycline concentration, the optical density of the band at 376 nm increases and that at 363 nm diminishes. Evidently, the band at 376 nm arises from a molecular complex between tetracycline and adenine. When balanced against the same concentration of tetracycline in DMSO the band appears at 385 nm, definitely establishing a red shift in the spectra with respect to tetracycline band (Fig. 2).




Fig. 1




Fig. 2

Similar measurements were made with other purines, pyrimidines and amino acids and new bands were detected in all the cases. Oxytetracycline behaved in a similar fashion. The relevant data are summarised in Tables 1 and 2.

The spectral measurements at a fixed concentration of antibiotic but different concentrations of purines, pyrimidines and amino acids may be utilised to determine the equilibrium constant for complex formation. Since free antibiotic absorb quite strongly at the complex band, the simple Benesi-Hildebrand<sup>5</sup> treatment cannot be used in the present case. For these types of situation de Maine<sup>6</sup> has worked out an iterative method for estimating equilibrium constants,  $K_s$ , from optical density measurements at complex band. About four/five iterations were necessary to get self consistency in  $K_s$  values. The calculated values are also given in Tables 1 and 2. A perfect linearity of  $[A]/(O.D.)_c$  versus  $1/[D]$  plots, where  $[A]$  is the

concentration of antibiotic and  $[D]$  the concentration of donors, shows that the complexes studied are of 1 : 1 type.

The thermodynamic functions  $\Delta H^\circ$ ,  $\Delta S^\circ$  and  $\Delta G^\circ$  connected with the complex formation are calculated from the changes in formation constant with temperature by Van't Hoff equation (Tables 1 and 2).

It appears from the  $K_s$  values recorded in Tables 1 and 2 that antibiotics tetracycline and oxytetracycline form strong complexes with purines, pyrimidines and aromatic amino acids. So, both proteins and nucleic acid bases form strong complexes with these antibiotics. From the points of view of drug action, as stated earlier, these findings obviously mean that tetracycline and oxytetracycline will have both bactericidal and bacteriostatic effects. As a matter of fact, Snell and Cheng<sup>7</sup> reported that tetracyclines are bacteriostatic at low concentrations but bactericidal at higher concentrations; they decrease protein synthesis at low concentrations and nucleic acid formation at higher concentrations. It is also evident (Tables 1 and 2) that oxytetracycline forms much stronger complexes with purines, pyrimidines and amino acids than those formed by tetracycline. This may account for the selectivity of oxytetracycline as compared to tetracycline, although they have similar biological behaviour.

It must be stated categorically that this is no one-to-one correlation between the actual biological reactions and the systems studied in the present investigation. This is only a good model system reproducing reasonably well some of the findings in biological system.

Now a word about the nature of the forces involved in molecular complex formation. Since the appearance of the famous book on molecular biology by Szent-Györgyi<sup>8</sup>, a majority of workers support the proposition that the interaction in many biological processes is charge-transfer in nature. So the question is whether the molecular complexes studied in the present case can be considered as charge-transfer complexes.

One way of verifying this is to plot  $h\nu_{\text{transition}}$  against the ionization energies of the purines, pyrimidines and amino acids, considering the antibiotics as acceptors. The experimental ionization energies of all the purines, pyrimidines and amino acids are not available in the literature. However, we can take the energy of the highest filled  $\pi$ -molecular orbital,  $HFMO/\beta$ , which is related to the ionization energies of the respective compounds as calculated by Pullman and Pullman<sup>9</sup>. Such curves are shown in Fig. 3. The relevant data are given in Table 3. It may be observed that the plot is fairly linear for purine-, pyrimidine-tetracycline systems and for amino acid-tetracycline system. The same is true for the oxytetracycline acceptor as is evident from Fig. 4.

TABLE 1—SOLVENT DMSO

Donors	$\lambda_{\max}$ nm	$-\Delta H^\circ$ K Joule mole $^{-1}$		$-\Delta S^\circ$ Joule mole $^{-1}$ deg $^{-1}$		Temp °C	$K_c$ L mole $^{-1}$		$\epsilon$ L mole $^{-1}$ cm $^{-1}$	
		Tetra- cycline	Oxytetra- cycline	Tetra- cycline	Oxytetra- cycline		Tetra- cycline	Oxytetra- cycline	Tetra- cycline	Oxytetra- cycline
Adenine	385	388	26.11 $\pm$ 0.28	26.58 $\pm$ 0.15	9.54 $\pm$ 0.08	4.19 $\pm$ 0.04	22.26 $\pm$ 0.06	25.32 $\pm$ 0.02	14,390 $\pm$ 685	15,088 $\pm$ 13
							14,918	14,706		
							14,164	14,653		
							15,194	14,589		
Guanine	387	389	26.32 $\pm$ 0.18	27.33 $\pm$ 0.17	10.71 $\pm$ 0.09	5.73 $\pm$ 0.02	23.10 $\pm$ 0.04	23.61 $\pm$ 0.03	11,770 $\pm$ 70	13,945 $\pm$ 50
							10,471	12,195		
							10,454	12,191		
							13,2	13,114		
Hypoxanthine	392	390	22.53 $\pm$ 0.19	23.94 $\pm$ 0.18	7.66 $\pm$ 0.04	3.05 $\pm$ 0.03	20.31 $\pm$ 0.08	23.02 $\pm$ 0.04	12,500 $\pm$ 64	13,984 $\pm$ 45
							12,891	12,891		
							12,433	12,658		
							19.2	12,440		
Xanthine**	397	404	28.12 $\pm$ 0.19	26.32 $\pm$ 0.10	14.52 $\pm$ 0.27	9.54 $\pm$ 0.07	23.81 $\pm$ 0.06	23.43 $\pm$ 0.05	17,031 $\pm$ 103	19,193 $\pm$ 67
							16,667	18,181		
							16,598	18,018		
							13,15	15,68		
Thymine	370	371	19.13 $\pm$ 0.09	21.26 $\pm$ 0.08	6.49 $\pm$ 0.04	3.67 $\pm$ 0.03	17.20 $\pm$ 0.05	18.79 $\pm$ 0.06	18,100 $\pm$ 190	20,000 $\pm$ 145
							17,699	19,043		
							17,667	19,039		
							17,043	19,096		
Uracil	371	375	23.94 $\pm$ 0.14	25.53 $\pm$ 0.09	9.03 $\pm$ 0.09	3.43 $\pm$ 0.05	21.51 $\pm$ 0.07	24.43 $\pm$ 0.05	13,333 $\pm$ 965	15,985 $\pm$ 95
							13,345	15,867		
							13,386	15,886		
							13,218	15,967		
Phenylalanine	400	398	23.94 $\pm$ 0.19	25.54 $\pm$ 0.04	5.73 $\pm$ 0.03	6.48 $\pm$ 0.06	22.32 $\pm$ 0.09	23.56 $\pm$ 0.07	13,945 $\pm$ 76	13,893 $\pm$ 152
							13,168	18,345		
							12,821	18,338		
							12,500	13,073		
Tyrosine	402	400	24.78 $\pm$ 0.16	27.33 $\pm$ 0.07	8.94 $\pm$ 0.07	7.66 $\pm$ 0.05	22.73 $\pm$ 0.08	25.07 $\pm$ 0.02	11,770 $\pm$ 156	12,500 $\pm$ 353
							11,110	12,492		
							11,060	12,414		
							11,019	12,369		
Histidine	403	401	21.26 $\pm$ 0.12	25.52 $\pm$ 0.08	3.60 $\pm$ 0.09	3.80 $\pm$ 0.06	20.17 $\pm$ 0.05	21.14 $\pm$ 0.07	9,999 $\pm$ 1304	12,384 $\pm$ 95
							9,804	11,111		
							9,615	10,870		
							9,524	10,811		
Tryptophan	405	402	24.32 $\pm$ 0.17	21.36 $\pm$ 0.04	1.88 $\pm$ 0.07	3.43 $\pm$ 0.04	19.54 $\pm$ 0.09	20.21 $\pm$ 0.09	16,529 $\pm$ 346	18,181 $\pm$ 95
							16,385	18,018		
							15,267	17,357		
							15,366	17,794		

\* Calculated from absorption data of 4 different [Donors]+[Tetracycline] or [Oxytetracycline] solutions in DMSO mole/l. [Donors] varied from 0.0435 to 0.095 moles/l using 1 cm cells

\*\* Xanthine using 10 cm cells.

TABLE 2—SOLVENT DMF

Donor	OT <sup>a</sup> λ <sub>max</sub> nm	-ΔH <sup>b</sup> K Joule mole <sup>-1</sup>		-ΔS <sup>b</sup> Joule mole <sup>-1</sup> deg <sup>-1</sup>		-ΔG <sup>b</sup> K Joule mole <sup>-1</sup>		Temp. °C	K <sub>c</sub> L mole <sup>-1</sup>		ε <sub>a</sub> L mole <sup>-1</sup> cm <sup>-1</sup>	
		Tetra- cyclyne	Oxytetra- cyclyne	Tetra- cyclyne	Oxytetra- cyclyne	Tetra- cyclyne	Oxytetra- cyclyne		Tetra- cyclyne	Oxytetra- cyclyne	Tetra- cyclyne	Oxytetra- cyclyne
Adenine	380	40.23 ± 0.28	33.99 ± 0.34	3.85 ± 0.09	18.75 ± 0.09	37.08 ± 0.04	26.79 ± 0.06	23	39.6 ± 1	47.5 ± 0.75	13,333 ± 192	14,705 ± 520
	400	38.30 ± 0.45	29.46 ± 0.26	4.01 ± 0.05	19.00 ± 0.09	39.09 ± 0.02	24.06 ± 0.05	40	16	11.2	13,500	14,385
								50	12.80	5.64	12,422	14,164
								60	6.44	3.33	12,414	14,174
Guanine	400							23	90 ± 0.5	40 ± 1	10,000 ± 83	11,111 ± 185
								40	16.8	19	9,823	10,969
								50	10.55	7.26	9,478	10,964
								60	7	3.65	9,488	10,969
Hypoxanthine	400	81.99 ± 0.55	27.33 ± 0.09	3.43 ± 0.09	17.20 ± 0.05	90.99 ± 0.07	22.89 ± 0.07	23	28 ± 0.60	40.3 ± 0.30	12,821 ± 890	13,422 ± 45
								40	16.4	14	12,196	11,764
								50	10	7	12,131	11,695
								60	7.2	5	12,094	11,697
Xanthine <sup>bb</sup>	406	23.35 ± 0.18	35.11 ± 0.04	15.69 ± 0.69	9.53 ± 0.03	13.66 ± 0.08	22.36 ± 0.06	23	37.2 ± 0.08	42.94 ± 0.94	15,394 ± 50	17,700 ± 25
								40	20.85	35.2	15,263	16,667
								50	8	98.86	16,181	16,699
								60	3.6	19.42	16,090	16,502
Thymine	388	33.34 ± 0.44	29.46 ± 0.31	3.60 ± 0.18	15.07 ± 0.07	37.21 ± 0.07	34.65 ± 0.05	23	41.8 ± 1.4	44 ± 1	10,926 ± 950	13,693 ± 101
								40	18	15	10,000	13,333
								50	12.94	10.57	9,808	13,345
								60	8.2	4.56	9,756	13,157
Uracil	384	34.33 ± 0.69	33.12 ± 0.19	3.64 ± 0.09	19.33 ± 0.04	33.73 ± 0.03	23.53 ± 0.06	23	28.08 ± 0.28	37.5 ± 0.5	13,422 ± 80	13,333 ± 800
								40	18	16	13,333	13,500
								50	7.6	8	13,245	13,422
								60	3.4	5	13,267	13,414
Phenylalanine	390	31.96 ± 0.27	29.46 ± 0.31	14.55 ± 0.14	16.11 ± 0.09	23.46 ± 0.05	24.65 ± 0.07	23	172.5 ± 0.5	180 ± 4	13,890 ± 50	15,333 ± 19
								40	28	90.5	13,500	13,945
								50	90	8.94	12,422	13,266
								60	8	4.16	12,414	13,301
Tyrosine	392	34.49 ± 0.24	30.97 ± 0.07	16.49 ± 0.09	17.20 ± 0.07	33.33 ± 0.02	25.78 ± 0.08	23	147 ± 3	162 ± 3.5	9,091 ± 125	11,111 ± 25
								40	40	31.6	9,090	11,110
								50	15.7	11	8,695	11,049
								60	5	4.34	8,669	11,043
Histidine	395	27.33 ± 0.19	27.33 ± 0.19	12.82 ± 0.13	14.52 ± 0.05	26.07 ± 0.04	23.03 ± 0.04	23	98 ± 2	126 ± 1	10,904	13,048 ± 45
								40	32	15.3	10,163	11,764
								50	14	10.26	10,147	11,695
								60	7	3.44	10,141	11,689
Tryptophan	400	33.94 ± 0.18	26.37 ± 0.04	11.46 ± 0.06	13.81 ± 0.03	30.51 ± 0.05	22.32 ± 0.06	23	161 ± 1	173 ± 0.54	11,765 ± 63	13,500 ± 55
								40	24.6	29.4	11,049	13,422
								50	12.67	12.66	11,049	13,414
								60	3.69	8.48	11,019	13,407

<sup>a</sup> Calculated from absorption data of 4 different [Donors] + [Tetra-cyclyne] or [Oxytetra-cyclyne] solutions in DMF, [Tetra-cyclyne] or [Oxytetra-cyclyne] = 1.0 - 1.55 × 10<sup>-3</sup> mole/l; [Donors] varied from 0.0435 to 0.095 mole/l using 1 cm cells.

<sup>bb</sup> Xanthine using 10 cm cells.






Fig. 3




Fig. 4

Donors	Solvent DMSO $\nu \times 10^{-3}(\text{cm}^{-1})$		Solvent DMF $\nu \times 10^{-3}(\text{cm}^{-1})$		HFMO ( $\beta$ )
	Tetra- cycline	Oxytetra- cycline	Tetra- cycline	Oxytetra- cycline	
Adenine	25.97	25.77	25.64	25.25	0.486
Guanine	25.84	25.71	25.00	25.00	0.507
Xanthine	25.19	24.75	24.87	24.68	0.597
Hypoxanthine	25.51	25.64	25.00	24.81	0.402
Cytosine	25.64	25.84	25.31	25.12	0.595
Thymine	27.08	26.95	25.77	25.31	0.510
Uracil	26.95	26.67	26.04	25.97	0.597
Phenylalanine	25.00	25.13	25.64	25.44	0.908
Tyrosine	24.88	25.00	25.51	25.31	0.792
Histidine	24.81	24.94	25.31	25.25	0.660
Tryptophan	24.69	24.87	25.00	25.06	0.534

The reason for the two different plots for the two systems is obvious. The energy of charge-transfer transition is given as

$$h\nu_{\text{CT}} = I_D - E_A - \Delta.$$

where  $I_D$  is the ionization energy of the donor,  $E_A$  the electron affinity of the acceptor and  $\Delta$  is the stabilization energy of the donor-acceptor pair.

The linear  $h\nu_{\text{transition}}$  vs HFMO plot indicates a constant value for  $\Delta$ . This may be true for chemically allied donors but is not certainly valid for completely chemically dissimilar donors like purines, pyrimidines and amino acids.

We may conclude that linear  $h\nu_{\text{transition}}$  vs HFMO plots indicate that the purines, pyrimidines and amino acids are acting as donors and tetracycline and oxytetracycline as acceptors in the molecular complexes in two solvents and the complex is of charge-transfer type.

Regarding the temperature variation, we may observe that the formation constants,  $K_a$ , and the extinction coefficient,  $\epsilon$ , both diminish with rise of temperature. In Figs. 5, 6, 7 and 8 plots of  $-\Delta S^\circ$  vs  $-\Delta H^\circ$  and  $\Delta G^\circ$  vs  $-\Delta H^\circ$  are shown. These are found to be fairly linear as reported earlier<sup>9</sup>. The position of equilibrium showed reversibility with temperature. The negative enthalpy term and the intensification of band on cooling clearly indicate the charge-transfer nature of the complex<sup>9</sup>.




Fig. 5




Fig. 6




Fig. 7


As is observed, the formation constants increase with increase<sup>10-12</sup> in dielectric constant of the medium for the purines and pyrimidines whereas these decrease<sup>14</sup> with increase in the dielectric constant of the medium for the amino acids. Since charge transfer complexation takes place on a molecular level, the formation constant may be expected to be independent of the bulk dielectric constant. If the electrostatic interaction holds the molecules together, the formation constant will depend strongly on the dielectric constant of the medium and in fact will be lowered with an increase in the dielectric constant of the medium<sup>14</sup>. However, considering the various factors contributing to the formation of charge-transfer complexes, it is practically difficult to separate the influence of one factor from the others. Moreover, the high dielectric constants of the solvents used should have a direct impact also. As previously<sup>14</sup> pointed out, the model developed from the concept of reaction field<sup>14</sup>, though capable of describing approximately the interaction between a solute and weakly polar solvents, becomes too crude an approximation for polar solvent.

TABLE 4—SOLVENT DMSO: ESTIMATED CONTRIBUTION OF THE DATIVE BOND WAVE FUNCTION FOR PURINES, PYRIMIDINES AND AMINO ACIDS+TETRACYCLINE/OXYTETRACYCLINE

Donors	$-\Delta H^\circ$ (ev)		$h\nu_{CT}$ (ev)		$b^2/a^2$	
	Tetracycline	Oxytetracycline	Tetracycline	Oxytetracycline	Tetracycline	Oxytetracycline
Adenine	0.26	0.27	3.22	3.20	0.0807	0.0861
Guanine	0.27	0.28	3.20	3.19	0.0850	0.0888
Hypoxanthine	0.28	0.27	3.17	3.07	0.0787	0.0888
Xanthine	0.29	0.25	3.18	3.18	0.0932	0.0779
Thymine	0.20	0.26	3.38	3.34	0.0594	0.0825
Uracil	0.25	0.22	3.34	3.31	0.0741	0.0659
Phenylalanine	0.25	0.26	3.10	3.12	0.0799	0.0848
Tyrosine	0.26	0.28	3.09	3.10	0.0832	0.0918
Histidine	0.22	0.23	3.08	3.09	0.0716	0.0754
Tryptophan	0.21	0.22	3.06	3.08	0.0681	0.0714

TABLE 5—SOLVENT DMF: ESTIMATED CONTRIBUTION OF THE DATIVE BOND WAVE FUNCTION FOR PURINES, PYRIMIDINES AND AMINO ACIDS+TETRACYCLINE/OXYTETRACYCLINE

Donors	$-\Delta H^\circ$ (ev)		$h\nu_{CT}$ (ev)		$b^2/a^2$	
	Tetracycline	Oxytetracycline	Tetracycline	Oxytetracycline	Tetracycline	Oxytetracycline
Adenine	0.42	0.32	3.18	3.18	0.1809	0.1024
Guanine	0.40	0.30	3.10	3.11	0.1278	0.0982
Hypoxanthine	0.38	0.28	3.08	3.09	0.1065	0.0917
Xanthine	0.34	0.26	3.08	3.05	0.0788	0.0851
Thymine	0.39	0.30	3.20	3.14	0.1942	0.0972
Uracil	0.36	0.29	3.28	3.22	0.1116	0.0904
Phenylalanine	0.34	0.30	3.18	3.16	0.1070	0.0967
Tyrosine	0.35	0.32	3.17	3.14	0.1129	0.1021
Histidine	0.28	0.28	3.14	3.13	0.0902	0.0908
Tryptophan	0.26	0.27	3.10	3.20	0.0799	0.0878



According to Mulliken<sup>1\*</sup>, the ground state and excited state of the molecular complex may be written as

$$\psi_N(DA) = a\psi_0(DA) + b\psi_1(D^+A^-)$$

$$\text{and } \psi_E(DA) = a^*\psi_1(D^+A^-) - b^*\psi_0(DA)$$

where  $\psi_0(DA)$  is the no-bond wave function and  $\psi_1$  the dative bond wavefunction. For weak complexes  $a \gg b$ ,  $a^* \gg b^*$ ; moreover  $a^* \sim a$  and  $b^* \sim b$ . The ratio  $b^2/a^2$  can be calculated from the observed heat of formation and position of CT bands following Ketelaar<sup>1\*</sup> and Tamres and Brandon<sup>2</sup>.

$$b^2/a^2 \approx -\frac{\Delta H_0}{h\nu}$$

These values are listed in Tables 4 and 5. It appears that the charge-transfer interactions are of the order of 6-14%.

#### Acknowledgement

Thanks of the authors are due to University Grants Commission, New Delhi for a Teacher Fellowship to one (J. L.) of them.

#### References

1. A. E. HUSSAR and H. L. HOLLEY, "Antibiotics and Antibiotic Therapy, (A Clinical Manual)", The Macmillan Company, New York, 1954.
2. J. LAHIRI and R. BASU, *J. Chem. Soc., Faraday Trans. I*, 1961, 77, 1405.
3. H. A. BENNETT and J. H. HILDEBRAND, *J. Amer. Chem. Soc.*, 1949, 71, 2708.
4. P. A. D. DE MAINE and R. D. SEAWRIGHT, "Digital Computer Programs for Physical Chemistry", Macmillan, New York, 1968, Vol 1; 1965, Vol 2.

5. J. F. SMELL and L. CHENG, *Antibiot. Ann.*, 1957-58, 588.
6. A. SZENT-GYÖRGYI, "Introduction to a Submolecular Biology", Academic Press, New York, 1960.
7. B. FULLMAN and A. POLLMAN, *Rev. Mod. Phys.*, 1960, 32, 428.
8. M. TAMMERS and M. BRANDON, *J. Amer. Chem. Soc.*, 1960, 82, 2184.
9. R. FOSTER and P. HANSON, *Trans. Faraday Soc.*, 1964, 2189.
10. S. D. CHRISTIAN and J. GRUNDNES, *Nature*, 1967, 214, 1111.
11. S. D. CHRISTIAN and J. GRUNDNES, *J. Amer. Chem. Soc.*, 1968, 90, 2239.
12. R. P. LANG, *J. Phys. Chem.*, 1968, 72, 2199.
13. E. AUGDAHL, J. GRUNDNES and P. KLAMBOZ, *Inorg. Chem.*, 1965, 4, 1475.
14. S. D. CHRISTIAN, "Techniques of Chemistry, Vol. 8, Part I: Solutions and Solubilities", (Ed.) A. WEISSBERGER and M. R. J. DACK, Wiley-Interscience, 1975.
15. B. DAS GHOSH and R. BASU, *J. Phys. Chem.*, 1960, 64, 1887.
16. L. ONSAGER, *J. Amer. Chem. Soc.*, 1936, 58, 1486.
17. R. S. MULLIKEN, *J. Phys. Chem.*, 1954, 51, 341 and earlier papers.
18. J. A. A. KETELAAR, *J. Phys. Radium*, 1954, 15, 197.

## Formation Constants of the Chelates of 2-Hydroxy-1-Naphthalidene-*ortho*-Fluoroaniline with Some Bivalent Metal Ions

M. S. MAYADBO\*, A. M. CHAUBAL and S. H. HUSSAIN

Department of Chemistry, Ramnarain Ruia College, Matunga, Bombay-400 019

Manuscript received 26 March 1979, revised 18 February 1982, accepted 23 May 1982

Potentiometric studies on metal chelates of  $\text{Cu}^{2+}$ ,  $\text{Ni}^{2+}$ ,  $\text{Co}^{2+}$ ,  $\text{Zn}^{2+}$  and  $\text{UO}_2^{2+}$  with 2-hydroxy-1-naphthalidene-*ortho*-fluoroaniline have been carried out. The formation constant,  $pK_{\text{f}}$ , of the reagent and the formation constants of its metal chelates have been determined by Bjerrum's method at  $25 \pm 0.1^\circ$  and at ionic strength 0.1 *M* in 75 : 25 percent (v/v) dioxane-water medium. The order of stability of metal chelates is found to be  $\text{UO}_2^{2+} > \text{Cu}^{2+} > \text{Zn}^{2+} > \text{Co}^{2+} > \text{Ni}^{2+}$ .

A survey of literature indicates that no systematic study of the stabilities of 2-hydroxy-1-naphthalidene-*o*-fluoroaniline and its metal chelates with bivalent metal ions has been carried out. The present communication, therefore, deals with the determination of the stability constants of the chelates of 2-hydroxy-1-naphthalidene-*o*-fluoroaniline in 75% (v/v) dioxane-water medium employing the Calvin-Bjerrum pH titration technique as adopted by Irving and Rossotti<sup>1</sup>.

### Experimental

A precision research pH meter, Corning Model 12, with a wide range glass electrode and calomel reference electrode was used for pH measurements. The meter has an arrangement for normal and expanded scales. The smallest division on the expanded scale is 0.005 pH unit.

The ligand, 2-hydroxy-1-naphthalidene-*o*-fluoroaniline, was prepared and repeatedly crystallised from alcohol to get an analytically pure sample (m.p.  $104^\circ$ ). The purity of the ligand was ascertained by elemental analysis. The carbon and hydrogen content of the fluoro compound was determined by the method described by Steyermark<sup>2</sup>. Fluorine was determined by the volumetric procedure of Schoniger<sup>3</sup>. (Found: C, 76.8; H, 4.30; N, 5.20; F, 6.90. Calcd. for  $\text{C}_{17}\text{H}_{13}\text{FNO}$ ; C, 76.98; H, 4.53; N, 5.28; F, 7.17%).

All the chemicals used except the ligand and the perchloric acid were of B. D. H. analytical grade. The perchloric acid was E. Merck G. R. grade. The medium of titration was a 75% (v/v) dioxane-water mixture. The dioxane used was purified by the method described by Vogel<sup>4</sup>. Distilled water, redistilled over alkaline potassium permanganate, was used throughout the investigation. Sodium perchlorate was added to maintain a constant ionic strength (0.1 *M*). The titrations were carried out in an inert atmosphere by bubbling oxygen free

nitrogen gas through the solutions. Metal perchlorates were prepared from the oxides or carbonates and standardised complexometrically by EDTA<sup>5</sup>. Measurements were carried out at  $25 \pm 0.1^\circ$ .

The following solutions were titrated potentiometrically against standard carbonate free sodium hydroxide solution (1.01 *M*):

- (i) 5 ml 0.16 *M*  $\text{HClO}_4$  + 5 ml 0.64 *M*  $\text{NaClO}_4$  + 30 ml dioxane.
- (ii) 5 ml 0.16 *M*  $\text{HClO}_4$  + 5 ml 0.64 *M*  $\text{NaClO}_4$  + requisite amount of the reagent to give 0.004 *M* reagent concentration in the final solution + 30 ml dioxane.
- (iii) 5 ml 0.64 *M*  $\text{NaClO}_4$  + 5 ml 0.008 *M* metal salt solution in 0.16 *M*  $\text{HClO}_4$  + requisite amount of the reagent to give 0.004 *M* reagent concentration in the final solution + 30 ml dioxane.

All titrations were performed in duplicate to test for reproducibility. The results are depicted in Fig. 1.

The experimental method of Irving and Rossotti<sup>1</sup> was applied to find out the values of  $\bar{n}$  and  $pL$ .

### Results and Discussion

In the ligand, it is the phenolic OH group that takes part in complex formation and the proton is replaced by metal ions during chelation. Since only one proton per ligand molecule is liberated during complexation,  $\bar{Y}$ , the number of dissociable protons attached per ligand molecule is one.

From the titration curves using solutions (i) and (ii),  $\bar{n}_A$  values at various B values (pH meter readings) were calculated, and the curve of B against the corresponding  $\bar{n}_A$  values was plotted. The formation curve extends over a range  $0.18 < \bar{n}_A < 0.97$ . This indicates the formation of the species




Fig. 1. Titration curves of 2-hydroxy-1-naphthalidene-o-fluorocyaniline.

HL only. The value of  $pK_H^H$  could be determined from the half-integral point at  $\bar{n}_A = 0.5$ .

The maximum values of  $\bar{n}$  for  $\text{Cu}^{2+}$ ,  $\text{Ni}^{2+}$ ,  $\text{Co}^{2+}$  and  $\text{Zn}^{2+}$  systems range from 0.606 to 0.998 indicating the formation of 1:1 complexes only. Precipitation in these systems occurs at  $B = 6.4, 7.2, 6.9$  and  $6.6$ , respectively. Since the maximum value of  $\bar{n}$  obtained at the point of incipient precipitation is 1.0,  $\log K_2$  for the above systems could not be determined by the reported method. For  $\text{UO}_2^{2+}$ , precipitation does not occur till  $B = 5.32$  at which point  $\bar{n}$  values lie well above 1.5. Both  $\log K_1$  and  $\log K_2$  could, therefore, be obtained. Since the difference between  $\log K_1$  and  $\log K_2$  for  $\text{UO}_2^{2+}$  obtained by the half  $\bar{n}$  method was less than 1.78 log units, the least square method was used to obtain refined values.

Fig. 2 shows the experimental data ( $\bar{n}, pL$ ) for the metal ligand systems in 75% dioxane-water medium together with theoretical formation curves<sup>a</sup> calculated from the relationship  $\bar{n} + (\bar{n} - 1) K_1(L) + (\bar{n} - 2) K_1 K_2 (L)^2 = 0$ .

Values of stability constants for all the systems, except  $\text{UO}_2^{2+}$ , obtained from the half-integral method were used for the above calculation. For  $\text{UO}_2^{2+}$ , the values of stability constants obtained from the least square treatment were employed. The curve for  $\text{Cu}^{2+}$  is in appreciably better agreement with the experimental points. A lower precision is indicated for the systems involving  $\text{Co}^{2+}$  and  $\text{Ni}^{2+}$ . A more satisfactory agreement




Fig. 2. Formation curves of metal ligand systems of 2-hydroxy-1-naphthalidene-o-fluorocyaniline.

for these systems could not be obtained since the values of  $\log K_2$  calculated by the method of successive approximations remained within the limits of error.

The most representative values are recorded in Table 1. Standard deviations<sup>a</sup> and limits of error

TABLE 1—STEPWISE STABILITY CONSTANTS OF THE COMPLEXES OF 2-HYDROXY-1-NAPHTHALIDENE-O-FLUOROANILINE WITH SOME DIVALENT METAL IONS

Cations	$t = 25 \pm 0.1^\circ$		$\mu = 0.1 \text{ M (NaClO}_4\text{)}$			
	$\text{H}^+$	$\text{Cu}^{2+}$	$\text{UO}_2^{2+}$	$\text{Ni}^{2+}$	$\text{Co}^{2+}$	$\text{Zn}^{2+}$
$\log K_1$	9.84	8.47	8.96	6.08	5.95	5.40
$\log K_2$	—	—	7.18	—	—	—

For  $\text{H}^+$ ,  $K_1$  corresponds to the species  $\text{LH}$ , while for metal ions  $K_1$  and  $K_2$  correspond to the species  $\text{ML}$  and  $\text{ML}_2$  respectively.

for  $\log K$  values range from  $\pm 0.2$  to  $\pm 0.03$  and  $\pm 0.13$  to  $\pm 0.02$ , respectively. The order of stability for the metal chelates was found to be  $\text{UO}_2^{2+} > \text{Cu}^{2+} > \text{Zn}^{2+} > \text{Co}^{2+} > \text{Ni}^{2+}$ .

#### Acknowledgement

The authors sincerely thank Dr. D. G. Vartak, B. A. R. C., Bombay for valuable suggestions and Prof. A. P. Rao, Head, Chemistry Dept., Ramnarain Ruia College for encouragement.

References

1. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
2. A. STREYERMAN, "Quantitative Organic Microanalysis", Academic Press, Inc., N. Y., 1961, p. 232.
3. W. SCHÖNIGER, *Mikrochim. Acta*, 1956, 869.
4. A. I. VOGL, "A Text Book of Practical Organic Chemistry", 3rd Edn., Longman, p. 177.
5. G. SCHWARZENBACH, "Complexometric Titrations", Methuen and Co. Ltd., London, 1956, p. 60.
6. H. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1958, 3897.

# Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-2',6'-Dimethylaniline Complexes with $\text{La}^{3+}$ , $\text{Y}^{3+}$ , $\text{Pr}^{3+}$ , $\text{Nd}^{3+}$ , $\text{Dy}^{3+}$ and $\text{Gd}^{3+}$

M. S. MAYADEO\*, S. S. PUROHIT and S. H. HUSSAIN

Department of Chemistry, Ramnarain Ruia College, Matunga, Bombay-400 019

Manuscript received 10 July 1981, revised 2 February 1982, accepted 23 May 1982

Potentiometric studies on metal complexes of  $\text{La}^{3+}$ ,  $\text{Y}^{3+}$ ,  $\text{Pr}^{3+}$ ,  $\text{Nd}^{3+}$ ,  $\text{Dy}^{3+}$  and  $\text{Gd}^{3+}$  with 2-hydroxy-1-naphthalidene-2',6'-dimethylaniline have been carried out. The proton-ligand dissociation constants ( $pK_1$  and  $pK_2$ ) of the reagent and the formation constants of its metal complexes have been determined by Bjerrum's method at  $25 \pm 0.1^\circ$  and at an ionic strength  $0.1M$  ( $\text{NaClO}_4$ ) in 75:25 percent (v/v) dioxane-water medium. The validity of Born's relation was examined by studying the plot of  $Z^2/r$  vs  $\log K$  values of rare earth complexes of the ligand.

THE successive stability constants of the complexes of 2-hydroxy-1-naphthalidene-2',6'-dimethylaniline with trivalent metal ions have been determined potentiometrically following the Calvin-Bjerrum pH titration technique as adopted by Irving and Rossotti<sup>1</sup> and the findings are reported in the present communication.

A precision research pH meter, Corning Model 12, with combined glass electrode and a calomel reference electrode was used for pH measurements. Both the electrodes dip into the titration mixture without vitiating any results. The meter has an arrangement for normal and expanded scales and the pH can be measured with an accuracy of 0.005 pH unit.

## Experimental

The ligand, 2-hydroxy-1-naphthalidene-2',6'-dimethylaniline was prepared and repeatedly crystallised from alcohol to get an analytically pure sample with m.p.  $116^\circ$  (observed).

The dioxane used was purified by the method described by Vogel<sup>2</sup>. Distilled water, redistilled over alkaline potassium permanganate, was used throughout the investigation.

The medium of titration was 75:25 per cent dioxane-water (v/v) mixture. Sodium perchlorate was added to maintain a constant ionic strength. The titrations were carried out in an inert atmosphere by bubbling oxygen free nitrogen gas through the solutions. The free acid, the free acid plus the ligand and the mixture of metal ion, the acid and the ligand were titrated against standard carbonate free sodium hydroxide. Metal ion solutions of yttrium, gadolinium and neodymium were prepared by taking metal nitrates of A.R. grade which were converted to their respective carbonates and then to their perchlorates. Metal

ion solutions of dysprosium, praseodymium and lanthanum were prepared by taking the metal carbonates of A. R. grade which were converted to their respective perchlorates. The metal nitrates and carbonates were supplied by S. D. Lab. Chem. Industry, Bombay. All the solutions were standardised complexometrically<sup>3</sup> by EDTA titrations. All measurements were carried out at  $25 \pm 0.1^\circ$ .

The following solutions were titrated potentiometrically against standard carbonate free sodium hydroxide (1.07  $M$ ) solution:

- (i) 5 ml 0.16  $M$   $\text{HClO}_4$  + 5 ml 0.64  $M$   $\text{NaClO}_4$  + 30 ml dioxane.
- (ii) 5 ml 0.16  $M$   $\text{HClO}_4$  + 5 ml 0.64  $M$   $\text{NaClO}_4$  + 60.0 mg reagent to give 0.004  $M$  reagent concentration in the final solution + 30 ml dioxane.
- (iii) 5 ml 0.64  $M$   $\text{NaClO}_4$  + 5 ml metal salt 0.008  $M$  solution in 0.16  $M$   $\text{HClO}_4$  + 60.0 mg reagent to give 0.004  $M$  reagent concentration in the final solution + 30 ml dioxane.

The appropriate correction factor for converting pH meter readings ( $B$  values) to  $-\log[\text{H}^+]$  in 75% (v/v) dioxane-water was applied<sup>4</sup> and the curves plotted accordingly. The experimental method of Irving and Rossotti<sup>1</sup> was applied to find out values of  $\bar{n}$  and  $pL$ . The titrations were performed in duplicate to test for reproducibility.

## Results and Discussion

It may be pointed out here that the ligand used in this study did not undergo hydrolysis under the experimental conditions. This was indicated by rapid attainment of equilibrium during titration and by the absence of any significant drift in the pH even after 1 hr. In the ligand, it is the phenolic OH group that takes part in complex formation and the ligand behaves as a monoprotic one.



From the titration curves using the solutions (i) and (ii),  $\bar{n}_A$  values at various pH were calculated and a curve between pH and the corresponding  $\bar{n}_A$  values was plotted (Fig. 1). The values of  $pK_1^H$  and  $pK_2^H$  were evaluated by the half-integral method as well as from the plots of  $\log \bar{n}_A/(1-\bar{n}_A)$  vs pH and  $\log (2-\bar{n}_A)/(\bar{n}_A-1)$  vs pH (Figs. 2 and 3). Both these values agree well.

From the titration curves of solutions (ii) and (iii),  $\bar{n}$  and pL values were calculated. The  $\bar{n}$  values were plotted against the corresponding pL values to get the formation curves of metal complex ion equilibria (Fig. 4). For lanthanum and praseodymium metal systems,  $\log K_1$  and  $\log K_2$  values were evaluated by the half-integral method. These values agree well with those obtained from




Fig. 1. Formation curve of 2-hydroxy-1-naphthalidene-2',6'-dimethylaniline. Plot of  $\bar{n}_A$  vs pH




Fig. 4. Metal ligand systems of 2-hydroxy-1-naphthalidene-2',6'-dimethylaniline. Plot of  $\bar{n}$  vs pL




Fig. 2. 2-Hydroxy-1-naphthalidene-2',6'-dimethylaniline. Plot of  $\log \bar{n}_A/(1-\bar{n}_A)$  vs pH




Fig. 3. 2-Hydroxy-1-naphthalidene-2',6'-dimethylaniline. Plot of  $\log (2-\bar{n}_A)/(\bar{n}_A-1)$  vs pH



Fig. 5 2-Hydroxy-1-naphthalidene-2',6'-dimethylaniline Plot of  $\log \bar{n}/1-\bar{n}$  vs  $pL$ Fig. 6 2-Hydroxy-1-naphthalidene-2',6'-dimethylaniline Plot of  $\log 2-\bar{n}/1-\bar{n}$  vs  $pL$ 

TABLE I—STEPWISE STABILITY CONSTANTS OF THE COMPLEXES OF 2-HYDROXY-2',6'-DIMETHYLANILINE WITH TRIVALENT LANTHANIDES

	$t=25 \pm 0.1^\circ$			$\mu=0.1$ (NaClO <sub>4</sub> )		
Cations	Y <sup>3+</sup>	Dy <sup>3+</sup>	Nd <sup>3+</sup>	Pr <sup>3+</sup>	Gd <sup>3+</sup>	La <sup>3+</sup>
$\log K_1$	9.65	8.19	9.06	9.10	8.09	7.87
$\log K_2$	2.97	6.90	7.06	6.42	7.13	7.15
$\sigma^a$	$\pm 0.025$	$\pm 0.058$	$\pm 0.058$	$\pm 0.058$	$\pm 0.07$	$\pm 0.13$
Limits of error	$\pm 0.018$	$\pm 0.04$	$\pm 0.03$	$\pm 0.03$	$\pm 0.04$	$\pm 0.07$

For proton association (H<sup>+</sup>)  $K_1$  corresponds to the species  $HL$ , while for metal ions,  $K_1$  and  $K_2$  correspond to the species  $ML_1$  and  $ML_2$ , respectively

the linear plots of  $\log \bar{n}/1-\bar{n}$  and  $\log 2-\bar{n}/1-\bar{n}$  vs  $pL$  (Figs. 5 and 6). In the case of metal systems of neodymium, yttrium, dysprosium and gadolinium, where the difference between  $\log K_1$  and  $\log K_2$  values was found to be less than 1.78 log unit, the same were calculated by the least square method. The most representative values are recorded in Table I. Standard deviations range from 0.04 to 0.13, the lower precision being observed for dysprosium. Limits of error lie between  $\pm 0.03$  and  $\pm 0.07$ . The order of stability of the trivalent metal chelates was found to be  $Gd > La > Pr > Y > Nd > Dy$ .

Rare earths normally form ionic compounds. The possibility of covalent interaction, however,

cannot be completely excluded as reported in the case of acetylacetonate chelates of rare earths<sup>6</sup>. If the bonds are ionic, the Born relation  $E = Z^2/2r(1-1/D)$  should hold for the energy change on complexation of a gaseous ion of charge  $Z$  and radius  $r$  in a medium of dielectric constant  $D$ . Since the stability constant is related directly to this energy, the  $\log K$  values should increase linearly with  $Z^2/r$ . The plots of  $\log K_1$  vs  $Z^2/r$  values of the rare earth complexes do not exhibit any linear increase of  $\log K_1$  with increase in  $Z^2/r$ .

#### Acknowledgement

The authors sincerely thank Dr. D. G. Vartak, B. A. R. C., Bombay, for valuable suggestions and Prof. A. P. Rao, Head of Chemistry Department, Ramnarain Ruia College, for continuous encouragement.

#### References

1. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
2. A. I. VOGEL, "A Text Book of Practical Organic Chemistry", 3rd Edn., Longmans, p. 177.
3. H. A. FLASCHKA, "EDTA Titrations", Pergamon Press, N. Y., p. 78.
4. A. GORSINI and E. J. BILLO, *J. Inorg. Nuclear Chem.*, 1970, 32, 1249.
5. T. D. MORLER, *Chem. Rev.*, 1965, 65, 1.
6. H. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1953, 3897.

## Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Hydroxyaniline Complexes with $Mg^{2+}$ , $Co^{2+}$ , $Ni^{2+}$ and $Cu^{2+}$

M. S. MAYADBO and S. S. PUROHIT

Department of Chemistry, Ramnarain Ruia College, Matunga, Bombay-400 019

Manuscript received 6 August 1981, accepted 1 May 1982

Potentiometric studies on metal complexes of  $Mg^{2+}$ ,  $Co^{2+}$ ,  $Ni^{2+}$  and  $Cu^{2+}$  with 2-hydroxy-1-naphthalidene-4'-hydroxyaniline have been carried out. The proton-ligand dissociation constants ( $pK_1$  and  $pK_2$ ) of the reagent and the formation constants of its metal complexes have been determined by Bjerrum's method at  $25 \pm 0.1^\circ$  and at an ionic strength 0.1 M in 75 : 25 percent (v/v) dioxane-water medium.

THE successive stability constants of the complexes of 2-hydroxy-1-naphthalidene-4'-hydroxyaniline with bivalent metal ions have been determined potentiometrically following the Calvin-Bjerrum pH titration technique as adopted by Irving and Rossotti<sup>1</sup> and the results are presented here.

A precision research pH meter, Corning Model 12, with combined glass electrode and a calomel reference electrode was used for pH measurements. Both electrodes dip into the titrating mixture without vitiating any results. The meter has an arrangement for normal and expanded scales. The changes in the pH can be measured with an accuracy of 0.005 pH unit.

### Experimental

The ligand 2-hydroxy-1-naphthalidene-4'-hydroxyaniline was prepared and repeatedly crystallised to obtain an analytically pure sample with m.p.  $224^\circ$  (Lit. m.p.  $224^\circ$ )<sup>2</sup>.

The dioxane used was purified by the method described by Vogel<sup>3</sup>. Distilled water redistilled over alkaline potassium permanganate was used throughout the investigation.

The medium of titration was 75 : 25 per cent dioxane-water (v/v) mixture. A constant ionic strength was maintained by adding sodium perchlorate. The titrations were carried out in an inert atmosphere by bubbling oxygen free nitrogen gas through the solutions. The free acid, the free acid plus the ligand and the mixture of metal ion containing the acid plus the ligand were titrated against standard carbonate free sodium hydroxide. Metal ion solutions of nickel and magnesium were prepared by taking the metal carbonates of A. R. grade, and those of copper and zinc were prepared by taking the metal oxides of A. R. grade. These were standardised complexometrically<sup>4</sup> by EDTA titrations. All measurements were carried out at  $25 \pm 0.1^\circ$ .

The following solutions were titrated potentiometrically against standard carbonate free sodium hydroxide (1.07 M) solution.

- (i) 5 ml 0.16 M  $HClO_4$  + 5 ml 0.64 M  $NaClO_4$  + 30 ml dioxane.
- (ii) 5 ml 0.16 M  $HClO_4$  + 5 ml 0.64 M  $NaClO_4$  + requisite amount of reagent to give 0.004 M reagent concentration in the final solution + 30 ml dioxane.
- (iii) 5 ml 0.64 M  $NaClO_4$  + 5 ml metal salt 0.008 M solution in 0.16 M  $HClO_4$  + the requisite amount of the reagent to give 0.004 M reagent concentration in the final solution + 30 ml dioxane.




The experimental method of Irving and Rossotti was applied to find out the value of  $\bar{n}$  and  $pL$ . The titrations were performed in duplicate to test for reproducibility.

### Results and Discussion



It may be pointed out here that the ligand used in this study did not undergo hydrolysis under the experimental conditions. This was indicated by rapid attainment of equilibrium during the titration and by the absence of any significant drift in the pH even after 1 hr.

In the ligand, it is the phenolic OH group that takes part in the complex formation and the ligand behaves as monoprotic.

From the titration curves using the solutions (i) and (ii),  $\bar{n}_A$  values at various B values, (pH meter readings), were calculated and a curve between B and the corresponding  $\bar{n}_A$  values was plotted (Fig. 1). The value of  $pK_1^H$  was evaluated by half integral method as well as from the plot of  $\log \left[ \frac{\bar{n}_A}{1-\bar{n}_A} \right]$  vs B (Fig. 2). Both these values agree well.

Fig. 1. Formation curve of 2-hydroxy-1-naphthalidene-4'-hydroxyaniline. Plot of  $\bar{h}_A$  vs BFig. 2. 2-Hydroxy-1-naphthalidene-4'-hydroxyaniline  
Plot of  $\log \left[ \frac{\bar{h}_A}{1 - \bar{h}_A} \right]$  vs BFig. 3. 2-Hydroxy-1-naphthalidene-4'-hydroxyaniline.  
Plot of  $\log \left[ \frac{2 - \bar{h}_A}{\bar{h}_A - 1} \right]$  vs B

From the titration curves of solutions (ii) and (iii)  $\bar{h}$  and  $pL$  values were calculated. The  $\bar{h}$  values were plotted against the corresponding  $pL$  values to get the formation curves of metal complex ion equilibria. From this  $\log K_1$  and  $\log K_2$  values were evaluated by the half integral method. In the

Fig. 4. Metal ligand systems of 2-hydroxy-1-naphthalidene-4'-hydroxyaniline. Plot of  $\bar{h}$  vs  $pL$ Fig. 5. 2-Hydroxy-1-naphthalidene-4'-hydroxyaniline  
Plot of  $\log \left[ \frac{\bar{h}}{1 - \bar{h}} \right]$  vs  $pL$ 

case of nickel and copper systems, the difference between  $\log K_1$  and  $\log K_2$  values was found to be less than 1.78 log unit and hence these were calculated by the least square method and are reported.

The most representative values are recorded in Table 1. The order of stability of the various metal chelates was found to be  $\text{Cu}^{2+} > \text{Co}^{2+} \approx \text{Ni}^{2+} > \text{Mg}^{2+}$ . This is in agreement with Murakami order<sup>6</sup>.

TABLE 1—STEPWISE STABILITY CONSTANTS OF VARIOUS COMPLEXES

Cations	$t=25^\circ$				
	$\text{H}^+$	$\text{Mg}^{2+}$	$\text{Co}^{2+}$	$\text{Ni}^{2+}$	$\text{Cu}^{2+}$
$\log K_1$	10.98	5.00	7.57	7.57	9.08
$\log K_2$	3.94	—	—	6.29	7.99

For proton association ( $\text{H}^+$ ),  $K_1$  corresponds to the species  $\text{LH}$ , while for metal ions  $K_1$  and  $K_2$  correspond to the species  $\text{ML}_1$  and  $\text{ML}_2$ , respectively.

#### Acknowledgement

The authors record sincere thanks to Dr. D. G. Vartak, B. A. R. C., Bombay for valuable suggestions

MAYADBO & PUROHIT : DETERMINATION OF STABILITY CONSTANTS ETC.

and to Prof. A. P. Rao, Head of Chemistry  
Department, R. Ruia College for encouragement.

References

1. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
2. L. CROWTHER, T. ABELL and H. PACHECO, *Bull. Soc. Chim. Biol.*, 1964, 46, 703.
3. A. I. VOGEL, "A Text Book of Practical Organic Chemistry", 3rd Edn., Longmans, p. 177.
4. H. A. FLASCHKA, "EDTA Titrations", Pergamon Press, N. Y., p. 78.
5. Y. MURAKAMI, K. NAKAMURA and M. TOKUNAGA, *Bull. Chem. Soc., Japan*, 1963, 36, 669.

# Studies on the Polarographic Reduction of Progesterone

(Miss) GUNJAN SRIVASTAVA and ARVIND KUMAR

Chemical Laboratories, Agra College, Agra-282 002

Progesterone gave a well defined slightly drawnout wave when studied polarographically. The process is irreversible and a continuous negative shift in  $E_{1/2}$  is observed with increasing pH. The value of  $k_{1/2}D^{-1/2}$  varies from 0.016 to 5.348 at the foot of the wave to the plateau indicating that the process is completely kinetically controlled at the foot of the wave but becomes diffusion controlled and reversible at the plateau. A tentative mechanism for the reduction process has been proposed.

THE direct polarographic reduction of conjugated keto steroids has been studied earlier<sup>1</sup> and it is reported that ketones with a conjugated double bond are directly reducible at the d. m. e. Wolfe, Hershberg and Fieser (*loc. cit.*) were the pioneers in the polarography of keto steroids and they introduced a method for assaying the 17-keto steroid. Eisenbrand and Picher<sup>2</sup> found it possible to determine polarographically some hormones such as, testosterone, progesterone, corticosterone and desoxycorticosterone, which contain keto group and conjugated double bonding  $O=C-C=C-$ . Barnett and Morris<sup>3</sup> studied some water soluble steroidal hydrazones polarographically.

The polarographic reduction of keto steroids depends greatly on external factors such as pH, nature and concentration of buffer and solvent. Much of the early work on the  $\Delta^4,5$ -unsaturated keto steroid was performed in unbuffered or poorly buffered systems. Adkins and Cox<sup>4</sup> obtained reduction waves for cholesterol in 0.1 N ammonium chloride solutions. Later, Eisenbrand and Picher (*loc. cit.*) observed the behaviour of several  $\Delta^4$ -3-keto steroid in 90% ethanol and 0.1 N LiCl.

Sartori and Bianchi<sup>5</sup> reported the half wave dependence on pH for 17-ethinyl-testosterone and methyl testosterone, but did not describe any changes in the wave form or diffusion current with pH. Later, Zuman *et al.*<sup>6</sup> made a fairly exhaustive study on the behaviour of certain  $\Delta^4$ -3-keto steroids in 30-60% ethanol solutions buffered with Britton and Robinson buffer mixtures.

The present paper deals with the polarographic behaviour of a conjugated keto steroid, progesterone, in presence of phosphate buffer. The study has been carried out in two different supporting electrolytes, LiCl and KCl, and an attempt has been made to suggest a mechanism for the reduction process.

## Experimental

Pure sample of progesterone (B. D. H.) was used in all the experiments. All other chemicals were of B. D. H. AR grade. Solutions were prepared in double distilled water and were deaerated by

bubbling pure nitrogen gas. The temperature was maintained at  $15 \pm 0.1^\circ$  using a thermostat.

Polarograms were taken at different pH by using phosphate buffer in presence of KCl or LiCl used as supporting electrolyte. A Toshniwal manual polarograph, in conjunction with a sensitive polyflex galvanometer was used. The half wave potential refers to the saturated calomel electrode (S.C.E.). Pure distilled mercury was used in dropping mercury electrode and the capillary characteristics at mercury height of 35 cm was  $m^{2/3} t^{1/6} = 2.031 \text{ mg}^{2/3} \text{ sec}^{-1/6}$  in 0.1 N KCl.

## Results and Discussion

A well defined single step reduction of progesterone is observed when it is reduced at the d. m. e. The diffusion current varies linearly with increase in the concentration of progesterone and the plots of  $i_d$  vs  $\sqrt{h_{\text{corr}}}$  indicate the phenomenon as diffusion controlled.

Analysis of C-V curves indicates the irreversibility of the process which is further confirmed by the nature of log plots and the value of  $E_{1/4} - E_{3/4}$  (Table 1; Fig. 1); when  $\log (1-i_r)$  is plotted against  $-E_d$ , an initial straight line followed by a curve, a characteristic of irreversible process, is obtained. The values of the product of transfer coefficient and the number of electrons involved in the reduction process,  $\alpha n$ , have been determined (Table 1) which are in conformity with the irreversible nature of the reduction process.

The diffusion current is markedly affected by the nature of the supporting electrolyte and the half wave potential is almost the same in both the supporting electrolytes ( $-0.92 \text{ V}$  vs S.C.E.). The half wave potential is unaffected by the concentration of the depolarizer. However, it changes with temperature, first it increases and then decreases with the rise in temperature. All the while, the temperature coefficient of half wave potential is more than 2 mV per degree as can be expected of an irreversible process. The diffusion current varies linearly with temperature and the temperature coefficient is  $0.0903 \mu \text{ amp per degree}$ .

TABLE I  
 Conc. of progesterone =  $2.4 \times 10^{-3}\%$   
 Hg height = 85 cm  
 Temp. =  $16 \pm 0.1^\circ$   
 Buffer = Phosphate buffer ( $\text{Na}_2\text{HPO}_4$  and  $\text{NaH}_2\text{PO}_4$ )

Supporting electrolyte	0.1 M LiCl				0.1 M KCl			
	$i_d$ ( $\mu\text{A}$ )	$-E_{1/2}$ (Volts)	$E_2 - E_{1/2}$ (Volts)	$\alpha n$	$i_d$ ( $\mu\text{A}$ )	$-E_{1/2}$ (Volts)	$E_2 - E_{1/2}$ (Volts)	$\alpha n$
pH								
5.8	0.9080	0.84	0.14	0.1564	1.0960	0.88	0.16	0.2513
6.2	0.8882	0.84	0.20	0.1281	0.9997	0.89	0.18	0.1774
6.4	0.8062	0.88	0.22	0.1625	0.9875	0.90	0.20	0.1922
6.8	0.7417	0.90	0.26	0.1186	0.9080	0.90	0.24	0.2809
7.4	0.7096	0.92	0.22	0.1182	0.7417	0.92	0.24	0.1478
7.8	0.6450	0.96	0.28	0.1106	0.6450	0.94	0.26	0.1774
8.1	0.6127	0.98	0.28	0.1184	0.5808	0.98	0.28	0.1922




Fig. 1. C-V curves of progesterone at different pH

A regular negative shift in half wave potential and decrease in diffusion current with increasing pH has been observed and a strict proportionality of both the factors with pH has been obtained

(Figs. 2, 3) The negative shift of half wave potential and the decrease in the value of the diffusion current may be due to the complexation of the depolarizer with the constituents of buffer.




Fig. 2. pH vs  $i_d$ .




Fig. 3. pH vs  $-E_{1/2}$ .

The values of the rate constant  $k_{t,h}$  at different potentials have been calculated by Koutecky's method<sup>7</sup>. An increase in the value of  $k_{t,h}$  with potential is observed and  $-\log k_{t,h}$  vs  $-E_{d.e.}$  plots are straight lines (Fig. 4). The value of  $k_{t,h}$   $D^{-1/2}$  varies from 0.016 to 5.348 (Table 2) with the increase in potential at the d. m. e. which clearly indicates that the electrode process is totally irreversible and kinetically controlled at the foot of the wave while it is reversible and diffusion controlled at the top. During the entire rising portion of the wave the process is controlled kinetically and by diffusion. The value of heterogeneous rate constant  $k_{t,h}^0$  increases regularly with the increase in pH, indicating that the phenomenon becomes more and more reversible. The variation in free energy change with pH also supports this view. The value of  $k_{t,h}^0$  first increases and then decreases with a rise in temperature and the value at 25° is maximum. This variation is in accordance with the shift in  $E_{1/2}$  with temperature (Table 3).

**Mechanism of polarographic reduction:** Progesterone molecule possesses conjugated carbonyl group at 3-C atom and therefore, the electrolytic



Fig. 4.  $-\log k_{t,h}$  vs  $-E_{d.e.}$ 

TABLE 2												
Supp. electrolyte pH	0.1 M LiCl					0.1 M KCl						
	$-E_{d.e.}$ (V)	$-\log k_{t,h}$	$k_{t,h} \times 10^3$	$k_{t,h} \times D^{-1/2}$	$k_{t,h}^0 \times 10^3$ (cm sec <sup>-1</sup> )	$\Delta G$ (K cal)	$-E_{d.e.}$ (V)	$-\log k_{t,h}$	$k_{t,h} \times 10^3$	$k_{t,h} \times D^{-1/2}$	$k_{t,h}^0 \times 10^3$ (cm sec <sup>-1</sup> )	$\Delta G$ (K cal)
5.8	0.5	4.7212	1.90	0.09042	3.1623	72.7955	0.7	4.3208	1.20	0.01921	3.1623	72.7955
	0.6	4.6020	2.50	0.04003			0.8	3.9871	10.30	0.01649		
	0.7	4.2291	5.90	0.09447			0.9	3.6602	21.80	0.08660		
	0.8	3.8181	15.20	0.24839			1.0	3.3056	49.40	0.79103		
	0.9	3.4685	34.20	0.54763			1.1	3.0079	98.00	1.56925		
6.2	0.5	4.7055	1.97	0.08154	4.4668	71.9287	0.7	4.4962	3.10	0.05108	5.0119	71.6397
	0.6	4.4089	3.90	0.06244			0.8	4.0640	8.60	0.06507		
	0.7	4.1988	6.40	0.10248			0.9	3.6223	23.80	0.98206		
	0.8	3.9208	12.90	0.20880			1.0	3.3453	45.10	0.72281		
	0.9	3.4239	47.20	0.75580			1.1	2.9375	116.4	1.84147		
6.4	0.5	4.7212	1.99	0.08186	6.3096	71.0619	0.7	4.1898	3.23	0.05172	7.9438	70.4840
	0.6	4.2676	5.40	0.08646			0.8	3.9847	10.35	0.18578		
	0.7	4.0861	8.20	0.06542			0.9	3.6500	22.38	0.85836		
	0.8	3.8860	18.70	0.21987			1.0	3.1486	71.88	1.15090		
	0.9	3.6528	28.80	0.44836			1.1	2.7945	254.3	4.06726		
6.8	0.5	4.6989	2.00	0.08202	7.9438	70.4840	0.7	4.6020	2.50	0.04008	26.0000	67.5946
	0.6	4.4948	3.20	0.05124			0.8	3.9828	10.09	0.16156		
	0.7	4.2144	6.10	0.09767			0.9	3.7841	16.43	0.25620		
	0.8	3.8968	11.20	0.85068			1.0	3.5048	31.27	0.50072		
	0.9	3.6596	21.90	0.57966			1.1	3.3120	48.74	0.78046		
7.4	0.5	4.6615	2.18	0.08490	14.000	69.039	0.7	4.5406	2.88	0.04611	50.000	65.8609
	0.6	4.4698	3.39	0.05428			0.8	4.2168	3.04	0.04867		
	0.7	4.2021	6.27	0.10040			0.9	3.9309	11.72	0.18767		
	0.8	3.9390	11.75	0.18815			1.0	3.6822	32.92	0.52746		
	0.9	3.6988	20.00	0.32025			1.1	3.4899	64.57	1.08894		
7.8	0.5	4.7178	1.90	0.08069	17.000	68.5192	0.7	4.8191	2.40	0.08849	79.000	64.7052
	0.6	4.6182	2.40	0.08848			0.8	4.1528	7.01	0.11284		
	0.7	4.4105	3.80	0.06222			0.9	3.8711	18.45	0.21587		
	0.8	4.1419	7.20	0.11548			1.0	3.5442	28.55	0.38697		
	0.9	3.8576	13.80	0.20816			1.1	3.2478	71.14	1.18718		
8.1	0.5	4.7117	1.90	0.08106	50.000	65.8609	0.7	4.4482	1.55	0.06729	126.000	68.5494
	0.6	4.5905	2.50	0.04110			0.8	4.2239	11.17	0.09582		
	0.7	4.3822	4.10	0.06642			0.9	3.9585	20.88	0.17886		
	0.8	4.1126	7.70	0.12855			1.0	3.7086	49.19	0.78778		
	0.9	3.8188	15.10	0.24828			1.1	3.4000	125.88	2.00160		




TABLE 3  
Conc. of progesterone =  $1.6 \times 10^{-3}$  %  
Hg height = 35 cm  
pH = 7.4

Supporting electrolyte	0.1 M LiCl				0.1 M KCl			
	$i_d$	$-E_{1/2}$	$k_p \times 10^3$	$\Delta G$	$i_d$	$-E_{1/2}$	$k_p \times 10^3$	$\Delta G$
Temp. (°C)	( $\mu$ A)	(Volt)	(cm. sec <sup>-1</sup> )	(K cal)	( $\mu$ A)	(Volt)	(cm. sec <sup>-1</sup> )	(K cal)
15	0.7740	0.90	5.0119	68.75088	0.8062	0.90	5.0119	71.63978
20	0.9880	0.96	6.3036	71.06190	0.8757	0.92	6.3036	71.06190
25	0.9675	0.98	40.0000	66.43886	0.9352	0.94	16.0000	68.75088
30	1.8867	0.92	32.0620	67.01674	1.2320	0.90	13.0000	69.82826
35	1.4500	0.90	7.9433	70.48402	1.4512	0.86	7.9433	70.48402



Progesterone

reduction of this molecule can take place in a manner similar to that of unsaturated conjugated ketones. One electron bimolecular reduction process is possible which proceeds through a coupling reaction resulting in the formation of a pinacol.



The probability of reduction of second carbonyl group attached at 20-C atom is comparatively less because this carbonyl group lacks conjugation and

is sterically more hindered than carbonyl group of C-3 atom. Further, this reduction is difficult as it requires more energy for fission of side chain at C-17 atom from the pentenophenanthrene nucleus. Similar mechanism had been proposed by Kabasakalian and McGlotten<sup>8</sup> for the polarographic reduction of  $\Delta^4$ -3-keto steroids.

## References

- 1 J K WOLF, F B HERBERGER and I F FISHER, *J Biol. Chem.*, 1940, 136, 653.
- 2 EISENBRAND and PITCHER, *Z. Physiol. Chem.*, 1939, 260, 88.
- 3 J BARNETT and C. J O R MORRIS, *Biochem. J.*, 1946, 40, 150.
- 4 H ADKINS and F W COX, *J. Amer. Chem. Soc.*, 1938, 60, 1151.
- 5 G SARTORI and E BIANCHI, *Gazz. Chim. Ital.*, 1944, 74, 8.
- 6 P ZUMAN, J TENYGL and M BREZINA, *Coll. Czech. Chem. Commun.*, 1954, 19, 46.
- 7 J KOUTECKY, *Chem. Listy*, 1953, 47, 323, *Coll. Czech. Chem. Commun.*, 1953, 18, 597, *Chem. Listy*, 1955, 49.
- 8 P KABASAKALIAN and J M GLOTTEN, *J. Amer. Chem. Soc.*, 1956, 78, 5032.

# Polarographic Studies on the Effect of Some Ionic and Non-ionic Surfactants on the Kinetics of Irreversible Electrode Processes of Arylazopyrimidine and Arylazopyrazole


WAHID U. MALIK\* and RAJEEV JAIN

Department of Chemistry, University of Borkes, Borkes-247 672

Manuscript received 27 July 1981, revised 19 March 1982, accepted 1 May 1982

Polarographic behaviour of 2-amino-4,6-dimethyl-5-arylazopyrimidine and N'-phenyl-3,5-dimethyl-4-phenylazopyrazole has been studied in 0.1 M KCl in presence of some ionic and non-ionic surfactants. The effect of an increase in surfactant concentration, beyond the concentration just sufficient to eliminate the maxima, on the kinetic parameters of irreversible reduction of arylazo-pyrimidine and arylazopyrazole has been investigated.

A survey of literature reveals that work on the effect of surfactants on the reaction kinetics of heterocycles at DME is surprisingly scarce<sup>1,2</sup>. Pyrimidines and pyrazoles are of great medicinal and biological importance and a knowledge of the effect of surfactants on their redox behaviour at the solution-mercury interface may prove very useful from the physiological point of view<sup>3</sup>. As surfactants are used as emulsifiers in drugs, the effect of the surfactants on redox behaviour of these compounds is of immense importance. With this aim in view the present study covering totally irreversible electrode processes of 2-amino-4,6-dimethyl-5-arylazopyrimidine (A) and N'-phenyl-3,5-dimethyl-4-arylazopyrazole (B) was undertaken.



## Experimental

Arylazopyrimidine (A) and arylazopyrazole (B) were synthesized by the method reported from this laboratory<sup>4,5</sup>. Stock solutions ( $1.0 \times 10^{-3}$  M) of compound A and B were prepared in methanol (AnalaR). The buffer used was Britton-Robinson buffers in the pH range 2.0-12.0. All the surfactants used were of high purity and their aqueous solutions were employed.

Polarograms were recorded on a Cambridge pen recording polarograph. The capillary characteristic was  $2.040 \text{ mg}^{1/2} \text{ sec}^{-1/2}$ . SCE was used as the reference electrode. For recording polarograms 1.0 ml of stock solution ( $1.0 \times 10^{-3}$  M) of compound A or B, 1.0 ml of 0.1 M KCl, 5.0 ml of buffer and 3.0 ml of water were mixed and a stream of pure

nitrogen gas was passed for about 5 min to ensure complete deaeration. The requisite amount of surfactant was added, keeping the volume constant in each case. The cell was kept in a thermostated water bath ( $25 \pm 0.1^\circ$ ). The number of electrons involved in the reduction process was calculated by millicoulometry method<sup>6</sup> using  $\text{CdSO}_4$  as a reference solution. Ilkovic equation was used to calculate the value of diffusion coefficient ( $D_0^{1/2}$ ). The kinetic parameters ( $\alpha n$  and  $k_{t,n}$ ) were calculated by Koutecky's treatment<sup>7</sup>.

## Results and Discussion

Pyrimidine A and pyrazole B gave single, well defined, irreversible diffusion controlled reduction waves whose  $E_{1/2}$  were pH dependent but  $i_d$  remained constant throughout the entire pH range. The  $E_{1/2}$  was shifted towards negative potential with increase in pH thereby showing that protonation precedes reduction.

A perusal of the slope value of log plots reveals that the irreversible reduction of pyrimidine and pyrazole becomes more irreversible when the surfactant is gradually increased beyond the concentration just sufficient to eliminate the maxima. For both the ionic and the non-ionic surfactants,  $i_d$  decreases and  $E_{1/2}$  records a negative shift (Tables 1 and 2) as their concentration is increased.

The product  $\alpha n$ , shows a decrease with the increase in surfactant concentration. The polarographic reduction of arylazopyrimidine and arylazopyrazole was found to be two electron reduction and therefore  $\alpha n$ , the number of electron involved in the rate-determining step can either be 1 or 2. Since the decrease in the  $\alpha n$  value is indistinct and at no stage the two consecutive values vary by a factor of 2, the possibility of decrease in value of the product  $\alpha n$ , due to a change in  $n$ , is ruled out. It can thus be safely concluded that it is the  $\alpha$  which is decreasing<sup>8,9</sup>.

\* Present address: Kashmir University, Srinagar (J & K).

TABLE 1—EFFECT OF INCREASING CONCENTRATIONS OF IONIC AND NON-IONIC SURFACTANTS ON THE KINETICS OF IRREVERSIBLE ELECTRODE PROCESS OF ARYLAZOPYRIMIDINE AT pH 6.2

Surfactants	(Surfactant) %	$-E_{1/2}$ V	$i_d$ $\mu A$	$\alpha n_a$	$D_0^{1/2} \times 10^4$ $cm^2/sec$	$k^0_{t,h}$ $cm/sec$
Cationic CTAB	$1.0 \times 10^{-3}$	0.56	1.25	0.62	8.6	$1.2 \times 10^{-10}$
	$1.6 \times 10^{-3}$	0.57	1.22	0.60	8.2	$8.6 \times 10^{-11}$
	$2.2 \times 10^{-3}$	0.59	1.16	0.57	8.0	$8.0 \times 10^{-11}$
OPB	$1.4 \times 10^{-3}$	0.56	1.25	0.64	8.6	$1.2 \times 10^{-10}$
	$2.0 \times 10^{-3}$	0.58	1.20	0.62	8.0	$7.2 \times 10^{-11}$
	$2.6 \times 10^{-3}$	0.61	1.14	0.60	7.2	$2.2 \times 10^{-11}$
Anionic SDS	$1.2 \times 10^{-3}$	0.56	1.25	0.62	8.6	$1.2 \times 10^{-10}$
	$1.6 \times 10^{-3}$	0.59	1.18	0.59	7.8	$9.2 \times 10^{-11}$
	$2.0 \times 10^{-3}$	0.62	1.10	0.57	7.0	$9.4 \times 10^{-11}$
SLS	$1.2 \times 10^{-3}$	0.56	1.25	0.64	8.6	$1.4 \times 10^{-10}$
	$1.6 \times 10^{-3}$	0.60	1.08	0.61	7.9	$1.2 \times 10^{-11}$
	$2.0 \times 10^{-3}$	0.64	1.04	0.58	7.5	$8.4 \times 10^{-11}$
Non-ionic Tween-20	$2.0 \times 10^{-3}$	0.56	1.25	0.62	8.67	$1.2 \times 10^{-10}$
	$2.4 \times 10^{-3}$	0.58	1.09	0.60	8.2	$8.8 \times 10^{-11}$
	$2.8 \times 10^{-3}$	0.62	1.04	0.57	7.7	$8.4 \times 10^{-11}$
Triton X-100	$2.0 \times 10^{-3}$	0.56	1.25	0.64	8.6	$1.2 \times 10^{-10}$
	$2.4 \times 10^{-3}$	0.61	1.16	0.62	8.1	$8.4 \times 10^{-11}$
	$2.8 \times 10^{-3}$	0.65	1.06	0.60	7.5	$8.6 \times 10^{-11}$

TABLE 2—EFFECT OF INCREASING CONCENTRATIONS OF IONIC AND NON-IONIC SURFACTANTS ON THE KINETICS OF IRREVERSIBLE ELECTRODE PROCESS OF ARYLAZOPYRAZOLE AT pH 6.2

Surfactants	(Surfactant) %	$-E_{1/2}$ V	$i_d$ $\mu A$	$\alpha n_a$	$D_0^{1/2} \times 10^4$ $cm^2/sec$	$k^0_{t,h}$ $cm/sec$
Cationic CTAB	$1.0 \times 10^{-3}$	0.62	1.10	0.72	9.2	$1.6 \times 10^{-11}$
	$1.6 \times 10^{-3}$	0.63	1.08	0.69	8.8	$9.2 \times 10^{-12}$
	$2.2 \times 10^{-3}$	0.64	1.04	0.65	8.2	$8.0 \times 10^{-12}$
OPB	$1.4 \times 10^{-3}$	0.62	1.10	0.72	9.2	$1.6 \times 10^{-11}$
	$2.0 \times 10^{-3}$	0.63	1.06	0.69	9.0	$8.4 \times 10^{-12}$
	$2.6 \times 10^{-3}$	0.65	1.00	0.65	8.4	$3.4 \times 10^{-12}$
Anionic SDS	$1.2 \times 10^{-3}$	0.62	1.08	0.70	9.2	$1.6 \times 10^{-11}$
	$1.6 \times 10^{-3}$	0.64	1.04	0.68	8.4	$5.6 \times 10^{-12}$
	$2.0 \times 10^{-3}$	0.66	1.00	0.65	7.9	$1.0 \times 10^{-12}$
SLS	$1.2 \times 10^{-3}$	0.62	1.10	0.72	9.2	$1.8 \times 10^{-11}$
	$1.6 \times 10^{-3}$	0.66	1.06	0.70	8.8	$3.4 \times 10^{-12}$
	$2.0 \times 10^{-3}$	0.68	1.01	0.68	8.4	$9.3 \times 10^{-12}$
Non-ionic Tween-20	$2.0 \times 10^{-3}$	0.62	1.10	0.72	9.2	$1.6 \times 10^{-11}$
	$2.4 \times 10^{-3}$	0.66	1.06	0.69	8.9	$6.2 \times 10^{-12}$
	$2.8 \times 10^{-3}$	0.70	1.00	0.66	8.4	$9.8 \times 10^{-12}$
Triton X-100	$2.0 \times 10^{-3}$	0.62	1.10	0.72	9.2	$1.6 \times 10^{-11}$
	$2.4 \times 10^{-3}$	0.66	1.06	0.70	8.7	$5.2 \times 10^{-12}$
	$2.8 \times 10^{-3}$	0.70	1.00	0.65	8.2	$9.4 \times 10^{-12}$

\* Concentration of surfactant just sufficient to eliminate the maxima.

CTAB—Cetyltrimethylammonium bromide.

OPB—Octylpyridinium bromide.

SDS—Sodium dodecyl sulphate.

SLS—Sodium lauryl sulphate.

The transfer coefficient,  $\alpha$ , signifies the fraction of the applied voltage which favours the cathodic reduction. A decrease in its value implies that transfer of electrons is made increasingly

difficult. In other words, the electrode reaction of arylazopyrazole and arylazopyrimidine is rendered increasingly irreversible as surfactant is increased beyond the concentration just sufficient to eliminate

the maxima. The decrease in the value of  $K_{1,2}^0$  (Tables 1 and 2) with increasing surfactant concentration lends support to this conclusion.

#### References

1. W. U. MALIK, R. N. GOYAL and R. JAIN, *J. Electroanal. Chem.*, 1978, **87**, 129.
2. R. N. GOYAL, R. JAIN and S. TYAGI, *J. Indian Chem. Soc.*, 1978, **53**, 1960.
3. B. PILLMAN and A. PILLMAN, "Quantum Biochemistry", John Wiley & Sons, New York, 1968.
4. H. G. GARG and R. A. SHARMA, *J. Med. Chem.*, 1969, **12**, 112.
5. H. G. GARG, *J. Indian Chem. Soc.*, 1961, **38**, 850.
6. T. DEVERIES and J. L. KROON, *J. Amer. Chem. Soc.*, 1958, **75**, 2484.
7. J. KOUTECKY, *Chem. Listy*, 1958, **47**, 323.
8. S. S. SHARMA, S. K. JHA and M. SINGH, *Z. Naturforsch.*, 1977, **32b**, 416.
9. S. S. SHARMA, S. K. JHA and M. SINGH, *Indian J. Chem.*, 1977, **15A**, 742.

# 4-(2-Pyridylazo) Resorcinol, A Sensitive Amperometric Reagent for Ultramicro Determination of $\text{Pr}^{3+}$ and $\text{Nd}^{3+}$

S. C. LAVALLE and K. S. PITRE

Department of Chemistry, University of Sagar, Sagar-470 003, M.P.

Manuscript received 19 July 1981, revised 15 February 1982, accepted 1 May 1982

4-(2-Pyridylazo) resorcinol has been employed successfully as an amperometric reagent for the precise determination of  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$ . The reagent's sensitivity is high. 0.1409 mg of  $\text{Pr}^{3+}$  and 0.1442 mg of  $\text{Nd}^{3+}$  could be detected successfully in 10 ml solution of each ion with an error of less than  $\pm 0.8\%$ . The titrations have been performed at  $\text{pH } 6.1 \pm 0.02$  and an ionic strength of 0.5 M [KCl]. The molar ratio of metal : PAR complexation is found to be 1 : 2. Titrations are not hampered by the presence of fairly large amounts of  $\text{K}^+$ ,  $\text{Na}^+$ ,  $\text{NH}_4^+$ ,  $\text{Mg}^{2+}$ ,  $\text{Ti}^4$ ,  $\text{Ca}^{2+}$ ,  $\text{Mo}^{6+}$ ,  $\text{Cl}^-$ ,  $\text{ClO}_4^-$ ,  $\text{CH}_3\text{COO}^-$ ,  $\text{NO}_3^-$  and  $\text{SO}_4^{2-}$  ions. Experimental and calculated statistical data support the utility of the method

AMONG the various heterocyclic azo dyes<sup>1</sup> PAN, PAR and TAR have been satisfactorily used for the spectrophotometric<sup>2-4</sup> determination of rare earths. 4-(2-Pyridylazo) resorcinol [abbreviated PAR] has also been used for the determination<sup>5-7</sup> of  $\text{V}^{5+}$ ,  $\text{Ti}^{4+}$ ,  $\text{In}^{3+}$ ,  $\text{Mn}^{2+}$  and various other ions. The spectrophotometric method is not suitable when precipitation occurs, nor it can be used at the close proximity of the wave length of absorption of complex and the ligand. It may predict wrong stoichiometric ratio of metal : ligand. Keeping this in mind an attempt has been made to estimate  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$  amperometrically using PAR as a reagent. The present paper deals with the results of amperometric titration of these metal ions with PAR, using d.m.e. as indicator electrode. The method is applicable in presence of various other ions.

## Experimental

The chemicals used were of AnalaR or extrapure quality.  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$  solutions were prepared and standardized<sup>11</sup>. Solution of 4-(2-pyridylazo) resorcinol was prepared by dissolving the requisite quantity of monosodium salt of the reagent (E. Merck) and was standardized potentiometrically<sup>8</sup> in 1 : 1 v/v dioxane-water by standard  $\text{Pr}^{3+}$  solution. Ionic strength (0.5 M) was adjusted with potassium chloride solution. Dil. hydrochloric acid and sodium hydroxide solutions were used to adjust the pH at  $6.1 \pm 0.02$ .

Amperometric titrations were made on a manually operated polarograph with multiflex galvanometer (sens.  $8.10 \times 10^{-8}$  amp/div), using d.m.e. as indicator electrode and S.C.E. as reference electrode. The capillary used for d.m.e. had a m value of 2.3733 mg/sec at a drop time 3.0 sec in air free 1 M potassium chloride solution at 41 cm effective height of mercury column ( $m^{3/2}/s^{1/2} = 2.136 \text{ mg}^{3/2}/s^{1/2}$ ). An Elico digital pH meter

(model LI-120) was used for measuring pH of the test solutions.

**Voltammograms of 4-(2-pyridylazo) resorcinol :** The voltammetric studies were carried out on C.I.C., Baroda (India) pen recording polarograph. 4-(2-Pyridylazo) resorcinol gives a well defined polarographic wave at pH 6.1 (Fig. 1-A). The polarograms of PAR at different concentrations were recorded and it was found that diffusion current was proportional to the concentration of PAR.




Fig. 1. A : Polarogram of 1 mM PAR in 0.5 M KCl at pH 6.1  
B : Polarogram of 2 mM metal ( $\text{Pr}^{3+}$  or  $\text{Nd}^{3+}$ ) in 0.5 M KCl at pH 6.1

**Procedure of amperometric titrations :** For titrations, sets of solutions containing known amount of  $\text{Pr}^{3+}$  or  $\text{Nd}^{3+}$  in 0.5 M KCl as supporting electrolyte (in 10 ml volume) were prepared and the pH of the solutions were adjusted at  $6.1 \pm 0.02$ . The metal solution was taken into the

TABLE 1—AMPEROMETRIC TITRATION OF  $\text{Pr}^{3+}$  AND  $\text{Nd}^{3+}$  WITH PARPlateau potential =  $-0.85$  V vs S.C.E.;  $\Delta = 0.5$ ;  $\text{pH} = 6.1 \pm 0.02$ 

Sl No.	Approximate concentration (M)	Amount of $\text{Pr}^{3+}$ Taken (mg)	Found* (mg)	% Error	Coefficient of variation*	Amount of $\text{Nd}^{3+}$ Taken (mg)	Found* (mg)	% Error	Coefficient of variation*
1.	$1 \times 10^{-4}$	0.1409	0.1400	-0.63	0.89	0.1442	0.1431	-0.76	0.82
2.	$2 \times 10^{-4}$	0.2818	0.2824	+0.56	0.85	0.2882	0.2868	-0.48	0.86
3.	$4 \times 10^{-4}$	0.5636	0.5608	-0.49	0.86	0.5768	0.5798	+0.52	0.70
4.	$6 \times 10^{-4}$	0.8454	0.8404	-0.59	0.64	0.8682	0.8628	-0.27	0.52
5.	$8 \times 10^{-4}$	1.1272	1.1398	+0.23	0.81	1.1586	1.1584	+0.41	0.66
6.	$1 \times 10^{-3}$	1.4091	1.4048	-0.34	0.70	1.4424	1.4424	+0.48	0.86
7.	$2 \times 10^{-3}$	2.8182	2.8006	-0.62	0.86	2.8648	2.8764	-0.29	0.41
8.	$3 \times 10^{-3}$	4.2273	4.2456	+0.43	0.41	4.3272	4.3886	+0.96	0.47
9.	$4 \times 10^{-3}$	5.6364	5.6818	-0.45	0.82	5.7686	5.7890	-0.65	0.70
10.	$5 \times 10^{-3}$	7.0455	7.0942	-0.69	0.57	7.2120	7.1815	-0.42	0.64

\* The values calculated from replicate set of observations for each concentration.

titration cell. The plateau potential [at which  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$  do not give any diffusion current (Fig. 1-B)] on the wave of PAR i.e.,  $-0.85$  V vs S.C.E. was applied and a standard solution of PAR ( $\text{pH} = 6.1 \pm 0.02$ ) was added drop by drop from a 1 cm<sup>3</sup> semi micro burette and the current was noted. On plotting galvanometer readings after necessary volume corrections\* against titrant volumes, reversed L shaped curve was obtained (Fig. 2). The end point indicated a metal to PAR ratio of 1 : 2 which is in good agreement with the spectrophotometric results observed by Munshi and Dey<sup>2</sup>. Similar results were observed by using PAR as titrate and  $\text{Pr}^{3+}$  or  $\text{Nd}^{3+}$  as titrant under the identical experimental conditions, but an L shaped curve was obtained in this case.




Fig. 2. Amperometric titration curve of  $\text{Pr}^{3+}$  solution with PAR. Concentration of  $\text{Pr}^{3+}$  solution taken in cell =  $0.001$  M. Concentration of PAR solution =  $0.002$  M/ml.  $V$  = Volume of  $\text{Pr}^{3+}$  solution taken in cell i.e. 10 ml.  $v$  = Volume of PAR solution added.

**Effect of diverse ions:** The amperometric titrations of the titled metal ions are not in any way hampered by the presence of fairly large amounts

of foreign ions, viz., alkali and alkaline earth metal ions,  $\text{NH}_4^+$ ,  $\text{Ti}^+$ ,  $\text{Cr}^{3+}$ ,  $\text{Mo}^{3+}$ ,  $\text{Cl}^-$ ,  $\text{ClO}_4^-$ ,  $\text{NO}_3^-$ ,  $\text{SO}_4^{2-}$ ,  $\text{CH}_3\text{COO}^-$  etc. However, it is found that small amounts of  $\text{CO}_3^{2-}$ ,  $\text{PO}_4^{3-}$ ,  $\text{Cd}^{2+}$ ,  $\text{Bi}^{3+}$ ,  $\text{Pb}^{2+}$ ,  $\text{Sb}^{3+}$ ,  $\text{Fe}^{3+}$ ,  $\text{Ni}^{2+}$ ,  $\text{Cu}^{2+}$  and  $\text{Zn}^{2+}$  interfere seriously in this titrimetric method.

### Results and Discussion

The results of amperometric titrations of the titled metal ions are shown in Table 1. The results indicate that PAR is a sensitive reagent for ultramicro determination of  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$ . The minimum amount (nearly 0.14 mg) of each of the said metal ions can be estimated successfully with a practical error of less than  $\pm 0.8\%$ . In our earlier communications, we reported that  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$  could be estimated upto 0.70 mg using cupferron<sup>10</sup>, ARS<sup>11</sup> and XO<sup>12</sup> as amperometric reagents. The present results clearly show the sensitivity of PAR over these reagents. The low detection limit of PAR is nearly 5 times to that observed with the other three reagents. The repeated experimental observations and finally calculated statistical values like coefficients of variation show the accuracy and precision of the method. It is found that the value of coefficient of variation never exceeded 0.9.

### Acknowledgement

One of the authors (S. C. L.) is grateful to the U. G. C., New Delhi for the award of a Teacher Fellowship. Thanks of the authors are also due to the Head of the Department of Chemistry, University of Saugar, Saugar for laboratory facilities.

### References

1. H. A. FLASCHKA and A. J. BERNARD, JR., "Chelates in Analytical Chemistry", Marcel Dekker, Inc., New York, 1979, Vol. 4.
2. K. N. MUNSHI and A. K. DEY, *Anal. Chem.*, 1964, 36, 2008.
3. H. K. LIN, K. I. CHEN and Y. F. CHEN, *Hua Hsueh Tung-Pao*, 1966, 365.
4. I. M. RAO and D. SATYANARAYANA, *J. Indian Chem. Soc.*, 1980, 57, 1182.

# LAVALLE & PITRE : 4-(2-PYRIDYLAZO) RESORCINOL, A SENSITIVE AMPEROMETRIC REAGENT

5. M. SROGI and G. DJORDJEVIC, *Anal. Chim. Acta*, 1971, 57, 801.
6. JU. LUTZ, "Handbook of Analytical Chemistry", Mir Publishers, Moscow, 1975, p. 240.
7. S. O. LAVALLE and K. S. PITRE, *Revus Roumaine De Chimie*, 1981 (in press).
8. CHANG TAO-HSU, LIN AI-LING and YANGSU-ING, *Hua Hsueh Tung. Pa.*, 1971, 111.
9. J. T. STOECK, "Amperometric Titrations", R. E. Krieger Pub. Co., Huntington, New York, 1975, p. 7.
10. K. S. PITRE and S. O. LAVALLE, *J. Inst. of Chemist (India)*, 1981, 53, 211.
11. S. O. LAVALLE and K. S. PITRE, *J. Electrochem. Soc., India*, 1981, 30, 898.
12. S. O. LAVALLE and K. S. PITRE, *Madhya Bharat, J. Sag. Univ.*, 1978-80, 26-28, 49.

# Structure of Faceted Naphthalene-Benzonic Acid Eutectic

P. S. BASSI\* and N. K. SHARMA\*\*

Department of Chemistry,

and

K. N. GOSWAMI

Department of Physics, Jammu University, Jammu-180 001

Manuscript received 29 January 1979, revised 11 March 1982, accepted 7 June 1982

Microstructure studies of naphthalene-benzoic acid eutectic have shown it to be a faceted-faceted structure in agreement with the recent classification of the eutectics. X-ray studies of the eutectic have shown that certain interplanar distances and the intensities of the reflections in the solidified eutectic differ markedly from those of the pure components, indicating a preferential orientation between the components in the eutectic.

ACCORDING to the classification given by Jackson and Hunt<sup>1</sup>, micromorphologies depend on the entropy of fusion of the pure components; the high entropy constituents form an eutectic having irregular (faceted) growth from the melt. Little has been studied about such faceted eutectics<sup>2</sup> and hence naphthalene-benzoic acid system, in which both the components have a high entropy of fusion, has been chosen for study. Growth kinetics and the structure of the liquid eutectics have also been studied recently<sup>3</sup>. Hogan<sup>4</sup> showed a unique crystallographic orientation relationship between constituent phases and their mating planes. Perfect lamellar grains have been found in lamellar Sn - Cd eutectic by Gruzleski and Winegard<sup>5</sup> but in a number of systems, the eutectic grains do not exhibit a fixed crystal orientation with respect to external lines of forces. Recently, it has been shown that certain frequencies in the ir spectra of naphthalene-benzoic acid eutectic are restricted, showing thereby that there is a specific orientation between the constituents with respect to each other in this composite material<sup>6</sup>. In the present investigation, microscopic, X-ray and D.S.C. studies of naphthalene-benzoic acid eutectic has been made and it has been further established that there is orientation of some of the planes of the new composite formed.

## Experimental

Naphthalene (U.S.S.R.) was purified by sublimation and benzoic acid (A.R., B.D.H., London) was taken as such. Purity of naphthalene (m.p. 80.30°) and benzoic acid was checked by the determination of their melting points. Accurately weighed naphthalene and benzoic acid were taken in a tube which was then sealed to avoid evaporation. The material in the tube was melted and then suddenly chilled in ice cold water. This process of melting and chilling was repeated 4-5 times. The tube was then broken and the solid mixture thus formed was

powdered using agate mortar and pestle. The phase diagram of naphthalene-benzoic acid system was determined by thaw point method. Eutectic was formed at 0.667 mole fraction of naphthalene with its eutectic point at 69.1°. The accuracy in determining the eutectic point was  $\pm 0.1^\circ$ .

A small amount of the eutectic or that of the pure components was taken on a clean glass slide and carefully melted. A cover slip was then glided over it. These glass slides were then observed under microscope. The heat of fusion of the eutectic and the pure components were determined using differential scanning calorimeter, DSC IB, Perkin Elmer, USA in N<sub>2</sub> atmosphere. These were found to be 32.2, 33.4 and 29.4 cal/g for naphthalene, benzoic acid and the eutectic, respectively.

The X-ray analysis of the eutectic and the pure components was carried out by powder method using Debye Scherrer camera with nickel filtered copper (K $\alpha$ ) radiation. The intensities of X-ray lines were determined by visual comparison of the lines with the standard intensity scale which had been prepared previously.

## Results and Discussion

(a) *Microscopic and D.S.C. studies*: Hunt and Jackson<sup>1</sup> argued that the type of growth of an eutectic depends upon a factor  $\alpha$ . Non-faceted growth occurs when  $\alpha < 2$ , whereas faceted growth occurs when  $\alpha > 2$ .

$$\alpha = \xi \frac{\Delta S_f}{R}$$

where  $\Delta S_f/R$  is the entropy of fusion in dimensionless units and  $\xi$  is a crystallographic factor depending upon the geometry of the molecule and is less than or almost equal to one. Benzoic acid and naphthalene have  $\Delta S_f/R$  values of 5.25 and 6.45, respectively ( $\Delta S_f$  values were calculated from the heat of fusion values at the melting points<sup>7</sup>).

\* Department of Chemistry, Guru Nanak Dev University, Amritsar-148 005.

\*\* Author for correspondence.



Hence growth of naphthalene and benzoic acid should be faceted. The values of heat of fusion obtained from D.S.C. agree with the theoretical values within the error range. Experimental values of  $\Delta S_f/R$  were found to be 5.91, 5.17 and 5.49 for naphthalene, benzoic acid and the eutectic, respectively. Higher values of  $\Delta S_f/R$  indicate that the eutectic is faceted-faceted type. When the growth of the eutectic was observed in the glass slide under a microscope with suitable magnification, it was seen that the growth was irregular (faceted) in agreement with the recent classification of the eutectics<sup>7</sup>. Not much literature is available on the studies of faceted-faceted eutectics.

(b) *X-ray studies*: From X-ray photographs of the eutectic, naphthalene and benzoic acid, it is clear that there is a marked difference in the interplanar distances and the relative intensities of the composite material and the individual components. From the study of X-ray photographs, the following are evident :

1. A number of X-ray reflections on the X-ray photographs indicate that the eutectic is crystalline in nature.
2. There is a rapid fall in the value of intensity of reflections as a function of the diffraction angle  $\frac{\sin \theta}{\lambda}$ .

From the study of Table 1, the following characteristic features have been observed. In eutectic, the reflections with interplanar spacing  $d = 3.65, 3.42, 2.93, 2.52$  and  $2.27 \text{ \AA}$  have relatively stronger intensities as compared to the similar lines found in benzoic acid and naphthalene. From the above observation, it is inferred that the X-ray diffraction pattern of the eutectic is different from that of the individual components constituting it. In other words, the X-ray photographs of the pure components cannot be exactly superimposed on the photographs of the eutectic composite. Some of the reflections as mentioned above show deviations in the intensity and in interplanar spacings.

It can be inferred from these observations that the eutectic is not only a pure mechanical mixture of two components, but there is orientation of some atomic planes in the composite. Such an observation has also been made by ir studies<sup>8</sup>.

The rapid fall in the intensity of reflections can be attributed to various reasons. There may be some disorder in the location of atoms forming the composite. It can also be due to thermal vibration of atoms making the composite. It is the thermal activation of the interaction of the two components which is responsible for the formation of the eutectic. As a confirmation of this effect it is found that reflections are slightly diffused in intensity.

TABLE 1

Naphthalene		Eutectic		Benzoic acid	
d/Å	R.I.	d/Å	R.I.	d/Å	R.I.
—	—	10.84	s	10.90	s
7.98	m	7.98	w	—	—
5.78	w	—	—	—	—
5.62	w	—	—	—	—
—	—	5.42	w	5.42	m
—	—	5.12	vs	5.12	vs
4.65	m	—	—	—	—
—	—	4.68	w	4.68	mw
4.50	vs	4.50	w	—	—
4.12	m	4.12	w	—	—
4.11	w	4.10	w	—	—
3.70	vw	3.71	s	3.71	s
3.64	vw	3.65	s	—	—
—	—	—	—	3.62	w
—	—	—	—	3.50	w
3.51	vw	—	—	—	—
3.48	w	3.48	w	—	—
—	—	3.42	vs	3.42	s
3.38	mw	3.38	m	—	—
3.21	w	3.19	s	3.19	m
3.00	w	2.99	w	—	—
—	—	2.93	s	2.95	mw
2.80	vw	—	—	—	—
2.76	vw	—	—	—	—
—	—	—	—	2.72	vw
—	—	2.56	vw	2.56	vw
2.55	vw	2.52	mw	—	—
2.48	vw	2.48	vw	—	—
—	—	2.42	vw	—	—
2.38	vw	2.27	mw	—	—
—	—	2.09	mw	2.09	vw
1.84	w	1.90	mw	1.91	vw
1.82	w	—	—	—	—
1.81	w	—	—	—	—
—	—	1.61	vw	—	—
—	—	1.68	vw	—	—

The classification of the relative intensity of lines is based on the following criteria: vs=80-100, s=60-80, m=40-60, mw=20-40, w=10-20 and vw=0-10

It can thus be concluded that X-ray studies indicate a sort of preferential ordering of atoms making an eutectic.

#### References

1. K. A. JACKSON and J. D. HUNT, *Acta Metallurgica*, 1966, 13, 1213.
2. N. B. SINGH and NARSINGH BHADUR SINGH, *J. Org. Growth*, 1975, 78, 367.
3. P. S. BASU and G. P. SACHDEV, *Indian J. Chem.*, 1974, 12, 727.
4. L. M. HOGAN, R. W. KRAFT and F. D. LEMKE, in "Advances in Material Research", (Ed.) H. HERMANN, Wiley Interscience, New York, 1971, Vol. 5.
5. J. E. GRUZYLSKI and W. C. WINEGARD, *J. Inst. Metals*, 1968, 96, 301.
6. P. S. BASU and N. K. SHARMA, *Indian J. Chem.*, 1976, 14A, 692.
7. J. D. HUNT and K. A. JACKSON, *Trans. Metallurgical Soc. of AIME*, 1966, 236, 848.
8. "Hand Book of Chemistry and Physics", (Ed.) C. HODGMAN, The Chemical Rubber Publishing Co., Cleveland, 1969, p. 2812.

# Transformations of $\beta$ -Pinene over Platinum-Alumina Catalyst. Part—I : Influence of Contact Time, Temperature and Platinum Concentration

P. MATHUR, V. KRISHNASAMY\* and K. CHANDRASEKHARAN

Department of Chemical Engineering, A. C. College of Technology, Madras-600 036

Manuscript received 27 April 1961, revised 9 November 1961, accepted 23 May 1962

The catalytic transformations of  $\beta$ -pinene have been investigated over platinum-alumina dual function catalyst containing varying amounts of platinum in the temperature range 200 to 400°. In addition, the influence of contact time on the rate and distribution of products has been studied over 0.6% platinum-alumina at 300°. The performance of the catalyst remains unchanged by its pretreatment either in hydrogen or in oxygen prior to catalytic run. The dehydrogenation activity of the catalyst increases upto 350° beyond which it declines.

$\beta$ -Pinene isomerizes via two parallel paths, one giving rise to bi- and tricyclic products such as camphene,  $\alpha$ -pinene, bornylene and tricyclene and the other giving monocyclic compounds such as dipentene, terpinolene,  $\alpha$ - and  $\gamma$ -terpinenes. The terpinenes have been identified as the immediate precursors of cymene. Apart from this, the terpinenes undergo disproportionation to menthene and menthane. At higher values of contact time and temperature, menthene and menthane get dehydrogenated to cymene.

Increase of platinum concentration inhibits both isomerization and dehydrogenation activities of the catalyst. This decrease is ascribed to reduction of the acid sites and enhancement of platinum crystallite size. Disproportionation reaction is favoured by strong acid sites and small well dispersed platinum crystallites.

$\beta$ -Pinene is a bicyclic mono-olefinic monoterpene present together with  $\alpha$ -pinene in the majority of essential oils derived from coniferae<sup>1</sup>. The first quality Indian turpentine oil contains about 10%  $\beta$ -pinene, 40%  $\alpha$ -pinene and 50% 3-carene<sup>2</sup>. These hydrocarbons undergo skeletal isomerization initially due to the cleavage of cyclobutane and cyclopropane rings followed by dehydrogenation and disproportionation reactions over dual function catalysts such as chromia and chromia-alumina catalysts<sup>3-5</sup>.

Platinum-alumina, another important bifunctional catalyst, is being increasingly employed in reforming processes as it is found to have enhanced sustained activity and high selectivity. Hence platinum-alumina catalyst was chosen for this work. Further, a survey of literature reveals that a systematic investigation of the transformation of  $\beta$ -pinene over this catalyst in the vapour phase has not so far been reported. The influence of contact time, platinum concentration and temperature on the rate and distribution of products of  $\beta$ -pinene was therefore studied and the results are presented in this paper.

## Experimental

### Preparation of catalysts :

**Alumina (catalyst A) :** Alumina was prepared according to the method of Pines *et al*<sup>6</sup>.

**Platinum-alumina (catalysts B, C, D and E) :** The catalysts B, C, D and E were prepared by adding calculated volumes of chloroplatinic acid in water to four weighed samples of alumina to give respectively 0.3, 0.6, 0.9 and 1.4% platinum by weight (confirmed by spectrophotometric analysis<sup>7</sup>). The slurry was stirred for 3 hr and dried at 120° for 24 hr. The temperature was raised slowly while passing pure dry hydrogen to reach 500° in a period of 2 hr and maintained at this for 8 hr. The activated material was powdered and pelletized to 4 × 4 mm size pellets.

TABLE I—NOMENCLATURE OF THE CATALYST

Catalyst	Composition
A	Alumina (from aluminium isopropoxide)
B	Platinum-alumina (0.3% Pt)
C	Platinum-alumina (0.6% Pt)
D	Platinum-alumina (0.9% Pt)
E	Platinum-alumina (1.4% Pt)

**$\beta$ -Pinene :** Since  $\beta$ -pinene (b.p. 165°) constitutes only 10% of first quality Indian turpentine oil and also it boils very close to 3-carene (b.p. 169°), the separation of this component by fractional distillation was not successful. Hence it was obtained from "Fluka" and its purity was checked by gas chromatography.

**Apparatus and procedure:** Initial experiments conducted both over oxidised and reduced catalysts did not show any significant variation in the product distribution as indicated in Table 3. Subsequent runs were, therefore, conducted over oxidised catalyst. Other details of the apparatus and experimental procedure have been described in the earlier publications<sup>8-10</sup>. The evolution of molecular hydrogen during this investigation was small due to side reactions. Hence the gaseous products were not considered for computing the *p*-cymene yield.

**Surface area:** The surface area measurements of catalysts C, D and E were made according to BET method, by adsorption of nitrogen at liquid nitrogen temperature. The experimental procedure and calculations were the same as described by Emmett<sup>11</sup>. The values are found to be 121.1, 171.7 and 230.7 m<sup>2</sup>/g respectively. The platinum metal area for the above three catalysts are found to be 30.5, 48.4 and 58.5 m<sup>2</sup>/g of catalyst respectively by carbon monoxide adsorption, according to procedure described by Dorling<sup>12</sup>.

## Results and Discussion

(a) **Contact time:** In order to determine the transformation sequence of  $\beta$ -pinene, the influence of contact time W/F (where W is the weight of catalyst and F is the weight of  $\beta$ -pinene passed per hr over the catalyst) on the product distribution has been studied at 300° over catalyst C (0.6% Pt) and the results are plotted in Fig. 1, while the overall conversion is summarised in Table 2. The

distribution of products varied to different extents with increasing contact time (Fig. 1). The various compounds formed are identified to be  $\alpha$ -pinene, dipentene, terpinolene,  $\alpha$ - and  $\gamma$ -terpinenes, camphene, tricyclene, bornylene, 1-, 3- and 4(8)-*p*-menthenes, *cis*- and *trans*-menthanes and *p*-cymene.

TABLE 2—EFFECT OF CONTACT TIME, PLATINUM CONCENTRATION AND TEMPERATURE ON THE OVERALL CONVERSION OF  $\beta$ -PINENE

Contact Time (hr)	% conversion of $\beta$ -pinene	% platinum concentration	% conversion of $\beta$ -pinene	Temperature (°C)	% conversion of $\beta$ -pinene
0.12	84.0	0.8	98.7	250	98.3
0.4	92.0	0.6	98.8	300	98.8
0.79	98.8	0.9	98.9	350	98.8
1.2	99.0	1.4	98.6	400	97.8
1.6	99.5				

The concentration of individual menthadienes, menthenes and menthanes were too small and varied widely with contact time; hence they were grouped as menthadienes, menthenes and menthanes. The concentration of *p*-cymene continues to increase with increase in contact time. It can be inferred from this that *p*-cymene is the final product in the transformation of  $\beta$ -pinene and the rest are only intermediates, though formed through different routes (Scheme) and exhibit their maxima at different contact times. Further, it has been observed experimentally that *p*-cymene undergoes neither side chain dehydrogenation nor ring hydrogenation under the experimental conditions. This lends support to the above view regarding the nature of *p*-cymene.

Bornylene and tricyclene register an increase upto 1.2 hr; thereafter their concentrations remain almost constant. This may be due to the establishment of dynamic equilibrium among tricyclene, bornylene and camphene. Camphene formed by the skeletal isomerization of  $\alpha$ - and  $\beta$ -pinenes suffers further skeletal isomerization to monocyclic menthadienes at higher contact time and at higher temperature.

The concentrations of  $\alpha$ - and  $\gamma$ -terpinenes were less than the concentrations of dipentene and terpinolene at all contact times studied (Fig. 2). The reason for the low concentration of terpinenes could be the faster rate with which they undergo dehydrogenation as soon as they are formed from dipentene and terpinolene. This observation reveals that terpinenes are the immediate precursors of *p*-cymene.

Menthanes also undergo dehydrogenation like menthadienes but this occurs at higher contact time. Thus the maxima for menthadienes and menthanes occur around 0.12 and 0.79 hr respectively. On the basis of their dehydrogenation to cymenes, menthanes cannot be designated as intermediates like menthadienes since they are formed by disproportionation of menthadienes




Fig. 1. Effect of contact time on product distribution.






Fig. 1. Effect of contact time on the percentage composition of menthadienes.

which is only a side reaction, not forming part of the dehydrogenation sequence of  $\beta$ -pinene:



However, they can be described as 'pseudo intermediates' which seems to be precise nomenclature on account of their increasing concentration to a maximum followed by a decrease.

Menthenes can either be formed by partial hydrogenation of menthadienes or by partial dehydrogenation of menthanes or by disproportionation of menthadienes. The first possibility is highly unlikely under this condition. Pines *et al.*<sup>2</sup> reported that dehydrogenation of menthanes to cymenes over platinum-alumina occurred without the intermediate formation of menthenes and menthadienes. Menthenes are therefore considered to be the disproportionation products of menthadienes as shown below:

drogenation of menthanes or by disproportionation of menthadienes. The first possibility is highly unlikely under this condition. Pines *et al.*<sup>2</sup> reported that dehydrogenation of menthanes to cymenes over platinum-alumina occurred without the intermediate formation of menthenes and menthadienes. Menthenes are therefore considered to be the disproportionation products of menthadienes as shown below:



From these observations, the sequence of reactions pertaining to the formation of various products from  $\beta$ -pinene is shown in the Scheme.

(b) *Platinum concentration*: In Table 2 and in Fig. 3 are given the influence of platinum concentrations on the overall conversion of  $\beta$ -pinene and the distribution of products respectively at 300° and at a contact time of 0.79 hr. There is no variation in the overall conversion of  $\beta$ -pinene with increasing platinum concentration as it has reacted almost completely even at 0.3% platinum concentration, showing that  $\beta$ -pinene is highly reactive. On the other hand the various species present in the catalysate are influenced to varying degrees by increased platinum additions. For instance, the proportions of  $\alpha$ -pinene and camphene increase while those of tricyclene and menthene decrease. *p*-Cymene and menthanes, after registering their maxima over 0.9% and 0.6% platinum respectively, begin to fall. Bornylene increases to a maximum whereas menthadienes decrease to a minimum, thereafter the former and the latter register decreasing and increasing trends respectively (Fig. 3).

$\alpha$ -Pinene and camphene, formed initially from  $\beta$ -pinene, may not be able to undergo further




Fig. 3. Effect of platinum concentration on product distribution.

skeletal isomerization due to decrease of the acidic sites of alumina by deposition of platinum metal and hence their concentration in the catalysate increases. Consequently the concentrations of tricyclene, bornylene, menthenes and menthanes in the catalysate decrease.

Among the transition metals, platinum, being the most effective dehydrogenating element, is expected to show greater activity for dehydrogenation reaction when its content in the catalyst increases. But actually a decrease in its activity is observed. Platinum metal area of catalysts C, D and E are 30.5, 48.4 and 58.5 m<sup>2</sup>/g of catalyst (and not per gram of platinum). Though the surface area registers an increasing trend, the rate of increase registers a fall in magnitude with increasing platinum concentrations. This is possibly due to a

tendency of the platinum crystallites to form clusters at higher concentration. This is reflected by corresponding decrease in the dehydrogenation activity and the increase in concentration of menthadienes. The decrease in the menthane concentration indicates that disproportionation reactions are favoured by both strong acid sites and small well-dispersed metal crystallites. Since at higher platinum concentrations these types of essential sites namely strong acid sites and well dispersed metal sites disappear, a decrease in the concentration of menthanes occurs.

(c) *Temperature*: The effect of temperature on the total conversion of  $\beta$ -pinene and on the distribution of products has been studied over catalyst C at 0.79 hr and the results are presented in Table 2 and Fig. 4, respectively. The catalyst has developed its maximum activity even at 250° with regard to the overall conversion of  $\beta$ -pinene. Temperature beyond 350° has no beneficial effect.




Fig. 4. Effect of temperature on product distribution.

TABLE 2—EFFECT OF CATALYST PRETREATMENT ON THE PRODUCT DISTRIBUTION: D<sup>a</sup>=0.9% Pt-Al<sub>2</sub>O<sub>3</sub>, REDUCED; D<sup>b</sup>=0.9% Pt-Al<sub>2</sub>O<sub>3</sub>, NOT REDUCED AFTER REGENERATION; E<sup>a</sup>=1.4% Pt-Al<sub>2</sub>O<sub>3</sub>, REDUCED AFTER REGENERATION; E<sup>b</sup>=1.4% Pt-Al<sub>2</sub>O<sub>3</sub>, NOT REDUCED AFTER REGENERATION

Sl. No.	Temp. °C	Contact time (hr)	Catalyst	$\beta$ -Pinene reacted	$\alpha$ -Pinene	Camphene	Menthadienes	Cymene	Tricyclene	Bornylene	Menthene	Menthane	Carbon estimated
1	250	0.79	D <sup>a</sup>	98.8	24.6	19.0	1.6	34.7	5.0	3.8	5.0	6.8	0.66
2			D <sup>b</sup>	98.8	20.4	21.5	4.8	34.6	5.0	3.5	4.0	6.3	0.6
1	350	0.79	E <sup>a</sup>	98.2	12.8	19.4	2.2	53.7	2.0	2.8	2.0	2.1	0.5
2			E <sup>b</sup>	98.7	13.9	20.1	2.2	54.3	2.0	1.8	2.2	2.0	0.6

a= reduced after regeneration.

b= not reduced after regeneration.

In fact a small deactivation of the catalyst was noted around 400°. Temperature around 400° may promote undesired side reactions like cracking and polymerization, leading to the formation of coke which may cause the deactivation of the catalyst.

The proportions of various intermediates, irrespective of their nature, fall rapidly due to their further conversion to the final product, *p*-cymene, which maintains its increasing trend almost linearly upto 350°. Between 350 and 400°, the *p*-cymene formation comes down on account of the deactivation of the catalyst as explained above.

The maximum concentration of menthanes and menthenes occurs around 250° and thereafter their formation registers a decrease. From this it is clear that disproportionation reactions are favoured in the lower temperature regions since at higher temperature the species undergoing disproportionation desorb easily before reaction.

#### Acknowledgement

Thanks of the authors are due to Dr. G. S. Laddha, Director, A. C. College of Technology, Madras, for necessary facilities.

#### References

1. J. L. SIMONSEN, "The Terpenes", Cambridge University Press, 1949, Vol II, p. 105.
2. V. KRISHNASAMY, *Chem. Age India*, 1976, 27, 710.
3. J. L. INFESTA and V. ALFMAN, *Chem. Abs.*, 1964, 48, 1977.
4. V. KRISHNASAMY, P. RATNASAMY and L. M. YEDDANAPALLI, *Chem. Age India*, 1971, 22, 18.
5. A. STANISLAUS and L. M. YEDDANAPALLI, *Cand. J. Chem.*, 1972, 50, 113.
6. H. PINES and W. O. HAAG, *J. Amer. Chem. Soc.*, 1961, 83, 2847.
7. F. B. SANDELL, "Colorimetric Determination of Traces of Metals", Interscience, New York, N. Y., 1959.
8. V. KRISHNASAMY and L. M. YEDDANAPALLI, *Cand. J. Chem.*, 1976, 54, 8458.
9. V. KRISHNASAMY, *Cand. J. Chem.*, 1977, 55, 8048.
10. V. KRISHNASAMY and L. M. YEDDANAPALLI, *Cand. J. Chem.*, 1978, 56, 1994.
11. P. H. EMMETT, *Catalysis*, 1954, 7, 31.
12. T. A. DORLING and R. L. MOSS, *J. Catal.*, 1967, 7, 878.
13. H. PINES, R. O. OLBERG and V. N. IPATIEFF, *J. Amer. Chem. Soc.*, 1948, 70, 588.

# Aza Triterpenes—III<sup>†</sup>: Action of Excess Hydrazoic Acid-Boron Trifluoride Etherate on 3-Oxo-Penta Cyclic Triterpenes

T. SUNDARA RAMAIAH\*, S. K. RAMRAJ, CH. GOVARDHAN and V. VISHWANATH RAO

Department of Chemistry, Nizam College, Hyderabad-500 001

Manuscript received 30 July 1961, revised 6 February 1962, accepted 7 June 1962

3-Oxo-pentacyclic triterpenes (I, II and III) furnished 3-cyano-4-azido-3,4-seco penta cyclic triterpenes (IB, IIB and IIIB) on treatment with excess N<sub>3</sub>H-BF<sub>3</sub> etherate both in benzene and chloroform media. The reaction did not proceed at 10°. Attempts to build up tetrazole ring system by the action of excess N<sub>3</sub>H-conc. H<sub>2</sub>SO<sub>4</sub> on 3-oxo-penta cyclic triterpenes (I, II and III) furnished lactams (IA, IIA and IIIA). The lactams were recovered unreacted on treatment with excess N<sub>3</sub>H-BF<sub>3</sub> etherate.


SCHMIDT reaction of ketones with equimolecular quantities of hydrazoic acid yields amides and with excess of hydrazoic acid tetrazoles. Tetrazoles are known to possess biological activity and some are of clinical significance. The tetrazole obtained from cyclohexanone, commercially known as metrazole or cardiazole, is a heart stimulant<sup>1,2</sup>. Steroidal tetrazoles are claimed to possess anti-fertility and anti-spermatogenic activity<sup>3,4</sup>.

A search in literature revealed that Schmidt reaction with excess of hydrazoic acid-boron trifluoride etherate on triterpene ketones has not been studied. In the present investigation lupenone (I), methyl betulonate (II) and methyl oleanonate (III) were treated with excess hydrazoic acid in presence of freshly distilled boron trifluoride etherate in benzene and chloroform media for 16 hr and 3 hr at room temperature. The reaction products in all the above three cases did not show characteristic absorption for tetrazole ring system in their ir spectra. The ir spectra were also lacking in 7-membered lactam carbonyl absorption, indicating that the reaction did not proceed to give either the tetrazole ring system or the normal Schmidt reaction product. Instead, the ir spectra of the reaction products showed absorption around 2250 cm<sup>-1</sup> and 2050 cm<sup>-1</sup>, characteristic of nitrile and azide groups, respectively. This is possible only when there is cleavage in ring A of these triterpene ketones.


The ring fission in the presence of excess hydrazoic acid-boron trifluoride etherate is not uncommon though not a usual feature. The 17-oxo steroids, esteron methyl ether<sup>5</sup> and 4-androstene-3,17-dione<sup>6,7</sup>, gave besides tetrazoles, 13, 17-seco-13 $\alpha$ -azido-17-nitriles. 5 $\alpha$ -Hydroxy-6-oxo-5 $\alpha$ -cholestan<sup>8</sup> furnished 3 $\beta$ -acetoxy-5-oxo-5,6-seco-cholestan-6-nitrile. On the basis of formation of lactams (IA, IIA and IIIA) in the normal Schmidt reaction of these triterpene ketones (I, II and III)<sup>9</sup>, ir spectra and analytical data, 3-cyano-4-azido-3,

4-seco structures were assigned to the reaction products (IB, IIB and IIIB). The cleavage of C<sub>3</sub>-C<sub>4</sub> bond in this reaction is in conformation with the results of Beckmann rearrangement<sup>9</sup> of the oximes of lupenone, methyl betulonate and methyl oleanonate. These triterpenes have a gem-dimethyl group adjacent to 6-membered keto function. As in the case of Beckmann rearrangement, even in the present instance the gem-dimethyl group next to oxo function is responsible for the cleavage of C<sub>3</sub>-C<sub>4</sub> bond. The signal at  $\delta$  2.5 (2H) in the nmr spectrum of IB can be assigned to -CH<sub>2</sub>-C $\equiv$ N supporting the 3-cyano-4-azido-3, 4-seco structure

In an attempt to build up the tetrazole ring system the reaction was conducted at 10° but the compounds were recovered unreacted both in benzene and chloroform media. The 3-oxo-pentacyclic triterpenes (I, II and III) furnished normal Schmidt reaction products (IA, IIA and IIIA) with excess of hydrazoic acid-conc. sulphuric acid both in benzene and chloroform media. For the formation of tetrazoles or the lactams, imido carbonium ion is the intermediate<sup>10</sup> which reacts with water present in sulphuric acid in preference to hydrazoic acid. Treatment of the lactams (IA, IIA and IIIA) with excess of hydrazoic acid-boron trifluoride etherate both in benzene and chloroform media proved unsuccessful in building the tetrazole ring system probably the lactam, once formed, is stable enough not to revert to imido carbonium ion which is a precursor for the formation of tetrazoles.



<sup>†</sup> Part of the work has presented at the Annual Convention of Chemists, 1970 at Kurukshetra.



### Experimental

Melting points are uncorrected. All the compounds showed consistent elemental analysis. IR spectra were recorded on Perkin-Elmer spectrophotometer in KBr.

1. *Preparation of hydrazoic acid in benzene and chloroform media*: A stirred solution of sodium azide (100 g) in water (250 ml) was cooled to 5-10° and benzene or chloroform (1 l) was added followed by drop-wise addition of conc. sulphuric acid (93 ml) during 30 min at 5-10°. The mixture was stirred for 30 min with temperature kept below 10°. The organic layer was separated and dried.

2. *Action of excess hydrazoic acid-boron trifluoride etherate on 3-oxo-pentacyclic-triterpenes (I, II, III) in benzene at room temperature*: Isolation of 3-cyano-4-azido-3,4-seco pentacyclic triterpenes (IB, IIB and IIIB): A typical experiment is described. To 3-oxo-pentacyclic triterpene (1.5 g) in benzene (100 ml), freshly distilled boron trifluoride etherate (10 ml) and hydrazoic acid solution in benzene (200 ml) were added and the mixture kept for 16 hr at room temperature (30-35°). Crushed ice was added to the reaction mixture and the organic layer was washed with ice-cold water. The benzene layer was dried and evaporated. The residue was adsorbed over a column of neutral alumina (50 g) and eluted with benzene (500 ml) and chloroform (500 ml). The benzene eluate gave 3-cyano-4-azido-3,4-seco pentacyclic triterpene (750 mg), crystallising from methanol as colourless needles. Chloroform eluate did not yield any residue on removal of the solvent.

The reaction was conducted in chloroform medium at room temperature for 16 hr and 3 hr duration. The reaction product was 3-cyano-4-azido-3,4-seco pentacyclic triterpene, m.p.: IB 220°, IIB 215° and IIIB 215°. IR: IB 2250 cm<sup>-1</sup> and 2050 cm<sup>-1</sup>; IIB 2250 cm<sup>-1</sup> and 2040 cm<sup>-1</sup> and IIIB 2235 cm<sup>-1</sup> and 2045 cm<sup>-1</sup> for -CN and N<sub>3</sub> groups, respectively. NMR for IB  $\delta$  2.5(2H for -CH<sub>2</sub>-C≡N).

3. *Action of excess hydrazoic acid on 3-oxo-pentacyclic triterpene in presence of conc. sulphuric acid in benzene*: Isolation of 3-oxo-3a-aza-A-homo pentacyclic triterpenes (IA, IIA and IIIA): A typical experiment is described. To 3-oxo-pentacyclic triterpene (1.5 g) in benzene (100 ml), conc. sulphuric acid (3 ml) and hydrazoic acid in benzene (200 ml) were added and kept for 16 hr at room temperature (30-35°). Crushed ice was added to the reaction mixture and the organic layer was washed with ice-cold water. The benzene layer was dried and evaporated. The residue (900 mg) was adsorbed over a column of neutral alumina (50 g) and eluted with benzene (500 ml) and chloroform (500 ml). The benzene eluate did not yield any residue on removal of the solvent. Chloroform eluate yielded 3-oxo-3a-aza-A-homo pentacyclic triterpene, identical with the product obtained in the Schmidt reaction of 3-oxo-pentacyclic triterpene<sup>9</sup>, m.p.: IA 258°; IIA 256°; IIIA 258° (lit<sup>9</sup> m.p.s 258, 256 and 258 for IA, IIA and IIIA, respectively).

IR: IA 3230 cm<sup>-1</sup> and 1675 cm<sup>-1</sup>; IIA 3225 cm<sup>-1</sup> and 1675 cm<sup>-1</sup>; IIIA 3220 cm<sup>-1</sup> and 1675 cm<sup>-1</sup> for NH and -CONH respectively. NMR IIIA  $\delta$  5.5 (H) exchangeable with D<sub>2</sub>O for NH.

### Acknowledgement

The authors are grateful to Prof. M. L. N. Reddy, Principal and Head, Department of Chemistry, Nizam College, Hyderabad for facilities. One of the authors (Ch. G.) thanks C.S.I.R., New Delhi for financial assistance. (S. K. R.) thanks V. V. Research Centre for encouragement.

### References

1. K. F. SCHMIDT, *Chem. Abs.*, 1935, 19, 2948.
2. K. F. SCHMIDT, *Chem. Abs.*, 1936, 20, 3480.
3. R. MECHOULAM, *Chem. Abs.*, 1965, 63, 8462.
4. R. MECHOULAM, *Israel J. Chem.*, 1968, 6, 909.
5. H. SINGH, R. K. MALHOTRA, A. S. CHAWLA and N. K. LUHADIV, *Indian J. Chem.*, 1976, 14, 618.
6. H. SINGH, R. K. MALHOTRA and V. V. PARASHAR, *Indian J. Chem.*, 1976, 13, 761.
7. H. SINGH, R. K. MALHOTRA and V. V. PARASHAR, *Tetrahedron Lett.*, 1978, 2587.
8. M. S. AHMED, Z. A. CHOUDARY and P. N. KHAN, *Aust. J. Chem.*, 1976, 29, 447.
9. T. S. RAMAIAH, S. K. RAMRAJ, K. L. BAO and V. V. BAT, *J. Indian Chem. Soc.*, 1976, 53, 664.
10. M. S. AHMED and I. A. KHAN, *Indian J. Chem.*, 1977, 15B, 1016.



# Synthesis of 3-Heteraryl Coumarins as Optical Brighteners


D. ANNAPURNA, Y. D. REDDY\* and V. V. SOMAYAJULU

Department of Chemistry, Regional Engineering College, Warangal-506 004

Manuscript received 10 October 1979, revised 4 March 1982, accepted 8 July 1982


A few 2-aryl and 2-heterocyclic substituted (6,7) coumarinoxazoles have been synthesised by condensing 6-amino-7-hydroxy-3-phenyl-4-methylcoumarin with aromatic and heterocyclic carboxylic acids with the aid of polyphosphoric acid. The ultraviolet, infrared, nmr, mass and fluorescence spectra of these compounds have been presented for characterisation.

7-(2'-Benzoxazolyl)-3-phenylcoumarins<sup>1</sup> and 2-(3'-coumarinyl) benzoxazoles<sup>2</sup> have been reported to be optical brighteners for polyesters, polyamides and polyvinyl chloride. 2-(3'-Coumarinyl) naphthoxazoles with a dialkylamino substituent in 7-position of the coumarin ring exhibit brilliant fluorescence with absorption in the visible range and are useful for the dyeing of organic fibres<sup>3</sup>. Coumarin derivatives, specially 3-aryl-7-substituted aminocoumarins, because of their intense blue fluorescence and good light fastness constitute an important group of optical brighteners for synthetic fibres like polyamide and polyester<sup>4</sup>. In our earlier studies<sup>5</sup> coumarino-oxazoles with aromatic or heterocyclic substitution in 2-position have been found to possess high fluorescence in uv and visible region. Encouraged by these results, in our present investigation, various 2-(3-coumarinyl)-4'-methyl-3'-phenylcoumarino-(6',7' : 4,5) oxazoles, 2-(3-aryl, 3-naphthyl, 3-heteraryl) oxazoles and *bis* oxazoles have been synthesized by the condensation of 4-methyl-3-phenyl-6-amino-7-hydroxycoumarin (I) with various substituted coumarin-3-carboxylic acids, aromatic carboxylic acids, naphthoic acids, pyridine carboxylic acids and dicarboxylic acids to get the corresponding oxazoles II, III using polyphosphoric acid as the cyclodehydrating agent.



In addition to the above compounds a few 2-(3'-coumarinyl)-coumarin (3:4) oxazoles have been synthesized to study the effect on fluorescence of oxazole moiety on the pyrone part of the coumarin. For the purpose of synthesizing the

above compounds 3-amino-4-hydroxycoumarin (IV) was condensed with various coumarin-3-carboxylic acids to get the corresponding oxazoles (V) using polyphosphoric acid as cyclodehydrating agent.



The above compounds have been characterized by uv, ir, nmr, mass and fluorescence spectral data.

**UV spectra** The uv spectra of all the compounds were recorded on Beckmann DK 2A spectrophotometer using dioxane as solvent. All the title compounds exhibited three main regions of absorption around  $368 \pm 30$ ,  $283 \pm 5$  and  $253 \pm 10$  nm. The fluorescence spectra for all the compounds were measured on Beckmann DK 2A spectrophotometer using dioxane as the solvent. The results are tabulated in Tables 1A, 1B and 1C.

The information obtained from the fluorescence spectrum may be used in the evaluation of the compounds as possible fluorescent brighteners for synthetic fibres, plastics, papers etc. An ideal fluorescent brightener should absorb in the uv region between 340 and 400 nm and emit in the visible region<sup>6</sup>. The maximum of these resulting

TABLE 1A

Sl. No.	2-(Heteraryl)-4'-methyl-3'-phenylcoumarino-(6',7' : 4,5) oxazole	max. absorption nm	max. emission nm	Difference nm	Colour observed
1.	2-(3-Coumarinyl)-	369	455	86	Blue
2.	2-(6-Methyl-3-coumarinyl)-	371	457	86	Blue
3.	2-(8-Methyl-3-coumarinyl)-	369	456	87	Blue
4.	2-(6-Bromo-3-coumarinyl)-	370	469	99	Blue
5.	2-(5,6-Benzo-3-coumarinyl)-	396	488	87	Green
6.	2-(2-Naphthyl)-	369	400	41	Violet
7.	2-(p-Tolyl)-	342	426	84	Violet
8.	2-(1-Naphthyl)-	369	406	37	Violet
9.	2-(Benzyl)-	329	430	101	Light violet
10.	2-(3-Pyridyl)-	354	408	54	Light violet
11.	2-(4-Pyridyl)-	353.5	410	56.5	Light violet

TABLE 1B

Sl. No.	Name of the compound	max. absorption	max. emission	Difference	Colour observed
1.	Bis-[4'-methyl-3'-phenyl-coumarino-(6',7':4,5)-oxazolo] methane	396	497	111	Light violet
2.	Bis-[4'-methyl-3'-phenyl-coumarino-(6',7':4,5)-oxazolo] ethylene	406.5	466	47.5	Blue
3.	Bis-1,4-[4'-methyl-3'-phenyl-coumarino-(6',7':4,5)-oxazolo] benzene	398	478	105	Green

TABLE 10

Sl. No.	2-(3-Heteraryl)-coumarino(8',4':4,5) oxazole	max. absorption	max. emission	Difference	Colour observed
1.	2-(3-Coumarinyl)-	nm	nm		
2.	2-(3-Methyl-8-coumarinyl)-	365	455	100	Blue
3.	2-(3,6-Benzo-8-coumarinyl)-	365	457	92	Blue
3.	2-(3,6-Benzo-8-coumarinyl)-	393	478	115	Green

fluorescent light, which determines the colour ranges, is between 415-465 nm. The fluorescent maxima of all the 2-(3-coumarinyl)-coumarino oxazoles have emission in the ideal range and therefore these compounds are potential optical brighteners.

**IR spectra:** The ir spectra of the compounds have been recorded on Perkin Elmer Model 137 in KBr. All the coumarino-oxazoles exhibited a strong band around  $1730 \pm 15 \text{ cm}^{-1}$  characteristic of coumarin carbonyl group. In addition, peaks at  $1550$  to  $1570 \text{ cm}^{-1}$ ,  $1100 \pm 15 \text{ cm}^{-1}$ ,  $1360 \pm 10 \text{ cm}^{-1}$ , attributable to  $>\text{C}=\text{N}$ ,  $-\text{C}-\text{O}-\text{C}-$  and  $>\text{C}-\text{N}=$  of the oxazole system, respectively, have also been found to be common.

**NMR spectra:** The nmr spectra were recorded on Varian A-60 nmr spectrophotometer in DMSO and  $\text{CDCl}_3$ . The details of the spectra are given in Table 2.

TABLE 2—2-(6-METHYL-8-COUMARINYL)-4'-METHYL-3'-PHENYLCOUMARINO-(6',7':4,5) OXAZOLE

$\delta$ values	No. of protons	Assignment
2.45 (s)	8	6 Methyl protons
2.55 (s)	8	4' Methyl protons
7.33-7.55(m)	10	Aromatic protons
8.95(s)	1	Vinyl proton

**Mass spectra:** The mass spectra was recorded on RMU-6L Mass spectrometer with inlet temperature ranging from  $150$  to  $200^\circ$  and an electron beam energy of  $70 \text{ ev}$ . The mass spectrum of 2-(8-methyl-3-coumarinyl)-4'-methyl-3'-phenyl-coumarino-(6',7':4,5) oxazole has been recorded. The molecular ion peak at  $m/z$  435 is the base peak. The peaks at  $m/z$  (% abundance) 407 (95%), 379 (22%), 105 (70%) and 64 (38%) are observed in the mass spectrum of the above compound. The major

fragmentation mode is loss of carbon monoxide as observed in the case of simple coumarins<sup>7</sup>.

### Experimental

**Preparation of 6-amino-7-hydroxy-3-phenyl-4-methylcoumarin:** Synthesized from 5-nitroresacetophenone as reported earlier<sup>8</sup> but with certain modifications in the process of deacetylation and reduction.

5-Nitroresacetophenone (5 g), sodium phenyl acetate (10 g) and acetic anhydride (60 ml) were mixed together and refluxed in an oil bath at  $180^\circ$  for 8 hr. The reaction mixture on pouring in ice water, filtration and recrystallisation from acetic acid yielded 6-nitro-7-acetoxy-3-phenyl-4-methylcoumarin, m.p.  $201^\circ$ . 2 g of the above compound was added to 50 ml of 5% sodium carbonate solution and refluxed for 3 hr. On neutralisation, it gave 6-nitro-7-hydroxy-3-phenyl-4-methylcoumarin, m.p.  $223^\circ$ .

2.7 g of the above nitro compound was mixed with 7 g sodium dithionite, 30 ml ammonia, 30 ml water and 15 ml rectified spirit, refluxed for 15 min and cooled. The compound separated on recrystallisation gave 6-amino-7-hydroxy-3-phenyl-4-methylcoumarin, m.p.  $240^\circ$ .

**Preparation of 2-(3-coumarinyl, aryl, heteraryl, naphthyl)-4'-methyl-3'-phenylcoumarino-(6',7':4,5) oxazoles:** Polyphosphoric acid was prepared by stirring a mixture of phosphorous pentoxide (15 g) and orthophosphoric acid (10 ml) at  $100^\circ$  for 1 hr. A mixture of 6-amino-7-hydroxy-3-phenyl-4-methylcoumarin (0.005 mole) and appropriate acid (0.005 mole) was then dropped into the above. The reaction mixture was heated first at  $150-60^\circ$  for 2 hr and then at  $200-205^\circ$  for further 2 hr. The reaction product was poured over ice cold water and the resulting solid was washed with sodium bicarbonate. Recrystallisation was effected with appropriate solvent as shown in Table 3.

**Preparation of bis oxazoles:** The quantity of the 6-amino-7-hydroxy-3-phenyl-4-methylcoumarin taken was (0.01 mole), twice the quantity of the dicarboxylic acid (0.005 mole). The reaction was maintained at  $140^\circ$  for 2 hr and then at  $160^\circ$  for 4 hr. The reaction product was worked out as above.

**Preparation of 2-(3-heteraryl)-coumarino-(3',4',:4,5)-oxazoles:** Polyphosphoric acid was prepared as above and a mixture of 3-amino-4-hydroxycoumarin<sup>9</sup> (0.005 mole) and appropriate acid (0.005 mole) was dropped into it. The reaction mixture was heated first at  $150-60^\circ$  for 2 hr and then at  $200-205^\circ$  for 2 hr. The reaction mixture was poured over ice water and the resulting solid was washed with sodium bicarbonate. Recrystallisation details are included in Tables 3A, 3B and 3C.

TABLE 8A

Sl. No.	2-(Heteraryl)-4'-methyl-3'-phenylcoumarino-(6',7' : 4,5) oxazole	m.p. °C	Yield %	Solvent of recrystallisation
1.	2-(8-Coumarinyl)-	225	60	Dioxane
2.	2-(8-Methyl-8-coumarinyl)-	275	60	Dioxane
3.	2-(8-Methyl-8-coumarinyl)-	356	60	Dioxane
4.	2-(8-Bromo-8-coumarinyl)-	330	60	Dioxane
5.	2-(5,6-Benzo-8-coumarinyl)-	315	40	Dioxane
6.	2-(2-Naphthyl)-	325	70	Benzene
7.	2-(1-Naphthyl)-	308	60	Benzene
8.	2-(p-Tolyl)-	280	75	Benzene
9.	2-(Bansyl)-	288	50	Benzene
10.	1-(3-Pyridyl)-	325	60	Benzene
11.	2-(4-Pyridyl)-	320	60	Benzene
12.	2-(o-Tolyl)-	263	75	Benzene

TABLE 8B

Sl. No.	Name of the compound	m.p. °C	Yield %	Solvent of recrystallisation
1.	Bis-[4'-methyl-3'-phenyl-coumarino-(6',7' : 4,5)-oxazole] methane	268	40	Dioxane
2.	Bis [4'-methyl-3'-phenyl-coumarino-(6',7' : 4,5)-oxazole] ethylene	325	40	Dioxane
3.	Bis-1,4-[4'-methyl-3'-phenyl-coumarino-(6',7' : 4,5)-oxazole] benzene	272	60	Dioxane

TABLE 8C

Sl. No.	2-(8-Heteraryl)-coumarino-(8',4' : 4,5) oxazole	m.p. °C	Yield %	Solvent of recrystallisation
1.	2-(8-Coumarinyl)-	278	50	Dioxane
2.	2-(5,6-benzo-8-coumarinyl)-	290	40	Dioxane
3.	2-(8-Methyl-8-coumarinyl)-	295	50	Dioxane

## Acknowledgement

The authors are thankful to Prof. K. Koteswara Rao, Principal, Regional Engineering College, Warangal for facilities. One of the authors (D. A.) is thankful to Sri P. S. Sastry, Asst. Professor for help in getting the spectra, Shri G. V. P. Chandramouli, Teaching Assistant for helpful suggestions and C.S.I.R., New Delhi for a Junior Research Fellowship.

## References

1. CIBA, French Patent, 1,496,700, *Chem. Abs.*, 1958, 69, 8798.
2. CIBA, British Patent, 914,719; *Chem. Abs.*, 1964, 61, 3242
3. FARBENFABRIKEN BAYER, German Patent, 2,030,567, *Chem. Abs.*, 1972, 76, 128,626.
4. S. D. MEHENDALE and S. V. SONTAKKAR, *J. Indian Chem. Soc.*, 1970, 47, 989.
5. K. U. JOSEPH, "Synthetic Studies in the Heterocyclic Field - Synthesis of Substituted Benzoxazoles", Ph. D. Thesis, Jawaharlal Nehru Technological University, India, 1976.
6. K. VENKATRAMAN (Ed.), "Chemistry of Synthetic Dyes", Academic Press, 1971, Vol. 5.
7. SPITZLER, "Physical Methods in Heterocyclic Chemistry", (Ed.) KATRIZKY, Academic Press, New York, 1971, Vol. 3.
8. V. V. SOMAYAJULU and N. V. SUBBA RAO, *Proc. Ind. Acad. Sci.*, 1965, 61, 177.
9. K. S. R. KRISHNA MOHAN RAO and N. V. SUBBA RAO, *Proc. Ind. Acad. Sci.*, 1968, 67, 42.

## Free Acids in Lac Resin

N. PRASAD, S. C. AGARWAL, J. N. CHATTERJEA\* and S. C. SENGUPTA\*\*

Chemistry Division, Indian Lac Research Institute, Namkum, Ranchi-834 010,

Manuscript received 20 November 1981, accepted 8 July 1982

Lac resin has been found to contain 10.70% free fatty and 2.7% free aldehydic terpenic acids. The free fatty acids are composed of (i) saturated and unsaturated straight, chain lengths of  $C_{14}$ ,  $C_{16}$  and  $C_{18}$ , (ii) 6-ketotetradecanoic, (iii) 6-hydroxy-tetradecanoic (butolic), (iv) 16-hydroxyhexadecanoic, (v) 16-hydroxyhexadec-*cis*-9-enoic, (vi) *threo*-9,10-dihydroxy of  $C_{14}$  and  $C_{16}$  chain lengths and (vii) *threo*-9,10,16-trihydroxy hexadecanoic (aleuritic) acids, while the terpenic acids constitute a mixture of jalaric, laccijalaric and a new aldehydic acid ( $C_{18}H_{34}O_2$ ).

**STUDIES** on the constitution of lac resin<sup>1-3</sup> and its two fractions, the pure<sup>4,10</sup> and the soft<sup>4,6</sup> resins, revealed that at least 18 constituent acids, comprising non-hydroxy and hydroxy fatty acids of  $C_{14}$  to  $C_{18}$  carbon chains and terpenic acids take part in the resin formation. It is believed that these acids are present in the resin mainly through ester<sup>1</sup> and acylal<sup>7-9</sup> linkages. Some workers<sup>10,11</sup>, however, have casually indicated that a few of these acids are free in the resin to some extent. Since the presence of some of the constituent acids in the free state might have some interesting bearing on the resin formation, a systematic study was necessary to arrive at a decisive conclusion. The present paper relates to such an attempt to isolate and identify the free acids present in lac resin.

**Isolation of free acids:** A 30% solution of dewaxed lac in 95% ethanol was exhaustively extracted with *n*-hexane and 12 fractions collected. TLC examination showed the fractions to contain mainly non-, mono-, di- and tri-hydroxy acids. However, butolic acid (6-hydroxytetradecanoic acid) appeared to be the major component of fractions 4 to 12. The fractions were combined and after removal of the neutral fraction and traces of wax, methylated and then acetylated<sup>12</sup>. The acetylated product was fractionated with urea<sup>13</sup> to give adducted (A) and non-adducted (B) esters. TLC examination on silver nitrate impregnated plates<sup>14</sup> revealed that A consisted of saturated and unsaturated non-hydroxy and *o*-acetoxy esters along with keto ester while B of keto esters along with mono-, di- and triacetoxy esters.

Fractionation of A with increasing proportions of ether in light petroleum on a column of silica gel impregnated with silver nitrate<sup>15</sup> afforded the pure components. Similarly, pure constituents from B were separated over a column of silica gel. The pure constituents were identified by adopting various methods as described in the experimental.

In the above investigation, the presence of free aleuritic acid has only been indicated but its exact

amount, as well as the presence of jalaric and other aldehydic terpenic acids could not be obtained, although their presence in sufficient amounts was reported earlier<sup>10,11</sup>. This may be due to the fact that these acids are practically insoluble in hexane. The following alternate method was, therefore, tried to achieve their isolation.

*Palas* seedlac was dissolved in  $Na_2CO_3$  solution, the sodium salts of lac resin salted out with  $NH_4Cl$  solution and the neutral fraction separated from the mother liquor. Half of the liquor was treated for estimation of aleuritic acid and the other half for the terpenic acids. TLC of the mother liquor showed that the aldehydic acids were mainly composed of jalaric acid with small amount of laccijalaric acid and a new aldehydic acid recently isolated by Prasad<sup>16</sup>. Table I summarises the percentage of the free acids isolated so far from lac resin in the present study.

TABLE I—PERCENTAGE OF FREE ACIDS

1 Saturated straight chain lengths of $C_{14}$ , $C_{16}$ and $C_{18}$	0.30
2 Unsaturated straight chain lengths of $C_{14}$ , $C_{16}$ and $C_{18}$	0.06
3 6-Ketotetradecanoic	0.45
4 6-Hydroxytetradecanoic	2.37
5 16-Hydroxyhexadecanoic	0.57
6 16-Hydroxyhexadec- <i>cis</i> -9-enoic	0.77
7 <i>Threo</i> -9,10-dihydroxy of chain lengths $C_{14}$ and $C_{16}$	1.37
8 <i>Threo</i> -9,10,16-trihydroxy hexadecanoic (aleuritic)	4.88
9 Aldehydic terpenic	2.68
Total	12.40

The results obtained in the present study confirmed the findings of Sengupta<sup>11</sup> who reported the presence of free acids to the tune of 8-10% in lac resin. Though the presence of  $C_{14}$  straight chain free acids have been indicated, no indication has been observed for the presence of such hydroxy saturated or unsaturated acids in lac resin.

The unsaturated acids indicated at Sl. Nos 2 and 6 appear to be the precursors of various mono-, di- and tri-hydroxy acids. These free acids as such

\* Chemistry Department, Patna University, Patna-800 005.

\*\* Indian Mica and Micanite, Koderma, Bihar.

or in loose combination may be considered as the primary building blocks of lac resin. This contention has been further supported by Singh *et al.*<sup>11</sup>, who have succeeded (i) in isolating 4 essentially pure acid esters (jalaric ester—I and II and laccijalaric ester—I and II) constituting the bulk of soft resin, (ii) in synthesising the possible key compounds (jalaric ester—I and laccijalaric ester—I) of lac resin. They have reported that 16-hydroxy hexadec-9-enoic acid seems to play a key role in the elaboration of these compounds by the insect.

### Experimental

All m.p.s and b.p.s are uncorrected. Light petroleum refers to the fraction b.p. 40-60. Silica gel for column chromatography was 100-200 mesh. TLC was carried out on silica gel layers (0.3 mm) containing 15% gypsum; visualization agent—iodine vapours or heating at 150°. Mixed solvent composition is by volume. Perkin-Elmer Infracord 700A and AIMIL, Gas-liquid chromatography equipment were used for ir spectral and constituent analyses, respectively.

Dewaxed shellac (100 g), prepared from *Palas* seedlac by the method of Khurana *et al.*<sup>4</sup>, was dissolved in 95% methanol (300 ml) and exhaustively extracted with 1 litre lots of *n*-hexane in succession. Altogether 12 fractions, totalling 7.06 g, which were 2.98, 1.25, 0.97, 0.63, 0.42, 0.29, 0.27, 0.09, 0.06, 0.05, 0.04 and 0.014 g, respectively, were isolated. The tlc examination of the fractions (solvent system, 2% acetic acid in ethyl acetate) along with authentic samples revealed that all the fractions were mixtures of mainly non-, mono-, di-, tri-hydroxy and keto acids. However, butolic acid was found as the major component in fractions 4 to 12. These fractions were, therefore, mixed together and repeatedly extracted with warm light petroleum. The warm extract yielded a crystalline mass (0.65 g) on cooling which, after recrystallisation from aqueous methanol, melted at 56-57°. The acid was identified as butolic (6-hydroxytetradecanoic) acid on the basis of its tlc (R<sub>f</sub> 0.73), mixed m.p. (55-56°), oxidative degradation and ir spectrum 3225 cm<sup>-1</sup> (OH), 1710 cm<sup>-1</sup> (COOH).

As the nature of the first 3 fractions and the combined one, left after separation of butolic acid, was similar, they were combined, taken in ether and extracted with 10% Na<sub>2</sub>CO<sub>3</sub> solution (100 ml × 4) leaving the wax and neutral portions in the ether. The acidic mass (6.04 g) recovered on acidification of Na<sub>2</sub>CO<sub>3</sub> extract, was converted into methyl esters by refluxing with 1% methanolic H<sub>2</sub>SO<sub>4</sub> for 4 hr. The methyl esters were then acetylated<sup>12</sup> with acetic anhydride (35 ml) at 100° for 4 hr to yield 6.6 g acetylated esters.

**Urea-fractionation<sup>13</sup>**: The acetoxy esters (6.5 g) were dissolved in methanol (70 ml), urea (12 g) added and warmed to get a clear solution. The solution was allowed to stand at room temperature for 48 hr. The adduct was separated, washed with methanol saturated with urea, decomposed with

warm water and extracted with ether yielding adducted acetoxy ester (A; 2.12 g). Similarly, non-adducted acetoxy (B; 4.41 g) was also recovered. TLC of the fractions on silver nitrate impregnated plates<sup>14</sup> indicated A to contain saturated and unsaturated non-hydroxy and  $\omega$ -acetoxy esters along with keto esters [solvent system, light petroleum: ether (80:20)] while B to contain keto esters along with mono-, di- and tri-acetoxy esters.

### Chromatography of adducted esters A (2.10 g):

The fraction A was chromatographed in 6 lots on silica gel columns impregnated with silver nitrate<sup>15</sup> (10 g) mixed with hyfiosupercel (5 g) and eluting with 100 ml lots of light petroleum-ether mixtures and collecting in 10 ml portions. The fractionation was monitored by tlc on silver nitrate impregnated plates and the corresponding fractions combined, giving finally 6 fractions (A-1 to A-6; 2.02 g). The fractions A-1 and A-2 were saturated (R<sub>f</sub> 0.65) and unsaturated (R<sub>f</sub> 0.46) non-hydroxy esters, respectively while the fractions A-3 and A-5 were saturated (R<sub>f</sub> 0.32) and unsaturated (R<sub>f</sub> 0.25)  $\omega$ -acetoxy esters, respectively. Fraction A-4 appeared to be keto ester (R<sub>f</sub> 0.61) and A-6 was a mixture of esters. Fractions A-1 and A-2 were identified by glc as mixtures of saturated and unsaturated C<sub>14</sub>, C<sub>16</sub> and C<sub>18</sub> ordinary esters respectively on the column of polyethylene glycol adipate (PEGA, 10% w/w) at a column temperature of 200° by running separately with standard esters.

### $\omega$ -Acetoxy esters

**Saturated**: The hydroxy acid derived from fraction A-3 was shown to be 16-hydroxy hexadecanoic acid on the basis of the following evidences.

The acid, on crystallisation from ether, melted at 92-93° (lit<sup>17</sup> 91-93°). Mixed m.p. 93-94°; ir (methyl ester, m.p. 52-53°): 3278 cm<sup>-1</sup> (OH), 1047 cm<sup>-1</sup> (primary OH) and 1718 cm<sup>-1</sup> (ester carboxyl). Oxidation<sup>18</sup> of the acid gave 1,16-hexadecanedioic acid<sup>16</sup>, m.p. 118-119°. The chain length determination<sup>19</sup> showed that the ester was mainly C<sub>16</sub> in its chromatographic behaviour over glc. (Found: C, 70.67; H, 11.72. C<sub>16</sub>H<sub>32</sub>O<sub>2</sub> requires C, 70.59; H, 11.76%). (A.V. = 200.7, H.V. = 194.0 and acid equiv. = 279.0).

**Unsaturated**: The liquid unsaturated hydroxy acid isolated from A-5 was confirmed as 16-hydroxy hexadec-*cis*-9-enoic acid on the basis of its oxidation<sup>21,22</sup> to C<sub>7</sub> and C<sub>9</sub> dibasic acids, hydrogenation to saturated  $\omega$ -hydroxy acid and ir spectrum. The methyl ester did not show any peak at 968 cm<sup>-1</sup> corresponding to a *trans* double bond indicating its configuration as *cis*. (Found: C, 70.22; H, 10.57. C<sub>16</sub>H<sub>30</sub>O<sub>2</sub> requires C, 71.11; H, 11.11%).

**Keto ester (A-4)**: The acid recovered from fraction A-4 melted at 70-71° (mixed m.p. 70-71°) was identified as 6-keto tetradecanoic acid on the basis of tlc (methyl ester, R<sub>f</sub> 0.61), ir (two peaks at 1737 cm<sup>-1</sup> and 1718 cm<sup>-1</sup> corresponding to keto and ester carboxyl groups, respectively), semi carbazone derivative<sup>23</sup> (m.p. 129-130°) and sodium

borohydride reduction to 6-hydroxy tetradecanoate (methyl butolate).

*Chromatography of non-adducted esters B :*

The non-adducted acetoxy esters B (4.4 g) were chromatographed over silica gel into 4 fractions (B-1 to B-4; 4.21 g) with increasing proportions of ether in light petroleum. TLC showed B-1, B-2 and B-3 to be 6-ketotetradecanoate (R, 0.61), acetoxy butolate (R, 0.42) and diacetoxy ester (R, 0.28), respectively. B-4 was mainly triacetoxy ester (R, 0.12). The acids recovered from B-1 and B-2 were identified in usual manner as described earlier.

*Diacetoxy ester B-3 :* The acid derived from fraction B-3 formed isopropylidene<sup>24</sup> derivative. The derivative was a liquid which moved as single spot (R, 0.62). The corresponding R<sub>f</sub> value for the derivative of an authentic 9-10-dihydroxy tetradecanoic acid was 0.61 in the solvent system, light petroleum : ether : methanol (50 : 40 : 10). The dihydroxy acid has R<sub>f</sub> 0.30 and its methyl ester R<sub>f</sub> 0.25. The hydroxy ester behaved in a similar manner as methyl *threo*-isomer on a tlc plate impregnated with boric acid<sup>24</sup> in the solvent system, light petroleum : ether (60 : 40). Chromic acid as well as potassium permanganate and periodate oxidation<sup>21</sup> yielded azelaic acid as one of the oxidation products. The other fission products may presumably be either pentanal or heptanal if the dihydroxy acid is C<sub>14</sub> or C<sub>16</sub>. Since either of the two fission products could not be isolated in pure form, it is presumed that the fraction B-3 is probably a mixture of *threo*-9-10-dihydroxy C<sub>14</sub> and C<sub>16</sub> acids. The melting point of the acid (m.p. 83-87°) was, however, not sharp.

*Triacetoxy ester B-4 :* Fraction B-4 on hydrolysis afforded a trihydroxy acid (0.29 g) which melted at 99-100°. The acid was identified as *threo*-9,10,16-trihydroxyhexadecanoic acid (aleuritic acid) by the established methods.

*Isolation of free aldehydic terpene acids :* Powdered *Palas* seedlac (100 g) was dissolved in Na<sub>2</sub>CO<sub>3</sub> solution (4%) by warming and diluting the solution to 1 litre with warm water. The cold solution was filtered to remove wax and impurities. The sodium salts of lac resin were then salted out with saturated NaCl solution and allowed to stand overnight. The clear liquor was decanted and the residue washed twice with NaCl solution. The solutions were mixed together and extracted with ether to remove the neutral portion, if any. The liquor portion was then divided into two parts (X) and (Y).

The first part (X) was decomposed with dil. H<sub>2</sub>SO<sub>4</sub>, impurities filtered and the solution extracted with ethyl acetate. The resinous mass thus obtained was examined by tlc, [solvent system, ethyl acetate : acetic acid (100 : 2)], plate sprayed with 2,4-DNPH solution which revealed it to be a mixture of jalaric (R, 0.44), *laccijalaric* (R, 0.65) and an unknown aldehydic acid (R, 0.56). The resinous mass was then digested with chloroform

and 2 fractions, chloroform-soluble and chloroform-insoluble, were separated.

*Chloroform-insoluble fraction :* It was gummy in nature. TLC showed it to be a mixture of mainly jalaric and *laccijalaric* acid (R, 0.42 and 0.65). It was chromatographed over silica gel eluting with increasing proportion of ethyl acetate in benzene and collecting altogether three fractions. The first fraction (R, 0.42) was confirmed as jalaric acid by adopting the established procedures. The second fraction was a mixture of jalaric and *laccijalaric* acids while the third fraction was identified as *laccijalaric* acid (R, 0.65).

*Chloroform-soluble fraction :* It was evaporated to dryness to get a viscous liquid mass which showed a single spot (R, 0.56) on tlc plate sprayed with 2,4-DNPH reagent. The acid could not be crystallised and hence 2,4-DNPH derivative was prepared which melted at 113-115°. IR : 1740 cm<sup>-1</sup> (-CHO), 1725 cm<sup>-1</sup> (-COOH) and 1610, 1590 cm<sup>-1</sup> (-C=C, absence of -OH group).

UV :  $\lambda_{\text{max}}^{\text{EtOH}}$  210 nm and  $\epsilon = 7,280$  (Found : C, 73.18 ; H, 7.30. C<sub>11</sub>H<sub>18</sub>O<sub>8</sub> requires C, 73.17 ; H, 7.31%). A.V. = 228.8, acid equiv. = 246. Mol. formula C<sub>11</sub>H<sub>18</sub>O<sub>8</sub>. It appears that the acid does not resemble either jalaric or *laccijalaric* acid but seems to be a new one. The structure is being studied.

In another lot, the resinous mass containing the mixture of aldehydic acids was treated with excess of aqueous 2,4-DNPH solution. There was immediate separation of yellow precipitate. The mixture was heated and allowed to stand overnight. The precipitate was filtered and repeatedly washed with dil. HCl. The derivative, on recrystallisation from absolute MeOH, melted at 204-207° with decomposition. The weight of the pure derivative was 4.4 g which amounts to 2.68 g of aldehydic acids on the basis of jalaric acid, the major component.

*Isolation of free aleuritic acid :* The second part (Y) of the mother-liquor was made just acidic with dil. H<sub>2</sub>SO<sub>4</sub> and extracted with *n*-butanol. The extract was dried over anhydrous Na<sub>2</sub>SO<sub>4</sub>, distilled and finally evaporated to dryness to get a viscous compound (0.47 g from 200 ml mother liquor). TLC showed it to be a mixture of 2 components (R, 0.22 and 0.79) indicating one of the components as aleuritic acid [R, 0.21 in the solvent system ethyl acetate-acetic acid (100 : 2)]. The amount of aleuritic acid in this compound was estimated by adopting the method of Sengupta<sup>25</sup> and found to be 4.83%.

**Acknowledgement**

The authors are grateful to Dr. T. P. S. Teotia, Director and Sri S. Kumar, Head of the Chemistry Division for permission to publish the paper. The technical assistance of Sri T. K. Saha and Smt. P. Devi is also acknowledged.

References

1. P. K. BOSE, Y. SANKARANARAYANAN and S. C. SENGUPTA, "Chemistry of Lac", Indian Lac Research Institute, Ranchi (India), 1968.
2. W. W. CHRISTIE, F. D. GUNSTON, H. G. PRENTICE, and S. C. Sengupta, *J. Chem. Soc.*, 1964, *Supp. I*, 5838.
3. SUKDEV, *J. Indian Chem. Soc.*, 1974, *51*, 149.
4. R. G. KHURANA, A. N. SINGH, A. B. UPADHYE, V. V. MHASKAR and SUKDEV, *Tetrahedron*, 1970, *26*, 4187.
5. A. N. SINGH, A. B. UPADHYE, V. V. MHASKAR and SUKDEV, *Tetrahedron*, 1974, *30*, 867.
6. J. N. CHATTERJEA, S. C. SENGUPTA, G. S. MISRA and S. C. AGARWAL, *Indian J. Chem.*, 1978, *14B*, 719.
7. N. B. KAMATH and V. B. MAINKAR, *J. Sci. Ind. Res.*, 1955, *14B*, 555.
8. S. C. SENGUPTA and S. K. M. TRIPATHI, *J. Sci. Ind. Res.*, 1959, *1*, B, 535.
9. S. C. SENGUPTA, S. C. AGARWAL and N. PRASAD, *J.O.C.C.A.*, 1979, *62*, 85.
10. H. WEINBERGER and W. H. GARDNER, *Ind. Eng. Chem.*, 1938, *30*, 454.
11. S. C. SENGUPTA, Annual Report, Indian Lac Research Inst., 1955-56, *45*, 1959-60, *23*.
12. A. P. TULLOCH, J. F. T. SPENCER and P. A. J. GORIN, *Canad. J. Chem.*, 1962, *40*, 1828.
13. H. SCHLENK and R. T. HOLMAN, *J. Amer. Chem. Soc.*, 1950, *72*, 5001.
14. L. J. MORRIS, *Chem. and Ind.*, 1962, (Pt 2), 1288; *J. Chromato.*, 1968, *12*, 321.
15. B. DE VRIES, *Chem. and Ind.*, 1962, (Pt 1), 1049; *J. Amer. Oil. Chem. Soc.*, 1963, *40*, 184.
16. N. PRASAD, Ph.D. Thesis, Ranchi University, Ranchi, 1978.
17. CHUIT and HAUSER, *Helv. Chim. Acta*, 1929, *12*, 487.
18. M. MATIC, *Biochem. J.*, 1956, *63*, 168.
19. CHUIT, *Helv. Chim. Acta*, 1928, *9*, 274.
20. DOWNING, KRANZ and MURRAY, *Aust. J. Chem.*, 1960, *13*, 80.
21. E. VON RUDLOFF, *J. Amer. Oil Chem. Soc.*, 1956, *33*, 126.
22. N. S. RAJGOPAL, P. K. SARASWATHY, M. R. SUBBARAM and K. T. ACHAYA, *J. Chromato.*, 1966, *24(1)*, 217.
23. S. C. SENGUPTA and P. K. BOSE, *J. Sci. Ind. Res.*, 1962, *11B*, 458.
24. W. NAGEL and W. MERTENS, *Ber.*, 1936, *69B*, 2050.
25. A. N. SINGH, V. V. MHASKAR and SUKDEV, *Tetrahedron*, 1978, *34*, 595.
26. S. C. SENGUPTA, *J. Sci. Ind. Res.*, 1955, *14B*, 587.

# Paper Electrophoretic Separation and Estimation of the Constituents of Pyrolusite and Indian Coin (Cupro-nickel)<sup>†</sup>

H. G. MUKHERJEE\* and (Miss) ALOKA DEVI

Department of Pure Chemistry, University College of Science, Calcutta-700 009

Manuscript received 18 February 1961, revised 21 January 1962, accepted 21 May 1962

The separation of the main constituents of pyrolusite and Indian coin paper electrophoretically under a potential gradient of 2.2 volts/cm using 0.1 M sodium acetate and 0.1 M sodium formate as carrier electrolyte on Whatman Paper No. 1 (3 cm × 40 cm) shows that iron and manganese from pyrolusite and copper and nickel from cupro-nickel Indian coin can be successfully separated and determined spectrophotometrically after eluting from the paper. Advantage of this method over existing methods is that separation is possible in 15 min.

**SUCCESSFUL** separations<sup>1-4</sup> of Fe(III) from Co(II), Mn(II) and Ni(II); Pb(II) from Co(II) and Mn(II); Bi(III) from Co(II) and Mn(II); Hg(II) from Cu(II), Mn(II) and Co(II); and Cu(II) from Co(II) using 0.1 M sodium acetate solution as supporting electrolyte, and Cu(II) from Mn(II), Co(II), Ni(II); Fe(III) from Co(II), Ni(II), Mn(II) using 0.1 M sodium formate solution as supporting electrolyte by paper electrophoresis have been achieved. This prompted us to attempt an analysis of pyrolusite and Indian coin (cupro-nickel) by paper electrophoresis and a subsequent estimation of Fe, Mn and Cu, Ni.

## Ore analysis :

**Preparation of migrant solution (pyrolusite)<sup>5-8</sup> :** Pyrolusite (0.4987 g) was decomposed by 15 ml conc. HCl by evaporating to almost dryness. 15 ml dil. HCl (1 : 1) was added, heated to dissolve the residue and evaporated. The soluble residue was dissolved in minimum amount of dil. HCl. The solution was filtered in a 50 ml volumetric flask. The volume of the solution was made up with dil. HCl.

**Paper electrophoresis of the migrant :** A drop of pyrolusite solution ( $1.2 \times 10^{-4}$  g) having iron and manganese as the main constituents was electrophoresed using 0.1 N sodium acetate as the supporting electrolyte. Apparatus used for the separation of iron and manganese of pyrolusite was a Durrum's type vertical electrophoretic instrument. Paper strips (3 cm × 40 cm) from Whatman No. 1 were used as the supporting medium, 800 volt applied and the paper strip was taken out after 15 min run and dried. The zones of the migrants were identified with the help of specific reagent, potassium ferrocyanide for iron and 3 N potassium hydroxide solution for manganese.

It was found that clean separation of iron and manganese was possible. Separation sequences and position of migrating zone from the point of

application after 15 min run is shown in Table I, where '+' sign indicates migration towards the anode and '-' sign towards the cathode.

TABLE I—CARRIER ELECTROLYTE 0.1 N SODIUM ACETATE

Migrant	Separation sequences of the migrant and the distance traversed by the zone in cm	
	Iron	Manganese
Pyrolusite	+0.9 to -0.9	-1.9 to -2.7

**Estimation of iron and manganese :** After electrophoresis, the electrophoregram was dried and the portions of the strip containing iron and manganese were cut out from it after matching the said portions against the stained marked strip

**Iron (direct method) :** The region of the strip containing iron was treated with 2 N HCl and evaporated almost to dryness. The residue was treated with 0.8 N H<sub>2</sub>SO<sub>4</sub>, warmed and filtered into a 25 ml measuring flask. A little of 0.8 N H<sub>2</sub>SO<sub>4</sub> was added and washings of the strips were poured into the measuring flask. The volume was made up to the mark with 0.8 N H<sub>2</sub>SO<sub>4</sub>.

A blank solution was prepared taking the same paper strip of identical dimension, having no iron, which was treated with 2 N HCl and 0.8 N H<sub>2</sub>SO<sub>4</sub> as before.

The optical density of the eluted iron was measured against this blank at the wave length of 305 mμ and found to be 0.012.

In this method, the amount of iron present in pyrolusite was calculated using the equation

$$C = \frac{O.D.}{\epsilon} = \frac{\text{Optical density}}{\text{Extinction co-efficient}}$$

C = Concentration in molarity  
 $\epsilon = 2180^{-1}$

<sup>†</sup> Paper presented at the Convention of Chemists (1960) held at I. I. T., Bombay.



**Manganese ( $KIO_4$  method):** Portion of the electrophoregram containing manganese was treated with  $2 N H_2SO_4$  and manganese was extracted in the same way as iron. To this eluted solution, 5 ml 85%  $H_3PO_4$ , 20 mg  $AgNO_3$  and 0.15 g potassium meta-periodate were added; heated to boiling with stirring and kept at slightly below the boiling point for 1 hr. It was cooled and diluted to 50 ml in a volumetric flask.

The blank solution was prepared, as in the case of iron and similarly treated with  $H_2SO_4$ ,  $H_3PO_4$ ,  $AgNO_3$  and  $KIO_4$ . The optical density of the eluted manganese solution was measured against this blank solution at 525  $m\mu$  and found to be 0.04.

A standard solution of manganous sulphate was prepared and a calibration curve for manganese was drawn from which the concentration of this eluted solution was calculated.

The percentages of iron and manganese in pyrolusite were calculated as given in Table 2.

TABLE 2

Constituents in pyrolusite as oxide	Optical densities of the eluted solutions after separation by paper electrophoresis	Concentration of the eluted solutions calculated from spectrophotometric method in terms of Fe and Mn in g/lit.	Percentage of Fe and Mn calculated from molar concentration, volume of migrants, volume of diluents and weight of pyrolusite taken	Actual % of the constituents as Fe and Mn calculated by standard method
Fe	0.012	$3 \times 10^{-2}$	6.17%	6.44%
Mn	0.04	$11.80 \times 10^{-2}$	48.45%	49.26%

**Standard methods for estimation of iron and manganese:** Iron and manganese were estimated titrimetrically using standard dichromate as usual.

#### Alloy analysis:

**Preparation of Indian coin solution** The coin (2.4937 g) was taken in a conical flask and 10 ml conc.  $HNO_3$  was added. It was then heated and allowed to react till all the alloy dissolved. The solution was diluted with water, 0.5 g urea added and heated nearly to boiling to decompose the nitrous fumes. The solution was transferred quantitatively into a 100 ml volumetric flask and the volume was made up to the mark with water.

**Experimental procedure:** Quantitative separation of the constituents of coin was possible electrophoretically using 0.1  $M$  sodium formate as carrier electrolyte. The vertical apparatus was used for the paper electrophoretic separation of the main constituents of the coin solution. Potential gradient of 2.2 volts/cm for 3 hr run was maintained. After electrophoresis the electrophoregram was dried and developed carefully avoiding spreading of the zones. The electrophoregram was developed with yellow ammonium sulphide. A brown band for  $Cu(II)$  and a black one for  $Ni(II)$  were located and an attempt was made to estimate copper and nickel from the band spectrophotometrically.

The separation of the principal constituents (copper and nickel) is shown in Table 3, where '+' stands for anionic movement and '-' for cationic movement. The solution used for separation was 0.004 ml.

TABLE 3—CARRIER ELECTROLYTE 0.1  $M$  SODIUM FORMATE

Migrant	Separation sequences of the migrant and the distance traversed by the zone in cm	
	Copper	Nickel
Coin	-0.8 to -1.9	-3.8 to -5.3

**Estimation of copper ("Neo-cuproin" method):** After electrophoresis, the electrophoregram was dried and the portion of the strip containing copper was cut out from the electrophoregram after matching the said portion against the stained marked strip.

The region of the strip containing copper was treated with  $2 N H_2SO_4$  and copper was extracted as in the case of iron. Total volume was 15 ml. From the extracted solution 5 ml was taken. To the 5 ml solution in a separatory funnel, 5 ml of 10% hydroxyl-ammonium chloride solution to reduce  $Cu(II)$  to  $Cu(I)$  and 5 ml of a 30% sodium citrate solution to complex any other metals present, were added. Ammonia solution was then added for adjustment of the pH to about 4 (with congo red paper), followed by 5 ml of 0.1% solution of "neocuproin" (2,9-methyl-1,10-phenanthroline) in absolute ethanol. It was shaken for about 30 sec with 5 ml of chloroform and the layers were allowed to separate. A further extraction with 2.5 ml of chloroform was carried out. The optical density at 457  $m\mu$  against a reagent blank was measured and found to be 0.575.

A standard solution of copper sulphate was prepared and a calibration curve for copper was drawn from which the extinction coefficient of copper was calculated.

Using this extinction co-efficient the concentration of copper in the eluted solution was calculated. The percentage of copper in coin (25 paise) was then calculated as given in Table 4.

TABLE 4

	Optical densities of the eluted solution after separation by paper electrophoresis	Concentration of the eluted solution calculated from spectrophotometric method in terms of Cu and Ni in g mole/lit	Percentage of Cu and Ni calculated from molar concentration, volume of migrant, volume of diluents and weight of coin taken	Actual % of Cu and Ni calculated by standard method analysis
Cu	0.76	$7.56 \times 10^{-2}$	72%	74.2%
Ni	0.009	$0.95 \times 10^{-2}$	28.1%	28.8%

**Estimation of nickel (dimethylglyoxime method):** The region of the strip containing nickel was treated with  $2 N H_2SO_4$  and nickel was extracted in

the usual procedure. The extracted volume of nickel solution was 10 ml. The solution was taken in a 50 ml volumetric flask. To 10 ml of the solution 5 ml of 10% citric acid solution was added and neutralised with ammonia, a few drops of which was added in excess ( $pH > 7.5$ ). Then 3 ml of 1% dimethyl glyoxime in ethanol was added. The solution was extracted with three 3 ml portion of chloroform, shaking for 30 sec each time. The combined chloroform was shaken with 6 ml of 0.5 M ammonia (1:30). The ammonia washing was shaken with 2 ml of chloroform and the latter was added to the main chloroform extract. The nickel was returned to the ionic state by shaking the chloroform extract vigorously for 1 min with two 5 ml portions of 0.5 M HCl. The HCl solution was transferred to a 50 ml volumetric flask, diluted to about 50 ml, 1 ml of saturated  $Br_2$  water added, followed by 2 ml of conc. ammonia. 1 ml of 1% dimethylglyoxime solution was added and diluted up to the mark. After 5 min the optical density at 445 m $\mu$  against a blank was measured and found to be 0.009.

A standard solution of nickel sulphate was prepared to obtain a calibration curve for nickel.

The extinction co-efficient of nickel was used to calculate its concentration in the eluted solution. The percentage of nickel in Indian coin (25 paise) was then calculated from the concentration term as shown in Table 4.

Using the equation,

$$O.D. = E.C. \cdot l$$

the extinction co-efficient of copper and nickel were calculated. The extinction co-efficients (E)  $0.76 \times 10^4$  for copper and  $0.094 \times 10^4$  for nickel were obtained.

So, the amounts of copper and nickel present in the coin (25 paise) were calculated by the equation,

$$C = \frac{O.D.}{E} \text{ in molarity}$$

*Standard method for estimation of copper and nickel:* Copper was estimated gravimetrically using ammonium thiocyanate and nickel using dimethylglyoxime as usual.

It can be said from the experimental data that paper electrophoresis technique can equally be applied for analysis of pyrolusite and Indian coin.

#### Acknowledgement

The authors are thankful to Professor N. N. Ghosh of Chemistry Department, Calcutta University and to Dr. N. C. Saha, Dr. E. V. Srisankar, Mr. P. C. Mondal and Mr. Bardhan of Nuclear Chemistry Department, Saha Institute of Nuclear Physics, Calcutta for valuable advice.

#### References

1. S. NAKANO, *J. Chem. Soc., Japan*, 1962, 73, 912
2. B. K. KORCHEMNAYA, V. I. NAUMOVA and A. N. BRMAKOV, *Zh. Anal. Khim.*, 1969, 24, 842.
3. DANUTA MALYSZ, *Acta Polon. Pharm.*, 1960, 17, 221.
4. M. PATTANAYAK, Study of Metal Ions by Paper Electrophoresis, Ph.D. Dissertation, 1976, University of Calcutta.
5. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", 3rd Edn., 1961, p. 299, 287 and 787.
6. E. B. SANDELL, "Colorimetric Determination of Traces of Metals", 1944, Vol. III, 814.
7. J. WEISS, A. O. ALLEN and H. A. SCHWARZ, "Proc Intern. Conf. Peaceful Uses Atomic Energy", United Nations, New York, 1956, p. 14, 179.
8. R. H. SCHULER and A. O. ALLEN, *J. Chem. Phys.*, 1966, 24, 56

# NOTES

## Nickel(II) Complexes with Substituted Amino Benzothiazoles

RAJENDRA P. MISRA and S. GURU\*

Department of Chemistry, Ravenshaw College, Cuttack-753 008

Manuscript received 7 August 1981, accepted 1 May 1982

In our recent work<sup>1,2</sup> we reported the synthesis of a series of Co(II), Cu(II) and Hg(II) complexes with substituted amino benzothiazoles. As an extension of the previous studies, the present communication describes the preparation and characterisation of some Ni(II) complexes with the monodentate ligands, 2-amino-6-methyl benzothiazole and 2-amino-6-chloro benzothiazole.

### Experimental

All the chemicals used were of AnalaR grade. The substituted amino benzothiazoles have been synthesised by standard procedure<sup>3</sup>.

**Preparation of the complexes:** Methanolic solution of the nickel(II) salts were reacted separately with methanolic solution of the substituted amino benzothiazoles in 1 : 2 ratio and refluxed for about 2 hr. Crystalline compounds separated out on cooling. These were filtered, washed with methanol followed by ether and dried *in vacuo*.

Metal contents of the complexes were estimated gravimetrically as dimethyl glyoximate. Nitrogen and sulphur were estimated by standard procedure. Conductance was measured in 10<sup>-3</sup> M acetone solution using Toshniwal conductivity bridge. IR

spectra were recorded in KBr phase using Unicam Sp-1025 spectrophotometer. Electronic spectra of the complexes in chloroform solution were recorded by using Hilger Watt Uvispeck spectrophotometer.

### Results and Discussion

All the eight complexes reported in the present investigation are of the composition [Ni(L<sub>2</sub> or L'<sub>2</sub>)X<sub>2</sub>] and [Ni(L<sub>2</sub> or L'<sub>2</sub>)Y<sub>2</sub>], where X=Cl<sup>-</sup>, NO<sub>3</sub><sup>-</sup>, SCN<sup>-</sup> and Y=ClO<sub>4</sub><sup>-</sup>; L=2-amino-6-methyl benzothiazole and L'=2-amino-6-chloro benzothiazole. All the complexes of the composition [Ni(L<sub>2</sub> or L'<sub>2</sub>)X<sub>2</sub>] are yellow to deep brown in colour whereas the two perchlorate complexes are green in colour. The complexes have low melting points and are soluble in acetone in which medium they are found to be non-electrolytes, the  $\Delta_M$  being in the range of 10-25 mhos cm<sup>2</sup> except for the perchlorate complexes. The  $\Delta_M$  values of the two perchlorate complexes are found to be around 230 mhos cm<sup>2</sup> indicating 1 : 2 electrolytic nature of these complexes.

The ir spectra show a sharp peak at ~815 cm<sup>-1</sup> in the free ligands which can be assigned<sup>1</sup> to  $\nu(C-S)$  vibrations. On complexation, this frequency is shifted down to lower frequency region of ~800 cm<sup>-1</sup> indicating the bonding of the benzothiazole molecule to metal ions through ring sulphur atom. The bands observed<sup>4</sup> around 1535 and ~3250 cm<sup>-1</sup> in the free ligands are due to  $\nu(C=N)$  and  $\nu(N-H)$  vibrations, respectively. No change of these bands has been noticed in the complexes which conclusively proves that both the

TABLE 1—ANALYSIS, CONDUCTANCE, MAGNETIC SUSCEPTIBILITY AND IR SPECTRAL DATA

Compound	%Metal Found (Calcd.)	%N Found (Calcd.)	%S Found (Calcd.)	$\Delta_M$ mhos cm <sup>2</sup>	$\mu_{eff}$ B.M.	$\nu(C-S)$
[NiL <sub>2</sub> Cl <sub>2</sub> ]	12.74 (12.88)	12.08 (12.28)	18.82 (18.98)	10.8	—	808
[NiL' <sub>2</sub> Cl <sub>2</sub> ]	11.60 (11.77)	11.12 (11.28)	12.70 (12.88)	11.6	—	795
[NiL <sub>2</sub> (NO <sub>3</sub> ) <sub>2</sub> ]	11.41 (11.49)	16.34 (16.44)	12.40 (12.58)	16.5	—	800
[NiL' <sub>2</sub> (NO <sub>3</sub> ) <sub>2</sub> ]	10.82 (10.84)	15.10 (15.22)	11.42 (11.60)	18.0	—	800
[NiL <sub>2</sub> (SON) <sub>2</sub> ]	11.58 (11.67)	16.59 (16.71)	25.84 (25.46)	22.4	—	810
[NiL' <sub>2</sub> (SON) <sub>2</sub> ]	10.86 (10.80)	15.36 (15.45)	22.40 (22.54)	20.8	—	805
[NiL <sub>2</sub> (ClO <sub>4</sub> ) <sub>2</sub> ]	6.80 (6.42)	12.16 (12.28)	13.92 (14.01)	225.0	3.80	800
[NiL' <sub>2</sub> (ClO <sub>4</sub> ) <sub>2</sub> ]	5.72 (5.89)	11.12 (11.28)	12.72 (12.85)	228.0	3.60	795

L=2-amino-6-methyl benzothiazole.

L'=2-amino-6-chloro benzothiazole.

\* Author for correspondence.

endo- and exo-cyclic nitrogen atoms are not bonded to the metal ions. In the nitrate complexes, absorption bands appear in the region  $\sim 1280$  and  $1400\text{ cm}^{-1}$ . The position of  $\nu_4$  and  $\nu_2$  and their separation ( $\Delta\nu$ ) of  $\sim 120\text{ cm}^{-1}$  suggest<sup>8-9</sup> the nitrate group to be monodentate in the two complexes. The thiocyanato complexes have two sharp bands at  $\sim 2080$  and  $735\text{ cm}^{-1}$  attributable<sup>10</sup> to  $\nu(\text{C}\equiv\text{N})$  and  $\nu(\text{C}-\text{S})$  vibrations, respectively of N-bonded terminal thiocyanato group. In the present investigation, an increase of  $30\text{--}40\text{ cm}^{-1}$  relative to the free thiocyanate ion is indicative of N-bonded terminal thiocyanate group on the basis of previous observations<sup>10</sup>. The appearance of a broad hump in the region  $1040\text{--}1150\text{ cm}^{-1}$  indicates<sup>11-12</sup> the presence of ionic perchlorate group in the two perchlorate complexes and this is also corroborated by the molar conductance data of these complexes.

The chloro-, nitrate- and thiocyanato complexes are found to be diamagnetic. The perchlorate complexes have high magnetic moments (3.6 to 3.8 B. M.) indicating<sup>13</sup> a tetrahedral environment.

Visible electronic spectra of the chloro-, nitrate- and thiocyanato nickel(II) complexes show absorption bands at  $\sim 19800$  and  $20000\text{ cm}^{-1}$  and have relatively high extinction coefficient values, indicative of a square configuration. In case of the perchlorate complexes, two bands are observed at  $\sim 15200(180)$  and  $8100(35)\text{ cm}^{-1}$  attributable to  ${}^3\text{T}_{1g}(\text{F}) \rightarrow {}^3\text{T}_{1g}(\text{P})$  and  ${}^3\text{T}_{1g}(\text{F}) \rightarrow {}^3\text{A}_{1g}$  transitions, respectively. The high molar absorptivity values of the former band and the high magnetic moment values suggest<sup>14</sup> a possible tetrahedral geometry for the two complexes.

#### Acknowledgement

One of the authors (R. P. M.) is indebted to Dr. D. C. Pati, Department of Chemistry, B. J. B. College, Bhubaneswar for help.

#### References

1. RAJENDRA P. MISRA, BIPIN B. MOHAPATRA and S. GURU, *J. Indian Chem. Soc.*, 1979, 56, 832.
2. RAJENDRA P. MISRA, BIPIN B. MOHAPATRA and S. GURU, *J. Indian Chem. Soc.*, 1981, 58, 809.
3. J. L. WOOD, "Inorganic Reactions", (Ed.) ROGER ADAMS, 1969, Vol. 8, p. 240.
4. N. C. MISHRA, B. B. MOHAPATRA and S. GURU, *J. Indian Chem. Soc.*, 1978, 55, 437.
5. R. V. BRAGGETT, W. O. BUTTNER and H. M. HANDLER, *Inorg. Chem.*, 1966, 5, 879.
6. N. LUGAN and W. SIMPSON, *Spectrochem. Acta*, 1965, 21, 857.
7. A. B. P. LEVER, *Inorg. Chem.*, 1935, 4, 1042.
8. K. SWAMINATHAN and H. M. N. H. IRVING, *J. Inorg. Nuclear Chem.*, 1962, 26, 1391.
9. A. TURCO and C. PECILE, *Nature*, 1961, 191, 86.
10. A. TRAMER, *J. Chim. Phys.*, 1969, 59, 282.
11. G. DWYER, J. G. HARTLEY and L. M. VENANZI, *J. Chem. Soc.*, (A), 1966, 1985.
12. K. NAKAMOTO, "Infrared Spectra of Inorganic and Coordination Compounds", Wiley, New York, 1970.
13. J. GOPALKRISHNA, A. BAVI and C. O. PATEL, *Bull. Chem. Soc., Japan*, 1967, 40, 791.
14. F. A. COTTON and G. WILKINSON, "Advanced Inorganic Chemistry", Interscience, 2nd Edn., 1968, 884.

15. P. K. PANDA and B. K. MOHAPATRA, *J. Indian Chem. Soc.*, 1980, 57, 329.
16. D. M. L. GOODGAME, M. GOODGAME and F. A. COTTON, *J. Amer. Chem. Soc.*, 1961, 83, 4161.

### Complexes of Co(II), Ni(II), Cu(II), Zn(II), Cd(II) and Hg(II) with Chelating Bidentate Schiff's Base

BIPIN B. MAHAPATRA\*, S. M. MAHAPATRA,  
S. K. PUJARI and A. CHIRANJEEVI

Post-Graduate Department of Chemistry, G. M. College,  
Sambalpur-768 004

Manuscript received 22 May 1981, revised 2 December 1981,  
accepted 23 May 1982

WE have been trying to synthesise complexes of rare coordination number through complexation of polydentate ligands with divalent metal salts. Earlier, we reported<sup>1-3</sup> metal complexes with bi-, tri- and tetradentate ligands having oxygen-nitrogen oxygen-sulphur, nitrogen-sulphur and oxygen-nitrogen-sulphur as the potential bonding sites. The present communication describes the synthesis and characterisation of six metal complexes with a new bidentate Schiff's base derived from benzoin and aniline.

#### Experimental

All the chemicals were analytical reagent grade products.

**Preparation of the Schiff's base :** To a methanolic solution of benzoin (2.12 g) and aniline (1.0 ml) was added anhydrous sodium acetate (4.0 g) and the mixture was refluxed for 1 hr over a water bath. The hot solution was poured into ice-cold water when a yellowish crystalline precipitate of the Schiff's base separated out. It was filtered, washed with water, dried and recrystallised from rectified spirit, m.p.  $130^\circ$ , yield 60%. (Found : C, 82.64; H, 5.52; N, 4.84.  $\text{C}_{20}\text{H}_{14}\text{ON}$  requires C, 83.91; H, 5.59; N, 4.89 %)

**Preparation of the complexes :** Ethanolic solutions of the metallic chlorides were treated separately with ethanolic solution of the Schiff's base in 1 : 2 molar ratio followed by drop-wise addition of ammonia when metallic chelates separated out. These were filtered, washed with ethanol followed by ether and dried *in vacuo*.

Metal content of the complexes was estimated by complexometric EDTA titration method. The conductance measurements were carried out with a Toshniwal conductivity bridge in  $1 \times 10^{-3}\text{ M}$  acetone solution of the complexes. Magnetic susceptibility measurements were made at room temperature using Gouy method. Electronic spectra were recorded in  $1 \times 10^{-3}\text{ M}$  chloroform solution of the complexes using Hilger Watt Uvispek spectrophotometer. The infrared spectra on Nujol mulls

TABLE 1—ANALYSIS, CONDUCTANCE, MAGNETIC SUSCEPTIBILITY AND IR SPECTRAL DATA

Compound	m.p. °C	Colour	% metal Found (Calcd.)	% N Found (Calcd.)	$\Lambda_M$ mhos cm <sup>2</sup>	$\mu_{eff}$ B.M.	$\nu(C-O)$	$\nu(C=N)$
LH	180	Yellow	—	4.85 (4.89)	—	—	1210	1600
CoL <sub>2</sub> B <sub>2</sub>	142	Pink	8.81 (8.86)	4.17 (4.21)	14.5	4.85	1900	1590
NiL <sub>2</sub> B <sub>2</sub>	280	Light green	8.75 (8.82)	4.18 (4.22)	12.0	3.00	1900	1585
CuL <sub>2</sub>	281	Blue	9.93 (10.08)	4.88 (4.41)	10.6	1.8	1205	1590
ZnL <sub>2</sub>	924	White	10.15 (10.38)	4.85 (4.40)	15.0	—	1900	1590
CdL <sub>2</sub>	199	White	16.88 (16.47)	8.95 (4.10)	12.5	—	1900	1590
HgL <sub>2</sub>	126	Yellowish white	25.78 (26.08)	8.52 (8.63)	10.0	—	1905	1595

LH = Schiff's base derived from benzoin and aniline

B = H<sub>2</sub>O.

were recorded using Unicam SP 200 spectrophotometer in the region 4000-650 cm<sup>-1</sup>. Analytical, conductance, magnetic susceptibility and ir spectral data are recorded in Table 1.

### Results and Discussion

Complexes reported in the present investigation have the composition [ML<sub>2</sub>B<sub>2</sub>] and [M'L<sub>2</sub>] where M = Co(II), Ni(II); M' = Cu(II), Zn(II), Cd(II), Hg(II); LH = Schiff's base derived from benzoin and aniline and B = H<sub>2</sub>O. All the six complexes have fairly low melting points and low conductance values (Table 1), indicating their non-electrolytic nature. Magnetic moment values show the presence of three, two and one unpaired electrons in case of Co(II), Ni(II) and Cu(II) complexes, respectively.

The ir spectra of the Schiff's base and the metal complexes are quite illustrative. It can function as a bidentate ligand with the hydroxy oxygen and the imino nitrogen atom as the principal bonding sites. The  $\nu(C-O)$  vibration in the ligand appears at 1210 cm<sup>-1</sup>. The decrease of this frequency by 10-15 cm<sup>-1</sup> in the metal chelate shows the bonding of the hydroxylic oxygen atom to the metal ions. Coordination of the azomethine nitrogen atom to the metal ions is probably indicated by the shift of  $\nu(C=N)$  frequency to the lower side<sup>9</sup>. In the ir spectra of the Schiff's base, a strong band due to  $\nu(C=N)$  appears at 1600 cm<sup>-1</sup> whereas in the complexes this band is observed at ~1500 cm<sup>-1</sup>. In case of Co(II) and Ni(II) complexes, a broad hump is observed at ~3450 cm<sup>-1</sup> indicating the presence of coordinated water<sup>10,11</sup>.

In the electronic spectra of Ni(II) complex, three bands appear at 8.5(7), 13.5(7.5) and 25.0(18) kK region, assignable to  ${}^3A_{2g} \rightarrow {}^3T_{2g}(F)$ ,  ${}^3A_{2g} \rightarrow {}^3T_{1g}(F)$  and  ${}^3A_{2g} \rightarrow {}^3E_g(P)$  transitions, respectively. Cobalt(II) complex exhibits two absorption bands at 21(26) and 9.0(10) kK regions attributable to  ${}^4T_{1g}(F) \rightarrow {}^4T_{1g}(P)$  and  ${}^4T_{1g}(F) \rightarrow {}^4T_{2g}(F)$  transitions,

respectively. Molar absorptivity values, position of absorption bands and magnetic moment values indicate high spin octahedral configuration for these complexes. One broad band is observed in case of Cu(II) complex at ~17.0(30) kK region. This broad band is a combination of  ${}^2B_{1g} \rightarrow {}^2A_{1g}$ ,  ${}^2B_{1g} \rightarrow {}^2B_{2g}$  and  ${}^2B_{1g} \rightarrow {}^2E_g$  transitions corresponding to  $D_{4h}$  symmetry, indicating most probably a square planar configuration<sup>12-14</sup> for this complex.

From analysis, conductance and ir spectral studies, Zn(II), Cd(II) and Hg(II) complexes are found to be four coordinated having a tetrahedral environment around the metal ions.

### References

1. B. B. MAHAPATRA, B. K. MAHAPATRA and S. GURU, *J. Inorg. Nuclear Chem.*, 1977, 39, 2291.
2. B. B. MAHAPATRA, B. K. MAHAPATRA and S. GURU, *Acta Chimica*, 1977, 94, 191.
3. B. B. MAHAPATRA, B. K. MAHAPATRA and S. GURU, *J. Inorg. Nuclear Chem.*, 1978, 40, 134.
4. B. B. MAHAPATRA, B. K. MAHAPATRA and S. GURU, *Indian J. Chem.*, 1978, 16A, 445.
5. B. B. MAHAPATRA, B. K. MAHAPATRA and S. GURU, *Indian J. Chem.*, 1978, 16A, 923.
6. B. B. MAHAPATRA, B. K. MAHAPATRA and S. GURU, *J. Indian Chem. Soc.*, 1978, 55, 889.
7. B. B. MAHAPATRA, N. C. MISRA and S. GURU, *J. Inorg. Nuclear Chem.*, 1979, 41, 408.
8. B. B. MAHAPATRA, S. S. DASH and S. K. PUJARI, *J. Indian Chem. Soc.*, 1980, 57, 98.
9. J. E. COVACIS, *Spectrochim. Acta*, 1967, 23(A), 183.
10. K. NAKAMATO, "Infrared Spectra of Inorganic and Coordination Compounds", John Wiley, New York, 1963.
11. I. GAMAQ, *Bull. Chem. Soc., Japan*, 1961, 34, 780.
12. J. BJERRUM, C. J. BALLAUSSEN and C. K. JORGENSEN, *Acta Chim. Scand.*, 1954, 8, 1975.
13. C. J. BALLAUSSEN, "Introduction to Ligand Field Theory", McGraw Hill Book Company, Inc., N. Y., 1962, p. 268.
14. W. BYRNS, A. B. P. LEVER and R. V. PARISH, *Inorg. Chem.*, 1968, 7, 1885.

# Binuclear Oxofluoro Complex of Quinquevalent Molybdenum

M. C. CHAKRAVORTI, A. K. BERA

and

P. K. BHARADWAJ

Department of Chemistry, Indian Institute of Technology,  
Kharagpur-721 802Manuscript received 18 June 1981, revised 5 December 1981,  
accepted 23 May 1982

VERY little work has been done on the oxofluoro complexes of Mo(V) compared to an extensive volume of work on the analogous oxochloro complexes. It is well known that paramagnetic oxochloromolybdates(V) hydrolyse as the acid concentration is decreased and ultimately dimerise to give oxo bridged diamagnetic or very weakly paramagnetic complexes. There are a few reports<sup>1-3</sup> till now on the preparation of oxo bridged Mo(V) fluoro complexes, but none of these has been adequately characterised. We have studied the magnetic susceptibility of  $[\text{MoOF}_6]^{3-}$  at different HF concentrations and have isolated a binuclear complex  $\text{K}_4[\text{Mo}_2\text{O}_4\text{F}_6] \cdot 2\text{H}_2\text{O}$ .

## Experimental

$\text{K}_4[\text{MoOF}_6]$  and  $\text{MoO}(\text{OH})_3$  were prepared by methods reported earlier<sup>1,4</sup>. Molybdenum was analysed gravimetrically as oxinate<sup>5</sup>, after decomposing the sample with fuming  $\text{HNO}_3$  and  $\text{H}_2\text{SO}_4$ . The methods of analysis of potassium and fluorine and the determination of the oxidation state of molybdenum (by oxidation with dichromate) were described earlier<sup>6,7</sup>.

Magnetic susceptibility was determined by Gouy method using  $\text{Hg}[\text{Co}(\text{NCS})_4]$  as calibrant. The diamagnetic corrections were taken from standard sources<sup>8</sup>. The magnetic susceptibility of  $\text{K}_4[\text{MoOF}_6]$  or  $\text{MoO}(\text{OH})_3$  in aqueous HF was measured at 30° using polythene tubes having ebonite stopper. The molybdenum content in aliquots was determined by oxinate method [after removal of  $\text{F}^-$  and oxidation of Mo(V)]. That all molybdenum was practically present as Mo(V) was checked by the determination of Mo(V) in aliquots by oxidation with dichromate.

Infrared spectra in the range of 4000-650  $\text{cm}^{-1}$  were recorded using a Perkin Elmer spectrophotometer No. 257. Electronic spectra were recorded with Carl Zeiss DMR-21 and Carl Zeiss, Jena VSU2-P spectrophotometers.

**Preparation of  $\text{K}_4[\text{Mo}_2\text{O}_4\text{F}_6] \cdot 2\text{H}_2\text{O}$ :** Potassium fluoride (14.0 g; 0.24 mole) dissolved in 2% HF was added to a concentrated solution of  $\text{MoO}(\text{OH})_3$  (1.0 g; 0.006 mole) in 2% HF. The brown red micro crystalline substance was separated by filtration and dried by pressing between filter papers and then keeping in a desiccator over  $\text{H}_2\text{SO}_4$  and NaOH. The yield was 0.5 g (29%). (Anal. Found :

Mo, 33.6; F, 20.0; K, 27.7. Calcd. for  $\text{K}_4[\text{Mo}_2\text{O}_4\text{F}_6] \cdot 2\text{H}_2\text{O}$ ; Mo, 34.1; F, 20.3; K, 27.8%). The same compound was also obtained by mixing together aqueous solutions of  $\text{K}_4[\text{MoOF}_6]$  (0.3 g) and KF (2.4 g).

## Results and Discussion

The magnetic susceptibility of  $\text{K}_4[\text{MoOF}_6]$  in HF medium has been measured as a function of the acid concentration. Because of the limited solubility of  $\text{K}_4[\text{MoOF}_6]$  in dilute HF we preferred to use  $\text{MoO}(\text{OH})_3$ . It is known<sup>1</sup> that  $\text{MoO}(\text{OH})_3$  dissolves in 40% HF from which green crystalline salts  $\text{M}_4[\text{MoOF}_6]$  can be isolated by the addition of alkali metal fluorides. In a few representative cases it was checked that equimolecular solutions of  $\text{K}_4[\text{MoOF}_6]$  and of  $\text{MoO}(\text{OH})_3$  in HF medium of identical concentration registered almost the same magnetic susceptibility.

The molar magnetic susceptibility of a solution of  $\text{MoO}(\text{OH})_3$  or  $\text{K}_4[\text{MoOF}_6]$  in 40% HF was found to be about  $1310 \times 10^{-6}$  cgs units and the magnetic moment was 1.79 B.M. As the acid concentration was lowered the solutions turned from light green to brownish red and the susceptibility decreased. Ultimately, at an acid concentration of about 3%, the solution was diamagnetic. This behaviour of  $[\text{MoOF}_6]^{3-}$  is very similar<sup>9</sup> to that of  $[\text{MoOCl}_6]^{3-}$ . The susceptibility of solutions of  $\text{MoO}(\text{OH})_3$  in dilute HF did not change on standing for half an hour.

$\text{K}_4[\text{Mo}_2\text{O}_4\text{F}_6] \cdot 2\text{H}_2\text{O}$  is soluble in water from which it can be recrystallised. It loses the two molecules of water slowly at 140°. The molecular conductance of  $1 \times 10^{-3} M$  aqueous solution ( $650 \text{ ohm}^{-1} \text{ mol}^{-1} \text{ cm}^2$ ) at 30° indicates some dissociation of the anion. The complex is very weakly paramagnetic ( $\mu_{\text{eff}}$  is 0.20 B.M. at 30°). IR spectra give bands due to  $\nu(\text{OH})$  and  $\delta(\text{H}_2\text{O})$  at about 3500 and 1650  $\text{cm}^{-1}$ . The terminal  $\nu(\text{Mo}=\text{O})$  modes appear at 950 vs, 925 vw and 905 m, while two bridging  $\text{MoO}_2\text{Mo}$  modes occur at 845 vs and 740 vs which agree with the presence of a bent  $\text{MoO}_2\text{Mo}$  bridge with the  $\text{Mo}=\text{O}$  groups on the same side of the bridge (i.e., *cis*)<sup>10</sup>.

Like other complexes containing  $\text{Mo}_2\text{O}_5^{2+}$  the electronic spectra of  $\text{K}_4[\text{Mo}_2\text{O}_4\text{F}_6] \cdot 2\text{H}_2\text{O}$  do not display the low energy transitions which are characteristics of monomeric  $\text{MoO}^{5+}$  complexes<sup>10</sup>. The reflectance or the Nujol mull spectra gave two bands at about 20,000 and 23,000  $\text{cm}^{-1}$ .

## References

1. M. C. CHAKRAVORTI and S. C. PANDIT, *J. Coord. Chem.*, 1976, 5, 85.
2. R. MATTHE and G. LUX, *Angew. Chem.*, 1974, 86, 598.
3. G. E. BLOKHINA, I. N. BELYAEV, A. OPALOVSKI and L. I. BELAN, *Russ. J. Inorg. Chem.*, 1979, 17, 1113.
4. W. G. PALMER, "Experimental Inorganic Chemistry", The University Press, Cambridge, 1964, p. 406.

5. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", The English Language Book Society and Longman, 1978, p. 472.
6. M. C. CHAKRAVORTI and S. C. PANDIT, *J. Inorg. Nuclear Chem.*, 1974, **36**, 2265.
7. M. C. CHAKRAVORTI and S. C. PANDIT, *J. Inorg. Nuclear Chem.*, 1978, **35**, 8644.
8. J. LEWIS and R. G. WILKINS, "Modern Coordination Chemistry", Interscience Publishers, Inc., New York, 1960, p. 408.
9. L. SACCONI and R. GINI, *J. Amer. Chem. Soc.*, 1964, **76**, 4289.
10. E. I. STIEFEL, "Progress in Inorganic Chemistry", (Ed.) S. P. LIPPARD, Interscience, 1977, Vol. 22, p. 88.

### Polymeric Metal Complexes of 5,5'-(*p*-phenylenebisazo)-di-quinolin-8-ol

VISHWANATH BANERJEE and ARUN K. DEY\*

Chemical Laboratories, University of Allahabad,  
Allahabad-211 002

Manuscript received 9 January 1981, revised 4 September 1981,  
accepted 23 May 1982

THIS communication is in continuation of the previous work on metallated complexes of 5,5'-(benzidinebisazo)-8-hydroxyquinoline<sup>1</sup>, and is a part of work on polymeric metal complexes being carried out in our laboratories<sup>1-6</sup>. The synthesis and characterization of the insoluble pigments derived from 5,5'-(*p*-phenylenebisazo)-di-quinolin-8-ol (abbr. PDQO) are now being reported

#### Experimental

The synthesis of 5,5'-(*p*-phenylenebisazo)-di-quinolin-8-ol was carried out by tetraazotizing 0.1 mol (10.8 g) of *p*-phenylenediamine and coupling the tetraazonium salt with 0.2 mol (29.0 g) of 8-quinolinol in pyridine medium as reported earlier<sup>7</sup>.

Mixtures of 0.01 mol metal acetate hydrate [ammonium iron(II) sulphate in the case of Fe(II)] and 0.01 mol the above bisazo dye (4.20 g) were refluxed in DMSO for 6 hr to obtain the metallated complexes, which were filtered, washed with hot DMSO and dried as usual. The complexes were amorphous dark brown solids, insoluble in water and in the usual organic solvents.

The estimation of C, H, N and the metal, as well as spectral and thermal studies were done as described in an earlier communication<sup>1</sup>.

#### Results and Discussion

The analytical data (Table 1) reveal a metal to ligand ratio of 1 : 1 as expected for a chain polymer, and the coordination of 2 H<sub>2</sub>O per metal ion is inferred<sup>8</sup>. The ir spectra of the complexes of PDQO (Table 2) resemble closely those of the previously reported complexes of 5,5'-(benzidinebisazo)-8-hydroxyquinoline<sup>1-3</sup>.

\* For correspondence.

TABLE 1—ANALYTICAL DATA OF POLYMERIC  
PIGMENTS OF PDQO

Empirical formula	Analysis%, Found (Calcd.)			
	C	H	N	M
MnC <sub>24</sub> H <sub>14</sub> N <sub>4</sub> O <sub>2</sub> ·2H <sub>2</sub> O	56.89 (56.58)	3.68 (3.53)	16.15 (16.60)	10.62 (10.82)
FeC <sub>24</sub> H <sub>14</sub> N <sub>4</sub> O <sub>2</sub> ·2H <sub>2</sub> O	55.27 (56.48)	3.69 (3.52)	16.42 (16.49)	10.71 (10.96)
ZnC <sub>24</sub> H <sub>14</sub> N <sub>4</sub> O <sub>2</sub> ·2H <sub>2</sub> O	55.19 (55.48)	3.56 (3.48)	16.11 (16.18)	12.40 (12.52)
CdC <sub>24</sub> H <sub>14</sub> N <sub>4</sub> O <sub>2</sub> ·2H <sub>2</sub> O	50.45 (50.88)	3.27 (3.18)	14.64 (14.84)	19.56 (19.88)

TABLE 2—ASSIGNMENT OF IR BANDS (cm<sup>-1</sup>)

PDQO	Mn(II)	Fe(II)	Zn(II)	Cd(II)	Assignment
—	3400- 3350	3400- 3350	3400- 3350	3400- 3350	<sup>ν</sup> OH(H <sub>2</sub> O)
3880- 3120	—	—	—	—	<sup>ν</sup> OH
—	1640	1640	1630	1630	<sup>δ</sup> OH(H <sub>2</sub> O)
1600	1590	1590	1595	1595	<sup>ν</sup> C=N
1440	—	—	—	—	<sup>δ</sup> OH
—	1180	1180	1180	1180	<sup>ν</sup> C-O(C-O-M)
—	760	760	760	760	<sup>ν</sup> M-OH <sub>2</sub>
—	625	625	625	625	<sup>ν</sup> M-O
—	460	460	460	460	<sup>ν</sup> M-N

The electronic spectrum of the bisazo dye exhibits a band at 500 nm whose high intensity and wavelength suggest a  $\pi \rightarrow \pi^*$  transition attributed to the extensive conjugation resulting in lowering of the  $\pi^*$  orbital energy<sup>9</sup>. The  $d-d$  transition bands appear as weak shoulders on the intraligand band. The position and assignment of these bands are given in Table 3. Octahedral geometry around the

TABLE 3—ELECTRONIC SPECTRA OF Mn(II)  
AND Fe(II) PIGMENTS

Metal	Band (nm)	Assignment	Geometry
Mn(II)	580	<sup>4</sup> A <sub>1g</sub> → <sup>4</sup> T <sub>1g</sub> (G)	Octahedral
	490	→ <sup>4</sup> T <sub>2g</sub> (G)	
	440	→ <sup>4</sup> A <sub>1g</sub> (G)	
	380	→ <sup>4</sup> E <sub>g</sub> (G)	
	350	→ <sup>4</sup> T <sub>2g</sub> (D)	
Fe(II)	380	→ <sup>4</sup> E <sub>g</sub> (D)	Octahedral
	720	<sup>4</sup> B <sub>1g</sub> → <sup>4</sup> B <sub>1g</sub>	

central metal is assigned<sup>10</sup>, which is in accordance with that previously reported for Co(II), Ni(II) and Cu(II) complexes<sup>9</sup>. In Fe(II) complex of lower symmetry, the E<sub>g</sub> and T<sub>2g</sub> states further split into A<sub>1g</sub>, B<sub>1g</sub> and B<sub>2g</sub>, E<sub>g</sub>.

Doubling of band is anticipated. It is assumed that the ground state is B<sub>2g</sub> for these complexes, then <sup>4</sup>B<sub>2g</sub> → <sup>4</sup>B<sub>1g</sub> is <sup>10</sup>D<sub>q</sub><sup>17</sup>.


The modes of decomposition of these pigments resemble those of the previously reported complexes<sup>1,2</sup>. The chelates begin to lose weight at an accelerated rate between 300-380° (Table 4). The

TABLE 4—TGA DATA OF COMPLEXES

Temp. °C	% Weight loss of pigment containing			
	Mn(II)	Fe(II)	Zn(II)	Cd(II)
100	0.19	...	7.10	4.94
120	0.65	...	8.68	5.85
160	1.57	...	10.53	8.65
200	2.68	...	13.15	9.67
240	4.79	...	14.78	12.92
280	8.68	15.87	17.89	16.06
300	12.85	20.87	21.02	18.37
320	20.92	29.92	28.68	22.58
340	24.76	35.00	35.52	24.88
360	26.10	29.16	27.68	26.28
380	27.44	32.40	28.94	27.69
400	28.21	32.40	30.26	29.45
500	32.90	41.60	56.57	47.31
600	41.91	48.14	85.52	61.72
700	47.79	56.94	86.02	78.49
800	58.74	58.88	85.52	78.49
900	60.07			78.49

weight loss at temperatures lower than this range lies between 20–26%. The order of thermal stability is  $\text{Cd}(380^\circ) > \text{Mn}(320^\circ) > \text{Fe}(300^\circ) \sim \text{Zn}(300^\circ)$ . The weights of the residues do not conform to those of the metal oxides.

The insolubility of the pigments, composition, ir spectra and thermal stability are evidences of their polymeric structure, as given below.



$M = \text{Mn(II)}, \text{Fe(II)}, \text{Zn(II)}, \text{Cd(II)}$ .  
 $n = \text{degree of polymerization}$ .

#### Acknowledgement

Thanks of the authors are due to the Council of Scientific and Industrial Research, New Delhi, for the award of Senior Research Fellowship to V. B.

#### References

1. V. BANERJEE and A. K. DEY, *Polymer Bull.*, 1979, 1, 695.
2. V. BANERJEE and A. K. DEY, *Makromol. Chem.*, 1979, 180, 2185.
3. V. BANERJEE and A. K. DEY, *Makromol. Chem., Rapid Commun.*, 1980, 1, 41.
4. P. L. MAURVA, B. V. AGARWALA and A. K. DEY, *Indian J. Chem.*, 1978, 16A, 858.
5. P. L. MAURVA, B. V. AGARWALA and A. K. DEY, *Polymer Bull.*, 1979, 1, 681.
6. B. SINGH, V. BANERJEE, B. V. AGARWALA and A. K. DEY, *J. Indian Chem. Soc.*, 1980, 57, 365.
7. V. BANERJEE and A. K. DEY, *Current Sci.*, 1977, 46, 778.
8. J. C. BAILAR, JR., "Inorganic Polymers", The Chemical Society, London, 1961.
9. J. GRIFFITHS, "Colour and Constitution of Organic Molecules", Academic Press, London, 1976.
10. D. SUTTON, "Electronic Spectra of Transition Metal Complexes", McGraw Hill, London, 1968.

#### Mixed Ligand Complexes of Zinc(II)

P. C. PADHY and R. N. PATEL\*

Department of Chemistry, Regional Engineering College, Rourkela-769 008

Manuscript received 16 December 1980, revised 8 September 1981, accepted 6 July 1982

DIVALENT zinc ion has completely filled  $3d^{10}$  non-bonding shell and hence usually forms four coordinated tetrahedral compounds utilizing  $4s4p^2$  hybrid orbitals for bonding. If experimental conditions are favourable, the coordination number can be increased to five involving one  $4d$  orbitals<sup>1-3</sup>. This communication describes the mixed ligand complexes of the type  $M[\text{Zn}(\beta\text{-dik})_2\text{L}]$  and  $\text{Zn}(\beta\text{-dik})_2\text{L}'$  where  $M = \text{K}^+, \text{Na}^+$  or  $\text{Me}_4\text{N}^+$ ;  $\beta\text{-dik}$  = acetylacetonate or dibenzoylmethanate;  $\text{L} = \text{SCN}^-, \text{N}_3^-$  or  $\text{CN}^-$  and  $\text{L}'$  = imidazole, morpholine and their derivatives.

#### Experimental

The  $\beta$ -diketonates of  $\text{Zn(II)}$  were prepared by the usual method<sup>4</sup>. Their thiocyanate, cyanide and azide adducts were obtained by refluxing the solutions of  $\beta$ -diketonates of  $\text{Zn(II)}$  in methanol with methanolic solutions of potassium thiocyanate, cyanide or sodium azide in 1 : 1 molar ratio for 2 to 3 hr. The mixed ligand complexes separated out on cooling. The compound  $\text{K}[\text{Zn}(\text{bzbz})_2(\text{SCN})]$  so formed was treated with tetramethyl ammonium chloride in methanol. The precipitated potassium chloride was filtered off. The filtrate was evaporated to get the mixed ligand complex  $\text{Me}_4\text{N}[\text{Zn}(\text{bzbz})_2(\text{SCN})]$ . The complexes of the type  $\text{Zn}(\beta\text{-dik})_2\text{L}'$  were prepared by refluxing  $\text{Zn(II)}$  acetylacetonate with imidazole, morpholine and their derivatives in methanol for 30 min to 2 hr. Morpholine and 2-methyl imidazole adducts separated out after keeping the solution overnight whereas other compounds separated out after 3 days. All the compounds were suction filtered, washed several times with ethanol to ensure complete removal of the excess ligand, followed by ether and dried *in vacuo*.

The composition of the complexes was established by estimating zinc as  $\text{ZnNH}_4\text{PO}_4$ , sulphur as  $\text{BaSO}_4$  after oxidizing with bromine in carbontetrachloride solution and nitrogen by Kjeldahl method<sup>5</sup>. The conductance measurements were carried out with  $\sim 10^{-3} M$  solutions in acetone, pyridine and methanol medium using Toshniwal conductivity bridge and a dip type cell. The infrared absorption spectra were recorded on Nujol mull using Unicam SP-200 double beam spectrophotometer. The physical, analytical, conductance and infrared spectral data are given in Tables I and 2, respectively.

#### Results and Discussion

For the compounds of the type  $M[\text{Zn}(\beta\text{-dik})_2\text{L}]$ , the molar conductance data indicate them to be



TABLE 1

Sl. No.	Compound	Colour	m.p. °C	Zn% Found (Calcd.)	S% Found (Calcd.)	N% Found (Calcd.)	$\Delta$ m mhos (medium)
1.	$K[Zn(acac)_2(SCN)]$	White	>250	18.0 (18.1)	9.1 (8.8)	—	155 (acetone)
2.	$Na[Zn(acac)_2(N_3)]$	White	>250	20.0 (19.9)	—	—	66 (pyridine)
3.	$Me_4N[Zn(bzbx)_2(SCN)]$	Light orange	165	10.0 (10.1)	5.1 (4.9)	—	162 (acetone)
4.	$Na[Zn(bzbx)_2(N_3)]$	Yellowish white	>250	11.3 (11.8)	—	—	62 (pyridine)
5.	$K[Zn(acac)_2(ON)]$	White	>250	19.8 (19.9)	—	—	154 (acetone)
6.	$K[Zn(bzbx)_2(ON)]$	Light orange	>250	11.2 (11.3)	—	—	127 (methanol)
7.	$Zn(acac)_2(moph)$	White	223	18.3 (18.6)	—	4.0 (8.9)	18.2 (pyridine)
8.	$Zn(acac)_2(I.Z.)$	Pinkish white	185	19.6 (19.7)	—	4.0 (4.2)	24.5 (pyridine)
9.	$Zn(acac)_2(2Me.I.Z.)$	Light yellow	90	18.8 (18.9)	—	3.9 (4.0)	26.0 (pyridine)
10.	$Zn(acac)_2(B.I.Z.)$	White	>250	16.4 (16.9)	—	3.2 (3.4)	27.3 (pyridine)
11.	$Zn(acac)_2(2Me.B.I.Z.)$	White	215	15.6 (15.5)	—	3.3 (3.8)	25.4 (pyridine)

TABLE 2—INFRARED SPECTRAL DATA IN  $cm^{-1}$ 

Sl. No	Compounds	$\beta$ -diketone		Thiocyanate or cyanide		Azide		
		$\nu(C-C)$	$\nu(C-O)$	$\nu(C-N)$	$\nu(C-S)$	$\nu_{asym}$	$\nu_{sym}$	$\nu(N-H)$
1.	$K[Zn(acac)_2(SCN)]$	1600s	1520s	2035vs	715s	—	—	—
2.	$Na[Zn(acac)_2(N_3)]$	1605s	1525s	—	—	2080s	1260s	—
3.	$Me_4N[Zn(bzbx)_2(SCN)]$	1605vs	1530vs	2080vs	710s	—	—	—
4.	$Na[Zn(bzbx)_2(N_3)]$	1600s	1535s	—	—	2040s	1275s	—
5.	$K[Zn(acac)_2(ON)]$	1600s	1520s	2040m	—	—	—	—
6.	$K[Zn(bzbx)_2(ON)]$	1605s	1525s	2055m	—	—	—	—
7.	$Zn(acac)_2(moph)$	1605vs	1550vs	—	—	—	1425m	9255m
8.	$Zn(acac)_2(I.Z.)$	1618s	1555s	—	—	—	1428m	9350m
9.	$Zn(acac)_2(2Me.I.Z.)$	1610vs	1530vs	—	—	—	1440sh	9270m
10.	$Zn(acac)_2(B.I.Z.)$	1605s	1525s	—	—	—	1480m	9300m
11.	$Zn(acac)_2(2Me.B.I.Z.)$	1596vs	1520vs	—	—	—	1418sh	9360m

s = sharp

vs = very sharp

m = medium

sh = shoulder

1:1 electrolytes. The absorption due to  $\nu(C-C)$  and  $\nu(C-O)$  are shifted to lower frequencies due to metal ligand  $\pi$ -linkage superimposed on  $L \rightarrow M \sigma$  bond<sup>8</sup>.  $\nu(C-N)$  bands appear at 2030 and 2060  $cm^{-1}$  and  $\nu(C-S)$  appears at  $\sim 715 cm^{-1}$  indicating the presence of terminal S-bonded thiocyanate group<sup>9</sup>. The ionic  $KN_3$  absorbs at 2042  $cm^{-1}$  ( $\nu_{asym}$ ) and 1344  $cm^{-1}$  ( $\nu_{sym}$ )<sup>8</sup>. In the compounds under report, the strong bands observed for  $\nu_{sym}$  and  $\nu_{asym}$  are in accordance with the earlier observations<sup>8,10</sup>.

For complexes of the type  $Zn(\beta-dik)_2L'$ , the molar conductance data indicate them to be non-electrolytic. The  $\nu(M-O)$  of  $Zn(acac)_2$  is shifted to lower frequencies upon adduct formation showing direct coordination of donor molecule with the metal ions. The absence of absorption band<sup>8</sup> at 3490  $cm^{-1}$  due to coordinated water and the presence of absorption bands<sup>11</sup> at  $\sim 1430$  and  $\sim 3300 cm^{-1}$  due to (N-H) bending and stretching

frequencies clearly indicate the presence of N-donor ligands which have replaced the coordinated water from the parent compound. The compounds No. 3, 4, 6, 8, 9 exhibit light colours due to presence of the mixed ligands like other complexes<sup>12,13</sup> of  $Zn(II)$  and  $Cd(II)$ . Hence all the complexes are presumed to be penta coordinated.

## References

1. D. P. GRADDON and D. G. WENZEN, *Aust. J. Chem.*, 1968, 16, 960.
2. B. K. MAHAPATRA and D. V. RAMANA RAO, *Z. anorg. allg. Chem.*, 1970, 372, 332.
3. B. PRADHAN and D. V. RAMANA RAO, *Indian J. Chem.*, 1976, 14A, 585.
4. M. K. MISHRA and D. V. RAMANA RAO, *J. Inorg. Nuclear Chem.*, 1969, 31, 8875.
5. A. I. VOGEL, "Quantitative Inorganic Analysis", Longman's Publications, London, 1968, pp. 532, 467, 266.
6. M. K. MISHRA and D. V. RAMANA RAO, *J. Indian Chem. Soc.*, 1973, 50, 460.

7. E. A. V. ESWARAN, "Infrared Spectroscopy and Molecular Structure", Elsevier Publishing Co., 1966, p. 32.
8. G. BARTORI, O. FURLANI and A. DANIANI, *J. Inorg. Nuclear Chem.*, 1958, 6, 119.
9. J. FUJITA, K. NAKAMOTO and M. KOBAYASHI, *J. Amer. Chem. Soc.*, 1956, 78, 2896.
10. L. J. BROUWER and D. R. HARRINGTON, *Inorg. Chem.*, 1972, 11, 1772.
11. B. K. S. LUNDHRO, *Acta Crystallogr.*, 1966, 21, 901.
12. S. GURU and D. V. RAMANA RAO, *J. Indian Chem. Soc.*, 1968, 45, 160.
13. BHAWANI PRASAD MISHRA and D. V. RAMANA RAO, *Indian J. Chem.*, 1978, 16A, 908.

### Studies of ESR Spectra of Some Cu(II) Complexes

NARAYAN S. BHAVE and R. B. KHARAT

Department of Chemistry, Nagpur University, Nagpur-440 010

Manuscript received 20 April 1981, accepted 23 May 1982

THE esr spectra of copper(II) complexes have been studied by many workers<sup>1-6</sup>. Some of these studies have led to useful conclusion regarding the stereochemistry of Cu(II) in these complexes and the nature of metal-ligand bonding. Detailed esr studies on Cu(II) ion, bonded to oxygen, nitrogen and sulphur atom of the ligand, have been reported<sup>6,10</sup>. The authors have studied the metal-ligand bond strengths using esr data and the findings are presented here.

#### Materials and methods :

The copper(II) complexes studied in the present investigation are (i) Cu(HMMCO)<sub>2</sub>.3H<sub>2</sub>O and

Cu(HBMMCO)<sub>2</sub>.3H<sub>2</sub>O (HMMCO = 2'-hydroxy-4-methoxy-5'-methylchalcone oxime, HBMMCO = 2'-hydroxy - 3' - bromo-4-methoxy-5'-methylchalcone oxime); (ii) Cu(TMBHA)<sub>2</sub>.3H<sub>2</sub>O (TMBHA = *N*-*m*-tolyl-*p*-methoxy benzohydroxamic acid) and Cu(BPPTB)<sub>2</sub>.2H<sub>2</sub>O (BPPTB = 4-S-benzyl-1-*p*-Cl-phenyl-5-phenyl-2,4-isodithiobiuret). These complexes were prepared by the methods described earlier<sup>11-14</sup>. Electronic spectra, magnetic measurement, conductivity etc. suggest tetragonal symmetry to these complexes<sup>11-14</sup>.

The esr spectra of copper(II) complexes of HMMCO and BPPTB were taken at room temperature and liquid nitrogen temperature in chloroform solution (Fig. 1). ESR spectra of copper(II) complexes of HMMCO, HBMMCO, TMBHA and BPPTB were taken in polycrystalline state at room temperature only (Fig. 2).

The esr spectra of the same copper complexes at room temperature and liquid nitrogen temperature were obtained from the Regional Sophisticated Instrumentation Centre, I.I.T., Madras. The esr spectra of some copper complexes at room temperature were also run for us by the E.S.R. Laboratory, I.I.T., Bombay

#### Results and Discussion

The esr spectra were analysed by the method of Kneubuhl<sup>15</sup>, Sands<sup>16</sup> and Garman *et al.*<sup>14</sup>. The *g* values at room temperature are presented in Table 1 and the hyperfine coupling constants and *g* values at liquid nitrogen temperature are shown in Table 2. The nature of esr spectrum (Fig. 1 and Fig. 2) of copper(II) complexes in the present study




Fig. 1




Fig. 2

is indicating a tetragonal symmetry<sup>27-30</sup>. This fact supports the observations made on the basis of magnetic and spectral studies<sup>21-26</sup>.

TABLE 1—ESR SPECTRA OF POLYCRYSTALLINE COPPER(II) COMPLEXES AT ROOM TEMPERATURE

Copper(II) complexes of	$g_{\parallel}$	$g_{\perp}$	$ g $
HMMCO	2.217	2.049	2.105
HBMMCO	2.241	2.088	2.105
TMBHA	2.255	2.040	2.111
BPPTB	2.214	2.028	2.090

$$|g| = \frac{1}{2}(2g_{\parallel} + g_{\perp})$$

TABLE 2—ESR SPECTRA OF COPPER(II) COMPLEXES AT ROOM TEMPERATURE AND LIQUID NITROGEN TEMPERATURE IN CHLOROFORM

Copper(II) complexes of	$g_{\parallel}$	$g_{\perp}$	$ g $	$A_{\parallel}$ $10^{-4} \times \text{cm}^{-1}$	$A_{\perp}$	$ A $
HMMCO	2.200	2.041	2.094	168.95	18.78	67.13
BPPTB	2.204	2.085	2.091	168.64	32.79	78.07

$$|A| = \frac{1}{2}(2A_{\parallel} + A_{\perp})$$

Kivelson and Neiman<sup>3</sup> showed that  $g_{\parallel}$  is a moderately sensitive function for indicating covalency; for ionic environment  $g_{\parallel}$  is normally  $> 2.3$ , for covalent environment it is  $< 2.3$ . In view of this, covalency of the M-L bond in the present Cu(II) complexes follows the order BPPTB  $>$  HMMCO  $>$  HBMMCO  $>$  TMBHA.

$g_{\parallel}$  value of HMMCO and BPPTB in polycrystalline state is nearly the same as that of the value

obtained in chloroform solution. Therefore, it is quite probable that the arrangement of copper(II) ion in polycrystalline state and in chloroform solution may be the same<sup>10</sup>. Super hyperfine lines are clearly observed in the esr spectra of HMMCO (in frozen state) in the region between parallel and perpendicular components. This may perhaps come from the nitrogen atom as is observed in some other cases<sup>1</sup>. The nature of the  $\sigma$  and  $\pi$  bonds is investigated in the case of Cu(II)-HMMCO and Cu(II)-BPPTB systems where complete data are available (i.e. absorption peaks,  $|g|$ ,  $|A|$ ,  $g_{\parallel}$  and  $A_{\parallel}$  values). For electronic transitions Table 3 is referred.

TABLE 3—ASSIGNMENT OF THE ELECTRONIC TRANSITION IN CHLOROFORM SOLUTION

Copper(II) complexes of	$E_{xy, \leftarrow E_{x^2-y^2}}$ ( $B_{1g} \rightarrow B_{2g}$ ) kK	$E_{yz, \leftarrow E_{z^2}}$ ( $B_{1g} \rightarrow E_g$ ) kK
HMMCO	15.96	17.86
BPPTB	15.62	18.18

Molecular orbital theory put forward by Maki and McGarvey<sup>4</sup> is used to calculate metal-ligand bond nature. In fact, this theory is strictly applicable to square planar complexes. But many workers<sup>20-22</sup> applied this theory to complexes having other than square planar structure.

The approximate value of the plane bonding parameter  $\alpha^2$  can be estimated from the following simple expression:

$$\alpha^2 = \frac{|A|}{pK} + \frac{|g| - 2.0023}{K} \quad (1)$$

where,  $|A|$  and  $|g|$  are average  $A$  and  $g$  values,  $p$  is the free ion dipole term which is given a value of  $0.036 \text{ cm}^{-1}$  and  $K$  is the Fermi contact term which is actually given a value of  $0.43$ .

To obtain in-plane and out-of-plane bonding parameters  $\beta^a$  and  $\gamma^a$  respectively, the following simplified expressions were used assuming tetragonal  $D_{4h}$  symmetry for  $\text{Cu(II)}$  in HMMCO and BPPTB complexes<sup>12</sup>.

$$g_{\parallel} = 2.0023 - \frac{8\xi\alpha^a\beta^a}{\Delta E(B_{1g} \rightarrow B_{2g})} \quad \dots \text{ (II)}$$

$$g_{\perp} = 2.0023 - \frac{2\xi\alpha^a\beta^a}{\Delta E(B_{1g} \rightarrow E_g)} \quad \dots \text{ (III)}$$

The symbol  $\xi$  represents the one electron spin orbit coupling coefficient ( $= -828 \text{ cm}^{-1}$ ).

The values of  $\alpha^a$ ,  $\beta^a$  and  $\gamma^a$  are set out in Table 4. The bonding parameter  $\alpha^a$  is a measure

TABLE 4—BONDING PARAMETERS OF COPPER(II) COMPLEXES

Copper(II) complexes of	$\alpha^a$	$\beta^a$	$\gamma^a$
HMMCO	0.68	0.70	0.68
BPPTB	0.71	0.66	0.51

of the covalency of the plane  $\sigma$  bonding. A value of  $\alpha^a=1$  indicates complete ionic character while  $\alpha^a=0.5$  indicates essentially 100% covalent bonding. The  $\beta^a$  and  $\gamma^a$  parameters are a measure for covalency in the in-plane and out-of-plane bonding, respectively.  $\beta^a$  or  $\gamma^a=1$  indicates no covalent bond and  $\beta^a$  and  $\gamma^a=0.5$  corresponds to total covalent character.

The observed value of  $\alpha^a$ ,  $\beta^a$  and  $\gamma^a$  parameters in the present case are indicative of strong in-plane  $\sigma$  and  $\pi$  covalent bonding and out-of-plane  $\pi$  bonding. Out-of-plane covalency character is observed to be more in the BPPTB than in HMMCO complex which may be attributed to the presence of vacant  $d$  orbitals in sulphur atom of BPPTB. This favours back  $\pi$  bonding from metal to ligand.

#### Acknowledgement

The authors are thankful to Prof. K. N. Munshi, Head, Department of Chemistry, Nagpur University, for facilities.

#### References

1. M. N. CHARY, B. A. SASTRY, G. PONTICELLI and J. S. SHANNON, *Aust. J. Chem.*, 1968, **18**, 878.
2. B. J. HATHAWAY and A. A. G. TOMLINSON, *Coord. Chem. Reviews*, 1970, **5**, 1.
3. D. KIVELSON and B. NEIMAN, *J. Chem. Phys.*, 1961, **35**, 149, 158, 162.
4. A. H. MAKI and B. R. MCGARVEY, *J. Chem. Phys.*, 1958, **29**, 81, 85.
5. B. R. MCGARVEY, "Transition Metal Chemistry", 1966, **3**, 90.
6. K. NAKAMOTO and B. J. MCGARTHY, "Spectroscopy and Structure of Metal Chelate Compounds", John Wiley & Sons, Inc., London, 1968, p. 286.

7. R. P. SINGH, K. B. PANDEYA and ASHA KAPANI, *Indian J. Chem.*, 1976, **14A**, 444.
8. D. W. SMITH, *J. Chem. Soc. (A)*, 1970, 8108.
9. M. J. BEW, D. E. BILLING, R. J. DUDLEY and B. J. HATHAWAY, *J. Chem. Soc. (A)*, 1970, 2640.
10. M. N. CHARY, K. V. R. CHARY, B. A. SASTRY and G. PONTICELLI, *Indian J. Pure Appl. Phys.*, 1977, **15**, 560.
11. M. N. CHARY and B. A. SASTRY, *Indian J. Pure Appl. Phys.*, 1977, **15**, 172.
12. M. N. CHARY, B. A. SASTRY, G. PONTICELLI and M. BIDAUD, *Indian J. Chem.*, 1977, **15**, 888.
13. R. S. DRAGO, "Physical Methods in Chemistry", W. B. Saunders Company, London, 1977, p. 168, 818, 487, 486, 647.
14. H. R. GARMAN and J. D. SWALEN, *J. Chem. Phys.*, 1962, **56**, 3221.
15. B. J. HATHAWAY, D. E. BILLING and R. J. DUDLEY, *J. Chem. Soc. (A)*, 1970, 1420.
16. S. G. KULKARNI, Ph.D. Thesis, Marathwada University, Aurangabad, 1976.
17. B. R. MCGARVEY, *J. Phys. Chem.*, 1956, **60**, 71.
18. T. R. REDDY and R. SRINIVASAN, *J. Chem. Phys.*, 1966, **43**, 1404.
19. B. A. SASTRY and G. S. SASTRY, *Indian J. Pure Appl. Phys.*, 1974, **12**, 682.
20. V. C. SWETT and E. P. DUDEK, *J. Phys. Chem.*, 1968, **72**, 1244.
21. N. S. BHAVE and R. B. KHARAT, *J. Indian Chem. Soc.*, 1979, **56**, 244.
22. N. S. BHAVE and R. B. KHARAT, *J. Inorg. Nuclear Chem.*, 1980, **42**, 977.
23. N. S. BHAVE and R. B. KHARAT, *J. Indian Chem. Soc.*, 1981, **58**, 1194.
24. N. S. BHAVE and R. B. KHARAT, *J. Indian Chem. Soc.*, 1980, **57**, 871.
25. F. K. KNEUBUHL, *J. Chem. Phys.*, 1960, **33**, 1074.
26. R. H. SANDS, *Phys. Rev.*, 1955, **99**, 1222.
27. S. FUJIWARA, S. KATSUMATA and T. SEKI, *J. Phys. Chem.*, 1967, **71**, 155.
28. D. E. O'REILIKY, *J. Chem. Phys.*, 1958, **29**, 1188.
29. F. M. ROBERTS and W. S. KOSHI, *J. Amer. Chem. Soc.*, 1960, **82**, 3006.
30. R. H. SANDS, *Phys. Rev.*, 1955, **99**, 1222.
31. W. B. LEWIS, M. ALI and J. O. MORGAN, *J. Chem. Phys.*, 1966, **44**, 2409.
32. A. K. GREGSON and S. MITRA, *J. Chem. Phys.*, 1968, **49**, 3996.
33. D. G. BULUGGIUVE, D. L. GIORI and A. VERA, *J. Chem. Phys.*, 1971, **54**, 2191.

#### Stability Constants and Thermodynamic Parameters of Neodymium(III) Complexes with Mandelic, Cinnamic and Phenylacetic Acids - A Polarographic Study

FARID KHAN and A. V. MAHAJANI\*

Department of Chemistry, University of Sagar,  
Sagar-470 003, M. P.

Manuscript received 29 January 1982, accepted 8 July 1982

**M**ANDELIC, cinnamic and phenylacetic acids were used as complexing agents for metals by different authors<sup>1-3</sup>. A survey of literature shows that the complexation study of rare earth metal ions with these ligands have not been reported polarographically. In the present paper the authors report the stability constants and thermodynamic parameters of neodymium(III) complexes with mandelic, cinnamic and phenylacetic acid.

TABLE 1—METAL LIGAND STABILITY CONSTANTS AND THERMODYNAMIC PARAMETERS OF THE COMPLEXES AT  $\mu=1.0$  M POTASSIUM CHLORIDE

		Mandelic acid 1:2		Cinnamic acid 1:1		Phenylacetic acid 1:1	
		25°	35°	25°	35°	25°	35°
Metal ligand stability constant $\log K$	Neodymium(III)	6.5	6.0	3.2	2.7	4.8	3.8
Change in enthalpy ( $\Delta H$ ) in K cal/mole	Neodymium(III)	-20.5		-17.7		-24.0	
Change in free energy ( $\Delta G$ ) in K cal/mole	Neodymium(III)	-8.9	-8.5	-4.3	-3.9	-5.9	-5.3
Change in entropy ( $\Delta S$ ) in cal/degree/mole	Neodymium(III)	-39.0	-40.0	-45.0	-45.0	-60.9	-66.6

### Experimental

A.R. grade chemicals were used to prepare all the solutions. The metal solution was prepared by dissolving the calculated amount of metal oxide in minimum hydrochloric acid and was standardized with EDTA<sup>4</sup>. The solutions of ligands were prepared in double distilled water.

The concentration of metal ion, gelatine and potassium chloride in the test electrolytic solution was fixed at 2 mM, 0.01% and 1.0 M, respectively. The ligand concentration was varied from 1.0 mM to 10.0 mM. Ionic strength was fixed at  $\mu=1.0$  with potassium chloride. An Elco digital pH meter (Model L 1-120) was used to fix the pH of the test electrolytic solution at  $2.4 \pm 0.02$ .

An automatic pen recording (C.I.C., Baroda, India) polarograph was used to record the polarograms. The capillary used had an 'm' value of 2.20 mg/sec and drop time of 3.1 sec/drop when measured in an air free 1.0 M potassium chloride at 46.0 cm effective height of the mercury column. Pure nitrogen was used for deoxygenating the solution before recording the polarograms. All the measurements were carried out at 25° and 35°, thermostatically controlled.

### Results and Discussion

Nd(III) gives a well defined reversible three-electron reduction wave in 1.0 M potassium chloride + 0.01% gelatin at pH 2.75<sup>4-6</sup>. The reduction of Nd(III) and Nd(III)-complexes with all the three ligands were found to be of diffusion controlled nature as the plots of  $i$  vs  $\sqrt{h}$  yield straight lines passing through the origin. An analysis of the

plots of  $E_{\text{obs}}$  vs  $\log \frac{i}{i_a - i}$  and  $E_{3/4} - E_{1/4}$  values for

simple Nd(III) and its complexes with all the three ligands revealed the reversible nature of the reduction waves. The half wave potential of Nd(III) shifted to a more negative value on increasing the concentration of ligands. Lingane<sup>7</sup> method was used

to find out the composition and stability constants of Nd(III) complexes with mandelic, cinnamic and phenylacetic acids. The thermodynamic parameters were calculated by the well known thermodynamic relations<sup>8</sup>. The composition, stability constants and thermodynamic parameters are given in Table 1.

The stability constants of 1:1 complexes with respect to the ligands was found to be greater for phenylacetic acid than for cinnamic acid which is the order of their basicity. The unsaturated double bond present in cinnamic acid also contribute to lower stability<sup>8</sup> to its metal complexes. Mandelic acid forms a chelate with the stoichiometry 1:2 giving maximum stability to its metal complex.

### Acknowledgement

One of the authors (F. K.) is thankful to C.S.I.R., New Delhi for the award of Junior Research Fellowship.

### References

1. KURT WINKLER and K. B. ZABORENKO, *Z. Phys. Chem. (Leipzig)*, 1968, 238, 348.
2. J. E. POWELL and W. F. S. NEILLIE, *J. Inorg. Nuclear Chem.*, 1967, 29, 2371.
3. K. N. SAHU, *J. Indian Chem. Soc.*, 1976, 53, 657.
4. F. J. WELCHER, "The Analytical Uses of Ethylene diamine tetraacetic acid", D. Van Nostrand Company, Inc., 1957, p. 174, 181.
5. O. R. ESTER and G. GLOCKER, *J. Amer. Chem. Soc.*, 1948, 70, 1844.
6. K. S. PITRE and V. K. CHITALE, *Convention of Chem.*, 1979, Anal. 5.
7. J. J. LINGANE, *Chem. Rev.*, 1941, 29, 1.
8. J. O. FRANCIS, ROSSOTTI and H. ROSSOTTI, "The Determination of Stability Constants", McGraw-Hill Book Company, Inc., London, 1961, p. 10.

# Studies on the Flow and Sedimentation Characteristics of Sodium Bentonite Suspensions in Presence of Electrolytes and Humic Acids

K. D. GUPTA<sup>a</sup>, SWAPAN NANDI<sup>b</sup>,MUKHDEB<sup>c</sup> and DIPAK GUHA<sup>c</sup>

Indian School of Mines, Dhanbad-826 004

Manuscript received 14 August 1981, revised 13 November 1981,  
accepted 26 April 1982

THE flow behaviour of a clay suspension is a very sensitive criterion for particle interaction. The changes in flow behaviour of clay suspensions upon (i) addition of different electrolytes, (ii) addition of the same electrolyte at different concentrations<sup>1,2</sup>, (iii) addition of a polyelectrolyte, such as humic acids in (i) and (ii) above and (iv) changes of temperature in all the above cases<sup>3</sup>, provide a means for analysis of changes in particle interaction forces and modes of particle association occurring in flocculation processes.

Guha and Gupta<sup>4</sup> have shown that the departure from linearity in the plot of volume concentration against relative viscosity can be taken to be the onset of structure formation. A viscometric study of the concentration dependence of dilute montmorillonite dispersions was made by Granquist<sup>5</sup> both in distilled water and electrolyte containing water. The flocculating effect of anionic polyelectrolytes suspended in water, in relation to the mechanism of formation of polyanion linkage among the clay particles was studied by Diazakita and Kawaguchi<sup>6</sup>. The present work comprises studies on (a) the effect of the addition of different amounts of NaCl to Na-bentonite suspensions of different concentrations at room temperature (30°), (b) the stabilizing effect of humic acids addition (in different concentrations) to each of the systems mentioned above and (c) the swelling properties of clay upon the addition of humic acids.

## Experimental

Preparation of clay sample and its conversion to monoionic form and measurement of C. E. C. was done according to the method reported earlier<sup>4</sup>. The clay samples were characterised by chemical analysis (Table 1), B. E. T. surface area and C. E. C. measurements (Table 2).

The homogenised and non-settling clay suspension at a concentration where thixotropy was absent (0.8% w/v) was mixed with different amounts of NaCl (the suspension made 0, 0.31, 0.62, 1.25, 2.5 and 5 N with respect to NaCl) and with different amounts of humic acids (1.1, 2.1, 3.5 and 4.6 mg of dry humic acids per 100 g of clay), equilibrated overnight and viscosities measured by a thermostated Ostwald viscometer at 30°. The plots of

Chemical constituent	%
Loss on ignition	12.5
SiO <sub>2</sub>	52.1
Al <sub>2</sub> O <sub>3</sub>	25.8
Fe <sub>2</sub> O <sub>3</sub>	4.7
MgO	2.1
K <sub>2</sub> O	0.66
Na <sub>2</sub> O	0.41

TABLE 2—THE C.E.C. AND B.E.T. SURFACE AREA OF THE SIZE SEPARATED SAMPLE

C.E.C. meq/100 g	180
Surface area m <sup>2</sup> /g	188.5

relative viscosity versus volume concentration (of clay) at different electrolyte and humic acids concentrations are shown in Fig. 1 and Fig. 2.




Fig. 1. Changes in the flow properties of Na-bentonite on the addition of NaCl of different concentrations.

○... No NaCl added      Δ... 0.31 N NaCl added  
□... 0.62 N NaCl added    ●... 1.25 N NaCl added  
×... 2.5 N NaCl added    ▴... 5 N NaCl added




Fig. 2. Changes in the flow properties of Na-bentonite suspensions which is 5-N with respect to NaCl, on the addition of different amounts of humic acids.

○... No humic acid added  
Δ... 1.1 mg/100 g of clay, humic acid added  
□... 2.1 mg/100 g of clay, humic acid added  
●... 3.5 mg/100 g of clay, humic acid added  
×... 4.6 mg/100 g of clay, humic acid added

a—Dept. of Physics and Mathematics; b—Dept. of Petroleum Engineering; c—Dept. of Chemistry, Fuel and Mineral Engineering.




Fig. 3. Swelling of 0.8 Na-bentonite suspension flocculated by the addition of NaCl upon the addition of different amounts of humic acid.

For sedimentation volume studies, a 0.8% (w/v) sodium bentonite suspension was taken in a measuring cylinder and just enough 5 N NaCl solution was added until a clear supernatant liquid was observed. The suspension was left overnight and the volume of the suspension adjusted to 5 ml. Different amounts (1.1, 2.1, 3.5 and 4.8 mg) of humic acids were then added, the mixture homogenised for 4 hr and left overnight again. The final volume was then plotted against the amount of added humic acids (Fig. 3).

The humic acids used in this study were prepared by boiling powdered south Arcot lignite with 5 N NaOH, filtering and precipitating the humic acids with 2 N HCl. The precipitated humic acids were washed, dried in an air oven at 110° for 2 hr and cooled in a desiccator.

## Discussion

Clay particles carry a negative charge, which is balanced by the cations adsorbed on their surfaces. Positive edge charges for montmorillonites have been reported by Van Olphen<sup>10</sup> and Meldau *et al.*<sup>8</sup> but the magnitude of these edge charges is far too small compared to the surface negative charge on the clay plates. Schofield and Samson<sup>9</sup> reported that the flocculation of Na-kaolinite occurs due to the electrostatic attraction between positive edges and negative faces. No conclusive evidence of a similar mechanism exists for the flocculation of montmorillonite particles. The nature and extent of charge distribution in the clay particles is dependent on isomorphous lattice substitution of altrivalent ions (e.g., Al<sup>3+</sup> by Mg<sup>2+</sup>) as well as lattice distortion. The positive adsorption sites are, however, dependent on the particle size distribution of the clay material.

The addition of an electrolyte compresses the electrical double layer, presumably at the negative surface<sup>10</sup> resulting in a stronger interparticle association with consequent change in viscosity. A departure from the linear Einstein relation would

then be expected at a lower volume concentration with increasing electrolyte concentration.

The decreasing slope in the relative viscosity versus volume concentration (of clay) curves upon increasing electrolyte concentration (Fig. 1) supports this mechanism.

A polyelectrolyte (such as humic acids) has a polar group attached to a non-polar macro-molecular tail. This will effectively screen the double layer from compression on the addition of an electrolyte. Thus, the addition of a polyelectrolyte is expected to annul or suppress the effect of electrolyte addition. An increase in floc volume on the addition of a polyelectrolyte is also expected.

The increasing slope in the relative viscosity vs volume concentration (of clay) (Fig. 2) and increasing sedimentation volume (upto a limiting value) (Fig. 3) upon the addition of increasing amounts of humic acids supports this contention.

**Conclusion :** From a study of the flow properties of Na-bentonite suspensions in the presence of NaCl solutions of different concentrations and upon the addition of different amounts of humic acids, it was found that (a) electrolyte addition favours flocculation and reduction in viscosity of the suspensions and (b) humic acids (which are essentially polyelectrolytes) annul or suppress the effect of electrolyte addition and tend to increase the viscosity and floc volume of the clay suspensions.

## References

1. K. KAWAGUCHI, M. SEUNA and H. KUVO, *J. Colloid Interf. Sci.*, 1979, 70, 584.
2. K. D. GUPTA, DIPAK GUHA and S. C. TIWARI, *J. Indian Chem. Soc.*, 1979, 56, 599.
3. DIPAK GUHA, Proc. 54th Ind. Sc. Cong., 1967.
4. DIPAK GUHA and K. D. GUPTA, *Indian J. Appl. Chem.*, 1972, 35, 97.
5. W. T. GRADQUIST, Proc. 6th Nat. Conf. on Clays and Clay Minerals.

6. DIASOKITA and KEIZALEMRO KAWAGUCHI, *Chem. Abs.*, 1966, 65, 6884f.
7. W. D. KINGERY (Ed), "Ceramic Fabrication Processes", John Wiley & Sons, Inc., N. Y., 1966, 18.
8. R. MELDAU and R. H. S. ROBERTSON, *Ber. Deut. Keram. Ges.*, 1969, 29, 27.
9. R. K. SCHOFIELD and H. R. SAMSON, *Disc. Faraday Soc.*, 1964, 18, 185.
10. H. VAN OLPHEN, "An Introduction to Clay Colloid Chemistry", Interscience Publ., 1968.

## 2-Aryl amino-4-[4'-(benzene sulphonamido)-phenyl]-thiazoles

V. H. PATIL and D. B. INGLE


Department of Chemistry, Marathwada University,  
Aurangabad-431 004

Manuscript received 1 July 1978, revised 29 December 1981,  
accepted 7 June 1982

**VARIOUS 2-substituted amino-4-[4'-(benzene sulphonamido)-phenyl]-thiazoles** have been synthesized to study their anti bacterial activity.

The starting materials, 4-(4'-aminophenyl)-2-aryl amino)-thiazoles, were synthesized by condensing *p*-acetamido- $\omega$ -chloroacetophenone with substituted phenyl thioureas in alcohol. The thioureas used were phenyl, *o*-, *m*- and *p*-chlorophenyl, *o*-methoxyphenyl, *o*-, *m*- and *p*-methylphenyl, *o*-nitrophenyl and (2'-pyridyl)-thioureas. 4-(4'-Acetamidophenyl)-2-(substituted amino)-thiazoles were hydrolysed to 4-(4'-aminophenyl)-2-(substituted amino)-thiazoles (I) which on reacting with *p*-substituted phenyl sulphonyl chloride yielded compounds of the type (II). It should be noted here that 4-(4'-acetamido-phenyl)-2-(substituted

amino)-thiazoles did not give any reaction product with *p*-substituted phenyl sulphonyl chloride.



Hence, the primary amino group condenses with sulphonyl chloride group in the formation of the compounds (II). The ir spectra confirmed the presence of O=S=O grouping in these compounds from their strong absorption at  $\sim 1350\text{ cm}^{-1}$  (asymmetric stretch) and  $\sim 1125\text{ cm}^{-1}$  (symmetric stretch). The thiazole nucleus showed absorption bands at 1570–1530, 1438–1380 and 1390–1330  $\text{cm}^{-1}$ . The two bands in the region 3500–3260 and 3220–3180  $\text{cm}^{-1}$  are due to  $-\text{SO}_2-$ ,  $-\text{NH}$  and  $-\text{NH}-$  stretchings. The  $-\text{NH}-$  bending absorption was observed at 1610–1580  $\text{cm}^{-1}$ .

### Experimental

Melting points are uncorrected. The ir spectra were recorded on Perkin-Elmer-137 spectrophotometer in KBr phase.

**Synthesis of 4-(4'-aminophenyl)-2-(substituted amino)-thiazoles (I):** A mixture of *p*-acetamido- $\omega$ -chloro-acetophenone (0.1 mole), substituted phenyl

TABLE-I

Substituents R	4-(4'-aminophenyl)-2(substituted amino)-thiazole (I)			4-[4'-( <i>p</i> -substituted benzene sulphonamido)-phenyl]-2(substituted amino)-thiazoles (II)			Substituent R'					
							-OH <sub>2</sub>			-NHCOOH <sub>2</sub>		
	m.p. °C	N% Found (Calcd.)	S% Found (Calcd.)	m.p. °C	N% Found (Calcd.)	S% Found (Calcd.)	m.p. °C	N% Found (Calcd.)	S% Found (Calcd.)	m.p. °C	N% Found (Calcd.)	S% Found (Calcd.)
Phenyl	121	15.52 (15.72)	11.54 (11.98)	143	10.12 (9.97)	15.30 (15.30)	152	11.97 (12.07)	14.48 (14.16)	162	13.14 (13.24)	15.60 (15.16)
<i>o</i> -Chlorophenyl	210	18.84 (18.95)	10.52 (10.68)	196	9.14 (9.28)	14.32 (14.06)	192	11.34 (11.28)	12.62 (12.85)	196	12.32 (12.24)	13.92 (14.08)
<i>m</i> -Chlorophenyl	104	18.81 (18.95)	10.61 (10.68)	179	9.40 (9.28)	14.40 (14.06)	124	11.37 (11.28)	12.59 (12.85)	191	12.28 (12.24)	14.37 (14.08)
<i>p</i> -Chlorophenyl	212	18.75 (18.95)	10.65 (10.68)	192	9.87 (9.28)	14.22 (14.06)	183	11.37 (11.28)	12.59 (12.85)	189	12.31 (12.24)	14.39 (14.08)
<i>o</i> -Methoxyphenyl	203	14.25 (14.14)	10.53 (10.77)	187	9.50 (9.27)	14.00 (14.19)						
<i>o</i> -Methylphenyl	142	14.65 (14.95)	10.32 (11.39)	188	9.71 (9.55)	14.32 (14.71)	192	11.74 (11.68)	13.22 (13.88)	180	12.33 (12.81)	14.62 (14.67)
<i>p</i> -Methylphenyl	157	15.01 (14.95)	11.49 (11.39)	217	9.73 (9.55)	14.95 (14.71)	146	11.57 (11.68)	13.22 (13.88)	226	12.37 (12.81)	14.06 (14.67)
<i>o</i> -Nitrophenyl	146	17.98 (18.12)	10.39 (10.25)	140	11.35 (10.09)	14.71 (13.78)	145	12.81 (12.75)	12.85 (12.75)	208	15.10 (14.95)	13.69 (13.78)
(2'-Pyridyl)-	240	20.74 (20.89)	11.72 (11.94)				179	14.94 (15.09)	14.98 (15.16)	184	15.64 (15.55)	15.29 (15.18)



thiourea (0.1 mole) and ethanol (55 ml) was refluxed for 1.5 hr. 4-(4'-Acetamido-phenyl)-2-(substituted amino)-thiazoles were isolated following the method of Hantzsh<sup>1</sup>. These compounds were refluxed with 2 *N* NaOH (14 ml) and ethanol for 45 min. Ethanol was distilled off and the reaction mixture poured in water. The solid product was filtered, washed and crystallised from ethanol. The melting points and analysis are given in Table 1.

**General procedure for the synthesis of 4-[4'-(*p*-substituted benzene sulphonamido)-phenyl]-2-(substituted amino)-thiazoles (II):** A mixture of 4-(4'-amino-phenyl)-2-(substituted amino)-thiazole (0.01 mole), *p*-substituted benzene sulphonyl chloride (0.01 mole) and dry pyridine (20 ml) was heated on water bath for 1.0 hr and then kept at room temp for 36 hr. The reaction mixture was poured in ice containing little conc  $H_2SO_4$  with constant stirring. The crude product washed with dil  $NaHCO_3$  soln and distilled water, was crystallised from ethanol.

*p*-Methyl- and *p*-acetamido benzene sulphonyl chloride were condensed with different 4-(4'-amino-phenyl)-2-(substituted amino)-thiazoles. The 4-(4'-N-acetamido sulphonamido)-2-(substituted amino)-thiazole derivatives were hydrolysed with 2 *N* NaOH to 4-(4'-sulphanilamido)-2-(substituted amino)-thiazoles and crystallised from ethanol. The melting points and analysis are given in Table 1.

**Activity:** Some representative compounds from each series were tested against four different organism viz., *V. comma*, *M. tuberculosis*, *S. typhi* and *S. aureus*. None of them was found to be active.

#### Acknowledgement

Thanks of the authors are due to Prof. P. T. Manoharan, I.I.T., Madras for providing ir spectra and to Dr. M. H. Shah, Director, Haffkine Institute, Bombay for biological test reports. One of the authors (V. H. P.) is grateful to C. S. I. R., New Delhi for a Junior Research Fellowship.

#### Reference

1. A. HANTZSH, *Chem. Ber.*, 1927, 60, 2537, 1928, 61, 1776.

### Selective Methylation of Quercetin and Myricetin


LAL CHAND, R. MAURYA and A. B. RAY\*

Department of Medicinal Chemistry, Institute of Medical Sciences, Banaras Hindu University, Varanasi-221 005


Manuscript received 24 July 1981, revised 22 December 1981, accepted 7 June 1983

SEVERAL methods are known for selective methylation of flavonoids<sup>1-3</sup>. The key factor permitting methylation of certain hydroxyl groups in preference to others is the differential acidity of the hydroxyl groups placed at different positions of the flavone nucleus. The pioneering work in this

direction was done by Simpson and Beton<sup>1</sup> who studied the methylation of flavones and flavonols with dimethyl sulphate in refluxing acetone in presence of sodium bicarbonate and postulated the acidity order of the flavone hydroxyls as  $7 > 4' > 3' > 3$  on the basis of the results. But recent spectroscopic data, particularly the observation<sup>4</sup> that flavones bearing a hydroxyl group at 3 rather than 3' position exhibit bathochromic shift in uv spectra in presence of a weak base like sodium acetate, clearly indicate the enhanced acidity of the hydroxyl group at 3 position compared to that at 3' position. This is clearly reflected in our selective methylation experiments with polyhydroxyflavones like myricetin (1,  $R=R_1=R_2=H$ ) and quercetin (2,  $R=R_1=R_2=H$ ) which gave in our hands 3,7,4'-trimethyl ethers (1 and 2,  $R=R_2=H$ ,  $R_1=Me$ ) as major products and 3,7,3',4'-tetramethyl ethers (1 and 2,  $R=H$ ,  $R_1=R_2=Me$ ) as the minor constituents. It was further observed that replacement of sodium bicarbonate with anhydrous sodium acetate gave essentially 7,4'-dimethyl ethers and the major product of methylation of quercetin with dimethyl sulphate in presence of sodium acetate was 7,4'-dimethylquercetin (3). The partially methylated flavonols were fully characterised from detailed spectral analysis of the compounds, their derivatives and also by degradative studies in some cases. Thus, the major compound obtained from myricetin yielded a triethylether (1,  $R_1=Me$ ,  $R=R_2=Et$ )



which on alkali hydrolysis afforded  $\omega$ ,4-dimethoxy-2-ethoxy-6-hydroxy-acetophenone (4) and 3,5-diethyl-4-methyl gallic acid. Similarly, ethylation and subsequent alkali hydrolysis of the major product obtained from quercetin furnished the acetophenone, 4 and *O*-ethyl-isovanillic acid.



#### Experimental

Melting points were taken on a Toshniwal apparatus and are uncorrected. UV spectra were recorded on a Cary-14 instrument using spectrograde methanol (E.M.). IR spectra were recorded on a Perkin-Elmer 720 spectrophotometer in Nujol mull. <sup>1</sup>H NMR spectra were taken on Bruker WH-90 and Varian A-60D instruments using deuteriochloroform as solvent and TMS as internal standard. Anhydrous  $Na_2SO_4$  was normally used

for drying organic solvents. Analytical samples were routinely dried over  $P_2O_5$  for 24 hr *in vacuo*. Silica gel for column chromatography refers to B.D.H. (60-120 mesh).

**Methylation of myricetin to 3,7,4'-trimethylmyricetin** (1,  $R=R_1=H$ ,  $R_2=Me$ ) and 3,7,3',4'-tetramethylmyricetin (1,  $R=H$ ,  $R_1=R_2=Me$ ): A mixture of myricetin (4 g), freshly distilled  $Me_2SO_4$  (5 ml) and  $NaHCO_3$  (25 g) was refluxed under anhydrous condition with dry  $Me_2CO$  (500 ml) for 12 hr. The reaction mixture was cooled, filtered and the filtrate was concentrated and chromatographed over a bed of silica gel (100 g). The column after initial washing with  $C_6H_6$  to remove unreacted  $Me_2SO_4$  was first eluted with  $C_6H_6$ - $Me_2CO$  (49:1) mixture to afford 3,7,3',4'-tetramethylmyricetin (0.8 g) and then with  $C_6H_6$ - $Me_2CO$  (19:1) to furnish 3,7,4'-trimethylmyricetin (2.5 g).

3,7,4'-Trimethylmyricetin crystallised from MeOH as fine yellow needles, m.p. 207-08° (Lit.<sup>8</sup> m.p. 208-10°),  $C_{18}H_{16}O_8$ ,  $\lambda_{max}$  (MeOH) 262, 346 nm (log  $\epsilon$ , 4.41, 4.36). MS: m/e 360 ( $M^+$ ), 346, 345, 332, 331, 317, 167. Found: C, 59.78; H, 4.64.  $C_{18}H_{16}O_8$  requires C, 60.00; H, 4.48%. Colourless crystals of triacetate,  $C_{24}H_{20}O_{11}$ , m.p. 196-97°;  $^1H$  nmr:  $\delta$  2.35 and 2.45 (6H and 3Hs each, 3-OAc), 3.84 and 3.89 (6H and 3Hs each, 3-OMe), 6.60 and 6.80 (1H *d* each,  $J=2.5$  Hz, C-6 and C-8 H), 7.72 (2H, *s*, C-2' and C-6'-H). Found: C, 59.98; H, 4.72.  $C_{24}H_{20}O_{11}$  requires C, 59.26; H, 4.56%. Triethylether  $C_{24}H_{22}O_8$ , m.p. 139°. Found: C, 64.34; H, 6.18.  $C_{24}H_{22}O_8$  requires C, 64.85; H, 6.35%.

**Alkali hydrolysis of 3,7,4' trimethyl 5,3',5'-triethyl myricetin to  $\omega$ ,4-dimethoxy-2-ethoxy-6-hydroxy acetophenone (4) and 3,5-diethyl-4-methyl gallic acid**: A solution of 3,7,4'-trimethyl-5,3',5'-triethyl myricetin (0.5 g) in ethanolic NaOH (3 N; 70 ml) was refluxed on water bath for 1 hr. The solvent from the reaction mixture was removed by evaporation, the residue diluted with water, acidified with dil.  $H_2SO_4$  (6 N) and extracted with ether. The ether extract was washed several times with aq.  $NaHCO_3$  and then with water, dried and evaporated to give a phenolic solid (0.09 g) which crystallised from methanol as colourless needles of 4,  $C_{18}H_{16}O_8$ , ( $M^+$ , 240), m.p. 95°;  $^1H$  nmr:  $\delta$  3.55 and 3.85 (3H, *s* each, R-OMe and Ar-OMe), 1.5 (3H, *t*,  $-OCH_2CH_3$ ), 1.45 (2H, *q*,  $-OCH_2CH_3$ ), 5.92 and 6.12 (1H, *d* each,  $J=2.5$  Hz, C-3 and C-5 H), 4.7 (2H, *s*,  $-COCH_2OCH_3$ ), 13.85 (1H, *br*, chelated ArOH); MS: m/e 240 ( $M^+$ ), 195 ( $M^+-CH_2OMe$ ), 167 ( $M^+-COCH_2OMe$ ). Found: C, 59.72; H, 6.85.  $C_{18}H_{16}O_8$  requires C, 59.99; H, 6.71%.

The combined bicarbonate washings of the above ether extract was acidified and extracted with ether. The ether extract was washed, dried and evaporated to dryness to give a solid (0.12 g) which crystallised from petrol (60-80°) as needles of 3,5-diethyl-4-methyl gallic acid, m.p. 108°;  $^1H$  nmr:  $\delta$  3.90 (3H, *s*, -OMe), 1.40 (6H, *t*,  $J=7$  Hz) and 4.20 (4H, *q*,  $J=7$  Hz, 2-OEt), 7.40 (2H, *s*, C-2 and C-6 H), 10.6

(1H, *br*,  $CO_2H$ ), identical with synthetic sample<sup>9</sup> of 3,5-diethyl-4-methyl gallic acid (m.m.p., ir).

3,7,3',4'-Tetramethylmyricetin crystallised from MeOH as pale yellow needles,  $C_{19}H_{18}O_8$ , m.p. 148-50° (Lit.<sup>7</sup> m.p. 149-51°). Found: C, 60.73; H, 4.74.  $C_{19}H_{18}O_8$  requires C, 60.96; H, 4.85%. It gave a diacetate, m.p. 185-86°;  $^1H$  nmr:  $\delta$  2.35 and 2.45 (3H, *s* each, 2-OAc), 3.82, 3.90, 3.95 and 3.96 (3H, *s* each, 4-OMe), 6.58 and 6.78 (1H, *d* each,  $J=2.5$  Hz, C-6 and C-8 H), 7.38 and 7.60 (1H, *d* each,  $J=2.5$  Hz, C-2' and C-6' H); MS: m/e 374 ( $M^+$ ) 360, 359, 331, 167.

**Selective methylation of quercetin to 3,7,4'-trimethylquercetin** (2,  $R=R_1=H$ ,  $R_2=Me$ ) and 3,7,3',4'-tetramethylquercetin (2,  $R=H$ ,  $R_1=R_2=Me$ ): Methylation of quercetin (2 g) with  $Me_2SO_4$  in presence of  $NaHCO_3$  and subsequent chromatography of the reaction mixture furnished trimethylquercetin (0.96 g) and tetramethylquercetin (0.36 g).

3,7,4'-Trimethylquercetin crystallised from MeOH as yellow microneedles,  $C_{18}H_{16}O_7$ , m.p. 174° (Lit.<sup>6</sup> m.p. 172-73°). Found: C, 67.58; H, 4.90.  $C_{18}H_{16}O_7$  requires C, 62.79; H, 4.68%. It gave a diacetate, m.p. 173-75°;  $^1H$  nmr (90 MHz):  $\delta$  2.35 and 2.45 (3H, *s* each, 2-OAc), 3.80, 3.89, 3.91 (3H, *s* each, 3-OMe), 6.61 and 6.83 (1H, *d* each,  $J=2$  Hz, C-6 and C-8 H), 7.08 (1H, *d*,  $J=9$  Hz, C-5' H), 7.81 (1H, *d*,  $J=2$  Hz, C-2' H), 8.05 (1H, *dd*,  $J_1=9$  Hz,  $J_2=2$  Hz, C-6' H). Found: C, 61.54; H, 4.95.  $C_{18}H_{16}O_7$  requires C, 61.68; H, 4.71%. MS: m/e 344 ( $M^+$ ), 330, 329, 315, 301, 287.

Ethylation of 3,7,4'-trimethylquercetin followed by alkali hydrolysis *in situ* gave the acetophenone (4) and O-ethylisovanillic acid, m.p. 164° (Lit.<sup>9</sup> m.p. 165-66°).

3,7,3',4'-Tetramethylquercetin crystallised from MeOH as pale yellow needles,  $C_{19}H_{18}O_7$ , m.p. 158° (Lit.<sup>10</sup> m.p. 159-60°). Found: C, 63.53; H, 4.89.  $C_{19}H_{18}O_7$  requires C, 63.68; H, 5.06%. MS: m/e 358 ( $M^+$ ), 344, 343, 329, 313, 301. It gave colourless crystals of monoacetate,  $C_{21}H_{20}O_8$ , m.p. 168-69°;  $^1H$  nmr (90 MHz):  $\delta$  2.46 (3H, *s*, -OAc), 3.80, 3.91, 3.98 (3H, 3H and 6H, *s* each, 4-OMe), 6.62 and 6.83 (1H, *d* each,  $J=2.5$  Hz, C-6 and C-8 H), 7.00 (1H, *d*,  $J=9$  Hz, C-5' H), 7.67 (1H, *d*,  $J=2$  Hz, C-2' H), 7.72 (1H, *dd*,  $J_1=9$  Hz,  $J_2=2$  Hz, C-6' H). Found: C, 62.99; H, 4.83.  $C_{21}H_{20}O_8$  requires C, 62.99; H, 5.04%.

**Methylation of quercetin with  $Me_2SO_4$  in presence of NaOAc to 7,4'-dimethylquercetin** (3): Methylation of quercetin (1 g) with  $Me_2SO_4$  in dry acetone in presence of NaOAc (instead of  $NaHCO_3$ ) gave 7,4'-dimethyl quercetin (0.56 g) as bright yellow needles,  $C_{17}H_{14}O_7$ , m.p. 230-31° (Lit.<sup>11</sup> m.p. 229-30°),  $\lambda_{max}$  (MeOH) 255, 305 sh, 367 nm (log  $\epsilon$ , 4.39, 3.93, 4.38);  $\lambda_{max}$  (MeOH/NaOAc) 255, 305, 367 nm;  $\lambda_{max}$  (MeOH/NaOAc/ $H_3BO_3$ ) 255, 305 sh, 367 nm;  $\nu_{max}$  (KBr): 3280, 3450, 1655, 1618  $cm^{-1}$ ;  $^1H$  nmr (90 MHz):  $\delta$  3.86 and 3.99 (3H, *s* each, 2-OMe), 6.30 and 6.58 (1H, *d* each,  $J=2.5$  Hz, C-6 and C-8 H), 7.05 (1H, *d*,  $J=9$  Hz, C-5' H), 7.77

(2H, *m*, C-2' and C-6' H); MS: *m/e* 330 (*M*<sup>+</sup>), 315, 301, 287, 259, 231, 149, 135. Found: C, 62.11; H, 4.26. C<sub>17</sub>H<sub>15</sub>O<sub>2</sub> requires C, 61.81; H, 4.24%.

#### Acknowledgements

The authors sincerely thank Dr. B. C. Das, I.C.S.N., Gif-sur-Yvette, France for mass spectra and Dr. V. B. Pandey, formerly Alexander von Humboldt Fellow, University of Bonn, West Germany for 90 MHz <sup>1</sup>H nmr spectra and for elemental analyses of some compounds.

#### References

1. T. H. SIMPSON and J. L. BETON, *J. Chem. Soc.*, 1954, 4065.
2. L. JORD, *J. Org. Chem.*, 1962, 27, 1294.
3. S. MAHEY, S. K. MUKHERJEE and T. R. SESHADRI, *Indian J. Chem.*, 1970, 8, 1052.
4. T. J. MARRY, K. R. MARHAM and M. B. THOMAS, "The Systematic Identification of Flavonoids", Springer Verlag, N. Y., 1970.
5. G. A. HENRICK and P. R. JEFFERIES, *Aust. J. Chem.*, 1964, 17, 984.
6. A. B. BAY, S. C. DUTTA and S. DASGUPTA, *Phytochemistry*, 1976, 15, 1797.
7. G. BERTI, O. LIVI, D. SEGNI and I. CAVERO, *Tetrahedron*, 1967, 23, 2295.
8. F. E. KING, T. J. KING and K. SELLARS, *J. Chem. Soc.*, 1952, 92.
9. I. HEILBRON, A. H. COOK, H. M. BUNBURY and D. H. HEY, "Dictionary of Organic Compounds", Eyre and Spottiswood, London, 1965, Vol. 8, p. 1711.
10. I. HEILBRON, A. H. COOK, H. M. BUNBURY and D. H. HEY, "Dictionary of Organic Compounds", Eyre and Spottiswood, London, 1965, Vol. 5, p. 2892.
11. G. B. MARINI-BETTOLO, V. DELORFEO and E. HUG, *Gazz. Chim. Ital.*, 1950, 80, 63.

### Thiocarbamide as Dealkylating Agent : Debenzylation of Certain 2-S-Benzyl- 1,5-diaryl-2,4-isodithiobiurets with Thiocarbamide

R. T. JADHAV and M. G. PARANJPE\*

Department of Chemistry, Nagpur University, Nagpur-440 010


Manuscript received 19 October 1981, accepted 7 June 1982

**A**PPPLICATION of thiocarbamide as debenzylating agent for 1-aryl-S-benzyl isothiocarbamides in acid medium was reported earlier<sup>1</sup>. It is of interest to investigate this debenzylation reaction in other S-benzylated thioamido systems like 2-S-benzyl-1,5-diaryl-2,4-isodithiobiurets (I). With this end in view, debenzylations of I have been attempted in basic and acidic conditions. No debenzylation is observed in acid medium. However, smooth debenzylation reaction of I is observed in presence of a tertiary base like pyridine. The present note describes these observations.

The debenzylation reaction of 2-S-benzyl-1,5-diphenyl-2,4-isodithiobiuret (Ia) with thiocarbamide in presence of pyridine in boiling ethanolic medium

affords a product, m.p. 143°. Elimination of hydrogen sulphide is not observed during the reaction. The product is desulphurisable when boiled with alkaline plumbite solution. On pyrolysis, it gives a distinct odour of phenyl isothiocyanate. The ir spectrum of the product clearly indicates the presence of  $\nu(\text{NH})$  (3300  $\text{cm}^{-1}$ ),  $\nu(\text{C}=\text{S})$  (1210  $\text{cm}^{-1}$ ) and  $\nu(\text{C}-\text{S})$  (705  $\text{cm}^{-1}$ ) bands<sup>2</sup>. No depression in melting point is observed when it is mixed with an authentic sample of 1,5-diphenyl-2,4-dithiobiuret (IIa)<sup>3</sup>. On the basis of all these facts, the product with m.p. 143° has been assigned structure IIa. In this reaction, S-benzyl isothiocarbamide (III) has been isolated as its picrate derivative, m.p. 181°.

Other 2-S-benzyl-1,5-diaryl-2,4-isodithiobiurets (Ib and Ic) also get debenzylated into the related 1,5-diaryl-2,4-dithiobiurets (IIb and IIc) under analogous reaction conditions.



where R = (a) phenyl, (b) *p*-chlorophenyl and (c) *m*-chlorophenyl and R' = phenyl.

#### Experimental

The required 2-S-benzyl-1,5-diaryl-2,4-isodithiobiurets (I) have been prepared by the interaction of 1-aryl-S-benzyl isothiocarbamides<sup>4</sup> and aryl isothiocyanates by a known procedure<sup>5</sup> (Ib, m.p. 120° and Ic, m.p. 102° have been prepared for the first time).

**Debenzylation of 2-S-benzyl-1,5-diaryl-2,4-isodithiobiurets (I); Formation of 1,5-diaryl-2,4-dithiobiurets (II):** Details of a typical experiment (where aryl = phenyl) are as follows:

2-S-benzyl-1,5-diphenyl-2,4-isodithiobiuret (Ia, 2g) is suspended in ethanol (20 ml) and thiocarbamide (0.4 g) and pyridine (1 ml) are added to this. The reaction mixture is refluxed for 3 hr. Neither hydrogen sulphide nor benzyl mercaptan is eliminated. The reaction mixture is then cooled and acidified with dilute aqueous hydrochloric acid when an oily mass is obtained. The clear supernatant liquid is decanted off and to this is added an aqueous solution of picric acid when a yellow product is obtained. This is filtered and crystallized from ethanol, m.p. 181°. It is identified as the picrate of S-benzyl isothiocarbamide (III).

The oily mass is washed thoroughly with water and then triturated several times with petroleum ether followed by ethanol when a yellow solid

(1.7 g) is obtained. It is crystallized from ethanol, m.p. 143° (Found: N, 14.93; S, 21.53.  $C_{14}H_{11}N_2S_2$  requires N, 14.63; S, 22.30%). This has been identified as 1,5-diphenyl-2,4-dithiobiuret (IIa) on the basis of m.m.p. with an authentic sample<sup>a</sup>.

When the debenzylations of other 2-S-benzyl-1,5-diaryl-2,4-isodithiobiurets (Ib and Ic) were carried out with thiocarbamide in presence of pyridine in an ethanolic medium, the related products were obtained (IIb, m.p. 156°; Found: N, 13.56; S, 19.25.  $C_{14}H_{11}N_2S_2Cl$  requires N, 13.06; S, 19.91% and IIc, m.p. 145°; Found: N, 13.26; S, 20.34.  $C_{14}H_{11}N_2S_2Cl$  requires N, 13.06; S, 19.91%).

#### References

1. V. K. VERMA, *Indian J. Chem.*, 1968, 1, 116.
2. N. B. COLTHUP, L. H. DILLY and S. E. WIERLMEY, "Introduction to Infrared and Raman Spectroscopy", Academic Press, New York, 1964.
3. S. N. DIXIT, "Contribution to the Chemistry of Dithiobiurets, Dithiazolidines, the Related Formamidinothiocarbamides and Cyanothiocarbamides and Thiadiazolidines", Ph.D. Thesis, Banaras Hindu University, 1969.
4. WERNER, *J. Chem. Soc.*, 1890, 57, 295.
5. S. N. DIXIT, *J. Indian Chem. Soc.*, 1969, 39, 407.

### Some Interesting Reactions of N-Phenyl-S-chloro isothiocarbamoyl Chloride


R. T. JADHAV and M. G. PARANJPE\*

Department of Chemistry, Nagpur University, Nagpur-440 010

Manuscript received 19 October 1981, accepted 7 June 1982


**C**HEMISTRY of N-phenyl-S-chloro isothiocarbamoyl chloride (I) with special reference to its application as an important intermediate in heterocyclic synthesis has been exhaustively investigated in this laboratory. The present note describes the intramolecular reaction of I in presence of anhydrous aluminium trichloride and intermolecular reaction in presence of aqueous ethanol and mixture of chloroform and aqueous ethanol in different proportions.

When N-phenyl-S-chloro isothiocarbamoyl chloride is boiled with anhydrous aluminium trichloride in dry diethyl ether medium for 4 hr evolution of hydrogen chloride is observed. The reaction mixture on fractional distillation gives an oily product, b.p. 248°. It is identified as 2-chlorobenzothiazole (II) on the basis of its reaction with phenyl thiocarbamide in acetone medium when 1-(phenylformamidino)-1-phenyl thiocarbamide hydrochloride (III), m.p. 158° is isolated<sup>a</sup>. The formation of 2-chlorobenzothiazole (II) may be explained as follows:



When rectified spirit is added to a chilled N-phenyl-S-chloro isothiocarbamoyl chloride (I) solution with stirring, a pale yellow solid, m.p. 118° is obtained. It is identified as 3-oxo-4-phenyl-5-phenylimino-1,2,4-dithiazolidine (IV) on the basis of m.m.p. with an authentic sample<sup>a</sup>.

When the same reaction of I is carried out with a mixture of chloroform and rectified spirit (1 : 1, v/v), only IV is obtained. However, the reaction of I with a mixture of chloroform and rectified spirit (2 : 1, v/v) gives IV and also 5-oxo-4-phenyl-2-phenylimino-1,3,4-dithiazolidine (V). The latter has been identified on the basis of m.m.p. with an authentic sample<sup>a</sup>. As the ratio of chloroform in the mixture of chloroform and rectified spirit is increased, (3 : 1, v/v), V is formed almost exclusively. The IV and V may form as shown below.



No definite reaction mechanism could be established for the formation of IV and V. However, it is almost clear that the ratio of IV and V formed is dependant upon the concentration of rectified spirit. In presence of higher concentration of rectified spirit, more of IV is formed while in lower concentration of rectified spirit, V is the major product.

## Experimental

The required N-phenyl-S-chloro isothiocarbamoyl chloride (I) has been prepared as usual<sup>4</sup>.

*Intramolecular cyclisation of N-phenyl-S-chloro isothiocarbamoyl chloride (I) in presence of anhydrous aluminium trichloride; Formation of 2-chlorobenzothiazole (II):*

Anhydrous aluminium trichloride (16 g) is gradually added to an ice cold solution of I in dry diethyl ether (0.1 M; 21 g in 75 ml), maintaining the temperature at  $-5^{\circ}$ . After complete addition, the reaction mixture is allowed to stand for 30 min below  $10^{\circ}$  and then refluxed for 3 hr. It is then cooled and crushed ice ( $\sim 100$  g) is gradually added to decompose the probable aluminium trichloride complex. The resultant oily mass separated at the bottom is repeatedly extracted with diethyl ether. The ethereal solution on fractional distillation gives a fraction collected at  $245-248^{\circ}$  in the form of a viscous oily liquid (Found: N, 8.48; S, 18.02.  $C_7H_4NSCl$  requires N, 8.26; S, 18.88%). It is identified as 2-chlorobenzothiazole (II) on the basis of its interaction with phenyl thiocarbamide in acetone medium, when 1-(phenylformamidino)-1-phenyl thiocarbamide hydrochloride (III), m.p.  $158^{\circ}$  is obtained (Found: N, 18.31; S, 9.88.  $C_{14}H_{12}N_4S_2Cl$  requires N, 18.23; S, 10.42%). The latter also gives picrate, m.p.  $142^{\circ}$ . Both these products are identified on the basis of m.m.p. with authentic samples<sup>1</sup>.

*Intermolecular condensation of N-phenyl-S-chloro isothiocarbamoyl chloride (I). Formation of 3-oxo-4-phenyl-5-phenylimino-1,2,4-dithiazolidine (IV) and 5-oxo-4-phenyl-2-phenylimino-1,3,4-dithiazolidine (V):*

(a) *Reaction in aqueous ethanol:* N-Phenyl-S-chloro isothiocarbamoyl chloride (I) (0.1 M; 21 g) is cooled to  $0^{\circ}$  and chilled aqueous ethanol (25 ml) is added. An extremely vigorous and exothermic reaction is observed and almost immediately a pale yellow solid separates out. It is filtered, washed with a little ethanol and crystallized from glacial acetic acid, m.p.  $118^{\circ}$  (Found: N, 9.88; S, 21.92.  $C_{14}H_{10}N_4S_2O$  requires N, 9.79; S, 22.39%). It is identified as 3-oxo-4-phenyl-5-phenylimino-1,2,4-dithiazolidine (IV) on the basis of m.m.p. with an authentic sample<sup>2</sup>.

(b) *Reaction in a mixture of aqueous ethanol-chloroform (1 : 1, v/v):* To N-phenyl-S-chloro isothiocarbamoyl chloride (21 g) is gradually added a mixture of chloroform aqueous ethanol (1 : 1, v/v; 50 ml) at  $0^{\circ}$ . A vigorous exothermic reaction, accompanied by evolution of hydrogen chloride

is observed and almost immediately a pale yellow solid separates out. It is filtered, washed with a little aqueous ethanol and crystallized from glacial acetic acid, m.p.  $118^{\circ}$  (Found: N, 10.05; S, 22.55.  $C_{14}H_{10}N_4S_2O$  requires N, 9.79; S, 22.39%). It is identified as 3-oxo-4-phenyl-5-phenylimino-1,2,4-dithiazolidine (IV) on the basis of m.m.p. with an authentic sample<sup>2</sup>.

(c) *Reaction in a mixture of aqueous ethanol-chloroform (1 : 2, v/v):* To an ice cold N-phenyl-S-chloro isothiocarbamoyl chloride (21 g) is added a chilled mixture (75 ml) of chloroform-aqueous ethanol (2 : 1, v/v) when a vigorous reaction is noticed and a pale yellow solid separates out. It is filtered, washed with a little aqueous ethanol and crystallized from glacial acetic acid, m.p.  $118^{\circ}$ . It is identified as 3-oxo-4-phenyl-5-phenylimino-1,2,4-dithiazolidine (IV) as usual.

The filtrate, on addition of petroleum ether, affords a semisolid mass which on trituration several times with petroleum ether followed by ethanol is converted into a pale yellow solid, crystallized from glacial acetic acid/benzene/chlorobenzene, m.p.  $245^{\circ}$  (Found: N, 9.82; S, 22.45.  $C_{14}H_{10}N_4S_2O$  requires N, 9.79; S, 22.39%). It is identified as 5-oxo-4-phenyl-2-phenylimino-1,3,4-dithiazolidine (V) on the basis of m.m.p. with an authentic sample<sup>2</sup>.

(d) *Reaction in a mixture of aqueous ethanol-chloroform (1 : 3, v/v):* To N-phenyl-S-chloro isothiocarbamoyl chloride (21 g) is added a mixture (100 ml) of aqueous ethanol-chloroform (1 : 3, v/v) at  $0^{\circ}$  and the reaction mixture is allowed to stand below  $10^{\circ}$  for about 30 min. A very mild reaction is noticed. The reaction mixture is then allowed to stand for 3 hr at room temperature and treated with excess petroleum ether when a semisolid mass is obtained. This, on trituration several times with petroleum ether followed by ethanol, affords a pale yellow solid crystallized from glacial acetic acid, m.p.  $245^{\circ}$ . This is identified as 5-oxo-4-phenyl-2-phenylimino-1,3,4-dithiazolidine (V) on the basis of m.m.p. with an authentic sample<sup>2</sup>.

## References

1. S. N. PANDEYA and G. P. JOSHUA, *The Vikram (Sci.)*, 1961, 3, 115.
2. M. G. PARANJPE, *Indian J. Chem.*, 1967, 5, 21.
3. R. T. JADHAV, N. M. NIMDROKAR and M. G. PARANJPE, *Indian J. Chem.*, 1980, 19B, 970.
4. G. ORTMANN and H. HOOKS, *J. Org. Chem.*, 1966, 31, 838.

## Studies on 2-pyrazolin-5-one Derivatives

(Miss) P. MITRA, A. NAYAK and A. S. MITTAL  
Mayurbhanj Chemical Laboratory, Ravenshaw College,  
Cuttack-758 008

Manuscript received 2 July 1981, revised 2 December 1981,  
accepted 7 June 1982

In our earlier communications, we reported that 5-pyrazolone<sup>1-4</sup> and its derivatives, 4-acetyl-2-pyrazolin-5-one<sup>5</sup> and 2-pyrazolin-5-thione<sup>6</sup>, were

associated with significant fungicidal activity against the rice blast pathogen *Piricularia oryzae* and brown leaf spot pathogen *Helminthosporium oryzae*. Fungicidal property<sup>6,7</sup> has been noted in 2-mercapto-3-aryl-4-thiazolidone and 2-pyrazolin-5-thione. It was therefore considered worthwhile to synthesise a new heterocyclic compound containing both the fungicidally active moieties, pyrazolone and thiazolidone.

4-Acetyl-1-phenyl-3-methyl-2-pyrazolin-5-one condensed at the active methyl site of 2-mercapto-3-aryl-4-thiazolidone in ethanol to afford the compound [2-(1-phenyl-3-methyl-2-pyrazolin-5-one-4-yl)-2-(2'-mercapto-3'-aryl-4'-thiazolidone-5'-ylidene)-ethane]. The structure of the compound was established from analytical data and ir spectra. The ir spectra of the compound indicate the characteristic band at  $1740\text{ cm}^{-1}$  for ring ( $>\text{C}=\text{O}$ ), weak band at  $2990\text{ cm}^{-1}$  for heterocyclic  $-\text{CH}$  stretching vibration, band at  $1490\text{ cm}^{-1}$  for  $-\text{CH}_2$  bonding vibration, and at  $1590, 1050, 750\text{ cm}^{-1}$  attributed to  $-\text{C}=\text{N}$ ,  $-\text{C}=\text{S}$ ,  $>\text{C}-\text{S}-\text{C}<$  stretching vibrations, respectively.

1-Phenyl-3-methyl-2-pyrazolin-5-thione condensed at the 5 position with phenacyl bromide in presence of ethanol and fused sodium acetate to yield 5-ether product of 1-phenyl-3-methyl-2-pyrazolin-5-thione and phenacyl bromide. It does not dissolve in 10% aq. alkali and does not give any colouration with alcoholic  $\text{FeCl}_3$  solution.


The ir data indicate the absence of enolic band. Band at  $1680\text{ cm}^{-1}$  indicates the presence of characteristic exocyclic carbonyl group absorption, aromatic nucleus at  $1370\text{ cm}^{-1}$  and hydrogen atoms of mono-substituted aromatic nucleus at  $760$  and  $740\text{ cm}^{-1}$ . From nmr data in  $\text{CDCl}_3$ , it has been noted that peaks at  $\delta 2.2$  comes as singlet for  $3\text{H}$  of one methyl group,  $\delta 3.9$  indicates a singlet for  $2\text{H}$ ,  $\delta 6.15$  comes as singlet of  $1\text{H}$  at  $\text{C}_4$  position. Also, a multiplet in between  $\delta 7.4-87.9$  indicates the presence of phenyl group. The molecular weight of this compound has been determined from the mass spectra and found to be  $308\text{ (M}^+)$ . Peaks at  $308, 203, 188, 173, 103, 77, 51\text{ m/e}$  are obtained.

The compounds thus prepared were screened for their antifungal activity against the rice blast pathogen *P. oryzae* and the brown leaf spot pathogen *H. oryzae* by the standard method<sup>8</sup> of spore germination tests at various concentrations. It is found that only one compound (Sl. No. 9, Table 1) is active against both the pathogens. It was of further interest to note that 5 other compounds (Sl. No. 1, 5, 6, 7, 10, Table 1) were active at  $1000\text{ ppm}$ . The compound No. 1 in Table 2 is found to be more active than the O-ether product earlier reported by Das and Mitra<sup>9</sup>.

#### Experimental

All melting points are uncorrected. IR spectra were recorded in Infrared spectrophotometer.

TABLE 1




Sl. No.	$\text{R}_1$	m.p. $^{\circ}\text{C}$	%S Found (Calcd.)	% inhibition of germination at $1000\text{ ppm}$	
				<i>P. oryzae</i>	<i>H. oryzae</i>
1.	$\text{C}_6\text{H}_5$	167	15.85 (15.72)	63.4	58.8
2.	$o\text{-C}_6\text{H}_4\text{Cl}$	107	14.82 (14.99)	45.9	36.2
3.	$m\text{-C}_6\text{H}_4\text{Cl}$	72	14.55 (14.99)	49.6	39.7
4.	$p\text{-C}_6\text{H}_4\text{Cl}$	101	14.82 (14.99)	50	42.1
5.	$o\text{-C}_6\text{H}_4\text{OOCH}_3$	85	11.52 (11.61)	69	40
6.	$p\text{-C}_6\text{H}_4\text{OOCH}_3$	169	11.53 (11.61)	55	45
7.	$p\text{-C}_6\text{H}_4\text{OOC}_2\text{H}_5$	62	14.06 (14.19)	32	27
8.	$o\text{-C}_6\text{H}_4\text{OH}$	99	15.16 (15.30)	65.9	56
9.	$m\text{-C}_6\text{H}_4\text{OH}$	75	15.85 (15.20)	70.1	61
10.	$p\text{-C}_6\text{H}_4\text{OH}$	117	15.18 (15.30)	61	52.6

**General method for the preparation of 2-(1-phenyl-3-methyl-2-pyrazolin-5-one-4-yl)-2-(2'-mercapto-3'-aryl-4'-thiazolidone-5'-ylidene) ethane:** A solution of 1-phenyl-3-methyl-4-acetyl-2-pyrazolin-5-one (0.01 mole) and 2-mercapto-3-aryl thiazolidone (0.01 mole) in ethanol (20 ml) was added dropwise to 40%  $\text{NaOH}$  (15 ml) and allowed to stand overnight. It was then refluxed for 1 hr on a water bath. Excess of the solvent was removed and the resulting solution was acidified with dil. acetic acid. A yellow solid mass separated which was filtered, washed with water and finally crystallised from ethanol.

**Procedure for the synthesis of S-ether product of 2-pyrazolin-5-thione and phenacyl bromide:** 1-Phenyl-3-methyl-2-pyrazolin-5-thione (1.9 g) and phenacyl bromide (1.9 g) were taken in ethanol (10 ml) followed by fused sodium acetate (3 g) and was refluxed for 2 hr on a water bath. Excess ethanol was evaporated and cooled and water added. The brown compound thus isolated was then dissolved in 10% aqueous sodium hydroxide solution. It was allowed to stand at room temperature for 1 hr and filtered. The filtrate and the residue were collected separately. The filtrate was acidified with dil.  $\text{HCl}$  when no product was obtained. The residue was repeatedly washed with water and dried. It was then recrystallised from ethanol. A cream coloured product was obtained, m.p.  $49^{\circ}$ , yield 60%.

The compound is insoluble in 10% aqueous sodium hydroxide solution and does not give any colouration with alcoholic ferric chloride solution.

TABLE 2



Sl. No.	m.p. °C	%S Found (Calcd.)	%inhibition of germination at 1000 ppm	
			<i>P. oryzae</i>	<i>H. oryzae</i>
1.	47	10.54 (10.88)	70	48

### Acknowledgement

The authors are thankful to the authority of C. R. R. I., Cuttack for facilities for fungicidal tests.

### References

1. B. NANDA, SAVITRI PADMANAVAN, B. TRIPATHY and A. S. MITTRA, *J. Indian Chem. Soc.*, 1976, **52**, 888.
2. A. NAYAK, S. DAS, C. R. MISHRA and A. S. MITTRA, *J. Indian Chem. Soc.*, 1977, **54**, 485.
3. N. B. DAS and A. S. MITTRA, *J. Indian Chem. Soc.*, 1978, **55**, 893.
4. N. B. DAS and A. S. MITTRA, *J. Indian Chem. Soc.*, 1979, **56**, 898.
5. S. K. MOHANTY, R. SRIDHAR, S. Y. PADMANAVAN, S. RAO and A. S. MITTRA, *Indian J. Chem.*, 1977, **15B**, 1146.
6. SUNDAR RAO and A. S. MITTRA, *Indian J. Chem.*, 1977, **15B**, 1062.
7. F. O. BROWN, *J. Amer. Chem. Soc.*, 1956, **78**, 6189.
8. A. MOORE and J. MONTGOMERY, *J. Pomol. Hort. Sci.*, 1988, **15**, 253.
9. N. B. DAS and A. S. MITTRA, *J. Indian Chem. Soc.*, 1978, **55**, 907.

### Flavonoids and other Constituents of

#### *Indigofera hetrantha*

ANILA THUSOO, NANCY RAINA

and

SHAKTI RAIS AHMED

Department of Chemistry, Regional Engineering College, Hazratbal, Srinagar, J & K-190 006

Manuscript received 21 February 1981, revised 22 June 1981, accepted 7 June 1982

THE plant *Indigofera hetrantha* (wild) belonging to Leguminosae was collected from Gulmarg, Kashmir in June and was identified in the herbarium of the Botany Department, Kashmir University. The sister species of *Indigofera hetrantha* were found to contain toxic nitro compounds<sup>1,2</sup> of insecticidal activity<sup>3</sup>. It was, therefore, considered worthwhile to investigate this plant for its chemical composition.

### Experimental

The dried plant material (12 kg) was extracted by percolation with ethanol. After removal of the

solvent *in vacuo* at 40° the residue (100 g) was partitioned between 2% aq. citric acid and ether to give a basic and a non-basic fraction. The non-basic fraction was fractionated by standard methods into neutral (20 g), acidic (15 g) and phenolic (6 g) fractions.

The phenolic fraction was chromatographed over silica gel (60-100 mesh). Elution with  $\text{CHCl}_3$ ,  $\text{CHCl}_3$ -MeOH afforded  $\text{IH}_4$ ,  $\text{IH}_5$  and  $\text{IH}_6$  which were purified by re-column chromatography and preparative paper chromatography (Whatman No. 3, 15% HOAc).

The acidic fraction on chromatography over silica gel using  $\text{C}_6\text{H}_6$ - $\text{CHCl}_3$  (1:3) as the eluent gave  $\text{IH}_7$  which was purified by recrystallization.

The neutral fraction on chromatography over silica gel using light petrol, petrol- $\text{C}_6\text{H}_6$ ,  $\text{C}_6\text{H}_6$  as the eluents afforded  $\text{IH}_1$ ,  $\text{IH}_2$  and  $\text{IH}_3$ .

Refrigeration of acidic solution of the basic fraction gave an alkaloidal precipitate (300 mg). The tlc examination of this fraction revealed the presence of several compounds but could not be worked further because of the small amount.

### Results

$\text{IH}_4$ : Yellow needles, m.p. 347-8°,  $M^+$ , 270 agreed with elemental analysis of  $\text{C}_{14}\text{H}_{10}\text{O}_4$ . The compound was identified as apigenin<sup>4</sup> by uv, ir, nmr, m.m.p. The structure was further confirmed by its conversion to tri-acetate, m.p. 186°.

$\text{IH}_5$ : Yellow needles crystallized from EtOH, m.p. 261°,  $M^+$ , 284 agreed with elemental analysis of  $\text{C}_{14}\text{H}_{10}\text{O}_5$ . The compound was identified as acacetin<sup>5,6</sup> by co-tlc, m.m.p. and superimposable ir. Acetylation with  $\text{Ac}_2\text{O/py}$  gave a di-acetate, m.p. 203-5° further confirming its structure.

$\text{IH}_6$ : Yellow needles, m.p. 234-6°,  $M^+$ , 464. The compound was isolated by preparative paper chromatography and gave an olive-green colouration with  $\text{FeCl}_3$ . It was identified as isoquercitrin<sup>7</sup> by uv, ir, nmr and m.m.p. On acid hydrolysis it gave quercetin<sup>8</sup>, m.p. 313-16° and glucose confirming its structure.

$\text{IH}_7$ : It was identified as ursolic acid<sup>10</sup> (150 mg), m.p. 242-4°. Its ir in KBr pellet showed the following absorption bands:  $\nu_{\text{max}}$  3450, 2950, 2890, 1685, 1450, 1030 and 990  $\text{cm}^{-1}$ . MS  $M^+$ , 456. Treatment with  $\text{Ac}_2\text{O/py}$  gave O-acetyl ursolic acid, m.p. 268-270°. Direct comparison (m.p., m.m.p., ir) with an authentic sample confirmed the identity.

$\text{IH}_1$  and  $\text{IH}_2$  could not be processed further due to their small amounts.

$\text{IH}_3$ : A white crystalline solid, m.p. 135-6°, was found to be  $\beta$ -sitosterol<sup>9</sup> by co-tlc and m.m.p.

This appears to be the first record of the isolation of these compounds from this species.

### Acknowledgement

The authors are thankful to C. S. I. R., and U. G. C. for financial assistance, to Dr. M. S. Chadha, Head Bio-organic Division, BARC, Trombay for spectral facilities and to Dr. J. Shanker, Director, CORD, University of Kashmir, for help and suggestions.

### References

- 1 THEODORE A. ALSTON, LILIANA MELA and HAROLD BRIGHT, *J. Proc. Natl. Acad. Sci. USA*, 1977, **74**, 3767
- 2 M. P. MORRIS and C. P. GAN, *Ann. Rept. of Federal Expt. Sta. Puerto Rico*, 1958, 28.
- 3 H. K. PLANK, *J. Econ. Entomol.*, 1944, **37**, 787.
- 4 SEIKEL, *J. Amer. Chem. Soc.*, 1955, **77**, 5685.
- 5 R. ROBINSON and VENKATARAMAN, *J. Chem. Soc.*, 1926, 2844.
- 6 HATTORI, *Acta Phytochem.*, 1935, **2**, 99.
- 7 WENDER ICE, *J. Amer. Chem. Soc.*, 1952, **74**, 4606.
- 8 MARSH, *Nature*, 1955, **176**, 176.
- 9 KOFUD NILSON, *Acta Chem. Scand.*, 1963, **17**, 1161.
- 10 S. YA. ZOLOTITSKAYA, *Dokl. Akad. Nauk, SSSR*, 1954, **7**, 27.

### Chemical Constituents of *Eucalyptus citriodora* Roots

RAMESHWAR DAYAL

Forest Research Laboratory, Bangalore-560 003

Manuscript received 18 August 1981, revised 8 February 1982, accepted 7 June 1982

*EUCALYPTUS citriodora* (F: Myrtaceae) is distributed<sup>1</sup> in India, Australia and many other countries. An essential oil (0.5-2.0%) is obtained from its leaves which is used in soap perfumery and as a source of citronellal. *Eucalyptus*<sup>2</sup> is used in the treatment of catarrhal states of bronchopulmonary mucous membrane, intermittent and septic fevers, diphtheria, whooping cough etc. Earlier examination showed the presence of oil and flavonoids in the leaves<sup>3-5</sup> while the gum<sup>6</sup> contained ellagic acid and flavonoids.

The present note deals with the chemical examination of the roots of *Eucalyptus citriodora*. The roots (3 kg) were extracted with hot acetone and alcohol separately. The acetone extract, on column chromatography over silica gel, gave six compounds (A-F). Compound A ( $\beta$ -sitosterol) crystallised from chloroform-methanol as colourless needles (50 mg), m.p. 136°,  $[\alpha]_D^{25} - 34.5^\circ$  (CHCl<sub>3</sub>). Co-TLC and m.m.p. with an authentic sample confirmed its identity<sup>7</sup>. Compound B (Betulinic acid) crystallised from methanol as silky needles (500 mg), m.p. 312-14°,  $[\alpha]_D^{25} + 9^\circ$  (CHCl<sub>3</sub>). It responded to L.B. test and formed an acetate, m.p. 286-8°. Identity established by m.m.p. with an authentic sample of betulinic acid<sup>8</sup>, co-tlc and superimposable ir.

Compound C (ursolic acid) crystallised from methanol as colourless needles (200 mg), m.p.

288-90°,  $[\alpha]_D^{25} + 69^\circ$  (CHCl<sub>3</sub>) and gave +ive L. B. test (pink  $\rightarrow$  blue). Acetate, m.p. 245-46°,  $[\alpha]_D^{25} + 57^\circ$  (CHCl<sub>3</sub>). It was identified as ursolic acid<sup>10</sup> by m.m.p., co-tlc and superimposable ir.

Compound D (7-O-methylaromadendrin) crystallised from CHCl<sub>3</sub>-MeOH as light pale flat needles (2.0 g), m.p. 187-88°,  $[\alpha]_D^{25} + 30^\circ$  (MeOH) and gave a transient purple to brown colour with FeCl<sub>3</sub> and +ive Zn/HCl test. Acetate, m.p. 136-37° (M<sup>+</sup> 428). It resembled in all respect with authentic 7-O-methylaromadendrin<sup>9</sup> (ir, uv, nmr and mass). Compound E (aromadendrin) crystallised from methanol-benzene as colourless needles (800 mg), m.p. 247-48°,  $[\alpha]_D^{25} + 25.5^\circ$  (MeOH) (M<sup>+</sup> 288). Acetate, m.p. 80-82°. It was characterised as aromadendrin<sup>9</sup> by ir, uv, nmr, mass and by direct comparison with an authentic sample (co-tlc, m.m.p.). Compound F (fustin) obtained as colourless solid from ethyl acetate-petroleum ether (250 mg), m.p. 213-15°, gave green colour with FeCl<sub>3</sub> and +ive Zn/HCl test. Acetate, m.p. 149-51°. It was identified as fustin<sup>11</sup> by ir, uv, nmr and by direct comparison with an authentic sample (co-tlc and m.m.p.).

Thus the occurrence of  $\beta$ -sitosterol, betulinic acid, ursolic acid, aromadendrin and 7-O-methylaromadendrin is noted for the first time in the roots of a *Eucalyptus* species and fustin for the first time in *Eucalyptus*.

No single compound could be isolated from alcohol extract.

### Acknowledgement

The author is thankful to Dr. J. A. Lamberton, CSIRO, Australia for a gift of ursolic acid and Dr. M. R. Parthasarathy, University of Delhi for the authentic samples. The author is also thankful to Dr. M. C. Tewari, Head, Forest Research Laboratory, Bangalore for facilities

### References

- 1 "The Wealth of India, Raw Materials", C. S. I. R., New Delhi, p. 210.
- 2 K. M. NADKARNI, "India Materia Medica", Popular Book Depot, Bombay, 1954, p. 514.
- 3 S. S. JAIN, A. N. SAOJI and V. K. DESMUKH, *Indian J. Pharm.*, 1976, **38**, 57.
- 4 J. M. GARRECH, E. SANTOS and P. CRABBE, *Rev. Soc. Quim. Mas.*, 1974, **18**, 269.
- 5 M. A. ELKHIY, M. DARWISH, F. M. HASHIM and K. A. ASSEM, *Bull. Fac. Pharm.*, 1964, **31**, 83.
- 6 R. DAYAL, *Current Science*, 1980, **49**, 116.
- 7 S. S. SATWALCHAR, T. R. GUPTA and P. L. NARASIMHA RAO, *J. Indian Institute of Science*, 1957, **39**, 195.
- 8 T. O. JAIN and O. M. BARNES, *Canad. J. Chem.*, 1968, **46**, 2825.
- 9 BENGT O. LINGREN and O. M. SVANEN, *Acta Chem. Scand.*, 1966, **20**, 1720.
- 10 A. ZÜRCHER, O. JEGGER and L. RIZICKA, *Helv. Chim. Acta*, 1954, **37**, 2145.
- 11 H. H. KEPPLER, *J. Chem. Soc.*, 1957, 2721.



# Systematic Study of the Solvent Extraction of Metal-Tridentate Schiff Base Complexes

G. N. RAO

Department of Chemistry, Indian Institute of Technology,  
Hauz Khas, New Delhi-110 029

and

A. VARADARAJULU

Department of Chemistry, J N Technological University  
Engineering College, Anantapur-515 002

Manuscript received 28 May 1981, revised 17 December 1981,  
accepted 11 March 1982

GENERAL surveys of the solvent extraction of metals by oxine<sup>1</sup> (8-hydroxy quinoline),  $\beta$ -diketones<sup>2</sup> and N-benzoyl-N-phenyl hydroxylamine<sup>3</sup> have been published. However, there has been no systematic study of solvent extraction of metals by Schiff base ligands. A general study of over twenty-five metal ions with salicylidene amino thiophenol has been carried out to assess the utility of this type of ligands in the solvent extraction. Schiff base ligands form strong complexes with several metals and as such are expected to be attractive as chelating ligands in extraction work.

## Experimental

**Reagents.** All reagents used were of A. R. quality. Benzene (A.R.) was used as such without any further purification.

**Preparation of 2-salicylidene amino thiophenol:** The ligand was prepared by mixing o-amino thiophenol (Koch Light) and salicylaldehyde (England) in the ratio of 1 : 1 in benzene solution. The ligand separated out after 2 hr. It was filtered under suction. The ligand was recrystallised from benzene. Its melting point was found to be  $135^\circ \pm 2^\circ$ .

**Buffer solution:** Perchloric acid, sodium perchlorate and sodium hydroxide mixtures were used as buffer between pH 2-4, acetic acid and ammonia mixtures for the pH range 4-8 and ammonium chloride ammonia mixtures for the pH range 8-10.

**Instrumental measurements.** Measurements of pH were made using Elico pH meter standardised with standard buffer solutions of pH 4 and 7. The accuracy of the instrument was  $\pm 0.05$  pH units. In every case, the pH of the aqueous phase was measured after the extraction. For spectrophotometric measurements, Bausch and Lomb spectrophotometer (Spectronic-20) was employed. The spectrophotometric measurements are reproducible to  $\pm 0.01$  absorbance unit. A calibration curve for each metal was obtained by using known concentrations of the metal and the unknown concentration of a metal was calculated from its respective calibration curve.

**Procedure for solvent extraction:** A solution of salicylidene amino thiophenol (10 ml of  $1 \times 10^{-3}$  M) in chloroform was added to an equal volume of an

aqueous phase containing the appropriate metal and buffer in a glass stoppered bottle and shaken in wrist type mechanical shaker. All experiments were carried out at  $30 \pm 2^\circ$ . The total ionic strength of the aqueous phase was kept constant at 0.1 M. The equilibration time was 3 hr unless otherwise specified. After the equilibrium had been reached, the two phases were separated and the concentration of the metal ion in the aqueous phase was determined spectrophotometrically. The distribution ratio (or per cent extraction) was then calculated from the known concentration of the metal, ( $1.0 \times 10^{-4}$  M) and from the equilibration concentration of the metal in aqueous phase. The metal content in the organic phase was calculated by difference. The distribution ratio was calculated according to the following relationship.

$$D_o = \frac{\text{Total metal concentration in the organic phase}}{\text{Total metal concentration in the aqueous phase}}$$

**Attainment of the extraction equilibrium:** The rate of attainment of the equilibrium depends upon many factors. Primarily, it depends on the properties of the metal under investigation. Achievement of the equilibrium also depends on the pH and the concentration of the ligand. In general, it may be said that the rate of extraction increases with increasing pH values, irrespective of the ligand concentration. It is also observed that the rate of extraction increased with increase of equilibration time. Therefore, the equilibration time was kept at 3 hr for most of the metals unless otherwise specified.

All the metal extractions were carried out keeping the ligand concentration at  $1 \times 10^{-3}$  M and varying the pH of the aqueous phase from 2-10. The ligand dissolution took place at a pH higher than 10. Ishii has reported that nickel(II)<sup>4</sup> and zinc(II)<sup>5</sup> can be quantitatively extracted in the neutral or alkaline medium. It was thought worthwhile to carry out systematically the metal extraction studies at varying pH.

From the results obtained, the metals can be divided into the following three categories based on their extraction behaviour with salicylidene amino thiophenol

- Metals which are quantitatively extracted under certain pH ranges.
- Metals with the maximum percentage extraction of 50% and above but less than 100%.
- Metals with the maximum percentage extraction of less than 50%.

(A) **Metals which are quantitatively extracted under certain pH ranges** The metals studied in this category are lead(II), cadmium(II), mercury(II), cobalt(II), nickel(II), zinc(II), cerium(IV) and vanadium(V). All the above metals can be quantitatively extracted under proper conditions as shown in Fig. 1. Extraction of all these metals is sensitive to pH and rigorous control over pH is necessary for complete extraction.




Fig. 1  
Fig. 2  
Extraction curves for metal - salicylidene aminothiophenol




Fig. 3  
Fig. 4  
Extraction curves for metal - salicylidene aminothiophenol

**Lead(II):** The extraction of lead(II) started from pH 6.0 and complete extraction took place from pH 8.0-8.5. The extraction decreased from pH 9.0 and above.

**Cadmium(II):** The extraction started from pH 5.0 and complete extraction took place between pH 7.0 and 10.0. Extraction and spectrophotometric determination of cadmium(II) seem to be attractive. Precipitation was observed at pH higher than 10.0.

**Mercury(II) and vanadium(V):** Both these metals were extracted completely from pH 3.5 to 8.5 and 1.0 to 4.5, respectively. The extraction of vanadium(V) decreased above pH 5.5.

**Cerium(IV):** The complete extraction took place between pH 2.0 and 4.0 and the extraction decreased above pH 4.0.

**Cobalt(II), nickel(II) and zinc(II):** Nickel(II) and zinc(II) can be extracted and estimated spectro-

photometrically as already reported<sup>4</sup>. Present studies also confirm the data reported in the literature. Cobalt(II) also can be extracted quantitatively in the pH range 5.5 to 7.3.

(B) *Metals with the maximum percentage extraction of 50% and above but less than 100%*: The metals in this category are calcium(II), lanthanum(III), aluminium(III), thorium(IV), zirconium(IV), uranium(VI), molybdenum(VI) and tungsten(VI).

The pH extraction curves are given in Figs. 2 and 3, from which it is clear that the metal extraction increases as the pH increased except in the case of molybdenum(VI) and tungsten(VI). Tungsten(VI) extraction decreased as the pH increased, perhaps due to the formation of polytungstic acids in the aqueous phase. In the extraction of molybdenum(VI), first the metal extraction decreased up to pH 2.0 and then increased as the pH increased. This behaviour may be due to the formation of different species of molybdenum at pH less than 2 when it exists essentially as  $H_2MO_4$  according to Sary<sup>1</sup>, and as some different species at pH above 2. In the case of calcium(II), thorium(IV) and aluminium(III), there was initial extraction but above certain pH values, there was slight precipitation. Therefore the extraction curves could not be plotted for the entire pH range.

(C) *Metals with the maximum percentage extraction of less than 50%*: The metals studied under this category are ferrous and ferric iron, manganese(II), beryllium(II) and chromium(III). The pH variation curves of these metals are shown in Fig. 4. Even when the equilibration time was prolonged to 12 hr in case of beryllium(II) and chromium(III), no significant extraction took place. In case of manganese(II), colour developed immediately which faded out in a few minutes. In case of iron(II) and iron(III), the spectrophotometric studies could not be performed at pH higher than 4.0 as there was precipitation.

*Silver(I)*: Systematic studies of solvent extraction could not be carried out as the distribution ratios obtained by spectrophotometric methods were not reproducible due to absorption of silver ions on glass vessel. As there was no facility to determine the distribution ratios by radiometric method, the investigations are incomplete.

From the above study it can be seen that salicylidene amino thiophenol would be effective in the solvent extraction of various metals discussed above. Detailed investigations will be published subsequently.

#### References

1. J. SARY, *Anal. Chim. Acta*, 1968, 28, 182.
2. J. SARY and E. HLADKY, *Anal. Chim. Acta*, 1968, 28, 227.
3. A. BIEDL, *J. Radiat. and Chem.*, 1978, 13, 126.
4. H. ISHII and H. EINAGA, *Nippon Kagaku Zasshi*, 1969, 90, 179.
5. H. ISHII, *Bunseki Kagaku*, 1971, 20, 1018.

## Detection and Chromatographic Separation of Phenols on Papers Impregnated with Ferric Hydroxide

J. P. RAWAT, K. P. SINGH MUKTAWAT  
and

ONKAR SINGH

Department of Chemistry, Aligarh Muslim University,  
Aligarh-202 001

Manuscript received 6 March 1981, revised 6 February 1982,  
accepted 28 April 1982

THE use of chromatographic papers loaded with amberlite ion exchange resin has been reported by Clark<sup>1</sup>. Scant attention has been paid on the chromatography of phenols on papers impregnated with inorganic ion exchangers. Use of papers impregnated with stannic molybdate, has been made in our laboratory for the separation of phenols<sup>2</sup>.

#### Experimental

*Preparation of ion exchange papers*: Whatman No. 3 paper strips of size 14 × 3 cm were dipped in 0.1 M ferric nitrate solution for 15-20 sec and then dried at room temperature. These paper strips were then dipped in 0.1 M sodium hydroxide solution for 40-45 sec. The excess of reagent was drained off and the strips were dried at room temperature over the filter sheets. These treated strips were washed twice with demineralized water to remove the excess of reagent. Finally, the strips were dried again at room temperature and used as such for chromatography.

*Procedure*: One or two spots of test solution in ethanol were placed on the paper strip with the help of a glass capillary. The paper was conditioned for 15 min and then solvent was allowed to ascend 11 cm in every case using 20 × 5 cm glass jars.

#### Results and Discussion

*Detection*: The colours observed with the phenols are listed below:

$\beta$ -Hydroxy benzoic acid,  $\beta$ -naphthol, vanilline, *p*-nitrophenol, *m*-cresol, *p*-cresol, *o*-nitrophenol, picric acid, phloroglucinol, 4-(4-nitrophenyl)-azo resorcinol, di-(2-hydroxyphenylimino) ethane, 4-chlorophenol and 4-(2-pyridilazo) resorcinol gave yellow spots.

Tannic acid,  $\alpha$ -naphthol, pyrogallol, resorcinol, catechol, gallic acid and xyleneol gave violet spots.

2,4-Dinitrophenol, phenol, quinol and 8-hydroxy-7-iodoquinoline-5-sulphonic acid gave red spots.

Thymol blue, 1,2,5,8-hydroxyanthraquinone and phenyl fluorone, (9-phenyl-2,3,7-trihydroxy-6-fluorone), appeared as grey spots.

1-Nitroso-2-naphthol and bromocresol gave green spots.

TABLE 1— $R_f$  VALUES OF PHENOLS ON FERRIC HYDROXIDE PAPERS IN WATER, SODIUM NITRATE (1.0 M, 0.1 M, 0.01 M), SODIUM CHLORIDE, ALCOHOL AND ALCOHOL+WATER (1:1) SYSTEMS

Sl. No.	Phenol	Water	1.0 M NaNO <sub>3</sub>	0.1 M NaNO <sub>3</sub>	0.01 M NaNO <sub>3</sub>	1.0 M NaCl	Alcohol	Alcohol + water (1:1)
1.	$\beta$ -Hydroxy benzoic acid	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2.	Tannic acid	0.00	0.00	0.00	0.00	0.00	0.86	1.00
3.	Phloroglucinol	0.00	0.65	0.75	0.72	0.71	0.48	0.75
4.	$\alpha$ -Naphthol	0.50	0.54	0.86	0.96	0.00	0.90	0.72
5.	$\beta$ -Naphthol	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6.	$p$ -Hydroxy benzoic acid	0.00	0.00	0.00	0.00	0.00	0.00	0.00
7.	Pyrogallol	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8.	2,4-Dinitrophenol	0.31	0.46	0.86	0.94	0.56	0.92	0.27
9.	$p$ -Nitrophenol	0.81	0.73	0.72	0.72	0.67	0.81	0.68
10.	Catechol	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11.	$m$ -Cresol	0.09	0.00	0.00	0.00	0.00	0.89	0.00
12.	$p$ -Cresol	0.00	0.77	0.45	0.40	0.00	0.97	0.65
13.	Phenol	0.00	0.00	0.00	0.00	0.00	0.00	0.00
14.	Resorcinol	0.00	0.77	0.76	0.72	0.70	0.72	0.86
15.	Gallie acid	0.00	0.00	0.00	0.00	0.00	0.00	0.00
16.	$o$ -Nitrophenol	0.81	0.75	0.79	0.80	0.00	0.45	0.82
17.	1-Nitroso-2-naphthol	0.72	0.00	0.00	0.00	0.00	0.81	0.27
18.	Xylenol	0.81	0.65	0.50	0.45	0.18	0.72	0.81
19.	Quinhydrone	0.00	0.00	0.00	0.00	0.00	0.91	0.90
20.	Quinol	0.00	0.76	0.80	1.00	0.00	0.90	0.81
21.	Picric acid	0.73	0.60	0.56	0.60	0.57	0.60	0.81
22.	Vanilline	0.00	0.59	0.59	0.54	0.05	0.80	0.88
23.	Thymol blue	0.82	0.00	0.00	0.00	0.00	1.00	0.95
24.	1,2,5,8-Anthroxanthraquinone	0.00	0.00	0.00	0.00	0.00	0.00	0.00
25.	4-(4-Nitrophenyl)-azo resorcinol	0.18	0.09	0.09	0.09	0.09	0.61	0.68
26.	Di-(2-hydroxyphenylimino) ethane	0.00	0.00	0.00	0.00	0.00	0.61	0.54
27.	8-Hydroxy-7-iodoquinoline-5-sulphonic acid	0.13	0.00	0.00	0.00	0.00	0.56	0.54
28.	Phenylfluorone (9-phenyl-2,3,7-trihydroxy-6-fluorone)	0.00	0.00	0.00	0.00	0.00	0.00	0.00
29.	Trihydroxy-6-fluorone	0.00	0.00	0.00	0.00	0.27	0.00	0.00
30.	4-Chlorophenol	0.54	0.50	0.54	0.81	0.52	0.91	1.00
31.	Bromocresol green	0.82	0.67	0.86	0.68	0.59	0.65	0.81

The detection of phenols using ferric hydroxide impregnated papers can be made without the use of a separate detecting reagent for chromatographic studies.

**Chromatography:** 31 phenols were chromatographed in aqueous solution of sodium nitrate (1.0 M, 0.1 M, 0.01 M), water, alcohol, water + alcohol (1:1) and NaCl (1.0 M). The  $R_f$  values in different solvent systems are presented in Table 1.

The important separations of phenols were achieved on the basis of difference in  $R_f$  values in different solvent systems, e.g.  $\alpha$ -naphthol from  $\beta$ -naphthol, 2,4-dinitrophenol from  $o$ -nitrophenol, 4-chlorophenol from phenol, picric acid from 2, 4-dinitrophenol, catechol from quinol, pyrogallol from resorcinol, 1-nitroso-2-naphthol from  $\alpha$ -naphthol, 4-(4-nitrophenyl)-azo resorcinol from resorcinol in 0.1 M NaNO<sub>3</sub>;  $m$ -cresol from  $\alpha$ -naphthol in 0.01 M NaNO<sub>3</sub>; phloroglucinol from pyrogallol in 1.0 M NaCl; and  $o$ -nitrophenol from  $p$ -nitrophenol in alcohol solvent system as binary separations, and picric acid from 2,4-dinitrophenol and catechol,  $\alpha$ -naphthol from  $\beta$ -naphthol and resorcinol,  $o$ -nitrophenol from picric acid and 2,4-dinitrophenol and bromocresol from vanilline and di-(2-hydroxyphenylimino) ethane as ternary separations in 0.1 M NaNO<sub>3</sub> solvent system.

The time required for the ascend of the solvent to a height of 11 cm was approximately 30 min. This shows the importance of the ferric hydroxide papers using simple aqueous systems and thus achieving clean separations in a short period. The use of ferric hydroxide increases the compactness of the spots and removes the tailings, which are commonly observed with plain papers in these simple solvent systems. Ferric hydroxide<sup>8</sup> being a weak inorganic ion exchanger shows a selectivity towards the various phenols which are weakly ionized. This fact gives the basis for separations.

#### Acknowledgement

Financial assistance of Council of Scientific and Industrial Research and University Grants Commission to (K. P. S. M.) and (O. S.) respectively is gratefully acknowledged.

#### References

1. I. T. OLARK, *J. Chromatogr.*, 1964, 15, 65.
2. J. P. RAWAT, S. Q. MUJUMDAR and P. S. THIND, *Z. anal. Chem.*, 1976, 279, 888.
3. E. UPOR, A. B. J. and M. GORRICH, *Acta Chim. Acad. Sci. Hung.*, 1969, 61, 1.

## Studies on 3-Oxo-Glutaric Acid Dianilide.

## Part—I : Acid-Base Properties

• M. A. ZAYED, SALAH A. ABOU-TALEB\*

and

M. M. S. EL-MORSY

Department of Chemistry, Faculty of Science, Cairo University,  
Giza, EgyptManuscript received 8 December 1980, revised 7 November 1981,  
accepted 26 February 1982

THE fact that several di- and tri-keto compounds (their enol forms) have wide application in analytical chemistry has created renewed interest in their analytical properties such as acid-base properties, and behaviour as metallochromic indicators with the emphasis on specificity or selectivity, stoichiometry and sensitivity.

A number of these compounds<sup>1,2</sup> have been thoroughly investigated, their absorption spectra recorded and the stability constants and composition of some of their metal complexes established. The acid-base properties and keto-enol equilibria of some  $\beta$ -di- and tri-keto compounds were studied by several investigators, using *pH*-metric<sup>3,4</sup>, spectrophotometric<sup>5,6</sup>, nmr<sup>7,8</sup> and polarographic<sup>9,10</sup> methods.

The present work aims to throw light on the phenomena and processes taking place as the acidity of acetone dicarboxylic acid dianilide and its chloride and methyl derivatives [ADDA (I), *p*-Cl-ADDA (II) and *p*-CH<sub>3</sub>-ADDA (III), respectively] is changed, depending on the substituted group. In order to investigate the acid-base properties of compounds I, II and III, titrations of their dilute solutions against standard sodium hydroxide solution were carried out potentiometrically. From the plot of  $\log [\text{salt}]/[\text{acid}]$  vs *pH* (Fig. 1), the *pK* values of the hydroxyl groups of the enol forms were determined. The absorption spectra of compounds I, II and III were studied in the uv region at various *pH* values to determine the ionization constants of their weaker hydroxyl groups and to confirm the *pH*-measurements.

## Experimental

**Reagents and equipments:** All reagents used were of A. R. grade.

**Dianilides (I, II, III):** The tri-ketoanilides under investigation were prepared by heating ethyl acetone dicarboxylate (1 mole) with amine (2 moles) in 30 ml pyridine for 4 hr. The crude products were crystallized twice from ethanol in 80% yield<sup>11</sup>. The  $10^{-3}$  M solutions of dianilides (I, II, III) were prepared by dissolving the required amount of these compounds in known volumes of ethanol and dilute solutions were prepared by appropriate dilution, using the same solvent. Ethanol-water




Fig. 1 (a) *p*-CH<sub>3</sub>-ADDA, (b) *p*-Cl-ADDA; (c) ADDA.

(1 : 1) solutions were used for studying the absorption spectra.

A Beckman *pH*-meter H-2 model G 8509 with T-2 titration attachment was used for recording the *pH* and a PYE Unicam UV spectrophotometer, Model 1750, with 1 cm quartz cells was used for recording the absorbance at different *pH* values. The titration cell consisted of a 100 ml beaker, a microburette and calomel electrodes. 0.01 M solution of NaOH (carbonate free) was used for titration and 0.01 N solution of Na<sub>2</sub>CO<sub>3</sub> and 0.01 N solution of HCl were used for adjusting the *pH*. The water used was twice distilled from all glass equipments.

***pH*-metric titration:** 5 ml of 0.01 M solution of ADDA or one of its two derivatives, *p*-Cl-ADDA and *p*-CH<sub>3</sub>-ADDA, was taken in the titration cell and 50 ml of alcohol-water mixture (1 : 1) was added. The mixed solution was titrated with 0.01 M sodium hydroxide solution, keeping the tip of the burette immersed in the solution. The *pH* of the solution was recorded after each addition of alkali.


**Absorbance measurements:**  $8 \times 10^{-5}$  M solutions of ADDA or *p*-Cl-ADDA and  $5 \times 10^{-5}$  M solution of *p*-CH<sub>3</sub>-ADDA were prepared by dilution of the respective stock and 10 ml portion of each was taken, *pH* adjusted to the required value with Na<sub>2</sub>CO<sub>3</sub> or HCl solution and absorbances in the region 210 to 350 nm were recorded. Alcohol-water mixture (1 : 1) was used as blank. *pH* of the solutions were also checked immediately after each set of measurements.

\* Author for correspondence.

## Results and Discussion

The results obtained in the titration of 5 ml  $10^{-3}$  M ADDA (I), *p*-Cl-ADDA (II) or *p*-CH<sub>3</sub>-ADDA (III) against 0.01 M NaOH indicate that the extent of ionization increases in the order of *p*-CH<sub>3</sub>-ADDA, ADDA, *p*-Cl-ADDA. The calculated *pK* values, at the intersection of the straight line of the plot of  $\log [\text{salt}]/[\text{acid}]$  vs *pH* (Fig. 1 a, b and c), amount to 9.90, 9.35, 9.25.

A typical absorption spectrum of the compound (III) (Fig. 2) in solutions of different *pH* values from 1.4 to 7.0 is characterized by a sharp band at 250 nm which is due to a  $\pi$ - $\pi^*$  transition within the conjugate system of the molecules (i, ii, iii), as given by the equilibria,



The fact that the absorption spectra is unchanged over the *pH* range 1.4 to 7.0 confirms high *pK* values of the enol form (i). The increase of *pH* from 7.0 to 12.0 results in a hypochromic effect and a subsequent decrease in *E* from 28400 to 19000 for the primary band at 250 nm. Ascending band appears at 300 nm in case of I and III and at 310 nm in case of II. The intensity of this band increases with the increase of *pH* reaching the limiting value with *E* of 20500 at *pH* 12, which may be assigned to the  $\pi$ - $\pi^*$  transition of the forms (ii and iii).

The first decrease in absorbance at 250 nm is attributed to the ionization of OH of the enol forms (i and ii) of the anilide carbonyl groups. This is substantiated by the fact that the ionization of the OH groups which are not involved in a hydrogen bond, requires a lower energy<sup>1,2</sup>. Also the tautomerism favouring the participation of the

anilide carbonyl in hydrogen bonding in structure (i) may retard the ionization of the OH of the enol form of the acetone carbonyl which is confirmed by increase in absorbance at 300-310 nm within the *pH* range 7-12. These results are in good agreement with these obtained by *pH* measurements.

The presence of some isobestic points in the absorption spectra is an indication of the equilibria, existing previously (i, ii and iii).




Fig 2 Absorption spectra of  $5 \times 10^{-3}$  M *p*-CH<sub>3</sub>-ADDA in solutions of varying *pH* values.

The variation of absorbance with *pH* is used for calculating *pK* values using recommended procedure<sup>1,2</sup>. These values differed within  $\pm 0.1$  from the *pH*-metric data. Therefore, both *pH*-metric and spectrophotometric data indicate that *p*-Cl helps and *p*-CH<sub>3</sub> decreases the ionization of the parent ADDA. This becomes more clear by the calculation of the standard free energy changes from the ionization constants of the given compounds (Table 1).

TABLE 1

Compound	X or R	<i>pK</i>	$\Delta G^\circ$ Kcal mol <sup>-1</sup>
I	H	9.35	12.898
II	Cl	9.25	12.696
III	CH <sub>3</sub>	9.90	13.588

The difference between  $\Delta G^\circ$  of *p*-Cl-ADDA and that of ADDA is equal to  $-0.137$  Kcal mol<sup>-1</sup> and means that Cl helps ionization of enol form of *p*-Cl-ADDA, whereas the difference between free

## Study of Transition and Non-Transition Metal Complexes with 3-Amino-2-Benzoylbenzofuran

N. V. HUGGI, M. B. HALLI and A. C. HIREMATH\*

Department of Chemistry, Gulbarga University, Gulbarga-585 106

Manuscript received 6 August 1981, accepted 27 May 1982

The complexes of 3-amino-2-benzoylbenzofuran, (L), with Co(II), Ni(II), Cu(II), Zn(II), Cd(II) and Hg(II) have been synthesized and characterised on the basis of chemical analysis, conductance, magnetic measurements, electronic and infrared spectral studies. Co(II), Zn(II), Cd(II) and Hg(II) complexes are found to possess tetrahedral structure whereas Ni(II) and Cu(II) complexes exhibit polymeric, octahedral structures and Cu(II) complex undergoes Jahn-Teller distortion.

BENZOFURAN derivatives are well known as biologically and pharmacologically important compounds<sup>1-3</sup>. There are reports on metal complexes of benzofurans and their derivatives<sup>4-7</sup>, but no information on metal complexes derived from 3-amino-2-benzoylbenzofuran is available. The present communication is a part of a programme to study such complexes and deals with the synthesis and structural features of Co(II), Ni(II), Cu(II), Zn(II), Cd(II) and Hg(II) complexes of 3-amino-2-benzoylbenzofuran.

### Experimental

**Materials:** The chemicals used in this investigation were of analytical grade.

**Ligand:** 3-Amino-2-benzoylbenzofuran was prepared by the known<sup>8</sup> procedure.

**Preparation of the complexes:** Co(II), Ni(II), Cu(II), Zn(II) and Hg(II) complexes were prepared by treating the hot ethanolic solution of the ligand with ethanolic solution of corresponding metal chloride in 1 : 1 molar ratio. The reaction mixture was refluxed for about 1-2 hr. The solution was then reduced to a smaller volume on water bath, cooled and treated with petroleum ether (60-80°) to isolate the respective metal complexes, except Cu(II) complex, for which the solution was concentrated to a pasty mass and treated with solvent ether in excess. The respective solid complexes were filtered and dried over anhydrous CaCl<sub>2</sub> in a desiccator.

**Cd(II) complex:** Ethanolic solutions of the metal chloride (CdCl<sub>2</sub>·2.5H<sub>2</sub>O) and the ligand, in molar ratio 1 : 1, were mixed with vigorous stirring. The resulting mixture was refluxed for 2 hr. The precipitation of the complex was aided by further digestion on water-bath for about 1 hr. The resulting precipitate was filtered, washed with hot ethanol and dried in a desiccator over anhydrous CaCl<sub>2</sub>.

All the complexes were further purified by Soxhlet.

**Chemical analysis:** The complexes were analysed for metal and halogen by standard methods. Nitrogen was estimated by Kjeldahl method<sup>9</sup>.

**Physical measurements:** The molar conductance of the complexes were measured, using ELICO CM-82 conductivity bridge with a cell having cell constant of 1.0 cm<sup>-1</sup>. The magnetic susceptibility measurements were made on a Gouy balance at room temperature, using Hg[Co(SCN)<sub>4</sub>] as calibrant. The IR spectra of the ligand and the complexes in nujol mull were recorded on Perkin-Elmer 297, in 4000-600 cm<sup>-1</sup> region. The far IR spectra of the complexes in nujol mull were recorded on Perkin-Elmer 599 spectrophotometer using CsI plates. The electronic spectra were recorded on ELICO model CL-24 spectrophotometer in 900-340 nm region in DMF.

### Results and Discussion

All the complexes are soluble in common organic solvents, except Ni(II) and Cu(II) complexes which are soluble in DMF and DMSO. The molar conductance of all the complexes, except Ni(II) and Cu(II) complexes, in DMF (10<sup>-3</sup> M) fall in the range of 1-12 ohm<sup>-1</sup> cm<sup>2</sup> mole<sup>-1</sup>, indicating that they are non-electrolytes<sup>10</sup>.

In the case of Ni(II) and Cu(II) complexes, the observed conductivity values (Table I) in DMF (10<sup>-3</sup> M) indicate the complexes to be 1:1 electrolytes<sup>11</sup>.

**Magnetic moment:** The magnetic moments of Co(II), Ni(II) and Cu(II) complexes calculated from the corrected magnetic susceptibilities (at room temperature) are given in Table I. The observed magnetic moment, 4.9 B.M., of the Co(II) complex is higher than the 'spin only' value of three unpaired electrons and is considered to be due to large orbital contribution in a tetrahedral environment. The magnetic moment, 3.1 B.M., observed for the Ni(II) complex is within the range of 2.9-3.4 B.M. reported<sup>12</sup> for octahedral complex.

\* For correspondence.

TABLE 1—ANALYTICAL DATA, MAGNETIC SUSCEPTIBILITY AND CONDUCTANCE FOR Co(II), Ni(II), Cu(II), Zn(II), Cd(II) AND Hg(II) COMPLEXES

Complex	Metal% Found (Calcd)	N% Found (Calcd)	Cl% Found (Calcd)	$\mu_{eff}$ B.M.	Molecular conductivity ohm <sup>-1</sup> cm <sup>2</sup> mole <sup>-1</sup>
CoCl <sub>2</sub>	15.98 (16.06)	3.85 (3.81)	18.97 (19.85)	4.9	3.45
NiCl <sub>2</sub> ·H <sub>2</sub> O	14.92 (15.28)	3.53 (3.64)	18.65 (18.46)	3.1	66.51
CuCl <sub>2</sub>	17.41 (17.1)	3.68 (3.77)	19.39 (19.11)	1.9	90.01
ZnCl <sub>2</sub>	17.29 (17.51)	3.46 (3.74)	18.88 (19.01)	—	12.01
CdCl <sub>2</sub> ·H <sub>2</sub> O	25.78 (25.64)	3.82 (3.19)	16.29 (16.19)	—	1.42
HgCl <sub>2</sub>	39.72 (39.43)	3.05 (2.75)	13.73 (13.9)	—	3.32

The magnetic moment value of the Cu(II) complex lies within the range of 1.67-1.90 B.M., which indicates that the complex does not involve spin-spin interaction. However, the polymeric nature of the complex cannot be precluded, as the polymeric complexes with no spin interaction are known in literature<sup>1,2,4</sup>. Zn(II), Cd(II) and Hg(II) being d<sup>10</sup> ions show diamagnetism.

**Electronic spectra:** The electronic spectra of the Co(II), Ni(II) and Cu(II) complexes are characterised by the band maxima around 660 nm with a shoulder at 590 nm, 725 nm-675 nm, and 690 nm, respectively. All these complexes display an absorption peak centered around 410 nm. Considering the intensity of this band, we have attributed it to the L→M charge transfer band.

It is known<sup>1,2</sup> that Co(II) complex in tetrahedral environment exhibits a high intensity multiplet (630-700 nm) due to <sup>4</sup>A<sub>g</sub>→<sup>4</sup>T<sub>1</sub>(P) transition. The observed band maxima lie very well in the region of tetrahedral configuration. The Ni(II) complex exhibits a spectrum typical of octahedral environment. It is documented in literature<sup>1,2</sup> that d<sup>8</sup> system, viz. Ni(II), displays three bands in the 400-1400 nm region. These have been attributed to various transitions. The limit of our spectrophotometer does not allow the location of the band due

to <sup>3</sup>A<sub>g</sub>→<sup>3</sup>T<sub>2g</sub> transition. However, the <sup>3</sup>A<sub>g</sub>→<sup>3</sup>T<sub>1g</sub>(F) transition for the complex under consideration occurs in the region 725-675 nm as a split band. The splitting envisaged in the transition may be due to the spin-orbital coupling. The transition due to <sup>3</sup>A<sub>g</sub>→<sup>3</sup>T<sub>1g</sub>(P) has been overlaid by the high intensity charge transfer band around 410 nm. It is evident from literature<sup>1,2</sup> that the Cu(II) complexes in an octahedral environment show a broad band around 800 nm due to <sup>2</sup>E<sub>g</sub>→<sup>2</sup>T<sub>2g</sub>. This is highly sensitive to Jahn-Teller distortion and shifts hypsochromically with an increase in the tetragonal distortion. The observed band in the region 680 nm can be considered to be due to <sup>2</sup>E<sub>g</sub>→<sup>2</sup>T<sub>2g</sub> and the hypsochromic shift indicates the distortion brought about in the complex due to Jahn-Teller phenomenon.

Zn(II), Cd(II) and Hg(II) being d<sup>10</sup> ions do not show d-d transitions. Therefore, the stereochemistry of their complexes cannot be derived from their electronic spectra. The information on their structure has, therefore, been derived from ir spectral measurements only.

**Infrared spectra:** Selected infrared frequencies along with their tentative assignments are listed in Table 2. In the ir spectra of Ni(II) and Cd(II) complexes, broad band around 3500-3450 cm<sup>-1</sup> due to ν(OH) of water molecule appears. On heating the complexes above 110°, the water molecule is lost showing that it is lattice held and not coordinated. The bands observed in the region 3400-3100 cm<sup>-1</sup> are attributed to the ν(NH) vibrations. The coordination of the metal through nitrogen should cause splitting of these bands and decrease in their intensities<sup>1,2</sup>, or shifting of these bands towards low frequency side. The Co(II), Cu(II), Cd(II) and Zn(II) complexes of 3-amino-2-benzoylbenzofuran show neither such splitting nor shifting towards low frequency side, indicating non-involvement of NH<sub>2</sub> group in bond formation. In the case of the Ni(II) and Hg(II) complexes, ν(NH) band shifts towards low frequency side, indicating the involvement of NH<sub>2</sub> group in bond formation.

In the case of 3-amino-2-benzoylbenzofuran complexes, the ligand band observed at 1625 cm<sup>-1</sup>

TABLE 2—SELECTED INFRARED ABSORPTION FREQUENCIES (cm<sup>-1</sup>) OF THE LIGAND AND ITS METAL COMPLEXES

Ligand (L)	CoCl <sub>2</sub>	NiCl <sub>2</sub> ·H <sub>2</sub> O	CuCl <sub>2</sub>	ZnCl <sub>2</sub>	CdCl <sub>2</sub> ·H <sub>2</sub> O	HgCl <sub>2</sub>	Assignment
—	—	3500-3450b	—	—	3500-3450b	—	ν(OH)
3418mb	3520b	3400w	3430m	3430w	3440s	3380ms	—
3280mb	3380b	3280w	3320b	3320w	3330s	3270ms	ν(N-H)
3170mb	—	3160w	—	3180b	3170w	3160w	—
1625s	1610ms	1620ms	1590mb	1615ms	1620s	1610ms	ν(C=O)
1250w	1245w	1250w	1245vw	1240w	1250w	1250w	—
1170mb	1165mb	1170b	1145b	1175s	1180s	1175mb	ν(C-O-C)
—	—	—	—	1150sh	1165sh	—	—
—	490m	—	505ms	490m	500ms	—	ν(M-O) furan ring oxygen
—	300w	220w	300s	290w	262w	325w	ν(M-O)
—	—	235ms	—	—	—	420s	ν(M-N)
—	330w	—	—	230w	220w	290s	ν(M-Cl)
—	—	282w	280w	—	—	—	ν(M-Cl) <sub>b</sub>

s = strong, w = weak, m = medium, ms = medium strong, mb = medium broad, vw = very weak, b = bridging, sh = shoulder.




due to  $\nu(\text{C}=\text{O})$  has been shifted towards lower frequency side in all the complexes. This shift is suggestive of coordination of (C=O) group through oxygen<sup>17</sup>.

The ligand band observed in the range 1075-1250  $\text{cm}^{-1}$  has been attributed to the  $\nu(\text{C}-\text{O}-\text{C})$  mode in view of previous assignments<sup>18,19</sup>. This band shifts towards the lower frequency side in the case of Co(II), Cu(II), Cd(II) and Zn(II) complexes indicating the involvement of furan ring oxygen in bond formation, whereas in the case of the Ni(II) and Hg(II) complexes no such shift is observed indicating non-involvement of furan ring oxygen in bond formation. In the complexes of Co(II), Cu(II), Cd(II) and Zn(II), a very sharp band observed at  $500 \pm 10 \text{ cm}^{-1}$  is the band involving the metal and furan oxygen linkage<sup>20,21</sup>.

The low frequency bands in the range 325-260  $\text{cm}^{-1}$ , not observed in the ligand spectrum, are assigned to M-O stretching vibration in all the complexes and agree well with previous assignments<sup>22,23</sup>. The bands observed at 420  $\text{cm}^{-1}$  and 235  $\text{cm}^{-1}$  in the spectra of Ni(II) and Hg(II) complexes respectively, have been assigned to  $\nu(\text{M}-\text{N})$  vibrations<sup>24</sup>. The bands in the range of 330-220  $\text{cm}^{-1}$  are assigned to  $\nu(\text{M}-\text{Cl})$  vibrations<sup>25-26</sup> in all the complexes except Ni(II) and Cu(II) complexes. In the case of Ni(II) and Cu(II) complexes, which exhibit polymeric nature, a band around 280  $\text{cm}^{-1}$  is assigned to the  $\nu(\text{M}-\text{Cl})$ , which agrees well with previous assignments<sup>22</sup>.

In view of the spectral observations taken together with analytical data, magnetic moments and molar conductance, we propose the following structures for the complexes.



M=Co(II), Zn(II) and Cd(II)

## Acknowledgement

The authors are thankful to Prof. S. P. Hiremath, Head, Department of Chemistry, Gulbarga University, Gulbarga for facilities, to Dr. Y. S. Agasimundin, Dr. V. H. Kulkarni, Gulbarga University, Gulbarga and Dr. D. N. Satyanarayan, I.I.Sc., Bangalore for fruitful discussions. One of the authors (M.B.H.) is thankful to C.S.I.R., New Delhi for a Junior Research Fellowship and another (N.V.H.) to U.G.C., New Delhi for financial assistance. Thanks of the authors are also due to Prof. M.A.K. Kazimi, Principal, Government College, Gulbarga for encouragement.

## References

- 1 J D COCKER and G I GREGORY, *Ger Offen*, 1969, 2,022,024, *Chem Abs* 1971, 74, 14131d.
- 2 C F KOLLSCH, US Pat, 1957, 2,809,201 *Chem Abs.*, 1958, 52, 8871f.
- 3 H HANEKAKA, US Pat, 1952, 2,589,978, *Chem Abs.*, 1958, 47, 1482.
- 4 A. N. NESMEYANOV, K. K. ANISIMOV and N. E. KOLOROVA, *Izv Akad Nauk, SSSR, Ser Khim*, 1964, 12, 2247, *Chem Abs.*, 1965, 62, 9162h.
- 5 E O FISHER, H A GOODWIN, C G KREITER, H D SIMMONS, Jr, K SONOGASHIRA and S B WILL, *J Organometal Chem*, 1968, 14, 359.
- 6 V. V. ZELENTOV and T G AMINOV, *Zh Strukt Khim*, 1969, 10, 259, *Chem Abs.*, 1969, 71, 94607j.
- 7 S GULD EDWIN, *J Amer Chem Soc*, 1970, 92, 6797.
- 8 V P VAIDYA, S B MAHAJAN and Y S AGASIMUNDIN, *Indian J. Chem.*, 1981, 20B, 391.
- 9 A I VOGL, 'A Text Book of Quantitative Inorganic Analysis', 3rd Edn, Longman, Green and Co, London, 1964.
- 10 W J GRAY, *Coord Chem Rev*, 1971, 7, 81.
- 11 R WHYMAN and W E HATFIELD, *Inorg Chem*, 1967, 6, 1859.
- 12 F A COTTON and G WILKINSON, 'Advanced Inorganic Chemistry', Wiley Eastern, New Delhi, 1972.
- 13 M F ISKANDAR, A M EL AGAN, L S RIFAAT and S EL SAYED, *Inorg Chim Acta*, 1975, 14, 187.
- 14 N S BIRADAR, B R PATIL and V H KULKARNI, *Monatsh Chem*, 1976, 107, 251.
- 15 R S DRAGO, 'Physical Methods in Inorganic Chemistry', Reinhold Publishing Corporation, 430 Park Avenue, Ed. 1968.
- 16 G MARCOTRIGIANO and R BATTISTUZZI, *J Inorg Nuclear Chem*, 1974, 36, 3719.
- 17 V. V. SAVANT, J. GOPALKRISHNAN and C C PATIL, *Inorg Chem.*, 1970, 9, 748.
- 18 C N. R. HAO, 'Chemical Applications of Infrared Spectroscopy', Academic Press, New York, 1963.
- 19 V. B. JIGAJINNI, S C BENNUR RAJANI S. BENNUR and V. V. BADIGER, *J. Karnatak Univ (Sci)*, 1975, 20, 2.
- 20 R J NIEDZIELSKI and Z AIDERIC, *Canad J. Chem.*, 1965, 213, 1618.
- 21 H K HALL and R ZBINDEN, *J. Amer Chem Soc*, 1958, 80, 6428.
- 22 G. PONTICELLI, *J Inorg Nuclear Chem*, 1977, 39, 45.
- 23 G. DEVOTO, M MASSACESI, G. PONTICELLI and C. PRETI, *J. Inorg. Nuclear Chem*, 1977, 39, 271.
- 24 G. DEVOTO, M. MASSACESI, G. PONTICELLI and R. BUGGERI, *J. Inorg. Nuclear Chem*, 1977, 39, 855.
- 25 G. DEVOTO, G. PONTICELLI, C PRETI and G TOSI, *J. Inorg. Nuclear Chem*, 1976, 38, 1744.

# Alkaline Earth Metal Complexes : Mixed Ligand Complexes of Some Organic Compounds of Magnesium with Nitrogen Donor Ligands

A. K. BANERJEE, SAILENDRA K. SINHA, MONOJIT K. GHOSH and S. K. ROY

Chemistry Department, Patna University, Patna-800 005

Manuscript received 27 July 1981, accepted 23 May 1982

Mixed ligand complexes of magnesium salts of salicylic acid, salicylaldehyde, 1-nitroso-2-naphthol, 8-hydroxyquinoline, *o*-nitrophenol and 2-hydroxy-3-naphthoic acid with nitrogen donor ligands 1,10-phenanthroline and ethylenediamine have been synthesised in absolute ethanol. A study of the far infrared region (between 604-470  $\text{cm}^{-1}$ ) is very conclusive for a *trans* structure for the magnesium complexes formed with ethylenediamine.

COMPARED to those of transition and rare-earth metals, mixed ligand complexes of magnesium with bidentate ligands are less well documented; only complexes with monodentate ligands have been reported<sup>1,2</sup>. Fenton<sup>3</sup> synthesised a few mixed complexes of magnesium salts with bidentate ligands, viz., ethylenediamine, *o*-phenanthroline, 2,2'-bipyridyl, etc. We have extended the investigation by synthesising some new mixed ligand complexes of magnesium metal salts of salicylic acid (SalA), salicylaldehyde (SalH), 1-nitroso-2-naphthol (1N2N), 8-hydroxyquinoline (8HQ), *o*-nitrophenol (ONP) and 2-hydroxy-3-naphthoic acid (2H3NA) with nitrogen donor ligands 1,10-phenanthroline and ethylenediamine.

## Experimental

For the different organic acid salts of magnesium, our usual method of synthesis was to take a suspension of magnesium hydroxide in absolute ethanol and to add to it the above mentioned ligands, (having replaceable protons HL'), in slight excess. The reaction was allowed to take place for 5 to 6 hr on a hot plate magnetic stirrer when magnesium hydroxide, which is insoluble in absolute ethanol, passed into solution. Coloured compounds separated out on cooling, which were filtered, washed with absolute ethanol and dried at 90°.

To the suspension of these organic acid salts of magnesium in absolute ethanol, a saturated solution of 1,10-phenanthroline or ethylenediamine was added drop by drop in slight excess, with constant stirring. After 3 to 4 hr, the suspended salts passed into solution, which were then concentrated. On cooling, adducts of the general formula  $\text{MgL}_2 \cdot \text{en/phen}$ , (where L=organic acids), separated out which were filtered, washed with absolute ethanol and dried in an oven at 90°. The number of ethylenediamine/phenanthroline molecules attached was always found to be one.

The colour, transition or decomposition temperatures and analytical values of the compounds are given in Table I.

## Results and Discussion

*Different organic acid salts of magnesium*: All these compounds are stable under dry condition. When exposed to atmosphere they absorb 2 molecules of water.

The infrared spectra of  $\text{Mg}(\text{SalA})_2 \cdot 2\text{H}_2\text{O}$  complex indicate that O-H is strongly hydrogen bonded. The O-H stretching band of SalA at 3240  $\text{cm}^{-1}$  shows up as a broad peak between 3200-3040  $\text{cm}^{-1}$ . Further, there are two humps at 2700 and 2600  $\text{cm}^{-1}$ . The antisymmetric stretching frequency at 1660  $\text{cm}^{-1}$  of the  $\text{COO}^-$  group in salicylic acid is shifted down to 1630  $\text{cm}^{-1}$ .

In the compound with salicylaldehyde, the C=O frequency at 1630  $\text{cm}^{-1}$  is much lower than that observed for free salicylaldehyde (1700  $\text{cm}^{-1}$ ).

In magnesium-*o*-nitrophenolate, the anti-symmetric (1510  $\text{cm}^{-1}$ ) and symmetric (1330  $\text{cm}^{-1}$ ) stretching frequency of the nitro group of ONP is shifted to 1520  $\text{cm}^{-1}$  and 1315  $\text{cm}^{-1}$ , respectively, suggesting association of the  $\text{NO}_2$  group in the magnesium compound.

There is a broad absorption at 3300-3000  $\text{cm}^{-1}$  with a hump at 3040  $\text{cm}^{-1}$  in the 2-hydroxy-3-naphthoic compound. Moreover, there is another broad peak at 2700  $\text{cm}^{-1}$ , which indicates that there is strong hydrogen bonding in the compound. The C=O peak at 1590  $\text{cm}^{-1}$  of the acid is observed at 1620  $\text{cm}^{-1}$  in the magnesium compound.

*Complexes formed with the above salts*: The complexes formed by these different organic acid salts of magnesium with 1,10-phenanthroline or ethylenediamine are stable when stored dry. The transition or decomposition temperatures of these adducts are much higher than the melting/boiling

TABLE 1

Compound	Colour	Transition (t°C) or decomp. (d°C) temp.	Calcd. (%)				Found (%)			
			O	H	N	M	O	H	N	M
Mg(SaIA) <sub>2</sub> .2H <sub>2</sub> O	White	298d	52.14	4.34		7.45	51.78	4.19		7.16
Mg(SaIA) <sub>2</sub> .phen	White	285d	55.27	3.76	5.85	5.02	54.82	3.52	5.53	4.86
Mg(SaIA) <sub>2</sub> .en	Dirty white	172t & 240d	58.88	5.02	7.82	6.40	52.95	4.74	7.48	6.32
Mg(SaIH) <sub>2</sub>	Pale yellow	315d	53.15	3.75		9.02	52.76	3.48		8.76
Mg(SaIH) <sub>2</sub> .phen	Pale yellow	240d	59.95	4.08	6.29	5.38	59.43	3.86	5.86	5.02
Mg(SaIH) <sub>2</sub> .en	Yellow	168t	58.89	5.52	8.58	7.36	58.27	5.28	7.97	6.83
Mg(1N2N) <sub>2</sub>	Green	900d	55.21	3.26	7.60	6.52	54.08	3.09	7.31	6.15
Mg(1N2N) <sub>2</sub> .phen	Light green	250d	70.07	3.64	10.21	4.37	69.87	3.62	9.26	3.79
Mg(1N2N) <sub>2</sub> .en	Brownish green	168t	61.68	4.67	13.08	5.60	60.79	4.18	12.54	5.12
Mg(ONP) <sub>2</sub>	Orange	180d	48.00	2.66	9.33	8.00	47.64	2.41	8.92	7.64
Mg(ONP) <sub>2</sub> .phen	Orange	160t	60.00	3.33	11.66	5.00	59.62	3.12	11.23	4.86
Mg(2H3NA) <sub>2</sub> .2H <sub>2</sub> O	Dirty white	295d	60.82	4.14		5.53	60.13	3.92		5.37
Mg(2H3NA) <sub>2</sub> .phen	White	252d	70.58	3.80	4.84	4.15	69.87	3.62	4.26	3.79
Mg(2H3NA) <sub>2</sub> .en	Light green	162t	62.88	4.80	6.11	5.24	62.24	4.42	5.67	4.92
Mg(8HQ) <sub>2</sub> .phen	Yellow	240d	73.17	4.06	11.38	4.87	72.48	3.91	10.78	4.32
Mg(8HQ) <sub>2</sub> .en	Pale yellow	160t	64.51	5.37	15.05	6.45	63.65	5.00	14.82	6.21

points of the corresponding ligands showing the greater stability. That these adducts are genuine complexes and not stoichiometric mixtures, is clear from the fact that organic salts of magnesium, which remain in suspension in absolute ethanol, passes into solution on addition of the second ligand i.e. 1,10-phen or en and the adducts then separate out from the above ethanolic solution.

In all the magnesium complexes formed with 1,10-phenanthroline, the corresponding *phen* absorptions are there, but none have been found to be metal sensitive.

The blue shift in the NH<sub>2</sub> stretching vibrations in the 3340 to 3250 cm<sup>-1</sup> region clearly shows that *en* is coordinated to the metal. As regards conformation of *en* in these complexes, multiplicity of certain infrared bands have been used as the criteria.

One broad band is observed at 1600 cm<sup>-1</sup> region in all these complexes; only Mg(2H3NA)<sub>2</sub>.en shows two at 1605 and 1624 cm<sup>-1</sup>. The Mg(SaIH)<sub>2</sub>.en and Mg(1N2N)<sub>2</sub>.en show only one band at 1100 cm<sup>-1</sup> and 1132 cm<sup>-1</sup>, respectively, whereas Mg(SaIA)<sub>2</sub>.en has two in that region at 1090 and 1135 cm<sup>-1</sup>. The *cis*-complex usually shows four bands in that region.

Moreover, the bands observed in far infrared region (between 604-400 cm<sup>-1</sup>) are very conclusive for a *trans* structure (Table 2) for all these magnesium

TABLE 2—SELECTED NH<sub>2</sub> BANDS (cm<sup>-1</sup>) IN THE FAR INFRARED REGION

Mg(SaIA) <sub>2</sub> .en	470	500	515
Mg(SaIH) <sub>2</sub> .en	520	535	555
Mg(1N2N) <sub>2</sub> .en	515	530	560
Mg(2H3NA) <sub>2</sub> .en	510	542	552

complexes. In conformity with the observations that *trans* complexes of *en* show three bands between 604-470 cm<sup>-1</sup>, all these magnesium complexes have three bands in that region. Further, the pattern of distribution of the bands is also even in that region. For a *cis*-isomer, one expects four or more in that region and the pattern is three (or more) clustered together, and one farther removed. As such, a *trans-en* polymeric structure can be suggested for all these complexes.

#### Acknowledgement

Thanks of the authors are due to C. S. I. R., New Delhi for financial assistance.

#### References

1. R. Y. LEE and P. HAMBRIGHT, *J. Inorg. Nuclear Chem.*, 1970, 31, 477.
2. A. G. HINZE and W. L. GROENEVELD, *Rec. Trav. Chim. Pays-Bas*, 1969, 88, 1275.
3. D. E. FARRON, *J. Chem. Soc. A*, 1971, 3481.

## Mixed Ligand Anionic Complexes of Cadmium(II)

BIPIN B. MAHAPATRA, D. PANDA, S. K. PUJARI and A. CHIRANJEEVI

Post-Graduate Department of Chemistry, G. M. College, Sambalpur-768 004

Manuscript received 20 August 1981, revised 7 January 1982, accepted 8 July 1982

Sixteen mixed ligand anionic complexes of cadmium(II) having the composition  $[M]_2[CdCl_4L_2]$ ,  $[M]_2[CdCl_4L']$ ,  $[M]_2[CdCl_4L'']$  and  $[M]_2[CdCl_4L''']$ , where M=monomethylammonium cation, L=pyridine,  $\beta$ -picoline,  $\gamma$ -picoline, quinoline, 4-aminopyridine, piperidine or thiourea; L'= $\alpha$ -picoline, quinaldine or 2,6-lutidine; L''=ethylenediamine, *o*-phenylenediamine, 1-10-phenanthroline or 2-2'-bipyridine; L'''=oxine or piperidylthiocarbamate, have been synthesized. The compounds of the first and third categories are octahedral and the later two types are penta-coordinated as inferred from elemental analysis, conductance and IR spectral studies.

DIVALENT cadmium forms several four coordinated tetrahedral complexes<sup>1-3</sup> with a variety of ligands containing O, N, S potential donor sites, involving the use of 5S 5P<sup>2</sup> hybrid orbitals. Even though the complexes of the composition  $CdX_4$  and  $CdX_4^{2-}$ , where X=Cl<sup>-</sup> and SCN<sup>-</sup>, have been studied<sup>4</sup> in detail potentiometrically, little work has been done to change the stereochemistry of these anionic complexes by reacting with other nitrogen and sulphur donor ligands. To increase the coordination number, particularly to synthesize complexes of coordination number five, we had earlier reported<sup>4,5</sup> penta-coordinated base-adducts of Zn(II) and Cd(II) dithiocarbamates with N and S donor ligands. Some anionic mixed ligand complexes of Co(II) and Ni(II) exhibiting unusual coordination number have also been reported<sup>6,7</sup>. This communication describes the preparation and characterisation of sixteen anionic mixed ligand complexes of cadmium(II) containing monomethylammonium chloride and nitrogen and sulphur donor ligands.

### Experimental

All chemicals used were of A. R. grade. An ethanolic solution of cadmium(II) chloride was treated with an ethanolic solution of monomethylammonium chloride in 1:2 ratio when a white crystalline compound separated out immediately. This was filtered, washed with ethanol and dried *in vacuo*.

The mixed ligand complexes were prepared by adding requisite amount (1:2 ratio) of the nitrogen/sulphur donor ligands to the methanolic solution of di-monomethylammonium tetrachlorocadmium(II). In some cases the compounds were formed immediately and in some cases refluxing was continued for 2 to 3 hr till a clear solution was obtained. A shining needle-shaped crystalline compound separated out on cooling, which was washed with ethanol, followed by ether and dried *in vacuo*.

Cadmium, nitrogen and chloride were estimated by following the standard methods. The conductance measurements were carried out at room temperature with 10<sup>-3</sup> M solution in acetone medium using a Toshniwal conductivity bridge. IR spectra of the complexes were recorded on KBr phase using Beckman IR-20 spectrophotometer. Relevant analytical and conductance data are given in Table I.

### Results and Discussion

Analysis and conductance data indicate that the complexes have the following composition:  $[M]_2[CdCl_4L_2]$ ,  $[M]_2[CdCl_4L']$ ,  $[M]_2[CdCl_4L'']$  and  $[M]_2[CdCl_4L''']$ , where M=monomethylammonium cation; L=pyridine,  $\beta$ -picoline,  $\gamma$ -picoline, quinoline, 4-aminopyridine, piperidine or thiourea; L'= $\alpha$ -picoline, quinaldine or 2,6-lutidine; L''=ethylenediamine, *o*-phenylenediamine, 1-10-phenanthroline or 2-2'-bipyridine and L'''=oxine or piperidylthiocarbamate.

All the compounds have high melting points and are white, greyish-white to yellow in colour, soluble in acetone in which medium the  $\Delta_M$  values are around 230 mhos cm<sup>2</sup> indicating 2:1 electrolytic nature of the first fourteen complexes. The  $\Delta_M$  values for the last two complexes are ~115 mhos cm<sup>2</sup> indicating them to be 1:1 electrolytes.

Study of IR spectra is quite informative. Absorption bands are noticed at 930(vs), 980(s), 1260(vs), 1410(s), 1485(s) and 3150(s) cm<sup>-1</sup>, characteristic of the bands due to monomethylammonium chloride, modified due to complexation. Most of the absorption bands due to free sulphur and nitrogen donor ligands have been modified in the anionic mixed ligand complexes, indicating their bonding to the cadmium(II) ion. In sodium salt of piperidylthiocarbamate, the appearance of bands at 840 and 1260 cm<sup>-1</sup> can be assigned to thiol (C-S) and thiocarbonyl (C=S) absorption bands, respectively. In Cd(II) complexes, shifting of these bands to lower

TABLE 1—ANALYSIS, MELTING POINT AND CONDUCTANCE DATA

Compound	m.p. °C	%Cd		%N		%Cl		$\Lambda_m$ mhos cm <sup>2</sup>
		Found	Reqd	Found	Reqd.	Found	Reqd.	
[M] <sub>2</sub> [CdCl <sub>4</sub> (Py) <sub>2</sub> ]	>250	23.52	23.69	11.72	11.80	29.47	29.77	240.00
[M] <sub>2</sub> [CdCl <sub>4</sub> ( $\beta$ -Pic) <sub>2</sub> ]	>250	22.17	22.46	11.12	11.19	28.08	28.12	230.00
[M] <sub>2</sub> [CdCl <sub>4</sub> ( $\gamma$ -Pic) <sub>2</sub> ]	>250	22.29	22.46	11.07	11.19	28.02	28.12	245.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (4-AP) <sub>2</sub> ]	>250	22.16	22.28	16.67	16.65	27.92	28.01	225.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (Q) <sub>2</sub> ]	>250	19.92	19.56	9.68	9.74	24.95	24.60	220.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (tu) <sub>2</sub> ]	>250	23.81	23.91	11.85	11.93	30.06	30.15	215.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (Pip) <sub>2</sub> ]	250	22.95	23.10	11.43	11.51	28.95	29.04	240.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (en) <sub>2</sub> ]	>250	29.75	29.89	14.72	14.87	32.18	32.35	220.00
[M] <sub>2</sub> [CdCl <sub>4</sub> ( <i>o</i> -Ph.D) <sub>2</sub> ]	>250	26.27	26.48	13.15	13.19	26.48	26.54	230.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (1,10-Ph) <sub>2</sub> ]	>250	22.51	22.64	11.16	11.28	28.37	28.46	225.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (2,2'-Bi) <sub>2</sub> ]	>250	23.62	23.79	11.79	11.85	29.83	29.90	220.00
[M] <sub>2</sub> [CdCl <sub>4</sub> ( $\alpha$ -Pic) <sub>2</sub> ]	>250	27.35	27.52	10.17	10.28	34.99	34.48	235.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (Quin) <sub>2</sub> ]	>250	24.27	24.46	9.08	9.14	30.58	30.74	225.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (2,6-Lut) <sub>2</sub> ]	>250	26.43	26.67	9.78	9.96	33.29	33.94	220.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (OX) <sub>2</sub> ]	>250	28.48	28.57	7.05	7.11	27.95	28.00	115.00
[M] <sub>2</sub> [CdCl <sub>4</sub> (P-dtc) <sub>2</sub> ]	>250	27.82	27.45	6.79	6.83	25.82	25.89	110.00

M = monomethylammonium cation, Py = pyridine,  $\alpha$ -Pic =  $\alpha$ -picoline,  $\beta$ -Pic =  $\beta$ -picoline,  $\gamma$ -Pic =  $\gamma$ -picoline, Q = quinaldo, 4-AP = 4-aminopyridine, tu = thiourea, Pip = piperidine, en = ethylenediamine, *o*-Ph.D = *o*-phenylenediamine, 1,10-Ph = 1,10-phenanthroline, 2,2'-Bi = 2,2'-bipyridine, Quin = quinaldine, 2,6-Lut = 2,6-lutidine, OX = oxine, P-dtc = piperidylthiocarbamate.

frequency region occurs, indicating coordination through both sulphur atoms  $\nu(\text{C}=\text{O})$  and  $\nu(\text{C}=\text{N})$  of oxine appear at 1200  $\text{cm}^{-1}$  and 1590  $\text{cm}^{-1}$ , respectively, indicating the coordination of oxine moiety to the Cd(II) ion through hydroxyl oxygen and ring nitrogen atom.

From the analysis, conductance and ir spectral studies, the compounds of the first and the third categories are octahedral in configuration. The compounds of the second category are presumed to be penta-coordinated because of the mono-adduct formation favoured by the sterically hindered nitrogen donor ligands like  $\alpha$ -picoline, quinaldine and 2,6-lutidine. The compounds of the fourth category are also penta-coordinated as inferred from analysis, conductance and ir spectral data. In view of the

spherical nature of Cd(II) ion and absence of crystal field effects, this possibility is not entirely unexpected. However, X-ray crystallographic study will reveal the exact stereochemistry of these complexes.

#### References

- 1 J C BAILAR, "Chemistry of the Coordination Compounds", Reinhold Publishing Co 1956 p 373
- 2 V I KUMOV, *Obshch Khim* Chem Abs, 1950 1993
- 3 J LEDER, *Z. Physikal Chem*, 1941, 188, 160
- 4 BIPIN B MAHAPATRA, B K MAHAPATRA and S GURU, *J Inorg Nuclear Chem*, 1977 39 1577
- 5 BIPIN B MAHAPATRA, S K PUJARI and A CHIRANJEEVI, *J. Indian Chem Soc*, 1981, 58, 714
- 6 BIPIN B MAHAPATRA, B K MAHAPATRA and S GURU, *J. Indian Chem Soc*, 1978 5, 513.
- 7 BIPIN B MAHAPATRA, S K PUJARI and S GURU, *J Indian Chem Soc*, 1980, 57, 372

# Isolation, Characterisation and Antimicrobial Activity Studies of the Mixed Ligand Complexes of Cd(II) with 8-Hydroxyquinoline and Various Salicylic Acids

Y. ANJANEYULU\*, R. PRADHAKARA RAO and R. Y. SWAMY

Department of Chemistry, Nagarjuna University, Nagarjunanagar-522 510

and

A. EKNATH and K. NARASIMHA RAO

Govt. Medical College, Guntur-522 004

A series of mixed ligand complexes of Cd(II) with the general formula  $CdL_1L_2$ , (where  $L_1$  = 8-hydroxyquinoline;  $L_2$  = salicylic acid, 5-chloro, 3,5-dibromo, 3,5-diiodo, 3,5-dinitro acetyl salicylic acids) are isolated in pure state and characterised by elemental analysis and infrared data. The low molar conductance of these complexes in DMF indicates non-electrolyte nature of these complexes. The antimicrobial activity of these complexes against 14 pathogenic bacteria and 5 fungi is studied under various conditions. Even though one 8-hydroxyquinoline molecule in the binary cadmium-oxinate is replaced by a low cost fungicide like salicylic acid in the formation of mixed ligand complexes, these mixed ligand complexes are found to possess fairly higher antimicrobial activity against several organisms than the binary cadmium-oxinate. The lipophilic tendency of these complexes is determined and its influence on the antimicrobial activity is critically examined. The probable mechanism of the toxic action of these complexes against various organisms is discussed.

**T**HOUGH 8-hydroxyquinoline (oxine) and its divalent metal chelates are known to possess fungicidal and bactericidal properties, the high cost of 8-hydroxyquinoline limits their applicability. It has been observed by the present authors in the use of oxine chelates as antimicrobial agents that the cost factor can be minimised by replacing one oxine molecule in the divalent metal oxinates of Cu(II)<sup>1</sup>, Hg(II)<sup>2</sup> and Cd(II) with a low cost fungicide like salicylic or substituted salicylic acids as heteroligands. A series of mixed ligand complexes of Cd(II) with oxine and salicylic acids are prepared and their antimicrobial activity is studied under various conditions. The relation between their antimicrobial activity and physico-chemical properties is examined critically to understand the mechanism of action. The results of these investigations are presented in this paper.

## Experimental

All the chemicals used are of analytical grade (B.D.H.) reagents.

**General method for the preparation of the complexes:** Equimolar solutions of salicylic acids (0.2 M), Cd(II) acetate (0.2 M) and 8-hydroxyquinoline (0.2 M) in 80% aqueous methanol are mixed. After stirring for 0.5 hr, the product is removed by filtration, washed with several volumes of water, digested in acetone and filtered. The complexes are dried at 70° for 12 hr. Metal and nitrogen are estimated by standard methods.

**Physical measurements:** Infrared spectra are recorded on a Perkin-Elmer model 577 spectrophotometer ( $4000\text{ cm}^{-1}$  to  $200\text{ cm}^{-1}$ ) by KBr disc technique. The conductivity of the complexes ( $10^{-3}\text{ M}$ ) is measured at 27° by Systronics conductivity bridge 305 in dimethyl sulphoxide (DMSO).

**Antimicrobial activity:** The antimicrobial activity of the compounds in DMSO is examined *in vitro* by serial dilution method<sup>3</sup> against various bacteria and by paper disc method<sup>4</sup> against fungi. All the stock cultures are obtained from the Department of Microbiology, All India Institute of Medical Sciences, New Delhi. Peptone water and saline water are used for making the inoculum for bacteria (18 hr cultures) and fungi, respectively. Nutrient broth and Sabourauds dextrose agar (M/s Hindustan Dehydrated Media, Bombay) are used as test media for bacteria and fungi, respectively. The minimum inhibition concentration (MIC;  $\mu\text{g/ml}$ ) of the compounds against bacteria and the average zone of inhibition (mm) of the compounds at 1000  $\mu\text{g/ml}$  against fungi are given in the Tables 2 and 3, respectively. All the tests are carried out in duplicate.

## Results and Discussion

The elemental analysis of these complexes (Table 1) show that Cd(II) forms mixed ligand complexes of general formula  $CdL_1L_2$  (where  $L_1$  = 8-hydroxyquinoline and  $L_2$  = salicylic or substituted salicylic acids). The low molar conductance

\* Author for correspondence.

TABLE 1—ANALYTICAL, CONDUCTOMETRIC AND IR DATA OF THE Cd-oxine-salicylate mixed ligand complexes

Sl. No.	Compounds	Colour	Decomp temp. °C	% metal		% nitrogen		$\Lambda$ mhos cm <sup>2</sup>	IR frequencies in mixed ligand complexes (cm <sup>-1</sup> )				
									Oxine		Salicylic acids		
				cal	obs	cal	obs		$\nu(M-O)$	$\nu(C-O)$	$\nu(M-N)$	$\nu_{asy}(O-C-O)$	$\nu_{sy}(O-C-O)$
1.	Cd(OX)(SA)	Greenish yellow	>300	28.55	28.50	3.56	3.52	8.1	380 b	1110 s	500 s	1570 b	1420 s
2.	Cd(OX)(Cl-SA)	Greenish yellow	>300	26.25	26.28	3.27	3.25	8.6	390 b	1110 s	500 s	1570 b	1420 s
3.	Cd(OX)(2Br-SA)	Greenish yellow	>300	20.38	20.36	2.54	2.55	8.4	380 b	1110 s	500 s	1570 s	1420 s
4.	Cd(OX)(2I-SA)	Greenish yellow	292	17.57	17.58	2.18	2.14	8.8	380 b	1110 s	500 s	1570 s	1420 s
5.	Cd(OX)(2NO <sub>2</sub> -SA)	Golden yellow	298	23.24	23.21	8.69	8.66	8.2	390 b	1110 s	490 s	1570 s	1420 s
6.	Cd(OX)(Ace-SA)	Greenish yellow	>300	25.79	25.81	3.27	3.23	8.4	380 b	1110 s	490 s	1570 s	1420 s

OX = 8-hydroxyquinoline, SA = salicylic acid, Cl-SA = 5-chloro salicylic acid, 2Br-SA = 3,5-dibromo salicylic acid, 2NO<sub>2</sub>-SA = 3,5-dinitro salicylic acid, 2I-SA = 3,5-diiodo salicylic acid, Ace-SA = acetyl salicylic acid, s = sharp, b = broad

TABLE 2—ANTIBACTERIAL ACTIVITY MIC ( $\mu$ g/ml) OF THE CADMIUM COMPLEXES WITH 8-HYDROXYQUINOLINE AND SUBSTITUTED SALICYLIC ACIDS AT 37° AFTER 18 Hr IN NUTRIENT BROTH

Sl No	Compound	Gram-positive		Gram-negative											
		1	2	3	4	5	6	7	8	9	10	11	12	13	14
1.	Cd(OX) <sub>2</sub>	12.5	6.2	12.5	25	50	12.5	50	12.5	100	25	12.5	12.5	12.5	>100
2.	Cd(OX)(SA)	6.2	3.1	12.5	100	3.1	50	50	12.5	12.5	25	25	12.5	25	25
3.	Cd(OX)(Cl-SA)	6.2	3.1	12.5	100	3.1	50	100	25	3.1	25	25	12.5	50	50
4.	Cd(OX)(2Br-SA)	6.2	3.1	12.5	100	3.1	50	100	12.5	3.1	25	25	12.5	25	50
5.	Cd(OX)(2I-SA)	12.5	6.2	12.5	100	6.2	50	100	25	25	25	25	25	50	50
6.	Cd(OX)(2NO <sub>2</sub> -SA)	6.2	3.1	6.2	100	3.1	50	100	12.5	6.2	25	25	25	50	50
7.	Cd(OX)(Ace-SA)	12.5	3.1	25	100	6.2	50	100	25	50	50	25	12.5	25	25

(1) *Staph. albus*, (2) *Staph. aureus*, (3) *Sch. schmitzi*, (4) *Pseudomonas pyocanes*, (5) *Shigella sonnei*, (6) *Klebsilla aerogenes*, (7) *Proteus morganii*, (8) *Shigella flexneri*, (9) *Vibrio cholerae*, (10) *Escherichia coli*, (11) *Salmonella typhi*, (12) *Salmonella paratyphi-A*, (13) *Salmonella paratyphi-B*, (14) *Shigella boydii*.

values of these complexes in DMSO indicate that they are of non-electrolyte type.

**Infrared data:** The asymmetric  $\nu(O-C-O)$  and the symmetric  $\nu(O-C-O)$ , which appeared in all the salicylic acids around 1600 and 1440 cm<sup>-1</sup> respectively are found to be shifted in the mixed complexes to lower values of 1570 and 1420 cm<sup>-1</sup>, indicating metal carboxylate linkage<sup>5,6</sup>. Charles *et al*<sup>7</sup> reported that in several oxine complexes of metals, the  $\nu(C-O)$  is observed at 1120 cm<sup>-1</sup> region but the position of the bands slightly varies with the metal. The  $\nu(C-O)$ , which appeared in the free oxine molecule at 1090 cm<sup>-1</sup> is found to be shifted in all the mixed complexes giving a strong absorption band at 1110 cm<sup>-1</sup> indicating clearly the oxine coordination in the complex. In all the mixed ligand complexes, the observed band in the neighbourhood of 500 cm<sup>-1</sup> may be identified as M-N stretching frequency<sup>8</sup>. A broad band at 380-400 cm<sup>-1</sup> in all the complexes may be assigned to metal-oxygen stretching frequency<sup>8</sup>.

**Antimicrobial activity:** The toxic effect of the cadmium-oxine-salicylic or substituted salicylic acid mixed ligand complexes against various bacteria and fungi is found to be either equal or slightly greater than the cadmium-bis-8-hydroxyquinoline complex. Salicylic acid or substituted salicylic acids and their cadmium chelates are

found to have measurable activity against these bacteria and fungi only at relatively high concentrations (for bacteria >100  $\mu$ g/ml, fungi >2000  $\mu$ g/ml). This may be due to their higher water solubility. Albert *et al* explained the antimicrobial activity of copper(II)-bis-8-hydroxyquinoline by assuming that this complex first penetrates the cell and undergoes dissociation to a 1:1 copper-oxine complex and free oxine at the site of action. The 1:1 chelate will become the toxic entity by combining with and blocking metal binding sites on enzymes. Thus the 1:2 chelate due to its lipo solubility is necessary to take the toxic moiety i.e. the 1:1 charged complex to the site of action. The assumption was supported by the fact that antimicrobial activity of these complexes was reversed in the presence of excess of copper. This may be due to the inability of the ionically charged 1:1 chelate (which is produced in the presence of excess of metal) to penetrate the cell membrane. Block<sup>9</sup> proposed that the natural chelates within the cell were poisoned by removing copper from Cu(II)-oxine, thereby freeing oxine which could then bind the metallic prosthetic groups of the enzymes. Zentmyer *et al*<sup>10</sup> proposed a mechanism of detoxication of the 1:2 chelate by natural metabolites. The 1:2 chelate dissociates to the 1:1 chelate, thereby entering the aqueous phase of the cell. Histidine and cystine, which form more

stable complexes with copper than the 1 : 1 chelate of copper and 8-hydroxyquinoline, remove the copper and form lipid soluble chelates. Esposito and Fletcher<sup>11</sup> proposed that the activity of copper(II)-8-hydroxyquinoline was due to the 1 : 1 complex which could bind with an enzyme site involved in the biosynthesis of pteridines. This was based on the reversal of inhibition by several pteridines and precursors. It is also believed that a similar mechanism may be working well in explaining the toxic action of all other bivalent oxinates.

According to Overton's concept of cell permeability, the lipid membrane surrounding the cell favours the passage of lipid soluble materials through the membrane and lipo solubility is considered as one of the important factors that control the antimicrobial activity of any toxic agent. The partition of the toxic agent between oily alcohol or chloroform and pH 7.4 phosphate buffer system is considered as a good model to understand the lipophilic or lipophobic tendency<sup>12</sup>. So we have determined the distribution of all these complexes between chloroform and pH 7.4 buffer and the results are given in Table 4. As expected, the cadmium-oxine salicylic acid or substituted salicylic acids

salicylic acids and cadmium-oxine-diiodosalicylic acid must have maximum activity. But no such relation is found to exist from their antimicrobial activity screening studies (Tables 2 and 3) which

TABLE 4—PERCENTAGE EXTRACTION OF METAL INTO CHLOROFORM AT pH 7.4

Sl. No.	Complex	% of cadmium extracted
1.	Cd(OX) <sub>2</sub>	45
2.	Cd(OX)(SA)	26
3.	Cd(Cl-SA)(OX)	37
4.	Cd(2Br-SA)(OX)	40
5.	Cd(2I-SA)(OX)	42
6.	Cd(NO <sub>2</sub> -SA)(OX)	35
7.	Cd(Ace-SA)(OX)	35
8.	Cd(SA) <sub>2</sub>	7
9.	Cd(Cl-SA) <sub>2</sub>	3
10.	Cd(2Br-SA) <sub>2</sub>	9
11.	Cd(2I-SA) <sub>2</sub>	5
12.	Cd(2NO <sub>2</sub> -SA) <sub>2</sub>	2
13.	Cd(Ace-SA) <sub>2</sub>	2

TABLE 3—ANTIFUNGAL ACTIVITY OF THE CADMIUM COMPLEXES WITH 8-HYDROXYQUINOLINE AND SALICYLIC ACIDS AT 1000 µg/ml IN SABOROUND'S DEXTROSE AGAR AFTER 48 Hr AT 80°

Sl. No.	Compound	Zone of inhibition in mm at 1000 µg/ml				
		1	2	3	4	5
1.	Cd(OX) <sub>2</sub>	9	7	—	—	7
2.	Cd(OX)(SA)	—	7	—	—	9
3.	Cd(OX)(Cl-SA)	7	10	9	12	7
4.	Cd(OX)(2Br-SA)	9	—	—	8	9
5.	Cd(OX)(2I-SA)	—	8	—	9	9
6.	Cd(OX)(2NO <sub>2</sub> -SA)	7	7	—	—	7
7.	Cd(OX)(Ace-SA)	—	8	—	7	7

Fungi: (1) *Penicillium* spp., (2) *Asp. niger*, (3) *Tricophyton rubrum*; (4) *Asp. fumigatus*, (5) *Candida albicans*.

mixed complexes have lower partition coefficient in chloroform when compared to cadmium(II)-oxine complex. However, they have equal or slightly more toxic effect against various bacteria and fungi in comparison to cadmium(II)-bis-8-hydroxyquinoline complex. This indicates that in the mixed complexes not only the 1 : 1 cadmium oxine complex is having toxic activity but also the released salicylic acid may be playing an important role in the antimicrobial activity through a different mechanism. The salicylic acids or cadmium salicylate chelates, though possessing toxic effects due to their higher water solubility, cannot go to the site of action as much as the mixed complexes can penetrate. If in the mixed complexes also the 1 : 1 cadmium oxine is the only toxic moiety then the antimicrobial activity of the mixed complexes should increase with increasing  $pK_1$  values of the

indicate that salicylic acids also play an important role in the toxic action. It is also believed that if the geometry and charge distribution around the molecule are incompatible with geometry and charge distribution around the peripheries of the pores of the fungal or bacterial cell wall, penetration through the wall by the toxic agent cannot take place and toxic reactions within the spore do not occur. This may be one of the reasons for certain mixed ligand complexes showing less effective antimicrobial activity than the corresponding Cd(OX)<sub>2</sub> complex.

#### Acknowledgement

The authors thank Prof. L. N. Mohapatra, Professor and Head of the Department of Microbiology, All India Institute of Medical Sciences, New Delhi for the stock cultures of the bacteria and fungi, and Prof. G. D. Mehta, Dean, School of Chemistry, University of Hyderabad, for help in obtaining the ir data. Financial support of the Council of Scientific and Industrial Research, New Delhi is also gratefully acknowledged.

#### References

1. Y. ANJANEYULU, R. Y. SWAMY and R. PRABHAKARA RAO, in XXII<sup>nd</sup> COO, Budapest, 1982, 208.
2. Y. ANJANEYULU, R. PRABHAKARA RAO, R. Y. SWAMY, A. EKNATH and K. NARASIMHA RAO, *Proc. Indian Acad. Sci. (Chem. Sci.)*, 1982, 91, 157.
3. I. G. SCHAUZ, M. K. FOLBY, E. G. SCOTT and W. R. BAILEY, "Diagnostic Bacteriology", the C. V. Mosby Company, St. Louis, 1958, p. 198.
4. C. JASPER, MARUZZELLA and P. A. HENRY, *J. Amer. Phar. Assoc.*, 1958, 47, 471.
5. L. J. BELLAMY "Infrared Spectra of Complex Molecules", Methuen & Co. Ltd., London, 1956, p. 279.



6. K. C. GOYAL and B. D. KHOSLA, *J. Indian Chem. Soc.*, 1980, **57**, 124.
7. R. C. CHARLES, M. FANISH, R. FRIEDEL, L. E. HILLAR and W. D. JOHNSTON, *Spectrochim. Acta*, 1956, **8**, 1.
8. K. NAKAMOTO "Infrared Spectra of Inorganic and Coordination Compounds", Wiley-Interscience, New York, 1970.
9. S. B. BLOCK, *J. Agr. Food Chem.*, 1955, **3**, 7229.
10. G. A. ZENTMYER, S. RICH and J. G. HORSFALL, *Phyto Pathology*, 1960, **50**, 421.
11. R. G. ESPOSITO and A. M. FLETCHER, *Arch. Biochem. Biophys.*, 1961, **93**, 869.
12. F. P. DWYER and D. P. MELLOR "Chelating Agents and Metal Chelates", Academic Press, New York, 1964, p. 407.

## Some Anionic Organotellurium Complexes

T. N. SRIVASTAVA\*, R. C. SRIVASTAVA and (Miss) M. SRIVASTAVA

Chemistry Department, Lucknow University, Lucknow-226 007

Manuscript received 9 September 1981, accepted 23 May 1982

Complexes of the formulae  $[R_4N]^+ [C_6H_{10}TeI_2X']^{2-}$  and  $[R_4N]^+ [p-C_6H_4-$

$OC_6H_4TeCl_2X']^{2-}$ , where  $R = CH_3, C_2H_5, C_6H_5$ , or  $C_4H_9$ ;  $X' = I, Br$  or  $Cl$ , have been synthesised by refluxing a solution of 1-telluracyclohexane 1:1 diiodide or *p*-phenoxyphenyltellurium trichloride in chloroform with tetraalkylammonium halides in the same solvent. The complexes are ionic in nature and have been characterised through analytical, conductance and molecular weight data and nmr spectral studies. The activity of the complexes against certain microorganisms has been tested but not found significant.

COMPLEXES containing dihalo- or tetrahalomono-organoyltellurate anions of the formula  $[R_4N]^+ [TeX_4]^{2-}$  and  $[R_4N]^+ [TeX_4]^{2-}$  have recently been reported<sup>1-4</sup>. In continuation of our studies on Lewis acid behaviour of diorganoyltellurium dihalides<sup>5,6</sup> we report the synthesis, characterization and antimicrobial activity of some new complexes of the formulae  $[R_4N]^+ [C_6H_{10}TeI_2X']^{2-}$  and  $[R_4N]^+ [p-C_6H_4-OC_6H_4TeCl_2X']^{2-}$ .

### Experimental

1-Telluracyclohexane-1,1-diiodide<sup>7</sup> and *p*-phenoxyphenyltellurium trichloride<sup>8</sup> were prepared by reported methods. Tetraalkylammonium halides were obtained from B.D.H. and used as such. <sup>1</sup>H NMR, molecular weight and conductivity data were collected as reported earlier<sup>5</sup>.

The desired complexes were prepared (a) by the direct interaction of tetraalkylammonium halides with organotellurium halides and (b) by halogen exchange reaction in certain organotellurium(IV) tetrahalo anions.

(a) 1-Telluracyclohexane-1,1-diiodide (2 m mol) was refluxed with a solution of tetraalkylammonium salt (4 m mol) in chloroform or dichloromethane (50 ml) for 4-5 hr. Concentration of the reaction mixture followed by addition of petroleum ether (40-60°) afforded the desired complexes which were recrystallised from dichloromethane/petroleum ether (40-60°) mixture.

(b) An aqueous solution of potassium iodide (4 m mol) was added to a solution of tetramethylammoniumtrichlorobromo-*p*-phenoxyphenyltellurate(IV) (0.55 g; 1 m mol) in 4 N HCl with constant stirring. The corresponding tetraiodo compound was precipitated in quantitative yield, filtered, washed with water and air dried.

Analytical data of the complexes prepared are given in Tables I and 2.

### Results and Discussion

All the complexes are crystalline solids with sharp melting points. Molar conductance values of 10<sup>-3</sup>M solution in acetonitrile lie in the range 208-250 ohm<sup>-1</sup> cm<sup>2</sup> mol<sup>-1</sup> for tetrahalocyclohexanetellurates and 124-168 ohm<sup>-1</sup> cm<sup>2</sup> mol<sup>-1</sup> for tetrahalo-*p*-phenoxyphenyltellurates. The values correspond to 2:1 and 1:1 electrolytic behaviour of the complexes, respectively<sup>9</sup>. The observed molecular weights (in nitrobenzene) for tetrahalocyclohexanetellurates are approximately one-third of the calculated value indicating that the complexes are dissociated into three ions in solution, whereas the observed molecular weights of tetrahalo-*p*-phenoxyphenyltellurates are about half of the calculated values showing their 1:1 electrolytic behaviour.

**Infrared spectra:** Infrared spectra of the complexes have been recorded in the region 4000-400 cm<sup>-1</sup>. Vibrational frequencies associated with the cations are in close agreement with those reported<sup>10</sup> and are not tabulated. Infrared absorption associated with  $\nu(Te-C)$  lies in the range 530±10 cm<sup>-1</sup> and is not significantly affected by the nature of the halide groups attached to the metal atom.

**<sup>1</sup>H NMR:** <sup>1</sup>H NMR spectra of  $[(C_2H_5)_4N]^+ [C_6H_{10}TeI_2Br_2]^{2-}$  and  $[(C_2H_5)_4N]^+ [p-C_6H_4-OC_6H_4TeCl_2]^{2-}$  were recorded at room temperature. A multiplet in the region  $\delta$  3.34- $\delta$  3.12 is observed due to  $CH_2-N$  protons whereas a triplet in the region  $\delta$  1.27- $\delta$  1.21 may be assigned to  $-CH_2$  protons. Two multiplets at  $\delta$  3.34 (coupled with  $CH_2-N$  protons) are attributed to  $-CH_2-Te$  and the singlet at  $\delta$  2.35 to  $-CH_2-C$  protons of ring in telluracyclohexane derivatives<sup>11</sup>. Two doublets at  $\delta$  7.90 and  $\delta$  6.51 are observed due to *m*- and *o*-protons of aromatic ring bonded to tellurium in *p*-phenoxyphenyl derivative<sup>12</sup>. A complex at  $\delta$  6.90 may be assigned to phenyl ring ( $C_6H_5O-$ ) in

TABLE 1—ANALYTICAL DATA OF  $[R_4N]_2[C_6H_4TeI_2X']_2$ 

R	X'	m.p. °C	Yield %	Colour	Analysis%, Found (Calcd)				X'	Conductance ohm <sup>-1</sup> mol <sup>-1</sup> cm <sup>2</sup>	Molecular weight, Found (Calcd)
					Te	O	H	N			
Me	Cl	280	70	White	19.00 (19.04)	23.25 (23.31)	5.01 (5.11)	4.15 (4.18)	48.09 (48.48)	208	215.2 (215.8)
Me	Br	190d	75	Greenish	16.66 (16.79)	20.50 (20.55)	4.55 (4.51)	3.50 (3.68)	54.16 (54.44)	235	240.2 (240.6)
Me	I	128	76	Purple	14.75 (14.94)	18.15 (18.28)	4.00 (4.01)	3.22 (3.28)	59.40 (59.50)	220	415.5 (415.6)
Et	Cl	120	85	Brown	15.90 (16.29)	32.10 (32.21)	6.35 (6.43)	3.55 (3.57)	41.80 (41.47)	210	250.0 (250.0)
Et	Br	175	79	Yellow	14.55 (14.63)	28.80 (28.93)	5.50 (5.78)	3.15 (3.21)	47.02 (47.43)	239	280.6 (271.8)
Et	I	194	72	Brown	13.00 (13.21)	25.99 (26.11)	5.15 (5.21)	2.88 (2.90)	52.50 (52.55)	212	324.8 (325.8)
Pr	I	189-141	80	Brown	10.95 (11.88)	32.09 (32.80)	6.15 (6.17)	2.56 (2.59)	47.00 (47.08)	210	359.3 (359.9)
Bu	Cl	110	80	Brown	12.50 (12.66)	44.10 (44.11)	8.10 (8.20)	2.70 (2.78)	31.90 (32.28)	250	320.8 (320.4)
Bu	I	122	68	Brown	10.52 (10.72)	37.20 (37.38)	6.92 (6.94)	2.30 (2.35)	42.16 (42.64)	240	350.0 (350.0)
*Et	I	194	75	Dark brown	13.15 (13.21)	25.95 (26.11)	5.20 (5.21)	2.80 (2.90)	52.45 (52.55)	210	315.5 (315.8)

TABLE 2—ANALYTICAL DATA OF  $[R_4N]_2[p-C_6H_4OC_6H_4TeCl_2X']_2$ 

R	X'	m.p. °C	Yield %	Colour	Analysis%, Found (Calcd)				X'	Conductance ohm <sup>-1</sup> mol <sup>-1</sup> cm <sup>2</sup>	Molecular weight, Found (Calcd)
					Te	O	H	N			
Me	Cl	290	70	White	24.56 (24.87)	37.75 (37.46)	4.10 (4.12)	2.68 (2.73)	27.68 (27.73)	140	240.4 (242.9)
Me	Br	172	85	Light yellow	22.70 (22.89)	34.30 (34.47)	3.70 (3.79)	2.45 (2.51)	32.86 (33.44)	151	260.6 (267.8)
Me	I	196	89	Brown	20.95 (21.11)	31.60 (31.79)	3.45 (3.50)	2.29 (2.31)	38.55 (38.63)	150	302.1 (304.9)
Et	Cl	116	80	White	21.90 (22.40)	42.15 (42.21)	5.12 (5.13)	2.42 (2.46)	24.80 (24.95)	124	280.5 (289.4)
Et	Br	118-115	89	Light yellow	20.59 (20.80)	38.96 (39.15)	4.68 (4.76)	2.25 (2.28)	30.25 (30.38)	142	290.2 (291.4)
Et	I	105	81	Brown	19.23 (19.32)	36.27 (36.37)	4.40 (4.42)	2.10 (2.12)	34.90 (35.18)	150	320.2 (320.4)
Pr	I	111-114	90	Brown	17.70 (17.81)	40.20 (40.28)	5.15 (5.20)	1.90 (1.95)	32.40 (32.58)	158	345.2 (346.8)
Bu	I	84	85	Purple	16.45 (16.51)	42.50 (42.52)	6.70 (6.87)	1.75 (1.81)	30.15 (30.22)	142	315.2 (317.6)
*Me	I	159	82	Reddish brown	14.40 (14.58)	21.70 (21.87)	2.30 (2.40)	1.49 (1.59)	57.67 (57.77)	155	480.0 (478.0)
*Et	I	116-117	92	Reddish brown	13.54 (13.66)	25.52 (25.70)	3.10 (3.12)	1.40 (1.49)	53.95 (54.80)	168	487.0 (484.0)

\* Anionic complexes obtained by halogen exchange reaction

$[(C_6H_5)_4N] [(C_6H_4OC_6H_4TeCl_2)]_2$ . The spectra and their integrations correspond to the proposed stoichiometry of the complexes. An octahedral and a square pyramidal structure are tentatively assigned to tetrahalocyclohexanetellurates and *p*-phenoxyphenyltetrahalotellurates, respectively in analogy with previous reports<sup>2-6</sup>.

**Bio-assay:** The antimicrobial activity of the complexes were screened against five bacteria *Streptococcus faecalis*, *Klebsiella pneumoniae*, *Escherichia coli*, *Pseudomonas aeruginosa*, *Staphylococcus aureus*, and five fungi *Candida albicans*, *Cryptococcus neoformans*, *Sporotrichum schenikii*, *Trichophyton mentagrophytes*, *Aspergillus fumigatus*.

The complexes show moderate activity towards the bacteria and are inactive against the fungi.

The activity of the complexes (soluble in methanol) was assayed by twofold serial dilution method. The maximum concentration for the tested compound was 100 µg/ml. The fungi was incubated at 28 ± 1° and the bacteria at 37°. The incubation period was 24 hr for all the bacteria and the fungi *Candida albicans*, *Sporotrichum schenikii*, 48 hr for *Cryptococcus neoformans* and *Aspergillus fumigatus* and 96 hr for *Trichophyton mentagrophytes*. *Klebsiella pneumoniae* is affected by all the complexes. *Staphylococcus aureus* (gram positive) appears to be sensitive against bis-tetraethyl ammo-

nium tetraiodocyclohexanetellurate. *Bis*-tetramethyl ammonium tetraiodocyclohexanetellurate is active against *Streptococcus faecalis*. All the complexes are completely inactive against gram negative bacteria, *E. coli* and *Pseudomonas aeruginosa* and all the fungi used.

#### Acknowledgement

The authors are thankful to the Director, C.D.R.I., Lucknow for spectroscopic and analytical facilities. Financial assistance to one of the authors (M.S.) from U.G.C., New Delhi is gratefully acknowledged.

#### References

1. K. J. INGOLIS, "The Organic Chemistry of Tellurium", Gordon and Breach, New York, 1974.
2. N. PETRAGNANI, L. C. TORRES, K. J. WYNNE and D. J. WILLIAMS, *J. Organometal. Chem.*, 1974, 76, 241.
3. N. PETRAGNANI, L. C. TORRES, K. J. WYNNE and W. MAXWELL, *J. Organometal. Chem.*, 1978, 55(2), 295.
4. N. PETRAGNANI, J. V. CAMAROTTO and Y. KAWANO, *J. Inorg. Nuclear Chem.*, 1978, 38, 608.
5. T. N. SRIVASTAVA, R. C. SRIVASTAVA and MALA SINGH, *J. Organometal. Chem.*, 1978, 157, 405.
6. T. N. SRIVASTAVA, R. C. SRIVASTAVA and MALA SINGH, *Indian J. Chem.*, 1979, 18A, 527.
7. W. V. FARRAR and J. M. GULLAND, *J. Chem. Soc.*, 1945, 11.
8. H. D. K. DREW, *J. Chem. Soc.*, 1926, 228.
9. W. J. GEARY, *Coord. Chem. Rev.*, 1971, 7, 81.
10. E. MASLOWSKY, Jr., *J. Organometal. Chem.*, 1974, 70, 153.
11. E. T. STORM, B. S. SNOWDEN, H. C. GUSTARD JR., D. E. WOESSNER and J. R. NORTON, *J. Org. Chem.*, 1968, 33, 2555.
12. V. I. MINKIN, I. D. SADEROV, L. M. SAYAPINA and MINYANV, *Z. Obshch. Khim.*, 1978, 43, 809.

## • Metal Derivatives of Organoantimony Compounds : Reactions of Anhydrous Chlorides of B(III), V(III) and Sn(IV) with Arylantimony Compounds

HEMANT K. SHARMA, S. N. DUBEY and D. M. PURI\*

Department of Chemistry, Kurukshetra University, Kurukshetra-132 119

The reactions of anhydrous B(III), V(III) and Sn(IV) chlorides with tetraphenylstibonium chloride, triphenylantimony dichloride and triphenylstibine have been studied. Tetraphenylstibonium chloride is found to form ionic complexes with anhydrous metal chlorides. Triphenylantimony dichloride forms adducts with the chlorides of B(III) and V(III) involving chlorine bridges whereas no adduct has been isolated from anhydrous stannic chloride. The complexes have been characterized by elemental analyses, spectral data (ir and pmr), molar conductivity and magnetic susceptibility measurements.

TAKASHI<sup>1</sup> has studied the reactions of alkylantimony compounds with titanium chlorides. Ionic complexes of the type  $[R_4M][R'_3M'X_3]$  or  $[R_4M]_2[R'_3M'X_3]$  (where R, R' = CH<sub>3</sub>, C<sub>2</sub>H<sub>5</sub> or C<sub>6</sub>H<sub>5</sub>; M = N, P, As or Sb; M' = Sn or Te and X = halo or pseudo-halo anion) have also been reported both from structural as well as biological activity points of view<sup>2-7</sup>. Study of the reactions between organoantimony compounds and titanium(IV) chloride has also been reported from our laboratory<sup>8</sup> and the formation of  $[Ph_4Sb][TiCl_4]$ ,  $[Ph_4Sb]_2[TiCl_4]$  and  $Ph_4SbCl_3 \cdot TiCl_4$  has been confirmed. The work has been extended to the reactions of B(III), V(III) and Sn(IV) chlorides.

### Experimental

Anhydrous boron trichloride (Hopkin William; b.p. 12.5°), vanadium(III) chloride, stannic chloride (B.D.H.) and triphenylstibine (E. Merck) were used as such. Tetraphenylstibonium chloride<sup>9</sup> and triphenylantimony dichloride<sup>10</sup> were prepared by known methods. Solvents were dried and deoxygenated before use. Because of the hygroscopic nature of some of the reactants and products, all preparations were carried out under anhydrous conditions. The reaction mixtures were flushed with dry nitrogen gas to maintain an inert atmosphere.

**General method of preparation of ionic complexes:** To a dry benzene or alcoholic solution of anhydrous metal chloride was added slowly and dropwise a benzene or alcoholic solution of tetraphenylstibonium chloride at room temperature under dry nitrogen atmosphere with vigorous shaking. There was no evolution of heat during the course of reaction. The nitrogen gas was passed for 6 to 10 hr and then the flask was stoppered and kept aside for a day or two for complete separation of the solid product. In case of Sn(IV) complex, volume of the reaction mixture was reduced under vacuum. The supernatant solvent was decanted off. The

compound was washed successively with dry benzene and dry *n*-hexane and dried *in vacuo* (1-2 mm) at room temperature. The analytical data is given in Table I.

The reaction of boron trichloride was carried out at 0°.

**Preparation of adducts:** A benzene or acetonitrile solution of triphenylantimony dichloride was added dropwise to a dry benzene or acetonitrile solution of metal chloride under dry nitrogen atmosphere. There was no change in colour or temperature of the reaction mixture. The mixture was refluxed for 10 to 15 hr. The flask, after cooling, was stoppered and kept aside for a day when a solid compound settled down. Excess of solvent was decanted off and the precipitate was washed with dry benzene (2 to 3 times) and finally with dry *n*-hexane. It was dried *in vacuo* at 70°. The analytical data is given in Table I.

In case of boron, the compound formed at room temperature. However, no compound formed when anhydrous stannic chloride was reacted with triphenylantimony dichloride.

**Physical measurements:** Infrared spectra of the compounds (4000-600 cm<sup>-1</sup>) were recorded in nujol or KBr in Beckman IR-20 spectrophotometer. Far ir spectra of the compounds (600-250 cm<sup>-1</sup>) were taken using polythene sheets. PMR spectrum was recorded on Perkin-Elmer 90 MHz spectrophotometer in DMSO-d<sub>6</sub>. The conductivity measurements were carried out in *N,N'*-dimethylformamide on an Elico conductivity bridge, type CM-82T. The magnetic susceptibilities were determined on Gouy's balance.

### Results and Discussion

The analytical data of the quaternary complexes of boron(III) and vanadium(III) indicated the formation of  $[Ph_4Sb][MCl_4]$  [M = B(III) or V(III)] from tetraphenylstibonium chloride and anhydrous

TABLE 1—ANALYTICAL AND CONDUCTIVITY DATA OF THE COMPLEXES

Compound	Colour	m.p. °C	Analysis%, Found (Calcd)			$\Delta M$ (in <i>N,N'</i> -Dimethyl formamide) mhos $\text{cm}^2 \text{mole}^{-1}$
			C	H	Cl	
$[\text{Ph}_4\text{Sb}][\text{BCl}_4]$	White-crystalline	245(d)	48.96 (49.44)	2.86 (3.43)	25.56 (24.38)	53.2
$\text{Ph}_4\text{SbCl}_2 \cdot 2\text{BCl}_3$	White	>260	81.84 (82.81)	2.77 (2.27)	42.68 (43.14)	—
$[\text{Ph}_4\text{Sb}][\text{VCl}_4]$	Green	—	45.16 (46.25)	2.96 (3.21)	21.46 (22.81)	75.4
$\text{Ph}_4\text{SbCl}_2 \cdot \text{VCl}_3$	Grey	>260	36.18 (37.36)	1.98 (2.59)	31.48 (30.7)	—
$[\text{Ph}_4\text{Sb}]_2[\text{SnCl}_6]$	White-crystalline	195	47.68 (48.36)	3.14 (3.35)	19.68 (17.88)	114.8 50.3*

d = decomposed, \* molar conductivity in nitrobenzene.

metal chlorides in the molar ratio of 1 : 1 whereas the complex  $[\text{Ph}_4\text{Sb}]_2[\text{SnCl}_6]$  was formed when tetraphenylstibonium chloride and stannic chloride were reacted in molar ratio of 2 : 1.

The adducts of the type  $\text{Ph}_4\text{SbCl}_2 \cdot x\text{MCl}_3$  [ $x = 1$  or 2,  $M = \text{B(III)}$  or  $\text{V(III)}$ ] were formed when triphenylantimony dichloride was reacted with the chlorides of boron(III) and vanadium(III). Attempts to synthesize the adduct between stannic chloride and triphenylantimony dichloride were unsuccessful.

The reactions of triphenylstibine with vanadium(III) and tin(IV) chloride were studied with a view to synthesizing either triphenylantimony dichloride or obtaining addition products. However, the attempt was unsuccessful. The solid products obtained in these cases after the decantation of the solvent did not show the presence of carbon. The elemental analyses also did not tally with any definite composition. Further, the products were not reproducible. It could be inferred from these observations that a cleavage of the C-Sb bond was probably taking place.

The molar conductance values of the compounds obtained from  $\text{Ph}_4\text{SbCl}_2$  and metal chlorides (Table 1) indicated them to be 1 : 1 electrolytes for  $[\text{Ph}_4\text{Sb}][\text{MCl}_4]$  [ $M = \text{B(III)}$  or  $\text{V(III)}$ ] and 2 : 1 electrolyte for  $[\text{Ph}_4\text{Sb}]_2[\text{SnCl}_6]$ . The conductivity of the adducts  $\text{Ph}_4\text{SbCl}_2 \cdot x\text{MCl}_3$  could not be determined due to their insolubility in common organic solvents.

The infrared spectra of the cations  $[\text{Ph}_4\text{Sb}]^+$  showed bands in the region  $450\text{--}440 \text{ cm}^{-1}$  for carbon-antimony asymmetric stretching frequency<sup>11,12</sup>.

For a regular tetrahedral ion  $[\text{MCl}_4]^-$ , there are only two fundamentals which are infrared active, viz.,  $\nu_2$  and  $\nu_4$  which are triply degenerate<sup>13</sup>. In the tetrachloroborate anion  $[\text{BCl}_4]^-$ , three weak bands were observed at  $1470$ ,  $1380$  and  $1270 \text{ cm}^{-1}$  and two strong bands at  $685$  and  $670 \text{ cm}^{-1}$  which could be assigned to  $2\nu_2$ ,  $\nu_1 + \nu_4 + \nu_2$ ,  $2\nu_1 + 2\nu_4$ ,  $\nu_3$  and  $\nu_1 + \nu_4$  vibrations, respectively as has been observed by Waddington *et al* for  $[\text{POCl}_3]^+[\text{BCl}_4]^-$  complex<sup>14</sup>. Occurrence of a band at  $370 \text{ cm}^{-1}$  in

the anion  $[\text{BCl}_4]^-$  suggests distortion in the tetrahedral symmetry which may be due to the  $\nu_1$  vibrations<sup>15</sup>. The triply degenerate asymmetric vibrations of the  $[\text{VCl}_4]^-$  ion occurred at  $410 \text{ cm}^{-1}$ . This value for the  $\nu(\text{V}-\text{Cl})$  modes is in agreement with the value of  $406 \text{ cm}^{-1}$  for  $[\text{Ph}_3\text{MeAs}]^+[\text{VCl}_4]^-$  reported earlier<sup>16</sup>. Metal-halogen stretching frequency decreases with increasing coordination number of the metal in a given oxidation state. This is consistent with the results observed here.

A regular octahedral molecule gives rise to six normal modes of vibrations. Of these,  $\nu_2$  (tlu) and  $\nu_4$  (tlu) are infrared active. The ir spectrum of the anion  $[\text{SnCl}_6]^{2-}$  showed a band at  $285 \text{ cm}^{-1}$  due to  $\nu_2$  vibrations. The assignment of the observed band is comparable with those of other related hexa-halo species<sup>17</sup>.

The adducts,  $\text{Ph}_4\text{SbCl}_2 \cdot x\text{MCl}_3$  were found to be insoluble in the common organic solvents and their melting points were also very high (Table 1). The ir bands of the ligand assigned to phenyl ring vibrations did not undergo any shift on adduct formation<sup>18</sup>. The bands at  $440\text{--}430 \text{ cm}^{-1}$  assigned to  $\nu\text{Sb}-\text{C(Ph)}$  frequency also did not show any shift. Two sharp bands were observed at  $730$  and  $680 \text{ cm}^{-1}$  due to B-Cl stretching vibrations<sup>14</sup>. The band observed at  $350 \text{ cm}^{-1}$  in case of  $\text{Ph}_4\text{SbCl}_2 \cdot \text{VCl}_3$  could be assigned to  $\nu(\text{V}-\text{Cl})$  terminal vibrations. Another band observed at  $280 \text{ cm}^{-1}$  could be assigned to  $\nu(\text{V}-\text{Cl})$  bridging vibrations. Therefore, a hexa-coordinated structure involving chlorine bridges could be assigned to this adduct.

The pmr spectrum of  $[\text{Ph}_4\text{Sb}]_2[\text{SnCl}_6]$  in DMSO- $d_6$  showed complex multiplets in the range  $\delta$  7.55-7.85 which were attributed to the aromatic protons of the phenyl rings.

The magnetic susceptibility measurements showed the magnetic moments of  $[\text{Ph}_4\text{Sb}][\text{VCl}_4]$  and  $\text{Ph}_4\text{SbCl}_2 \cdot \text{VCl}_3$  to be 2.76 and 2.71 B.M., respectively<sup>19</sup> indicative of the presence of two unpaired electrons per vanadium atom.

#### Acknowledgement

The authors are indebted to the authorities of Kurukshetra University, Kurukshetra for necessary

facilities and also to C.S.I.R., New Delhi for providing Fellowship to one of them (H K.S.).

#### References

1. Y. TAKASHI, *Bull. Chem. Soc., Japan*, 1967, **40**, 1194.
2. T. N. SRIVASTAVA, R C SRIVASTAVA and M SINGH, *Indian J. Chem.*, 1979, **18A**, 527
3. S. N BHATTACHARYA and A K. SAXENA, *Indian J Chem.*, 1960, **19A**, 222
4. S. N. BHATTACHARYA, P RAJ and V. K. AWASTHI, *Indian J. Chem.*, 1980, **19A**, 592
5. N. BERTAZZI, G ALONZU, A. SILVESTRI and G CONSIGLIO, *J. Organometal Chem.*, 1972, **37**, 281
6. GERMAN PATENT, 1966, 1, 204, 226, *Chem. Abs.*, **64**, 2128f, NETHERLAND PATENT, 1966, 6 414, 757, *Chem. Abs.*, **64**, 757g
7. B. A. RICHARDSON, *Stone Ind.*, 1973, **8**, 2
8. H. K SHARMA, S N. DUBEY and D M PURI, *Indian J Chem.*, 1981, **20A**, 620
9. J. ORATT and F. G. MANN, *J. Chem. Soc.*, 1940, 1192
10. A. E. GODDARD, *J. Chem. Soc.*, 1923, 1181
11. R. R. HOLMES and E. BERTAUT, *J. Amer. Chem. Soc.*, 1958, **80**, 2980.
12. K. A. JENSEN and P NIELSEN, *Acta Chem. Scand*, 1968, **17**, 1875.
13. HERZBERG, "Infrared and Raman Spectra of Polyatomic Molecules", D. VAN Nostrand Co. Inc., 1946
14. T C WADDINGTON and F. KLENBERG, *J. Chem. Soc.*, 1960, 2839.
15. J I BULLOCK, F W PARRETT and N J. TAYLOR, *J. Chem. Soc., Dalton*, 1972, **17**, 1843
16. R J H. CLARK, R S NYHOLM and D E SCAIFE, *J Chem. Soc. A*, 1966, 1296
17. R J H CLARK, L MARESCA and R J PUDDIPHATT, *Inorg Chem.*, 1963, **7**, 1609
18. G O DOAK, G G. LONG and L D FREEDMAN, *J. Organometal Chem.*, 1965, **4**, 82
19. A T CASEY and R J H. CLARK, *Inorg Chem*, 1968, **7**, 1598.

# A Study on Solid State Thermal Decomposition Characteristics of Some Metallo-organic Compounds. Part-I : Dehydration and Decarboxylation of Hydrated Calcium Salts of Pyridine Monocarboxylic Acids

S. GHOSH\*, S. K. RAY\*\*, P. K. RAY and T. K. BANDYOPADHYAY

Department of Inorganic Chemistry, Indian Association for the Cultivation of Science, Jadavpur, Calcutta-700 082

Manuscript received 20 August 1981, revised 26 January 1982, accepted 23 May 1982

Solid state dehydration of hydrated calcium salts of picolinic acid, nicotinic acid and isonicotinic acid and subsequent decarboxylation of the corresponding anhydrous salts have been studied by simultaneous TG, DTA and DTG techniques. From the analysis of the TG, DTA and DTG traces for the dehydration of the hydrated salts, the thermal stability order of the hydrates has been found to be  $\text{Ca}(\text{pic})_2 \cdot \text{H}_2\text{O} > \text{Ca}(\text{isoNic})_2 \cdot 4\text{H}_2\text{O} > \text{Ca}(\text{Nic})_2 \cdot 3\text{H}_2\text{O}$ . But the trend observed in the decarboxylation process is  $\text{Ca}(\text{Nic})_2 > \text{Ca}(\text{isoNic})_2 > \text{Ca}(\text{pic})_2$ . Thermal parameters like activation energy, enthalpy change and order of reaction for each process have been computed by standard methods. An attempt has been made to correlate the trend in the thermal stability of the anhydrous salts towards decarboxylation with their molecular structure.

THE calcium salts were prepared by the reaction of a slight excess of  $\text{CaCO}_3$  (G.R., E. Merck) with the appropriate acids in hot aqueous solutions followed by filtration and subsequent crystallisation.

Simultaneous DTA, TG and DTG determinations of the salts were carried out with a Paulik-Paulik-Erdey type MOM Derivatograph with dry air as the atmospheric gas. The particle size of the samples was in the 100-150 mesh range. The heating rate was about  $4.25^\circ$  per minute and sample size of 180-210 mg was used to make the volume nearly the same in each case. The reference material was aluminium oxide previously heated to  $1600^\circ$ . The sample holder and the reference holder were made of platinum. TG curves were utilised for calculating the activation energies of the processes involved, whereas DTA curves were used to evaluate the enthalpy changes accompanying the reactions. The initial, peak and final temperatures for the dehydration and the decarboxylation processes were noted from the corresponding DTG curves. The hydrated calcium salts and their dehydrated varieties were characterised by recording their IR spectra in halocarbon mull on a Beckman IR 20A model spectrophotometer. All the hydrated and the anhydrous compounds were analysed for calcium by titration with a standard EDTA solution. Carbon, hydrogen and nitrogen were determined by microanalytical techniques.

## Results and Discussions

**Dehydration process :** On gradual heating from room temperature, the hydrated salts were completely dehydrated within the temperature range

$39^\circ$ - $240^\circ$ . From the TG, DTG and DTA traces of the dehydration stage it was found that all the dehydrations occurred in one step. All these processes might be represented by the general equation  $\text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_x \cdot x\text{H}_2\text{O} = \text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_x + x\text{H}_2\text{O}$ ; when  $x=1$ ,  $\text{C}_6\text{H}_4\text{NO}_2^-$  = picolinate ion;  $x=3$ ,  $\text{C}_6\text{H}_4\text{NO}_2^-$  = nicotinate ion;  $x=4$ ,  $\text{C}_6\text{H}_4\text{NO}_2^-$  = isonicotinate ion.

Initial, peak and final temperatures of the dehydration of each species, as obtained from the relevant DTG curves along with the corresponding weight loss are given in Table 1. Enthalpy changes accompanying dehydration of each species were determined by standard methods from the peak area of the corresponding DTA curves using  $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$  as the standard<sup>1</sup>. Activation energies for each dehydration process were computed from an analysis of the corresponding TG curves using the method of Horowitz and

Metzger<sup>2</sup> and the  $\ln \ln \frac{W_0 - W_i}{W - W_i}$  vs  $\theta$  plots are pre-

sented in Fig. 2. The order of reaction was determined by standard methods<sup>3,4</sup> and was found to be unity. The results obtained are presented in Table 1 and the corresponding curves presented in Fig. 1. IR spectra of the hydrated and the anhydrous varieties were recorded and compared to ascertain the completion of the dehydration process.

**Decarboxylation processes :** All the anhydrous salts exhibit considerable thermal stability and undergo decarboxylation within the temperature range  $340^\circ$ - $600^\circ$ . Initial, peak and final temperatures for the decarboxylation processes of the anhydrous

\* For correspondence.

\*\* Present address : Dept. of Inorg. Chem., Jadavpur University, Calcutta 700 032 and Dept. of Chemistry, Ramsaday College, Agra, Howrah.






Fig. 1




Fig. 2

salts along with the corresponding weight losses are given in Table 2. The final product left in the crucible was found to be  $\text{CaCO}_3$ . This has been confirmed by comparing the X-ray diffraction pattern of the end product with that of a pure  $\text{CaCO}_3$  sample. Applying the same methods used in the dehydration processes, activation energies of the decarboxylation processes were evaluated from

the  $\ln \frac{W_0 - W_i}{W - W_i}$  vs  $\theta$  plots, given in Fig. 3.

Enthalpy changes accompanying each decarboxylation process were measured from the DTA curves and are presented in Table 2. The order for the decarboxylation reactions was found to be unity in all the three cases. The corresponding curves are presented in Fig. 1.




Fig. 3

TABLE 1

Reaction	Initiation temp. °C	Peak temp °C	Completion temp °C	Loss in wt. %		E <sub>Act</sub> Kcal/mole	ΔH Kcal/mole	Order of reaction
				Calcd	Found			
1. $\text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 \cdot 3\text{H}_2\text{O} \rightarrow \text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 + 3\text{H}_2\text{O}$ Calcium nicotinate trihydrate	39	90	120	15.97	16	15.55	46.97	1
2. $\text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 \cdot 4\text{H}_2\text{O} \rightarrow \text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 + 4\text{H}_2\text{O}$ Calcium isonicotinate tetrahydrate	82	130	215	20.22	20	22.96	62.07	1
3. $\text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 \cdot \text{H}_2\text{O} \rightarrow \text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 + \text{H}_2\text{O}$ Calcium picolinate monohydrate	160	198	240	5.96	5.88	52.13	26.24	1

TABLE 2


Reaction	Initiation temp °C	Peak temp °C	Completion temp °C	Loss in wt. %		E <sub>Act</sub> Kcal/mole	ΔH Kcal/mole	Order of reaction
				Calcd	Found			
4. $\text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 \rightarrow \text{CaCO}_3 + \text{products}$ Calcium nicotinate	432	560	622	64.78	60.84	76.14	166.3	1
5. $\text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 \rightarrow \text{CaCO}_3 + \text{products}$ Calcium isonicotinate	985	486	620	64.78	64.83	50.85	44.46	1
6. $\text{Ca}(\text{C}_6\text{H}_4\text{NO}_2)_2 \rightarrow \text{CaCO}_3 + \text{products}$ Calcium picolinate	380	442	540	64.78	65.38	14.86	20.37	1

Solid state thermal decomposition of the salts of aromatic or heterocyclic acids has received little attention from the kinetic point of view. Most of the workers, who studied the thermal decomposition of the salts of organic acids (mostly aliphatic acids) in the solid state, used the maximum point method<sup>4-6</sup> and the Freeman-Carroll method<sup>7</sup> for the determination of the kinetic parameters. In the present work we have utilised Horowitz and Metzger's method, an analytical technique which utilises a single TG plot to determine the pertinent Arrhenius parameters and reaction order. The values obtained by the application of this method have been verified by the Coats and Redfern<sup>8</sup> method wherever possible. We have utilised the DTA curves for the evaluation of enthalpy changes for the dehydration as well as decarboxylation processes.

The single step dehydration of calcium nicotinate trihydrate and the calcium isonicotinate tetrahydrate indicated that all the water molecules in the nicotinate trihydrate are similarly bound and such is also the case with the water molecules in the calcium isonicotinate tetrahydrate. A single endotherm in each of the DTA curves definitely points to the accuracy of the above conclusion. In the single step dehydration of all the three hydrates represented by the general equation in Table 1, the activation energies and enthalpy changes of dehydration are in the order picolinate > isonicotinate > nicotinate. This difference in thermal stabilities of the hydrates may be attributed to the differences in the mode of binding of the water molecules in the crystals of the three different pyridine monocarboxylates. It may thus be concluded that the water molecules in calcium picolinate are more firmly bound than those in isonicotinate and nicotinate and the water molecules in the calcium isonicotinate are held more strongly in comparison to those present in the calcium nicotinate.

In the decarboxylation of the anhydrous salts represented by equations given in Table 2, the activation energy follows the order nicotinate > isonicotinate > picolinate. The enthalpy change in the decarboxylation process also follows the same order.

It may be concluded from the data in Table 2 that the thermal stabilities of the carboxylates follow the order nicotinate > isonicotinate > picolinate. This trend is quite logical as the negatively charged carboxylate ion has a +I effect<sup>9</sup> and hence releases electrons with a consequent increase of electron density on the ring carbon atom which, if present in a benzene ring, would have stabilized the ring carbon-carboxyl carbon bond. But in the present case, as the ring is a heterocyclic ring, the nitrogen atom being much more electronegative than carbon, would change the situation significantly and we find that unlike benzene, electron density distribution in the pyridine ring<sup>10</sup> is as follows:



Due to the *ortho-para* orienting influence of the carboxylate ion the positions *ortho* and *para* to the ring carbon containing the carboxylate ion will have greater electron density and in the case of calcium picolinate, where the electronegative nitrogen atom is present in the position *ortho* to the ring carbon containing the carboxylate ion, it conveniently draws away this excess electron cloud towards itself and consequently reduces the electron cloud accumulated on the adjacent ring carbon atom considerably. It thus weakens the ring carbon-carboxylate carbon bond to a significant extent making it comparatively thermolabile.

In the case of the 4-picolinate anion, the enhanced electron density in the position *para* with respect to the carboxylate ion is accommodated on the nitrogen atom as a result of which the 4-carbon atom is relieved of some of its electron cloud acquired from the carboxylate anion and results in the weakening of the ring carbon-carboxyl carbon bond and consequently induces thermolability. But overall destabilisation effect is greater in 2-picolinate than in 4-picolinate due to the closeness of the ring nitrogen to the carboxylate substituent in the former and makes the 4-picolinate thermally more stable than the 2-picolinate compound. In the case of the 3-picolinate, the *ortho-para* orienting carboxylate ion would again result in electron enrichment in the *ortho* and *para* positions leaving the *meta* position unaffected. Thus, the increased electron density on the ring carbon atom containing the carboxylate ion is not decreased in this case. This leads to the stabilisation of the ring carbon-carboxyl bond when compared to the 2- and 4-picolinates and makes the 3-picolinate thermally stabler than the other two. Thus, the thermal stability order nicotinate > isonicotinate > picolinate, observed in this study, is quite in accordance with the theoretical principles.

#### Acknowledgement

The authors are grateful to Dr. Bimanesh Sur, Reader, Department of Inorganic Chemistry, Jadavpur University for valuable suggestions and encouragement. Thanks of the authors are also due to Dr. N. Ray Chaudhury and Mr. Sasanka Mukherjee for recording TG, DTA and DTG curves.

#### References

- 1 K SANO, *Sci. Rep. Tohoku, Imp Univ*, 1st Ser., 1936, **24**, 719
- 2 H H HOROWITZ and G M METZGER, *Anal Chem*, 1963, **35**, 1464
- 3 A W COATES and J P REDFERN, *Nature*, 1964, **201**, 68
- 4 K AKITA and M KASE, *J. Polymer Sci.*, 1967, **A1**, 833.
- 5 J. H FLYNN and L. A WALL, *J. Res Nat Bur Stand*, 1966, **70A**, 487
- 6 R M FUOSS, I D SALVER and H. S WILSON, *J. Polymer Sci.*, 1964, **A2**, 3147
- 7 E. S FREEMAN and B CARROL, *J. Phys Chem. Ithaca*, 1959, **62**, 894
- 8 J. MARCH, "Advanced Organic Chemistry Reactions, Mechanisms and Structure", McGraw-Hill, 1968, p. 21.
- 9 I L FINAR, "Organic Chemistry", ELBS and Longmans, Green, 1964, Vol 1, p 760

# Stability Constants and Related Thermodynamic Functions of Some Rare-Earth Metal Complexes of Sodium 2-[4-Amino-3-(1,2,4-Triazolylazo)]Naphthol-4-Sulphonate

SURESH K. GARG, SUSHMITA MUKHERJEE, B. S. GARG and R. P. SINGH

Department of Chemistry, University of Delhi, Delhi-110 007

Manuscript received 23 July 1981, revised 17 December 1981, accepted 23 May 1982

The stability constants of  $\text{La}^{3+}$ ,  $\text{Pr}^{3+}$ ,  $\text{Nd}^{3+}$ ,  $\text{Sm}^{3+}$ ,  $\text{Gd}^{3+}$ ,  $\text{Tb}^{3+}$ ,  $\text{Dy}^{3+}$ ,  $\text{Yb}^{3+}$  and  $\text{Y}^{3+}$  complexes of sodium 2-[4-amino-3-(1,2,4-triazolylazo)]naphthol-4-sulphonate have been determined in aqueous medium at different ionic strengths and temperatures employing the Bjerrum-Calvin titration technique as modified by Irving and Rossotti. The free energy, enthalpy and entropy changes involved in complexation have been determined.

THE stability constants of the complexes of sodium 2-[4-amino-3-(1,2,4-triazolylazo)]naphthol-4-sulphonate (ATN-4S) with some rare-earth metal ions have been determined potentiometrically following the Bjerrum-Calvin pH-titration technique as modified by Irving and Rossotti<sup>1</sup> and the results are reported in the present communication.

A Beckman Expandomatic SS-2 pH meter in conjunction with glass and calomel electrode assembly (0-14 pH range) was used for pH measurements. Constant temperature was maintained by using a thermostat fitted with a contact thermometer.

## Experimental

The synthesis and characterisation of ATN-4S were reported earlier<sup>2</sup>. Its solution was prepared in double distilled water. The nitrates of the rare-earths (99.99% pure) were procured from Indian Rare Earths Ltd., Bombay and their solutions were prepared in double distilled water. In cases where nitrates were not available, the oxides were dissolved in nitric acid, the solutions were heated to dryness and the residues dissolved in double distilled water. All the solutions were standardised complexometrically using EDTA as the titrant. Sodium perchlorate (Riedel) was used to maintain constant ionic strength. A 0.05 M standardised solution of tetramethylammonium hydroxide (TMAH) was used as the titrant for potentiometric titrations.

The following solutions (total volume 25.0 ml) were titrated against standard TMAH solution: (i) 1.0 ml  $\text{HClO}_4$  (0.05 M) + 1.5 ml  $\text{NaNO}_3$  (0.02 M) + water, (ii) 1.0 ml  $\text{HClO}_4$  (0.05 M) + 1.5 ml  $\text{NaNO}_3$  (0.02 M) + 10.0 ml ATN-4S (0.05 M) + water, (iii) 1.0 ml  $\text{HClO}_4$  (0.05 M) + 0.5 ml  $\text{Ln}(\text{NO}_3)_3$  (0.02 M) + 10.0 ml ATN-4S (0.05 M) + water.

All titrations were carried out under nitrogen atmosphere at the desired temperature, maintained

with an accuracy of  $\pm 0.1^\circ$  and with appropriate amounts of  $\text{NaClO}_4$  to maintain the desired ionic strengths.

## Results and Discussion

The  $pK_a$  value of the ligand has been obtained from a plot of  $\log [\bar{n}_H/(1-\bar{n}_H)]$  vs pH and the values obtained at  $30^\circ$  and different ionic strengths, viz., 0.01 M, 0.05 M, 0.10 M and 0.20 M are 5.92, 5.85, 5.81 and 5.78, respectively. The  $pK_a$  values at  $40^\circ$  and  $50^\circ$  and  $I=0.10$  M are 5.71 and 5.61, respectively. The  $pK_a$  value at zero ionic strength and  $30^\circ$ , obtained by extrapolation, is 5.96.

The  $\bar{n}$  and  $pL$  data were subjected to the least squares treatment of Sullivan *et al.*<sup>3</sup> to give  $\beta_n$  values. The stability constants thus calculated at three different temperatures and  $I=0.10$  M are given in Table I. In cases of ATN-4S complexes, the first two steps involved in complexation proceed almost simultaneously and hence in the case of most metals the step-wise stability constant values for the first two steps cannot be evaluated. Moreover, the lighter elements form only 1:2 complexes, while the heavier ones form 1:3 complexes also. Hence,  $\log \beta_n$  values are most convenient for comparison as they are available for all the metals used.

A plot of  $\log \beta_n$  vs  $1/r$  ( $r$ =ionic radius) shows a regular increase from lanthanum to ytterbium with a break at gadolinium. The position of yttrium lies between gadolinium and terbium. In terms of electrostatic considerations, the gadolinium break may be attributed to the discontinuity of the crystal radius at gadolinium. However, this approach is based on the assumption that the trends in the crystal radii are reflected in the solvated as well as in the coordinated ions, which may not be entirely true<sup>4</sup>.

The gadolinium break may be explained in terms of the ligand field theory<sup>5</sup>. Crystal field

ffects due to presence of ligand may be operative<sup>6,7</sup>, and there may be varying degree of interaction of the 4f orbital with the ligand field. No such stabilisation is expected for the Gd<sup>3+</sup> ion. Rossotti<sup>7</sup> questioned the validity of this suggestion, since on this basis the stability constants for Y<sup>3+</sup> and Gd<sup>3+</sup> complexes should be equal (both ions have no field stabilisations), but due to the smaller size of Y<sup>3+</sup> ion, Y<sup>3+</sup> complexes are expected to have higher stability than Gd<sup>3+</sup> complexes. This has been observed in the present case.

The stability constants of the complexes have been found to decrease with increasing ionic strength of the medium, which is in agreement with the Debye-Hückel equation<sup>8</sup>.

The values of stability constants in Table 1 reveals that the stability constant value decreases

TABLE 1—METAL-LIGAND STABILITY CONSTANTS AT DIFFERENT TEMPERATURES (I=0.10 M NaClO<sub>4</sub>)

Constant	Temp., °C		
	30	40	50
La <sup>3+</sup>			
log β <sub>1</sub>	6.15	5.78	5.84
log β <sub>2</sub>	11.25	10.68	10.00
Pr <sup>3+</sup>			
log β <sub>1</sub>	6.71	6.30	5.73
log β <sub>2</sub>	12.00	11.39	10.68
Nd <sup>3+</sup>			
log β <sub>1</sub>	—	6.67	5.84
log β <sub>2</sub>	12.49	11.83	11.16
log β <sub>3</sub>	15.27	—	—
Sm <sup>3+</sup>			
log β <sub>1</sub>	—	6.22	4.93
log β <sub>2</sub>	12.57	11.80	11.24
log β <sub>3</sub>	17.89	14.92	—
Gd <sup>3+</sup>			
log β <sub>1</sub>	—	—	—
log β <sub>2</sub>	12.60	12.04	11.35
log β <sub>3</sub>	18.10	15.00	14.42
Tb <sup>3+</sup>			
log β <sub>1</sub>	—	—	—
log β <sub>2</sub>	13.15	12.85	11.68
log β <sub>3</sub>	18.96	17.83	15.91
Dy <sup>3+</sup>			
log β <sub>1</sub>	—	—	—
log β <sub>2</sub>	13.74	13.00	12.32
log β <sub>3</sub>	19.11	17.85	16.66
Yb <sup>3+</sup>			
log β <sub>1</sub>	—	—	—
log β <sub>2</sub>	14.11	13.39	12.63
log β <sub>3</sub>	19.39	17.98	16.70
Y <sup>3+</sup>			
log β <sub>1</sub>	—	—	—
log β <sub>2</sub>	13.13	12.46	11.78
log β <sub>3</sub>	18.66	17.38	15.83

with increase in temperature. The ΔG, ΔH and ΔS values have been calculated<sup>9</sup> and the results are shown in Table 2. ΔG values have

TABLE 2—THERMODYNAMIC PARAMETERS OF THE RARE-EARTH METAL COMPLEXES OF ATN-4S AT I=0.10 M NaClO<sub>4</sub>

Cations	-ΔG(β <sub>n</sub> )(KJ/mole)			-ΔH(β <sub>n</sub> ) KJ/mole	ΔS(β <sub>n</sub> ) (J/deg/mole)
	30°	40°	50°		
La <sup>3+</sup>	65.27	64.00	61.88	57.90	24.32
Pr <sup>3+</sup>	69.61	68.32	66.46	57.78	58.86
Nd <sup>3+</sup>	72.46	70.90	69.00	56.35	53.30
Sm <sup>3+</sup>	72.91	70.96	68.88	65.48	24.52
Gd <sup>3+</sup>	74.59	73.00	70.85	66.24	25.58
Tb <sup>3+</sup>	76.27	74.06	72.22	65.48	35.61
Dy <sup>3+</sup>	79.70	77.90	76.32	64.84	82.08
Yb <sup>3+</sup>	81.84	80.28	78.09	69.40	74.09
Y <sup>3+</sup>	76.17	74.66	72.84	53.33	75.39

been found to be negative in all cases, showing complex formation to be a spontaneous process. ΔG values have been found to increase with increase in temperature indicating that low temperature favours complexation. This is also confirmed by negative enthalpy values. The positive entropy values show increase in randomness in the systems indicating the presence of a larger number of species. However, the change in entropy for β<sub>3</sub> is negative, which indicates that randomness decreases in going from species ML<sub>3</sub> to ML<sub>4</sub>. This might be due to the change in dentate character of the ligand or as a result of the increase in coordination number of the metal ion.

#### Acknowledgement

The authors thank the Centre of Advanced Studies in Chemistry, University of Delhi, for financial assistance to one of them (S. M.).

#### References

1. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
2. S. MUKHERJEE, S. K. GARG, B. S. GARG and R. P. SINGH, *Asiadad*, 1980, 37, 454.
3. J. C. SULLIVAN, J. HYDERG and W. F. MILLER, *Acta Chem. Scand.*, 1959, 13, 2023, 2059.
4. E. V. KLEBER in "Rare Earth Research", McMillan, New York, 1964.
5. L. A. K. STEVELEY and T. RANDALL, *Discuss. Faraday Soc.*, 1958, 26, 157.
6. G. R. CHOPPIN and J. A. CHOPOORIAN, *J. Inorg. Nuclear Chem.*, 1961, 22, 97.
7. F. J. O. ROSSOTTI, *Discuss. Faraday Soc.*, 1958, 26, 190.
8. R. NASAMEN and A. ELMAR, *Acta Chem. Scand.*, 1959, 6, 1369.
9. K. B. YATSIMIRSKII and V. P. VASILEV in "Instability Constants of Complex Compounds", Pergamon Press, New York, 1960.

# Oxidation Studies. Part—XV : Ag(I)-Catalysis in Oxidation of Amines by Ce(IV) in Nitric Acid, A Kinetic Study

M. ANAND RAO, B. SETHURAM and T. NAVANEETH RAO\*

Dept. of Chemistry, Osmania University, Hyderabad-500 007

Manuscript received 19 December 1981, revised 16 March 1982, accepted 8 July 1982

The kinetics of Ag(I)-catalysed oxidation of methyl, ethyl, isopropyl, n-butyl, isobutyl, dimethyl and trimethyl amines by Ce(IV) was studied in nitric acid medium. The Ag(I)-catalysis of Ce(IV)-amine reaction is explained in terms of a 1 : 1 complex formation between Ag(I) and amine which later reacts with Ce(IV) bimolecularly to give the products. The rate law for the Ag(I)-catalysed oxidation of amines was found to be

$$-\frac{d[\text{Ce(IV)}]}{dt} = \frac{kK[\text{Ce(IV)}][\text{amine}][\text{Ag(I)}]}{1 + K[\text{amine}] + K[\text{Ag(I)}]}$$

Ammonia and the corresponding aldehyde or ketone were identified as the products of oxidation of aliphatic primary amines, while formaldehyde and other amines were the products when dimethyl or trimethyl amines were the substrates. The activation parameters for the oxidation of amines are presented and discussed.

It is reported that amines could be oxidised using oxidants like permanganate<sup>1</sup>, lead tetraacetate<sup>2</sup>, cobaltic perchlorate<sup>3</sup> and chlorinedioxide<sup>4</sup>. Recently, we reported<sup>5</sup> the kinetics of oxidation of amines by Ce(IV) in nitric acid medium. It was shown in all these cases that amines could be oxidised by two distinct mechanisms, one involving dehydrogenation and the other by an attack at the lonepair electrons on nitrogen in the rate determining step. Even though Ag<sup>+</sup> ions were found to be good catalysts, only sporadic references have been made in the literature about their use as catalyst in the oxidation of organic compounds by Ce(IV), specially in HNO<sub>3</sub> medium. In view of this, we have taken up a systematic kinetic study of oxidation of amines by Ce(IV) in presence of Ag<sup>+</sup> to find out whether the presence of Ag<sup>+</sup> ions results in a change in the mechanism of oxidation as also the mechanism of catalysis.

## Experimental

All the chemicals used were of reagent grade. The method of following the kinetics was the same as reported earlier<sup>5</sup>. Approximate amount of ceric ammonium nitrate (AnalaR) was weighed and dissolved to give a ~0.10 M solution. The concentration was estimated by titrating against standard ferrous ammonium sulphate. This solution was diluted with nitric acid (0.50 M) to give 0.01 M solution. Salts of the general formula R.CH<sub>2</sub>NH<sub>2</sub><sup>+</sup>NO<sub>3</sub><sup>-</sup> were prepared by mixing one mole of amine with one mole of nitric acid. The silver nitrate used as catalyst was also of AnalaR grade.

Ammonia and corresponding aldehydes or ketones were the products of Ag<sup>+</sup>-catalysed oxidation of aliphatic amines while formaldehyde and other corresponding amines were the products when the dimethyl or trimethyl amines were used

as substrates. Ammonia was detected with Nessler's reagent. Formaldehyde and corresponding aldehyde or ketone were identified by their characteristic tests<sup>7</sup> and further confirmed by m. p. of their 2,4-DNP derivatives.

## Results and Discussion

Under the conditions of [Ce(IV)] << [amine] in the presence of constant amount of Ag(I) the order in [Ce(IV)] was found to be unity. The pseudo first order rate constants (k') were calculated from the slope of the linear plots of log [a/(a-x)] vs time [where, a and a-x are the concentrations of Ce(IV) at zero and time t, respectively]. The order in [amine] obtained from the plots of log k' vs log [amine] was found to be fractional. Increase in [Ag(I)] increased the rate and the order in [Ag(I)] was also fractional in all the cases (Table 1). Increase in [H<sup>+</sup>] or [NO<sub>3</sub><sup>-</sup>] decreased the rate of oxidation (Table 2). The reactions were studied in the temperature range 313-333°K to evaluate the activation parameters. Typical results with methylamine as the substrate are given in Tables 1 and 2 and Fig. 1. Induced polymerisation was observed when acrylamide was added to the reaction mixture.

Wylie employed<sup>8</sup> the solvent extraction technique and suggested the existence of H<sub>2</sub>[Ce(NO<sub>3</sub>)<sub>6</sub>] in moderately strong nitric acid solutions. Shorter<sup>9</sup>, who studied the oxidation of acetone by ceric nitrate in nitric acid assumed that Ce(OH)<sup>3+</sup> was the reactive species. Similar conclusions were drawn by Mathur and Bakore<sup>10,11</sup> in the oxidation of sec-butanol and iso-propanol. However, Sethuram and Muhammad<sup>6</sup> and Santappa and Sethuram<sup>7</sup> concluded from the effect of [NO<sub>3</sub><sup>-</sup>] and [H<sup>+</sup>] on the rate of oxidation of formaldehyde and some alcohols in nitric acid medium that the neutral Ce(NO<sub>3</sub>)<sub>4</sub>.(H<sub>2</sub>O)<sub>2</sub> was the most likely

TABLE 1—EFFECT OF [Ag(I)] ON  $k'$  IN Ce(IV)-ALIPHATIC AMINE REACTIONS CATALYSED BY Ag(I)  
 [Ce(IV)]=0.005 M; [HNO<sub>3</sub>]=0.500 M; Temp.=338°K;

Amine	$k' \times 10^3 \text{ min}^{-1}$ at [Ag(I)] mol dm <sup>-3</sup>							
	0.010	0.015	0.020	0.030	0.040	0.060	0.080	0.090
Methyl (0.40 M)	6.10	—	8.89	—	13.9	—	19.8	25.8
Ethyl (0.80 M)	—	13.0	17.7	21.0	26.4	—	35.9	—
<i>n</i> -Propyl (0.20 M)	7.08	—	10.1	—	13.4	—	19.2	25.1
<i>iso</i> -Propyl (0.10 M)	2.65	—	5.00	—	9.60	—	12.0	16.8
<i>n</i> -Butyl (0.10 M)	14.8	—	20.3	26.4	31.0	39.5	—	—
<i>iso</i> -Butyl (0.40 M)	—	26.7	32.0	39.1	49.0	—	57.0	—
Dimethyl (0.20 M)	—	20.0	34.8	50.6	60.7	72.4	79.4	—
Trimethyl (0.10 M)	10.7	—	14.0	17.8	21.4	23.7	—	—

 TABLE 2—EFFECT OF [NO<sub>3</sub><sup>-</sup>] AND [H<sup>+</sup>] ON Ce(IV)-*n*-PROPYLAMINE REACTION CATALYSED BY Ag(I)

 [Ce(IV)]=0.005 M; [HNO<sub>3</sub>]=1.00 M, [Ag(I)]=0.020 M,  
 [*n*-propylamine]=0.200 M, Temp.=328°K

[Salt] or [Acid] mol dm <sup>-3</sup>	$k' \times 10^3 \text{ min}^{-1}$	
	(NO <sub>3</sub> <sup>-</sup> )	(H <sup>+</sup> )
0.400	22.4	20.4
0.800	16.6	17.0
1.20	12.6	13.9
1.60	10.2	11.7
2.00	8.70	10.0
2.40	5.90	9.00

reactive species of Ce(IV). The probable species that could exist in nitric acid solutions of Ce(IV) are Ce(NO<sub>3</sub>)<sub>3</sub><sup>2+</sup>, Ce(NO<sub>3</sub>)<sub>2</sub><sup>3+</sup>, Ce(OH)(NO<sub>3</sub>)<sub>2</sub><sup>+</sup> and Ce(NO<sub>3</sub>)<sub>4</sub> at fairly high [nitrate ion]. The choice of the reactive species was rather difficult but the fact that the rate of oxidation of amines by Ce(IV) in nitric acid was retarded by NH<sub>4</sub>NO<sub>3</sub> coupled with the fact that the oxidation in perchloric acid medium was inhibited by the addition of nitrate ions indicated that the reactive species might be the neutral ceric nitrate molecule Ce(NO<sub>3</sub>)<sub>4</sub> or more correctly Ce(NO<sub>3</sub>)<sub>4</sub>(H<sub>2</sub>O)<sub>2</sub>. The presence of





Fig. 1


- (A')—Plot of  $\log [a/(a-x)]$  vs time, [Ce(IV)]=0.005 M, [HNO<sub>3</sub>]=0.500 M, [Ag(I)]=0.020 M, [methylamine]=0.800 M; temp.=338°K  
 (A, B and C)—Plots of  $1/k'$  vs  $1/[\text{methylamine}]$  at temp. 318, 328 and 338°K, respectively [conditions same as in (A')]  
 (D)—Plot of  $(2 + \log k')$  vs  $(1/T \times 10^3)$  [conditions same as in (A')]  
 (E)—Plot of  $(3 + \log k')$  vs  $(1 + \log [\text{methylamine}])$  [conditions same as in (A')]  
 (F)—Plot of  $(3 + \log k')$  vs  $(3 + \log [\text{Ag}^+])$  [conditions same as in (A')]

species  $[\text{Ce}(\text{OH})(\text{H}_2\text{O})(\text{NO}_3)_2]^-$  could not be discounted, though at high acid concentrations employed in the present work these hydroxylated species could be neglected. The inverse dependency of rate on  $[\text{NO}_3^-]$  may be explained if one assumes neutral  $\text{Ce}(\text{NO}_3)_4$  to be the reactive species according to the following equilibria









In the presence and absence of  $\text{Ag}^+$  it was found that  $\text{H}^+$  ions inhibit the reaction. This could be either due to the hydrolysed species acting as the reactive species

$\text{Ce}(\text{NO}_3)_4(\text{H}_2\text{O})_2 \rightleftharpoons [\text{Ce}(\text{NO}_3)_4(\text{OH})(\text{H}_2\text{O})]^- + \text{H}^+$   
or due to the presence of equilibrium of the type



with  $\text{R}-\ddot{\text{N}}\text{H}_2$  as the reactive species. To find out whether hydrolysed species is the reactive one, we have studied the effect of  $[\text{H}^+]$  on the oxidation of *n*-propanol, where the protonation equilibrium is not likely. It was found that increase in  $[\text{H}^+]$  increases the rate of oxidation of *n*-propanol indicating clearly that hydrolysis equilibrium exists and that neutral ceric nitrate is the reactive species. Since  $[\text{Ce}(\text{IV})]$  and  $[\text{HNO}_3]$  are the same in the amines oxidation, we believe that in this case also the unhydrolysed species is the reactive one. The inhibition of  $\text{H}^+$  ions on the amines oxidation could therefore be attributed to the removal of reactive free amine by protonation.

It was reported<sup>8</sup> that in the absence of  $\text{Ag}(\text{I})$  the order in [amine] is unity. The fractional order in [amine] in presence of  $\text{Ag}(\text{I})$  indicated that it may be involved in complex formation either with  $\text{Ce}(\text{IV})$  or  $\text{Ag}(\text{I})$ . Spectral studies in the present study indicated no complexation between  $\text{Ce}(\text{IV})$  and aliphatic amine in conformity with our earlier observations<sup>8</sup>. Induced polymerisation due to the addition of acrylamide indicated the formation of the free radicals.  $\text{Ag}(\text{I})$  is known to form colourless adducts with organic compounds<sup>10</sup>. Therefore, the formation of an adduct between  $\text{Ag}(\text{I})$  and amine, before oxidation by  $\text{Ce}(\text{IV})$  in a slow step to yield  $\text{Ag}^{2+}$ -amine adduct, is proposed. If the adduct formation is taken as the first step, the reaction scheme for  $\text{Ce}(\text{IV})$ -amine reaction in the presence of  $\text{Ag}(\text{I})$  could be written as follows:



From the above mechanism, the rate equation comes out to be

$$\begin{aligned}-\frac{2.303 d \log [\text{Ce}(\text{IV})]}{dt} &= k' \\ &= \frac{kK[\text{amine}][\text{Ag}(\text{I})]}{1 + K[\text{amine}] + K[\text{Ag}(\text{I})]} \quad (1)\end{aligned}$$

where  $k'$  is the observed pseudo first order rate constant,  $k$  the bimolecular rate constant for the slow step and  $K$  the formation constant of  $\text{Ag}(\text{I})$ -amine adduct. Equation 1 accounts for the observed fractional order dependence of rate in [amine] and  $[\text{Ag}(\text{I})]$ . At constant  $[\text{Ag}(\text{I})]$ , we get the equation 1 modified as below:

$$\frac{1}{k'} = \frac{1}{[\text{amine}]} \left[ \frac{1}{kK[\text{Ag}(\text{I})]} + \frac{1}{k} \right] + \frac{1}{k[\text{Ag}(\text{I})]} \quad \dots (2)$$

It is clear from equation 2 that plots of  $1/k'$  vs  $1/[\text{amine}]$  at constant  $[\text{Ag}(\text{I})]$  should be linear. Such plots were obtained in the present work for all the amines studied (Fig. 1). From the intercept and slope values, the bimolecular rate constants,  $k$ , and the formation constants,  $K$ , for  $\text{Ag}(\text{I})$ -amine adduct were evaluated at different temperatures and the various activation parameters calculated (Table 3).

TABLE 3—ACTIVATION PARAMETERS FOR  $\text{Ce}(\text{IV})$ -AMINE REACTION CATALYSED BY  $\text{Ag}(\text{I})$

Amine	$k \times 10^3$ $\text{dm}^3 \text{mol}^{-1} \text{sec}^{-1}$ (at 323°K)	$K$ $(\text{dm}^3 \text{mol}^{-1})$	$E_{\text{app}}$ $\text{kJ mol}^{-1}$	$\Delta H^\ddagger$ $\text{kJ mol}^{-1}$	$\Delta G^\ddagger$ $\text{J deg}^{-1} \text{mol}^{-1}$	$-\Delta S^\ddagger$ $\text{J deg}^{-1} \text{mol}^{-1}$
Methyl	1.78	1.40	45.0	43.8	90.6	118
Ethyl	3.27	3.12	77.0	74.8	89.0	45
<i>n</i> -Propyl	3.79	4.88	44.0	41.8	88.6	146
<i>n</i> -Butyl	5.25	4.98	59.5	56.8	87.7	96
iso-Propyl	5.95	6.98	76.5	73.8	87.4	42
iso-Butyl	4.17	6.15	68.5	60.8	88.3	85
Dimethyl	18.5	9.30	44.8	42.1	84.3	180
Trimethyl	5.90	6.70	72.5	69.8	87.4	54

It was observed in the present study that the electron releasing groups accelerate the formation of adduct between  $\text{Ag}(\text{I})$  and aliphatic amine, the order of reactivity being  $\text{Me} < \text{Et} < \textit{n}-prop < *n*-but < *i*-but < *i*-prop. It was also observed that increase in the length of the carbon chain of amine had little effect on  $K$  whereas increase in the number of methyl groups on  $\alpha$ -carbon atom had a significant effect (Table 3). These results could explain the$



ease of formation of adduct between Ag(I) and aliphatic amine as the  $\alpha$ -carbon atom to the amine group becomes more and more electron rich. This in turn facilitates the reaction between the adduct and Ce(IV) in the rate determining step.

*Applicability of Taft's equation :*

To study the applicability of Taft's equation for all the primary amines log K values were plotted against  $\sigma^*$  values at 323°K according to the general equation

$$\log(K/K_0) = \rho^* \sigma^* + \delta E_s \quad \dots (3)$$

where K and  $K_0$  represent the formation constants of Ag(I)-adducts of substituted amines and methylamine, respectively,  $\sigma^*$  and  $E_s$  the polar and steric substituent constants, and  $\rho^*$  and  $\delta$  the reaction constants for the same two effects, respectively. Using the standard least square method of bivariate linear regression<sup>18</sup> the reaction constants due to the polar  $\rho^*$  and steric  $\delta$  effects were found to be  $-3.37 \pm 0.04$  and  $-0.195 \pm 0.02$ , respectively. It was found that the formation constants for all the amines studied could satisfactorily be fitted into equation 3, using the above values. From the values of the reaction constants  $\rho^*$  and  $\delta$  it is evident that the polar effects are playing a major role in the formation of the adduct compared to the steric effects.

The activation parameters for all the amines studied may be explained on the basis of isokinetic relationship. The  $\Delta H^\ddagger$  and  $\Delta S^\ddagger$  are related by

the equation  $\Delta H^\ddagger = \Delta H_0 + \beta \Delta S^\ddagger$  where  $\beta$  is the isokinetic temperature. In the present study the plot of  $\Delta H^\ddagger$  vs  $\Delta S^\ddagger$  (Table 3) was linear with a slope equal to 380°K which is the isokinetic temperature,  $\beta$ , for this reaction series. The value is found to be much above the temperature range used (313-333°K) in the present study suggesting that the reactions are enthalpy controlled.

**References**

1. S. S. RAWALAY and H. SHECHTER, *J. Org. Chem.*, 1967, 32, 2129.
2. M. L. MIHAILOVIC, A. STOJILJKOVIC and ANDREJEVIC, *Tetrahedron Lett.*, 1966, 461.
3. R. A. SHERK and W. A. WATERS, *J. Chem. Soc., B*, 1970, 988.
4. D. H. ROSENBLATT, A. J. HAYES, JR., B. L. HOROBON, R. A. STREATY and K. A. MOORE, *J. Org. Chem.*, 1963, 28, 2790.
5. M. ANAND RAO, B. SETHURAM and T. NAVANEETH RAO, *Indian J. Chem.*, 1960, 19A, 747.
6. S. S. MUHAMMAD and B. SETHURAM, *Acta Chim. Hung.*, 1966, 46, 115.
7. M. SANTAPPA and B. SETHURAM, *Proc. Indian Acad. Sci.*, 1968, 67A, 78.
8. A. W. WYLLIE, *J. Chem. Soc.*, 1961, 1474.
9. J. SHORTER, *J. Chem. Soc.*, 1962, 1868.
10. D. L. MATHUR and G. V. BAKORE, *Bull. Chem. Soc. Japan*, 1971, 44, 2800.
11. D. L. MATHUR and G. V. BAKORE, *J. Indian Chem. Soc.*, 1971, 48, 363.
12. A. D. E. PULLIN and J. MCPOLLOCK, *Trans. Faraday Soc.*, 1968, 54, 11.
13. H. MARGENAU and G. S. MURPHY, "The Mathematics of Physics and Chemistry", Affiliated East-West Press Pvt. Ltd., New Delhi, 1971, p. 801.

## Studies in Triethylamine-Water. Part—IV : Predicting the Solubilities of Triethylamine and Water

S. THANGAVEL and MATHEW J. MOOLEL\*

Department of Chemistry, Loyola College, Madras-600 084

Manuscript received 27 January 1982, accepted 7 June 1982

The solubility curve of the binary system triethylamine-water, which has a lower critical solution temperature of 18.3°, is predicted from simple thermodynamics by analysing the vapour pressure data. In this method, the equation for  $g^E$  (the molar excess free energy of mixing) of amine-water systems is assumed to hold good for temperatures at which the system is only partially miscible. The common tangential points on the curves of  $g^M$  (the molar free energy of mixing) vs  $X$  (the solvent composition, expressed in mole fraction of  $\text{Et}_3\text{N}$  in water), drawn as isotherms, reproduce the experimental solubility curve of the binary system within  $\pm 2$  per cent.

THE solubility curve of the binary system triethylamine-water has been experimentally studied by a number of workers<sup>1-12</sup>. The effect of ion size on the phase separation of the binary system has been brought out by comparing the effect of about 80 electrolytes on the phase separation temperature (PST) of this binary solvent mixture<sup>13</sup>. Phase separation effects in the ternary system  $\text{Et}_3\text{N}$ -water-KI have been quantitatively predicted<sup>14</sup> by using the hydration numbers of  $\text{K}^+$  and  $\text{I}^-$  ions, obtained from conductance studies of KI in this solvent mixture<sup>14</sup>. In the present work, the solubility curve of the binary system  $\text{Et}_3\text{N}$ -water is predicted from simple thermodynamics by analysing the vapour pressure data available in literature<sup>4, 15-27</sup>.

### Method :

The excess molar free energy of mixing,  $g^E$ , of a binary mixture can be calculated from the observed molar free energy of mixing,  $g^M$ , using the equations :

$$g^M = g^I + g^E \quad (1a)$$

$$g^I = RT(1-X) \ln(1-X) + RT X \ln X \quad (1b)$$

where  $g^I$  is the ideal molar free energy of mixing.  $g^M$  is calculated from vapour pressure measurements :

$$g^M = RT(1-X) \ln(p_1/p_1^0) + RT X \ln(p_2/p_2^0) \quad (2)$$

where  $R$  is the gas constant,  $T$  is the absolute temperature,  $p_1$  and  $p_1^0$  are the vapour pressure of water in solution and in pure form, respectively at temperature  $T$ ,  $p_2$  and  $p_2^0$  are the vapour pressure of  $\text{Et}_3\text{N}$  in solution and in pure form, respectively at temperature  $T$ ,  $X$  is the mole fraction of  $\text{Et}_3\text{N}$  in the binary mixture.

When  $g^M$  is plotted against the mole fraction of  $\text{Et}_3\text{N}$  for various temperatures, the common tangential points of the isotherm give the compositions of the coexisting phases. When the compositions of these coexisting layers are plotted against temperature, the course of the variation of these points gives the solubility curve of the binary system.

This method needs the vapour pressure data for temperatures at which the binary system is not completely miscible (in fact it is impossible to have data at these temperatures practically). Copp and Everett<sup>15</sup> have proposed a fitting equation for  $g^E$  by modifying the one proposed by Guggenheim<sup>28</sup>. By considering only the first nine terms, the equation becomes

$$g^E/RT = AX(1-X) + X(1-X)(1-2X)[B+C(1-2X)+D(1-2X)(1-X)^6] \quad (3)$$

In  $\text{Et}_3\text{N}$ -water system, equation (3) reproduces the  $g^E$  within  $\pm 1$  cal in the homogeneous regions.

The following simple assumptions are made to obtain the  $g^E$  for temperatures above the lower critical solution temperature (LCST) of  $\text{Et}_3\text{N}$ -water system :

- Equation (3) holds good for temperatures at which the system is heterogeneous.
- Since the terms  $A$ ,  $B$ ,  $C$  and  $D$  of equation 3 all show a linear dependence on temperature below LCST in the homogeneous phase, they are considered to have the same dependency at temperatures above LCST in heterogeneous regions also.

### Vapour pressure data :

Vapour pressures for  $\text{Et}_3\text{N}$ -water mixtures have been reported by various authors<sup>4, 15-27</sup>. Chun and coworkers<sup>20</sup> have fitted their experimental  $g^E$  to equation 3 and have reported the values of the terms  $A$ ,  $B$ ,  $C$  and  $D$  for homogeneous solutions below LCST of the binary solvent mixtures.

### Results and Discussion

The values of  $A$ ,  $B$ ,  $C$  and  $D$  against temperature have been plotted (Fig. 1) and extrapolated to temperatures upto 23°. The extrapolated values of these terms are given in Table 1.  $g^E$  is calculated




Fig. 1. Distribution ratio,  $D$ , of N-arylhydroxamic acids between  $\text{CHCl}_3$  and aqueous  $\text{HCl}$ .

TABLE 1—VALUES OF THE TERMS A, B, C AND D OF EQUATION 3 AT VARIOUS TEMPERATURES ABOVE LCST

Temp °C	A	B	C	D
19	2.442	0.1985	0.579	1.016
20	2.456	0.2015	0.590	1.034
21	2.470	0.2045	0.602	1.050
22	2.483	0.2075	0.613	1.066
23	2.498	0.2105	0.624	1.084

TABLE 2—VARIATION OF  $g^M$  WITH SOLVENT COMPOSITION X AT VARIOUS TEMPERATURES

X	$-g^M$ (cal.mol <sup>-1</sup> )				
	Temp. °C				
	19	20	21	22	23
0.01	8.88	8.67	8.45	8.23	8.00
0.02	11.45	11.92	10.58	10.17	9.71
0.04	13.06	12.25	11.46	10.69	9.84
0.06	13.68	12.54	11.45	10.40	9.38
0.08	14.85	13.02	11.69	10.43	9.04
0.10	15.42	13.92	12.42	10.11	9.40
0.15	19.47	14.69	15.89	14.19	12.30
0.20	24.84	22.48	20.48	18.65	16.60
0.30	33.62	31.61	29.59	27.68	25.51
0.40	41.45	39.48	37.50	35.64	33.49
0.50	47.98	46.11	44.22	42.47	40.40
0.60	52.75	51.00	49.23	47.58	45.65
0.70	55.80	53.70	52.08	50.59	48.88
0.80	55.88	54.06	52.70	51.46	50.02
0.90	50.07	49.27	48.48	47.65	46.78

using equation 3 and  $g^M$  is calculated with equation 1. Table 2 gives the values of  $g^M$  for different temperatures.  $g^M$  vs X isotherms are drawn and the common tangent points are obtained from these isotherms (Fig. 2). Fig. 3 shows the course of the variation of the common tangential points obtained at various temperatures (Table 3).

The variation of the common tangential points of  $g^M$ -X isotherms reproduces the solubility curve of Et<sub>3</sub>N-water system given by Kohler and Rice<sup>6</sup>,




Fig. 2. Estimation of  $K_D$  ( $\text{CHCl}_3$  and aqueous phase)




Fig. 3. Estimation of  $K_D$ , chloroform and aqueous phase.

who had taken special care in the purification of the solvents. Copp and Everett<sup>12</sup> have used this procedure to work out the solubility curve of the system methyldiethylamine-water. But in their work they assumed that the terms B, C and D are temperature independent. The curve obtained in

TABLE 2—PREDICTED VALUES OF THE COMPOSITIONS OF THE COEXISTING PHASES 1 AND 2 AT VARIOUS TEMPERATURES  
X = Mole fraction of Et<sub>3</sub>N

Temp. °C	X <sub>1</sub>	X <sub>2</sub>
19	0.080	0.200
20	0.028	0.275
21	0.026	0.275
22	0.026	0.275
28	0.020	0.585

their analysis showed a second minimum, which is absent in the experimental curve. In the present work, there is no such anomaly for Et<sub>3</sub>N-water system. The solubility curve is reproduced within  $\pm 2\%$  of the experimental values.

#### Acknowledgement

The authors gratefully acknowledge the financial assistance of the U. G. C., New Delhi for this work.

#### References

1. BETHMUND, *Z. Physik. Chemie.*, 1898, **26**, 433.
2. J. TIMMERMANS, *Z. Physik. Chemie*, 1907, **58**, 124.
3. GUTHRIE, *Phil. Mag.*, 1909, **18**, 22.
4. L. D. ROBERTS and J. E. MAYER, *J. Chem. Phys.*, 1941, **9**, 852.
5. S. D. GOLOS, E. I. IGNATENKO and YU. YA. SERGEY, *Zh. Prikl. Khim. (Leningrad)*, 1972, **45**, 2224.
6. J. L. COFF, Ph.D. Thesis, University of Andrews, 1958.
7. G. F. ALFREVY and W. G. SCHNEIDER, *Discuss. Faraday Soc.*, 1958, **15**, 218.
8. I. R. KRICHEVSKII, N. E. KHAZANOVA and L. R. LINSHITS, *Zh. Fiz. Khim.*, 1965, **29**, 647.
9. F. KOHLER and O. K. RICH, *J. Chem. Phys.*, 1957, **26**, 1614.
10. J. F. COUNSEL, D. H. EVERETT and R. J. MUNN, *J. Pure and Appl. Chem.*, 1961, **2**, 885.
11. J. F. COUNSEL, Ph.D. Thesis, University of Bristol, 1959.
12. S. THANGAVEL and M. J. MOOLZEL, *J. Indian Chem. Soc.*, 1981, **58**, 528.
13. S. THANGAVEL and M. J. MOOLZEL, *J. Indian Chem. Soc.*, Communicated.
14. S. THANGAVEL and M. J. MOOLZEL, *J. Indian Chem. Soc.*, Communicated.
15. J. L. COFF and D. H. EVERETT, *Discuss. Faraday Soc.*, 1958, **16**, 18.
16. F. KOHLER, *Monatsh.*, 1961, **82**, 918.
17. M. EWERT, *Bull. Soc. Chim. Belg.*, 1938, **45**, 498.
18. A. V. STORONKIN and N. P. MARKUZIN, *Vestnik Leningrad Univ.*, 13 No. 14 Ser., *Fiz. i Khim.*, 1958, 100.
19. N. P. MARKUZIN, *Zh. Prikl. Khim. (Leningrad)*, 1969, **42**, 2618.
20. K. W. CHUN, J. C. CLINSCALES and R. R. DAVISON, *J. Chem. Eng. Data*, 1971, **16**, 448.
21. I. R. KRICHEVSKII, N. E. KHAZANOVA, G. M. SVETLOVA and R. S. PANINA, *Zh. Fiz. Khim.*, 1960, **34**, 2160.
22. P. M. MONVAL, *Compt. Rend.*, 1987, **205**, 1154.
23. R. CIGNAR and G. LUZZO, *Ann. Chem. (Rome)*, 1967, **57**, 88.
24. B. P. DAILEY and W. A. FALSING, *J. Amer. Chem. Soc.*, 1939, **61**, 2808.
25. I. R. KRICHEVSKII, N. E. KHAZANOVA and L. R. LINSHITS, *Kriticheskie Yavleniya i Fluktuatsii v Rastvorakh*, Moskov. Gosudarst. Univ. im. M. V. Lomonosova, Turdy Soveshchaniya, Moscow, 1960, 54.
26. I. R. KRICHEVSKII, N. E. KHAZANOVA and L. R. LINSHITS, *Zh. Fiz. Khim.*, 1962, **36**, 298.
27. R. T. LATTEY, *J. Chem. Soc.*, 1907, **91**, 1959.
28. H. A. GUGGENHEIM, "Thermodynamics. An Advanced Treatment for Chemists and Physicists", North Holland Publishing Company, Amsterdam, 3rd Edn., 1956, Chapt. 5.

## Studies on Electrolysis in a W-tube with Reference to Non-Faradaic Behaviour\*

SUBHALAKSHMI GHOSH and (LATE) SANTI R. PALIT

Department of Physical Chemistry,

Indian Association for the Cultivation of Science, Jadavpur, Calcutta-700 082

Manuscript received 19 November 1981, accepted 1 May 1982

Electrolysis of a dilute aqueous solution at low current density in a W-tube, though associated with high volume deficit, is nearly free from coliberation; its occurrence, if at all, being limited to the anode gas only. Unlike the electrolysis in a U-tube, two sharp and stationary boundaries formed in the intermediate zone of the W-tube may act as barriers to the migration of the ions responsible for the non-Faradaic phenomenon of coliberation.

It was observed by Palit<sup>1,2</sup> that if an alcoholic solution of an ionic dye or a dilute aqueous solution of  $K_2Cr_2O_7$  is electrolysed in a double-bent U-tube (called a W-tube), two very sharp boundaries appear inside the two inner tubes, dividing the solution into three zones as: anode - acidic dark coloured - neutral colourless - alkaline light coloured - cathode. Such phenomenon in a W-tube was also observed later by other workers<sup>3</sup>. Since electrolysis in a W-tube shows such intriguing features (depletion in the intermediate zone in violation of Hittorf mechanism of current conduction), it was considered interesting to examine the extent to which the W-tube shows non-Faradaic behaviour<sup>4,5</sup>. The earlier observations on non-Faradaic electrolysis were confined to U-tube only. The results reported in this paper also show the effect of cell geometry on non-Faradaic electrolysis.

### Experimental

The W-tube used for the electrolysis is shown in Fig. 1. Electrodes used are bright platinum foils




Fig. 1.

(1 cm<sup>3</sup>). Like U-tubes<sup>6</sup>, the arms of the W-tube are also connected to gas burrettes for collection of the liberated gases at the anode and the cathode. A coulometer containing 1.0 N  $K_2SO_4$  solution was connected in series. Current was passed either from D. C. mains (230 volts) or D. C. power supply unit. At the beginning, 2 mA current was allowed to pass but with the progress of electrolysis, the current density decreased to a very small value (a few hundred  $\mu A$ ) due to depletion of ions from the middle portion of the W-tube. The electrolysis was, therefore, allowed to run for several days so that a measurable amount of gas could be collected over the electrodes. Liberated gases were then analysed by sparking with the help of a tesla coil.

### Results and Discussion

The results are given in Fig. 2 and they are discussed with a comparison with those obtained in a U-tube under otherwise identical conditions.

(i) *Electrolysis of salt solution (0.001 N)*: With dilute solution of sodium sulphate or potassium sulphate, the results become very much different from those in a U-tube and the salient features are:

- High volume deficit (less than 50% of the total gas is liberated) and almost no coliberation on either side. Small amount of gas is evolved at the intermediate zone of the cell.
- Current falls to a very low value with the progress of electrolysis because the ions gradually get removed from the middle portion of the tube.

0.001 N  $K_2Cr_2O_7$  solution also does not give coliberation on either side but the deficit is not as high as with potassium or sodium sulphate solution.

Electrolysis of 0.01 N  $Na_2SO_4$  solution gives completely Faradaic results which is also very unlikely during electrolysis in a U-tube.

\* Presented At the Annual Convention of Chemists, 1980; Abstract No. 66(T).




Fig 2. Results of electrolysis in a W-tube. Of the three jointed columns, the left one (dotted) represents the total volume of gases liberated, the middle one the volume of gas at the cathode, and the right one that at the anode. The striped and the darkened parts in the middle and the right columns represent the volume of hydrogen and oxygen respectively in the mixture of the two.

a = 0.001 N NaOH at cathode and distilled water at anode, b = Distilled water at cathode and 0.001 N  $H_2SO_4$  at anode, c = 0.001 N NaOH at cathode and 0.001 N  $H_2SO_4$  at anode.

(ii) *Electrolysis of water*: With pure water, the volume deficit, though very high, is less than what is found with the salt solutions and a remarkable observation is that the anode gas explodes on sparking while the cathode gas remains totally free of coliberation.

(iii) *Electrolysis of 0.001N sulphuric acid solution*: At the beginning when some acid still remains near the cathode, no coliberation takes place on either side. With progress of electrolysis, as the acid concentration at the cathode side diminishes, the anode gas explodes on sparking while the cathode gas is pure hydrogen. However, the percentage of coliberation at the anode side is not very high.

(iv) *Electrolysis of 0.001 N sodium hydroxide*: Results are similar to those observed in the experiment with 0.001 N  $H_2SO_4$ .

(v) *Electrolysis of two different electrolytes at the cathode and the anode*: Few experiments were done by using alkali/acid, water/acid or alkali/water separately in the two compartments.

(a) (C) *alkali-acid (A)*: With 0.001 N NaOH at the cathode side and 0.001 N  $H_2SO_4$  at the anode side, the results are similar to those obtained with 0.001 N salt solutions. There is no coliberation either at the cathode gas or at the anode gas and volume deficit is also very high.

(b) (C) *water-acid (A)*: Distilled water at the cathode side and 0.001 N  $H_2SO_4$  at the anode side

give results different from those in the previous set up. The anode gas remains explosive while the cathode gas is free from any coliberation. Volume deficit is not very remarkable.

(c) (C) *alkali-water (A)*: Results similar to those in set up (b) are obtained with 0.001 N NaOH at the cathode side and distilled water at the anode side.

*Conclusion*: So far, the results with U-tube led us to believe that electrolysis at low current density and low concentration always produces non-Faradaic features, particularly deficit and coliberation. The results with W-tube brings forth the inadequacy of the above tenet. Here is a cell geometry where, though the current density and the concentration are both low, the deficit is extraordinarily high but there is no coliberation of the cathode gas in almost all cases, and whatever coliberation there is, it is limited only to the anode gas. These features are probably connected with boundary formation as is observed with many dyes. Since electrolysis in a W-tube shows a very intriguing behaviour mainly formation of two sharp and stationary boundaries separating the solutions into three zones: A/acid-water-alkali/C, it may be assumed that the intermediate zone somehow acts as a barrier to the ions which are responsible for the coliberation at cathode. If we presume these ions to be  $H_3O^+$ , they are likely to get discharged at the centre with production of some  $H_2O_2$ . This explains why in such experiments the

hydrogen-oxygen stoichiometry is unbalanced in favour of hydrogen. The observations reported in this paper also lend support to the contention\* that water getting charged at the electrodes and carrying a part of the current is responsible for non-Faradaic behaviour.

#### References

1. S. R. PALIT, *J. Indian Chem. Soc.*, 1973, **49**, 968.
2. S. R. PALIT and M. GUHA, *J. Indian Chem. Soc.*, 1974, **51**, 518.
3. M. D. LONDHEV, S. S. DARA and R. G. EDKIN, *Indian J. Phys.*, 1974, **48**, 916.
4. S. R. PALIT, *J. Indian Chem. Soc.*, 1974, **51**, 686.
5. S. R. PALIT, *Chemistry*, 1975, **48**, 16.
6. S. R. PALIT and S. GHOSH, *J. Indian Chem. Soc.*, 1976, **53**, 1099.

# Study of Dielectric Properties and Dipole Moments of Mn(II) Salts of Some Fatty Acids in Benzene Solutions

(MISS) LEEBA G. PARDESHI

Department of Chemistry, Government College of Arts and Science, Aurangabad-481 001

Manuscript received 4 September 1980, revised 11 May 1981, accepted 5 November 1981

The dipole moments of Mn(II) salts of palmitic, stearic and oleic acids were calculated by the methods of Gopal Krishna, Smyth-Dasgupta, Halverstadt-Kumler and Guggenheim. The values were calculated by Cole-Cole plots and parameters  $\epsilon_0$ ,  $\epsilon_\infty$  and  $\alpha$  were determined. From the plots of  $\log \tau$  vs  $1/T$ ,  $\Delta H$ ,  $\Delta F$  and  $\Delta S$  were evaluated. In the present investigation, dipole moment values obtained by Gopal Krishna method compared favourably with those obtained by Guggenheim method.

**T**HE present author has reported several studies on dipole moments and dielectric and other properties of salts of fatty acids. These include dipole moments and relaxation studies on Cu(II) stearate<sup>1</sup>, Cu(II) oleate<sup>2</sup>, pyridine adducts of salts of fatty acids<sup>3</sup>, effect of the salts of fatty acids on  $KMnO_4$ <sup>4-6</sup> and others<sup>7,8</sup>.

The present paper envisages to cover the dipole moments and dielectric relaxation properties of Mn(II) in all its aspects employing all possible recognised methods in literature. The initial problem faced by a worker in such studies is the sorting out of dielectric loss due to direct current conduction and one due to absorption. The present author being naturally interested in the latter conducted studies to ascertain whether the loss was due to absorption alone. This will be clear from Table 1 which gives the data involved in the well known expression :

$$\sigma = 5.5 \times 10^{-18} f \epsilon'' \text{ ohm}^{-1} \text{cm}^{-1}$$

where  $\sigma$  = specific conductance  
 $f$  = frequency in Hertz  
 $\epsilon''$  = the dielectric loss observed.

Since  $\log \epsilon''/\log f$  ratios in the present investigation (Table 1) are far from unity, it was concluded that the losses observed here are due to absorption alone.

## Experimental

The salts were prepared by double decomposition method from the sodium salts of the fatty acids and the chloride of the metal, the latter added in slight excess. However, the purest salts were prepared by the method described earlier<sup>9</sup>. The elemental analysis of the salts is in good agreement with the calculated values.

The dielectric constant,  $\epsilon'$ , and dielectric loss,  $\epsilon''$  were measured on DK-06 WTW decameter as described earlier<sup>1</sup>. The values of  $\epsilon_0$  and  $\epsilon_\infty$  were obtained from the Cole-Cole plots of dielectric constant  $\epsilon'$  vs dielectric loss  $\epsilon''$  on X axis<sup>10</sup>. The values of relaxation time were calculated using the expression

$$\frac{u}{v} = \omega \tau (1 - \alpha)$$

where  $v$  = distance on the Cole-Cole plot between  $\epsilon_0$  and experimental point,

$u$  = distance on the Cole-Cole plot between  $\epsilon_\infty$  and experimental point.

$\omega$  = angular frequency.

The enthalpy,  $\Delta H$ , entropy,  $\Delta S$ , and molar energies,  $\Delta F$ , were calculated from the plots of  $\ln \tau$  vs  $1/T$  using Eyring's equation. All the relevant data involved in these methods are set out in Table 2.

TABLE 1—LOG  $f$  AND LOG  $\epsilon''$  VALUES

Temp. °C	$f \times 10^{-3}$	$\epsilon''$	$\log f$	$\log \epsilon'' (-ve)$
System : Manganese palmitate-benzene				
34	260.0	0.3183	5.4150	0.6649
	272.5	0.0893	5.4364	1.0498
70	260.0	0.2082	5.4150	0.6815
	267.5	0.1160	5.4273	0.9351
System : Manganese stearate-benzene				
34	265.0	0.0984	5.4232	1.0068
	272.5	0.1147	5.4354	0.9408
70	260.0	0.2308	5.4150	0.6360
	275.0	0.0436	5.4398	1.3602
System : Manganese oleate-benzene				
34	257.5	0.2040	5.4108	0.6904
	265.0	0.1061	5.4232	0.8748
70	260.0	0.1372	5.4150	0.8955
	270.0	0.0762	5.4314	1.1181

TABLE 2—THERMODYNAMIC QUANTITIES AND THE RELEVANT DATA AT TEMPERATURES 34, 50, 60 AND 70° FOR Mn(II) PALMITATE, STEARATE AND OLEATE IN THAT SERIAL ORDER. ( $\Delta H$ ,  $\Delta F$  AND  $\Delta S$  IN Kcal/mole)

Temp. °C	$\epsilon_0$	$\epsilon_\infty$	$\alpha$	$\tau$	
34	2.2696	2.2589	0.06	2.13	$\Delta H = 2.50$
50	2.2891	2.2385	0.08	2.32	$\Delta F = 9.99$
60	2.2205	2.2125	0.27	3.05	$\Delta S = -0.044$
70	2.2140	2.2044	0.13	3.42	
34	2.2590	2.2513	0.40	2.88	$\Delta H = 3.54$
50	2.2314	2.2314	0.14	1.97	$\Delta F = 9.88$
60	2.2225	2.2135	0.24	2.19	$\Delta S = -0.0185$
70	2.2078	2.1967	0.05	1.23	
34	2.2345	2.2239	0.18	2.57	
50	2.2035	2.1928	0.18	2.05	$\Delta H = 3.51$
60	2.1864	2.1778	0.27	2.06	$\Delta F = 9.78$
70	2.1646	2.1564	0.82	1.80	$\Delta S = -0.02$



Thermodynamic quantities,  $\Delta H$ ,  $\Delta F$ , and  $\Delta S$ , are given in the last column of Table 2.

TABLE 2—DIPOLE MOMENT VALUES [ $\mu(D)$ ] OF Mn(II) SALTS OF PALMITIC, STEARIC AND OLEIC ACIDS BY SMYTH-DASGUPTA'S (1), GOPALKRISHNA'S (2), HALVERSTADT-KUMLER'S (3) AND GUGGENHEIM (4) METHODS AT 34, 50, 60 AND 70°

Compound	Temp. °C	(1)	(2)	(3)	(4)
MnPT <sub>2</sub>	34	3.62	3.50	3.48	3.50
	50	3.85	4.16	1.45	4.08
	60	3.12	3.16	1.54	3.29
	70	3.63	4.19	2.35	3.92
MnST <sub>2</sub>	34	6.57	6.34	—	5.53
	50	7.32	4.90	—	5.96
	60	7.74	5.57	6.29	6.23
	70	8.67	6.04	10.18	6.63
MnOL <sub>2</sub>	34	1.97	—	—	5.65
	50	2.26	—	—	5.81
	60	2.66	—	—	5.72
	70	3.89	—	—	5.12

### Results and Discussion

The methods of Gopalkrishna<sup>10</sup>, Smyth-Dasgupta<sup>11</sup>, Halverstadt-Kumler<sup>12</sup> and Guggenheim<sup>13</sup> were used to evaluate dipole moments of the salt at 34, 50, 60 and 70°. The Cole-Cole plots of dielectric constant  $\epsilon'$  vs dielectric loss  $\epsilon''$  gave the values of  $\epsilon_0$  and  $\epsilon_\infty$  on the X axis, which were used for calculating the  $\mu$  values by the methods of Gopalkrishna and Smyth-Dasgupta.

Literature indicates that there is a great scope in determining the  $\mu$  values of these salts, since a few salts like magnesium palmitate and calcium oleate<sup>14</sup> and magnesium oleate<sup>15,16</sup> have been studied and the dipole moment values reported are quite divergent. Palit *et al.*<sup>17</sup> have used the Guggenheim equation for the determination of  $\mu$  values of metal salts of fatty acids.

Guggenheim equation was modified by Palit and Banerjee<sup>18</sup> for a rational approach to the problem of computation of polarization and is given as :

$$P_s \mu = \frac{3M_s}{4\pi(\epsilon_1 + 2)} \cdot 2 \cdot \left[ \left( \frac{\delta}{\delta W_s} (\epsilon - n^2) \right) \right]$$

The attractive feature of the Guggenheim method could be retained without sacrificing the accuracy perceptibly.

Since the dipole moment values showed a slightly erratic trend, a search was made to ascertain whether the solutions were colloidal. No such behaviour was noticed when a cone of light was passed through the  $10^{-4}$  M solutions with the help of an arc appliance supplied with VNI SPECK constant deviation spectrometer.

In the present studies, the dipole moments are obtained by recent methods, namely those of Gopalkrishna and Smyth and Dasgupta. The  $\mu$  values obtained by these two methods have consistently agreed with each other and have also been in agreement with those obtained by the Guggen-

heim method. In Gopalkrishna's method, two plots are constructed to evaluate  $\mu$  values which are interdependant. The values are very susceptible to the values of  $[(\epsilon_0 - \epsilon_\infty)]$  which are obtained from Cole-Cole plots. Halverstadt-Kumler method suffers from the serious defect of measurement of densities of solutions.

Hence it was concluded that the changes in  $\mu$  observed may be attributed to viscosity changes<sup>9</sup> in the benzene solutions of the salts. A rough estimate would be that if the viscosity increases with temperature, the orientation of the molecules will hinder and there will be fall in dipole moment. In the case of MnPT<sub>2</sub> solutions the flow time was observed to decrease in the temperature interval of 60~70°. As against this, it was seen to increase in MnOL<sub>2</sub> (60~70°) and decrease in MnST<sub>2</sub> (50°~60°). Another explanation lies in the mesomorphic changes observed in the acids themselves which is carried to their salts.

Sydow<sup>19</sup> has investigated the mesomorphic forms in the fatty acids from their ir spectra in the range of 0-13 $\mu$ . Sindaire *et al.*<sup>20</sup> have observed in their studies of ir spectra of saturated hydrocarbons and esters of fatty acids that at least the two forms differ with respect to crystal axis. Phase transition was reported in some of the salts of fatty acids by X-ray diffraction.

The dipole moment values of palmitic, stearic and oleic acids are extremely small<sup>21-23</sup> and do not indicate any relationship between the chain length and the  $\mu$  values. However, in the present investigation, the chain length is found to play a major role in that generally the dipole moment order<sup>24</sup> is MnST<sub>2</sub> > MnPT<sub>2</sub> > MnOL<sub>2</sub>. This observation has been made by others in similar salts of magnesium. It is probable that the negative charge on the oleate, palmitate and stearate anions is distributed over the whole of the anion, much the same way as an electron cloud in an orbital, and hence the centre of gravity of charge lies further from the positive charge on the cation as the length of the chain goes on increasing. This may account for the order of  $\mu$  as MnST<sub>2</sub> > MnPT<sub>2</sub> > MnOL<sub>2</sub>.

The distribution parameter,  $\alpha$ , is found to be dependent on the length of the chain and double bonded structure and increases generally with temperature. The entropy values,  $\Delta S$ , are negative indicating an orderly orientation of these Mn(II) salts. This means free molar energies of these salts are larger than their enthalpy values. Again, the low values of  $\Delta S$  suggest that the molecules of the Mn(II) salts must be orienting themselves as a whole without segments or cations in them taking any prominent part.

Chitoku and Higasi<sup>25</sup> have stated that if the molecular shape is spherical or vary but a little from the spherical shape, the relaxation times are slightly dependent on the viscosity of the medium. They, however, observed that if the molecules are asymmetrical in shape its dipole rotation in the

medium automatically involves displacement of vast number of neighbouring molecules and as a result the relaxation times depend markedly on the viscosity of media. Some calculations on Mn(II) salts studied here, carried out according to O'Dwyer and Sack method<sup>26</sup>, show that the values differ largely from unity (a condition for spherical molecules) which according to these workers is a sure indication of asymmetry in the molecule.

#### Acknowledgement

The author thanks Dr. R. A. Bhobe for helpful suggestions.

#### References

1. LEELA PARDDESHI and R. A. BHOBE, *Monatsh.*, 1977, 108, 1235.
2. LEELA PARDDESHI and R. A. BHOBE, *Nat. Sc. J.*, 1976, 15, 16.
3. LEELA PARDDESHI, A. RASHEED and R. A. BHOBE, *Rev. Roum.*, 1978, 23, 1291.
4. P. D. JADHAV, LEELA PARDDESHI, A. RASHEED and R. A. BHOBE, *J. Indian Chem. Soc.*, 1978, 55, 650.
5. P. D. JADHAV, LEELA PARDDESHI and R. A. BHOBE, *Nat. Sc. J.*, 1978, 10, 17.
6. LEELA PARDDESHI, P. D. JADHAV and R. A. BHOBE, *Rev. Roum.*, 1979, 21a, 1060.
7. LEELA PARDDESHI, A. RASHEED, S. N. KHODASKAR and R. A. BHOBE, *Indian J. Chem.*, 1978, 16A, 621.
8. LEELA PARDDESHI, A. RASHEED and R. A. BHOBE, *Indian J. Chem.*, 1979, 18A, 520.
9. K. S. COLE and R. H. COLE, *J. Chem. Phys.*, 1951, 19, 1484.
10. K. V. GOPALEKRISHNA, *Trans. Faraday Soc.*, 1957, 53, 767.
11. O. P. SMYTH and S. DASGUPTA, *J. Amer. Chem. Soc.*, 1967, 89, 5682.
12. I. F. HALVERSTADT and W. D. KUMLER, *J. Amer. Chem. Soc.*, 1952, 64, 2988.
13. E. A. GUGGENHEIM, *Trans. Faraday Soc.*, 1957, 53, 767.
14. W. OSTWALD and R. BIEDEL, *Kolloid Z.*, 1984, 69, 185.
15. B. C. BANERJEE and S. R. PALIT, *J. Indian Chem. Soc.*, 1950, 27, 885.
16. N. PILPEL, *Trans. Faraday Soc.*, 1960, 56, 898.
17. S. BHATNAGER, B. C. BANERJEE and S. R. PALIT, *J. Indian Chem. Soc.*, 1962, 29, 175.
18. B. C. BANERJEE and S. R. PALIT, *J. Amer. Chem. Soc.*, 1962, 74, 8952.
19. E. V. SYDOW, *Acta Chem. Scand.*, 1955, 9, 119.
20. R. G. SINCLAIRE, A. F. MAKAY and R. N. JONES, *J. Amer. Chem. Soc.*, 1952, 74, 2570.
21. K. L. WOLF, *Physik Z.*, 1980, 31, 227.
22. M. P. VOTAROVICH and N. N. STEPANANKO, *Acta Physico. Chem. URSS*, 1940, 13, 47.
23. M. A. BOLLIER, *Gass. Chem. Ital.*, 1947, 77, 886.
24. W. OSTWALD and R. BIEDEL, *Kolloid Z.*, 1982, 59, 150.
25. K. OHITOKU and K. HIGASHI, *Bull. Chem. Soc. Japan*, 1968, 36, 1064.
26. J. O'DWYER and R. A. SACK, *Aust. J. Sc. Res. Ser.*, 1952, A5, 647.

## Studies on the Interfacial Tension and Electrical Conductance of Oil/Water Emulsions Stabilized by Lignosulphonate of *Eucalyptus teriticornis*

W. U. MALIK, S. K. SRIVASTAVA, TRILOK CHAND\* and A. K. JINDAL\*\*

Department of Chemistry, University of Roorkee, Roorkee-247 872

Manuscript received 17 December 1981, accepted 23 May 1982

Kerosene/water and turpentine/water emulsions stabilized by lignosulphonate have been prepared. Their interfacial tension and electrical conductance have been measured and discussed as a function of emulsifier concentration, temperature, salinity, alcohol-carbon chain length, emulsification time with temperature and phase volume ratio.

It is generally accepted that higher concentration of lignosulphonate, carbon chain length of alcohols and temperature lower the interfacial tension but increase the conductance and make the emulsions more conductive. Literature reveals that oil/water emulsions have been prepared by employing soaps<sup>1</sup>, Indian gums<sup>2</sup>, surfactants<sup>3</sup>, proteins<sup>4</sup>, saponins<sup>5</sup> etc., as emulsifiers and their properties such as interfacial tension<sup>6</sup>, surface tension and viscosity<sup>7</sup>, particle size<sup>8</sup>, stability<sup>9</sup>, creaming<sup>10</sup>, phase inversion<sup>11</sup> etc. have also been studied. The effect of phase-volume ratio on the physico-chemical properties of oil/water emulsions, dielectric constants<sup>12</sup> etc. has also appeared in literature. In the present investigations attempts have been made to assess the emulsifying power of lignosulphonates, a waste product of paper industry, by measuring the interfacial tension and electrical properties of kerosene/water and turpentine/water emulsions stabilized by this product. A correlation of interfacial tension with the conductance of emulsions has also been made.

### Experimental

Double distilled kerosene (sp. gr. 0.7948), turpentine (sp. gr. 0.8745) and water having conductance  $1 \times 10^{-8}$  ohm<sup>-1</sup> cm<sup>-1</sup> were used in all the experiments. The alcohols viz., methanol, ethanol, *n*-propanol, *n*-butanol, pentanol, and sodium chloride used were of B.D.H. AR grade. The lignosulphonate from eucalyptus wood was prepared at Star Paper Mill, Saharanpur and at Cellulose and Paper Branch, Forest Research Institute, Dehradun.

**Preparation of emulsion and measurement of its conductance:** Oil/water emulsions have been prepared by taking kerosene and turpentine as internal phase in the following manner:

1. Keeping the concentration of lignosulphonate constant (0.5%) and varying the oil/

water ratio viz., 10 : 10, 10 : 20, 10 : 30, 10 : 40, 10 : 50, 10 : 60, 10 : 70, 10 : 80 and 10 : 90.

2. Keeping the oil/water ratio (1 : 3) and concentration of lignosulphonate (0.5%) constant and varying the emulsification temperature viz., 20, 30, 40, 50 and 60° alongwith the emulsification time viz., 0.5, 1, 2, 4, 8 and 12 min, respectively.
3. Keeping oil/water ratio (1 : 3) and the concentration of lignosulphonate (0.5%) constant and adding 0.1% of alcohols viz., methanol, ethanol, *n*-propanol, *n*-butanol and pentanol.

Emulsions were prepared by agent-in-water method<sup>13</sup> and the conductance was measured with a sensitive conductivity bridge instrument.

**Measurements of interfacial tension:** The interfacial tension of different concentration of lignosulphonate in water viz., 0.01, 0.02, 0.04, 0.08 and 0.1% and the salinity effect by adding different concentrations viz., 0.01, 0.02, 0.04, 0.08, 0.1, 0.12, 0.16, 0.20 and 0.24% of NaCl to 0.05% lignosulphonate solution, have been measured against kerosene and turpentine oils by drop-volume method<sup>14,15</sup>, respectively.

The effect of various alcohols i.e. methanol, ethanol, *n*-propanol, *n*-butanol and pentanol on the interfacial tension of 0.05% aqueous solution of lignosulphonate against kerosene and turpentine have also been measured by keeping alcohol concentration constant (0.1% v/v) and calculated by

the equation: 
$$\gamma_{ow} = \frac{V(d_1 - d_2)g \times F}{r}$$
 where,  $\gamma_{ow}$

is the interfacial tension,  $V$  the volume of single drop,  $d_1$  and  $d_2$  the densities of respective phases,  $g$  the gravity,  $r$  the radius of the dropping tip and  $F$  is the correction factor<sup>16</sup>. All the results have been presented in Figs. 1 to 4 and Tables 1 to 5.

\* Asst. Chemist, IPE, Dehradun.

\*\* I. P. T., Saharanpur.

**TABLE 1—EFFECT OF TEMPERATURE ON THE INTERFACIAL TENSION OF OIL/0.05% A<sub>2</sub> SOLUTION OF LIGNOSULPHONATE**

Temp. °C	Interfacial tension (Dynes/cm)	
	Kerosene/water	Turpentine/water
20	11.24	8.58
25	10.99	8.43
30	10.88	8.18
35	10.50	7.98
40	10.18	7.78

**TABLE 2—EFFECT OF PHASE-VOLUME RATIO ON THE CONDUCTANCE OF O/W EMULSIONS**

Lignosulphonate = 0.5%, Temp. = 25 ± 1°

O/W Ratio	Conductance × 10 <sup>-3</sup> ohm <sup>-1</sup> cm <sup>-1</sup>	
	Turpentine/water	Kerosene/water
10 : 10	5.68	8.47
10 : 20	7.80	4.80
10 : 30	8.92	5.47
10 : 40	10.98	0.88
10 : 50	12.40	7.40
10 : 60	14.10	8.44
10 : 70	16.80	8.97
10 : 80	17.92	9.74
10 : 90	18.05	10.53

**TABLE 3—EFFECT OF EMULSIFICATION TEMPERATURE AND TEMPERATURE ON THE CONDUCTANCE OF O/W EMULSIONS**

O/W Ratio = 1 : 3, Lignosulphonate concn 0.5%

Temp. °C	Emulsification effect Conductance × 10 <sup>-3</sup> ohm <sup>-1</sup> cm <sup>-1</sup>		Temperature effect Conductance × 10 <sup>-3</sup> ohm <sup>-1</sup> cm <sup>-1</sup>	
	Kerosene/ water	Turpentine/ water	Kerosene/ water	Turpentine/ water
20	9.04	14.2	8.53	11.80
30	9.53	14.8	12.52	14.85
40	9.89	15.1	14.51	16.02
50	10.20	15.7	16.39	17.7
60	10.83	16.3	17.80	19.1

**TABLE 4—EFFECT OF ALCOHOL CARBON CHAIN LENGTH ON THE CONDUCTANCE OF O/W EMULSIONS**

Lignosulphonate concn : 0.5% ; O/W Ratio 1 : 3 ; Alcohol 0.1%

Alcohol	Conductance × 10 <sup>-3</sup> ohm <sup>-1</sup> cm <sup>-1</sup>	
	Kerosene/water	Turpentine/water
CH <sub>3</sub> OH	11.70	15.2
C <sub>2</sub> H <sub>5</sub> OH	11.74	15.4
n-C <sub>3</sub> H <sub>7</sub> OH	11.79	15.8
n-C <sub>4</sub> H <sub>9</sub> OH	11.81	15.95
C <sub>2</sub> H <sub>5</sub> OH	11.85	16.05
C <sub>4</sub> H <sub>9</sub> OH	11.89	16.8

**TABLE 5—EFFECT OF EMULSIFICATION TIME ON THE CONDUCTANCE OF O/W EMULSIONS**

O/W Ratio 1 : 3, Lignosulphonate = 0.5% ; Temp. = 25 ± 1°

Emulsification time (min)	Conductance × 10 <sup>-3</sup> ohm <sup>-1</sup> cm <sup>-1</sup>	
	Kerosene/water	Turpentine/water
0.5	10.05	13.8
1.0	10.69	14.2
2.0	10.91	14.9
4.0	11.34	16.5
8.0	12.56	18.8
12.0	12.57	18.31

## Results and Discussion

The interfacial tension of kerosene/water and turpentine/water interfaces against varying concentrations of lignosulphonate (Fig. 1) depict a




Fig. 1. Effect of lignosulphonate concentration on the interfacial tension of oil/water emulsions

decrease in surface tension of emulsions with an increase in lignosulphonate concentration. In both the cases, the decrease is linear at concentration 0.08% and beyond. This lowering of interfacial tension is attributed to the adsorption of lignosulphonate at oil/water interface and as adsorption reaches a constant value due to the formation of monolayer, the lowering in interfacial tension becomes smaller and smaller<sup>17</sup>.

Fig. 2 indicates a decrease in the interfacial tension of oil/water emulsion with an increase in




Fig. 2. Effect of alcohol carbon chain length on the interfacial tension of oil/water emulsions.

the carbon chain of alcohol. A break is observed on passing from *n*-propanol to *n*-butanol. This is expected as less soluble alcohols (in water) solubilize more oil and consequently lower the interfacial tension<sup>10</sup>. Fig. 3 shows the rise and fall in interfacial tension with increasing sodium chloride

while Table 2 indicates a fall in the conductance of emulsion with increasing phase-volume ratio. This may be attributed to an increase in the number of droplets with the increase in phase-volume ratio.

At higher emulsifier temperature the emulsions appear to be more conducting (Table 3). However,




Fig. 3. Effect of salinity on the interfacial tension of oil/water emulsions.

concentration. The temperature shows an adverse effect on interfacial tension, the decrease being linear with rise of temperature. This is in harmony with the results of earlier workers<sup>10</sup>.

It is clear from Fig. 4 that conductance increases with an increase in the concentration of emulsifier,




Fig. 4. Effect of lignosulphonate concn. on conductance of oil/water emulsions.

in some cases, emulsions first prepared at room temperature show an increase in conductance in the temperature range 20° to 60°. This may be due to an increase in the mobility of oil-droplets.

Tables 4 and 5 present the effect of alcohol carbon-chain and emulsification time on the conductance of kerosene/water and turpentine/water emulsions. It is evident that as the carbon chain of alcohols and emulsification time increase, the conductance of emulsions also increases. It can thus be concluded that emulsions having lower interfacial tension show higher conductance values.

#### Acknowledgement

Thanks of the authors are due to Shri L. N. Chowdhry, Works Manager, Star Paper Mills, Saharanpur and Dr. S. R. D. Guha, Director, Forest Products Division, Forest Research Institute and Colleges, Dehradun for necessary facilities for this work.

#### References

- (Miss) PRATIMA ACHARYA and TRILOK CHAND, *J. Indian Chem. Soc.*, 1961, **59**, 720.
- L. N. MUKHERJEE and S. D. SHUKLA, *Indian J. Appl. Chem.*, 1965, **20**, 177.
- P. K. SHARMA and TRILOK CHAND, *J. Indian Chem. Soc.*, 1979, **56**, 1206.
- TRILOK CHAND, *Rak. J. Sci. Res.*, 1979, **31**, 291.

5. B. K. NEOGY and B. N. GHOSH, *J. Indian Chem. Soc.*, 1958, 36, 118.
6. H. D. TAYAL and TRILOK CHAND, *J. Colloid and Polym. Sci.*, 1979, 257, 1125.
7. K. D. JAIN and M. K. SHARMA, *J. Indian Chem. Soc.*, 1971, 48, 779.
8. TRILOK CHAND and (Miss) PRATIMA ACHARYA, *Acta Olenola Indica*, 1980, 6, 217.
9. TRILOK CHAND, *J. Colloid and Polym. Sci.*, 1980, 258, 1904.
10. TRILOK CHAND, (Miss) PRATIMA ACHARYA and P. K. SHARMA, *Proc. Nat. Acad. Sci.*, 1979, 88.
11. P. SHERMAN, *Research (London)*, 1955, 8, 396.
12. TRILOK CHAND and P. K. SHARMA, *J. Indian Chem. Soc.*, 1981, 59, 86.
13. P. BECHTOLD, "Emulsion, Theory and Practice", Reinhold Publishing Corp., New York, 1966, p. 367.
14. E. MATIJEVIC and B. A. FETNICA, *Croat. Chem. Acta*, 1957, 29, 43.
15. H. C. FERRIERA, *J. Colloid Sci.*, 1965, 20, 44.
16. W. D. HARRINS and F. E. BROWN, *J. Amer. Chem. Soc.*, 1919, 41, 499.
17. TRILOK CHAND, *Egypt J. Chem.*, 1979, 22, 281.
18. T. MITSUI, S. NAKAMURA, F. HARUSAWA and Y. MACHIDA, *Kolloid Z. Z. Polymers*, 1973, 250, 227.

# Polarographic Studies on the Reduction of the Azomethine Bond in Aryl Thiosemicarbazides and the Determination of Hammett Parameters

WAHID U. MALIK\*, J. S. UPADHYAYA, RAJEEV JAIN\*\* and M. P. SHARMA

Department of Chemistry, University of Roorkee, Roorkee-247 672

Manuscript received 21 July 1981, revised 8 March 1982, accepted 8 July 1982

The reduction of 4-phenyl substituted thiosemicarbazides gave one, 2-electron transfer, well defined, irreversible, diffusion controlled reduction waves. The studies were made in Britton-Robinson buffer (pH range 2.0-11.0). The reduction in these compounds takes place at azomethine bond, formed due to a change in structure in alkaline medium. The effect of substituents on the reduction site and its correlation with Hammett substituent constants ( $\sigma$  x) have been studied. A possible mechanism for their reduction at DME has been proposed.

THE polarographic behaviour of sulphydryl compounds at the dropping mercury electrode has been studied<sup>1,2</sup> intensively during the past few years. Since this class is one of the most important among biologically important compounds, its oxidation reduction potential is of much importance. Thiosemicarbazides, well known precursors of antituberculous<sup>3</sup>, antifertility<sup>4</sup> and antineoplastic agents, have not been studied polarographically so far.

The present communication deals with the polarographic reduction of these compounds and the effect of various substituents on its half-wave potential and its correlation with the Hammett substituent constant ( $\sigma$  x).

## Experimental

**Preparation of thiosemicarbazides:** The 4-phenyl substituted thiosemicarbazides, having substituents hydrogen, 2-methyl, 3-methyl, 4-methyl, 2-methoxy, 3-methoxy, 4-methoxy, 2-chloro, 3-chloro, 4-chloro, 2-ethoxy and 2, 5-dimethyl, were prepared according to the method given in literature<sup>5</sup>.


**Solutions:** 0.01 M stock solutions of 4-phenyl substituted thiosemicarbazides were freshly prepared in dimethylformamide. Britton-Robinson buffers<sup>6</sup> and 1 M KCl solution were prepared in double distilled water from AnalaR grade chemicals.

**Apparatus:** Polarographic curves were recorded using a Cambridge pen recording polarograph. The capillary used possessed the characteristics 3.75 mg<sup>1/2</sup> S<sup>-1/2</sup> at a zero applied voltage. For the determination of the pH value of the solutions ELICO pH meter model LI-10, fitted with a glass-electrode was used. The number of electrons consumed in the electrode process was determined by the millicoulometry method of DeVries and Kroon<sup>7</sup>

in a small volume (0.3 ml) using a mercury pool as cathode.

## Results and Discussion

The polarographic behaviour of all these 4-phenyl substituted thiosemicarbazides was studied in the pH range 2.0-11.0. One well developed reduction wave was observed for all these compounds at pH above 7.0. The slope of  $E_{1/2}$  vs pH plots for all these thiosemicarbazides lie in the range 0.060-0.067 V/pH, which indicates that all substituted thiosemicarbazides reduce by similar mechanism. However, no wave was obtained below pH ~ 7.0. This can be accounted for on the basis of change in structure in alkaline medium. Thio form of thiosemicarbazides (1a) changes into thiol form (1b or 1c). Such changes of thio form to



thiol form in alkaline medium have also been reported by other workers<sup>8</sup>. Since the change in structure produce  $-C=N-$  as a site for facile reduction, the polarographic wave is obtained only in alkaline medium.

All these thiosemicarbazides reduce in a one, 2-electron transfer, diffusion controlled reduction waves. A few typical polarograms have been depicted in Fig. 1. The change in  $E_{1/2}$  with increasing concentrations of depolarizer suggests the irreversible nature of the waves (Table 1). The diffusion character of the limiting current has been proved by the linear dependance of the wave height on the concentration of thiosemicarbazides and by the proportionality of the wave height to the square root of the mercury column.

Present address : \* Vice-Chancellor, Kashmir University, Srinagar, J & K.  
\*\* Corresponding Author : , School of Studies in Chemistry, Jiwanj University, Gwalior 474 011, M.P.




Fig. 1. Polarograms of *o*-tolylthiosemicarbazide at various concentrations

TABLE 1—HALF-WAVE POTENTIALS OF 4-PHENYLTHIOSEMICARBAZIDES AT VARIOUS CONCENTRATIONS

No	R	Concentration <sup>a</sup>			
		$0.416 \times 10^{-3} M$	$0.832 \times 10^{-3} M$	$0.125 \times 10^{-3} M$	$0.166 \times 10^{-3} M$
		$E_{1/2}$ (V)	$E_{1/2}$ (V)	$E_{1/2}$ (V)	$E_{1/2}$ (V)
I	H	-1.20	-1.20	-1.26	-1.28
II	2-CH <sub>3</sub>	-1.20	-1.20	-1.27	-1.30
III	3-CH <sub>3</sub>	-1.22	-1.26	-1.30	-1.31
IV	4-CH <sub>3</sub>	-1.20	-1.26	-1.30	-1.34
V	2-OCH <sub>3</sub>	-1.20	-1.28	-1.30	-1.32
VI	3-OCH <sub>3</sub>	-1.20	-1.21	-1.28	-1.30
VII	4-OCH <sub>3</sub>	-1.22	-1.22	-1.28	-1.30
VIII	2-Cl	-1.26	-1.28	-1.32	-1.34
IX	3-Cl	-1.26	-1.30	-1.38	-1.40
X	4-Cl	-1.26	-1.31	-1.35	-1.37
XI	2-OC <sub>2</sub> H <sub>5</sub>	-1.34	-1.36	-1.38	-1.39
XII	4-OC <sub>2</sub> H <sub>5</sub>	-1.22	-1.26	-1.29	-1.32
XIII	2,5-(OH) <sub>2</sub>	-1.23	-1.26	-1.30	-1.32

The following mechanism based on two electron transfer can be proposed for the reduction of azomethine bond in these thiosemicarbazides. Similar reduction steps of the reduction of semicarbazones have also been proposed by Zuman<sup>9</sup>.




TABLE 2—POLAROGRAPHIC CHARACTERISTICS OF SOME 4-PHENYLTHIOSEMICARBAZIDES AT pH 10.0 IN 1.0*M* KCl, Conc. =  $0.832 \times 10^{-3} M$

No	R	$-E_{1/2}$ V	$i_d$ $\mu A$	$D_0^{1/2} \times 10^{-6}$	$\alpha_{11}$	$k_{1/2}^{1/2} \times 10^{-10} \text{ cm}^{-1}$	$\sigma_x$
I	H	1.32	1.75	0.82	0.54	1.90	0.00
II	2-CH <sub>3</sub>	1.31	1.70	0.90	0.56	1.60	-0.17
III	3-CH <sub>3</sub>	1.33	1.70	0.80	0.54	1.70	-0.07
IV	4-CH <sub>3</sub>	1.34	1.80	0.88	0.54	1.77	-0.17
V	2-OCH <sub>3</sub>	1.32	1.70	0.90	0.57	1.75	-0.39
VI	3-OCH <sub>3</sub>	1.33	1.75	0.93	0.54	1.67	-0.11
VII	4-OCH <sub>3</sub>	1.35	1.75	0.92	0.56	1.65	-0.27
VIII	2-Cl	1.28	1.80	0.98	0.56	1.65	+0.20
IX	3-Cl	1.39	1.70	0.90	0.57	1.67	+0.37
X	4-Cl	1.30	1.70	0.90	0.54	1.89	+0.28
XI	2-OC <sub>2</sub> H <sub>5</sub>	1.32	1.80	0.98	0.54	1.86	-0.35
XII	4-OC <sub>2</sub> H <sub>5</sub>	1.34	1.75	0.83	0.57	1.70	-0.28
XIII	2,5-(OH) <sub>2</sub>	1.30	1.70	0.80	0.59	1.70	-0.24

Controlled potential electrolysis further suggests 2 electron reduction mechanism for phenylthiosemicarbazide. Four electron reduction mechanism would have resulted in the production of aniline

( $-N=C-\xrightarrow{4H^+, 4e} -NH_2 + -CH_3$ ). Products were isolated after electrolysis for about 12 hr at 1.6 V in a H shaped cell and did not give any dye test for aromatic amine. Moreover, on analysing the products by tlc and taking aniline as reference, there was no indication of the presence of aniline. This clearly support 2 electron mechanism for the reduction of phenylthiosemicarbazides.

The  $E_{1/2}$  was found to shift towards more negative potential with increase in concentration of the depolarizer (Table 1). Such type of change in  $E_{1/2}$  values suggests the irreversible nature of the waves.

The plots of  $E_a$  vs  $[\log \frac{i}{i_d - i} - 0.546 \log t]$  were

found linear. The values of  $an$  and  $K_{1/2}^0$  calculated from the slope and intercept, further suggests the irreversible nature of the waves.

It is observed from Table 2 that the half-wave potentials are shifted towards more negative potential for compounds with substituents having electron donating nature, viz., 2-CH<sub>3</sub>, 3-CH<sub>3</sub>, 4-CH<sub>3</sub>, 2-OCH<sub>3</sub>, 3-OCH<sub>3</sub>, 4-OCH<sub>3</sub>, 2-Cl, 3-Cl, 4-Cl, 2-OC<sub>2</sub>H<sub>5</sub>, 4-OC<sub>2</sub>H<sub>5</sub> and 2,5-(CH<sub>3</sub>)<sub>2</sub>. This behaviour can be accounted for by considering the effect of the substituents. An electron donating group on the benzene ring would increase electron density on carbon attached to the hetero atom, viz. nitrogen due to which the reduction would become less facile and the  $E_{1/2}$  would shift to more negative potentials.

**Correlation of half-wave potential with Hammett constants:** The correlation between the structure of compounds and their chemical reactivity is fundamental problem in organic chemistry. One of the most important and versatile of these correlations is the Hammett equation<sup>10</sup> which relates the effect of structure on the reactivity of the molecule

For application in polarography, Hammett equation is transformed to the form<sup>11</sup>

$$\Delta E_{1/2} = P + M + S,$$



where P, M and S represent the shift in the half-wave potential due to the change in activation energy by polar, mesomeric and steric effects. In *m*- or *p*-substituted thiosemicarbazides the substituents are rigid and lie much away from the reaction centre with the result that generally the steric interaction between the substituent and reaction centre is almost negligible. The change in  $E_{1/2}$  of parent thiosemicarbazide can, therefore, be attributed to the electron repelling nature of the substituent. Thus, when steric effects are not taken into account, the modified Hammett equation,

$$\Delta E_{1/2} = \rho_{\pi, R} \sigma x,$$

represents the polar effect of the substituents. Considering the relationship for the substituent effect<sup>1,2</sup>

$$\sigma x = \log k_1 - \log k_1^0$$

where  $k_1^0$  and  $k_1$  represent the ionisation constants for the unsubstituted and substituted molecules, respectively and  $\sigma x$  is the substituent constant. The corresponding relationship for the irreversible wave may be written as

$$\sigma x = \log k_{f,h(\text{sub})}^0 - \log k_{f,h(\text{unsub})}^0$$

The value of  $\sigma x$  at pH 10.0 thus determined are given in Table 2.

Fig. 2 exhibits the relation between  $E_{1/2}$  of substituted thiosemicarbazides and the Hammett sub-




Fig 2 Plot of  $-E_{1/2}$  vs  $\sigma$  for some 4-phenylthiosemicarbazide in B. R. buffer at pH=10.0.

stituent constant  $\sigma x$ , which include both polar induction and polar configuration effect. It is of interest to note that substituents like 3-Cl, 4-Cl, 3-CH<sub>3</sub>, 4-CH<sub>3</sub>, 4-OCH<sub>3</sub> and 4-OC<sub>2</sub>H<sub>5</sub> fit in the straight line, whereas 2-Cl, 2-CH<sub>3</sub>, 2-OCH<sub>3</sub>, 2-OC<sub>2</sub>H<sub>5</sub> and 2,5-(CH<sub>3</sub>)<sub>2</sub> show deviation. This deviation may be accounted for on the basis of slight steric hindrance to coplanarity. The value of specific rate constant ( $\rho$ ) was found to be 0.12 V.

It is observed in the above reaction series that methyl, chloro, methoxy and ethoxy substituents show positive polarographic *ortho* shift which indicates that *ortho* derivative is easily reducible in comparison to its *p*-analogue.

TABLE 3—POLAROGRAPHIC *ortho* SHIFTS ( $\Delta_0$ ) FOR SOME 4-PHENYLTHIOSEMICARBAZIDES AT pH 10.0.

R	$\Delta_0$ , V
Methyl	+0.03
Chloro	+0.02
Methoxy	+0.03
Ethoxy	+0.02

#### References

1. HANS BERGE, *Naturwiss. Reihe*, 1961, **10**, 19
2. R. S. SAXENA and K. C. GUPTA, *Electrochim. Acta*, 1968, **13**, 1745.
3. R. BEHNISCH, F. MIETESCH and H. SCHMIDT, *Amer. Rev. Tuberc.*, 1950, **61**, 1.
4. S. S. TIWARI and A. SHARMA *J. Indian Chem. Soc.*, 1975, **52**, 158.
5. NG. Ph. BUIHOI, NG. D. XUONG and NG. H. NAM, *J. Chem. Soc.*, 1956, 2160.
6. H. T. S. BRITTON, "Hydrogen Ion", D. Van Nostrand Co., Inc., N. Y., 4th Edn., 1956, Vol. 1, p. 360-365.
7. T. DEVERIES and J. L. KROON, *J. Amer. Chem. Soc.*, 1953, **75**, 2484.
8. S. N. PODDAR and N. SAHA, *J. Indian Chem. Soc.*, 1975, **52**, 57.
9. B. FLEET and P. ZUMAN, *Coll. Czech. Chem. Comm.*, 1967, **32**, 2036.
10. L. P. HAMMETT, "Physical Organic Chemistry", McGraw Hill, New York, 1940.
11. J. WEBER, *Chem. Listy*, 1958, **52**, 1249.
12. J. HEYROVSKY and J. KUTA, "Principles of Polarography", Academic Press, New York, 1966.

# Polarographic Reduction of Some 5,5-Dimethylcyclohexane-2-Benzothiazolyldiazono-1,3-Diones and its 2-Methyl, 4-Methyl, 4-Methoxy, 4-Ethoxy Derivatives


WAHID U. MALIK, (Miss) S. AGARWAL and RAJEEV JAIN\*

Department of Chemistry, University of Roorkee, Roorkee-247 672


Manuscript received 2 April 1982, accepted 21 July 1982

Polarographic studies of some 5,5-dimethylcyclohexane-2-benzothiazolyldiazono-1,3-diones were carried out in B. R. buffer in the pH range 2.0-12.0. All the compounds gave a single, well defined, irreversible, diffusion controlled reduction wave whose  $E_{1/2}$  was pH dependent but  $i_d$  remained constant throughout the entire pH range. The  $E_{1/2}$  shifted towards negative potential with increase in pH, thereby showing that protonation precedes reduction. The effect of the double layer structure on the  $E_{1/2}$  is also studied.

**M**OST of the polarographic investigations on sulphur containing organic compounds deal with



$-\text{NH}-\text{CS}-\text{S}-$  and  $\text{RSO}_2\text{H}$  groups<sup>1-6</sup> but not much has been done to study the polarography of other classes of sulphur containing organic compounds such as thiazoles and benzothiazoles<sup>7-11</sup> which are of great biological importance. A knowledge of their redox behaviour at the solution-mercury interface may prove useful from physiological point of view. Moreover, the polarographic behaviour of hydrazones has received little attention<sup>8-10</sup> and little information is available about the hydrazones in which the carbon atom of the  $-\text{NH}-\text{N}=\text{C}-$  group is attached to cyclohexane ring. Polarographic studies on the reduction of these compounds at DME were therefore undertaken. The present paper describes the results of such studies on some recently synthesised diazono derivatives of 2-aminobenzothiazoles (A).



## Experimental

**Apparatus:** The polarographic measurements were carried out using a Cambridge pen recording polarograph. The capillary characteristic was  $2.040 \text{ mg}^{1/2} \text{ sec}^{-1/2}$ . SCE was used as the reference electrode. pH measurements were made with an expanded scale ECIL pH-meter in connection with glass electrodes. The polarograms were recorded at  $20 \pm 0.1^\circ$ .

**Reagents and solutions:** 5,5-Dimethylcyclohexane-2-benzothiazolyldiazono-1,3-diones having

substituents  $\text{H}$ ,  $2\text{-CH}_3$ ,  $4\text{-CH}_3$ ,  $4\text{-OCH}_3$ ,  $4\text{-OC}_2\text{H}_5$ , were prepared according to the method developed earlier<sup>10</sup> and their purity was assured by repeated recrystallisation. Britton-Robin buffers in the pH range 2.0-12.0 were prepared adding requisite amount of 0.2 M sodium hydroxide solution to stock acid solution composed of boric acid, phosphoric acid and acetic acid. Chemicals used were of A. R. grade. Stock solution ( $1 \times 10^{-3} \text{ M}$ ) of hydrazones were prepared in dimethylformamide.

**Procedure:** Solutions for recording polarograms were prepared by mixing 3.0 ml hydrazone solution ( $1.0 \times 10^{-3} \text{ M}$ ), 1.0 ml 1.0 M KCl and 1.0 ml buffer. The polarograms were then recorded after passing hydrogen for about 10 min. The number of electrons involved in the reduction process were calculated by millicoulometric method<sup>11</sup> using  $\text{CdSO}_4$  solution as reference. Controlled potential electrolysis was carried out at potential corresponding to the plateau (1.6 V) of the wave. The electrolysis cell was a H-shaped one, the cathodic and anodic compartments being separated by a diaphragm of sintered glass. Mercury was used as electrode material. A complete electrolysis (about 6 hr) of the cathode was analysed for the identification of the product.

## Results and Discussion

The compounds listed in Table 1 gave a single reduction wave in B. R. buffer of pH 2.0-12.0 and in 0.1 M NaOH. The nature of the wave found to be diffusion controlled as evident by linear dependence of limiting current on  $\sqrt{t}$  and concentration of depolarizer. The constancy of wave height in the pH range studied, together with the fact that  $di/dt$  had a very low value of temperature coefficient further confirmed that the reduction

\* Address for correspondence:

School of Studies in Chemistry, Jiwaji University, Gwalior-474 011 (M.P.).

TABLE 1—POLAROGRAPHIC CHARACTERISTICS OF 5,5-DIMETHYLCYCLOHEXANE-2-BENZOTHAZOLYLHYDRAZONO-1,8-DIONES AT pH 7.4; CONC.  $8.0 \times 10^{-4}$  M

Sl. No.	R	$-E_{1/2}$ , V	$i_d$ , $\mu A$	I	$\frac{dE_{1/2}}{dpH}$ , $\frac{V}{pH}$	$\frac{\Delta E_{1/2}}{V}$	$\alpha n$		P
							I Method*	II Method**	
1	H	0.48	0.85	0.22	0.063	0.00	1.20	1.20	1.22
2	2-CH <sub>3</sub>	0.56	0.85	0.22	0.066	0.08	1.02	1.07	1.80
3	4-CH <sub>3</sub>	0.51	0.90	0.23	0.062	0.03	1.08	1.10	1.24
4	4-OCH <sub>3</sub>	0.51	0.85	0.22	0.062	0.03	1.32	1.28	1.08
5	4-OC <sub>2</sub> H <sub>5</sub>	0.52	0.85	0.22	0.061	0.04	1.20	1.24	1.11

\*Log plots method.

\*\*Oldham and Perry method.

waves were fully diffusion controlled. The wave characteristics are shown in Table 1.

The half-wave potential of these compounds was found to be dependent on pH and shifted towards more negative potential with increase in pH. The plots of  $E_{1/2}$  vs pH were linear with slopes in the range 0.061 to 0.066 V/pH upto pH 8.3 and thereafter there was a small change in  $E_{1/2}$ . The value of the slope was significantly small. The irreversible nature of the waves was confirmed by log plots<sup>12</sup>. The fact that  $E_{1/2}$  shifted towards more negative potential with increasing concentration of the depolariser further pointed towards the irreversible nature of the waves. The value of  $\alpha n$  (product of transfer coefficient and the number of electrons transferred in the rate determining step) and p (number of protons involved during the rate determining step of the reaction) was determined using the expressions<sup>13</sup>

$$E_{1/4} - E_{3/4} = -\frac{0.0517}{\alpha n_a}$$

$$\frac{dE_{1/2}}{dpH} = -\frac{0.05915}{\alpha n_a} \cdot p$$


The values of  $\alpha n_a$  was also determined by the method of Oldham and Perry<sup>13</sup> using the expression

$$E_{1/2} = E_r + \frac{0.0592}{\alpha n_a} \log \left[ 1.35 K_r + \frac{t}{D} \right]$$

where t is the drop time at the potential  $E_r$ . The values of half-wave potentials together with  $dE_{1/2}/dpH$ ,  $\alpha n_a$  and p are also given in Table 1.

Since the  $E_{1/2}$  of these thiazoles were pH dependent and the limiting current pH independent upto pH 8.3, it was concluded that both acidic and basic forms of the compounds reached the electrode surface and are electroactive. Thus, the proton transfer reaction precedes the electrode process in such cases. Out of the two general sequences<sup>14</sup> for the proton and electron addition viz.,  $H^+$ , e,  $H^+$ , e and  $H^+$ , e, e,  $H^+$ , the former sequence was more probable for these compounds in the light of their structural genesis. After the uptake of a proton and one electron the radical (C) would accept a proton to form a protonated radical (D) which after taking one electron would get cleaved at nitrogen bond with the formation of aniline. The imine (F) formed was further protonated and got reduced.

Alternatively, the radical (C) could also combine with an electron instead of proton but this possibility was cancelled out by the fact that such a reduction would involve only 2 electrons whereas polarographic data clearly indicate 4-electron transfer reactions at the DME.



These mechanistic steps found support from the increase of  $E_{1/2}$  with pH as protons are consumed in reduction. As the rate of protonation becomes slow the  $E_{1/2}$  tends to become constant. Fig. 1





Fig. 1. Plots of  $-E_{1/2}$  vs pH for some 5,5-dimethylcyclohexane-2-benzothiazolylhydrazono-1,8-diones.

shows that above pH 8.3, the shifting of half-wave potential with pH towards negative potential is not so marked, as in the acidic range. Moreover, at pH above 8.3, the  $E_{1/2}$  is practically constant. In the pH range studied where both the electroactive forms (acidic as well as basic) are reduced, half-wave potential of the two forms are so close that the waves merge and no separation is observed.

Similar steps for the reduction of hydrazono group have also been proposed by others<sup>15-17</sup>, involving cleavage of the nitrogen-nitrogen bond.

Due to an acid-base equilibrium that exists between two structural forms of the compounds, wave height of the wave remains pH independent as long as the formation of the acidic form from the basic form is fast enough. When pH increases the rate of protonation decreases and the wave height decreases as well.



When the depolariser solution was tested after controlled potential electrolysis, it gave dye test thereby showing that at least one of the reduction product is aromatic amine. UV spectra of the solution during electrolysis were recorded at different intervals of time.  $\lambda_{\text{max}}$   $\text{CH}_3\text{OH}$  at 415 nm for  $-\text{NH}-\text{N}=\text{C}-$  grouping showed a decrease in the peak height after each interval of time and finally disappeared, confirming the above reduction mechanism.

**Effect of supporting electrolyte concentration.** The effect of the double layer structure on the  $E_{1/2}$  of a process preceded by the protonation is given by the equation<sup>18</sup>,

$$\Delta E_{1/2} \approx \Delta \psi_1 \left( \frac{\alpha n_s - Z}{\alpha n_s} - \frac{\partial E_{1/2}}{\partial \text{pH}} \frac{F}{2.30 RT} \right) \quad (1)$$

where  $\psi_1$  is the variation in the double layer potential,  $\alpha$  the transfer coefficient,  $n_s$  the number of electrons transferred in the rate determining step and  $Z$  the charge of the particle being discharged. Undoubtedly, a marked effect of change in ionic strength on  $E_{1/2}$  should be observed in cases where the depolarizer is in the ionic form and no such effect should be observed if it is in the non-ionic form, i.e.,  $Z=0$ . Since the second term in the bracket of equation (1) is nearly -1 and  $Z=0$ ,  $E_{1/2}$  will be almost independent of  $\psi_1$  or of ionic strength. This was verified by carrying out experiments with varying concentrations of KCl (0.01 M to 0.25 M). The values of  $dE_{1/2}/d\text{pH}$  thus obtained fell in the range 60-70 mV/pH and  $E_{1/2}$  and  $i_d$  remained unaffected by the change in concentration of the supporting electrolyte.

**Effect of solvent composition:** The polarogram of the above mentioned thiazoles were recorded in the minimum amount of DMF (20%) necessary for the dissolution of the compound. The DMF percentage was then progressively increased from 20 to 60% to see the effect of solvent composition on the electrode process.

$E_{1/2}$  of the compounds was found to shift towards more negative potential almost linearly<sup>19</sup> and that this effect is much more pronounced in compounds having comparatively more positive potential. This shift may be attributed<sup>20</sup> to a decrease in the surface concentration of the electroactive species in addition to a change of pH and pKa of the protonated depolarizer.

#### References

1. D. J. HALLS, A. TOWNSEND and P. ZUMAN, *Anal. Chem. Acta*, 1968, **41**, 51.
2. P. ZUMAN and M. KUJE, *Naturwiss.*, 1958, **45**, 541.
3. R. ZOHRAUDIK and P. ZUMAN, *Chem. Listy*, 1958, **52**, 281.
4. M. BREZINA and P. ZUMAN, "Polarography in Medicine, Biochemistry and Pharmacy", Interscience, New York, 1958, 470.
5. J. TIROUFIET and E. LAVIRON, *Acad. Sci.*, 244.
6. J. TIROUFIET, E. LAVIRON, J. METZGER and J. BLOCHARD, *Colln. Czech. Chem. Commun.*, 1960, **25**, 3277.
7. W. U. MALIK, R. N. GOYAL and M. B. BHAVIKATI, *Indian J. Chem.*, 1975, **13**, 955.
8. Y. ASAKI, *Chem. Pharm. Bull. (Tokyo)*, 1969, **11**, 990.
9. Y. P. KITAJEV, A. K. BUDNIKOV and I. I. MASLOVA, *Izv. Akad. Nauk SSSR, Ser. Khim.*, 1967, **9**, 1911.
10. R. N. GOYAL, R. JAIN and S. TYAGI, *J. Indian Chem. Soc.*, (In press).
11. T. DEVERIES and J. L. KROON, *J. Amer. Chem. Soc.*, 1958, **75**, 2484.
12. L. MEITES, "Polarographic Techniques", Interscience, New York, 1967.
13. K. B. OLDHAM and W. P. PERRY, *Anal. Chem.*, 1968, **40**, 65.
14. P. ZUMAN, "The Elucidation of Organic Electrode Process", Academic Press, New York, 1969.
15. H. LUND, *Acta Chem. Scand.*, 1959, **13**, 249.
16. J. W. HAAS and C. C. LYNCH, *Anal. Chem.*, 20, 479.
17. J. W. HAAS and C. C. LYNCH, *Acta Chem. Scand.*, 1964, **18**, 563.
18. S. G. MAIRANOVSKY, *J. Electroanal. Chem.*, 1962, **4**, 166.
19. K. SCHWOKKE, in "Progress in Polarography" (Ed.) P. ZUMAN and I. M. KOLTHOFF, Interscience, New York, 1962, Vol. 1, p. 333.
20. S. G. MAIRANOVSKY, *Talanta*, 1965, **12**, 1299.

# • The Reaction of Potassium Permanganate with Potassium Ferrocyanide and Some Binary Mixtures in Presence of Fluoride Ions\*

H. A. DESSOKI, M. G. ALLAM and A. M. HAMMAM

Department of Chemistry, Faculty of Science, Zagazig University, Benha, A. R. Egypt

Manuscript received 28 January 1982, accepted 7 June 1982

The reactions of potassium permanganate with potassium ferrocyanide and binary mixtures of ferrous-mercurous (1), ferrocyanide-mercurous (2) and ferrous-ferrocyanide (3) have been studied potentiometrically in acid medium containing fluoride ions. For potassium ferrocyanide, good results are obtained at 0.018-1.8  $N$   $H_2SO_4$  in presence of 0.238-0.357  $M$   $NaF$  at temperature range 25-50°. But in the case of the mixtures, the optimum acidities are 0.315  $N$   $H_2SO_4$  (2, 3) and 0.22  $N$  (1) in presence of 0.357  $M$   $NaF$  at 25°. 125-503 mg of ferrocyanide can be determined with high accuracy. The constituents of the mixtures can be titrated in presence of each other. The difficulty of precipitation of manganese(II) ferrocyanide can be overcome by keeping the reduction product of  $KMnO_4$  as complex  $Mn(III)$  fluoride.

**T**HE reaction between  $KMnO_4$  and ferrocyanide in acid medium was studied by De Beer and Hjort<sup>1</sup>.

Kolthoff<sup>2</sup> titrated ferrocyanide at concentration less than 0.02  $M$  by comparing the colour at the end point with that of ferrocyanide. Enough acid should be present to prevent the precipitation of manganous ferrocyanide. Potentiometric titration of ferrocyanide in alkaline medium was reported by Issa and Azin<sup>3</sup>.

The monovalent mercury<sup>4</sup> and bivalent iron<sup>5</sup> can be titrated quantitatively with  $KMnO_4$  in presence of fluoride ions. Ferrous iron reduces  $KMnO_4$  under these conditions in two steps with formation of  $Mn(III)$  and  $Mn(II)$ . However, monovalent mercury does not effect the reduction quantitatively to the  $Mn(II)$  step. This difference is obviously related to the reducing power of the different species which is known to depend on the redox potential values of the system concerned which amount to 0.92, 0.771 and 0.36 volt, respectively<sup>6</sup>. It is therefore of interest to find out how binary mixtures of these species and ferrocyanide behave in their oxidation with  $KMnO_4$ .

## Experimental

Potassium permanganate, potassium ferrocyanide, mercurous nitrate and ferrous sulphate solutions were prepared from chemically pure salts and standardised according to recommended procedures. 4.5  $M$   $H_2SO_4$  and 0.476  $M$   $NaF$  were also prepared from chemically pure products. The titration equipment is the same as described earlier<sup>7</sup>.

## Results and Discussion

*Reaction between potassium permanganate and potassium ferrocyanide :*

The titration curves of ferrocyanide with  $KMnO_4$  in absence of  $F^-$  ions and acidity of 0.045  $M$   $H_2SO_4$

includes one inflection corresponding to the reduction of  $KMnO_4$  to  $Mn(II)$ . This inflection amounts to 230 mV per 0.05 ml of the titrant. In presence of  $NaF$  of different molarities (0.119-0.357  $M$ ) a second inflection appears, representing the oxidation of the originally produced  $Mn(II)$  to  $Mn(III)$ . Under these conditions the second end point coincides with the theoretical value in presence of  $NaF$  (0.238 to 0.357  $M$ ) and occurs somewhat earlier at 0.119  $M$   $NaF$ . The first inflection occurs about 14% earlier than expected on the basis of the formation of  $Mn(II)$ . This is obviously due to partial precipitation of ferrocyanide as the  $Mn(II)$  salt. However, this precipitate undergoes oxidation at the second step together with the initially formed  $Mn(II)$ . This fact finds support from the effect of acidity on the titration process. As the acidity of the solution is increased the first end point retreats slowly until it coincides with the theoretical value for the  $Mn(II)$  step at 0.45  $M$   $H_2SO_4$ . The second end point always coincides with that expected for the  $Mn(III)$  step. At higher acidities (0.675  $M$ ) the second inflection disappears and the curve is restricted to the first step.

At temperatures between 25-40° and at an acidity of 0.02  $M$ , the two inflections do not deviate from the theoretical values. At 50° the  $Mn(II)$  step approaches the theoretical values probably as a result of the increased solubility of the  $Mn(II)$  ferrocyanide. The second end point is attained earlier than the expected value due to the partial decomposition of  $KMnO_4$  at high temperature.

Titration of different quantities of ferrocyanide can be achieved when the second end point is taken into consideration. The first end point shows larger negative errors on increasing the concentration of ferrocyanide. The amount of ferrocyanide precipitated apparently increases with the increase

\* This work was carried out under the supervision of the late Prof. I. M. Issa.

in the concentrations of the reactants—Mn(II) and ferrocyanide.

The redox potentials of the ferric/ferrocyanide couple and that of Mn(III)/Mn(II) couple under various conditions were evaluated from the titration curves (Figs. 1 and 2). The data in Table 1




Fig. 1. Titration of 0.00842 N  $K_4[Fe(CN)_6] \cdot 3H_2O$  with 0.0922 N  $KMnO_4$  in presence of NaF (0.357 M) and  $H_2SO_4$  of different molarities.

A—0.009 M, B—0.0225 M, C—0.045 M, D—0.225 M, E—0.45 M, F—0.675 M and G—0.90 M  $H_2SO_4$ .

indicate an increase of the formal potential with rise of acidity and decrease of fluoride ion concentration. They are not affected much by temperature or concentration of the reactants.

#### Titration of a mixture containing Fe(II) and $Hg_2^{2+}$ :

The titration curve of this mixture (Fig. 3) is characterised by two inflections, the first of which is small and amounts to 25–35 mV. The second inflection is larger and amounts to 170–230 mV. The first step corresponds to the oxidation of




Fig. 2. Titration of different molarities of  $K_4[Fe(CN)_6]$  with 0.0922 N  $KMnO_4$  at optimum conditions.

A—0.00842 N, B—0.00547 N, C—0.00344 N, D—0.0108 N and E—0.0187 N  $K_4[Fe(CN)_6]$ .




Fig. 3. Titration of a mixture containing  $Fe^{2+}$  and  $Hg_2^{2+}$  with 0.0922 N  $KMnO_4$  in presence of 0.225 N  $H_2SO_4$  and 0.357 N NaF.

A—0.000828 N  $Fe^{2+}$  and 0.006528 N  $Hg_2^{2+}$ ,  
B—0.001656 N  $Fe^{2+}$  and 0.006528 N  $Hg_2^{2+}$  and  
C—0.001656 N  $Fe^{2+}$  and 0.008264 N  $Hg_2^{2+}$ .

TABLE 1—TITRATION OF  $K_4[Fe(CN)_6]$  WITH 0.0922 N  $KMnO_4$  IN PRESENCE OF 0.357 M NaF AT 25°

$K_4[Fe(CN)_6]$		Volume of $KMnO_4$ consumed (ml)		Theoretical end point (ml)		Error		Inflection at end point (mV/0.05 ml)		Formal redox potential (V)	
ml	mg	a	b	a	b	a	b	a	b	1	2
5	125	3.51	4.65	3.75	4.69	-0.41	-0.85	112	88	0.474	0.824
8	201	4.92	7.50	6.02	7.51	-18.10	-0.13	130	74	0.476	0.842
10	251	6.50	9.35	7.50	9.38	-18.88	-0.32	146	58	0.449	0.842
15	377	9.41	13.96	11.23	14.07	-16.21	-0.78	152	46	0.469	0.848
20	508	13.00	18.60	15.01	18.76	-13.40	-0.85	158	29	0.464	0.852
Acidity											
ml	M										
0.2	0.009	3.41	4.68	3.75	4.69	-9.10	-0.21	176	70	0.450	0.844
0.5	0.0225	3.56	4.67	3.75	4.69	-5.38	-0.42	218	68	0.458	0.862
1.0	0.045	3.61	4.65	3.75	4.69	-3.78	-0.84	308	32	0.475	0.979
5	0.135	3.65	4.65	3.75	4.69	-2.67	-0.84	312	20	0.498	0.994
10	0.225	3.75	4.63	3.75	4.69	nil	-1.26	377	18	0.550	1.108
15	0.45	3.75	—	3.75	4.69	nil	—	395	—	0.614	—
20	0.9	3.72	—	3.75	4.69	-0.80	—	400	—	0.688	—

Normality of  $KMnO_4$  on the basis of valency change  $Mn^{7+} \rightarrow Mn^{2+}$ .

(a)  $MnO_4^- \rightarrow Mn^{2+}$ ; (b)  $Mn^{3+} \rightarrow Mn^{2+}$ .

(1)  $[Fe(CN)_6]^{4-}/[Fe(CN)_6]^{3-}$  system, (2)  $Mn^{3+}/Mn^{2+}$  system.

ferrous iron since the formal redox potential depicted from this step amounts to about 617 mV which is in harmony with the values obtained in the titration of ferrous iron alone<sup>4</sup>. The end point, as is evident from Table 2, is attained when  $\text{KMnO}_4$  is reduced to the  $\text{Mn(II)}$  step.

The second inflection in the titration curve represents oxidation of mercurous mercury and the formed manganese(II) whereby  $\text{MnO}_4^-$  is reduced to  $\text{Mn(III)}$ . The redox potential value, as evaluated from the second inflection, amounts to about 900 mV which approximates that of the  $\text{Hg}^{2+}/\text{Hg}_2^{2+}$  couple under the prevailing experimental conditions. The second end point coincides fairly well with theoretical values based on complete oxidation of  $\text{Fe(II)}$  and  $\text{Hg(I)}$  whereby  $\text{MnO}_4^-$  is reduced to the manganic state. The separation of the two steps of reduction is in harmony with the apparent difference in the redox potential of the two systems involved in the reaction. The success of the titration is confirmed by varying the amounts of the two reductants in the mixture and also by titrating the separate constituents alone under the same experimental conditions. The results depicted in Table 2 are in harmony with these speculation.

#### Titration of a mixture containing ferrocyanide and mercurous mercury :

The curves obtained in the titration of this mixture are approximately similar to those obtained in the case of ferrous iron and mercurous mercury and obviously represent the same sequence of the reaction steps (Fig. 4). The first inflection represents oxidation of ferrocyanide whereby  $\text{MnO}_4^-$  is reduced to  $\text{Mn(II)}$ . The latter, together with monovalent mercury, is oxidised in the second step whereby  $\text{MnO}_4^-$  is reduced to  $\text{Mn(III)}$ . The occurrence of these two steps is in harmony with the redox potential values of the systems involved, which amount to 0.432 and 0.93 V for the  $[\text{Fe}(\text{CH})_6]^{2+}/[\text{Fe}(\text{CN})_6]^{4-}$  and the  $\text{Hg}^{2+}$  systems, respectively. The end points (Table 3) coincide fairly well with the theoretical values for the




Fig. 4. Titration of a mixture of 0.0634 N  $[\text{Fe}(\text{CN})_6]^{4-}$  and 0.0816 N  $\text{Hg}_2^{2+}$  in presence of 0.815 N  $\text{H}_2\text{SO}_4$  and 0.857 N NaF.

A - 0.002786 N  $[\text{Fe}(\text{CN})_6]^{4-}$  and 0.006628 N  $\text{Hg}_2^{2+}$ ;  
B - 0.00646 N  $[\text{Fe}(\text{CN})_6]^{4-}$  and 0.006628 N  $\text{Hg}_2^{2+}$ ;  
C - 0.00549 N  $[\text{Fe}(\text{CN})_6]^{4-}$  and 0.008264 N  $\text{Hg}_2^{2+}$ .

different mixtures titrated. The mechanism of the reaction is confirmed by comparing the titration curve of the mixture with the titration curves of the separate constituents.

#### Titration of a mixture containing ferrous iron and potassium ferrocyanide :

The titration curves of this mixtures (Fig. 5) show two inflections. The first step as gathered from the redox potential of the two systems involved amounting to 150 and 260 mV, respectively, indicates oxidation of ferrocyanide whereby  $\text{MnO}_4^-$  is reduced to  $\text{Mn(II)}$ . The inflection involves oxidation of both ferrous iron and the manganous manganese produced in the first step. These speculations are confirmed by the coincidence of the end point with the theoretical and comparison of the curves of the mixture with those of the separate constituents. The data in Table 4 are in conformity with these facts.

Contrary to expectations, ferrous iron did not produce a step corresponding to the reduction of

TABLE 2—TITRATION OF 0.0457 N  $\text{Fe}^{2+}$  SOLUTION AND 0.0816 N  $\text{Hg}_2^{2+}$  SOLUTION WITH 0.0923 N  $\text{KMnO}_4$  IN PRESENCE OF 0.857 M NaF

Mixture	$\text{H}_2\text{SO}_4$ 9 N (ml)	Theoretical end point (ml)				Exp. end point (ml)		Error %		Max. inflec (mV/ 0.05 ml)		Formal redox potential (V)	
		$\text{Fe}^{2+}$		$\text{Hg}_2^{2+}$		1st	2nd	1st	2nd	1st	2nd	$\text{Fe}^{2+}/\text{Fe}^{3+}$	$\text{Mn}^{2+}/\text{Mn}^{3+}$
		$\text{Mn}^{2+}$	$\text{Mn}^{3+}$	$\text{Mn}^{2+}$	$\text{Mn}^{3+}$	Inflection		Inflection		Inflection		system	system
4 ml $\text{Fe}^{2+}$	2.5	2.06	2.57	7.08	8.85	2.07	11.45	+0.48	+0.96	23	190	0.747	0.864
8 ml $\text{Hg}_2^{2+}$	10.0	2.06	2.57	7.08	8.85	2.05	11.99	-0.48	-0.96	22	195	0.802	0.939
8 ml $\text{Fe}^{2+}$	2.5	4.12	5.14	7.08	8.85	4.10	18.96	-0.24	-0.96	30	175	0.788	0.850
8 ml $\text{Hg}_2^{2+}$	10.0	4.12	5.14	7.08	8.85	4.09	18.99	-0.78	-0.43	28	230	0.742	0.877
8 ml $\text{Fe}^{2+}$	2.5	4.12	5.14	8.54	4.34	4.10	9.56	-0.49	+0.84	28	170	0.732	0.837
4 ml $\text{Hg}_2^{2+}$	10.0	4.12	5.14	3.54	4.34	4.08	9.55	-0.97	+0.74	35	180	0.707	0.908
8 ml $\text{Fe}^{2+}$	2.5	4.12	5.14	—	—	4.10	5.12	-0.24	-0.99	310	25	0.617	1.264
8 ml $\text{Hg}_2^{2+}$	2.5	—	—	7.08	8.85	—	8.99	—	-0.45	—	205	—	0.930 <sup>5</sup>

\*  $\text{Mn}^{2+}/\text{Fe}^{2+}$

\*\*  $\text{Mn}^{2+}$  (total)


§  $\text{Hg(II)}/\text{Hg(I)}$  system

TABLE 3—TITRATION OF MIXTURES OF 0.068 N  $[\text{Fe}(\text{CN})_6]^{4-}$  AND 0.0816 N  $\text{Hg}_2^{2+}$  WITH 0.0922 N  $\text{KMnO}_4$  IN PRESENCE OF 0.857 M  $\text{NaF}$ 

Mixture	$\text{H}_2\text{SO}_4$ 9 N (ml)	Theoretical end point (ml)				Exp. end point (ml)		Error %		Max. inflec. mV/0.05 ml		F. redox pot- ential (V)	
		$[\text{Fe}(\text{CN})_6]^{4-}$		$\text{Hg}_2^{2+}$		1st	2nd	1st	2nd	1st	2nd	$[\text{Fe}(\text{CN})_6]^{4-}$	$\text{Mn}^{2+}$
		$\text{Mn}^{2+}$	$\text{Mn}^{2+}$	$\text{Mn}^{2+}$	$\text{Mn}^{2+}$	Inflection		Inflection		Inflection		$[\text{Fe}(\text{CN})_6]^{4-}$	$\text{Mn}^{2+}$
4 ml $[\text{Fe}(\text{CN})_6]^{4-}$	2.5	3.0	3.78	7.08	8.85	2.98	12.80	-0.87	-0.24	170	50	0.604	1.070
+ 8 ml $\text{Hg}_2^{2+}$	10	"	"	"	"	3.98	12.53	+0.87	-0.87	70	28	0.782	1.182
8 ml $[\text{Fe}(\text{CN})_6]^{4-}$	2.5	6.02	7.51	"	"	5.99	16.4	-0.49	-0.86	162	82	0.550	1.144
+ 8 ml $\text{Hg}_2^{2+}$	10	"	"	"	"	5.97	16.84	-0.88	-0.78	205	88	0.502	1.070
8 ml $[\text{Fe}(\text{CN})_6]^{4-}$	2.5	"	"	9.56	4.45	5.96	11.87	-0.99	+0.75	220	80	0.517	1.072
+ 4 ml $\text{Hg}_2^{2+}$	10	"	"	"	"	6.01	11.98	-0.16	+0.17	218	28	0.546	1.045
8 ml $[\text{Fe}(\text{CN})_6]^{4-}$	2.5	6.02	7.51	"	"	6.08	7.54	+0.16	+0.40	325	38	0.482	1.006
8 ml $\text{Hg}_2^{2+}$	2.5	—	—	7.08	8.85	—	8.91	—	+0.68	—	205	—	0.930 <sup>§</sup>
* $\text{Mn}^{2+}/\text{Fe}^{3+}$		** $\text{Mn}^{2+}$ (total)				§ $\text{Hg}(\text{II})/\text{Hg}(\text{I})$ system							

TABLE 4—TITRATION OF MIXTURE OF 0.0684 N  $[\text{Fe}(\text{CN})_6]^{4-}$  AND 0.0457 N  $\text{Fe}^{2+}$  WITH 0.0922 N  $\text{KMnO}_4$  IN PRESENCE OF 0.857 M  $\text{NaF}$ 

Mixture	$\text{H}_2\text{SO}_4$ 9 N (ml)	Theoretical end point (ml)				Exp. end point (ml)		Error %		Inflection mV/0.05 ml		F. redox pot- ential (V)	
		$\text{FeSO}_4$		$[\text{Fe}(\text{CN})_6]^{4-}$		1st	2nd	1st	2nd	1st	2nd	$[\text{Fe}(\text{CN})_6]^{4-}$	$\text{Mn}^{2+}$
		$\text{Mn}^{2+}$	$\text{Mn}^{2+}$	$\text{Mn}^{2+}$	$\text{Mn}^{2+}$	Inflection		Inflection		Inflection		$[\text{Fe}(\text{CN})_6]^{4-}$	$\text{Mn}^{2+}$
4 ml $\text{Fe}^{2+}$	0.5	2.06	2.57	6.02	7.51	5.97	10.0	-0.85	-0.79	150	30	0.486	1.01
8 ml $[\text{Fe}(\text{CN})_6]^{4-}$	3.5	2.06	2.57	6.02	7.51	6.00	10.05	-0.84	-0.29	220	40	0.457	1.076
8 ml $\text{Fe}^{2+}$	0.5	4.12	5.15	6.02	7.51	5.99	12.6	-0.51	-0.47	238	45	0.492	1.019
8 ml $[\text{Fe}(\text{CN})_6]^{4-}$	3.5	4.12	5.15	6.02	7.51	6.0	12.55	-0.84	-0.87	255	40	0.446	1.067
8 ml $\text{Fe}^{2+}$	0.5	4.12	5.15	8.0	9.78	3.02	8.90	-0.67	-0.94	260	85	0.398	1.084
4 ml $[\text{Fe}(\text{CN})_6]^{4-}$	3.5	4.12	5.15	3.0	3.78	3.01	8.89	-0.88	-0.45	375	80	0.445	1.082
8 ml $\text{Fe}^{2+}$	0.5	4.12	5.15	6.02	7.51	6.0	12.6	-0.84	-0.48	287	40	0.397	0.998
8 ml $[\text{Fe}(\text{CN})_6]^{4-}$	1.0	4.12	5.15	6.02	7.51	5.99	12.58	-0.51	-0.64	239	38	0.417	1.007
	2.5	4.12	5.15	6.02	7.51	6.0	12.66	-0.84	-0.80	240	40	0.418	1.044
	5.0	4.12	5.15	6.02	7.51	5.97	12.55	-0.85	-0.88	240	38	0.427	1.107
	10.0	4.12	5.15	6.02	7.51	5.98	12.53	-0.68	-1.04	242	36	0.467	1.129
8 ml $[\text{Fe}(\text{CN})_6]^{4-}$	0.5	—	—	6.02	7.51	6.01	7.50	-0.17	-0.13	295	30	0.482	1.109
8 ml $\text{Fe}^{2+}$	0.5	4.12	5.15	—	—	4.09	5.12	-0.72	-0.58	310	25	0.612 <sup>§</sup>	1.252
* $\text{Mn}^{2+}/[\text{Fe}(\text{CN})_6]^{4-}$		** $\text{Mn}^{2+}$ (total)				§ $\text{Fe}(\text{III})/\text{Fe}(\text{II})$ system							

Fig. 5. Titration of 0.0684 N  $[\text{Fe}(\text{CN})_6]^{4-}$  and 0.0457 N  $\text{Fe}^{2+}$  with 0.0922 N  $\text{KMnO}_4$  in presence of 0.816 N  $\text{H}_2\text{SO}_4$  and 0.857 N  $\text{NaF}$ .

A—0.000828 N  $\text{Fe}^{2+}$  and 0.00543 N  $[\text{Fe}(\text{CN})_6]^{4-}$ ,  
 B—0.001656 N  $\text{Fe}^{2+}$  and 0.00543 N  $[\text{Fe}(\text{CN})_6]^{4-}$  and  
 C—0.001656 N  $\text{Fe}^{2+}$  and 0.00278 N  $[\text{Fe}(\text{CN})_6]^{4-}$ .

$\text{MnO}_4^-$  to  $\text{Mn}(\text{II})$  state as occurs with pure ferrous solution, inspite of the relatively low potential of

the  $\text{Fe}(\text{III})/\text{Fe}(\text{II})$  system. The potential corresponding to the second step amounts to 1 volt, a value very close to that of the  $\text{Mn}(\text{III})/\text{Mn}(\text{II})$  couple. The absence of a step corresponding to  $\text{Fe}(\text{III})/\text{Fe}(\text{II})$  system can be explained by the interaction of the formed ferricyanide with the ferrous iron present to form Turnbull's blue. The latter apparently undergoes oxidation at a relatively higher potential than that of the ferric/ferrous system.

#### References

1. E. J. DE BURE and A. M. HJORT, *Ind. Eng. Chem., Anal. Ed.*, 1935, 7, 120.
2. I. M. KOLTHOFF, *Rec. Trav. Chim.*, 1939, 41, 52, 343.
3. I. M. ISSA and A. A. ABDUL AZIZ, *Analytical Chem. Acta*, 1958, 14, 224.
4. I. M. ISSA, A. S. MISSAW, M. H. HAMDY, *Microchem. J.*, 1972, 17, 604.
5. A. M. HAMMAM and I. M. ISSA, *Bull. Fac. Sci., Assiut Univ.*, 1974, 3, 209.
6. W. M. LATIMER, "The Oxidation State of Elements", Prentice Hall Inc., N. Y., 1953, p. 288.
7. I. M. KOLTHOFF and N. H. FURMAN, "Potentiometric Titrations", John Wiley and Sons Inc., N. Y., 1947, p. 264.



## Methylation of Phenol over Alumina in the Vapour Phase : Influence of Copper Sulphate

V. KRISHNASAMY\*, T. V. SUBRAMANIAM and S. SOUNDARARAJAN

A. O. College of Technology, Anna University, Guindy, Madras-600 026

Manuscript received 17 March 1980, revised 21 January 1982, accepted 25 August 1982

Phenol is methylated using methanol over alumina and alumina impregnated with varying amounts of copper sulphate at 360, 400 and 440°, at a molar ratio of 0.75 : 1 of phenol to methanol. Over alumina, phenol undergoes direct nuclear (carbon) methylation, giving cresols and xylenols. Alumina with 10 and 20% copper sulphate catalyses both carbon and oxygen methylation forming cresols and anisole, respectively. Xylenols, which were absent over the above two catalysts, appear when the copper sulphate concentration increases to 30%. Further increase of copper sulphate from 30 to 40% not only enhances the proportion of xylenols in the products by increasing the temperature and the contact time, but also decreases that of anisole under these conditions. However, the concentration of cresols seems to be unaffected. Methylation of phenol follows a first order kinetics irrespective of the concentration of copper sulphate in the catalysts.

ALKYLATION is an important unit process widely employed in chemical industries for introducing alkyl groups into other substances notably in hydrocarbons and hydroxy compounds of the aromatic series. Among the alkylation reactions, methylation of phenol has got great industrial importance, as methyl phenols are largely used as chemical intermediates for the production of valuable industrial products. Most of the work done on methylation of phenol is patented<sup>1-3</sup>. Consequently, very little information regarding these investigations is available. Others, who studied this reaction, used high acidic alumina<sup>4-6</sup>, zeolite<sup>7</sup> and silica-alumina<sup>8</sup>, with a view to get more of *m*-cresol, probably on account of its importance as a raw material for perfumes. Kotanigawa<sup>9-11</sup> and co-workers investigated extensively the methylation of phenol using  $\text{Fe}_2\text{O}_3$  catalyst impregnated with various metallic oxides and observed that  $\text{Fe}_2\text{O}_3$  -  $\text{CuO}$  was the most effective combination for selective methylation of phenol at the *ortho* position to get 2,6-xylenol. It has been reported recently<sup>12</sup> that alumina doped with copper sulphate suppresses the formation of xylenols and the product composition consists of a mixture of anisole and cresols. In the present investigation, alumina-copper sulphate has been employed to study the methylation of phenol in detail and to obtain the kinetic parameters.

### Experimental

#### Preparation of materials :

**Alumina A :** Alumina was prepared by hydrolysing aluminium isopropoxide (B.D.H., A.R.) with distilled water. The precipitated aluminium hydroxide was filtered, washed thoroughly, cut into cakes, dried at 120° for 24 hr and activated at 500° in a stream of dry air for another 24 hr. The activated samples were sieved (85-120 mesh) and a part

of it was mixed with 0.5% analytical grade stearic acid binder and made into cylindrical pellets of 0.5 cm diam and 4 mm height and the rest was used as support for copper sulphate.

Catalysts B, C, D and E were obtained by impregnating alumina A with appropriate amounts of copper sulphate (B.D.H., A.R.) solution in water to give respectively 10, 20, 30 and 40% by weight of copper sulphate. Catalysts B, C, D and E were made into pellets of the same size mentioned above. Prior to each run the catalyst was kept at 500° for 8 hr in an atmosphere of pure dry oxygen until no oxides of carbon was detected in the exit gas. After use, it was found that the copper sulphate remained unaffected.

Phenol used was of B.D.H., AnalaR grade and used as such. Methanol (B.D.H., L.R.) was purified further by fractionation. The purity of reactants was checked by gas chromatography.

#### Apparatus and procedure :

The reactions were carried out at atmospheric pressure in a fixed bed flow type reactor. The experimental set-up is shown in Fig. 1, which consists of (i) a constant flow bottle, (ii) preheater-vapourizer, (iii) a capillary flow meter for metering the feed, (iv) tubular reactor and (v) condenser and receiver.

The mixed feed was passed through a capillary tube flow meter which was calibrated earlier using the actual reactant mixtures. The feed enters the preheater-vapourizer (15 cm long and 1.2 cm internal diam) maintained at 220° through a micro feeder for conversion into vapour before entering the reactor. The catalyst (6.36 g) was kept in a Pyrex glass reactor tube (1.5 cm internal diam and 20 cm long). Pyrex glass beads (4 mm diam) were placed above the catalyst bed to a height of 3 cm. A vertical




Fig. 1. Experimental set-up

thermowell is provided for inserting thermocouple to measure the temperature of the catalyst bed. The reaction products were passed through a condenser and collected in a receiver kept in ice. Both the preheater and the reactor were heated on the outside by a uniformly wound nichrome wire, whose length had been predetermined to give the requisite temperature. This was then lagged by means of asbestos cords and magnesia powder to prevent loss of heat. The energy input is controlled by a 8 A dimmerstat. The temperature of the catalyst bed is indicated by a Pt-Pt-Rh thermocouple connected to a temperature controller-cum-indicator.

The liquid products collected for the first 15 min of each run of 45 min duration were discarded, and the products collected after this period were analysed. This was done to ensure the attainment of steady state for the reaction over the catalyst, and also to eliminate temperature fluctuations, if any, due to the starting of the reaction. The catalyst was regenerated after the reaction. Runs were repeated to check the reproducibility of the results.

The liquid products of methylation of phenol were identified and estimated using a one meter

column of Apiezon-L in a gas chromatograph (Model NCL-AIMIL MK II B) with Flame Ionization Detector. The optimum condition for the best resolution within a reasonable time was found to be : column temperature 130°, FID temperature 225°, nitrogen inlet pressure of 15 psi with hydrogen as fuel.

For the identification of different peaks in a chromatogram, retention times for the different compounds were obtained by introducing pure substances. For quantitative estimation, synthetic mixtures containing the different compounds in varying known proportions were introduced and calibration curves relating the concentration with peak area were drawn<sup>1,2-14</sup>.

### Results and Discussion

The thermodynamic feasibility of methylation of phenol to cresols had been ascertained by calculating the free energy change of the reaction by Van Krevelan's method using the equation,

$$F_T = A + BT$$

where A and B are constants of the equation. Using standard values<sup>15</sup> for the constants A and B, the change in free energy for the reaction at 600, 650 and 700°K were calculated and the values are found to be -17.37, -17.33 and -17.07 kcal/mole, respectively, indicating that methylation of phenol is quite feasible within the temperature range given above. Three contact times, namely, 17.05, 23.44 and 37.50 hr were chosen by trial and error methods. The reactions were carried out at 360, 400 and 440° and the molar ratio of phenol to methanol was kept constant at 0.75 : 1 throughout the investigation. The above temperatures were chosen because the conversion was found to be low below 360° and the phenols may decompose to benzene, toluene and xylene above 440°.

Increase of both contact time (Table 1; Fig. 2) and temperature (Table 2; Fig. 3) enhances the conversion of phenol over each catalyst but the enhancement is found not to be linear. The concentration of alkyl phenols in the product increased

TABLE 1—EFFECT OF CONTACT TIME ON PRODUCT DISTRIBUTION IN MOLES AT 400°

Catalyst	Contact time in hr	Anisole formed	Cresol formed	Xylenol formed	Phenol unreacted
A	17.05	—	0.6280	0.1642	0.2128
	23.44	—	0.7414	0.1880	0.0706
	37.50	—	0.7268	0.1446	0.1291
B	17.05	0.4995	0.3715	—	0.1290
	23.44	0.5010	0.3800	—	0.1190
	37.50	0.4982	0.3990	—	0.1028
C	17.05	0.3211	0.5881	—	0.0876
	23.44	0.3210	0.5900	—	0.0890
	37.50	0.3185	0.6118	—	0.0697
D	17.05	0.2020	0.6880	—	0.1600
	23.44	0.3180	0.6400	—	0.1420
	37.50	0.3100	0.6580	0.0530	0.0800
E	17.05	0.0400	0.5828	0.2503	0.1375
	23.44	0.0458	0.5900	0.2760	0.0887
	37.50	0.0524	0.6100	0.2800	0.0578




Fig. 2. Effect of contact time on product distribution at 400° over catalyst E.




Fig. 3. Effect of temperature on product distribution at a contact time of 37.5 hr over catalyst E.

with increase of these two parameters over each catalyst while the proportion of anisole went down under these conditions. The effect of copper sulphate on the distribution of products depended mainly on its concentration in the catalyst (Tables 1 and 2; Fig. 4).

Over alumina (catalyst A), anisole was absent, cresols were formed to a maximum extent of 0.74 mole per mole of phenol reacted along with a sizable amount of xylenols. The absence of anisole

TABLE 2—EFFECT OF TEMPERATURE ON PRODUCT DISTRIBUTION IN MOLES AT CONTACT TIME 37.5 HR.

Catalyst	Temp °C	Anisole formed	Cresol formed	Xylenol formed	Phenol unreacted
A	360	—	0.5264	0.0698	0.4038
	400	—	0.7268	0.1446	0.1291
	440	—	—	—	—
B	360	0.4523	0.3911	—	0.1566
	400	0.4983	0.3990	—	0.1028
	440	0.4012	0.4607	0.0520	0.0960
C	360	0.3018	0.5014	—	0.1968
	400	0.3185	0.6118	—	0.0697
	440	0.3012	0.6581	0.0580	0.0377
D	360	0.2016	0.6053	0.0488	0.1443
	400	0.2100	0.6580	0.0520	0.0800
	440	0.1200	0.7604	0.0985	0.0311
E	360	0.0891	0.5000	0.3099	0.1980
	400	0.0524	0.6100	0.2800	0.0576
	440	0.0256	0.6100	0.2800	0.0844




Fig. 4. Effect of copper sulphate on product distribution. Temp. 400°, contact time 37.5 hr.

over this catalyst may be attributed to either (i) direct nuclear methylation of phenol or (ii) rearrangement of anisole, that may be formed, by simultaneous parallel reactions as indicated in the reaction scheme. The complete absence of anisole in the product rules out its formation and subsequent rearrangement to alkyl phenols though this type of rearrangement was observed by Cullaine and Chard<sup>17</sup> over alumina. It may be concluded that over alumina, direct nuclear methylation of phenol occurs.

Impregnation of alumina with 10% copper sulphate (catalyst B) brings about the following changes in the activity pattern of the catalyst. Over this catalyst, anisole is formed to a maximum extent of 0.5 mole while the amount of cresols are reduced considerably with complete elimination of xylenols. The same type of products are formed over catalyst C and also over catalyst D except at high temperature and high contact time (*vide* Tables 1 and 2). In the case of catalyst E, a considerable proportion of xylenols is formed in addition to anisole and cresols.

Unlike over catalyst A, both oxygen and carbon methylations occur simultaneously over catalysts B

to E giving anisole and cresols as suggested in the scheme. With increase in reaction temperature, contact time and copper sulphate concentration in the catalyst, the anisole rearranges to cresols which are further methylated to xlenols, and as a result, C/O ratio increases. The rearrangement of anisole to cresol was confirmed by injecting anisole through catalyst E. The various possible transformations are given in the scheme.




Fig. 5. Effect of copper sulphate on C/O ratio at three temperatures. Contact time 37.5 hr.




Fig. 6. Effect of copper sulphate on C/O ratio at three contact times. Temp. 400°C.

Though the observed data over alumina-copper sulphate agree partly with the report appearing in a chemical weekly<sup>18</sup> that copper sulphate when incorporated with alumina gives a product composi-

tion consisting of anisole and cresols, they do not agree with the observation that copper sulphate suppresses the formation of xlenols. It may be emphasised that not only the proportion of xlenols in the product increases with increase in copper sulphate concentration, the anisole concentration is also reduced drastically (vide Tables 1 and 2).

**Kinetics:** The reaction sequence pertaining to the methylation of phenol, illustrated in the reaction scheme, shows that it involves parallel and consecutive steps simultaneously thereby making the process complex. On account of the complexity of the reaction, the kinetics of the reactant alone is followed by its disappearance with time. A plot of  $-\ln(1-x)$ , (where  $x$  is the mole of phenol reacted) vs contact time (i.e.,  $W/F_{A0}$ , where  $W$  is the weight of the catalyst and  $F_{A0}$  is the flow rate of the reactant mixture/hr) for catalyst E shows a straight line relationship (Fig. 7) indicating that the methylation of phenol follows a first order kinetics. The




Fig. 7. First order plot for catalyst E.

TABLE 8—EFFECT OF TEMPERATURE ON C/O RATIO (CARBON METHYLATION / OXYGEN METHYLATION)

Catalyst	Temp. °C	C/O ratio 17.05 hr	C/O ratio 23.44 hr	C/O ratio 37.50 hr
B	360	1.0060	0.9594	0.8849
	400	0.7488	0.7588	0.8010
	440	1.0800	1.1050	1.2528
C	360	1.8000	1.8440	1.6000
	400	1.8000	1.8880	1.9900
	440	2.6000	2.6000	2.7180
D	360	8.0500	2.9900	3.9440
	400	3.2700	3.2100	3.6900
	440	7.9400	10.2700	7.1560
E	360	5.5100	8.1500	8.7700
	400	20.5500	18.3100	16.4900
	440	56.0000	68.7600	84.7500





Fig. 8. Arrhenius plot for catalyst E.



log of rate constants was plotted against the reciprocal of absolute temperature for catalyst E (Fig. 8). The activation energies, calculated from the slopes of the Arrhenius plots of all the catalysts, are shown in Table 4.

TABLE 4—EVALUATION OF REACTION RATE CONSTANTS

Catalyst	Rate constant $k$ ( $\text{hr}^{-1}$ )			Energy of activation kcal/mole
	$k_{350}$	$k_{400}$	$k_{440}$	
A	—	—	—	7.60
B	0.0095	0.0125	0.0180	7.20
C	0.0120	0.0170	0.0240	6.98
D	0.0160	0.0270	0.0340	6.60
E	0.0220	0.0340	0.0520	6.40

## References

1. OSCAR HINSHERG, *Ger. Patent*, 538, 376, Dec. 11, 1930, *Chem. Abs.*, 1932, 26, p. 1617.
2. F. J. BOWA and G. F. HENNING, *J. Chem. Soc.*, 1935, 709.
3. W. C. OFFUT, *U. S. Patent*, 2684889, July 20, 1954.
4. L. F. ALBRIGHT and E. N. SHREVE, *Ind. Engg. Chem.*, 1956, 48, 1551.
5. VRELLING, GUNTER, HULTNER and RUDOLF (Union Rheinische Braunkohlen Kraftstoff A. G.) *Chem. Abs.* 1960, 70, 37457a.
6. R. NORRIS SHREVE, *Chem. Abs.*, 1968, 68, 59279c.
7. *Chem. Abs.*, 1966, 65, 2178c, [General Elec. Co. Neth., Appl. 6,506,880 (cl. c. 07c), Nov. 30 1965, U. S. Appl., May 29, 1964].
8. Coal Tar Research Assoc. (by JOHN A. SHARP and RAYMOND E. DEAN), *Chem. Abs.*, 1967, 67, 32401a.
9. T. KOTANIGAWA, M. YAMAMOTO, K. SHIMOKAWA and Y. YOSHIDA, *Bull. Chem. Soc. Japan*, 1971, 44, 1961.
10. T. KOTANIGAWA, and K. SHIMOKAWA, *Bull. Chem. Soc. Japan*, 1974, 47(b), 1585.
11. T. KOTANIGAWA, *Bull. Chem. Soc. Japan*, 1974, 47, 2466.
12. Annual Report 1975-76 of the Regional Research Laboratory, Hyderabad, *Chemical Weekly*, 1977, 23, 72.
13. A. DERWEILDT, *J. Chromatography*, 1961, 5, 98.
14. L. CANDAL-BISCH, *J. Chem. Educ.*, 1964, 41, 4285.
15. FRETTON, "A Guide to Analysis of Phenols", Poly Science Corporation.
16. R. C. REID and T. K. SHERRWOOD, "Properties of Liquids and Gases", McGraw Hill, New York, 1958.
17. N. M. CULLINAN and S. J. CHARD, *J. Chem. Soc.*, 1945, 821.

# Studies in Fluorinated 1,3-Diketones and Related Compounds. Part—XIV : Search for New NMR Shift Reagents

KRISHNA C. JOSHI\*, VIJAI N. PATHAK and (Miss) VINETA GROVER

Department of Chemistry, University of Rajasthan, Jaipur-302 004

Manuscript received 27 April 1981, revised 21 December 1981, accepted 25 August 1982

New fluorinated europium 1,3-diketones have been synthesised and characterized by ir,  $^1\text{H}$ -nmr and  $^{19}\text{F}$ -nmr spectral studies as possible nmr shift reagents and the shifts produced with *n*-hexanol, *n*-heptanol, *p*-fluoroaniline and *m*-trifluoromethylaniline have been studied.

$^1\text{H}$ -NMR spectra of simple organic molecules are not complicated as the resonances do not overlap at easily accessible field strengths but in the spectra of complex molecules, many resonances do overlap and important structural information may be lost.

Hinckley<sup>1</sup>, in 1969, reported the potential of rare earth chelates as nmr shift reagents and described the successful applications of lanthanide shift reagents to a wide range of structural problems. Horrocks<sup>2</sup> tested several  $\text{Ln}(\text{thd})_3$  reagents, some of which caused still greater shifts than the classical Eu and Pr chelates.

A number of similar reagents, e.g. *tris* (dibenzoylmethanate) and *tris* (benzoylacetonates), were also reported but did not appear to offer any particular advantage over the dipivaloylmethanates. Subsequently, Feibush *et al*<sup>3</sup> reported fluorinated lanthanide shift reagents. These reagents proved

to be superior to their non-fluorinated analogues as they provide improved solubility due to perfluoroalkyl groups and the presence of fluorine atoms on the ligands confers higher Lewis acidity on the lanthanide. This higher acidity makes it a more versatile shift reagent for general applications.

Our recent interest in the chemistry of fluorinated 1,3-diketones prompted us to examine some new fluorinated 1,3-diketoneeuropium chelates as possible nmr shift reagents and thus add to the variety of useful lanthanide shift reagents. For this purpose, we have selected [4,4,5,5,6,6,6-heptafluoro-1-(4'-fluorophenyl)-1,3-hexanedionato]europium(III) [(hfh)<sub>3</sub>Eu] and [4,4,5,5,5-pentafluoro-1-(4'-fluorophenyl)-1,3-pentanedionato] europium(III) [(pfp)<sub>3</sub>Eu], synthesized by us earlier<sup>4</sup>, as possible nmr shift reagents and have studied the shifts produced with *n*-hexanol, *n*-heptanol, *p*-fluoroaniline and *m*-trifluoromethylaniline using a 60 MHz spectrometer model RB-12.

TABLE 1—SHIFT STUDIES OF *n*-HEXANOL, *n*-HEPTANOL, *p*-FLUOROANILINE, *m*-TRIFLUOROMETHYLANILINE BY  $\text{Eu}(\text{pfp})_3$  AND  $\text{Eu}(\text{hfh})_3$  IN  $\text{CDCl}_3$  (1 ml)

Sl. No.	Shift reagent	Nucleophile	Ratio of Shift : Nucleophile (in mg)	Time in hr	Position of different signals in $\delta$ ppm				
					-OH	-OH, attached to OH	$(\text{OH})_2/(\text{OH})_1$	$\text{OH}_2$	-NH <sub>2</sub> , -Aromatic protons
1.	$\text{Eu}(\text{pfp})_3$	<i>n</i> -heptanol	Control	1	4.25	3.55	1.4	0.9	
2.	$\text{Eu}(\text{pfp})_3$	<i>n</i> -heptanol	6 : 1	2	3.5	3.60	1.3	0.85	
3.	$\text{Eu}(\text{pfp})_3$	<i>n</i> -heptanol	6 : 1	3.5	3.7	3.65	1.35	0.9	
4.	$\text{Eu}(\text{pfp})_3$	<i>n</i> -heptanol	6 : 1	24	3.9	3.65	1.35	0.9	
5.	$\text{Eu}(\text{pfp})_3$	<i>n</i> -hexanol	Control	1	4.45	3.55	1.4	0.9	
6.	$\text{Eu}(\text{pfp})_3$	<i>n</i> -hexanol	5 : 1	2	4.0	4.2	1.4	0.9	
7.	$\text{Eu}(\text{pfp})_3$	<i>n</i> -hexanol	5 : 1	24	3.9	4.0	1.3	0.85	
8.	$\text{Eu}(\text{hfh})_3$	<i>n</i> -heptanol	Control	1	4.25	3.55	1.4	0.9	
9.	$\text{Eu}(\text{hfh})_3$	<i>n</i> -heptanol	6 : 1	1.5	4.15	3.5	1.25	0.85	
10.	$\text{Eu}(\text{hfh})_3$	<i>n</i> -heptanol	8 : 1	2	4.35	3.45	1.20	0.75	
11.	$\text{Eu}(\text{hfh})_3$	<i>n</i> -heptanol	2 : 1	70	4.65	3.6	1.35	0.95	
12.	$\text{Eu}(\text{hfh})_3$	<i>n</i> -hexanol	Control	1	4.45	3.55	1.4	0.9	
13.	$\text{Eu}(\text{hfh})_3$	<i>n</i> -hexanol	5 : 1	2.5	3.15	3.5	1.3	0.85	
14.	$\text{Eu}(\text{hfh})_3$	<i>n</i> -hexanol	5 : 1	60	3.45	3.5	1.3	0.85	
15.	$\text{Eu}(\text{pfp})_3$	<i>p</i> -fluoroaniline	Control	1					3.5
16.	$\text{Eu}(\text{pfp})_3$	<i>p</i> -fluoroaniline	3 : 1	1					5.9
17.	$\text{Eu}(\text{pfp})_3$	<i>m</i> -trifluoromethylaniline	Control	1					3.85
18.	$\text{Eu}(\text{pfp})_3$	" "	4 : 1	1					5.15
19.	$\text{Eu}(\text{pfp})_3$	" "	2 : 1	1.5					5.0
20.	$\text{Eu}(\text{pfp})_3$	" "	2 : 1	45					5.15

### Experimental

**Synthesis of polyfluorinated 1,3-diketones :** These polyfluorinated 1,3-diketones have already been reported by us<sup>4,5</sup>.

**Europtum 1,3-diketonates :** EuCl<sub>3</sub> (0.004 mole), dissolved in a minimal amount of methanol, was added dropwise to a methanolic solution of  $\beta$ -diketonatoenolate anion (0.012 mole). The complex was precipitated by slow addition of water to the resulting methanolic solution. The precipitated europium 1,3-diketonates were crystallized from benzene and dried in vacuum, over phosphorus pentaoxide, for 24 hr<sup>6</sup>.

### Results and Discussion

The substrate associates with the complex at the hydroxyl group (*n*-hexanol, *n*-heptanol) or the amino group (*p*-fluoroaniline or *m*-trifluoromethyl-aniline) and the induced shifts decrease rapidly

with increasing distance of protons from the hydroxyl group. The results are tabulated in Table 1.

### Acknowledgement

The authors are thankful to C. S. I. R., New Delhi, for the award of a Fellowship to one of them (V. G).

### References

1. C. C. HINCKLEY, *J. Amer. Chem. Soc.*, 1969, **91**, 5160.
2. J. P. HORROCKS, *J. Amer. Chem. Soc.*, 1973, **95**, 2920.
3. B. FEIBUSH, M. F. RICHARDSON, R. E. SIEVERS and C. S. SPRINGER, JR., *J. Amer. Chem. Soc.*, 1972, **94**, 6717.
4. K. C. JOSHI, V. N. PATHAK and V. GROVER, *J. Fluorine Chem.*, 1980, **15**, 245.
5. K. C. JOSHI, V. N. PATHAK and V. GROVER, *J. Fluorine Chem.*, 1981, **17**, 555.
6. K. C. JOSHI, V. N. PATHAK and V. GROVER, *J. Fluorine Chem.*, 1979, **13**, 961.

# Synthesis of Some New Benzimidazoles as Antiamoebic Agents

VINAY S. MISRA\*, PRAMILA SHAH and V. K. SAXENA

Department of Chemistry, University of Lucknow, Lucknow-226 007

Manuscript received 31 July 1981, revised 6 December 1981, accepted 7 June 1982

Fourteen new substituted 1'-acetyl [3N-aminomethyl substituted quinazolinol]-2'-alkyl substituted phthalamido benzimidazoles have been synthesised and their effect on the axenic culture of *Entamoeba histolytica* have been studied *in vitro* at 125 µg/ml. Some of them have shown significant antiamoebic activity.

**T**HE discovery and success of metronidazole (2-methyl-5-nitro-1-ethanol imidazole) as a potent amoebicidal agent stimulated research in imidazole chemistry. A number of compounds of this category have been synthesised and tested for various therapeutic effects<sup>1-3</sup>. Some nitro imidazoles<sup>4-7</sup> have been shown to possess marked amoebicidal and trichomonocidal activity. A lot of work has also been done with the benzimidazole moiety as benzimidazoles have shown significant antibacterial, antiviral and antifungal activity<sup>8,9</sup>. This prompted us to synthesise some substituted benzimidazoles and screen them for amoebicidal activity.

## Experimental

Melting points of the compounds synthesised were determined in open capillary tubes. Infrared spectra were taken on a Perkin-Elmer 157 spectrophotometer in KBr pellets. NMR spectra were taken on Perkin-Elmer model R32 at a frequency of 90 MHz. TLC was carried out by using silica-gel coated glass plates of 2 mm thickness, using benzene-methanol (10 : 1) as the solvent.

**Infrared spectra :** The infrared spectra of the compounds in Tables 1, 2 and 3 show sharp peaks at 3000-3400 cm<sup>-1</sup> (-NH), 1700 cm<sup>-1</sup> (-C(=O)-NH)

and 1500 cm<sup>-1</sup> (-NO<sub>2</sub>).

**NMR spectra (DMSO-d<sub>6</sub>) :** These benzimidazoles gave a singlet at δ 2.26 for N-CH<sub>3</sub>-N, singlet at δ 4.28 for N-CH<sub>2</sub>-C and multiplet between

δ 6.24-δ 8.38 for the aromatic protons.

The identity of the compounds was further confirmed by their melting points and elemental analysis, while the purity was ascertained by thin layer chromatography.

**2-Alkyl substituted benzimidazoles :** These were prepared by the method of Cescon and Day<sup>10</sup>.

**3-Nitro phthalic anhydride :** This was synthesised by the method given in Vogel<sup>11</sup>.

**Substituted 3-N-aminomethyl 4(3H)quinazolones :** The method of Mukerji and Nautiyal<sup>12</sup> was followed for the synthesis of these quinazolones.

**2-[Phthalamido-alkyl]-benzimidazoles (a) :** 2-Alkyl-substituted benzimidazole (0.01 mole), 3-nitro phthalic anhydride (0.01 mole) and dry pyridine (7 ml) were refluxed together for 5-6 hr on a sand bath. The reaction mixture, after cooling, was poured into ice-cold water containing a few drops of conc. HCl. The precipitate was filtered, washed with cold water, dried and crystallised from ethanol.

Four new 2-[phthalamido-alkyl]-benzimidazoles were thus synthesised (Table 1).

TABLE-1

Sl No	R	R <sub>2</sub>	m.p. °C	Molecular formula
1	CH <sub>3</sub>	H	242	C <sub>18</sub> H <sub>11</sub> N <sub>3</sub> O <sub>4</sub>
2	CH <sub>2</sub> CH <sub>3</sub>	H	264(d)	C <sub>19</sub> H <sub>13</sub> N <sub>3</sub> O <sub>4</sub>
3	CH <sub>2</sub>	8-NO <sub>2</sub>	>275	C <sub>18</sub> H <sub>10</sub> N <sub>3</sub> O <sub>6</sub>
4	CH <sub>2</sub> CH <sub>3</sub>	8-NO <sub>2</sub>	242	C <sub>19</sub> H <sub>11</sub> N <sub>3</sub> O <sub>6</sub>

Yield ranged between 55-60 %

%N within ± 0.8% of the theoretical values.

**3-[N-(Chloroacetyl)-aminomethyl]4(3H)quinazolones (b) :** To substituted 3-N-aminomethyl 4(3H)quinazolinone (0.01 mole)<sup>13</sup>, chloroacetyl chloride (0.01 mole) was added and the mixture refluxed for 2-2½ hr in presence of dry benzene (12 ml). The flask was cooled, excess benzene distilled off, the solid filtered, washed with ice-cold water, dried and recrystallised from methanol.

\* Author: for correspondence.



Four such compounds were prepared (Table 2).

TABLE-2



Sl. No.	R <sub>1</sub>	R <sub>2</sub>	m.p. °C	Molecular formula
1.	H	H	244	C <sub>11</sub> H <sub>10</sub> N <sub>2</sub> O <sub>2</sub> Cl.2HCl
2.	Br	H	268	C <sub>11</sub> H <sub>8</sub> N <sub>2</sub> O <sub>2</sub> ClBr.2HCl
3.	Br	Br	270(d)	C <sub>11</sub> H <sub>6</sub> N <sub>2</sub> O <sub>2</sub> ClBr <sub>2</sub> .2HCl
4.	NO <sub>2</sub>	H	265(d)	C <sub>11</sub> H <sub>8</sub> N <sub>2</sub> O <sub>2</sub> Cl.2HCl

Yield ranged between 65-70%.

% N within  $\pm 0.4\%$  of the theoretical values.

Isolated as hydrochlorides.

**Substituted 3-[N-(1'-acetyl)-aminomethyl]quinazolino-2'-[phthalamido-alkyl] benzimidazoles :** An equimolar mixture of (a) and (b) was refluxed in dry acetone (12 ml) in presence of anhydrous potassium carbonate (0.015 mole) for 3-4 hr. Excess acetone was distilled off and methanol added to the solid residue. The mixture was heated till the reactants dissolved leaving the potassium carbonate behind. Excess methanol was distilled off, the solution cooled and the solid after filtration and drying was recrystallised from methanol. Fourteen such compounds were synthesised (Table 3).



Scheme

#### Pharmacology :

For the evaluation of amoebicidal activity of the compounds, the method of Das *et al*<sup>18</sup> was followed, except for the TPS-1 medium which was kept at pH 6.8 and not 7.2, since acidic pH is favourable for growth of the amoebae.

A three day old culture of *E. histolytica* was used and the final results were obtained after observing under an inverted microscope after 72 hr. Amoebicidal activity was carried out at 125  $\mu$ g/ml. Out of the fourteen compounds screened, three were

TABLE-3

Sl. No.	R	R'	R <sub>1</sub>	R <sub>2</sub>	m.p. °C	Molecular formula	Amoebicidal activity at 125 $\mu$ g/ml
1.	OH <sub>2</sub>	H	H	H	> 275	C <sub>27</sub> H <sub>20</sub> N <sub>4</sub> O <sub>4</sub> .2HCl	NA
2.	OH <sub>2</sub>	H	Br	H	220(d)	C <sub>27</sub> H <sub>18</sub> N <sub>4</sub> O <sub>4</sub> Br.2HCl	NA
3.	OH <sub>2</sub>	H	Br	Br	> 275	C <sub>27</sub> H <sub>16</sub> N <sub>4</sub> O <sub>4</sub> Br <sub>2</sub> .2HCl	NA
4.	OH <sub>2</sub>	H	NO <sub>2</sub>	H	270(d)	C <sub>27</sub> H <sub>18</sub> N <sub>4</sub> O <sub>4</sub> .2HCl	125
5.	OH <sub>2</sub> OH <sub>2</sub>	H	H	H	> 275	C <sub>28</sub> H <sub>22</sub> N <sub>4</sub> O <sub>5</sub> .2HCl	NA
6.	OH <sub>2</sub> OH <sub>2</sub>	H	Br	H	300(d)	C <sub>28</sub> H <sub>20</sub> N <sub>4</sub> O <sub>5</sub> Br.2HCl	NA
7.	OH <sub>2</sub> OH <sub>2</sub>	H	Br	Br	180(d)	C <sub>28</sub> H <sub>18</sub> N <sub>4</sub> O <sub>5</sub> Br <sub>2</sub> .2HCl	NA
8.	OH <sub>2</sub> OH <sub>2</sub>	H	NO <sub>2</sub>	H	> 275	C <sub>28</sub> H <sub>22</sub> N <sub>4</sub> O <sub>5</sub> .2HCl	NA
9.	OH <sub>2</sub>	3-NO <sub>2</sub>	H	H	> 275	C <sub>27</sub> H <sub>18</sub> N <sub>4</sub> O <sub>4</sub> .2HCl	NA
10.	OH <sub>2</sub>	3-NO <sub>2</sub>	Br	Br	285(d)	C <sub>27</sub> H <sub>16</sub> N <sub>4</sub> O <sub>4</sub> Br <sub>2</sub> .2HCl	NA
11.	OH <sub>2</sub>	3-NO <sub>2</sub>	Br	H	278(d)	C <sub>27</sub> H <sub>17</sub> N <sub>4</sub> O <sub>4</sub> Br.2HCl	NA
12.	OH <sub>2</sub>	3-NO <sub>2</sub>	NO <sub>2</sub>	H	270(d)	C <sub>27</sub> H <sub>16</sub> N <sub>4</sub> O <sub>4</sub> .2HCl	125
13.	OH <sub>2</sub> OH <sub>2</sub>	3-NO <sub>2</sub>	H	H	278(d)	C <sub>28</sub> H <sub>22</sub> N <sub>4</sub> O <sub>5</sub> .2HCl	125
14.	OH <sub>2</sub> OH <sub>2</sub>	3-NO <sub>2</sub>	Br	Br	> 275	C <sub>28</sub> H <sub>20</sub> N <sub>4</sub> O <sub>5</sub> Br <sub>2</sub> .2HCl	NA

Yield ranged between 45-50%.

O, H, N ranged within  $\pm 0.4\%$  of the theoretical values.

The compounds were isolated as hydrochlorides.

\*Amoebicidal at 125  $\mu$ g/ml.

NA=Non-amoebicidal.

active at this concentration. Emetine hydrochloride and metronidazole (FLAGYL) were used as the standard drugs, the former was active as 62.5 µg/ml and the latter at 7.8 µg/ml at pH 6.8.

### Results and Discussion

The results of the bioassay show that three compounds are active at 125 µg/ml. All the three compounds, i.e. no. 4, no. 12 and no. 13 (Table 3) have a nitro group either in the quinazolone moiety or in the phthalamido ring. The presence of a bromo group in the quinazolone ring system has not been effective in exhibiting the amoebicidal activity in these compounds. Therefore, the only conclusion that can be drawn from these results is that the nitro group, irrespective of its position is responsible for activity in the compounds.

### Acknowledgement

The authors thank Dr. Nitya Nand, Director, C. D. R. I., for facilities for elemental and spectral screening and Dr. S. K. Gupta, Head, Microbiology Division, Dr. B. N. K. Prasad and Miss Indu Bansal for the bioassay of the compounds. One

of the authors (P. S.) is thankful to C. S. I. R., New Delhi, for a Junior Research Fellowship.

### References

1. P. MELLONI, E. DRADI and W. LONGMANN, *J. Med. Chem.*, 1972, **15**, 926
2. C. COBAN, R. ORISON, R. N. HORCLOIS and J. J. BOBART, *Ant. Forams.*, 1966, **16**, 23
3. R. RAFFER and V. BUNFIE, *J. Med. Chem.*, 1971, **14**, 984
4. ARSO ILVESPAAL, (Ciba Gelgy A-G) Ger. Offen., 2,348,284, (OLCo7d, A61k) 1974, Swiss Appl. 14,481/74, *Chem. Abs.*, 1974, 13515u
5. W. J. RUSS, W. B. JAMINSON and M. O. MCGOWEN, *J. Med. Chem.*, 1978, **16**, 847.
6. M. SHAFER, H. S. JEFFERIES and D. M. RYAN, *Ann. Trop. Med. Parasitol.*, 1972, **66**, 187
7. MAS HOFFER (Hoffman La Roche, F and Co, A-G), S. African, 72 01808 (OLCo9b), U. S. Appl. 193,737, 13 Apr. 1971, 17 pp, *Chem. Abs.*, 1973, 126510r.
8. V. S. MISRA and M. VARSHNEYA, *Indian J. Pharm.*, 1977, **39**, 35.
9. V. J. RAM and H. N. PANDEV, *Agr. Biol. Chem.*, 1978, **37**, 1465.
10. I. A. GESCON and A. B. DAY, *J. Org. Chem.*, 1962, **27**, 581
11. A. I. VOGEL, "A Text Book of Practical Organic Chemistry", E.L.B.S. Longman Group Ltd., 3rd Ed., 1971
12. D. D. MUKERJI and S. R. NAUTIVAI, *J. Indian Chem. Soc.*, 1979, **56**, 1226
13. S. R. DAS and B. N. K. PRASAD, *Curr. Sci.*, 1978, **42**, 796

## Synthesis of $\alpha$ -Amino adipic Acid

NASEEM H. KHAN, MOHD. ALI, H. PANDA and (Miss) RAKHSHINDA\*

Department of Chemistry, Aligarh Muslim University, Aligarh-202 001

Manuscript received 28 December 1981, accepted 21 July 1982

A two-step synthesis of  $\alpha$ -amino adipic acid in quite encouraging yield through reduction and hydrolysis of azlactone of succinic anhydride with hydriodic acid in presence of red phosphorus has been reported.

SEVERAL synthetic schemes for the preparation of  $\alpha$ -amino adipic acid have been reviewed by Greenstein and Winitz<sup>1</sup>. Published methods show that only the azlactones of acetic and phthalic anhydrides have been used for the synthesis of amino acids. Attenburrow and co-workers<sup>2</sup> prepared threonine from 2-phenyl-4-(1-hydroxyethylidene)-5-oxazolone, an azlactone of acetic anhydride. Recently<sup>3</sup>, we have employed 2-phenyl-4-phthalidene-5-oxazolone for the synthesis of  $\beta$ -amino- $\beta$ -(*o*-benzene carboxylic acid) alanine. We now describe the formation of 2-phenyl-4-succinylidene-5-oxazolone and  $\alpha$ -amino adipic acid from this azlactone.

Unlike the analogous preparation of azlactones of carbonyl compounds, reaction of succinic anhydride (1) with hippuric acid (2) gives some other products in addition to the azlactone. Treatment of the anhydride (1) with hippuric acid (2) in presence of fused sodium acetate as a base catalyst and acetic anhydride affords 2-phenyl-4-succinylidene-5-oxazolone (3) as well as benzoic acid (4) and N-acetylglycine (5). This is due to the transformation of hippuric acid into benzoic acid and glycine to some extent by water produced during the course of azlactone formation in the reaction mixture. The liberated glycine reacts with acetic anhydride to yield N-acetylglycine (5). If in this reaction, the sodium acetate is replaced by triethylamine, the rate of hydrolysis is increased and the compounds (4) and (5) are formed in excess.

Condensation of glycine with equimolecular proportion of succinic anhydride in presence of acetic anhydride and fused sodium acetate results in the formation N-acetylglycine (5) and water soluble pigments, when the mixture is warmed for various lengths of time. The compound (5) does not react with succinic anhydride to give 2-methyl-4-succinylidene-5-oxazolone, an analogue of the product (3). If excess of glycine is taken keeping other reaction conditions the same, polymerization takes place and a green fluorescing polymer is obtained.

Subjection of the compound (3) to hydrolysis with hydriodic acid in presence of red phosphorus and glacial acetic acid leads to simultaneous scission of the lactone and oxazolone rings as well as the benzoyl group. The carbon-carbon double bond is also reduced during the hydrolysis. No difficulty is encountered in the isolation of the amino acid (6) from the reaction mixture. After hydrolysis is complete, which takes 2 hr, the contents are filtered and the filtrate is evaporated to dryness under reduced pressure after trituration with solvent ether. In this way the salt of  $\alpha$ -amino adipic acid is obtained which on treatment with ammonia gives the free amino acid (6) in a well crystallized form (Fig. 1).

### Experimental

**Synthesis of 2-phenyl-4-succinylidene-5-oxazolone (3):** An intimate mixture of succinic anhydride (10 g), hippuric acid (17.9 g) and fused sodium acetate (8.4 g) was heated with acetic anhydride (30 ml) on an electric hot plate to obtain a clear solution and then on a steam bath for 2 hr. The reaction mixture was poured in ice-cold water. The gummy product separated was extracted with sodium carbonate solution to remove benzoic acid and then with light petroleum ether (40-60°). The azlactone was obtained on evaporation of the ether. This was purified by a column of alumina using benzene; m.p. 114-15°, yield 4.19 g (16%). Anal. Found: C, 64.49; H, 3.70; N, 5.48. Calcd. for  $C_{12}H_9NO_4$ ; C, 64.20; H, 3.73; N, 5.76%.

The water layer obtained from the above reaction mixture was evaporated to dryness and the residue was dissolved in methanol. On cooling, crystallized product, N-acetylglycine (5), was obtained. This was filtered and dried, m.p. 205-6°, mixed m.p. 205°. Anal. Found: C, 40.79; H, 6.31; N, 12.23. Calcd. for  $C_4H_7NO_2$ ; C, 41.02; H, 6.03; N, 11.96%.

**Synthesis of  $\alpha$ -amino adipic acid (6):** 2-Phenyl-4-succinylidene-5-oxazolone (2 g) was refluxed with

\* Author for correspondence. Present Address: Research Officer, Research & Development Section, The Indian Turpentine & Rosin Co. Ltd., P. O. Clutterbuckganj-248 502, Bareilly.




Fig. 1

a mixture of hydriodic acid<sup>1</sup> (sp. gr. 1.7; 15 ml), glacial acetic acid (10 ml) and red phosphorus (2.5 g) for 2 hr. Unreacted phosphorus was filtered and the filtrate was evaporated to dryness under diminished pressure. The residue was taken up in 20 ml of water and re-evaporated. The residue was again suspended in water (25 ml) and extracted several times with ether to remove benzoic acid. The aqueous layer was neutralized carefully with ammonia solution. The separated amino acid (6) was filtered, washed with ethanol and dried; m.p. 204-5° (lit.<sup>4,5</sup> m.p. 206° and 202°), yield 0.88 g (95%). IR(KBr) 3020, 1900, 1650, 1580, 1500, 1250, 1180 and 760 cm<sup>-1</sup>. Anal. Found: C, 44.52; H, 7.08; N, 8.91. Calcd. for C<sub>8</sub>H<sub>11</sub>NO<sub>4</sub>: C, 44.71; H, 6.88; N, 8.69%.

#### Acknowledgement

The authors are thankful to Prof. W. Rahman, Head of the Department for facilities.

#### References

1. J. P. GREENSTEIN and M. WINITZ, in "Chemistry of the Amino Acids", John Wiley, New York, N. Y., 1961, Vol. 3, p. 2408.
2. J. ATTENBURROW, D. F. ELLIOT and G. F. PANNY, *J. Chem. Soc.*, 1948, 810.
3. M. ALI, N. H. KHAN and A. A. SIDDIQUI, *Synth. Commun.*, 1976, 6, 227.
4. W. DIECKMANN, *Ber.*, 1905, 38, 1659.
5. I. P. WAALKES, W. S. FOWES and J. WHITE, *J. Amer. Chem. Soc.*, 1959, 72, 5760.

## High Content of Cholesterol in the Lipid of *Acacia farnesiana* Leaves\*\*

C. K. ANDHIWAL\* and KAMAL KISHORE

Research Laboratory, Department of Chemistry, S. V. College, Aligarh-202 001

Manuscript received 6 November 1981, accepted 21 July 1982

The lipidic composition of the leaves of *Acacia farnesiana* has been determined using gas liquid chromatographic techniques. The light petroleum extract has been found to contain *n*-alkanes ( $C_{21}$ – $C_{31}$ ) with maximum occurrence of *n*-nonacosane (60%), triacontanol and phytosterols: cholesterol (8.7%), campesterol (21.6%), stigmasterol (37.2%) and sitosterol (32.4%). Occurrence of this relatively large amount of cholesterol (8.7%) in plants is an unique finding.

*ACACIA farnesiana* commonly called 'Vilayati kikar' in Hindi belongs to family "Mimosaceae". The plant is cosmopolitan in tropics. According to *Sushruta's* "Kaharagoda", the plant is one of the ingredients in a preparation for the treatment of snake bite<sup>1</sup>. The tender leaves, bruised in a little water, are swallowed for treatment of gonorrhoea. Only  $\beta$ -diketones and flavones have been isolated from some *Acacia* species<sup>2</sup>. The oil of *Acacia farnesiana* has been analysed by Demole<sup>3</sup>. Considering its medicinal importance and the fact that no systematic work on the leaves of this species has been done so far, a chemical analysis of the leaves was undertaken.

### Experimental

The leaves of *Acacia farnesiana* were collected locally. Air dried leaves (600 g) were extracted thrice with light petroleum (60–80°) at boiling temperature for 36 hr. A dark green solid (4%) was obtained. It was found to be neutral and gave positive Libermann-Burchard test. After usual work-up, the extract was chromatographed over a column of neutral activated alumina (~20 fold excess) and gave different fractions on elution with increasing polarity of the solvent.

**Fraction A:** Elution with hexane and crystallisation from acetone gave a waxy product (22 mg), m.p. 59–61°. It gave a single spot on tlc (silica gel plate impregnated with 2%  $AgNO_3$ ). IR spectrum indicated it to be a long chain aliphatic hydrocarbon. GLC analysis represented the homologous series of *n*-alkanes ( $C_{21}$ – $C_{31}$ ) with maximum occurrence of *n*-nonacosane ( $C_{29}$ ; 60.0%) and *n*-heptacosane ( $C_{27}$ ; 18.0%). Odd numbered homologues predominated only in the higher members (Table 1). Some branched hydrocarbons were also present in traces. The distribution pattern of *n*-alkanes has been found to be of unimodal type<sup>4</sup>.

TABLE 1—COMPOSITION OF *n*-ALKANES

Sl. No	<i>n</i> -Alkanes	Composition <sup>a</sup> %
1.	<i>n</i> -heneicosane $C_{21}H_{44}$	0.2
2.	<i>n</i> -docosane $C_{22}H_{46}$	0.6
3	<i>n</i> -tricosane $C_{23}H_{48}$	0.6
4.	<i>n</i> -tetracosane $C_{24}H_{50}$	0.7
5	<i>n</i> -pentacosane $C_{25}H_{52}$	2.5
6	<i>n</i> -hexacosane $C_{26}H_{54}$	2.7
7	<i>n</i> -heptacosane $C_{27}H_{56}$	18.0
8.	<i>n</i> -octacosane $C_{28}H_{58}$	11.6
9	<i>n</i> -nonacosane $C_{29}H_{60}$	60.0
10	<i>n</i> -triacontane $C_{30}H_{62}$	1.8
11	<i>n</i> -hentriacontane $C_{31}H_{64}$	1.2
12	<i>n</i> -dotriacontane $C_{32}H_{66}$	0.5
13.	<i>n</i> -tritriacontane $C_{33}H_{68}$	traces

<sup>a</sup> According to glc analysis.

**Fraction B:** Further elution of the column with petroleum ether: benzene (1:4 v/v) gave another waxy product, homogeneous on tlc. It was crystallised from methanol (1.754 g), m.p. 85–86°. Its ir spectrum indicated it to be a long chain primary aliphatic alcohol showing prominent peaks at 1060, 3360  $cm^{-1}$ . It was characterised as *n*-triacontanol on the above basis and on comparison with authentic specimen (co-tlc and m.m.p.). Its acetyl derivative<sup>5</sup> had m.p. 68–69° and was identical with the authentic derivative (co-tlc and m.m.p.).

**Fraction C:** The next fraction of sterol was obtained on elution with benzene:chloroform (3:1). It gave positive Libermann-Burchard test and yellow colour with tetranitromethane. This fraction, on crystallisation from methanol, gave shining crystals (130 mg), m.p. 138–40°. This fraction was then acetylated (m.p. 131–32°) in  $Ac_2O$ -pyridine and the identification of each sterol was carried out as the acetates by argentation tlc followed by glc on both OV-1 and OV-17 SCOT glass capillary column. The acetylated sterol mixture was separated into three different zones by argentation tlc having  $R_f$  value of the least polar

\*\* Partly presented in the 68th Session of Indian Science Congress Association, Varanasi, Jan., 1981.

zone 0.87 (zone 1) and the medium polar zone 0.80 (zone 2) while the most polar zone (zone 3) was not evident.

The fraction from zone 1 was a mixture of cholesterol, campesterol and sitosterol. The next fraction from zone 2 consisted mainly of the acetate of stigmasterol. The fraction from zone 3 was shown to contain the acetates of cholesterol, campesterol, sitosterol and stigmasterol which might have resulted from the "tailing" of the components on the argentation tlc. The approximate content of each of the four sterols in the acetylated total sterol fraction as determined by glc on OV-17 column, has been given in Table 2.

TABLE 2—COMPOSITION OF STEROIDS

Sterol acetate	OV-17(%)	RRT*	
		OV-17	OV-1
Cholesterol	8.7	1.00	1.00
Campesterol	21.6	1.29	1.32
Stigmasterol	37.2	1.41	1.44
Sitosterol	32.4	1.61	1.64

\* Retention times of cholesterol acetate 7.93 has been taken to be 1.00.

It is worth mentioning here that the occurrence of relatively larger amount of cholesterol (8.7%) in this plant is an unique finding. Cholesterol is

generally of animal origin, but is widely distributed in higher plants in trace amount<sup>6</sup>.

#### Acknowledgement

The authors are grateful to Dr. S. C. Gupta Principal and Dr. M. Behari, Head of the Chemistry Department, S. V. College, Aligarh, for facilities. Their sincere thanks are due to Dr. Carl Hultmar Gannon University, Erie (USA) for ir spectra and to Prof. Taro Matsumoto for glc analysis. Thanks are also due to U. G. C., New Delhi for the award of a Junior Research Fellowship to one of the authors (K. K.).

#### References

1. K. R. KIRTIKAR and B. D. BASU, "The Indian Medicinal Plants", 1975, Vol 2, p. 920.
2. D. H. S. HORN and J. A. LAMBERTON, *Chem. Ind (London)*, 1962, 2036.
3. DEMOLE *et al.*, *Helv. Chim. Acta*, 1969, **52**, 983.
4. S. HAMILTON and R. J. HAMILTON, *Top. Lipid Chem.*, 1972, **3**, 199.
5. "Dictionary of Organic Compounds", I. M. HEILBRON, H. M. BUNBURY (Eds), Oxford Uni. Press, 1963, 2nd Ed. Vol IV, p. 536.
6. a. C. K. ANDHIWAL, KAMAL KISHORE and J. A. BALLANTINE, *J. Indian Chem. Soc.*, 1980, **57**, 1044.  
b. M. BEHARI and C. K. ANDHIWAL, *Current Sci.*, 1976, **45**, 481.

## Amperometric Estimation of $\text{La}^{3+}$ and $\text{Ce}^{3+}$ with Cupferron using d.m.e.

K. S. PITRE\* and S. C. LAVALLE

Department of Chemistry, University of Sagar, Sagar-470 003

Manuscript received 19 June 1980, revised 29 June 1981, accepted 8 July 1982

Cupferron has been employed as a reagent for the amperometric titrations of  $\text{La}^{3+}$  and  $\text{Ce}^{3+}$  in very dilute solution using d.m.e. Hydrochloric acid ( $\text{pH}=2.75$ ) has been used as supporting electrolyte. These titrations revealed cupferron to metal ratio of 1:1. Titrations are not hampered by the presence of a fairly large amount of  $\text{Li}^+$ ,  $\text{Na}^+$ ,  $\text{K}^+$ ,  $\text{Mg}^{2+}$ ,  $\text{Zn}^{2+}$ ,  $\text{Al}^{3+}$ ,  $\text{Cl}^-$ ,  $\text{Br}^-$ ,  $\text{I}^-$ ,  $\text{NO}_2^-$ ,  $\text{NO}_3^-$ ,  $\text{CH}_3\text{COO}^-$  and  $\text{ClO}_4^-$  ions. Furthermore, micro and ultramicro quantities of  $\text{La}^{3+}$  and  $\text{Ce}^{3+}$  have been successfully determined with an error of less than  $\pm 0.70\%$ .

CUPFERRON, an ammonium salt of N-nitroso-phenyl hydroxylamine [ $\text{C}_6\text{H}_5\text{N}(\text{NO})\text{ONH}_4$ ] was introduced as a precipitant for  $\text{Cu}^{2+}$  and  $\text{Fe}^{3+}$ . The reagent has been successfully used in the determination of metals, such as those belonging to titanium family<sup>1</sup>. Kolthoff and Liberti<sup>2</sup> have amperometrically titrated  $\text{Cu}^{2+}$  ion with cupferron using d.m.e. as an indicator electrode. The amperometric titration of yttrium and some other rare earths using a rotating platinum anode and stationary platinum cathode in an ammoniacal acetate medium of  $\text{pH}$  3.5 to 6, has been reported by Vasilenko<sup>3</sup>. The use of cupferron in the amperometric titrimetry of various other ions e.g.  $\text{Fe}^{3+}$ ,  $\text{Tl}^{3+}$ ,  $\text{Sn}^{4+}$ ,  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$  has been discussed in the literature. No account, however, is available in literature on the use of cupferron as a reagent for amperometric titration of  $\text{La}^{3+}$  and  $\text{Ce}^{3+}$  on a d.m.e.

The results of amperometric titrations of  $\text{La}^{3+}$  and  $\text{Ce}^{3+}$  with cupferron on a d.m.e. at  $\text{pH}=2.75 \pm 0.01$  are reported in the present paper.

### Experimental

Cupferron (B.D.H.) was purified\* by recrystallisation from ethanol. The dried crystals were stored in dark over ammonium carbonate. A fresh solution of this reagent was prepared in air free distilled water before use and the solution was standardised by amperometric titration method<sup>4</sup>.  $\text{La}^{3+}$  and  $\text{Ce}^{3+}$  solutions were prepared by dissolving a calculated amount of  $\text{La}(\text{NO}_3)_3 \cdot 6\text{H}_2\text{O}$  [Riedel] and  $\text{CeCl}_3 \cdot 6\text{H}_2\text{O}$  [Fluka], respectively in the required volume of double distilled water. The solutions were standardised by conventional titrimetric method<sup>5</sup>.

Hydrochloric acid ( $\text{pH}=2.75$ ) was used as a supporting electrolyte for the study of the polarographic behaviour of cupferron and purified nitrogen gas was passed through the solutions before recording the polarograms. A manual polaro-

graphic set up with multiflex galvanometer (sens =  $8.10 \times 10^{-9}$  amp/div) was used for measurement of current. The d.m.e. used in conjunction with S.C.E. had the characteristics  $m=2.45$  mg/sec,  $t=2.5$  sec drop and  $h=43.5$  cm.

For titrations, a number of solutions containing calculated amounts of  $\text{La}^{3+}$  and  $\text{Ce}^{3+}$  (0.005 mM to 0.05 mM) were prepared. The  $\text{pH}$  of these solutions was adjusted at 2.75 with hydrochloric acid. Titrations of these solutions were carried out at an applied voltage of  $-1.20$  volts (vs S.C.E.) using an H-type cell with d.m.e. as an indicator electrode and S.C.E. as reference electrode.

### Results and Discussion

Cupferron gives a well defined cathodic wave in hydrochloric acid<sup>6</sup>. The half wave potential varies with  $\text{pH}$ . The height of the diffusion current is proportional to the concentration of cupferron. The plateau potential of the polarogram for cupferron, i.e.  $-1.20$  V (vs S.C.E.) (at which  $\text{La}^{3+}$  or  $\text{Ce}^{3+}$  do not give any diffusion current) was applied. The metal ion solution in dil. HCl ( $\text{pH}=2.75$ ) was taken in a titration cell and the solution was titrated against cupferron ( $\text{pH}=2.75$ ). After each addition of an aliquot of the titrant the galvanometer reading was noted. On plotting galvanometer reading against the titrant volume a reversed L shape curve was observed (Fig 1). The end point has been located graphically as the point of intersection of the two straight lines. This estimates the metal to cupferron ratio of 1:1 (Tables 1 and 2). The literature, however, records 1:3 stoichiometric ratio of metal ( $\text{La}^{3+}$  or  $\text{Ce}^{3+}$ ) to cupferron. The observed 1:1 ratio may be attributed to the relatively low  $\text{pH}$  value of the test solution<sup>7,12</sup>.

Similar results were observed by choosing metal as titrant and the rare earth as titrate under the identical experimental conditions. In this case a L shaped curve was observed.




TABLE 1—AMPEROMETRIC DETERMINATION OF  $\text{La}^{3+}$  WITH CUPFERRON  
 $\text{pH}=2.75 \pm 0.01$

Amount of $\text{La}^{3+}$ taken (mM)	Amount of Cupferron consumed (mM)	Mole ratio M : L	% error
0.005	0.005	1 : 1	—
0.010	0.010	1 : 1	—
0.015	0.0140	1 : 0.999	-0.70
0.020	0.020	1 : 1	—
0.025	0.0249	1 : 0.996	-0.40
0.030	0.0298	1 : 0.998	-0.70
0.040	0.0401	1 : 1.0025	+0.25
0.050	0.05	1 : 1	—

TABLE 2—AMPEROMETRIC DETERMINATION OF  $\text{Ce}^{3+}$  WITH CUPFERRON,  $\text{pH}=2.75 \pm 0.01$

Amount of $\text{La}^{3+}$ taken (mM)	Amount of Cupferron consumed (mM)	Mole ratio M : L	% error
0.005	0.00503	1 : 1.0060	+0.60
0.010	0.010	1 : 1	—
0.015	0.01492	1 : 0.9946	-0.54
0.020	0.0201	1 : 0.9950	-0.50
0.025	0.025	1 : 1	—
0.030	0.0302	1 : 1.0067	+0.67
0.040	0.040	1 : 1	—
0.050	0.0502	1 : 1.004	+0.40

The data in Tables 1 and 2 clearly indicate that the method is successfully applicable for the estimation of micro and ultramicro quantities of the metal ions under study with an error of less than  $\pm 0.70\%$ .

**Effect of diverse ions:** Concentrated solutions of the diverse ions used were prepared. For interference studies, known amount of diverse ion was added to a definite amount of metal ion and the

pH was adjusted to 2.75 using dil HCl solution. The solution was titrated against cupferron amperometrically as described above. Titrations are not in any way hampered by the presence of different amount of the diverse ions (Table 3). Moreover,

TABLE 3—EFFECT OF DIVERSE IONS ON THE AMPEROMETRIC DETERMINATION OF  $\text{La}^{3+}$  AND  $\text{Ce}^{3+}$

Metal taken :  $\text{La}^{3+}=0.01 \text{ mM}$  (1.8891 mg),  $\text{Ce}^{3+}=0.01 \text{ mM}$  (1.4012 mg)

Diverse ion added	$\text{La}^{3+}$ found (mg)	% error	$\text{Ce}^{3+}$ found (mg)	% error
$\text{K}^+$ (180 mg)	1.8920	+0.20	1.3937	-0.58
$\text{Na}^+$ (115 mg)	1.8781	-0.79	1.4086	+0.53
$\text{Al}^{3+}$ (67 mg)	1.8854	-0.26	1.3929	-0.59
$\text{Mg}^{2+}$ (80 mg)	1.8782	-0.78	1.4106	+0.67
$\text{Li}^+$ (85 mg)	1.4015	+0.89	1.3950	-0.44
$\text{Zn}^{2+}$ (16 mg)	1.8804	-0.62	1.4185	+1.28
$\text{Cr}^{3+}$ (7 mg)	1.4058	+1.20	1.3851	-1.15

Figures within parenthesis indicate the maximum amount of foreign ion which do not interfere under the experimental condition

a fairly large amount of the ions  $\text{Cl}^-$ ,  $\text{I}^-$ ,  $\text{NO}_3^-$ ,  $\text{NO}_2^-$ ,  $\text{SO}_4^{2-}$ ,  $\text{CH}_3\text{COO}^-$  is tolerated. However, neither of these two rare earths could be estimated in presence of each other. It is also found that  $\text{Cu}^{2+}$ ,  $\text{Fe}^{3+}$ ,  $\text{MnO}_4^-$ ,  $\text{Ti}^{4+}$ ,  $\text{Pr}^{3+}$  and  $\text{Nd}^{3+}$ , even in small amount, interfere seriously.

#### Acknowledgement

The authors are thankful to the U. G. C., New Delhi for financial assistance.

#### References

1. P. J. ELVING and E. C. OLSON, *Anal. Chem.*, 1955, 27, 1817.
2. I. M. KOLTHOFF and A. LIBERTI, *Analyst*, 1949, 74, 685.
3. V. D. VASILENKO, *Ukr. Khim. Zh.*, 1960, 26, 767.
4. I. A. TSEKOVNITSKAYA, I. A. KALIMEN and V. MORACHEVSKII Yu, *Ind. Lab.*, 1961, 26, 853.
5. I. VSATENKO Yu and G. F. BELKESHOVA, *Zavodsk. Lab.*, 1955, 21, 779.
6. V. D. VASILENKO, E. B. OSTROVSKAYA and T. S. FOMENKO, *Zh. Analit. Khim.*, 1961, 16, 433.
7. K. S. PILLAI and S. C. LAVALLE, *J. Inst. Chem. (India)*, (In Press.)
8. E. C. OLSON and P. J. ELVING, *Anal. Chem.*, 1954, 26, 1747.
9. F. J. WELCHER, "The Analytical Uses of Ethylene Diamine Tetraacetic Acid", D. Van Nostrand Company, Inc., 1957, p. 174, 181.
10. P. J. ELVING and E. C. OLSON, *J. Amer. Chem. Soc.*, 1957, 79, 2697.
11. A. I. VOGL, "Quantitative Inorganic Analysis", Lowe and Brydson Ltd, London, ELBS, 1971, p. 418.



# Polarographic Determination of Stannous (tin) with Acrylic Acid

A. L. J. RAO and MAKHAN SINGH

Department of Chemistry, Punjab University, Patiala-147 002

Manuscript received 11 May 1981, revised 26 February 1982, accepted 21 July 1982

Stannous (tin) produces a well defined diffusion controlled, irreversible reduction wave in acrylic acid which has been employed for its determination. The limiting current increased with the increase in the  $\text{Sn(II)}$  concentration. The possibility of determining  $\text{mg}$  quantities of  $\text{Sn(II)}$  in solution by this method has been examined. The variation in acrylic acid concentration has no effect on the shape of the polarogram. However, the value of half wave potential shifted to more negative potential with increase in acrylic acid conc. and the  $\text{pH}$  of solution. The value of half wave potential and diffusion current constant came out to be  $-0.476$  S.C.E. and  $3.02$  vs, respectively in  $0.1$  M acrylic acid. A 10 fold ratio of  $\text{In(III)}$ ,  $\text{Cu(II)}$ ,  $\text{Sn(IV)}$ ,  $\text{Pt(IV)}$ ,  $\text{Te(VI)}$ ,  $\text{Co(II)}$ ,  $\text{Ni(II)}$ ,  $\text{Zn(II)}$ ,  $\text{Mn(II)}$ ,  $\text{Al(III)}$  and  $\text{Fe(III)}$  does not interfere. However,  $\text{Pb(II)}$  and  $\text{Tl(I)}$  interfere but their relatively lower amounts could be tolerated. The method is one of the most selective.

**P**OLAROGRAPHIC reduction of stannous (tin) has been studied in a number of supporting electrolytes. The polarographic characteristics of stannous are very favourable for practical analytical purposes. The reduction wave in various supporting electrolytes, such as hydrochloric acid, nitric acid, perchloric acid, sulphuric acid, phosphoric acid, sodium fluoride, sodium tartrate-sodium hydroxide<sup>1</sup>, ammonium acetate-acetic acid<sup>2</sup>, sodium formate<sup>3</sup>, hydrochloric acid-ammonium chloride-ascorbic acid<sup>4</sup>, potassium hydrogen phosphate-citric acid<sup>5</sup> and lactic acid<sup>6</sup> has been reported. In most of the supporting electrolytes, a maximum appears and it gives a double wave, one anodic and other cathodic. In the present paper, a polarographic method has been developed for the determination of stannous (tin) using acrylic acid as a ground electrolyte. The method does not require external adjustment of  $\text{pH}$ , maximum suppressor and addition of any other auxiliary electrolyte. Interference of various ion has been studied in detail. Stannic (tin) does not undergo reduction at all in this medium. The method may be used for the determination of stannous (tin) in pure solution as well as in complex mixture.

## Experimental

All polarograms were recorded at  $25 \pm 0.1^\circ$  with a manual Toshniwal polarograph.  $\text{pH}$  measurements were made with a Philips  $\text{pH}$  meter. The dissolved oxygen was removed by passing nitrogen through the cell solution for about 5 min before recording the polarograms. A saturated calomel electrode and a dropping mercury electrode with a capillary constant,  $m^{2/3}t^{1/6}$  was  $1.96$  in distilled water and on open circuit were used. Stannous chloride solution and adjustment of  $\text{pH}$  were made with hydrochloric acid. The resistance of the cell was less than  $200$  ohms, so no correction for the IR

drop through the cell was necessary. The reproducibility of the half wave potential was  $\pm 1$  mV. The experimental conditions were selected to maintain constant liquid junction potentials as much as possible.

The effect of  $\text{pH}$  was studied in  $\text{pH}$  range of 1 to 2. The  $E_{1/2}$  shifted to more negative potential with the increase in  $\text{pH}$ . The reduction wave remained well defined in this  $\text{pH}$  range. So all the polarograms were recorded at  $\text{pH}$  2 as there was no need of  $\text{pH}$  adjustment.

A variation of acrylic acid concentration from  $0.1$  M to  $0.5$  M had no effect on the shape of the polarogram. The diffusion current decreased while the value of  $E_{1/2}$  shifted to more negative potential with the increase in acrylic acid concentration indicating the increase in the stability of stannous acrylic acid complex.

Polarograms were recorded for different concentration of stannous ( $0.2$  mM to  $1.2$  mM) in  $0.1$  M acrylic acid. A linear plot passing through the origin was obtained when diffusion current (after correcting for the residual current) was plotted against stannous concentration, suggesting that this reduction can be used for the quantitative determination of stannous (tin).

## Results and Discussion

The effect of the height of the mercury column on the diffusion current was also studied. The linear plot of  $i_d$  vs  $\sqrt{h}$  showed the diffusion controlled nature of the reduction, which was already suggested by the linear plot of diffusion current vs stannous concentration. When  $E_{d.c.}$  was plotted against  $\log \frac{i}{i_d - i}$  a straight line was obtained. The slope of this log plot and the value of  $E_{d.c.} - E_{1/2}$

were both  $-46$  mV and were not in agreement with theoretical values, indicating the irreversible nature of the electrode reduction at d. m. e. Due to this irreversibility no deduction can be made about the nature of the complex formed. The value of  $I$  was calculated from Ilkovic equation and was found to be 3.02. This showed that stannous undergoes two electron change during the reduction process. Hence, the reduction can be shown as  $\text{Sn(II)} \rightarrow \text{Sn(0)}$ . Taking all the experimental observations into consideration,  $0.1$  M acrylic acid is found suitable for the estimation of stannous.

**Interferences:** Polarograms recorded in the presence of 10 fold amounts of W(VI), Sn(IV), Pt(IV), Te(IV), Mn(II), Ni(II), Zn(II), Co(II), Cr(III), U(VI), Fe(III), Pb(II), Sb(III) and Tl(I) revealed that only Pb(II) and Tl(I) interfered but their relatively lower amounts (Pb, 0.020 mg and Tl, 0.025 mg) could be tolerated. The results of the analysis of Sn(II) in presence of various ions are given in Table 1.

TABLE 1—EFFECT OF DIVERSE IONS (1 mg)

Diverse ion	Taken (mg)	Found (mg)	Error (%)
Fe(III)	0.88	0.88	0
Cu(II)	0.88	0.86	-2.2
Pt(IV)	0.88	0.86	-2.2
Mn(II)	0.88	0.88	—
Ni(II)	0.88	0.89	+1.1
Zn(II)	0.88	0.87	-1.1
Co(II)	0.88	0.88	—
Cr(III)	0.88	0.87	-1.1
U(VI)	0.88	0.90	+2.2
Se(IV)	0.88	0.88	—
Te(VI)	0.88	0.88	—
Sb(III)	0.88	0.90	+2.2
As(III)	0.88	0.88	—
Zr(IV)	0.88	0.88	—
Th(IV)	0.88	0.87	-1.1

**Simultaneous determination of Sb(III)—Sn(II):** As indicated in a preliminary observation, antimony do not interfere under these conditions. Based upon this fact, a method has been developed for the simultaneous determination of Sb(III)—Sn(II). A series of polarograms of solutions of mixed metal ions in  $0.1$  M acrylic acid were recorded. The value of diffusion current measured for each metal ion was referred to their respective calibration graph as before. The results observed for some mixture are given in Table 2.

TABLE 2—SIMULTANEOUS DETERMINATION OF Sb(III)—Sn(II)

Amount taken (mg)		Amount found (mg)		% Error	
Sb(III)	Sn(II)	Sb(III)	Sn(II)	Sb(III)	Sn(II)
1.2715	2.07	1.2710	2.07	-0.04	0
1.5719	2.97	1.5719	2.90	0	-2.35
1.2715	2.07	1.2700	2.07	-0.11	0
2.1269	2.97	2.1250	2.90	-0.09	-2.35

## References

1. L. MEITES, "Polarographic Techniques", Interscience Publishers, New York, 1955, 1st Edn, Appendix B, p. 250-295
2. M. A. DESRESA, D. N. HUME, A. C. GLAMM, JR. and D. D. DEFORD, *Anal. Chem.*, 1953, **25**, 983
3. G. S. DESHMUKH and Y. D. KANE, *J. Sci. Ind. Res.*, 1962, **21b**, 235.
4. T. MARKUSIC, *Chem. Ind.*, 1965, **14**, 559.
5. G. PATRIARCHE and A. A. GERBAUX, *J. Pharm. Belg.*, 1965, **20**, 51.
6. H. S. MAHANTI and G. S. DESHMUKH, *J. Indian Chem. Soc.*, 1974, **51**, 713

# Complex Formation of Vanadium(V) with Salicylhydroxamic Acid in MIBK : Photometric Methods of Determination of Vanadium in Alloy Steel and Ores

S. P. BAG, A. B. CHATTERJEE, A. K. CHAKRABARTI and P. R. CHAKRABORTY\*

Department of Chemistry, Jadavpur University, Calcutta-700 082

Manuscript received 8 July 1981, revised 1 December 1981, accepted 12 August 1982

Reactions of vanadium(V) with N-salicylhydroxamic acid under varying conditions of pH and acidity and extraction behaviour of binary and ternary complexes in methyl isobutylketone are reported. New sensitive and selective photometric methods for trace determination of vanadium(V) in absence or presence of thiocyanate and its applications in the analyses of high speed steel, ilmenite and bauxite are also described.

IN this paper we report the use of a hydroxamic acid (N-SHA) where a phenolic -OH group is attached to the *ortho* position of the phenyl ring<sup>1-3</sup>. In N-AHA molecule a basic -NH<sub>2</sub> group is attached to *ortho* position and the mixed-ligand extraction has been described<sup>4</sup>. Formations of different complexes of vanadium(V) with N-SHA under varying conditions of pH have been investigated along with ternary extraction involving thiocyanate. The sensitivity and selectivity of the determinations have been found to increase considerably both in binary and ternary extractions in methyl isobutylketone (mibk) even in presence of moderate excess of Fe(III) and Ti(IV). Fe(III) and Ti(IV) interfered in almost all the procedures mentioned with N-arylhydroxamic acids and amines either in extraction or in direct measurement in aqueous medium. Analyses of standard alloy steel, ilmenite and bauxite were also undertaken and the methods worked successfully<sup>5-7</sup>.

## Experimental

**Reagents and solutions:** A stock solution of vanadium was prepared from ammonium vanadate (E. Merck) and standardized<sup>8</sup>. The reagent, N-SHA, was prepared by the reported method<sup>9</sup>. Standard reagent solutions (1% w/v) and of desired strengths in pure mibk were used directly for extractions. A standard 2% aqueous solution of ammonium thiocyanate was used in ternary extraction. All other chemicals, reagents and solvents used in the experiments were of A. R. grade quality.

**Apparatus:** Measurements were made with Hilger-Uvispek and Spektromom 204 spectrophotometers with matched 1 cm quartz or glass cells. A Systronics pH-meter (324, India) was used for pH measurements.

## Recommended procedure:

(A) **Binary extraction, pH 3.1:** An aliquot of vanadium solution ( $1.963 \times 10^{-5}$  M) was taken in a

100 ml separatory funnel and the pH was adjusted by adding very dil HCl after 5 ml of 1% reagent was added to 10 ml of aqueous phase and 0.5 ml of 0.1 M HCl. It was shaken with an equal volume of organic phase (10 ml) for 5 min. The blue-violet complex extracted from pH 3.1 was drained out in a 50 ml beaker and dried with anhydrous sodium sulphate. The extractions were repeated with 5 ml portions of the solvent. The combined extract was transferred into a 25 ml volumetric flask. The volume was made up to the mark with pure solvent. The absorbance of the complex solution was measured at 575 nm against solvent blank. A calibration curve was constructed.

(B) **Binary extraction, 1.8 M HCl:** An aliquot of the metal solution ( $1.963 \times 10^{-5}$  M) was taken in a 100 ml separatory funnel with 5 ml of 1% reagent. The pH was adjusted to 3.1 by adding 0.5 ml of 0.1 M HCl and the mixture was shaken with 10 ml of methyl isobutyl ketone. The acidity was then adjusted to 1.8 M HCl by adding 6 M HCl. The wine-red complex was extracted for 5 min. It was dried and transferred into a 25 ml volumetric flask and made up to the mark. The absorbance was measured against solvent blank at 510 nm. A calibration curve was also constructed.

(C) **Ternary extraction, pH 0.95/0.16 M HCl:** In the ternary extraction, the blue-violet complex was first extracted at pH 3.1 by adding 5 ml of 1% reagent and 0.5 ml of 0.1 M HCl for 2 min with 15 ml of methyl isobutyl ketone. 1 ml of 2% ammonium thiocyanate was added and the pH of the 15 ml aqueous phase was adjusted to 0.95. The blue-violet complex was again extracted for 8 min. The extractions were repeated with 5 ml portions of the solvent. The organic layer was dried over anhydrous sodium sulphate, transferred into a 25 ml volumetric flask and made up to the mark with pure solvent. A reagent blank was prepared similarly. The absorbance of the complex was measured against solvent

\* At present Chemist, Indian Oxygen Limited, Calcutta.

at 540 nm. A calibration curve was also constructed.

**Procedure for steel analysis:** 0.5 g of steel sample was dissolved in 25 ml dilute sulphuric acid (1 : 1) and the solution was digested on a hot plate to a syrupy solution, repeating the addition of acid. It was then treated with 5 ml of conc nitric acid for complete digestion and evaporated to dryness. The solution was diluted with 50 ml water, boiled, filtered, and washed with hot acidulated water and finally with hot water. The cold filtrate and the washings were taken in a 250 ml volumetric flask and the volume was made up to the mark. An aliquot of the steel solution was transferred and oxidised at room temperature with 0.1%  $\text{KMnO}_4$  solution till the pink colour persisted. A hot solution of 15%  $\text{NaOH}$  solution was then added and the mixture boiled. The precipitate was filtered off and redissolved in dil  $\text{HCl}$  and the procedure was repeated several times. The filtrates were collected and boiled down to a low volume. The solution was cooled and vanadium content was determined following the recommended procedures A, B and C. The absorbance of the extracts was measured at 575, 510 and 540 nm for the respective complexes and the metal content determined separately.

**Procedure for ore analysis** 0.5 g of finely powdered ore was fused with 9 g  $\text{KHSO}_4$  and a few drops of  $\text{H}_2\text{SO}_4$  in a silica crucible over a low flame to avoid spurling and a clear melt was obtained. The fused mass was cooled and leached with 1.9  $\text{H}_2\text{SO}_4$  acid. The solution was boiled and oxidised with a few drops of nitric acid. Iron and titanium was precipitated as hydroxides with an excess of 15%  $\text{NaOH}$  solution. Any adsorbed vanadium in the hydroxide was freed by double precipitation method. The filtrates were combined and the volume reduced to 0.5 ml by boiling. The cold solution was transferred into a 100 ml standard flask and the volume was made up with water. Different aliquots were taken and the metal was determined by procedures A, B and C using fluoride for traces of iron and titanium in the solution.

**Procedure for bauxite:** Bauxite sample was decomposed by alkaline flux. 0.5 g of the sample was fused for 2 hr with  $\text{Na}_2\text{CO}_3$  (3-4 g) and  $\text{NaOH}$  (1 g) in a nickel crucible. The melt was cooled and leached with hot water and kept overnight. The aqueous extract of vanadium and other insoluble materials along with iron and titanium was filtered, transferred into a 100 ml volumetric flask and the volume made up to the mark. The vanadium content was determined using appropriate amount of the solution.

## Results and Discussion

**Absorbance spectra:** The absorbance spectra of binary and ternary chelates of vanadium(V) showed maximum at 575, 510 and 540 nm (Fig. 1). Since reagent blanks showed no absorbance in these regions the absorbance has been measured against solvent blank mibk.




Fig 1 Spectral curves of the V(V) binary and ternary complexes  $\text{V(V)} = 7.858 \times 10^{-4} \text{ M}$ ,  $\text{N-SHA} = 1.806 \times 10^{-3} \text{ M}$ ,  $\text{NH}_4\text{SCN} = 5.256 \times 10^{-3} \text{ M}$ .  
Curve I—O: V(V)-N-SHA binary complex at pH=3.1.  
II—O: V(V)-N-SHA binary complex at 1.8 M HCl.  
III—●: V(V)-N-SHA ternary complex at pH=0.95

**Optimum reaction conditions:** The optimum pH range of extractions for blue-violet chelate was found to be 2.2-5.6 and pH was always adjusted to 3.1 for all measurements. At  $\text{pH} < 2.2$  a shift of the maximum occurs with corresponding colour change towards red-violet. The intensity of wine-red complex is constant in the region 0.6-4.2 M  $\text{HCl}$ . It was observed that direct addition of 6 M acid produced a very low absorbance. The complex is first extracted from pH 3.1 and then the acidity increased. An emulsion, requiring time to break, formed as acidity increased above 3.5 M  $\text{HCl}$ . All measurements were made at 1.8 M  $\text{HCl}$  for wine-red complex. The optimum acidity range for violet coloured mixed-ligand vanadium complex is pH 1.3 to 0.33 M  $\text{HCl}$ . This complex is formed from pH 1.8 to 3.0 M  $\text{HCl}$ , and separation and extraction is slow at  $\text{pH} > 1.8$  and  $> 0.8 \text{ M HCl}$  due to emulsion formation. Ternary extractions were made at pH 0.95/0.16 M  $\text{HCl}$ . The binary complex is first extracted from pH 3.0 and then a 0.16 M  $\text{HCl}$  acidity was maintained.

2.5 ml of 1%, 2.0 ml of 1% and 0.5 ml of 1% (w/v) reagent in mibk were found sufficient for full colour development of the respective complexes and their extractions. The optimum range is 2 to 10 ml of 1% for binary systems and 0.5-10 ml of 1% reagent for ternary system. 5 ml of 1% reagent was used for all three extractive methods. Ternary complex is formed with 0.1 to 12 ml of 1% reagent with a fixed amount [1 ml of 2% (0.26 M)] of thiocyanate added and 0.5 ml of 1% reagent. With 5 ml of 1% reagent (N-SHA) the violet complex of vanadium(V) was formed with 0.01 to 10 ml of 2%

ammonium thiocyanate and 0.75 ml was found sufficient. A 5 ml of 2% solution was always used in the method.

The binary and ternary complexes are completely extracted within 4 to 5 and 7 to 9 min and show constant absorbance immediately after the volume is made up. The complexes are stable for more than 24 hr at room temperature (27°).

**Calibration curve, optimum range and sensitivity :** For solutions of varied amount of vanadium(V), fixed amounts of reagent (N-SHA) and thiocyanate solutions were utilized in the above procedures and absorbances were measured at 575, 510 and 540 nm, respectively. The systems obeyed Beer's law (Fig. 2) in the range 0.2-8 (blue-violet), 0.25-9 (wine-red) and 0.4-12 (violet) ppm




Fig 2. Beer's law curves N-SHA= $1.806 \times 10^{-2}$  M,  $\text{NH}_4\text{SCN} = 5.255 \times 10^{-2}$  M.  
Plot I—○: V(V)-N-SHA binary complex at pH=8.1.  
II—○: V(V)-N-SHA binary complex at 1.8 M HCl.  
III—●: V(V)-N-SHA-SCN ternary complex at 0.16 M HCl

with optimum range obtained from Ringbom's plot<sup>9</sup> as 2-6.5, 2-6 and 1-6 ppm, respectively. The % relative error per 1% absolute photometric error using Ayres' equation<sup>10</sup> for the systems are 2.71, 2.72 and 2.73%, respectively.

The molar absorptivities are  $5.71 \times 10^3$  (at 575 nm),  $5.73 \times 10^3$  (at 510 nm) and  $8.34 \times 10^3$  (at 540 nm) l. mole<sup>-1</sup> cm<sup>-1</sup>. The corresponding Sandell sensitivities<sup>11</sup> are 0.00893, 0.0089 and 0.0061  $\mu\text{g cm}^{-2}$  V(V).

**Interference studies :** Solutions were prepared by the above procedures with 4 ppm vanadium(V) (25 ml) and different amounts of diverse ions at the pH acidity conditions. The ions were added before the reagent. Normally, Fe(III), Ti(IV), Mo(VI), W(VI), Zr(IV), Nb(V), Hf(IV) have low tolerance limits. Masking with fluoride ion is effective for moderate excess. Most of the metal ions do not

interfere in all the three systems. Anions have no other effect. The methods were found to be accurate and precise for analyses of geological materials and alloy. The results are summarized in Table I.

TABLE I—EFFECT OF DIVERSE IONS  
[V(V)=0.1 mg, N-SHA=1% in mlbk,  
 $\text{NH}_4\text{SCN}=2\%$  aq. solution]

Ions	Tolerance limits, mg		
	pH 8.1 575 nm	1.8 M HCl 510 nm	pH 0.95 540 nm
Acetate	10	10	20
Fluoride	20	10	20
Tartrate	50	45	30
Oxalate	2	8	20
Citrate	50	50	25
EDTA	1.5	40	10
Phosphate	10	75	50
Fe(III)	1	1.25	5*
Ti(IV)	Int.	1	5*
Mo(VI)	1.5	1.25	1.25*
W(VI)	1	4.5	2.5*
Zr(IV)	5	6.25	6.25*
Hf(IV)	5	6.25	6.25*
Th(IV)	10	20	10
Nb(V)	1.25	1.25	1.25*
Ta(V)	1.25	1.25	3*
$\text{UO}_2(\text{II})$	7.5	11.25	10
Co(II)	15	20	5
Ni(II)	10	15	5
Cu(II)	2.5	7.5	3.75
Mn(II)	4	20	12.5
Cr(III)	7.5	15	10
Al(III)	2.5	5	5
Zn(II)	7.5	15	10
Cd(II)	6.25	6.25	12.5
Pb(II)	10	20	15
Pd(II)	0.75	3.75	1

\*Fluoride masking.

**Determination of vanadium in steel, rock and ore :** The ilmenite samples were collected from Hornbendite rock of Tamil Nadu and Putkapahar of M.P. (GSI samples) and bauxite from Indian Oxygen Limited. These were finely powdered (200 mesh) and obtained directly after separation and the samples were standardized previously by spectroscopic methods. The present methods are found useful and the results of the analyses by the procedures are found to agree well with each other. The amounts of vanadium present in the samples from analyses report are given in the following Table 2. The present solvent extraction method is simple and rapid over the other existing methods.

TABLE 2—ANALYSES OF ALLOY STEEL (BAS 64b),  
ROCK (ILMENITE) AND ORE (BAUXITE)

Methods	BAS steel 64b, certified 1.99% V	Rock (ilmenite, mineral), certified 0.1% and 0.15% V	Ore (bauxite), certified > 0.08%
Binary (8.1 pH)	1.97*	0.09	0.14
Binary (1.8 M HCl)	1.965	0.08	0.188
Ternary (0.16 M HCl)	1.97	0.09	0.14
			0.26

\*Values are average of several determinations.

References

1. A. S. BEADURI, *Z. anal. Chem.*, 1956, 151, 109.
2. A. S. BEADURI and P. HAY, *Z. anal. Chem.*, 1957, 154, 108.
3. S. P. BAG and A. K. CHAKRABARTI, *J. Indian Chem. Soc.*, 1975, 52, 492.
4. S. P. BAG, A. B. CHATTERJEE, A. K. CHAKRABARTI and P. R. CHAKRABORTY, *Indian J. Chem.*, 1980, 19A, 1200.
5. A. K. MAJUMDER, "N-Benzoylphenylhydroxylamine and its Analogues", Pergamon Press, Oxford, 1972.
6. A. M. G. MACDONALD, *Ind. Chemist*, 1960, 36, 512.
7. M. ISHIZAKI and S. UENO, *Talanta*, 1979, 26, 523.
8. A. I. VOGEL, "Quantitative Inorganic Analysis", Longman's, London, 1964.
9. A. RINGBOM, *Z. anal. Chem.*, 1938, 115, 332.
10. G. H. AYRES, *Anal. Chem.*, 1949, 21, 652.
11. E. B. SANDELL, "Colorimetric Determination of Traces of Metals", Interscience, N. Y., 1957.

# NOTES

## Azo Complexes: Complexes of Alkali Metal Salts of Some Organic Acids with *o*-Hydroxybenzene-Azo-2-Naphthyl Amine

A. K. BANERJEE, TARKESHWAR SINGH  
and

S. K. ROY

Department of Chemistry, Patna University, Patna-800 005

Manuscript received 17 November 1981, accepted 23 May 1982

AS an extension of our previous work<sup>1,2</sup> on azo complexes, we are reporting the synthesis of alkali metal salt adducts of *o*-hydroxybenzene-azo-2-naphthylamine (OHBANM), which have two electron releasing groups -OH and -NH<sub>2</sub> in the *o* and *o'* positions to the azo group (-N=N-) and hence would increase the donor property of the azo group. Intramolecular hydrogen bonding in the ligand plays an important role in adduct formation.

### Experimental

The ligand OHBANM was prepared by standard method<sup>3</sup> (m. p. 192-193°). Solutions of the alkali metal salts used were prepared in 95% ethanol.

The general method of preparation was to add the alkali metal salts of organic acids to hot absolute ethanolic solution of OHBANM in mono molecular ratio. The mixture was refluxed over hot plate using magnetic stirrer for about 1 hr.

The solution, on keeping, yielded crystalline solid adducts. The crystals were filtered, washed with absolute ethanol and dried in an oven at 90°.

### Results and Discussion

The adducts are stable when stored under dry condition e.g. in a desiccator, but decompose in the presence of moisture. The adducts are thermally stable. When heated, they undergo decomposition at a temperature higher than the melting point of the ligand suggesting them to be pure compounds. The compounds are sparingly soluble in hot polar solvent. The colour, melting or decomposition temperatures and analytical data of the compounds are given in Table 1.

The presence of electron releasing -OH and -NH<sub>2</sub> groups at *o* and *o'* positions to the azo group increases the coordinating capacity of the azo-nitrogen which perhaps takes part in association. The NH<sub>2</sub>, O-H and -N=N- frequencies of ligand and adducts are listed in Table 2.

In ligand OHBANM, we observe that the two N-H stretch vibrations appear as medium peaks at ~ 3325 cm<sup>-1</sup> and ~ 3260 cm<sup>-1</sup>. In the alkali metal adducts, the ~ 3325 cm<sup>-1</sup> band remains unaffected after association, but the ~ 3260 cm<sup>-1</sup> band shifts down to ~ 3125 cm<sup>-1</sup>. It suggests that there has been decrease in the bond order of N-H. The OH group in the ligand is hydrogen bonded and does not show up at the original place. In OHBANM adducts with alkali metal salts, the O-H

TABLE 1

Compound	Colour	Melting/decomp. (d) temp (°C)	Found (%)				Calcd. (%)			
			C	H	N	M	C	H	N	M
OHBANM = L	Deep violet	193	72.98	4.89	16.01	—	73.00	4.94	15.99	—
Na1N2N.L	Brown	209(d)	68.10	4.45	12.57	4.92	68.11	4.13	12.23	5.02
K1N2N.L	Brown	213	65.65	4.22	11.99	8.11	65.82	4.01	11.81	8.22
Li8HQ.L	Deep green	237	72.25	4.79	13.84	—	72.46	4.58	13.52	1.69
Na8HQ.L	Deep green	232	69.15	4.62	13.84	5.11	69.74	4.41	13.02	5.34
K8HQ.L	Brown	245	67.11	4.47	12.87	8.34	67.26	4.26	12.55	8.74
NaONP.L	Deep green	225	62.11	4.24	13.51	5.12	62.26	4.01	13.20	5.42
KONP.L	Red	228	59.89	4.01	12.93	8.85	60.00	3.86	12.72	8.86
Na2H3NA.L	Red	242	68.12	4.41	9.11	4.21	68.49	4.22	8.87	4.86
K2H3NA.L	Deep green	246	66.14	4.21	8.96	7.42	66.25	4.08	8.58	7.97
Na anth.L	Bright red	225	65.12	4.71	13.57	5.12	65.40	4.50	13.27	5.64
K anth.L	Deep green	215	63.44	4.36	12.87	8.46	63.01	4.33	12.78	8.70
NaSalA.L	Brown	233	65.43	4.44	10.21	5.12	65.24	4.25	9.92	5.43
KSalA.L	Deep red	227	62.42	4.32	10.11	8.23	62.87	4.10	9.56	8.88
NaSalH.L	Reddish brown	226	67.51	4.72	10.72	5.12	67.81	4.42	10.31	5.65
Na.acac.L	Royal blue	—								

(Soluble in ethanol)

1N2N=1-nitroso-2-naphthol, 8HQ=8-hydroxyquinoline, ONP= *o*-nitrophenol, 2H3NA=2-hydroxy-3-naphthoic acid, anth=anthranilic acid, SalA=Salicylic acid, SalH=Salicylaldehyde, acac=acetylaceton.

TABLE I

Compound	N-H frequencies ( $\text{cm}^{-1}$ )	O-H frequencies ( $\text{cm}^{-1}$ )	-N=N- frequencies ( $\text{cm}^{-1}$ )
OHBANM=L	8925 8980		1535
NaIN2N.L	8925 8125	2450 1960	1535
KIN2N.L	8925 8160-25	2450 1920	1535
NaONP.L	8925 8125	2400 1940	1510
KONP.L	8925 8115	2400 1880	1507
Na2H8N.A.L	8300 8225	2400 1880	1580
K2H8N.A.L	8325 8125	2400 1880	1580
NaSHQ.L	8860(br)		1505
NaSalH.L		2880 1880	1500
KSalA.L		2880 1860	1505

br = broad.

frequencies show up as one or two broad humps, one at  $\sim 2500 \text{ cm}^{-1}$  and the other at  $1800\text{--}1960 \text{ cm}^{-1}$ . It suggests strong association of the OH group.

The -N=N- stretching frequency at  $1535 \text{ cm}^{-1}$  in the ligand has been spotted between  $1525 \text{ cm}^{-1}$  to  $1500 \text{ cm}^{-1}$  in the adducts, suggesting again the association of -N=N- group in the alkali metal adducts.

Our present work also shows that strong intra-molecular hydrogen bonding existing in the ligand breaks on complexation. It has been further observed that ligands, which have stronger intra-hydrogen bonding, form stable alkali metal adducts.

## References

1. A. K. BANERJEE, TARKESHWAR SINGH and S. K. ROY, *J. Indian Chem. Soc.*, (communicated).
2. A. K. BANERJEE, TARKESHWAR SINGH and S. K. ROY, *J. Indian Chem. Soc.*, (communicated).
3. BEILSTEIN-PRAGER-JACOBSON, *Org. Chemie*, XVI, System No. 2085-2858, 160.
4. K. NAKAMOTO, "Infrared and Raman Spectra of Inorganic and Coordination Compounds", 3rd Edn, p. 197

### Interaction Products of Triphenylphosphine Oxide with Some Organotin Halides

K. K. BAJPAI\*

Indian Institute of Sugarcane Research, Lucknow-226 002

and

BEENA BAJPAI

Department of Chemistry, University of Lucknow,  
Lucknow-226 007Manuscript received 17 December 1980, revised 31 December  
1981, accepted 8 July 1982

**COMPLEXES** of triorganophosphine oxide with a variety of metal salts have been extensively studied<sup>1-3</sup>. Syntheses and characterisation of adducts of the Lewis base with organometallic moieties have also been reported<sup>4-16</sup>. Molecular

addition compounds of triphenylphosphine oxide (TPPO) with organotin moieties appear not to have received adequate attention. In continuation of our studies on organotin<sup>17-21</sup>, we report here the interaction of TPPO with some organotins which yielded molecular addition compounds of the type  $R_n\text{SnX}_{4-n}\cdot n\text{L}$  ( $R$ =phenyl or butyl;  $X$ =Cl or Br,  $n=1,2$  or 3 and  $L$ =TPPO). The compounds have been characterised by elemental analysis, melting point and their data on conductance, molecular weight, ir and mass spectrometry have been discussed.

## Experimental

Di or triorganotin halides were prepared according to literature methods<sup>22</sup>. TPPO (Carlsile) and other reagents of analytical grade (B.D.H./S. Merck) were used without further purification.

In a typical reaction, 2 m mole of an organotin derivative and equimolar amount of TPPO were refluxed in 40 ml of benzene/chloroform for about 1 hr. A suitable volume of pet. ether (60-80)/ether was added to this (in some cases reaction mixture was kept in a fridge) and the solid so obtained was separated, washed with pet. ether, recrystallised from benzene-pet. ether solvent pair and dried under vacuum. The yield was about 66%.

The m. ps. of the adducts were determined on electrically operated apparatus (M/s. Toshniwal Bros., Bombay). Elemental analyses were done by micro analytical method but tin was estimated as stannic acid. The metal was weighed as oxide after ignition.

The infrared spectra of TPPO and their adducts with organotins were recorded in the region  $4000\text{--}200$  using Perkin Elmer IR spectrophotometer, model 521. Calibration was performed with a polystyrene film.

Conductance was measured in benzene by Philips, type PR 9500, conductivity bridge using dip type conductivity cell having a cell constant 0.7584. The molecular weights of the adducts were determined cryoscopically in benzene. Mass spectrometer, Hitachi model No. RMU-6E, was used for obtaining mass spectra.

## Results and Discussion

Experimental data of the adducts are given in Table 1. The adducts melt in the range of  $62\text{--}175^\circ$  while  $\text{Ph-SnCl}_3\cdot\text{TPPO}$  do not melt up to  $250^\circ$ . They are soluble in common organic solvents, are thermally stable and do not decompose when heated to their m. ps. for several hr. They are insensitive to atmospheric moisture but easily hydrolyse when refluxed with water or aqueous ammonia yielding polymeric organotin oxide as the final product. The conductance values in  $10^{-3}M$  solutions indicate

\* Author for correspondence.




TABLE 1—EXPERIMENTAL DATA FOR TRIPHENYLPHOSPHINE OXIDE (L) OF ORGANOTIN HALIDES

Adducts	m.p. (°C)	Sn	O	N	Mol wt.	IR absorption (cm <sup>-1</sup> ) P=O	IR absorption (cm <sup>-1</sup> ) P—Sn—O
Ph <sub>3</sub> SnCl <sub>2</sub> .L	>250	20.2 (20.4)	50.0 (49.6)	3.2 (3.4)	450 (581)	1145 m	320 s
Ph <sub>3</sub> SnCl <sub>2</sub> .L	175	19.4 (19.1)	57.5 (57.8)	4.2 (4.0)	422 (522)	1140 s	318 s
Ph <sub>3</sub> SnBr <sub>2</sub> .L	158	15.4 (16.7)	50.6 (50.6)	8.1 (3.5)	502 (711)	1135 s	315 s
Ph <sub>3</sub> SnCl.L	170	17.1 (17.9)	56.8 (56.5)	4.7 (4.5)	510 (564)	1155 s	320 s
Bu <sub>3</sub> SnCl <sub>2</sub> .L	88	20.9 (21.2)	47.3 (47.1)	4.2 (4.3)	400 (560)	1150 s	325 s
Bu <sub>3</sub> SnCl <sub>2</sub> .L	62	20.3 (20.4)	53.5 (53.6)	5.6 (5.7)	487 (582)	1153 s	335 s
Bu <sub>3</sub> SnBr <sub>2</sub> .L	78	18.4 (17.7)	46.3 (46.5)	5.1 (4.9)	498 (571)	1148 m	322 m

Figures in parenthesis are the calculated values, m=medium, s=strong.


the absence of ionic species and their observed low molecular weight, compared to formulae weight, suggest significant dissociation in solution.

As per equation below, the interaction of the adducts with some Lewis bases such as 1,10-phenanthroline, 2,2'-bipyridine, dimethylsulfoxide, pyridine-N-oxide was investigated in chloroform pet. ether. The complete substitution of TPPO molecule by the above bases indicates its comparatively poor donor ability towards the investigated Lewis acids. These replacements were confirmed by elemental analyses, m. ps. and infrared data of the adducts.



(L = 1,10-phen, 2,2'-bipy, py-N-oxide or DMSO)

Mass spectra\* of three adducts having different Lewis acid species (C<sub>6</sub>H<sub>5</sub>)<sub>3</sub>SnCl, (C<sub>6</sub>H<sub>5</sub>)<sub>2</sub>SnCl<sub>2</sub> and (C<sub>6</sub>H<sub>5</sub>)SnCl<sub>3</sub> were recorded as an aid to their characterisation and to study their fragmentation pattern. On electron impact, the adducts readily break up into their Lewis acid and Lewis base fragments viz. [(C<sub>6</sub>H<sub>5</sub>)<sub>3</sub>SnCl]<sup>+</sup> (m/e 386) or [(C<sub>6</sub>H<sub>5</sub>)<sub>2</sub>SnCl<sub>2</sub>]<sup>+</sup> (m/e 344) or [(C<sub>6</sub>H<sub>5</sub>)SnCl<sub>3</sub>]<sup>+</sup> (m/e 304) and [(C<sub>6</sub>H<sub>5</sub>)<sub>3</sub>PO]<sup>+</sup> (m/e 278) while the molecular ions were not observed. This indicated a weak linkage between the acids and the base forming the adducts. The fragment [(C<sub>6</sub>H<sub>5</sub>)<sub>3</sub>PO]<sup>+</sup> gave rise to smaller fragments m/e 201 [(C<sub>6</sub>H<sub>5</sub>)<sub>2</sub>PO]<sup>+</sup>, 108 [C<sub>6</sub>H<sub>5</sub>P]<sup>+</sup>, 47[PO]<sup>+</sup>, 31[P]<sup>+</sup> on further cleavage. The fragmentation pattern of [(C<sub>6</sub>H<sub>5</sub>)<sub>2</sub>SnCl<sub>2</sub>]<sup>+</sup>, [(C<sub>6</sub>H<sub>5</sub>)<sub>2</sub>SnCl<sub>2</sub>]<sup>+</sup> and [(C<sub>6</sub>H<sub>5</sub>)<sub>2</sub>SnCl<sub>2</sub>]<sup>+</sup> was dissimilar and gave mass spectral peaks (m/e) as per schemes given below :



\* The mass spectral fragments under consideration refer to appropriate combination of abundant isotopes for Sn and Cl.

The most significant absorption in the infrared spectra of TPPO and its adducts, the P=O stretching frequency appearing as a strong band at 1190 cm<sup>-1</sup> in the spectrum of the Lewis base, undergoes a negative shift of 37 cm<sup>-1</sup> to 55 cm<sup>-1</sup> on adduct formation. This lowering of P=O is indicative of coordination<sup>7-9,12,14</sup>.

A new spectral band of strong intensity has been observed in a close range of 315-335 cm<sup>-1</sup> in the spectra of adducts which was not present either in the spectra of TPPO or the Lewis acids. This band may possibly be associated with vibration of O→Sn. Sn—Cl and Sn—aryl stretches have been found at the known positions in the spectra of the Lewis acids<sup>17,18</sup>. A significant lowering of Sn—Cl stretching in the adducts characteristically depicts increase in the coordination number of the metal atom.

Investigations revealed some important biological properties of the adducts and the findings will be reported elsewhere.

#### Acknowledgement

The authors are grateful to Council of Scientific and Industrial Research, New Delhi for financial support to one of them (B.B.) and the Head, Chemistry Department, Lucknow University, Lucknow for the facilities. They are also thankful to Shri R. K. Singh, Medicinal Chemistry Division, C. D. R. I., Lucknow for a discussion on mass spectrometry.

#### References

1. D. M. L. GOODGAME and F. A. GOTTON, *J. Chem. Soc.*, 1961, 3299, 3785.
2. M. J. FRASER, W. GERARD and R. TWAITS, *J. Inorg. Nuclear Chem.*, 1963, 25, 637.
3. D. L. PLAYMATE, *J. Inorg. Nuclear Chem.*, 1969, 31, 236.
4. J. RIMBAULT and R. HUGEL, *Rev. Chim. Miner.*, 1978, 10, 772.
5. U. BARTORELLI, F. CONZIANI and L. GARLASCHIELI, *Gazz. Chim.*, 1974, 104, 56.

6. D. L. KEPERT, D. TAYLOR and A. H. WHITE, *J. Chem. Soc.*, 1979, 1668.
7. N. M. KARAYANIS, G. M. MUKULSKI, L. L. PYTLOWSKI and M. M. LINES, *Inorg. Chimica Acta*, 1974, 10, 97.
8. A. K. ANJANWAL, A. K. SRIVASTAVA and T. N. SRIVASTAVA, *Indian J. Chem.*, 1979, 18A, 469.
9. V. G. KUMAR and W. KITCHING, *J. Organometal. Chem.*, 1968, 13, 523.
10. F. P. MULLINS, *Canad. J. Chem.*, 1971, 49, 2719.
11. H. J. HAUFF and F. HUMER, *J. Organometal. Chem.*, 1971, 33, 175.
12. B. V. LINGME, R. S. RANDALL and J. R. SAMS, *Canad. J. Chem.*, 1972, 50, 8212.
13. R. C. PAUL, P. K. GUPTA and S. L. CHADHA, *Indian J. Chem.*, 1978, 16, 930.
14. J. P. OLAKK, V. M. LANGFORD and C. N. WILKINS, *J. Chem. Soc.*, 1967, 792.
15. G. B. DRACH and R. S. NYHOLM, *J. Chem. Soc.*, 1965, 6107.
16. A. J. OKENTY and G. B. DRACH, *Aust. J. Chem.*, 1971, 24, 489.
17. T. N. SRIVASTAVA, S. K. TANDON and B. BAJPAI, *J. Indian Chem. Soc.*, 1975, 52, 474.
18. T. N. SRIVASTAVA, S. K. TANDON and B. BAJPAI, *Inorg. Chimica Acta*, 1975, 13, 109.
19. BERNIA BAJPAI, *Indian J. Chem.*, 1976, 14A, 347.
20. T. N. SRIVASTAVA, BERNIA BAJPAI and P. C. SRIVASTAVA, *Indian J. Chem.*, 1978, 16A, 164.
21. T. N. SRIVASTAVA, P. C. SRIVASTAVA and BERNIA BAJPAI, *J. Inorg. Nuclear Chem.*, 1978, 40, 921.
22. R. K. INGHAM, S. D. RISENBURG and H. GILMAN, *Chem. News*, 1960, 60, 459.

### Mixed Ligand Cobalt(III) Complexes Containing Benzotriazole or 5-Nitrobenzotriazole

L. K. MISHRA and HIMANSHU BHUSHAN

Department of Chemistry, Patna University, Patna-800 005  
and

N. K. JHA†

Department of Chemistry, Indian Institute of Technology,  
New Delhi-110 016

Manuscript received 4 August 1981, revised 6 February 1982,  
accepted 27 May 1982

**C**OMPLEXING behaviour of benzotriazole<sup>1-4</sup> and its use in estimation of some transition metal ions<sup>5-7</sup> are well known. Preparation of mixed ligand Co(III) complexes of benzotriazole and of 5-nitrobenzotriazole from *trans*-[Co(en)<sub>2</sub>Cl<sub>2</sub>]Cl and [Co(NH<sub>3</sub>)<sub>5</sub>(NO<sub>2</sub>)Cl] and their characterization by electronic and ir spectral study and magnetic measurements are reported in this paper.

### Experimental

*Trans*-[Co(en)<sub>2</sub>Cl<sub>2</sub>]Cl<sup>8</sup>, [Co(NH<sub>3</sub>)<sub>5</sub>(NO<sub>2</sub>)Cl]<sup>9</sup> and benzotriazole<sup>6</sup> were prepared by reported methods and 5-nitrobenzotriazole was prepared by a modification of the method for benzotriazole.

[Co(en)<sub>2</sub>(Bt)Cl]Cl (rose red) and [Co(en)<sub>2</sub>(NO<sub>2</sub>-Bt)Cl]Cl (orange red) were obtained by treating an

aqueous solution of [Co(en)<sub>2</sub>Cl<sub>2</sub>]Cl with an aqueous ethanolic solution of benzotriazole and 5-nitrobenzotriazole respectively in 1 : 1 molar ratio and adjusting the pH to 7 with dil. NaOH. [Co(NH<sub>3</sub>)<sub>5</sub>(NO<sub>2</sub>)<sub>2</sub>(Bt)]·H<sub>2</sub>O (orange yellow) and [Co(NH<sub>3</sub>)<sub>5</sub>(NO<sub>2</sub>)<sub>2</sub>(NO<sub>2</sub>-Bt)]·1.5H<sub>2</sub>O (dull orange yellow) were prepared in a similar way from [Co(NH<sub>3</sub>)<sub>5</sub>(NO<sub>2</sub>)Cl]. [Co(en)<sub>2</sub>(Bt)Cl] 1.2H<sub>2</sub>O (orange red) was precipitated by adding a saturated aqueous solution of KI to an aqueous solution of [Co(en)<sub>2</sub>(Bt)Cl]Cl.

Cobalt in the complexes was estimated as cobalt sulphate after igniting the complex and treating the residue with conc. HNO<sub>3</sub> and conc. H<sub>2</sub>SO<sub>4</sub>. Nitrogen was estimated by Duma's semi-micro method. Water of crystallization was determined by heating the complex below 120° and chlorine was estimated as AgCl by decomposing the complex in presence of AgNO<sub>3</sub>. C and H analyses were obtained from microanalytical laboratory.

Magnetic susceptibilities were measured by Guoy method using Hg[Co(CNS)<sub>2</sub>] as standard. Effective magnetic moments were calculated after making diamagnetic correction using Pascal's constants<sup>11</sup>. Conductivity measurements of aqueous solutions were done on a conductivity bridge (Toshniwal, India). Electronic spectra were recorded on a Hilger Watts Uvispek spectrophotometer H700. Infrared spectra (4000-650 cm<sup>-1</sup>) were recorded in KBr discs on a Perkin Elmer spectrophotometer.

### Results and Discussion

*Substitution products from trans*-[Co(en)<sub>2</sub>Cl<sub>2</sub>]Cl : The analytical data of the complexes are reported in Table 1. The complexes are slightly soluble in water but almost insoluble in methanol or ethanol. They are diamagnetic suggesting the presence of octahedral low spin Co(III)<sup>12</sup>. Δ<sub>M</sub> values of freshly prepared 10<sup>-3</sup> M aqueous solutions of [Co(en)<sub>2</sub>(Bt)Cl]Cl and [Co(en)<sub>2</sub>(NO<sub>2</sub>-Bt)Cl]Cl were 125 and 130 ohm<sup>-1</sup> cm<sup>2</sup> mol<sup>-1</sup>, respectively which are in the range of 1 : 1 electrolytes<sup>13</sup>. The conductance gradually increased on standing which may be due to aquation e.g. [Co(en)<sub>2</sub>(Bt)Cl]<sup>+</sup> + H<sub>2</sub>O = [Co(en)<sub>2</sub>(Bt)(H<sub>2</sub>O)]<sup>2+</sup> + Cl<sup>-</sup>.

These complexes show only one weak band around 500 nm (Table 1) except [Co(en)<sub>2</sub>(Bt)Cl]Cl which displays an additional shoulder at 370 nm. The weak band corresponds to <sup>1</sup>A<sub>1g</sub> → <sup>1</sup>T<sub>1g</sub> and the shoulder to <sup>1</sup>A<sub>1g</sub> → <sup>1</sup>T<sub>2g</sub> transition of low spin octahedral Co(III) complexes<sup>14</sup>. Higher λ<sub>max</sub> values for the solid state than for the solution (Table 1) indicate lower symmetry in solid than in solution. *Cis*- and *trans*-isomers of the complexes of the type [CoA<sub>2</sub>BC]<sup>2+</sup> can be differentiated by ε<sub>max</sub> values of these bands<sup>14b</sup>, e.g. ε<sub>max</sub> values of <sup>1</sup>A<sub>1g</sub> → <sup>1</sup>T<sub>1g</sub> bands of *cis*-[Co(en)<sub>2</sub>Cl<sub>2</sub>]<sup>+</sup> and *cis*-[Co(en)<sub>2</sub>(H<sub>2</sub>O)(Cl)]<sup>2+</sup> are 89 and 90 compared to 41 and 40 for the corresponding *trans*-complex<sup>15,16</sup>.

† Author for correspondence. \* BtH = benzotriazole.

TABLE 1—ANALYTICAL RESULTS AND ELECTRONIC SPECTRAL DATA

Complex	Analysis%		${}^1A_{1g} \rightarrow {}^1T_{1g}$ band	
	Calcd	Found	$\lambda_{max}$ (nm)	$\epsilon_{max}$
[Co(en) <sub>3</sub> (Bt)Cl]Cl	Co 16.01	16.11	585 <sup>d</sup>	—
	N 26.74	26.84	500 <sup>a</sup>	117
	Cl 19.26	19.81		
[Co(en) <sub>3</sub> (Bt)Cl]·1.2H <sub>2</sub> O	Co 11.90	12.01	580 <sup>d</sup>	—
	N 19.78	19.81		
	C 24.28	24.41		
	H 4.88	4.91		
	H <sub>2</sub> O 7.27	7.02		
	Co 14.27	14.31	540 <sup>d</sup>	—
[Co(en) <sub>3</sub> (NO <sub>2</sub> -Bt)Cl]Cl	N 27.12	27.18	500 <sup>a</sup>	128
	Cl 17.17	17.05		
	Co 17.42	17.51	470 <sup>d</sup>	—
[Co(NH <sub>3</sub> ) <sub>3</sub> (NO <sub>2</sub> ) <sub>2</sub> Bt]·1.5H <sub>2</sub> O	N 33.13	33.21		
	C 21.25	21.31		
	H 2.56	2.61		
	H <sub>2</sub> O 4.28	4.01		
	Co 14.96	15.02	475 <sup>d</sup>	—
	N 32.07	32.18		

d = diffused reflectance, a = aqueous solution

In the present case, only one isomer has been obtained for each complex and hence such a comparison cannot be made. However, high  $\epsilon_{max}$  values viz., 117 for [Co(en)<sub>3</sub>(Bt)Cl]Cl and 128 for [Co(en)<sub>3</sub>(NO<sub>2</sub>-Bt)Cl]Cl and similarity in the band structure in these complexes with the *cis*-complexes reported earlier<sup>1,5,10</sup> indicate *cis*-configuration in these complexes.

The reported diagnostic splittings of NH<sub>3</sub> deformation, NH<sub>3</sub> rocking<sup>17,18</sup> and also some NH vibration bands<sup>19</sup> cannot be applied in the present case for establishing *cis*- or *trans*-configuration since bands of benzotriazoles interfere in these regions. However, the presence of a large number of bands in the present case and the presence of two -CH<sub>2</sub>- rocking modes, viz., 880 and 898 cm<sup>-1</sup> for [Co(en)<sub>3</sub>(Bt)Cl]Cl and 872 and 890 cm<sup>-1</sup> for [Co(en)<sub>3</sub>(NO<sub>2</sub>-Bt)Cl]Cl may be indicative of *cis*-configuration in these complexes<sup>20,21</sup>.

**Substitution from [Co(NH<sub>3</sub>)<sub>3</sub>(NO<sub>2</sub>)<sub>2</sub>Cl].** These complexes, viz., [Co(NH<sub>3</sub>)<sub>3</sub>(NO<sub>2</sub>)<sub>2</sub>Bt]·H<sub>2</sub>O and [Co(NH<sub>3</sub>)<sub>3</sub>(NO<sub>2</sub>)<sub>2</sub>(NO<sub>2</sub>-Bt)]·1.5H<sub>2</sub>O are insoluble in water, methanol, ethanol, benzene or chloroform. They lose water molecules on heating at 100 without change in colour. They are slightly paramagnetic,  $\mu_{eff}$  = 0.71 B.M. for the former and 0.75 B.M. for the latter. Their residual magnetism may be due to the formation of a little Co(II) or it may be due to second order Zeeman effect<sup>22</sup>.

The  $\nu_{as}$  and  $\nu_s$  of NO<sub>2</sub><sup>-</sup> are observed at 1395 cm<sup>-1</sup> and 1330 (and 1318) cm<sup>-1</sup> for [Co(NH<sub>3</sub>)<sub>3</sub>(NO<sub>2</sub>)<sub>2</sub>(Bt)]·H<sub>2</sub>O and at 1400 cm<sup>-1</sup> and 1332 (and 1308) cm<sup>-1</sup> for [Co(NH<sub>3</sub>)<sub>3</sub>(NO<sub>2</sub>)<sub>2</sub>(NO<sub>2</sub>-Bt)]·1.5H<sub>2</sub>O. The shift in  $\nu_{as}$  of NO<sub>2</sub><sup>-</sup> from 1250 cm<sup>-1</sup> in free ion to ~ 1400 cm<sup>-1</sup> in the complexes suggest N-bonding of NO<sub>2</sub><sup>-</sup><sup>23</sup> which is further confirmed by the absence of the characteristic  $\nu_{as}$  band of nitrito group at 1065 cm<sup>-1</sup><sup>24</sup>. The  $\delta$  (O-N-O), for

these complexes are observed at 811 and 822 cm<sup>-1</sup>, respectively. Further, the observed splitting of the  $\nu_{as}$  band of NO<sub>2</sub><sup>-</sup> may be indicative of *cis*-arrangement of the two NO<sub>2</sub><sup>-</sup> groups in the complexes.

It has not been possible to establish deprotonation of benzotriazoles in these complexes from the ir data because of the presence of N-H vibrations arising from ethylenediamine or ammonia. However, the necessity of alkaline medium for the formation of these complexes, their diamagnetic behaviour and their elemental analyses do confirm deprotonation.

#### References

1. R. F. WILSON and I. J. BAYNE, *J. Inorg. Nuclear Chem.*, 1954, 9, 140; *J. Amer. Chem. Soc.*, 1958, 80, 2652; *Texas J. Sc.*, 1958, 10, 280.
2. I. CAMBI, *Chem. Abs.*, 1956, 50, 5347.
3. R. F. WILSON and C. M. WOMACK, *J. Amer. Chem. Soc.*, 1958, 80, 2065.
4. M. INOUE, M. KISHITA and M. KUBO, *Inorg. Chem.*, 1966, 4, 626.
5. J. A. COMPTON, *Ind. Eng. Chem.*, 1941, 13, 349.
6. R. F. WILSON and I. E. WILSON, *Anal. Chem.*, 1956, 28, 93.
7. S. N. PODDAM and K. RAY, *Indian J. Appl. Chem.*, 1970, 33, 79; *J. Indian Chem. Soc.*, 1973, 50, 891.
8. W. O. FERNANDEZ, (Ed.) "Inorganic Syntheses", McGraw-Hill, 1946, Vol II, p. 223.
9. W. G. PALMER, "Experimental Inorganic Chemistry", University Press, Cambridge, 1954, p. 541.
10. P. W. NEBER, K. HARTUNG and W. RUOFF, *Ber.*, 1925, 58B, 1294.
11. R. G. WILKINS and J. LEWIS, (Eds.), "Modern Coordination Chemistry", Interscience, 1964, p. 403.
12. B. N. FERGUSON and J. LEWIS, "Progress in Inorganic Chemistry", (Ed.), F. A. COTTON, Interscience, 1964, Vol 6, p. 182.
13. A. WILKINSON and A. M. OLATI, *Z. Phys. Chem.*, 1893, 2, 35.
14. A. B. P. LEVINE, "Inorganic Electronic Spectroscopy", Elsevier, 1968, (a) 111, (b) 308.
15. M. LINHARD and M. WEIGEL, *Z. Anorg. Allgem. Chem.*, 1951, 266, 49.

16. L. MOGGI, N. SABATINI and V. BALZANI, *Gazz. Chim. Ital.*, 1967, 97, 1980
17. P. E. MERRITT and S. E. WISELEY, *J. Phys. Chem.*, 1955, 59, 55
18. M. L. MORRIS and D. H. BUSCH, *J. Amer. Chem. Soc.*, 1960, 82, 1621.
19. M. M. CHAMBERLAIN and J. C. BALLAR, Jr., *J. Amer. Chem. Soc.*, 1959, 81, 6412.
20. M. E. BALDWIN, *J. Chem. Soc.*, 1960, 4869
21. S. K. MANDAN and J. PEON, *Inorg. Chem.*, 1967, 6, 468.
22. R. W. ARMUSSEN and O. J. BALLEHAUSEN, *Acta Chem. Scand.*, 1957, 11, 479.
23. K. NAKAMOTO, "Infrared and Raman Spectra of Inorganic and Coordination Compounds", 3rd Edn., Wiley Interscience, 1978, p. 828
24. (a) R. B. PETLAND, T. J. LANE and J. V. QUAGLIANO, *J. Amer. Chem. Soc.*, 1956, 78, 888.  
(b) K. NAKAMOTO, J. FUJITO and H. MORATO, *J. Amer. Chem. Soc.*, 1958, 80, 4817

### Mixed Ligand Complexes of Co(II), Ni(II), Cu(II) and Zn Salts with *o*-Hydroxy Propiophenone and Quinoline

R. N. ROY

Department of Chemistry, Govt. College, Augul,

S. B. MISHRA

Department of Chemistry, Ravenshaw College, Cuttack-753 009

and

B. K. MOHAPATRA\*

Department of Chemistry, B. J. B. College, Bhubaneswar-751 014

Manuscript received 19 May 1981, revised 23 February 1982,  
accepted 8 July 1982

**C**HEMISTRY of metal  $\beta$ -diketonates has invoked<sup>1</sup> lot of interest in recent years in such diverse areas as spectral studies, gas chromatography, nmr shift reagents, laser technology and as radical initiators in polymerization reactions. The formation of adducts of metal  $\beta$ -diketone chelates plays an important role in the synergistic enhancement of solvent extraction of metal ions.  $\beta$ -Keto esters and *o*-hydroxy carbonyl compounds closely resemble the  $\beta$ -diketones. It was thought worthwhile to study the reactions of metal salts with *o*-hydroxy propiophenone and quinoline. As a result, this communication reports chelates of *o*-hydroxy propiophenone and their adducts with quinoline.

### Experimental

**Complexes of the type  $MLXQ$  or  $M'LXQ$ :** Absolute ethanolic solution of metal salts was treated with *o*-hydroxy propiophenone and quinoline in 1 : 1 : 1 proportion and the resulting solution refluxed for 30 min. To this solution, dilute ammonium hydroxide was added dropwise under constant stirring till the pH was 7. The resulting precipitates were filtered, washed with ethanol and ether and dried in vacuum.

\* Author for correspondence.

**Complexes of the type  $ML_2Q_2$  or  $M'L_2Q_2$ :** Aqueous solutions of metal acetates were treated with ethanolic solution of *o*-hydroxy propiophenone in 1 : 2 proportion and the mixture stirred for 30 min at 40°. Metal chelates were filtered, washed with ethanol and ether and dried in vacuum. Ethanolic suspension of different metal chelates was treated with quinoline in 1 : 2 ratio and the resulting solution refluxed for 30 min. On concentrating the solution in a rotary vacuum evaporator and keeping at 10° overnight crystalline base adducts separated. These were filtered, washed with ethanol and dried in vacuum.

Analyses and physical measurements were done as reported earlier<sup>2</sup>. The relevant analytical data are presented in Table 1 and the spectral data in Table 2.

### Results and Discussion

In the infrared spectra of hydroxy propiophenone  $\nu(C=O)$  is observed<sup>3</sup> at 1620 and  $\nu(O-H)$  at 3350  $cm^{-1}$ . In monochelate complexes,  $\nu(C=O)$  shifts to lower frequency region and is observed around 1600  $cm^{-1}$  whereas  $\nu(O-H)$  disappears. Thus the ligand anion forms the chelate using both the oxygen atoms. This has been substantiated by the observation<sup>4</sup> of  $\nu(M-O)$ ,  $\nu(M-N)$  and  $\nu(M-Cl)$  around 440-460, 320-335 and 230-250  $cm^{-1}$  region, respectively. Thus, these are four coordinated compounds involving the mono chelate, the coordinated anion and coordinated quinoline. In the nitrato complexes, the position of  $\nu_2$  and  $\nu_1$  (1410 and 1280  $cm^{-1}$ ) of  $NO_3$  and their difference of the order of 130  $cm^{-1}$  suggest<sup>5,6</sup> monodentate nitrate coordination.

In the *bis* chelates  $\nu(C=O)$  is found around 1590-1600  $cm^{-1}$  which shifts to slightly higher frequency region in the base adducts. The formation of the base adducts of the *bis* chelates has been confirmed<sup>4</sup> by the appearance of  $\nu(M-O)$  and  $\nu(M-N)$  around 460 and 320  $cm^{-1}$  region in the far infrared spectra.

In the visible region, cobalt mono chelate complexes give rise to one intense absorption band around 16.0 kK region assignable<sup>7</sup> to  ${}^4A_g \rightarrow {}^4T_1(P)$  transition. Position of the band, its high intensity and lower magnetic moment value suggest a possible tetrahedral configuration for these complexes. The base adduct of the *bis* chelate complex gives rise to two absorption bands at 18.8 and a shoulder at 19.5 kK assignable to  ${}^4T_{1g}(F) \rightarrow {}^4T_{1g}(P)$  transition. On the basis of the band positions and magnetic moment values an octahedral configuration is proposed for the complex.

Nickel(II) mono chelate complexes are diamagnetic and show one absorption band at 16.5 kK, presumably indicating a square planar configuration for these two complexes, whereas the base adduct of the nickel(II) *bis* chelate gives rise to three absorption bands at 9.5, 13.8 and 24.4 kK

TABLE 1—ANALYTICAL DATA OF MIXED LIGAND COMPLEXES

Compound	Colour	$\Delta M$ mhos $\text{cm}^{-1}$	Analysis %			$\mu_{\text{eff}}$ B.M.
			O Found (Calcd.)	H Found (Calcd.)	N Found (Calcd.)	
1. $\text{CoLClQ}$	Blue	10.5	57.85 (57.99)	4.01 (4.80)	3.56 (3.76)	4.5
2. $\text{CoL}(\text{NO}_3)\text{Q}$	Blue	8.4	54.19 (54.14)	4.18 (4.01)	5.82 (7.03)	4.6
3. $\text{CoL}_2\text{Q}_2$	Pink	11.6	70.02 (70.25)	5.38 (5.20)	4.31 (4.55)	5.0
4. $\text{NiLClQ}$	Red	10.2	58.24 (58.03)	4.06 (4.80)	3.65 (3.76)	Diamag.
5. $\text{NiL}(\text{NO}_3)\text{Q}$	Red	8.8	54.35 (54.17)	4.22 (4.01)	6.84 (7.02)	Diamag.
6. $\text{NiL}_2\text{Q}_2$	Green	6.5	70.08 (70.27)	5.26 (5.21)	4.22 (4.55)	8.1
7. $\text{CuLClQ}$	Brown	10.4	58.22 (58.05)	4.21 (4.80)	3.68 (3.76)	1.82
8. $\text{CuL}(\text{NO}_3)\text{Q}$	Brown	12.5	54.41 (54.2)	4.15 (4.01)	6.76 (7.08)	1.80
9. $\text{CuL}_2\text{Q}_2$	Blue	11.8	65.92 (65.04)	4.98 (5.09)	2.68 (2.85)	1.79
10. $\text{ZnLClQ}$	White	9.8	57.14 (57.01)	4.11 (4.22)	3.58 (3.69)	—
11. $\text{ZnL}(\text{NO}_3)\text{Q}$	White	9.9	53.2 (53.28)	3.86 (3.95)	6.81 (6.91)	—
12. $\text{ZnL}_2\text{Q}_2$	White	7.5	65.66 (65.80)	5.11 (5.07)	2.64 (2.84)	—

L=anion of 2-hydroxy propiophenone, Q=quinoline

TABLE 2—SPECTRAL DATA OF MIXED LIGAND COMPLEXES

Compound No.	Infrared spectra $\text{cm}^{-1}$				Electronic spectra $\mu_{\text{max}}$ in kK (e)
	$\nu(\text{C}=\text{O})$	$\nu(\text{M}-\text{O})$	$\nu(\text{M}-\text{N})$	$\nu(\text{M}-\text{Cl})$	
1.	1600	440	320	230	16.0(900)
2.	1590	450	325	235	16.1(900)
3.	1595	445	320	235	18.8(95), 19.5
4.	1600	445	325	240	15.5(55)
5.	1605	440	320	235	15.3(50)
6.	1600	450	320	230	9.5(6), 18.8(14), 24.4(16)
7.	1595	460	325	250	17.3(35)
8.	1590	455	320	250	17.0(30)
9.	1590	460	325	245	15.5(60)
10.	1600	460	320	245	—
11.	1605	455	325	250	—
12.	1600	450	320	250	—

attributable<sup>8</sup> to  $^3A_{1g} \rightarrow ^3T_{2g}(\text{F})$ ,  $\rightarrow ^3T_{1g}(\text{F})$  and  $\rightarrow ^3T_{1g}(\text{P})$  transitions, respectively. Position of spectral bands and magnetic moment value suggest an octahedral configuration for these complexes.

Monochelate complexes of copper(II) give rise to a broad band around 17.3 kK region indicating probably a four coordinated square planar configuration<sup>9</sup> for these complexes. Mono base adducts of the *bis* chelate of copper(II) also give rise to one broad band at 15.5 kK. On comparison with the spectra of *bis* chelate the band has shifted slightly to low frequency region and there is an increase in intensity of the absorption band. Hence the complex may be presumed to be penta-coordinated on the basis of earlier observations<sup>10-12</sup> on the mono base adducts of  $\beta$ -diketonato complexes of copper(II).

## References

1. K. C. JOSHI and V. N. PATHAK, *Coordn. Chem. Rev.*, 1977, 22, 87.
2. A. K. JENA and B. K. MOHAPATRA, *J. Indian Chem. Soc.*, 1976, 53, 424.
3. R. M. SILVERSTEIN and G. C. BASSELER, "Spectrometric Identification of Organic Compounds", John Wiley, New York, 1968.
4. J. R. FERRARO, "Low Frequency Vibrations of Inorganic and Coordination Compounds", Plenum Press, New York, 1971.
5. R. V. BIRAGETI, W. C. BOTJER and H. M. HAENDLER, *Inorg. Chem.*, 1966, 5, 879.
6. A. B. P. LEVER, *Inorg. Chem.*, 1965, 4, 1042.
7. B. N. FIGGIS, "An Introduction to Ligand Fields", Wiley Eastern, New Delhi, 1976.
8. A. B. P. LEVER, "Inorganic Electronic Spectroscopy", Elsevier, Amsterdam.
9. O. A. AGAMBER and K. G. ORRISI, *J. Chem. Soc.*, 1969, 80.
10. T. SHIGEMATSU, M. TABUSKI, M. MATSUI and M. MUKUNATA, *Bull. Chem. Soc. Japan*, 1958, 41, 2656.
11. P. E. BAKITA, S. J. KOPPEL and J. P. FACHLER, Jr., *J. Inorg. Nuclear Chem.*, 1958, 30, 2189.
12. D. F. GRADON and E. C. WATSON, *J. Inorg. Nuclear Chem.*, 1961, 21, 49.

# Infrared Spectra and Thermal Studies of Some Reported Heteropoly Complexes

S. K. ROY and P. P. JHA

Department of Chemistry, Ranchi University, Ranchi-8

Manuscript received 6 March 1981, revised 27 January 1982,  
accepted 8 July 1982

In this short communication thermal behaviour and infrared spectral analysis of five different heteropoly complexes namely, ammonium-12 heteropoly vanadomolybdate,  $(\text{NH}_4)_{10}[\text{MoV}_{12}\text{O}_{40}] \cdot 20\text{H}_2\text{O}$ , ammonium-6 heteropoly vanadotungstate,  $(\text{NH}_4)_6[\text{WV}_6\text{O}_{20}] \cdot 11\text{H}_2\text{O}$ , potassium-6 heteropoly vanadomolybdate,  $\text{K}_6[\text{MoV}_6\text{O}_{18}] \cdot 11\text{H}_2\text{O}$ , ammonium-10 heteropoly vanadocobaltate,  $(\text{NH}_4)_4[\text{CoV}_{10}\text{V}_{10}] \cdot 18\text{H}_2\text{O}$  and ammonium-12 heteropoly vanadoantimonate,  $(\text{NH}_4)_4[\text{SbV}_{12}\text{O}_{40}] \cdot 2\text{H}_2\text{O}$  have been discussed.

The compounds have been synthesised and analysed as reported earlier<sup>1-4</sup>. Thermal stability studies on the heteropoly compounds prepared were conducted<sup>5,6</sup> by thermogravimetric analysis (tga), differential thermal analysis (dta) and by heating at fixed temperatures followed by solubility determinations of the heated materials to ascertain decomposition. All dta and tga experiments were done at a heating rate of 5°/min. The heating at fixed temperatures was performed in air in a muffle furnace. To ascertain decomposition due to heating, the heated sample (2-3 g) was placed in 50 ml of water and stirred for 0.5 hr. Degree of insolubility of sample was taken as measure of stability. The weight loss employed to calculate the amount of water or ammonia lost was based on static heating experiments rather than tga results. The former were considered to be more accurate since larger samples weighing 2 to 3 g were taken. Complete analysis of the compound was carried out after the decomposition temperature to ascertain the final decomposition of the compounds into the lower oxides of the constituent atoms. All tga data on heteropoly vanadates and heteropoly molybdates show weight loss above 650° but this corresponds to slow volatilization of vanadium pentoxide and molybdenum trioxide, respectively.

Ammonium-12 vanadomolybdate is stable at 300° as is shown by its complete solubility in water. The dta data for this hydrate show unresolved endotherms from 25 to 245°. This correlates well with the tga data where the bulk of water as well as ammonia is lost upto this point. From thereon, the compound slowly decomposes by losing water or ammonia. At 350°, the compound is partly stable but the change is complete at 400° where the heteropoly complex breaks completely by losing 4 moles of water (or ammonia). Breakage of the heteropoly cage is confirmed by chemical analysis as well as the dta data which show exotherms at 400-420°.

Ammonium-6 vanadotungstate loses all its water of hydration and ammonia till 300°. The

heteropoly cage  $[\text{WV}_6\text{O}_{20}]^{4-}$  is stable at this temperature as it is completely soluble in water. This heteropoly complex breaks at 350° as is shown by its complete insolubility in water. DTA data corroborate the above result. Thermal stability of potassium-6 vanadomolybdate tallies closely with ammonium-6 vanadotungstate.

Ammonium-10 vanadocobaltate loses bulk of its water and ammonia till 200°. The static heating experiments for this salt show a loss of 20%. The tga results show a loss of 19.9% between 25 and 200°, the theoretical being 20.3% corresponding to the loss of 16 molecules of water or ammonia. Between 200 and 400° there is a plateau in the tga showing little loss of weight. A sudden break in tga curve near 400° shows a loss of 7.5% against the theoretical loss of 7.9% corresponding to the loss of 6 molecules of water or ammonia. The heteropoly complex also breaks at 400° as confirmed by dta data showing exotherms at 390-415°.

Ammonium-12 vanadoantimonate loses all its water of hydration as well as ammonia till 400° and it breaks at 450°. So, the thermal stability of the heteropoly cage  $[\text{SbV}_{12}\text{O}_{40}]^{7-}$  is 400°. The ammonium salts can lose ammonia as well as water and thermal analysis alone cannot distinguish this possibility<sup>7</sup>.

Infrared spectra of some heteropoly compounds have been examined by Tsigdinos<sup>8</sup>, Brown<sup>9</sup> and Sharpless *et al.*<sup>10</sup>. Infrared spectra of the above mentioned heteropoly compounds in KBr pellets have been recorded from 4000 to 400  $\text{cm}^{-1}$  on a grating IR spectrophotometer, Perkin-Elmer Model 577. Results are given in Table 1. The peaks at 3500-3300 and 3180-3130  $\text{cm}^{-1}$  region (antisymmetric and symmetric O-H stretching mode<sup>11</sup>) correspond to those of water<sup>12</sup>. The peaks at 1620-1600  $\text{cm}^{-1}$  are also attributed to water (H-O-H bending mode<sup>12</sup>). Lattice water also absorbs in the lower frequency region (600-300  $\text{cm}^{-1}$ ) owing to librational modes<sup>13,14</sup>. The sharp peaks at 1420-1390  $\text{cm}^{-1}$  may be attributed to the presence of N-H bond<sup>14</sup>. Deformative frequency of the ammonium ion is also known to be active in 3300-3100  $\text{cm}^{-1}$  region. So, the broad bands shown by these compounds in the 3500-3100  $\text{cm}^{-1}$  region may be due to lattice water as well as ammonium ion. Probable assignments<sup>15-17</sup> for other peaks are 1000-900  $\text{cm}^{-1}$  (sharp) for M-O and 800-750  $\text{cm}^{-1}$  due to M-O-M bridging (M=V, Mo or W). In the case of interacted heteropoly complexes of V, Mo and W, the absorption due to central metal octahedron may be masked by the absorption of metal oxygen linkage of the surrounding metal octahedra. Absorption due to Co-O linkage has been reported<sup>18</sup> in the lower frequency region 450-430  $\text{cm}^{-1}$ . So, in the case of  $(\text{NH}_4)_4[\text{CoV}_{10}\text{O}_{40}] \cdot 18\text{H}_2\text{O}$ , the broad band at 442  $\text{cm}^{-1}$  may be due to Co-O absorption of the central octahedron as well as lattice water. Sb-O absorbs below 400  $\text{cm}^{-1}$  and therefore could not be observed in the ir. Infrared spectra of the ignited

TABLE 1—INFRARED ABSORPTION FREQUENCIES (cm<sup>-1</sup>) OF HETEROPOLY COMPOUNDS

(NH <sub>4</sub> ) <sub>10</sub> [MoV <sub>10</sub> O <sub>38</sub> ]20H <sub>2</sub> O	3430b 3140b	1615m	1400s	985s 915s	800s 715s	560s 410m
Ignited sample (400°)	—	—	—	910s 890s	—	—
(NH <sub>4</sub> ) <sub>8</sub> [WV <sub>8</sub> O <sub>28</sub> ]11H <sub>2</sub> O	3445b 3170b	1605b	1405b	975s 980s	840b 755m	600s 410s
Ignited sample (850°)	—	—	—	910s 940s	—	—
K <sub>2</sub> [MoV <sub>8</sub> O <sub>28</sub> ]11H <sub>2</sub> O	3440s	1610m	—	940s	805s 730s	580s
Ignited sample (350°)	—	—	—	910s	—	—
(NH <sub>4</sub> ) <sub>8</sub> [CoV <sub>8</sub> O <sub>28</sub> ]18H <sub>2</sub> O	3180b	1615m	1410m	960s	850b 780b	600b 442b
Ignited sample (400°)	—	—	—	990	—	442s
(NH <sub>4</sub> ) <sub>7</sub> [SbV <sub>10</sub> O <sub>38</sub> ]28H <sub>2</sub> O	3435b 3175b	—	1390s	1000s 975s	745s	600s 455m
Ignited sample (450°)	—	—	—	915s 945s	—	—

s = sharp, m = medium, b = broad.

samples were also taken. The decomposition temperature of the heteropoly complexes was taken as the ignition temperature. The peaks, characteristic of lattice water as well as ammonium ion were not found. The observed peaks confirmed the breakage of heteropoly complexes into the lower oxides of their constituent atoms.

## References

1. S. K. ROY and P. P. JHA, *Indian J. Chem.*, 1980, **19A**, 919
2. G. C. BHATTACHARYA and S. K. ROY, *J. Indian Chem. Soc.*, 1979, **56**, 1027.
3. S. K. ROY and P. P. JHA, *J. Indian Chem. Soc.*, 1979, **56**, 1027.
4. S. K. ROY and P. P. JHA, *J. Indian Chem. Soc.*, 1980, **57**, 282.
5. A. PERLOFF, *Inorg. Chem.*, 1970, **9**, 2228
6. C. M. FLYNN and M. T. POPE, *J. Amer. Chem. Soc.*, 1970, **92**, 85.
7. C. DUVAL, "Inorganic Thermogravimetric Analysis", Elsevier Publishing Company, Amsterdam, London, New York, 1968, p. 245
8. G. A. TSIGDINOS and C. J. HALLADA, *J. Inorg. Chem.*, 1968, **7**, 437.
9. D. H. BROWN, *Spectrochim. Acta*, 1962, **19**, 585.
10. N. E. SHARPLESS and J. S. MUNDAY, *Anal. Chem.*, 1957, **29**, 1619.
11. P. J. LUCCHESI and W. A. GLASSON, *J. Amer. Chem. Soc.*, 1956, **78**, 1347.
12. K. NAKAMOTO, "Infrared Spectra of Inorganic and Coordination Compounds", John Wiley & Sons, 1968, p. 107
13. J. VANDER ELSEN and D. W. ROBINSON, *Spectrochim. Acta*, 1961, **17**, 1249.
14. J. W. WADDINGTON, *J. Amer. Chem. Soc.*, 1958, **80**, 4340.
15. K. NAKAMOTO, Y. MORIMOTO and A. E. MARTELL, *J. Amer. Chem. Soc.*, 1961, **83**, 4533.
16. H. SIEBERT, *Z. Anorg. Allgem. Chem.*, 1954, **275**, 225.
17. G. A. TSIGDINOS, "Heteropoly Compounds", Method Chim. (Eng. Edn.), Academic Press, New York, 1976, Vol. 8, Chap. 82.
18. J. FUJITA, A. E. MARTELL and K. NAKAMOTO, *J. Phys. Chem.*, 1969, **36**, 834, 831.

### Potential Local Anaesthetic Agents. Part-III · Alkylaryl aminoacetyl-2-aminothiazoles and Benzimidazoles

J. S. UPADHYAYA\*, P. K. SRIVASTAVA

and

R. D. SHARMA (LATE)

Surgical Research Laboratories, Institute of Medical Sciences,  
Banaras Hindu University, Varanasi-221 005Manuscript received 6 February 1981, revised 1 December 1981,  
accepted 7 June 1982

THE essential structural requirements for anaestheticophore group in local anaesthetics seems to be a lipophilic moiety containing an aromatic nucleus, an intermediate alkyl or aryl substituted chain and a hydrophilic end consisting of a tertiary amino group<sup>1-4</sup>. The thiazole and imidazole groups are of great importance in biological systems<sup>5-10</sup>. The title compounds appear to possess all the necessary structural requirements for local anaesthetic agent. Therefore, it was thought worthwhile to synthesise some alkylaryl-aminoacetyl-2-aminothiazoles and benzimidazoles by the condensation of chloroacetylchloride with 2-aminothiazole/benzimidazole followed by treatment with various primary and secondary amines.

The structures of these compounds have been established on the basis of their analysis and infrared spectrum. IR spectra of these compounds show characteristic strong absorption peaks at 1650-1625 cm<sup>-1</sup> and 1370-1360 cm<sup>-1</sup> corresponding to C=O and C-N bands, respectively. An

\*Author for correspondences, Present Address: Institute of Paper Technology, (University of Roorkee), Saharanpur-247 001.

absorption band at 3200-3150  $\text{cm}^{-1}$  indicates the NH stretching frequency. A strong absorption peak in the region 1700-1670  $\text{cm}^{-1}$  is attributed to secondary amide band.

### Experimental

Chloroacetyl-2-aminothiazole/benzimidazole were prepared by known methods<sup>8</sup>.



**Preparation of dimethylaminoacetyl-2-aminothiazole / N-methylanilinoacetyl-2-aminobenzimidazole:** Equimolar quantities of dimethylamine/N-methylaniline and chloroacetyl-2-aminothiazole/chloroacetyl-2-aminobenzimidazole in ethanol were mixed together with constant stirring. After the addition, the reaction mixture was refluxed for 6 hr and the excess of ethanol was distilled off. Residue, on washing with sodium bicarbonate and crystallisation from dilute ethanol afforded the title compounds. The homogeneity of these compounds were tested by tlc studies. The percentage yield and melting point of the compounds are reported in Table 1.

These bases were converted into the corresponding hydrochlorides by passing dry hydrogen chloride gas in ethereal solution.

Adopting a similar procedure, various alkylaryl-amine acetyl-2-aminothiazoles and benzimidazoles have been prepared by the condensation of chloroacetyl-2-aminothiazole/chloroacetyl-2-aminobenzimidazole with different amines.

**Biological screening results:** The compounds prepared were investigated for their local anaesthetic activity—surface anaesthesia in rabbit cornea<sup>11</sup>, infiltration anaesthesia in guinea pig<sup>12</sup> and conduction anaesthesia<sup>13</sup> on frog (*Rana tigrina*). The results of preliminary studies are recorded in Table 2. Procaine hydrochloride was used as the standard drug. The screening results indicate that all the compounds except compounds no. 2, 6, 10 and 14 were moderately active when tested as surface anaesthetic at concentration 2 to 2.5% in 0.7% saline. However, compounds no. 1, 4, 5, 11, 13 and 14 were found to be inactive when tested as infiltration anaesthetic at the same concentration, whereas compounds no. 17 and 18 showed

TABLE 1—ALKYLARYLAMINOACETYL-2-AMINOTHIAZOLES AND ALKYLARYLAMINOACETYL-2-AMINO BENZIMIDAZOLES

$X-NHCOCH_2-N \begin{matrix} \nearrow R_1 \\ \searrow R_2 \end{matrix} \quad (R_1 \neq R_2)$						
Sl. No.	Compounds*		Yield %	m p. °C	Formula	Hydrochloride m.p. °C
	X	R <sub>1</sub> (or H) R <sub>2</sub>				
1.		Diallyl	75	180	C <sub>11</sub> H <sub>11</sub> N <sub>2</sub> OS	215-17
2.	..	Dimethyl	70	188	C <sub>7</sub> H <sub>11</sub> N <sub>2</sub> OS	189-91
3.	..	Diisopropyl	65	118	C <sub>21</sub> H <sub>33</sub> N <sub>2</sub> OS	185-87
4.	..	N-methylaniline	70	90	C <sub>10</sub> H <sub>11</sub> N <sub>2</sub> OS	218-16
5.	..	Pyridyl	75	106	C <sub>10</sub> H <sub>10</sub> N <sub>2</sub> OS	221-22
6.	..	Pyrimidino	60	135	C <sub>8</sub> H <sub>8</sub> N <sub>2</sub> OS	192-94
7.	..	N,N-dimethyl anilino-p-	75	82	C <sub>13</sub> H <sub>15</sub> N <sub>2</sub> OS	201-08
8.	..	Piperidino	70	87	C <sub>10</sub> H <sub>13</sub> N <sub>2</sub> OS	224-26
9.	..	Piperizino	68	65	C <sub>9</sub> H <sub>11</sub> N <sub>2</sub> OS	205-07
10.	..	Morpholino	60	70	C <sub>8</sub> H <sub>11</sub> N <sub>2</sub> O <sub>2</sub> S	195-97
11.		Diallyl	80	120	C <sub>12</sub> H <sub>11</sub> N <sub>4</sub> O	185-87
12.	..	Dimethyl	75	125	C <sub>11</sub> H <sub>14</sub> N <sub>4</sub> O	241-42
13.	..	Diisopropyl	68	107	C <sub>21</sub> H <sub>29</sub> N <sub>4</sub> O	288-35
14.	..	N-methylaniline	65	98	C <sub>11</sub> H <sub>12</sub> N <sub>4</sub> O	197-99
15.	..	Pyridyl	76	92	C <sub>11</sub> H <sub>11</sub> N <sub>4</sub> O	208-06
16.	..	Pyrimidino	60	85	C <sub>9</sub> H <sub>11</sub> N <sub>4</sub> O	217-19
17.	..	N,N-dimethyl-anilino-p-	68	101	C <sub>17</sub> H <sub>19</sub> N <sub>4</sub> O	235-37
18.	..	Piperidino	70	135	C <sub>14</sub> H <sub>19</sub> N <sub>4</sub> O	176-77
19.	..	Piperizino	75	117	C <sub>13</sub> H <sub>17</sub> N <sub>4</sub> O	187-89
20.	..	Morpholino	62	79	C <sub>12</sub> H <sub>17</sub> N <sub>4</sub> O <sub>2</sub>	179-81

\* Elemental analyses results for C, H, N and S for these compounds are within  $\pm 0.5\%$  of the theoretical values.



TABLE 2—BIOLOGICAL SCREENING RESULTS OF ALKYLARYLAMINOACETYL-2-AMINOTHIAZOLES AND ALKYLARYLAMINOACETYL-2-AMINOBENZIMIDAZOLES AS LOCAL ANAESTHETIC

Compound No.	Surface anaesthesia			Infiltration anaesthesia			Conduction anaesthesia			
	Conc. of drug (%)	Intensity	Duration (min)	Conc. of drug (%)	Intensity	Duration (min)	Conc. of drug (%)	Onset of anaesthesia (min) in HCl of strength		
								0.5 N	0.1 N	0.2 N
1.	2	complete	3	0.2	nil	—	0.2	20	21	21
2.	2	nil	—	0.2	partial	8	—	—	—	—
3.	2	partial	8	0.2	complete	10	0.2	18	19	19
4.	2.5	complete	10	—	—	—	—	—	—	—
5.	2	complete	14	0.2	nil	—	0.2	16	16	17
6.	2	partial	6	0.2	nil	—	0.2	20	20	21
7.	2.5	complete	8	—	—	—	—	—	—	—
8.	2	nil	—	0.2	complete	9	0.2	28	24	24
9.	2	complete	22	0.2	complete	16	0.2	9	10	10
10.	2	complete	18	0.2	partial	5	0.2	13	15	16
11.	—	—	—	0.25	complete	7	—	—	—	—
12.	2	partial	12	0.2	complete	12	0.2	10	11	12
13.	2.5	complete	14	—	—	—	—	—	—	—
14.	2	nil	—	0.2	complete	8	0.2	5	6	7
15.	2	complete	4	0.2	nil	—	0.2	17	18	19
16.	2	partial	4	0.2	complete	3	0.2	20	22	22
17.	2.5	complete	5	—	—	—	—	—	—	—
18.	2	complete	7	0.2	nil	—	0.2	9	10	10
19.	2	nil	—	0.1	nil	—	0.2	19	20	20
20.	—	—	—	0.2	nil	—	—	—	—	—
21.	2	partial	2	0.1	partial	4	0.2	27	29	29
22.	2.5	complete	4	0.2	complete	6	—	—	—	—
23.	2	complete	8	0.2	complete	5	0.2	31	32	33
24.	2	complete	20	0.2	complete	37	0.2	7	8	8
25.	2	complete	19	0.2	complete	20	0.2	10	11	12
26.	2	partial	13	0.1	partial	10	0.2	12	13	13
27.	2.5	complete	15	0.2	complete	12	—	—	—	—
28.	2	complete	10	0.2	complete	10	0.2	16	17	17
Procaine hydrochloride (Standard)	2	complete	15	0.2	complete	12	0.2	15	16	17

maximum activity with duration of infiltration anaesthesia on frog. Compounds no 7, 8, 17 and 18 were found to be more active than the standard drug when tested as surface anaesthetic. In comparison to the standard drug, the compounds no. 4 and 20 were found to be equally active, compounds no. 1, 2, 5, 6, 11, 12 and 14 slightly more active and compounds no. 15 and 16 were observed to be most active.

#### Acknowledgement

The authors are thankful to C S.I.R., New Delhi for financial assistance.

#### References

1. F. F. BLICK and H. C. PARK, *J. Amer. Chem. Soc.*, 1939, **61**, 1200.
2. A. M. MATTOCKS and O. S. HUTCHINSON, *J. Amer. Chem. Soc.*, 1948, **70**, 8474.
3. P. N. BHARGAVA and G. C. SINGH, *J. Indian Chem. Soc.*, 1961, **38**, 77.
4. N. LOFGREN, *Ark. Kemi. Min. Geol.*, 1946, **22A** nr. 18, *Chem. Abs.*, 1949, **43**, 1031.
5. P. K. SRIVASTAVA and P. N. SRIVASTAVA, *J. Med. Chem.*, 1970, **13**, 804, 977.
6. J. S. UPADHYAYA, P. K. SRIVASTAVA and B. D. SHARMA, *Ind. J. Pharm. Sci.*, 1977, **39**, 56.
7. J. S. UPADHYAYA, S. P. SRIVASTAVA and M. P. SHARMA, *Ind. J. Pharm. Sci.*, 1980, **42**, 88.
8. J. S. UPADHYAYA, *Ind. J. Pharm. Sci.*, 1980, **42**, 188.
9. J. S. UPADHYAYA and P. K. SRIVASTAVA, *J. Indian Chem. Soc.*, 1981, **58**, 789.
10. I. A. KAYE, T. VITALI and B. LOWITZ, in a review on "The Design of Local Anaesthetic" in "Drug Design", (Ed.) Ariens, Vol. III, Chap. 6, p. 288.
11. T. BOLLMANN, *J. Pharmacol.*, 1918, **11**, 17.
12. E. BULBRING and I. WAJDA, *J. Pharmacol. Exp. Ther.*, 1945, **85**, 78.

#### Studies on Antitubercular Agents. Part-III : Preparation of Some *p*-(2,4-Diarylamino-6-S-Triazinylamino)-Benzaldehyde/ Acetophenone Thiosemicarbazones as Potential Tuberculostatic Agents

N. A. LANGALIA and K. A. THAKER


University Department of Chemistry, Bhavnagar University, Bhavnagar-364 002

Manuscript received 9 June 1981, revised 19 December 1981, accepted 1 May 1982

LITERATURE reveals that a number of studies have been carried out on the antileprotic and antitubercular activity of thiosemicarba-

zones<sup>1-3,17,20</sup>. The thiosemicarbazones of aromatic aldehydes in general possess potential drug activity. The study of structure-activity relationship suggests that the presence of substituent in benzene ring increases the *in vitro* tuberculostatic activity but only *p*-substituted benzaldehyde thiosemicarbazones have significant *in vivo* activity<sup>9-16</sup>. Further, *s*-triazine derivatives have wide spectrum of biological activity<sup>19-27</sup>. It was therefore thought that incorporation of 2,4-diaryl-amino-6-*s*-triazinyl moiety into *p*-aminobenzaldehyde/acetophenone thiosemicarbazones might modify their tuberculostatic activity.

The synthetic sequence of the title compounds is outlined in Scheme 1.



Scheme 1

## Experimental

**Preparation of 2,4-diaryl-amino-6-chloro-*s*-triazine (II):** These were prepared by reported method<sup>19-21</sup>.

**Preparation of *p*-(2,4-diaryl-amino-6-*s*-triazinyl-amino)-acetophenone (III):** To a solution of *p*-aminoacetophenone (0.01 mole) in dioxane (10 ml) was added a solution of appropriate II (0.01 mole) in dioxane (15 ml) at 80°. The solution heated at 85-90° for 2 hr with the simultaneous addition of NaOH (aqueous 10%; 4 ml) and poured on water, filtered, washed with water, dried and recrystallised from ethanol (95%).

**Preparation of 2,4-diaryl-amino-6-(4-carbomethoxyanilino)-*s*-triazine (IV):** Methyl-*p*-aminobenzoate (0.015 mole) and appropriate II (0.015 mole) were separately dissolved in dioxane (25 ml) and mixed at 80°. The solution refluxed for 2 hr with the

simultaneous dropwise addition of NaOH (aqueous 10%; 6 ml), the contents poured on ice, filtered, washed repeatedly with water and recrystallised from ethanol (95%).

**Preparation of *p*-(2,4-diaryl-amino-6-*s*-triazinyl-amino)-benzoyl *p*-toluenesulfonyl hydrazide (V):** The ethanolic solution of IV (0.012 mole) and *p*-toluenesulfonylhydrazide (0.0122 mole) was refluxed for 3.5 hr and allowed to cool to room temperature (25°) and filtered. The product so obtained was washed with boiling water and recrystallised from ethanol (95%). The ir spectra of V show strong bands in the 1180-1150, 1340-1305  $\text{cm}^{-1}$  regions.

**Preparation of *p*-(2,4-diaryl-amino-6-*s*-triazinyl-amino)-benzaldehyde thiosemicarbazone (VI):** Thiosemicarbazide (0.01 mole) and appropriate V (0.008 mole) were dissolved in a mixture of ethylene glycol and water (3:1) containing NaOH (10%; 10 ml). The solution heated at 90-95° for 2.5 hr and poured on ice, rendered acidic with 1 N HCl, filtered, washed with water and recrystallised from ethanol (95%).

**Preparation of *p*-(2,4-diaryl-amino-6-*s*-triazinyl-amino)-acetophenone thiosemicarbazone (VII):** Usual condensation of thiosemicarbazide and III in EtOH furnished VII which were recrystallised from ethanol (95%).

The physical data of the compounds are recorded in Tables 1 and 2. The ir spectra of VI and VII show strong bands in the 1660-1630, 1500-1470, 1380-1360 and 1220-1205  $\text{cm}^{-1}$  regions.

**Antimycobacterial activity:** The antimycobacterial activity of the compounds was studied *in vitro* by two fold serial dilution method against  $\text{H}_3\text{R}_v$  strain of *Mycobacterium tuberculosis* using Lowenstein-Jensen's egg medium. MIC (Table 2)

TABLE 1—PHYSICAL DATA OF THE 2,4-DIARYLAMINO-6-CHLORO/SUBSTITUTED ANILINO-*s*-TRIAZINES (II, III, IV AND V)

Ar	Type of compound	% Yield	m.p. °C	Type of compound	% Yield	m.p. °C
Phenyl	II	88.7	197 <sup>20</sup>	IV	97.6	184
<i>p</i> -Tolyl	II	98.1	197 <sup>20</sup>	IV	99.1	202
<i>p</i> -Anisyl	II	93.4	204 <sup>21</sup>	IV	96.0	205
<i>p</i> -Chlorophenyl	I'	90.9	222-23 <sup>21</sup>	IV	98.4	194
<i>p</i> -Bromophenyl	II	94.8	240-41	IV	96.5	199
<i>p</i> -Nitrophenyl	II	94.7	304 <sup>20</sup>	IV	95.6	222-23
<i>m</i> -Chlorophenyl	II	92.2	296-97	I'	97.0	214
<i>m</i> -Tolyl	II	93.4	144 <sup>20</sup>	IV	98.6	198
<i>o</i> -Tolyl	II	90.9	164 <sup>20</sup>	IV	97.5	198
<i>o</i> -Tolyl	III	97.2	209	V	50.7	293
<i>m</i> -Tolyl	III	95.1	214	V	54.0	296
<i>m</i> -Chlorophenyl	I'	90.8	263	V	44.1	284
<i>p</i> -Nitrophenyl	III	93.2	298	V	43.9	335(d)
<i>p</i> -Bromophenyl	III	94.6	273	V	47.7	281
<i>p</i> -Chlorophenyl	III	93.1	238	V	49.6	293
<i>p</i> -Anisyl	III	96.9	242	V	57.2	304
<i>p</i> -Tolyl	III	95.1	214	V	56.3	287
Phenyl	III	96.5	216	V	55.0	298

All the above compounds gave satisfactory C, N and S analyses.

TABLE 2—DATA OF THE THIOSEMICARBAZONES VI AND VII

Ar	R	% Yield	m.p. °C	MIC µg/ml
C <sub>6</sub> H <sub>5</sub> -	H	48.4	236	8
C <sub>6</sub> H <sub>5</sub> -	CH <sub>3</sub>	66.6	311	64
p-CH <sub>3</sub> -C <sub>6</sub> H <sub>4</sub> -	H	48.7	231	8
p-CH <sub>3</sub> -C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	68.3	298	64
p-CH <sub>3</sub> O-C <sub>6</sub> H <sub>4</sub> -	H	48.2	248	8
p-CH <sub>3</sub> O-C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	78.2	265	64
p-Cl-C <sub>6</sub> H <sub>4</sub> -	H	48.1	238	8
p-Cl-C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	76.9	275	64
p-Br-C <sub>6</sub> H <sub>4</sub> -	H	42.1	298(d)	16
p-Br-C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	77.1	302	—
p-NO <sub>2</sub> -C <sub>6</sub> H <sub>4</sub> -	H	42.6	245	—
p-NO <sub>2</sub> -C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	77.6	336	—
m-Cl-C <sub>6</sub> H <sub>4</sub> -	H	49.8	219-20	8
m-Cl-C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	74.9	283	32
m-H <sub>3</sub> C-C <sub>6</sub> H <sub>4</sub> -	H	48.0	230-31	8
m-H <sub>3</sub> C-C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	66.5	294	92
o-H <sub>3</sub> C-C <sub>6</sub> H <sub>4</sub> -	H	50.7	238	8
o-H <sub>3</sub> C-C <sub>6</sub> H <sub>4</sub> -	CH <sub>3</sub>	69.3	288	32

All the above compounds gave satisfactory C, N and S analyses.

is the minimum concentration which inhibits almost completely the growth of the test bacterium.

It is evident from the experimental data (Table 2) that *p*-(2,4-diarylamino-6-s-triazinyl-amino)-benzaldehyde thiosemicarbazones (VI) have higher tuberculostatic activity than the corresponding acetophenone thiosemicarbazone analogues (VII). The intermediate compounds II-V do not possess any significant activity against *Mycobacterium tuberculosis* reflecting on the key role of thiosemicarbazone moiety in the antimycobacterial activity of the title compounds.

#### Acknowledgement

The authors are thankful to Saurashtra University for facilities and to Dr. S.B. Trivedi, Director, Tuberculosis Research Centre, Amargadh, for his interest in the work and for facilities for *in vitro* screening.

#### References

- G. DOMAGE, R. BEHNISCH, F. MIETZSCH and H. SCHMIDT, *Naturwiss.*, 1946, **33**, 815.
- G. DOMAGE, *Amer. Rev. Tuberc.*, 1950, **61**, 8.
- J. LOWE, *Lancet*, 1954, **2**, 1065.
- H. BUU and J. P. JUIN, *Annls. Inst. Pasteur, Paris*, 1946, **72**, 580.
- H. H. FOX, *J. Org. Chem.*, 1952, **17**, 555.
- H. H. FOX, *Trans. N. Y. Acad. Sci.*, 1953, **15**, 234.
- A. GIRARD, O. LEVADITI, A. RAY and A. VAISMAN, *Compt. Rend.*, 1950, **231**, 1174.
- E. GRÜNBERG and B. LEIWANT, *Proc. Soc. Exptl. Biol. Med.*, 1951, **77**, 47.
- J. P. JUIN and H. BUU, *Annls. Inst. Pasteur, Paris*, 1946, **72**, 606.
- R. DONOVICK and J. BERNSTEIN, *Amer. Rev. Tuberc.*, 1949, **60**, 589.
- E. HOGGARTH, A. R. MARTIN, N. E. STORRY and E. H. P. YOUNG, *Brit. J. Pharmacol.*, 1949, **4**, 248, 1950, **5**, 168.
- D. HAMER, J. BERNSTEIN and R. DONOVICK, *Proc. Soc. Exptl. Biol. Med.*, 1950, **73**, 275.
- D. HAMER, J. BERNSTEIN and R. DONOVICK, *J. Bact.*, 1950, **59**, 675.
- R. DONOVICK, J. BERNSTEIN, F. E. PANST and G. STAYKE, *J. Bact.*, 1950, **59**, 667.
- E. HOGGARTH, *J. Chem. Soc.*, 1951, 2202.
- R. TOMPSETT, M. COUNE, M. ROBERT and WASL-HOECKERT OIE, *Amer. Rev. Tuberc.*, 1959, **70**, 748.
- F. A. FRENCH and E. J. BLANL, *Cancer Res.*, 1966, **2**, 1, 1454.
- F. A. FRENCH and E. J. BLANL, *J. Med. Chem.*, 1966, **9**, 585.
- W. W. CUTHBERTSON and J. J. MOFFATT, *J. Chem. Soc.*, 1948, 561.
- F. H. S. GURD, J. K. LANDQIST and F. L. ROSE, *J. Chem. Soc.*, 1947, 154.
- N. A. LANGALIA and K. A. THAKER, *J. Indian Chem. Soc.*, 1981, **58**, 89.
- E. GIORANESCU, *Rev. Chem. (Bucharest)*, 1954, **5**, 425.
- F. S. PHILLIPS and J. B. THIMERSCH, *J. Pharmacol. Exptl. Therap.*, 1950, **100**, 398.
- Ciba Ltd., B. P., 1956, 74071, *Chem. Abs.*, 1957, **51**, 8814.
- J. CONTROULIS, *J. Amer. Chem. Soc.*, 1944, **66**, 1775.
- ALFRED BURGEM, "Medicinal Chemistry", Interscience Publishers, New York, 1960, pp. 1012, 1030, 1037.
- J. H. BURCHENAL and S. F. JONSTON, *Proc. Soc. Exptl. Biol. Med.*, 1950, **74**, 788.
- E. MOSETTIG, *Org. Reactions*, 1954, **8**, 218.
- C. N. WOLF, U. S. P., 2720490, *Chem. Abs.*, 1956, **50**, 13101.
- N. V. KOZIOVA, *Z. Obsh. Khim.*, 1963, **30**, 13803, *Chem. Abs.*, 1964, **60**, 5498.
- M. GOI, *Yuki Gosei Kagaku Kyokasshi*, 1960, **18**, 327; *Chem. Abs.*, 1960, **54**, 19702.

#### Studies on Antitubercular Agents. Preparation of 2-Arylamino-4-(4-Carbethoxyanilino)-6-Isonicotinylhydrazino-1,3,5-Triazine

H. K. SHUKLA, N. A. LANGALIA, N. C. DESAI


and

K. A. THAKER

University Department of Chemistry, Bhavnagar University, Bhavnagar-364 003

Manuscript received 10 July 1981, revised 17 December 1981, accepted 1 May 1982

LITERATURE reveals that a number of studies has been carried out on the chemotherapeutic potentialities of 1,3,5-triazine derivatives. It was thought that incorporation of substituted amino-1,3,5-triazine moiety into the tuberculostatic agent isonicotinic acid hydrazide, might modify the biological activities. Thus, 2,4,6-trichloro-1,3,5-triazine and ethyl *p*-aminobenzoate were reacted to produce 2-(4-carbethoxyanilino)-4,6-dichloro-1,3,5-triazine, which on reaction with isonicotinic acid hydrazide and subsequently with different aromatic amines gave 2-arylamino-4-(4-carbethoxyanilino)-6-isonicotinylhydrazino-1,3,5-triazine<sup>1-4</sup>.



2-arylamino-4-(4-carbethoxyanilino)-6-isonicotinylhydrazino-1,3,5-triazine.

## Experimental

**Preparation of 2-(4-carbethoxyanilino)-4,6-dichloro-1,3,5-triazine :** 2,4,6-Trichloro-1,3,5-triazine (0.01 mole) and ethyl *p*-aminobenzoate (0.01 mole) were separately dissolved in acetone (100 ml) and mixed at 0°. To it, NaOH (aqueous 4% ; 100 ml) was added dropwise and mechanically stirred at 0-5°. The contents poured on ice, titrated with HCl (5 N), filtered and crystallised from THF, m.p. 284° (reported m.p. 282-87°). (Found : C, 50.40 ; Cl, 24.8 ; N, 19.25.  $C_{12}H_{10}Cl_2N_4O_3$  requires C, 51.25 ; Cl, 25.27 ; N, 19.97%).

**Preparation of 2-(4-carbethoxyanilino)-4-chloro-6-isonicotinylhydrazino-1,3,5-triazine :** Isonicotinic acid hydrazide (INH, 0.08 mole) and 2-(4-carbethoxyanilino)-4,6-dichloro-1,3,5-triazine (0.08 mole) were dissolved in dioxane at 10 to 15°, followed by dropwise addition of  $NaHCO_3$  (1 M ; 90 ml) and stirring at 30-35° for 3 hr. The product isolated and crystallised from ethanol (95%), m.p. 325°. (Found : C, 56.22 ; H, 3.91 ; N, 24.38.  $C_{22}H_{16}ClN_6O_3$  requires C, 55.89 ; H, 4.14 ; N, 25.36%).

**Preparation of 2-arylamino-4-(4-carbethoxyanilino)-6-isonicotinylhydrazino-1,3,5-triazine :** Amine (0.02 mole) and 2-(4-carbethoxyanilino)-4-chloro-6-isonicotinylhydrazino-1,3,5-triazine were taken in dioxane and the solution refluxed for 2 hr with the simultaneous dropwise addition of aqueous  $NaHCO_3$  (10% ; 2 ml). The solution was cooled, poured on ice, filtered, washed with water and crystallised from ethanol (95%) in 80 to 85% yields.

**Antimycobacterial screening :** The *in vitro* anti-tubercular activity of the hitherto synthesised 2-arylamino-4-(4-carbethoxyanilino)-6-isonicotinylhydrazino-1,3,5-triazine have been studied at 25 µg/ml concentration (solvent - acetone) against  $H_{37}R_v$  strain of *Mycobacterium tuberculosis* using Lowenstein-Jensen medium. The procedure was duplicated with solvent for control purposes.

TABLE I—DATA OF THE 2-ARYLAMINO-4-(4-CARBETHOXYANILINO)-6-ISONICOTINYLAHYDRAZINO)-1,3,5-TRIAZINE

Sl. No.	Ar	m.p. °C	Activity against $H_{37}R_v$ strain of <i>M. tuberculosis</i>
1	Phenyl	160	+
2	<i>o</i> -Chlorophenyl	218	+
3	<i>o</i> -Tolyl	281	+
4	<i>o</i> -Carboxyphenyl	228	+
5	<i>m</i> -Chlorophenyl	204	+
6	<i>m</i> -Tolyl	231	+
7	<i>m</i> -Nitrophenyl	246	+
8	<i>p</i> -Chlorophenyl	165	+
9	<i>p</i> -Tolyl	180	+
10	<i>p</i> -Anisyl	171	+
11	<i>p</i> -Nitrophenyl	190	+
12	<i>p</i> -Bromophenyl	228	+

All the above compounds gave satisfactory C, H and N analysis.

## Acknowledgement

The authors are thankful to Bhavnagar University for research facilities and Research Scholarship to (H.K.S.) and (N.C.D.) and to Dr. S. B. Trivedi, Director, Tuberculosis Research Centre, Amargadh, for facilities for antibacterial testing.

## References

1. H. NESTLER and H. FURST, *J. Prakt. Chem.*, 1968, 23, 86, 178.
2. C. N. WOLF, U. S. P., 2720480, *Chem. Abs.*, 1956, 50, 18101.
3. N. V. KOZIOVA, *Z. Obb. Sch. Khim.*, 1968, 30, 8808, *Chem. Abs.*, 1964, 60, 5498.
4. M. OGI and KYOKAISHI, *Chem. Abstr.*, 1960, 54 19702.

### Synthesis of Some New 1-Substituted 5-bromo-3-aryloxy acetyl hydrazono-2-indolinones as Potential Antibacterial Agents

ANIL K. SEN GUPTA and ANITA RASTOGI

Department of Chemistry, University of Lucknow, Lucknow-226 007

Manuscript received 28 October 1981, accepted 7 June 1982

SEVERAL isatin analogous have been reported to possess antibacterial<sup>1</sup>, antiviral<sup>2</sup>, anthelmintic<sup>3</sup>, herbicidal<sup>4</sup> and fungicidal<sup>5</sup> properties. In addition to this, cysticidal<sup>6</sup> and hypotensive<sup>7</sup> responses have also been reported in certain isatin derivatives. Furthermore, tuberculostatic responses<sup>8</sup> of aryloxy acetyl hydrazides are also well established.

Encouraged by these findings, 5-bromoisatin was condensed with *p*-substituted phenoxy acetyl hydrazides to furnish 5-bromo-3-aryloxy acetyl hydrazono-2-indolinones (I). Similarly, 5-bromo-1-methyl isatin gave 1-methyl-5-bromo-3-(*p*-substituted)-phenoxy acetyl hydrazono-2-indolinones. When compounds (I) were subjected to Mannich reaction, 1-aminomethyl-5-bromo-3-(*p*-substituted)-phenoxy acetyl hydrazono-2-indolinones were obtained and their antibacterial activity were tested.

## Experimental

Melting points were taken in open capillaries and are uncorrected. All the compounds were characterised by ir spectroscopy, recorded on Perkin-Elmer 137 IR spectrometer in KBr and the  $\lambda_{max}$  values are expressed in  $cm^{-1}$ . The purity of the compounds was checked by tlc on silica gel-G plates and the spots were located by  $I_2$  vapours.

**Synthesis of 5-bromoisatin (I) :** The 5-bromoisatin was prepared following the literature method<sup>9,10</sup>.

**N-Methylation of isatin (II) :** This was performed by the procedure described by Harley-Manson *et al*<sup>11</sup>.

**Aryloxy acetyl hydrazides (III-VII) :** Hydrazide derivatives of substituted phenols were prepared by the method of Yale *et al.*<sup>12</sup>

**3-Phenoxy acetyl hydrazono-2-indolinone (VIII) :** A mixture of 5-bromoisatin (4.4 g; 0.02 mole) and phenoxy acetyl hydrazide (3.3 g; 0.02 mole) in ethanol (25 ml) containing a few drops of glacial acetic acid was refluxed on a water bath for 2 hr. The reaction mixture was then allowed to cool to room temperature. The solid mass thus separated was filtered off, washed with cold ethanol and recrystallised from ethyl acetate.

**IR :** 3200 (N—H stretch, broad peak with shoulder), 1720 (C=O stretch shoulder at 1680 for non-cyclic C=O stretch) and 1620  $\text{cm}^{-1}$  (C=N), etc.

All the other compounds of the series (IX-XII) were synthesised in a similar manner and their relevant data are given in Table 1.

**1-Methyl-5-bromo-3-phenoxy acetyl hydrazono-2-indolinone (XIII) :** This was prepared by heating a mixture of 1-methyl-5-bromo isatin (1.2 g; 0.1 mole) and phenoxy acetyl hydrazide (0.83 g; 0.1 mole) in ethanol (25 ml) containing a few drops of glacial acetic acid for 4 hr on a water bath. The reaction mixture was cooled and the solid product thus separated was recrystallised from  $\text{CHCl}_3$ .

**IR :** 3150 (N—H stretch), 2900 (C—H stretch aliphatic), 1720 (C=O stretch cyclic), 1675 (C=O stretch non-cyclic) and 1610  $\text{cm}^{-1}$  (C=N), etc.

Other compounds of this series (XIV-XVII) were also synthesised by the similar method (Table 1).

**1-Morpholinomethyl-5-bromo-3-phenoxyacetyl hydrazono-2-indolinone (XVIII) :** The compound 5-bromo-3-phenoxy acetyl hydrazono-2-indolinone (1.24 g; 0.01 mole) was suspended in ethanol (15 ml). To this suspension was added 37% formalin (0.1 ml) and morpholine (0.2 ml; 0.01 mole) with vigorous stirring. This mixture was then heated on water bath for 10 min and allowed to stand overnight at room temperature. The separated product was filtered and washed with petroleum ether (60-80°) and air dried. Finally, it was recrystallised from  $\text{CHCl}_3$ -petroleum ether.

**IR :** 3200 (N—H stretch), 2850 (C—H stretch aliphatic), 1720 (C=O stretch cyclic), 1675 (C=O stretch non-cyclic), and 1610  $\text{cm}^{-1}$  (C=N), etc.

Similarly, compounds (XIX-XXVII) were also synthesised (Table 1).

**Antibacterial activity :** The method of agar diffusion technique<sup>13,14</sup> was employed for determining antibacterial activity of all the compounds. The test organisms included *Bacillus cereus*, *Staphylococcus aureus* and *Bacillus pumilus*. Sterile filter paper discs (diameter 5 mm) saturated with the solution of the test compound (10 mg/ml in ethanol) were placed on nutrient agar plates [1.5% (w/v) agar, 5% (w/v) NaCl, 0.5% (w/v) glucose and 3.5% (w/v) peptone; pH 6.8-7.0], after drying up of the solvent. The plates were incubated at 37° for

24 hr. Inhibition zones around the discs were measured. Tests were carried out in triplicate and the results are recorded in Table 1.

TABLE 1—PHYSICAL CONSTANTS AND ANTIBACTERIAL ACTIVITY OF 1-SUBSTITUTED-5-BROMO-3-ARYLOXY ACETYL HYDRAZONO-2-INDOLINONES (VIII-XXVII)


Compd. No.	R	R'	m.p. °C	Antibacterial activity		
				Mean inhibition areas after 24 hr		
				<i>B. cereus</i>	<i>S. aureus</i>	<i>B. pumilus</i>
VIII	H	H	280	++	++	++
IX	H	Cl	242	++	+	—
X	H	OH	272	+	+	+
XI	H	OCH <sub>3</sub>	288	+	—	+
XII	H	Br	262	—	+	—
XIII	CH <sub>3</sub>	H	212	—	+	+
XIV	CH <sub>3</sub>	Cl	202	+	—	+
XV	CH <sub>3</sub>	CH <sub>3</sub>	218	—	—	—
XVI	CH <sub>3</sub>	OCH <sub>3</sub>	188	—	—	—
XVII	CH <sub>3</sub>	Br	192	—	—	—
XVIII	morpholino methyl	H	152	+++	++	++
XIX	"	Cl	189	+	+	+
XX	"	OH	146	+	—	+
XXI	"	OCH <sub>3</sub>	147	+	—	—
XXII	"	Br	178	—	+	—
XXIII	piperidino methyl	H	158	+	—	+
XXIV	"	Cl	176	—	+	+
XXV	"	CH <sub>3</sub>	184	+	+	+
XXVI	"	OCH <sub>3</sub>	155	+	—	—
XXVII	"	Br	164	—	—	—

Elemental analysis of C, H and N were found within limits. Yields of all the compounds ranged between 60-80%.

(—) = No inhibition, (+) = Zone size 6-8 mm, (++) = Zone size 8-12 mm, (+++) = Zone size > 12 mm.

## Discussion

Compounds no 8 and 18 were found to be the most active against all the microorganisms tested, whereas compound no. 9 was found to be active only against *B. cereus*. Rest of the compounds were moderately active.



### Acknowledgement

Sincere thanks of the authors are due to Dr. V. S. Misra, Head, Chemistry Department, University of Lucknow for facilities and to the Director, C D. R. I., Lucknow for spectral and elemental analysis.

### References

1. R. S. VARMA and W. J. NOBLES, *J. Pharm. Sci.*, 1976, **64**, 881.
2. T. S. OSDANE, "Medicinal Chemistry", 3rd Edn., (Ed.) A. BRIDGE, Wiley Interscience, New York, 1970, 662.
3. R. OATIER, R. ROVER, R. RIPS and L. REWE, *Chim. Ther.*, 1969, **4**, 21.
4. F. HAMBACH, German patent, 1013459, 1975, *Chem. Abs.*, 1980, **54**, 196738.
5. KUPINIC, MIRJAMO, MEDIC-SARIC, MARICA, MAVERIN, MURIJA, MAYSINGER, *Dusica. J. Pharm. Sci.*, 1979, **68**, 459, *Chem. Abs.*, 1980, **91**, 758.
6. R. S. VARMA and I. A. KEAN, *Indian J. Med. Res.*, 1978, **67**, 315.
7. J. WYETH and Brothers Ltd, *Brit Pat.*, 1240648, 1971, *Chem. Abs.*, 1971, **75**, 118842.
8. M. B. MAHISHI, B. H. IYER and M. SIKSI, *J. Indian Chem. Soc.*, 1965, **42**, 67.
9. C. S. MARVEL and O. S. HENES, "Organic Synthesis", Coll. Vol. I, 1941, 827.
10. W. O. SUMPTER and W. F. JONES, *J. Amer. Chem. Soc.*, 1948, **65**, 1802.
11. JOHN HARLEY-MENSON and R. F. J. INGLEBY, *J. Chem. Soc.*, 1958, 3639.
12. H. L. YALE, K. LOSER, J. MARTINS, M. HOLSING, F. M. PERRY and J. BERNSTEIN, *J. Amer. Chem. Soc.*, 1958, **75**, 1983.
13. R. S. VARMA and W. L. NOBLES, *J. Pharm. Sci.*, 1952, **8**, 242.
14. O. ISLER, H. GILMAN, O. STRAUB, B. FAST, E. BAHNI and A. STUDER, *Helv. Chim. Acta*, 1955, **38**, 1083.

### Synthesis of Substituted 6-Pyrazolo and 6-Isioxazolo-Benzoxazoles and Their Physiological Activity

M. SADASIVA SHANKAR, B. RAJESHWARA RAO,  
G. V. P. CHANDRA MOULI and Y. D. REDDY

Department of Chemistry, Regional Engineering College,  
Warangal-506 004

Manuscript received 24 December 1981, accepted 7 June 1982

A wide range of physiological properties are found to be associated with benzoxazoles, isoxazoles and pyrazoles. Heterocycles, substituted with hydroxyphenyl moiety, have been used as analgesic<sup>1</sup>, antitissive<sup>2</sup> and anticonvulsant<sup>3</sup> agents. A number of hydroxyaryl pyrazoles were found to possess marked antifungal activity<sup>4</sup>. The present investigation is aimed at a study of antifungal activity of some substituted isoxazolobenzoxazoles and pyrazolobenzoxazoles and a series of the above new compounds are synthesised and screened for antifungal and antibacterial activities.

Chromones in their reactions with hydrazine or phenylhydrazine behave like  $\alpha,\beta$ -unsaturated ketones

and undergo Michael addition. The nucleophile attacks at C-2 with concomitant opening of the pyrone ring. The intermediates thus formed undergo cyclisation to give 3(5)-*o*-hydroxyphenyl-pyrazole system<sup>4,6</sup>.




Chart 1. R=alkyl or aryl, R'=H or ph

In the present investigation, the behaviour of some substituted chromonooxazoles with hydroxylamine, hydrazine and phenylhydrazine is studied. Substituted chromonooxazoles can be prepared starting from *o*-hydroxyaminochromones either by treating with various aldehydes in nitrobenzene<sup>7</sup> or treatment with carboxylic acids in presence of polyphosphoric acid<sup>8</sup>.

Chromonooxazoles (I), upon treatment with hydroxylamine hydrochloride in pyridine, underwent the cleavage of the chromone ring followed by the formation of isoxazole unit, resulting in the formation of II. The same chromonooxazole (I), when treated with hydrazinehydrate or phenylhydrazine in alcohol medium yielded III (Chart 2). These results are in accordance with Ghosh *et al*<sup>9</sup>.




Chart 2

All the products gave green colouration with neutral ferric chloride, pink colour with conc. sulphuric acid and dark violet colour with titanium(III) chloride. The uv maxima are recorded at  $250 \pm 10$  nm due to benzoxazole chromophore and at  $280 \pm 10$  nm due to extended conjugation. The ir bands at 1570, 1350, 1050  $\text{cm}^{-1}$  are characteristic of oxazole ring system. A broad absorption at 3200  $\text{cm}^{-1}$  is for chelated hydroxyl group. Further, absorption at 1640  $\text{cm}^{-1}$  is indicative of  $\text{C}=\text{N}$ . The pmr results have been included in Table 1.

#### Physiological activity :

All the above compounds have been tested for antibacterial activity using *Staphylococcus lutea*,

TABLE 1

Sl No	Compound	Assignment					
		3'-CH <sub>3</sub>	4'H	4H, 5H	Chelated 7-OH	Substituent at 2	Substituent at N
1.	2- <i>o</i> -Toluy1-6-(5'-methylisoxazole-3'-yl)-7-hydroxybenzoxazole	2.3(s) (5'-Me)	6.6(s)	8.1(m)	10.4 to 10.6 (broad)	2.8(s) Me, 7.2 to 7.6 (m) ar protons	—
2	2-Phenyl-6-(3'-methylpyrazole-5'-yl)-7-hydroxybenzoxazole	2.4(s)	6.6(s)	8.2(m)	10.4 to 10.6 (broad)	7.4 to 7.7(m) ar protons	2.5 (broad) (N-H)
3	2- <i>p</i> -Chlorophenyl-6-(1'-phenyl-3'-methylpyrazole-5'-yl)-7-hydroxybenzoxazole	2.4(s)	6.3(s)	8.2(m)	10.4 to 10.6 (broad)	2.7(s) Me, 7.2 to 7.5(m) ar proton (4H)	7.2 to 7.5(m) aromatic (5H)

TABLE 2

Sl No	Compound	m p °C	Yield %	Analysis % Found (Calcd)		
				C	H	N
2-(R)-6-(5'-Methylisoxazole-3'-yl)-7-hydroxybenzoxazole						
	R					
1	Phenyl	222	76	72.6 (72.8)*	4.3 (4.2)	10.1 (10.0)
2	( <i>p</i> -Chlorophenyl)	224	74	64.7 (64.8)	8.5 (8.4)	8.8 (8.9)
3	(2-Naphthyl)	236	72	73.7 (73.6)	4.1 (4.0)	8.2 (8.1)
4	(3-Pyridyl)	240	68	69.1 (69.3)	3.8 (3.9)	15.3 (15.1)
5	<i>o</i> -Toluy1	192	77	73.3 (73.4)	4.6 (4.7)	9.4 (9.6)
6	<i>p</i> -Toluy1	200	78	73.2 (73.4)	4.5 (4.7)	9.6 (9.5)
2-(R)-6-(1'-R'-3'-Methylpyrazole-5'-yl)-7-hydroxybenzoxazole						
	R	R'				
1	Phenyl	Phenyl	207	75.0 (75.2)	4.9 (4.8)	11.5 (11.4)
2	Phenyl	H	300	68.9 (68.8)	4.8 (4.7)	15.2 (15.0)
3	<i>p</i> -Chlorophenyl	Phenyl	232	68.6 (68.7)	4.0 (3.9)	10.5 (10.4)
4	2-Naphthyl	Phenyl	272	77.5 (77.6)	4.4 (4.5)	10.2 (10.0)
5	6-Methyl-3-coumarinyl	Phenyl	260	72.4 (72.3)	3.9 (4.0)	9.4 (9.0)

\* Figures in parentheses are calculated values.

*S. aureus*, *Escherichia coli* and *Bacillus magetenum* as representative species, employing glass humid chamber technique. None of the compounds are found to be antibacterial. The antifungal activity has been assessed by employing *Drechslera rostrata* (Drechs) and *Alternaria alternata* (Keissler) as the test organisms. All the compounds tested could inhibit the spore germination at 30 µg/ml up to the maximum level. Hence it is concluded that all the compounds possess high antifungal activity but not antibacterial.

#### Experimental

All the melting points are uncorrected. IR spectra are recorded on Perkin-Elmer 297 instrument in KBr pellets. NMR is recorded on a Varian

A-60 MHz instrument. Micro analysis is done on Hewlett-Packard 185-B Model. The data are given in Table 2

All the chromonooxazoles were prepared by procedures reported earlier<sup>1,2</sup>.

**2-Substituted-6-(5'-methylisoxazole-3-yl)-7-hydroxybenzoxazoles**—The parent chromonooxazole and hydroxylamine hydrochloride were taken in equimolar ratio and dissolved in pyridine, refluxed for 4 hr and excess pyridine removed by distillation. The reaction mixture was poured on crushed ice and neutralised with dilute acetic acid with constant stirring. The resulting solid product was washed thoroughly with cold water and dried. All the compounds were recrystallised from benzene-petroleum ether. Yields were above 80%.

**2-Substituted-6-[(1'-substituted-3'-methylpyrazol-5'-yl)]-7-hydroxybenzoxazoles:** All the N-phenyl pyrazolyl and pyrazolyl substituted benzoxazoles were prepared by taking equimolar proportions of chromonooxazole and phenylhydrazine or hydrazine hydrate in alcohol and refluxing and working out in the above manner.

#### Acknowledgement

The authors thank the Principal, Regional Engineering College, Warangal for facilities and Prof. S. R. Ramadas, Department of Chemistry, Indian Institute of Technology, Madras for valuable suggestions. One of the authors (M.S.S.) is thankful to the Principal, C. K. M. College, Warangal for encouragement. The authors are also grateful to Dr. M. A. Singaracharya, Lecturer, C. K. M. College, for kind help in testing antifungal and antibacterial activities

#### References

1. J. LEE, H. ZIERING, S. D. HEINEMANN and I. BERGER, *J. Org. Chem.*, 1947, 12, 885.
2. O. J. BRAENDEN, N. B. EDDY and B. HABACH, *Bull. World. Health Org.*, 1955, 13, 935.
3. A. H. BACKETT and A. F. GOSV, *Bull. Narcot.*, 1957, 9, 37.
4. T. C. SHARMA, M. M. BOKADIA and N. J. REDDY, *Indian J. Chem.*, 1980, 19B, 228.
5. W. BAKER, J. B. HORNBORNE and W. D. OLLIS, *J. Chem. Soc.*, 1952, 1805.
6. A. SCHOENBERG and M. M. SIDKY, *J. Amer. Chem. Soc.*, 1953, 75, 5138.
7. Y. D. REDDY and V. V. SOMAYAJULU, *Proc. Ind. Acad. Sci.*, 1971, 74, 265.
8. Y. D. REDDY and V. V. SOMAYAJULU, *Proc. Ind. Acad. Sci.*, 1975, 82, 280.
9. G. K. GHOSH and K. K. MUKHOPADHYAY, *J. Indian Chem. Soc.*, 1978, 50, 52.

### A Field Test for The Detection and Semiquantitative Determination of Sulphurdioxide in Air and Water

(MISS) ABHA CHAUBE and V. K. GUPTA

Department of Chemistry, Ravishanker University  
Raipur-493 010

Manuscript received 16 October 1981, revised 11 March 1982  
accepted 1 May 1982

**SULPHURDIOXIDE** is a major pollutant originating from industrial and domestic emissions. It is also a major component of automobile exhaust and its applications as a preservative or fungicide are major sources of sulphurdioxide pollution. The "Threshold Limit Value" adopted by American Conference of Governmental Industrial Hygienists (1969) is 5 ppm<sup>1</sup>. In view of its hazardous effects on health, vegetation and property<sup>2</sup>, a fast and reliable method for detection of traces of sulphurdioxide would be of immense value.

In search of better organic bases to increase the intensity of brick red colouration in the Bodeker

reaction<sup>3</sup>, it was found that malonyldihydrazide (MDH) along with zinc acetate and sodium nitroprusside gives a very intense brick red precipitate in solution. The reaction is used for spot test to detect as low as 0.2 ppm sulphurdioxide in air or water.

#### Experimental

**Preparation of malonyldihydrazide:** Malonyldihydrazide was prepared by adding hydrazine hydrate (0.1 mole in alcohol) to an alcoholic solution of diethyl malonate (0.05 mole in alcohol) in 2:1 mole ratio. The white solid obtained was crystallised from water, m.p. 150°.

**Reagents:** (1) 1 M zinc acetate solution in 5% v/v glycerol, (2) 2% w/v solution of sodium nitroprusside in distilled water and (3) 2% w/v solution of malonyldihydrazide in distilled water were used.

Sulphurdioxide for air analysis was prepared from freshly prepared sodium sulphite solution in water with a small amount of HCl

All reagents used were of A. R. grade.

#### Procedure

**Spot test for the detection of sulphurdioxide as sulphite ions in water:** 1 ml of each of the above mentioned reagents 1, 2 and 3 were taken in a 10 ml beaker serially. A cream coloured colloidal solution was formed. The solution was stable for a week. One drop of this solution was taken on a spot plate. One drop of sulphurdioxide solution (5 µg/ml) was added to this spot. A brick red precipitate formed immediately which indicated the presence of sulphurdioxide. The precipitate was stable for more than 24 hr.

**Detection in air:** Test papers were prepared and examined for the detection of traces of sulphurdioxide in air by the earlier reported method<sup>4</sup> using 2% w/v solution of malonyldihydrazide along with 1 M zinc acetate solution and 2% sodium nitroprusside solution. The colour produced in the test paper was compared with that obtained from passing 1 litre of air containing 0.1 to 2 ppm of sulphurdioxide. A semiquantitative determination was possible.

#### Results and Discussion

The present method is more sensitive than the earlier reported methods. Brick red precipitate is not soluble in organic solvents like chloroform, carbon tetrachloride, benzene, butanol, methanol, ethanol, methyl acetate, etc. Precipitate is either decomposed or remains undissolved in these solvents.

Carbonate, chloride, sulphate, ammonia, nitrate, nitrite, phosphate did not interfere in this reaction. Sulphide ion was found to give similar colour reaction. However, the interference from sulphide ion can be eliminated by passing the air sample through mercuric chloride solution.



The pH of the coloured solution after the formation of the precipitate was found to be between 5.5–5.8. Increase in intensity of the colour by addition of malonyldihydrazide was supposed to be due to the formation of  $[\text{Zn}(\text{MDH})_2]$ ,  $\text{Fe}(\text{CN})_6$ - $\text{NO.SO}_3$ . Following the described procedure, semi quantitative determination of sulphites in water is possible by comparing the colour of the precipitate produced by varying amounts of sulphites (0.1 to 2 ppm) with that produced by the unknown. Further studies to establish this reported reagent system as an absorbing reagent for sulphurdioxide are being pursued.

#### Acknowledgement

The authors are thankful to the Head, Department of Chemistry, Ravishankar University, Raipur, for necessary facilities.

#### References

1. I. M. KOLTHOFF, P. J. ELVING and F. H. SLOSS, "Treatise on Analytical Chemistry", Wiley Interscience, New York, 1971, p. 48.
2. F. A. PATTY, "Industrial Hygiene and Toxicology", 2nd revised Edn, Vol II, Interscience, New York, 1968, p. 71.
3. O. BODENKAMP, *Ann.*, 1981, 117, 188.
4. J. NAIR and V. K. GUPTA, *J. Indian Chem. Soc.*, 1977, 54, 841.

### Spectrophotometric Determination of Aromatic Amines Using Catechol and Iodine

C. S. PRAKASA SASTRY\*, B. G. RAO

and

K. V. S. S. MURTHY

Department of Chemistry, Andhra University, Waltair-530 003

Manuscript received 16 October 1981, revised 9 February 1982  
accepted 1 May 1982

**A** new spectrophotometric method for the assay of primary and secondary aromatic amines with catechol-iodine reagent at pH  $2.6 \pm 0.6$  has been developed. It is based on the development of purple-red colour of maximum absorbance ( $\lambda_{\text{max}}$  500-520 nm) within 5-20 min (depending on the amine) after mixing with the reagent. The colour is stable for 2 hr. The method is simple, reproducible and accurate within  $\pm 1.0\%$ . It has been extended to the determination of drugs in pure and dosage forms which either contain a free primary aromatic amino group (sulpha drugs, local anaesthetics, dapsona) or release it through hydrolysis (succinyl sulphathiazole) or reduction (chloramphenicol or folic acid).

#### Experimental

The absorbance measurements were made with Shimadzu UV 140 double beam spectrophotometer

with 1 cm glass cells. The pH of the solution was adjusted to the desired value using an Elico model LI-120 digital pH meter. A freshly prepared 0.1% aqueous solution of catechol was used. Glycine-HCl (pH 1.0-2.1) and potassium acid phthalate-HCl buffers were prepared according to the procedures given by Lurie<sup>1</sup>. All the other reagents used were of analytical grade.

**General procedure.** To a 25 ml flask, 15 ml of potassium acid phthalate buffer pH 3.1, 1 ml of 0.1% catechol, 1 ml of 0.01 N iodine and 1-5 ml of aromatic amine (concentration range, Table 1) were added in the given order. The solution was then diluted to the mark and allowed to stand at room temperature for 5-30 min (depending on the amine). At the end of this period, the absorbance was read at 500-520 nm against a reagent blank. The aromatic amine concentration was read from a calibration curve prepared with the same compound under identical conditions.

**Procedure for compounds which yield primary aromatic amino group on hydrolysis.** About 25 mg of the sample was boiled with 20 ml 6 N HCl for 1 hr under reflux, cooled and the excess hydrochloric acid removed under vacuum. The residue was dissolved in 50 ml of warm water and diluted to 250 ml after adjusting the pH to 5.0-7.0. The general procedure was then followed.

**Procedure for compounds which yield a primary arylamino group on reduction.** About 25 mg of the sample was treated with 20 ml 4 N HCl and 0.75 g zinc dust added in portions. After standing for 1 hr at room temperature, the solution was filtered through cotton wool, the residue was washed with water, excess HCl was removed and diluted to 250 ml after adjusting the pH to 5.0-7.0. The general procedure was then followed.

The sampling and preliminary treatment of dosage forms such as tablets and capsules was performed according to reported procedures<sup>2,3</sup> and the assays were carried out as above depending on the nature of the compound.

#### Results and Discussion

**Absorbance curves:** The absorbance curves of reagent, primary arylamines and N-methylaniline show maximum absorbance at 500-520 nm; whereas catechol-iodine or primary arylamine-iodine show practically no absorption. The maximum intensity of the colour is developed within 5-20 min and is stable for 2 hr.

**Effect of pH:** The optimum pH range for complete colour development is 2.0-3.1 with all aromatic amines. Above pH 7.0, the colour begins to fade slowly. All studies are confined to pH  $3.0 \pm 0.1$ .

**Amount of catechol:** 0.5-1.5 ml of 0.1% catechol solution is required for maximum colour development. 1 ml of 0.1% catechol was used.

**Effect of oxidizing agent :** A study was made of the use of various oxidizing solutions to be employed in the formation of the coloured species with catechol and aromatic amines. It was found that iron(III) (1 ml ; 0.02 M), sodium metaperiodate (1 ml ; 0.01 M), ammonium vanadate (2 ml ; 0.01 N), chromium(VI) (1 ml ; 0.05 N), cerium(IV) (2 ml ; 0.01 N), hexacyanoferrate(III) (2 ml, 0.01 N) or iodine (1 ml ; 0.01 N) was necessary for complete colour development. If hydrogen peroxide is used, the experimental conditions are to be modified (catechol, 2 ml of 0.5% ; hydrogen peroxide, 1 ml of 1.8 N ; pH 2.1) and the time taken for complete colour development is 30-50 min. Of these oxidising agents, iodine was preferred as it gave maximum colour development within 5-20 min possessing considerable stability.

**Effect of the order of addition :** The order of addition of reagents does not have any influence on the colour development, if mixing is carried out immediately or adding catechol at the end even after 30 min. However, any delay in mixing aromatic amine to catechol-iodine reagent causes considerable decrease in absorbance.

Beer's law limits, molar absorptivity values and % recoveries are given in Table 1. The values obtained by the proposed method and the Bratton-Marshall method for dosage forms are given in Table 2. Ten replicate determinations were made with a typical aromatic amine (aniline) and the

TABLE 2—ASSAY OF PHARMACEUTICAL AROMATIC AMINES IN DOSAGE FORMS

Dosage form	Nominal content, g	Proposed method	Found, g Bratton-Marshall method
<b>Tablets</b>			
Sulphadiazine, 1 P <sup>*</sup>	0.500	0.493	0.496
Madribon-Sulphadimethoxine, B.P. <sup>*</sup>	0.500	0.487	0.491
Loderkyu-Sulphamethoxy pyridazine, B.P. <sup>*</sup>	0.500	0.502	0.508
Sulphapyridine, B.P. <sup>*</sup>	0.500	0.485	0.493
Sulphano-Sulphamoxole, B.P. <sup>*</sup>	0.500	0.481	0.485
Elkosin-Sulphasomidine, B.P. <sup>*</sup>	0.500	0.494	0.498
Thiazole-Phthalyl sulphathiazole, 1 P <sup>*</sup>	0.500	0.476	0.484
Folic acid, 1 P <sup>*</sup>	0.050	0.048	0.047
<b>Capsules</b>			
Chloramphenicol, 1 P <sup>*</sup>	0.250	0.244	0.246
<b>Eye drops</b>			
Albucid-sulphacetamide sodium, 1 P <sup>*</sup>	1.420	1.38	1.40

relative standard deviation was found to be 0.4%. The advantage of this new method is that it works with most of the dosage forms of aromatic amines and the results obtained are reproducible. Excipients and adjuncts usually present in dosage forms do not interfere. The other nitrogen bearing compounds such as aliphatic amines (primary, secondary and tertiary), cyclohexylamine, benzylamine, diphenylamine, 4-aminophenazone and N,N-dimethylaniline do not respond to the method.

**Interferences** The following amounts (ppm) of other constituents usually present in dosage forms are found to give less than 3% error in the determination of aromatic amines (e.g. sulphathiazole) talc (250), magnesium stearate (300), calcium phosphate (250), sodium chloride (350), chloramphenicol (250), penicillins (250), tetracycline (60), streptomycin (150), glucose (500) and trimethoprim (10%).

**Mechanism** Titrimetric studies to know the reactivity of iodine separately with catechol and aromatic amine (sulphanilamide) at pH 3.1 revealed that iodine reacts almost completely within 15 min with catechol, whereas it does not react at all with sulphanilamide even after 1 hr. It is well known that oxidation of catechol under acidic conditions with oxidizing agents takes place in two steps, each involving removal of one electron, first to the semiquinone (purple-red colour) then to the *o*-benzoquinone<sup>\*,\*</sup>. If catechol-iodine reagent is replaced by *o*-benzoquinone in the general procedure, development of purple-red colour does not take place indicating that *o*-benzoquinone is not involved. Probably the intermediate semiquinone (because of resonance stabilisation, possesses longer life time and do not tend to attack the solvent or to initiate olefinic polymerisation) interacts with aromatic amine for the colour development. The composition of the coloured species formed between catechol (excess)-iodine reagent (semiquinone) and primary aromatic amine was determined spectrophotometrically using Job's continuous variation

TABLE 1—SPECTROPHOTOMETRIC ASSAY OF AROMATIC AMINES

Amine	Beer's Law limits µg, 25 ml	Molar absorptivity at 520 nm 1 mol <sup>-1</sup> cm <sup>-1</sup> × 10 <sup>-3</sup>	Recovery %
Aniline	25-150	1.1	99.4
<i>o</i> -Toluidine	50-250	2.9	99.9
<i>p</i> -Toluidine	50-300	3.9	99.1
<i>p</i> -Chlor aniline	50-300	1.4	98.4
<i>p</i> -Nitro aniline	50-250	3.1	97.9
Sulphanilic acid	50-200	4.3	99.7
<i>p</i> -Aminobenzoic acid	50-300	1.1	100.1
<i>p</i> -Phenetidine	50-300	1.6	99.3
Sulphanilamide	50-200	1.3	99.7
Sulphaacetamide	50-200	1.3	100.1
Sulphadiazine	50-200	1.5	99.8
Sulphamerazine	50-200	1.6	99.1
Sulphathiazole	50-200	4.9	99.3
Sulphamoxole	50-200	1.8	99.8
Sulphacandine	50-200	1.7	99.4
Sulphathiazole	50-200	4.3	99.5
Sulphaphenazole	50-150	1.9	99.6
Sulphamethoxazole	50-150	1.6	100.2
Sulphapyridine	50-200	1.8	99.7
Ben-zocaine	50-200	5.0	99.9
Procaine	50-300	4.2	98.9
Hyposine	50-250	8.9	99.2
1-Naphthylamine	50-200	2.9	98.8
2-Naphthylamine	50-300	1.6	99.1
3-Methylaniline	25-100	1.2	99.5
acetyl sulphathiazole*	50-150	2.9	100.3
Chloramphenicol**	50-200	1.1	100.5
Folic acid***	50-150	2.8	100.8

\*After hydrolysis \*\*After reduction \*\*\* After reduction and applying suitable correction for free amine and using *p*-aminobenzoic acid as standard

and slope ratio methods. These methods show that iodine and primary arylamine combine in a 2:1 molar ratio. The failure in getting colour in alkaline pH clearly rules out the possibility of oxidative coupling between aromatic amine and catechol and so it is regarded as charge-transfer complex. The charge transfer may be presumed to be taking place involving electron transfer from the highest occupied  $\pi$  molecular orbital of the primary arylamine to the lowest unoccupied molecular orbital,  $\pi^*$ , of the semiquinone radicals as in the case of metol NBS reagent<sup>6</sup>.

#### Acknowledgement

Thanks of the authors are due to Dolphin laboratories, Smith Stanistreet Co., Roche Products, Ciba-Geigy, German Remedies and Cyanamide (India) Ltd, IDPL, Warner-Hindustan, and May and Baker, for gift of sulphonamides. The authors are grateful to C.S.I.R. and U.G.C. for Fellowships to (B.G.) and (K.V.S.S.M.).

#### References

1. J. L. LORIM, "Hand Book of Analytical Chemistry", MHC Publisher, Moscow, 1975, p. 255.
2. T. HIGUCHI and H. E. BAUMANN, "Pharmaceutical Analysis", Interscience, New York, 1961, p. 137.
3. M. M. AMER and M. I. WALASH, *Bull. Fac. Pharm. Cairo*, 1973, 2, 161.
4. S. W. WHEIDMAN and E. T. KAISER, *J. Amer. Chem. Soc.* 1966, 88, 5820.
5. J. C. P. SMITH and A. CARRINGTON, *Mol. Phys.* 1967, 12, 439.
6. U. S. PRAKASH SASTRY, B. G. RAO and B. S. REDDY, *J. Indian Chem. Soc.*, 1981, 58, 601.

### Spectrophotometric Determination of Palladium with Rubeanic Acid in Presence of Piperidine, Quinoline, $\alpha$ -Picoline and Collidine

M. R. SAHA and A. K. CHAKRABURTY

Department of Inorganic and Analytical Chemistry,  
Jadavpur University, Calcutta-700 032

Manuscript received 15 July 1981, revised 9 December 1981,  
accepted 28 April 1982

**R**UBEANIC acid in conjunction with different organic heterocyclic bases have been utilised to estimate Pd, Co and  $\text{Ni}^{2+}$ . It has been found that piperidine, quinoline,  $\alpha$ -picoline and collidine also enhance the colour and solubility of Pd(II) complex of rubeanic acid as a result of which rubeanic acid and one of the above four heterocyclic aromatic bases make a suitable ligand pair for the determination of palladium spectrophotometrically. Among the four bases studied, collidine is found to form the most effective ligand pair with rubeanic acid, the molar extinction coefficient in this case being distinctly higher than in other systems. The yellow colours which are developed

in the above four systems have been found to absorb maximally at 380 nm in case of piperidine and quinoline and at 410 nm in case of  $\alpha$ -picoline and collidine. The optimum pH range has been found to be 7-10.5 in each of the four systems where Beer's Law is obeyed.

#### Experimental

**Chemicals, reagents and apparatus:** Palladium solution was standardised by dimethylglyoxime. A 0.1% solution of rubeanic acid was prepared in 95% ethyl alcohol. The solution was found to remain stable for several days. 10% solution of each, in distilled ethanol, were obtained from freshly distilled piperidine, quinoline,  $\alpha$ -picoline and collidine (analytical grade).

All absorbance measurements were made with a Hilger-Uvispek spectrophotometer. The pH values are determined with an Elico Model LI-10 pH meter, the later values being with respect to aqueous alcoholic solution.

**Procedure** To a slightly acidic solution of palladium, free from interfering ions, 1 ml reagent solution (0.1% w/v) was added after the addition of any of the four bases for determinations with piperidine, quinoline,  $\alpha$ -picoline or collidine. 2 ml piperidine, 5 ml quinoline, 3 ml  $\alpha$ -picoline and 2 ml collidine were added before the addition of the reagent. The final volume was made up to 25 ml with distilled alcohol and the absorbance measured at 380 nm for piperidine and quinoline and at 410 nm for  $\alpha$ -picoline and collidine. The results of the above investigations are represented in Table 1.

**Composition of the complexes** The composition of the complexes as determined by Job's method of continued variation<sup>7</sup> and molar ratio method<sup>8</sup> shows that there are two different species with different heterocyclic base systems. While with pyridine and collidine, the presence of 1:1 metal:rubeanic acid ratio is observed, the 1:2 system seems to be predominant in other three systems (piperidine and rubeanic acid, quinoline and rubeanic acid and  $\alpha$ -picoline and rubeanic acid). Bobtelsky and Eisenstadter<sup>9</sup> found by heterometric titration and micro analysis of the dried product that palladium combines with rubeanic acid to afford a number of compounds having the composition  $\text{Pd}_2\text{Rba}_2$ ,  $\text{PdRba}$ ,  $\text{Pd}_2\text{Rba}_3$  and  $\text{PdRba}_2$  (where Rba=rubeanic acid molecule or its radical) depending on the pH of the medium during precipitation and the amount of reagent present<sup>9</sup>. In the present case the units containing one Pd ion (1:1 and 1:2 variety) seems to be stabilised by the additional ligation of heterocyclic bases.

The results of Job's method and molar ratio method of the four systems are represented graphically (Figs. 1-8).

TABLE-I

Metal ion.	Reagents	Beer's Law and optimum range	Sensitivity	Molar extinction coefficient
Pd <sup>2+</sup>	Rubeanic acid and piperidine	1-8.4 ppm	0.017 $\mu\text{g Pd/cm}^2$	8946
Pd <sup>2+</sup>	Rubeanic acid and quinoline	8-8.4 ppm	0.018 $\mu\text{g Pd/cm}^2$	8129
Pd <sup>2+</sup>	Rubeanic acid and $\alpha$ -picoline	0.625-4.1 ppm	0.019 $\mu\text{g Pd/cm}^2$	5819
Pd <sup>2+</sup>	Rubeanic acid and collidine	1.87-4.8 ppm	0.0104 $\mu\text{g Pd/cm}^2$	10311
Pd <sup>2+</sup>	Rubeanic acid and pyridine	0.625-4.875 ppm	0.0148 $\mu\text{g Pd/cm}^2$	7324




Fig. 1 Job's method of composition Pd(II) Rubeanic acid piperidine complex  
Pd(II) = Rubeanic acid =  $5.588 \times 10^{-4}$  M




Fig. 3 Job's method of composition Pd(II) Rubeanic acid quinoline complex  
Pd(II) = Rubeanic acid =  $5.5875 \times 10^{-4}$  M.




Fig. 2. Molar ratio method of composition, Pd(II) Rubeanic acid piperidine complex.  
Pd(II) = Reagent =  $5.588 \times 10^{-4}$  M.




Fig. 4. Molar ratio method of composition, Pd(II) Rubeanic acid quinoline complex.  
Pd(II) = Rubeanic acid =  $5.588 \times 10^{-4}$  M




Fig. 5 Job's method of composition. Pd(II) Rubenic acid  $\alpha$ -picoline complex.

Pd(II) = Rubenic acid =  $1.175 \times 10^{-4}$  M




Fig. 6 Molar ratio method of composition. Pd(II) Rubenic acid  $\alpha$ -picoline complex

Pd(II) = Rubenic acid =  $1.7625 \times 10^{-4}$  M




Fig. 7. Job's method of composition. Pd(II) Rubenic acid collidine complex.

Pd(II) = Rubenic acid =  $1.175 \times 10^{-4}$  M.




Fig. 8 Molar ratio method of composition. Pd(II) Rubenic acid collidine complex

Pd(II) = Rubenic acid =  $1.7625 \times 10^{-4}$  M

**Effect of diverse ions:** Solutions were prepared in the same way as described under absorbance curve with 2.5 ppm of palladium(II) in each case containing different amounts of each ionic species whose effects were studied. It is observed that copper(II), cobalt(II), nickel(II), platinum(IV), molybdenum(VI), vanadium(V), tungsten(VI), manganese(II) and chromium(III) interfered with the determination

#### References

- 1 J. XAVIER and P. BAY, *J. Indian Chem. Soc.* 1956, 35, 485
- 2 P. JON, *Compt. Rend.*, 1925, 190 928, *Ann. Chim. (Paris)* 1928, 9, 113.
- 3 A. E. HANCOCK JR and D. L. MANNING, *J. Amer. Chem. Soc.*, 1950, 72, 4488
- 4 F. B. SANDRELLI, "Colorimetric Determination of Traces of Metals", 3rd Edn., Interscience, New York 1958
- 5 M. B. SAHA, Ph.D. Dissertation, Jadavpur University, 1977
- 6 M. B. SAHA and A. K. CHAKRABORTY, *J. Indian Chem. Soc.* 1976, 53, 1187.
- 7 M. B. SAHA and A. K. CHAKRABORTY, *J. Indian Chem. Soc.*, (Communicated).
- 8 BORTSELSKY and BISENSTADTER, *Anal. Chem. Acta*, 1957, 17, 529.

#### Oxalyldihydrazide: A New Reagent for Rapid Gravimetric Determination of Selenium

ANIL K. SAVEJA and V. K. GUPTA\*

Department of Chemistry, Ravishankar University, Raipur-492 010, M. P.

Manuscript received 20 January 1981, revised 26 January 1982  
accepted 23 May 1982

THE growing importance of selenium in industry and chemistry is reflected by the large number of papers dealing with its determination by

different methods which have been nicely reviewed<sup>1,2</sup>. The literature contains a number of methods based on the reduction of selenium(IV) and selenium(VI) to elemental selenium<sup>3-14</sup>. Based on the above principle the present paper describes the use of oxalyldihydrazide as a very convenient reagent for gravimetric determination of selenium. The method described allows rapid determination of selenium up to a minimum 5 mg. It has also been applied to selenium and tellurium mixtures for simultaneous estimation of both. Estimation of selenium can be done in the presence of several other foreign ions without the use of any masking agent

### Experimental

**Apparatus** : The elemental selenium was collected on a sintered glass crucible (porosity G 4). A single pan semi-micro balance, VEB Analytik SAHM-68, was used for weighing

### Reagents

(a) **Selenium solution** : The selenium solution was prepared by dissolving reagent grade sodium selenite and the amount of selenium was gravimetrically determined by both sulphur dioxide<sup>15</sup> and hydroxylamine<sup>16</sup> methods. A working solution of 2 mg/ml Se was prepared by dilution

(b) **Oxalyldihydrazide solution** : A 2% w/v solution of oxalyldihydrazide was prepared in water. The reagent was prepared by reported method<sup>16</sup>.

(c) **Solution of foreign ions** were prepared by the method of West<sup>17</sup>

AnalaR grade HCl was used to maintain the acidity.

**Procedure** : A suitable aliquot of standard selenium solution was transferred to a beaker and diluted. 10 ml of 2% oxalyldihydrazide solution was added and the acidity maintained between 2-3 M with HCl to a final volume of 100 ml. The solution was boiled for 15 min for complete reduction and was filtered while warm on a sintered glass crucible. The precipitated selenium was washed with water and alcohol, dried at 110° and weighed. Results are shown in Table 1.

TABLE 1—RECOVERY OF SELENIUM  
Acidity=3 M HCl

Sl. No	Se taken mg	Se obtained* mg	Error %	Recovery %
1	10	10.01	+0.10	100.10
2	40	40.02	+0.05	100.05
3	100	99.98	-0.02	99.98
4	150	150.02	+0.01	100.01
5	250	250.01	+0.04	100.04

\*Mean of five replicates.

**Determination of selenium and tellurium** : Synthetic samples containing definite amounts of

selenium and tellurium were prepared. Selenium was determined by the recommended procedure. For the determination of tellurium, the filtrate was concentrated, 20 ml of 2% oxalyldihydrazide was added and the acidity was fixed to 6 M and above. The solution was boiled for 1 hr for complete reduction of tellurium. The precipitated tellurium was filtered on a sintered glass crucible, washed with water and alcohol, dried at 110° and weighed. Results are shown in Table 2.

TABLE 2—SELENIUM-TELLURIUM ANALYSIS IN SYNTHETIC SAMPLES

Acidity for Se=3 M HCl Acidity for Te=6 M HCl					
Se taken mg	Te taken mg	Se found* mg	Te found* mg	Se Recovery %	Te Recovery %
20	10	19.97	10.02	99.80	100.20
20	20	19.98	19.99	99.90	99.95
20	40	20.01	40.01	100.05	100.02
40	60	39.99	60.01	99.97	100.01
40	100	39.98	99.98	99.95	99.98

\*Mean of three replicates

### Results and Discussion

Preliminary experiments were conducted to find out the optimal conditions for complete reduction. The influence of the variables have been investigated.

**Acidity** : The optimal acidity range for complete reduction of selenium was found to be 2.5 to 8 M HCl. Effect of other acid media for reduction process was also studied. The reduction took more time in case of sulphuric acid and acetic acid whereas no reduction took place in case of nitric acid.

**Amount of reagent** : It was found out that 10 ml of 2% solution of oxalyldihydrazide was sufficient for the reduction of 250 mg of selenium.

**Effect of foreign ions** : Studies revealed that up to 20 fold excess of the following ions do not interfere : Cu(II), Ni(II), Mg(II), Mn(II), Zn(II), Hg(II), Cd(II), Co(II), Bi(III), Al(III), Sb(III), Fe(II), Fe(III), Sr(II), V(V), Nb(VI), Mo(VI), Ti(IV), Th(IV), Be(II), and up to 50 fold excess of NO<sub>3</sub><sup>-</sup>, PO<sub>4</sub><sup>3-</sup>, tartrate, citrate, EDTA, SO<sub>4</sub><sup>2-</sup>. In case of Ce(III), Cr(VI) and Fe(III), larger amount of reagent and longer heating time were required. Only tungsten interferes in the system but it can be first precipitated and then selenium can be determined in the filtrate.

**Comparison with other methods** : The proposed reagent is very suitable and selective for the determination of selenium. The reagent can be easily prepared, is stable and can be stored for long periods which is not possible with many of the reported methods<sup>3,11,12,14</sup>. Another outstanding feature of this reagent is that it can be used for simultaneous estimation of selenium and tellurium.

The method is very fast as compared to other methods<sup>1,2</sup>.

### Acknowledgement

The authors are grateful to Prof. S. G. Tandon, Head, Department of Chemistry, Ravishankar University, Raipur for facilities.

### References

- 1 I. ROSENFELD and O. A. BEATH, "Selenium", Academic Press, New York, N. Y., 1964.
- 2 A. I. BUSEV, V. G. TITSOVA and V. M. IVANOV, "Hand Book of the Analytical Chemistry of Rare Elements", Ann Arbor Humphrey Science Publishers, Ann Arbor, London, 1970.
- 3 H. GOTO and Y. KAKITA, *Soc. Rept. Res. Inst. Tohoku Univ. Ser.*, 1952, 4, 121, *Chem. Abs.*, 1953, 47, 26350.
- 4 S. M. DESAI, *Rev. Obras Sav. Nac. Buenos Aires*, 1974, 20, 264, *Chem. Abs.*, 1948, 42, 2039b.
- 5 S. S. R. MURTHY, *Indian J. Chem.*, 1965, 3, 298.
- 6 G. J. MISRA and J. P. TANDON, *Indian J. Chem.*, 1967, 5, 560.
- 7 I. K. TAIMNI and M. N. SRIVASTAVA, *Anal. Chem. Acta*, 1956, 15, 517.
- 8 S. E. WISERLY *et al.*, *Anal. Chem.*, 1958, 25, 1586.
- 9 V. SIMON and V. GRIM, *Chem. Lett.*, 1954, 48, 1774, *Chem. Abs.*, 1955, 49, 4453b.
- 10 J. PIDLER, *Chem. Lett.*, 1952, 46, 221, *Chem. Abs.*, 1952, 46, 11029c.
- 11 L. R. MALEWAR and K. SATYANARAYANA, *J. Indian Chem. Soc.*, 1977, 54, 1165.
- 12 J. K. DIWAN and K. SATYANARAYANA, *Talanta*, 1978, 25, 44.
- 13 SUGAWARA, KUNIKI and TANTO, *Kochi Bunseki Kagaku*, 1977, 26, 803.
- 14 J. K. DIWAN and K. SATYANARAYANA, *J. Less Common Met.*, 1977, 55, 165.
- 15 A. I. VOGEL, "Text Book of Quantitative Inorganic Analysis", Longmans, London, 1962, p. 509.
- 16 J. NAIR and V. K. GUPTA, *Pollution Monitor*, 1978, 44, 33.
- 17 P. W. WEST, *J. Chem. Educ.*, 1941, 18, 528.

### Detection and Determination of Phosphate Using Monomethyl-*p*-Amidophenol as Reagent

N KRISHNA MURTY\* and A. V. SURYANARAYANA

Department of Engineering Chemistry, Andhra University, Waltair-580 008

Manuscript received 10 April 1981, revised 4 January 1982, accepted 28 April 1982

**M**OST of the methods available for the detection and determination of phosphate are indirect involving complexation of phosphate with molybdenum(VI) and subsequent reduction of the phosphomolybdate. The reagents used for the detection of phosphate are ammonium molybdate and benzidine<sup>1</sup>, *o*-dianisidine molybdate and hydrazine<sup>2</sup>, quinolinium molybdate<sup>3</sup> and ammonium molybdate and triphenyl methane dyes<sup>4,5</sup>. The reducing agents used for the development of the blue colour are tin(II) chloride<sup>6</sup>, hydroquinone<sup>7</sup>, hydrazine sulphate<sup>8</sup>, ascorbic acid<sup>9</sup> and 1,2,4-aminonaphthol sulphonic acid<sup>10</sup>. A few other methods, involving extraction of the blue colour

into an immiscible organic layer are also reported. Very few reports are available for direct detection and determination of phosphate.

The method for detection and determination of phosphate reported in this communication, is a simple and direct one. The phosphate in solution, on reaction with monomethyl-*p*-amidophenol in 1-5 *N* HCl or in 1-10 *N* H<sub>2</sub>SO<sub>4</sub>, will oxidise it to purple-red *p*-N-methylquinone. The absorption spectrum of the purple-red coloured solution gives maximum absorption at 525 nm.

### Materials and method :

**Standard phosphate solution :** 0.2197 g of potassium dihydrogen phosphate (previously dried at 110° for 1 hr and cooled in a desiccator) is dissolved in deionised water and diluted to 1 litre in a volumetric flask. 1 ml of this solution contains 0.05 mg P.

**Monomethyl-*p*-amidophenol solution :** 0.05 *M* solution is prepared by dissolving 17.190 g of the reagent (AnalaR grade) in 1 litre deionised water and standardised vanadometrically<sup>11</sup>.

All other reagents used are of AnalaR grade unless otherwise mentioned.

Beckmann-26 spectrophotometer with auto recorder is used for spectral measurements.

### Experimental

**Detection of phosphate in a test tube :** 0.5 ml of the test solution is taken in a test tube and 0.5 ml of monomethyl-*p*-amidophenol reagent solution is added followed by 1.5 ml of 2.5 *N* HCl. A purple-red colour develops immediately on shaking the test tube which indicates the presence of phosphate.

Limit of detection—2.63 µg/2.5 ml

Limit of dilution—1 : 2,000

**Detection of phosphate on a spot plate :** 0.04 ml of the test solution is taken in the cavity of the spot plate. 0.04 ml of the reagent followed by 0.04 ml HCl (1 : 4) are added and mixed with a glass rod. An immediate purple-red colour, stable for 48 hr indicates the presence of orthophosphate.

Limit of detection—0.53 µg/0.12 ml

Limit of dilution—1 : 10,000

**Photometric determination of phosphate :** To a known volume of the sample solution containing 4-13 µg of P in a 10 ml volumetric flask are added successively 3 ml of 0.05 *M* monomethyl-*p*-amidophenol and 1 ml of conc. HCl. The volume is made up to the mark with distilled water. The absorbance of the purple-red coloured solution, the oxidation product of the reagent, is measured at 525 nm against a reagent blank.

Typical results are presented in Table I.

### Results and Discussion

By preliminary experiments it is found that the acidity should be in between 1-5 *N* for HCl and

TABLE 1—SPECTROPHOTOMETRIC DETERMINATION OF PHOSPHATE USING MONOMETHYL-*p*-AMIDOPHENOL AS REAGENT


Sl. No.	Sample	Taken	P in $\mu\text{g}$ found*	Standard deviation
1.	$\text{Na}_3\text{PO}_4$	4.9274	4.9280	$\pm 0.01591$
2.	$\text{Na}_2\text{HPO}_4$	8.2125	8.2128	$\pm 0.01190$
3.	$\text{Na}_2\text{HPO}_4$	9.0652	9.0695	$\pm 0.01807$
4.	$(\text{Ca})_3(\text{PO}_4)_2$	11.8879	11.8883	$\pm 0.03901$
5.	NPK fertilizer	10.8438	10.8436	$\pm 0.02278$
6.	NPK fertilizer	6.5261	6.5264	$\pm 0.00702$

\* Average of five readings.

1-10 *N* for  $\text{H}_2\text{SO}_4$ . Below 1 *N* the colour development is rather slow and above 5*N* (10 *N* for  $\text{H}_2\text{SO}_4$ ) the colour developed gets discharged. HCl medium is preferred to  $\text{H}_2\text{SO}_4$  as the colour developed in  $\text{H}_2\text{SO}_4$  medium is less stable due to the heat developed in the mixing process. The oxidation of the reagent to *p*-N-methylquinone takes place readily in acid medium. It is observed that the colour attains maximum intensity within 5 min after mixing the reagent and remains stable for 48 hr, if the reductant is in excess.

The reagent prepared in distilled water is stable for 4 hr. The stability can be enhanced up to 10 hr if preserved in ambered coloured bottles. On prolonged preservation a brownish-red colour develops in the reagent solution due to aerial oxidation and this interferes in the process of oxidation by phosphate.

It is found that chloride, bromide, sulphate, metaborate, thiocyanate, silver(I), gelatin, *p*-hydroxyglycine, acetone, hydroquinone, iron(II), tin(II), arsenic(III), triphosphates or tetraphosphates do not interfere in the said conditions, but dichromate, cerate, quinones, citrate, oxalate, sulphite and bisulphite interfere seriously.

Fig 1 Absorbance spectrum of oxidation product of monomethyl-*p*-amidophenol with phosphate

## Acknowledgement

The authors are thankful to the C.S.I.R., New Delhi, for the award of Junior Research Fellowship to one of them (A.V.S.N.).

## References

1. F. FRIGL, *Z. anal. Chem.*, 1922, 61, 454
2. J. W. ROBINSON and P. W. WEST, *Machrochem. J.*, 1957, 1, 93.
3. I. S. ZACHNER, *Machrochem. Acta*, 1957, 150.
4. A. K. BAKKO, Y. F. SHKARAVSKII and R. M. IVASHKOVICH, *Ukr. Khim. Zh.*, 1957, 33, 951
5. F. JUNGNIER, *J. Chromatogr.*, 1957, 31, 617.
6. S. R. DICKMAN and R. H. BRAY, *Ind. Eng. Chem. Anal. Ed.*, 1940, 12, 605.
7. T. S. HARRISON and H. STORR, *J. Soc. Chem. Ind.*, 1944, 63, 154.
8. D. F. BOLTZ and M. G. MELLON, *Anal. Chem.*, 1947, 19, 873.
9. J. MURPHY and J. P. RILEY, *Anal. Chem. Acta*, 1962, 27, 81.
10. M. ADILA, *Rev. Quim. Farm.*, 1944, 2, 2.
11. G. GOPALARAO and T. P. SASTRY, *Z. anal. Chem.*, 1956, 151, 415



## Book Review

**Experimental Organic Chemistry by P. R. Singh, D. S. Gupta and K. S. Bajpal, Tata McGraw-Hill, 1981, Vol. 1. xvii+267 (Rs. 27.00) ; Vol. 2 xix+378 (Rs. 27.00).**

This book is designed as a text for an advanced undergraduate as well as post-graduate course in practical organic chemistry. Keeping in view its objectives, the development of theoretical background for experimental work, depth of coverage, selection of the list of experiments and the price make it an ideal choice both for the students as well as for the teachers. The book has been written in a lucid, non intimidating manner without, however, sacrificing the finer experimental details, wherever necessary.

The first volume deals with the preparative aspect of the practical organic chemistry. This has been divided into two parts comprising thirteen chapters. The first part concerns the basic techniques of practical organic chemistry presenting the subject matter in reasonable detail with inclusion of a brief introductory chapter on the working in the laboratory and safety measures.

A full chapter has been devoted to the Chromatographic Techniques which are now imperative in experimental organic chemistry. The chapter is well illustrated and all the necessary details are briefly incorporated.

The chapter on Spectroscopic Techniques, though enhances the utility of the book, is conspicuously inadequate. Although it includes the necessary theoretical and experimental details of IR, UV, PMR and Mass spectroscopic techniques, it lacks some illustrative problems of simple structural elucidation based on the combined use of these methods. Nevertheless, the Tables are quite comprehensive which, to some extent, covers this lapse.

The chapter seven, "Sources of Library Information" provides a list of useful current reference books, journals and abstracts.

The second part of volume one covers organic preparations which have been logically classified into several groups based on reaction mechanism. Each chapter first provides a brief introduction to the relevant reaction mechanism followed by experimental details of some selected preparations. Although the preparations are reasonably diversified, it appears that some pages could have been saved here and added more beneficially to the chapter on Spectroscopy, as mentioned above.

Volume Two has also been divided into two parts. The first part dealing with Qualitative Analysis comprises seven chapters. This part has been written in a routine manner. The characteristic IR absorption peaks have also been given for each class of compounds. However, it would have been better, had the IR spectrum of a representative compound of each class been reproduced. The Tables include a sufficient number of organic compounds with their relevant properties.

Part two concerns Quantitative Analysis including estimation of elements and functional groups followed by some experiments on Reaction Kinetics and some Miscellaneous Experiments. All the relevant details have been described briefly and this part seems complete in itself. Some experiments of industrial importance have also been incorporated in this section.

Each chapter ends with a few problems, which in some cases form a corollary to what has been described in that particular chapter. Many problems are quite interesting and are likely to induce the students to develop insight in the subject.

The appendices contain hints to some selected problems given in the chapters, as well as additional bibliography, methods of preparation of reagents and indicators and also some physical constants.

In summary, it can be said that this book succeeds in its objective of providing all the material of practical organic chemistry at one place to those for whom this book has been written.

**R. K. Bansal**

Now there is  
greater safety in surgery as  
**MANNITOL**  
is available

The arrival of Mannitol after 1962  
as osmotic diuretic after surgery  
have saved millions of lives in India.

Before the arrival of Mannitol  
kidney failure was a great hazard  
after urinary, brain and open heart  
surgeries. Today Mannitol infusion  
is indispensable as osmotic diuretic  
to surgeons.

SM brand Mannitol B.P. has been  
accepted with confidence by  
pharmaceutical industry for  
Mannitol infusion in India for  
over 16 years.



**SARABHAI M CHEMICALS**

Pioneer manufacturers of Mannitol.

SM/1075 R



# Metal Complexes of Some Model Peptides. Part—I : Complex Formation of Cu(II) with N-Salicyloyl Glycine

G. N. MUKHERJEE\*, (Miss.) S. SARKAR and S. K. CHATTERJEE

Department of Chemistry, University College of Science, Calcutta-700 009;

Manuscript received 9 March 1981, revised 7 April 1982, accepted 21 July 1982

**ABSTRACT.** pH-Metric study of the interaction of Cu(II) with N-salicyloyl glycine, *o*-(OH)-C<sub>6</sub>H<sub>4</sub>CONHCH<sub>2</sub>COOH, LH<sub>2</sub>, indicated the stepwise formation of 1:1 and 1:2 metal: ligand complexes. The phenolic -OH group was not involved in coordination to Cu(II), as its deprotonation occurred only after the completion of formation of the 1:2 complex. Coordination from the N-(peptide) atom occurred only through deprotonation. The stepwise equilibrium constants (K', and K'') of complex formation, stepwise deprotonation constants (K<sub>OH</sub> and K<sub>OH</sub>) of the 1:2 complex, Cu(LH)<sub>2</sub> ion and successive acid dissociation constants (K<sub>COOH</sub>, K<sub>OH</sub> and K<sub>NH</sub>) of the ligand LH<sub>2</sub> have been determined. The overall stability constants, β<sub>qr</sub> of the complexes [Cu<sub>q</sub>H<sub>q</sub>L<sub>r</sub><sup>2+q-1</sup>] have been calculated. The pK', pK'', pK<sub>OH</sub>, pK<sub>OH</sub>, pK<sub>COOH</sub>, pK<sub>OH</sub>, pK<sub>NH</sub>, log β<sub>111</sub>, log β<sub>122</sub>, log β<sub>133</sub> and log β<sub>144</sub> values have been found to be 6.54±0.04, 6.76±0.04, 8.68±0.04, 9.46±0.04, 4.26±0.02, 9.12±0.04, 12.88±0.04, 6.84±0.04, 13.46±0.04, 17.66±0.04 and 21.08±0.04, respectively at 30±0.5° in 50% (v/v) water-ethanol at a constant ionic strength μ=0.2 M (NaClO<sub>4</sub>). Trends in the pK<sub>OH</sub> values of the free and of the complexed ligand and the equilibrium distribution of the complex species have been discussed.

THE model peptide ligand N-salicyloyl glycine, *o*-(OH)C<sub>6</sub>H<sub>4</sub>CONHCH<sub>2</sub>COOH, (LH<sub>2</sub>) is widely used as an anti-inflammatory drug<sup>1</sup>. In the present work its interaction with Cu(II) ion has been followed pH-metrically at 30±0.5° in 50% (v/v) water-ethanol medium at a constant ionic strength, μ=0.2 M (NaClO<sub>4</sub>). The study indicated the stepwise formation of 1:1 and 1:2 metal: ligand complexes in which coordination to the metal was provided by the carboxylic oxygen and the N-(peptide) atom of the ligand. Coordination of the N-(peptide) atom occurred only on deprotonation<sup>2-12</sup>. Deprotonation of the phenolic-(OH) group occurred only after the completion of the formation of the 1:2 complex suggesting non-involvement of this group in coordination.

## Experimental

The ligand, N-salicyloyl glycine, was prepared and purified by the reported procedure<sup>14</sup>. All other reagents were either of A. R. quality or properly purified and their solutions were made in double distilled CO<sub>2</sub> free water and purified and dry ethanol<sup>15</sup>.

pH-Metric titrations of 50 ml solutions of the following compositions :

- (i) 0.02 M HClO<sub>4</sub>,
- (ii) 0.02 M HClO<sub>4</sub>+0.01 M LH<sub>2</sub>,
- (iii) 0.02 M HClO<sub>4</sub>+0.01 M LH<sub>2</sub>+0.001 M Cu(ClO<sub>4</sub>)<sub>2</sub>,
- (iv) 0.02 M HClO<sub>4</sub>+0.01 M LH<sub>2</sub>+0.002 M Cu(ClO<sub>4</sub>)<sub>2</sub>,

were performed in 50% (v/v) water ethanol medium with a standard NaOH solution in the same solvent medium maintaining a constant ionic strength, μ=0.2 M by adding requisite amounts of NaClO<sub>4</sub> at 30±0.5°. pH measurements were made with a Cambridge pH-meter (Portable type) having a glass electrode of 1-13 pH range and a saturated calomel electrode connected to the cell by means of an agar 2 M NaNO<sub>3</sub> bridge. The meter was calibrated using standard 0.02 M HClO<sub>4</sub>, phthalate buffer and borate buffer solutions with appropriate temperature corrections.

Titration curves, pH vs volume of alkali, were drawn (Fig 1) and the necessary concentration variables e.g.  $\bar{n}_H$ ,  $\bar{n}$ ,  $\bar{n}_{OH}$ ,  $pLH_2$ , etc. were calculated following the procedure of Irving and Rossotti<sup>16</sup>.

## Results and Discussion

*Stepwise acid dissociation of N-salicyloyl glycine (LH<sub>2</sub>) :*

Consumption of more than two equivalents of alkali per mole of the ligand N-salicyloyl glycine in the pH range 2.5 to 12.5 in the titration of solution (ii) indicated three successive steps of its acid dissociation as represented by the equilibria (1)-(3).





where  $k_{COOH}$ ,  $k_{OH}$  and  $k_{NH}$  are the successive acid dissociation constants. The possibility of enolisation,  $-CONH- \rightleftharpoons -C(OH)=N-$ , of the peptide




Fig. 1. pH-titration curves. Initial volume 50 ml in 50% (v/v) water-ethanol, ionic strength,  $\mu = 0.2$  ( $NaClO_4$ ) in each case.

Curve 1: 0.02 M  $HClO_4$ .

Curve 2: 0.02 M  $HClO_4$  + 0.01 M *N*-salicyloylglycine, ( $LH_2$ ).

Curve 3: 0.02 M  $HClO_4$  + 0.01 M *N*-salicyloylglycine, ( $LH_2$ ) + 0.001 M  $Cu(ClO_4)_2$ .





Curve 4: 0.02 M  $HClO_4$  + 0.01 M *N*-salicyloylglycine, ( $LH_2$ ) + 0.001 M  $Cu(ClO_4)_2$ .  
Titrant: 0.125 M  $NaOH$  ( $\mu = 0.2$ )

group could not, however, be ruled out. The plot of  $\bar{n}_H$  (the average number of protons bound to the ligand ion,  $L^{2-}$ ) against pH showed that the steps (1), (2) and (3) were all independent of one another and therefore, the constants  $k_{COOH}$ ,  $k_{OH}$  and  $k_{NH}$  were evaluated by curve fitting method for one step system and also by the method of linear plots. The refined  $pK_{COOH}$ ,  $pK_{OH}$  and  $pK_{NH}$  values are given in Table I.

#### Complexation of Cu(II) with *N*-salicyloyl glycine :

The nature of the pH titration curves of the ligand solution in the presence of Cu(II) (curves 3, 4; Fig. 1) indicated the liberation of four equivalents of acid per gm ion of the metal in the pH range from 2.5 to 7.0 and two further equivalents of acid in the pH range from 7.75 to 10.50. The buffer region corresponding to the liberation of the latter two equivalents of acid was practically the same as that was corresponding to the deprotonation of the  $-OH$  group of the ligand in the absence of Cu(II). Therefore, the liberation of four equivalents of acid at the early stages of the reaction below pH 7

is clearly due to coordination of  $-COOH$  group and N-(peptide) $^{17}$  atom to Cu(II) each with deprotonation, ultimately leading to the formation of the 1 : 2 complex  $[Cu(LH)_2]^{2-}$ , according to the reactions (4) and (5), and these were followed by the deprotonation of the phenolic-OH groups not coordinated to the metal in the pH range 7.75-10.50 in a stepwise manner according to the reaction (6) and (7) :



where  $K'_1$ ,  $K'_2$ ,  $k_{2OH}$  and  $k_{1OH}$  are the equilibrium constants of the respective complexation and deprotonation steps and  $LH_2^{2-}$  stands for the ligand ion  $o-(HO)C_6H_4CONCH_2COO^{2-}$ .

The presence of the phenolic-OH group in the isolated compound  $Cu(LH)_2 \cdot 2H_2O$  was indicated by the appearance of an intense violet colour on addition of neutral  $FeCl_3$  to its aqueous ethanolic solution and also by the appearance of a broad ir band in the region  $3500-3000\text{ cm}^{-1}$ . The green compound  $Cu(LH)_2 \cdot 2H_2O$  was obtained by treating a solution of the ligand  $LH_2$  (0.1 mole) with equimolar amount of copper sulphate solution in hot water and adjusting the pH to  $\approx 4.5$ . It was recrystallised from ethanol, air dried and analysed. Found : Cu, 21.86; N, 4.29; loss at  $105^\circ$ , 12.17%. Calcd. for  $Cu(LH)_2 \cdot 2H_2O$ ; Cu, 21.72; N, 4.78;  $H_2O$ , 12.31%. Metal : ligand ratios in the complexes formed in solution were also determined spectrophotometrically at 610 nm by the method of continuous variation, under the same experimental conditions at two different pH values, viz., at pH = 7 where  $\bar{n} \approx 4$  and at pH  $\approx 11$  where  $\bar{n}_{OH} \approx 0$ . At both the pH values the maximum absorption corresponded to the 1 : 2 metal : ligand ratio. Therefore, liberation of acid at pH values higher than 7 was due to deprotonation of the 1 : 2 complex, and not due to the formation of higher complexes. The  $pK'_1$  and  $pK'_2$  values were evaluated from the plot of  $\bar{n}$ , the average number of protons liberated due to reactions (4) and (5), against  $pLH_2 - 2pH$  and were refined by various computational methods $^{17}$ . The  $\bar{n}$  values were calculated using portion of the titration curves (3 and 4; Fig. 1) from pH 2.5 to pH 7.0 and assuming all the Cu(II) ions in the forms of  $Cu^{2+}$ ,  $Cu(LH)$  and  $Cu(LH)_2^{2-}$  ion, in this pH range. The values of  $pK_{2OH}$  and  $pK_{1OH}$  were evaluated from the plot of  $\bar{n}_{OH}$ , the average number of protons bound to the complex  $[Cu(LH)_2^{2-}]$  ion against pH, assuming all the Cu(II) ions in the forms of the complexes  $Cu(LH)_2^{2-}$ ,  $Cu(L)(LH)^{-}$

TABLE 1—PROTON LIGAND AND CU(II)-LIGAND STABILITY CONSTANTS AT  $30 \pm 0.5^\circ$ ,  $\mu = 0.2$  (NaClO<sub>4</sub>) 50% (v/v) WATER-ETHANOL

$pK_{\text{COOH}} = 4.28 \pm 0.02$	$pK_1 = 6.54 \pm 0.04,$	$\log \beta_{111} = 6.84 \pm 0.04$
	$pK' = 6.76 \pm 0.01,$	$\log \beta_{112} = 13.46 \pm 0.01$
$pK_{\text{OH}} = 9.12 \pm 0.04$	$pK_{\text{H}} = 8.68 \pm 0.04,$	$\log \beta_{113} = 17.66 \pm 0.04$
$pK_{\text{NH}} = 12.88 \pm 0.01$	$pK_{\text{OH}} = 9.46 \pm 0.04,$	$\log \beta_{114} = 21.06 \pm 0.04$

and  $\text{Cu}(\text{L})_2^{4-}$  in the pH range from 7.75 to 10.5, and were refined as before<sup>17</sup>.

The overall stability constants<sup>18,19</sup> of these Cu(II) complexes of the general formula  $[Cu_pH_qL_r]^{(2p+q-rx)+}$  as defined by the relation .

$$\beta_{\text{par}} = \frac{[\text{Cu}_p\text{H}_q\text{L}_r^{(2p+q-rx)+}]}{[\text{Cu}^{2+}]^p[\text{H}^+]^q[\text{L}^{x-}]^r} \quad \dots (8)$$

were calculated using  $p=1$  and  $x=3$ . Concordance of duplicate titrations [soln (iii) and (iv)] using two different concentrations of the metal ion ruled out the possibility of formation of any polynuclear complex under the condition studied. The overall stability constants  $\beta_{111}$ ,  $\beta_{122}$ ,  $\beta_{112}$  and  $\beta_{10}$ , have been evaluated from the relations :

$$\beta_{111} = \frac{[\text{Cu}(\text{LH})^0]}{[\text{Cu}^{2+}][(\text{LH})^{2-}]} = \frac{K'_1}{K_{\text{срррпкн}}} \quad \dots (9)$$


$$\beta_{1,2,2} = \frac{[\text{Cu}(\text{LH})_2^{2-}]}{[\text{Cu}^{2+}][(\text{LH})^{2-}]^2} = \frac{K'_1 K'_2}{(K_{\text{COOH}} K_{\text{OH}})^2} \quad \dots (10)$$

$$\beta_{112} = \frac{[\text{Cu}(\text{LH})(\text{L})^{2-}]}{[\text{Cu}^{2+}][\text{LH}^{2-}][\text{L}^{2-}]} = \frac{\beta_{112} k_{2\text{OH}}}{K_{\text{NH}}} \quad (11)$$

$$\beta_{102} = \frac{[\text{Cu}(\text{L})_2^{4-}]}{[\text{Cu}^{2+}][\text{L}^{2-}]^2} = \frac{\beta_{112} \cdot k_{1\text{OH}}}{k_{\text{NH}}} \quad (12)$$

The refined  $\log \beta_{\text{nar}}$  values are shown in Table 1.

Although the possibility of enolisation of the peptide group prior to deprotonation cannot be ruled out, metal ions such as Cu(II), Ni(II), Co(II) will prefer to bind with the N-(peptide) atom rather than the O-(peptide) atom because of the comparatively strong ligand field that the former can provide. In the absence of X-ray data, it is however, not possible to decide which atom of the peptide group is actually bonded to the metal in the complexes. The  $pK_{a,OH}$  value of the complex  $Cu(LH)_2^{2-}$  ion has been found to be slightly lower than the  $pK_{OH}$  of the ligand,  $LH_2$ , as a consequence of N-(peptide)  $\rightarrow$  metal sigma bond formation. Due to much accumulation of negative charge on the metal, the subsequent deprotonation is, however, less favoured, even the possibility of some back donation through the pi-system of the peptide bond cannot be ruled out. As a matter of fact,  $pK_{a,OH}$  of the complex is slightly higher than the  $pK_{OH}$  of the ligand. Equilibrium concentrations of the various species involved in the complexation reaction were calculated and the distribution curves (Fig. 2) were constructed. At pH near 7.0 almost



**Fig. 2. Complex distribution curve.**

all the metal remain in the form of the 1 : 2 complex  $\text{Cu}(\text{LH})_2^{2-}$  and concentration of the 1 : 1 complex  $\text{Cu}(\text{LH})$  is negligible. Therefore, the assumptions made in the evaluation of the constant  $k_{\text{aOH}}$  and  $k_{\text{OH}}$ , that the complexation steps (4) and (5) were not overlapping with the deprotonation steps (6) and (7) are justified.

## References

1. M. W. WHITEHOUSE, I. KIPPEN and J. R. KLINGENBERG, *Biochem. Pharmacol.*, 1971, 20, 3809, *Chem. Abs.*, 1972, 76, 185599s.
2. THOMAS A. NEUBECKER, SANFORD T. KIRKSEY, JR., K. L. CHELLAPPA and DALA W. MARGRUM, *Inorg. Chem.*, 1979, 18, 444
3. A. R. MANYAK, O. B. MURPHY and A. E. MARTELL, *Arch. Biochem. Biophys.*, 1955, 59, 373.
4. H. DOBBIN and W. O. KRAMACK, *Biochem. J.*, 1956, 59, 287.
5. A. E. MARTELL, "Recent Topics in Coordination Chemistry", (Eds) S. MIYUMI and K. UENO, Nankodo Publishing Co., Tokyo, Japan, 1968, Special Publication, No. 84, p. 47.
6. M. K. KIM and A. E. MARTELL, *J. Amer. Chem. Soc.*, 1966, 88, 914.
7. R. B. MARTIN, M. CHAMBERLIN and J. T. EDSALL, *J. Amer. Chem. Soc.*, 1960, 82, 495.
8. M. K. KIM and A. E. MARTELL, *J. Amer. Chem. Soc.*, 1967, 89, 6198.
9. H. O. FREEMAN, "The Biochemistry of Copper", (Eds) J. PIERCECH, P. A. AISEN and W. E. BLUMBERG, Academic Press, New York, N.Y., 1966.

10. M. S. MICHAELIDIS and R. B. MARTIN, *J. Amer. Chem. Soc.*, 1969, **91**, 4693.
11. P. J. MORRIS and R. B. MARTIN, *Inorg. Chem.*, 1971, **10**, 964.
12. E. W. WILSON, JR. and R. B. MARTIN, *Inorg. Chem.*, 1970, **9**, 528.
13. J. C. COOPER, L. F. WANG and D. W. MARGHEM, *Inorg. Chem.*, 1978, **17**, 261.
14. K. H. FOROMMING and W. VOLLENBERG, *Arch. Pharm.*, 1966, **299**, 179; *Chem. Abs.*, 1966, **64**, 15981b.
15. A. I. VOGEL, "Text Book of Practical Organic Chemistry", ELBS, 1968, p. 167.
16. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 3904.
17. F. J. C. ROSSOTTI and H. S. ROSSOTTI, "The Determination of Stability Constants", McGraw-Hill Book Co. Inc., New York, Toronto, London, 1961, Ch. 5, p. 83.
18. B. B. RABIN, *Biochem. Soc. Symp.*, 1968, **15**, 21.
19. H. C. FREEMAN, "Inorganic Biochemistry", (Ed.) G. L. RICHMOND, Elsevier Scientific Publishing Company, Amsterdam-London-New York, 1973, Vol. 1, p. 131.

# Stacked Ternary Complexes of Salicylanilide, Dithionon and Tryptophan with Co(II), Ni(II) and Cu(II)

R. SAHA<sup>\*</sup>, S. AGRAWAL and S. S. S. KUSHWAHA

Department of Chemistry, V. S. S. D. College, Kanpur University, Kanpur-208 002

Manuscript received 27 July 1981, revised 26 April 1982, accepted 21 July 1982

Formation constants of ternary complexes of the types  $MAL^+$  and  $MAL$  [where  $M=Co(II)$ ,  $Ni(II)$  or  $Cu(II)$ ,  $A=dth(MAL^+)$  or  $trp(MAL)$  and  $L=trp(MAL^+)$  or  $sal(MAL)$ ] have been determined in solution potentiometrically, to provide further evidence on complexation as a possible mode of action of fungicides. The formation tendency ( $\Delta \log K_M$ ) of these complexes has been found to be positive for  $MAL^+$  type of complexes which has been explained as being due to  $M \rightarrow dth$   $\pi$ -interaction and has also indicated intramolecular aromatic ring stacking between the ring systems of the two ligands. The negative values of  $\Delta \log K_M$  have been found to be due to weak  $M \rightarrow trp$   $\pi$ -interaction and absence of intramolecular aromatic ring stacking.

It was observed in our previous investigation<sup>1</sup> that salicylanilide forms considerably stable complexes with some metal ions of biological interest, such as  $Co(II)$ ,  $Ni(II)$ ,  $Cu(II)$ ,  $Zn(II)$ ,  $Zr(IV)$ ,  $La(III)$  and  $Th(IV)$ , thereby supporting complexation as a possible mode of action of this fungicide. Since some specific structural requirements<sup>2</sup> are essential for the occurrence of complexation and also for a compound to show activity<sup>3</sup>, ternary complexes of salicylanilide (*sal*), dithionon (*dth*) and tryptophan (*trp*) with  $Co(II)$ ,  $Ni(II)$  and  $Cu(II)$  have been studied in solution to provide further evidence of complexation mechanism.

## Experimental

**Materials:** The metal nitrates used were of A. R. grade. Salicylanilide was obtained from Boots Chemical, UK. Other chemicals were B.D.H. AnalaR grade. Dioxane was used after purification. A 70% aqueous dioxane (v/v) was chosen to keep salicylanilide, dithionon and their complexes in solution. All measurements were performed at constant ionic strength ( $0.1 M KNO_3$ ) and constant temperature ( $25^\circ$ ).

**Method:** The binary systems were investigated with 1 : 2 molar ratio of metal ion and ligand while the ternary systems were studied in 1 : 1 : 1 molar ratio of a metal ion, a primary ligand (*trp* or *dth*) and a secondary ligand (*sal* or *trp*) in acidic and non-acidic medium. The change in the pH of the solution, with each addition of  $0.1 M NaOH$  solution was recorded with a Beckman pH meter equipped with a glass-calomel assembly. The pH values were corrected for 70% aqueous dioxane (v/v) medium using the method of Van Uitert and Haas<sup>4</sup>.

**Calculations:** The protonation constants and the stability constants (Table 1) of the parent binary complexes of *sal* and *trp* were calculated by computational methods of Irving and Rossotti<sup>5</sup>. Although most of the protonation and stability constants of parent binary complexes of *trp* are studied in aqueous medium<sup>6,7</sup>, these were redetermined due to the change in medium of investigation. The stability constants of binary complexes of *dth* could not be calculated because evaluation of its protonation constant proved unsuccessful due to overlapping nature of the titration curves of ligand with or without mineral acid ( $HNO_3$ ). It is

TABLE 1—STABILITY CONSTANTS OF BINARY AND TERNARY METAL COMPLEXES OF SALICYLANILIDE, TRYPTOPHAN AND DITHIONON IN 70% AQUEOUS DIOXANE (v/v),  $\mu=0.1 M (KNO_3)$ ,  $T=25^\circ$

Primary ligand	Secondary ligand	Metal Ion	$\log K^M_{MA}$	$\log K^{MA}_{MA_2}$	$\log K^M_{ML}$	$\log K^{ML}_{ML_2}$	$\log K^M_{MAL}$	$\Delta \log K$
Trp	Sal	Co(II)	4.42	4.15	7.58	7.11	3.73	-0.80
		Ni(II)	5.51	5.10	7.72	7.35	6.82	-0.90
		Cu(II)	5.03	6.63	8.16	7.50	7.63	-0.53
Dth	Trp	Co(II)	—	—	4.42	4.15	4.77	+0.85
		Ni(II)	—	—	5.51	5.10	5.91	+0.40
		Cu(II)	—	—	8.08	6.63	8.71	+0.68

\*Author for correspondence.

not essential to know the stability constants of these complexes while calculating the stability constants of their ternary complexes as it was observed in the case of 2,2'-bipyridyl complexes<sup>8</sup>.

The stability constants of MAL<sup>+</sup> type of complexes were calculated using the method of L'Heureux and Martell<sup>9</sup> assuming dth as a primary ligand and trp as a secondary ligand because the nature of titration curve indicated the formation of 1:1, M-dth complex at very low pH which did not hydrolyse even at higher pH ~7. Some representative titration curves showing the sequence of addition of ligands and hydrolytic phenomenon are shown in Fig. 1. In MAL type of complexes trp has been considered as a primary ligand




Fig. 1. Representative potentiometric titration curves.  
A: dth, B: 1:1; Cu(II)-dth, C: trp,  
D: 1:1; Cu(II)-trp, E: 1:1:1; Cu(II)-dth-trp.




Fig. 2. Representative potentiometric titration curves.  
A: HNO<sub>3</sub>, B: HNO<sub>3</sub> + trp,  
C: 1:1; Cu(II)-trp, D: 1:1:1; Cu(II)-trp-sal.

because 1:1 M-trp complex hydrolyses at higher pH value than 1:1 M-sal complex. Further, the

titration curve (Fig. 2) of 1:1:1 M-trp-sal runs slightly above the 1:1 M-trp curve, then superimposes and subsequently moves below it, thereby indicating the formation of 1:1:1 MAL complex after the complete formation of 1:1 M-trp complex. Hence,  $K_{\text{prim(trp)}}$   $K_{\text{sec(sal)}}$  is not an essential requirement in the formation of ternary complexes. Such observations have also been noticed by Gergely *et al*<sup>10</sup> on the ternary complexes of  $\alpha$ -amino acids. The stability constants of MAL complexes have been calculated using modified form of Irving-Rossotti method<sup>8</sup> as employed by other workers<sup>10</sup>. These values have been listed in Table 1.

## Results and Discussion

**Binary systems:** The protonation and the stability constant values are more sensitive to the dielectric constant of the medium than to ionic strength or temperature. In dioxane-water mixtures of low dielectric constant, these values were expected to be significantly higher than those for the aqueous medium. But in the present investigation these values are not according to known general trend. It is evident from Table 1 that in the case of M-trp complexes the stability constant data in dioxane-water mixture are lower than those in water. Such irregularities have also been reported in literature<sup>6,7</sup> on binary complexes of ligands containing N or N and O as donor atoms where the stability constants were generally found to be lower in solvents of low dielectric constants.

**Ternary systems:** All ternary systems revealed the formation of MAL<sup>+</sup> or MAL type of complexes only.  $\Delta \log K_M$  values (Table 1) are positive for MAL<sup>+</sup> but negative for MAL complexes. The positive values of  $\Delta \log K_M$  were found to be due to the discriminating properties of dth towards trp because in addition to N→M  $\sigma$ -bonding in dth complexes there also exist  $M_{(d)} \rightarrow N_{(p)}$   $\pi$ -bonding. This renders the charge and electronegativity of the metal ion in M-dth complexes the same as in  $[M(H_2O)_6]^{n+}$ . These effects are not pronounced in the ternary complexes of trp containing mixed donor sites (N and O). Hence, the values of  $\Delta \log K_M$  were found to be negative. Such results have also been observed by Sigel and Griesser<sup>14</sup>. The positive values of  $\Delta \log K_M$  may also be due to the absence of coulombic repulsion between two dissimilar ligand bound to the same metal ion and the negative values are due to smaller coulombic attraction of secondary ligand (sal).

It is evident from the above discussion that the ternary complexes are stabilized by several factors. Besides these factors, intramolecular aromatic ring stacking also plays an important role in increasing the stability constants of ternary complexes<sup>15</sup>. Dithionon is a rigid as well as a good  $\pi$ -acceptor molecule while the ring system of trp is attached to a flexible side chain. Both of these ligands, when coordinated to the same metal ion, produce intramolecular aromatic ring stacking between the



aromatic ring systems of the two ligands. It is possible because the ring system of trp may reach easily to the rigid aromatic ring system of dth to produce these interactions. Such effects are less remarkable in the ternary complexes of sal and trp, because the ring system of sal is not rigid and there remains a freely hanging phenyl ring having no functional group that might involve in bonding. A tentative structure of stacked ternary complex of MAL<sup>+</sup> has been shown in Fig. 3. These results find

#### Acknowledgement

The authors are thankful to the authorities of I. I. T., Kanpur for computer facilities and also to Professors P. R. Sing and P. C. Nigam (I. I. T./K) for some experimental facilities and encouragement.




Fig. 3. A tentative structure of stacked ternary MAL<sup>+</sup> complex.

further support from the work of Sigel *et al.*<sup>14,16</sup> on the intramolecular hydrophobic interactions in ternary complexes of some aliphatic amino acids and ring stacking in ternary complexes of some aromatic amino acids. Similar results were also observed in our previous investigation on the stacked ternary complexes of some plant auxins involving 2,2'-bipyridyl and 1,10-phenanthroline as primary ligands<sup>17</sup>.

On the basis of considerably high stability constants of binary and ternary metal complexes reported here, the metal ions which are vital constituent of various enzymes may interact with fungicides forming binary complexes which are further converted into ternary complexes involving tryptophan. Thus, all the enzymatic equilibria are disturbed and the conversion of tryptophan into various products is inhibited causing growth regulation.

#### References

1. R. SAHAI, S. AGRAWAL and S. S. KUSHWAHA, *J. Indian Chem. Soc.*, in press.
2. H. SIGEL, (Ed.), "Metal Ions in Biological Systems", Marcel Dekker, N. Y., 1973.
3. C. H. FAWCETT, H. F. TAYLOR, R. L. WAIN and F. WIGHTMAN "Chemistry and Mode of Action of Plant Growth Substances", Academic Press and Butterworth, N. Y. and London, 1966, p. 187.
4. L. G. VAN UITER and C. G. HAAS, *J. Amer. Chem. Soc.*, 1958, 75, 451.
5. F. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1953, 3897, 1954, 2904.
6. L. G. SILLEN and A. E. MARTELL, "Stability Constants of Metal Ion Complexes", Special Publication No. 17, The Chemical Society, London, 1964.
7. D. R. WILLIAMS, *J. Chem. Soc. (A)*, 1970, 1650.
8. G. A. L'HUEREUX and A. E. MARTELL, *J. Inorg. Nuclear Chem.*, 1966, 28, 481.
9. A. GERGELY, I. SOVAGO, I. NAGYPAL and B. KIRALY, *Inorg. Chim. Acta*, 1972, 6, 435.
10. B. K. AGRAWALA, M. CHANDRA, R. V. AGRAWALA and A. K. DEY, *Indian J. Chem.*, 1977, 15A, 633.
11. B. R. JAMES and B. J. P. WILLIAMS, *J. Chem. Soc.*, 1961, 2007.
12. G. J. HOWKINS, H. DUNWELL and W. K. PICKERING, *Analyt. Chem. Acta*, 1961, 25, 267.
13. H. SIGEL, *Chimia*, 1967, 21, 489.
14. R. GRIESNER and H. SIGEL, *Inorg. Chem.*, 1970, 9, 1988.
15. R. F. FISCHER and H. SIGEL, *J. Amer. Chem. Soc.*, 1980, 102, 2999.
16. H. SIGEL, R. F. FISCHER and B. PRIJS, *J. Amer. Chem. Soc.*, 1977, 99, 4489.
17. R. SAHAI and S. S. KUSHWAHA, *Indian J. Chem.*, 1981, 20A, 817.

# Stabilisation of Molybdenyl Cations with 4,4'-Dimethyl 2,2-Bipyridyl in Different Salt and Non-electrolytic Complexes

H. K. SAHA, S. S. MANDAL and P. C. GHORAI


Pure Chemistry Department, University College of Science, Calcutta-700 009

Manuscript received 16 October 1981, revised 14 April 1982, accepted 21 July 1982

The aqueous chemistry of molybdenyl cation  $\text{MoO}^{2+}$  has been studied. The heterocyclic base 4,4'-dimethyl 2,2'-bipyridyl has been shown to function as diacidic base in strong hydrochloric acid medium to yield the salt  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$ . The non-electrolytic complexes  $[\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2]$  and  $[\text{MoOCl}_3\cdot\text{Me}_2\text{bipy}]$  have been isolated from the parent salt by hydrolytic and dehydrohalogenation reaction in solution and in solid state.

THE effect of substitution in 1,10-phenanthroline and 2,2'-bipyridyl on the complexation of metal ions has been studied only in some isolated cases. It is known that 1,10-phenanthroline gives stable complex with iron, but, 2,9-dimethyl 1,10-phenanthroline fails to do this due to steric factor. Identical observations have been reported by the present author in the case of molybdenyl cation also. The similarity of  $\text{MoO}^{2+}$  with  $\text{Fe}^{2+}$  ion in high spin state has also been established<sup>1</sup>.

In the present investigation the role of 4,4'-dimethyl 2,2'-bipyridyl in the aqueous chemistry of molybdenyl cation has been fully investigated. The salt  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$  and the non-electrolytic complexes  $[\text{MoOCl}_3\cdot\text{Me}_2\text{bipy}]$  (in two forms, reddish pink and green varieties) and  $[\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2]$ , isolated in pure state by the present authors, have been thoroughly studied by analytical and different physico-chemical methods. The interconversion of the products and reactants is shown below which establishes the stability of the "oxometal" entity  $\text{MoO}^{2+}$  in different chemical reactions.



## Experimental

All reagents used were of A. R. grade. Molybdenum was estimated gravimetrically as molybdenum trioxide and chlorine was estimated as silver chloride<sup>2</sup>. Nitrogen was estimated by Duma's method. The oxidation state of the metal was determined by ceric sulphate method.

**4,4'-Dimethyl 2,2'-bipyridinium oxopentachloro molybdate(V),  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$ :** This anhydrous salt was prepared by reducing  $\text{MoO}_3$  (2 g) with HI (2 ml) in hydrochloric acid (12 N) medium and the green crystalline salt was obtained by adding 2 g of the base, yield 5.3 g. (Found: Mo, 20.18; Cl, 37.68; N, 5.89. Calcd. for  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$ ; Mo, 20.20; Cl, 37.20; N, 5.88%). Oxidation state of the metal was found to be 4.99.

**Oxotrichloro(4,4'-dimethyl 2,2'-bipyridyl)molybdenum(V),  $\text{MoOCl}_3\cdot\text{Me}_2\text{bipy}$  (reddish pink):** Dehydrohalogenation was effected by refluxing 1 g of 4,4'-dimethyl 2,2'-bipyridinium oxopentachloro molybdate(V) with 20 ml of dehydrated ethanol for about 1 hr under positive pressure of the solvent. The pink product was filtered, washed and dried in a vacuum desiccator, yield about 0.7 g. (Found: Mo, 23.49; Cl, 26.93; N, 7.47. Calcd. for  $\text{MoOCl}_3\cdot\text{Me}_2\text{bipy}$ ; Mo, 23.85; Cl, 26.45; N, 6.95%). The oxidation state of the metal was found to be 5.0.

**Oxotrichloro(4,4'-dimethyl 2,2'-bipyridyl)molybdenum(V),  $\text{MoOCl}_3\cdot\text{Me}_2\text{bipy}$  (green):** A sample of about 1 g of the parent salt  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$  was refluxed with 15 ml acetonitrile for 3-4 hr. The evolved gas contained hydrogen chloride. The bright green crystalline solid so formed was filtered and dried in a vacuum desiccator, yield about 0.65 g. (Found: Mo, 23.69; Cl, 27.14; N, 7.12. Calcd. for  $\text{MoOCl}_3\cdot\text{Me}_2\text{bipy}$ ; Mo, 23.85; Cl, 26.45; N, 6.95%). The oxidation state of the metal was found to be 5.09.

Alternatively, the green compound can also be prepared by refluxing the parent salt with acetylacetone or heating the parent salt in solid state at 250° for 2 hr in  $\text{CO}_2$  atmosphere.

**Oxo-μ-dioxochloro(4,4'-dimethyl 2,2'-bipyridyl)molybdenum(V),  $[\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2]$ :** Hydrolysis of the parent salt (1 g) was effected by boiling with distilled water when the orange red solid separated. It was cooled, filtered in a sintered gooch crucible, washed with cold water and dried

in vacuum desiccator, yield 0.75 g. [Found : Mo, 27.44 ; Cl, 10.02 ; N, 8.04. Calcd. for  $\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2$  ; Mo, 27.62 ; Cl, 10.21 ; N, 8.05%]. The oxidation state of the metal was found to be 5.04.


This compound is insoluble in water and common organic solvents. Boiling it with 6*N* hydrochloric acid produces the reddish pink  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$ .

**Conductivity measurements :** The extensive hydrolysis and ionisation of the oxopentahalomolybdate(V) ion was confirmed by conductance measurement of the salts in aqueous medium. The non-electrolytic nature of  $\text{MoOX}_3 \cdot \text{L}$  type of compounds was established by conductance measurements in acetonitrile. The conductance values in  $10^{-3}$  *M* solution, of the reddish pink and the green forms of  $[\text{MoOX}_3 \cdot \text{Me}_2\text{bipy}]$  are 5.02 and 5.26  $\text{ohm}^{-1}\text{cm}^2 \text{mole}^{-1}$ , respectively which are much less than those for binary electrolytes<sup>8</sup> (the conductivity of a 1 : 1 electrolyte in  $10^{-3}$  *M* solution ranges from 120-160  $\text{ohm}^{-1}\text{cm}^2 \text{mole}^{-1}$ ). Since the hydrolytic product  $\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2$  is practically insoluble in almost all solvents, conductance measurement was not possible.

**Measurement of magnetic susceptibility :** Magnetic susceptibility measurements of the compounds were carried out at room temperature using Gouy balance having a field strength of 8500 gauss and the values of effective moments were found using the formula  $\mu_{\text{eff}} = 2.839 (\chi'_M \cdot T)^{\frac{1}{2}}$  where  $\chi'_M$  is the molar susceptibility after diamagnetic correction. The  $\mu_{\text{eff}}$  values of the compounds  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$ ,  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$  (reddish pink),  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$  (green) and  $\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2$  are 1.81, 1.81, 1.88 and 0.52 B.M., respectively.

It appears from the results of magnetic susceptibility measurements that the salt  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$  and both varieties of the mononuclear complex  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$  contain quinquivalent molybdenum having  $d^1$  configuration. The hydrolytic product  $\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2$  has a small magnetic moment due to oxobridges with a possible Mo-Mo interaction.

**Thermogravimetry** Thermogravimetric investigations were made in a T. G. Analyser of Cicco Pvt. Co. The results are plotted in Fig. 1. It appears that at 250° the stable state corresponds to the weight loss of 15.11%, whereas the theoretical weight loss according to the following thermal dehydrohalogenation is 15.35%. Therefore, the non-electrolytic paramagnetic derivative  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$  can be prepared at this temperature.



At 570°, the total weight loss is 70.36% which is in excellent agreement with the formation of  $\text{MoO}_3$ , which requires a theoretical weight loss of 69.69%. The synthesis of  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$  by thermal




Fig. 1. TGA Diagram of  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$

dehydrohalogenation of the salt  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$  has been mentioned which also confirms the thermogravimetric analysis of the compound.

**IR spectra :** Infrared spectra were recorded in Perkin-Elmer IR spectrophotometer using KBr pellet. The IR spectrum of the salt  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$  shows a strong absorption band at 980  $\text{cm}^{-1}$  while for the two isomers it appears at 960  $\text{cm}^{-1}$  (*cis*) and 965  $\text{cm}^{-1}$  (*trans*), respectively. The hydrolysed product  $\text{Mo}_2\text{O}_4\text{Cl}_2(\text{Me}_2\text{bipy})_2$  shows strong absorption at 945  $\text{cm}^{-1}$ . These bands can be assigned to the molybdenum oxygen stretching frequency, indicating the presence of  $\text{Mo(V)}=\text{O}$  species in all the compounds.

Examination of the stretching frequencies indicates that there is a gradual decrease in metal-oxygen bond strength from  $\text{Me}_2\text{bipyH}_2[\text{MoOCl}_4]$  to hydrolysed product, as the chlorine atom is replaced by a nitrogen atom (from 4,4'-dimethyl 2,2'-bipyridyl) and an oxygen atom (forming an oxobridge) causing a reduction in the value of the stretching frequency. This is probably due to the strong donating capabilities of the nitrogen atoms of  $\text{Me}_2\text{bipy}$  and oxygen of oxobridge, causing increased electron density around the central metal atom and thereby reducing its  $\pi$ -acceptance capacity and ultimately the metal-oxygen bond strength. The broader bands in the region 700-800  $\text{cm}^{-1}$  in the case of hydrolytic product may be assigned to metal oxygen chain ( $-\text{Mo}-\text{O}-\text{Mo}-\text{O}$ ) vibrations.

**UV and visible spectra :** UV and visible spectra were recorded on a Hilger Uvispek spectrophotometer. The solvent used in the case of the salt was 10 *M* hydrochloric acid and in the case of both the isomeric varieties of  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$ , it was acetonitrile (A.R.). As the hydrolytic product is insoluble in common organic solvents, its reflectance spectrum was taken in the solid state using spectrochemically pure liquid paraffin. Reflectance spectra were also taken for the two isomers of  $\text{MoOCl}_2 \cdot \text{Me}_2\text{bipy}$ . The absorption bands together

TABLE 1—ELECTRONIC SPECTRA OF THE SALT AND NON-ELECTROLYTIC ISOMERS

Compound	$\lambda_{\max}$ m $\mu$	$\nu$ (cm $^{-1}$ $\times 10^{-3}$ )	Molar extinction coefficient $\epsilon$	Assignment
Me <sub>2</sub> bipyH <sub>2</sub> [MoOCl <sub>4</sub> ] in 10 M HCl	700	14.39	19.50	$^2B_1 \rightarrow ^2E$ (I)
	440	22.72	15.04	$^2B_1 \rightarrow ^2B_1$
	370	27.08	207.00	$^2B_1 \rightarrow ^2E$ (II)
	295	33.90	15,450	$^2B_1 \rightarrow ^2B_1$ (I)
	232	43.10	12,000	$^2B_1 \rightarrow ^2E$ (III)
[MoOCl <sub>4</sub> .Me <sub>2</sub> bipy] (reddish pink) in acetonitrile	740	18.51	90.00	$^2B_1 \rightarrow ^2E$ (I)
	520	19.28	708.00	L $\rightarrow$ Mo
	490	23.25	504.00	Charge transfer
[MoOCl <sub>4</sub> .Me <sub>2</sub> bipy] (green)	370	27.03	900.00	$^2B_1 \rightarrow ^2B_1$ (I)
	750	18.38	65.00	$^2B_1 \rightarrow ^2E$ (I)
	530	19.28	125.00	L $\rightarrow$ Mo
				Charge transfer
	375	26.67	660.00	$^2B_1 \rightarrow ^2B_1$
	305	32.78	10,900	$^2B_1 \rightarrow ^2B_1$ (I)
	240	41.67	15,800	$^2B_1 \rightarrow ^2E$ (III)

with molar extinction coefficient and the corresponding intensities in the case of reflectance spectra and their tentative assignments are given in Tables 1 and 2. The results clearly agree with previous observations<sup>4,5</sup>.

TABLE 2—REFLECTANCE SPECTRA IN SOLID STATE

Compound	$\nu$ (cm $^{-1}$ $\times 10^{-3}$ )	Intensity	Assignment
MoOCl <sub>4</sub> .Me <sub>2</sub> bipy (reddish pink)	18.50	s	$^2B_1 \rightarrow ^2E$ (I)
	19.60	sh	L $\rightarrow$ Mo
	22.90	m	Charge transfer
	25.80	sh	$^2B_1 \rightarrow ^2B_1$ (I)
MoOCl <sub>4</sub> .Me <sub>2</sub> bipy (green)	14.00	m	$^2B_1 \rightarrow ^2E$ (I)
	18.90	w	L $\rightarrow$ Mo
	22.40	sh	Charge transfer
	26.00	m	$^2B_1 \rightarrow ^2B_1$ (I)
Mo <sub>2</sub> O <sub>7</sub> Cl <sub>2</sub> .(Me <sub>2</sub> bipy) <sub>2</sub>	11.50	m	$^2B_1 \rightarrow ^2E$ (I)
	17.00	sh	L $\rightarrow$ Mo
	22.90	sh	Charge transfer
	26.20	m	$^2B_1 \rightarrow ^2B_1$ (I)

s=strong; m=medium; sh=shoulder;  
sb=strong broad.

## Results and Discussion

The MoOCl<sub>4</sub><sup>2-</sup> ion is visualised as a tetragonal structure with a short Mo—O bond having C<sub>4v</sub> symmetry<sup>6</sup>. The expected transitions with identical scheme agree very closely with the experimental results. The salt 4,4'-dimethyl 2,2'-bipyridinium oxopentachloromolybdate(V) in 10 M HCl shows two crystal field transitions  $^2B_1 \rightarrow ^2E$  (I) and  $^2B_1 \rightarrow ^2B_1$  at 14,290 and 22,720 cm $^{-1}$  and three charge transfer transitions  $^2B_1 \rightarrow ^2E$  (II),  $^2B_1 \rightarrow ^2B_1$  (I) and  $^2B_1 \rightarrow ^2E$  (III) at 27,030, 33,900 and 43,100 cm $^{-1}$ , respectively. About the monomeric complex [MoOCl<sub>4</sub>.Me<sub>2</sub>bipy], the molecular orbital picture

is expected to be different. In this case the number of symmetry elements is expected to be less than that in the case of MoOCl<sub>4</sub><sup>2-</sup> ion which belongs to C<sub>4v</sub> point group. But the other distortions from octahedral structure compared to the distortion caused by Mo—O interaction are expected to be moderate. There may be considerable  $\pi$ -interaction with the filled  $\pi$ -orbitals of the ligand and metal d-orbitals. Therefore, a red shift is logical consequence of this effect and this has actually happened in this case as the following  $\nu$ -values of the first crystals field transition reveal.

Compound	$\nu$ in cm $^{-1}$ $\times 10^{-3}$
(a) Me <sub>2</sub> bipyH <sub>2</sub> [MoOCl <sub>4</sub> ]	14.29
(b) [MoOCl <sub>4</sub> .Me <sub>2</sub> bipy] (reddish pink)	13.51
(c) [MoOCl <sub>4</sub> .Me <sub>2</sub> bipy] (green)	13.33

The solution and reflectance spectrum of the two isomeric forms of [MoOCl<sub>4</sub>.Me<sub>2</sub>bipy] are similar. A new band appears in the region 19,000 cm $^{-1}$  which may be due to a Me<sub>2</sub>bipy  $\rightarrow$  Mo charge transfer transition. In the case of Mo<sub>2</sub>O<sub>7</sub>Cl<sub>2</sub>-(Me<sub>2</sub>bipy)<sub>2</sub>, the L  $\rightarrow$  Mo charge transfer band has undergone a red shift compared to the mononuclear complex [MoOCl<sub>4</sub>.Me<sub>2</sub>bipy], as the chlorine atom has been replaced by oxygen (forming bridge) which is expected to reduced the Mo-ligand bond strength.

## References

1. H. K. SAHA, S. S. MANDAL and T. K. RAY CHOUHDURY, *J. Inorg. Nuclear Chem.*, 1976, 37, 840.
2. H. K. SAHA, (Miss) S. CHAKRABORTY and (Miss) M. BAGCHI, *J. Inorg. Nuclear Chem.*, 1976, 36, 455.
3. W. J. GEARY, *Coord. Chem. Rev.*, 1971, 7, 110.
4. C. J. BALCHAUSEN and H. B. GRAY, *Inorg. Chem.*, 1962, 1, 111.
5. H. K. SAHA and A. K. BANERJEE, *J. Inorg. Nuclear Chem.*, 1972, 34, 1861.
6. H. B. GRAY and C. R. HARR, *Inorg. Chem.*, 1962, 1, 868.

# Synthesis and Structural Studies of the Complexes of Zn(II), Ni(II), Cu(II) and Co(II) with 3-Aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazoles

S. C. BAHTEL, B. L. DUBSH, N. NATH, A. TRIPATHI and J. K. SRIVASTAVA

Department of Chemistry, Gorakhpur University, Gorakhpur-273 001

Manuscript received 7 January 1982, accepted 21 July 1982

Complexes of Zn(II), Cu(II), Ni(II) and Co(II) with 3-aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazoles have been prepared. They have been characterised on the basis of elemental analyses, infrared spectra, thermogravimetry, magnetic susceptibility and powder X-ray diffraction patterns. Fungitoxicity of the complexes and free ligands has been evaluated against *H. oryzae*. X-ray studies reveal that the complexes possess cubic structure.

COMPOUNDS containing triazole ring have been reported to have bactericidal<sup>1,2</sup>, fungicidal<sup>3,4</sup>, insecticidal<sup>5,6</sup> and pesticidal<sup>7,8</sup> properties. 3-Amino-1,2,4-triazole (Amizole) is a commercial herbicide. Importance of metal complexes has also been established and some of them are found to possess biological activity. Some drugs have increased activity when administered as metal complexes<sup>9</sup> and a number of metal chelates inhibit tumour growth. The complexes of Co(II) and Cu(II) with 3-methyl-4-(2-pyridyl)-1,2,4-triazole-5-thiol have been reported<sup>10</sup>. The present communication reports the synthesis and characterisation of Zn(II), Co(II), Cu(II) and Ni(II) complexes with 3-aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazoles.

## Experimental

All chemicals used were of B. D. H. grade or of equivalent quality.

**Preparation of 3-aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazole:** A mixture of an aryloxyacetylhydrazine (0.01 M) and arylisothiocyanate (0.012 M) was refluxed in NaOH solution (20 ml; 8%) for 5 to 6 hr when a clear solution resulted. It was cooled, poured into water and filtered. The filtrate on acidification gave a precipitate which was filtered, washed and recrystallised. The compounds, thus prepared, were characterised by elemental analysis and ir spectra (Table 1).

**Preparation of metal complexes:** The complexes were precipitated by refluxing a methanolic solution of 3-aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazole (0.01 M) with aqueous solution of a metal salt (0.03 M) for 4 to 6 hr. The precipitate was filtered, washed successively with large excess of water, hot methanol, ether and dried *in vacuo*.

**Analyses of the metal complexes:** Metal ions in the complexes were estimated by the methods in literature<sup>11</sup>. The metal complexes were also analysed for their metal contents as their oxides.

For this purpose, weighed samples in silica crucible were first gently heated on a naked flame for 1 hr and then in an electric furnace at  $800 \pm 10^\circ$  to a constant weight. These were cooled and weighed. Sulphur and nitrogen were estimated by the usual methods (Table 1).

TABLE 1—3-ARYLOXYMETHYL-4-ARYL-5-MERCAPTO-1,2,4-TRIAZOLES

Sl No	R	m.p. °C	N% Found (Calcd.)	S% Found (Calcd.)
1	2-OH-C <sub>6</sub> H <sub>4</sub> -OOCH <sub>3</sub> -	178	18.92 (18.92) (14.14)	10.92 (10.77)
2	2-Cl-C <sub>6</sub> H <sub>4</sub> -OOCH <sub>3</sub> -	189	19.82 (19.80)	10.74 (10.06)
3	4-Cl-C <sub>6</sub> H <sub>4</sub> -OOCH <sub>3</sub> -	180	19.94 (19.90)	10.88 (10.06)

IR Spectral Data $\nu_{\max}$ in cm <sup>-1</sup>				
Conjugated >C=N	p-disubstituted benzene	monosubstituted benzene	C=S	C-O-C
1740	890	770	1175	1260

**Physical measurements:** The magnetic susceptibilities of the complexes were determined by Faraday method using ferrous ammonium sulphate as calibrant. Experimental magnetic susceptibilities were corrected for diamagnetism<sup>12</sup>. The magnetic moments of the complexes at room temperature are given in Table 2.

The ir spectra of the complexes and the ligand were recorded on a Perkin-Elmer spectrophotometer, Model 621, in KBr phase in 4000-200 cm<sup>-1</sup> range.

TABLE 2—ANALYTICAL DATA AND MAGNETIC MOMENTS OF THE COMPLEXES

Complex composition	Metal % Found (Calcd.)	N% Found (Calcd.)	$\mu_{\text{eff}}$ B.M. Found (Calcd.)
$[\text{ZnL}_2(\text{Ac})_2]$	8.80 (8.96)	10.21 (10.81)	Diamagnetic
$[\text{ZnL}_2\text{Cl}_2]$	4.8 (4.90)	13.3 (12.68)	Diamagnetic
$[\text{CuL}_2(\text{Ac})_2] \cdot \text{H}_2\text{O}$	7.3 (7.60)	10.8 (10.45)	1.18 (1.78)
$[\text{Ni}(\text{NO}_3)_2 \cdot \text{L}_2 \cdot 2\text{H}_2\text{O}]$	6.9 (6.86)	12.9 (12.10)	2.97 (2.85)
$[\text{Co}(\text{NO}_3)_2 \cdot \text{L}_2]$	4.2 (4.05)	10.2 (10.84)	3.94 (3.87)

TABLE 3—CRYSTAL DATA FOR THE COMPLEXES

Complex	Lattice parameter and lattice type
$[\text{ZnL}_2(\text{Ac})_2]$	$a = 20.6 \text{ \AA}$ Cubic
$[\text{CuL}_2(\text{Ac})_2] \cdot \text{H}_2\text{O}$	$a = 17.70 \text{ \AA}$ Cubic
$[\text{Ni}(\text{NO}_3)_2 \cdot \text{L}_2 \cdot 2\text{H}_2\text{O}]$	$a = 18.89 \text{ \AA}$ Cubic
$[\text{Co}(\text{NO}_3)_2 \cdot \text{L}_2]$	$a = 21.38 \text{ \AA}$ Cubic

The thermogravimetry of the complexes were carried out with the help of a manual thermogravimetric analyser (supplied by P & D Division, FCI Ltd., Sindri) at a heating rate of  $4^\circ \text{ min}^{-1}$  in air. Results are recorded in Table 4.

TABLE 4—TG DATA FOR METAL COMPLEXES

Stable phase or thermal decomposition	Temp. range ( $^\circ\text{C}$ )	%wt loss Found (Calcd.)
$\text{ZnL}_2(\text{Ac})_2$	60-300	8.53 (7.59)
$\downarrow$		
$\text{ZnL}_2(\text{Ac})_2$	300-540	46.85 (46.20)
$\downarrow$		
$\text{ZnL}(\text{Ac})$	540-700	88.89 (89.57)
$\downarrow$		
$\text{ZnO}$		
$\text{ZnL}_2\text{Cl}_2$	140-340	43.29 (44.80)
$\downarrow$		
$\text{ZnL}_2\text{Cl}_2$	310-700	90.90 (89.72)
$\downarrow$		
$\text{ZnCl}_2$		
$\text{CuL}_2(\text{Ac})_2 \cdot \text{H}_2\text{O}$	80-160	1.90 (2.15)
$\downarrow$		
$\text{CuL}_2(\text{Ac})_2$	160-460	47.908 (47.27)
$\downarrow$		
$\text{CuL}(\text{Ac})$	460-700	87.95 (90.48)
$\downarrow$		
$\text{CuO}$		
$\text{Ni}(\text{NO}_3)_2 \cdot \text{L}_2 \cdot 2\text{H}_2\text{O}$	80-130	4.76 (4.21)
$\downarrow$		
$\text{Ni}(\text{NO}_3)_2 \cdot \text{L}_2$	120-360	42.77 (41.41)
$\downarrow$		
$\text{Ni}(\text{NO}_3)_2 \cdot \text{L}$	360-660	93.55 (91.26)
$\downarrow$		
$\text{NiO}$		
$\text{Co}(\text{NO}_3)_2 \cdot \text{L}_2$	80-320	42.0 (43.71)
$\downarrow$		
$\text{Co}(\text{NO}_3)_2 \cdot \text{L}_2$	320-460	66.6 (65.56)
$\downarrow$		
$\text{Co}(\text{NO}_3)_2 \cdot \text{L}$	460-700	95.0 (94.84)
$\downarrow$		
$\text{CoO}$		

Powder X-ray diffraction patterns of the complexes were taken, using CuK radiation, employing a Guinier camera of 11.46 cm diam and X-ray unit of PW 1011 Philips, Holland. The diffraction patterns were indexed by Hess-Lipson method. The agreement between the observed and calculated values of  $\sin^2 \theta_{\text{hkl}}$  was satisfactory which indicated that the indexing was correct.

Fungitoxicity of the complexes and the ligands were also evaluated against *H. oryzae* by agar-plate method<sup>18</sup> at three different concentrations. The average per cent inhibition (Table 5) by various complexes were calculated by the expression:

$$\text{Per cent inhibition} = \frac{(C - T) \times 100}{C}$$

where C = diameter of the fungus colony in the control plate after 96 hr and T = diameter of the fungus colony in treated plates after 96 hr.

TABLE 5—FUNGICIDAL SCREENING  
(Organism—*H. oryzae*)


	Average Percent Inhibition after 96 hr Concentration		
	1 : 1,000	1 : 10,000	1 : 100,000
Zinc acetate complex	56.2	30.25	10.09
Zinc chloride complex	55.4	27.28	9.98
Ligand for the above complexes	44.9	21.30	11.05
Cobalt nitrate complex	45.2	22.75	12.54
Nickel nitrate complex	43.2	20.24	12.00
Ligand for the above complexes	38.9	19.25	9.25
Copper acetate complex	57.3	28.85	11.55
Ligand for the above complex	45.8	20.00	10.50

## Results and Discussion

The zinc complexes are found diamagnetic as expected. The structure proposed for the complexes is also in accordance with the diamagnetic behaviour. The magnetic moment value of Cu(II) acetate complex is found to be 1.18 B.M. This low value of magnetic moment could be explained by spin-spin interaction between two cupric ions, which is usually observed in other Cu(II) acetate complexes<sup>14</sup>. The magnetic moment value (2.97 B.M.) for Ni(II) complex lies well within the range accepted for the octahedral complexes of this metal ion<sup>15</sup>. The value of magnetic moment (3.94 B.M.) for Co(II) complexes is well within the range accepted for Co(II) complexes having three unpaired electrons.

The infrared spectra of ligands 3-tolyloxy-methyl-4-aryl-5-mercapto-1,2,4-triazole, 3-(*p*-chlorophenoxy)methyl-4-aryl-5-mercapto-1,2,4-triazole and 3-(*o*-chlorophenoxy)methyl-4-aryl-5-mercapto-1,2,4-triazole show bands at 3500, 3040  $\text{cm}^{-1}$ ; 3420, 3050  $\text{cm}^{-1}$  and 3412, 3025  $\text{cm}^{-1}$ , respectively which may be assigned to  $\nu_{\text{asym}} \text{N-H}$  and  $\nu_{\text{sym}} \text{N-H}$  vibrations, respectively. A weak band in the region 2550-2600  $\text{cm}^{-1}$  in the spectra of these ligands may be assigned as  $\nu_{\text{S-H}}$  stretching vibration. The bands observed at 1120, 1175 and 1060  $\text{cm}^{-1}$  in the spectra of the respective ligands are

due to  $\text{>C=S}$  stretch. The ligand spectra show bands due to conjugated  $\text{>C=N}$ , *o*- and *p*-disubstituted benzene rings at 1735-1740, 960-1040 and 800-855  $\text{cm}^{-1}$ , respectively. It may be concluded from these that the ligand exists in the following tautomeric form :



An analysis of the spectra of the complexes and their respective ligands shows that  $\nu_{\text{S-H}}$  band in the region 2550-2600  $\text{cm}^{-1}$  is absent in the spectra of the complexes whereas the  $\nu_{\text{N-H}}$  band is present. Further, there is a strong negative shift in  $\nu_{\text{C-S}}$  band in 1050-1200  $\text{cm}^{-1}$  region. These clearly indicate that the thione form is favoured for complexation, coordination takes place through S atom of the thione and the ligands act as monodentate.

The asymmetric and symmetric  $\text{>C=O}$  stretching frequencies of free acetate ion observed at 1578 and 1425  $\text{cm}^{-1}$ , respectively are observed at 1595 and 1430  $\text{cm}^{-1}$ , respectively in Zn(II) acetate complex and at 1610 and 1440  $\text{cm}^{-1}$  in Cu(II) acetate complex. A separation of about 165 and 160  $\text{cm}^{-1}$  in the above modes in Zn(II) and Cu(II) acetate complexes suggests that the acetate group behaves as monodentate ligand in these complexes<sup>16</sup>. In Cu(II) acetate complex there is a band at 3560  $\text{cm}^{-1}$  which is due to the presence of lattice water.

In case of Ni(II) and Co(II) nitrate complexes the presence of two bands at 1500, 1270  $\text{cm}^{-1}$  and 1495, 1275  $\text{cm}^{-1}$ , respectively due to  $\nu_2$  of nitrate group, indicates that the nitrate ion behaves as a monodentate ligand<sup>17</sup>.

Crystal data reported in Table 3 indicate that the crystal lattice of all the complexes belongs to cubic system. The lattice parameter of the complexes are also shown.

On the basis of thermoanalytical data, the mechanism of decomposition of complexes has been proposed and is shown in Table 4. The

decomposition products of all the complexes were analysed and the end products were found to be respective metal oxides except for zinc chloride complex. From the TG data it is clear that the mass loss starts at about 80°. The mass loss at a low rate right from the start may be due to desorption of adsorbed gases or moisture.

Fungicidal screening data (Table 5) indicate that the complexes are more fungitoxic than free ligand.

#### Acknowledgement

The authors are thankful to Prof. R. P. Rastogi, Head, Department of Chemistry, Gorakhpur University, for facilities, the P & D Division, F. C. I, Sindri for the powder diffraction patterns and Chemistry Department, B. H. U., Varanasi for IR spectra.

#### References

1. S. C. BENNUR, V. B. JIGAJINNI and V. V. BADIGER, *Rev. Roum. Chim.*, 1976, 21, 757, *Chem. Abs.*, 1976, 84, 9490j.
2. I. OHYOMARA, E. YOSHINAGA and G. DOTAKE, *Jap. Pat.*, 1978, 460, 7839, *Chem. Abs.*, 1974, 81, 78392m.
3. S. A. GREENFIELD, C. S. MICHAEL and W. C. VON MEYER, *Ger. Offen.*, 1974, 1, 806, 966, *Chem. Abs.*, 82, 160485.
4. W. KRAMER, K. H. BURCHIEL, W. BRANDES and P. E. PROBERGER, *Ger. Offen.*, 1975, 852, 2,384, *Chem. Abs.*, 1976, 82, 170967i.
5. G. TANAKA, *Japan Kokai*, 1974, 973, 7,495, *Chem. Abs.*, 1975, 82, 166390h.
6. T. I. WAKINS and D. M. WRIGHTON, *Ger. Offen.*, 1976, 287, 2,530,287, *Chem. Abs.*, 1976, 84, 136677i.
7. B. BOEHNER, W. MEYER and D. DOWNS, *Swiss*, 1976, 206, 573, *Chem. Abs.*, 1976, 84, 106677i.
8. L. GSELL and W. MEYER, *Ger. Offen.*, 1978, 084, 2,739, *Chem. Abs.*, 1978, 88, 190844z.
9. D. R. WILLIAMS, *Chem. Rev.*, 1972, 203, 72.
10. *Acta Pol. Pharm.*, 1976, 33, 336.
11. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", ELBS, 1973.
12. B. N. FICGIS and J. LEWIS, "Modern Coordination Chemistry", (Eds) J. LEWIS and R. G. WILLKINS, Interscience Publishers, Inc., N. Y., 1960, p. 400.
13. J. G. HORVATH, *Bot. Rev.*, 1954, 11, 357.
14. D. STAYA NARAYAN and B. K. MAHAPATRA, *Indian J. Chem.*, 1975, 13, 186.
15. F. A. COTTON and G. WILLKINSON, 2nd Edn., Interscience Publishers, Inc., New York, 1972.
16. K. NAKAMOTO, J. FUJITA and S. TANAKA, *J. Amer. Chem. Soc.*, 1957, 79, 4904.
17. B. M. GATHOUSE, S. E. LIVINGSTON and R. S. NYHOLM, *J. Chem. Soc.*, 1957, 4222, *J. Inorg. Nuclear Chem.*, 1958, 8, 75.

# Coordination Polymers of Terephthalaldehyde bis-(semicarbazone) with Some Bipositive Cations

BHAGWAT SINGH, P. L. MAURYA, B. V. AGARWALA and ARUN K. DEY\*

Chemical Laboratories, University of Allahabad, Allahabad-211 002

Manuscript received 9 December 1980, accepted 21 July 1982

Terephthalaldehyde bis-(semicarbazone) forms polymeric metal complexes,  $(-ML_2H_2O)_n$  (where  $M = Mn(II)$ ,  $Co(II)$ ,  $Ni(II)$ ,  $Cu(II)$  or  $Zn(II)$ , and  $L = C_{10}H_{10}N_4O_4$ ), which are coloured, powdery, air stable and insoluble in water and common organic solvents. The composition, structure and thermal stability of the complexes have been discussed on the basis of the results of analytical, magnetic, spectral (ir and drs) and thermogravimetric studies.

Terephthalaldehyde bis-(semicarbazone) acts as a tetradentate chelating agent, coordinating in enolic form. The coordination takes place through the enolic oxygens and azomethine nitrogens, and polymeric complexes are formed as the steric factors prevent the coordination of all the donors to the same metal ion. The complexes have octahedral geometry, and the order of thermal stability is  $Zn > Ni > Co > Mn > Cu$ .

In continuation of our earlier work<sup>1-4</sup> on coordination polymers of terephthalaldehyde derivatives, the present investigation was undertaken to isolate polymeric metal complexes of terephthalaldehyde bis-(semicarbazone) (TBSC) with  $Mn(II)$ ,  $Co(II)$ ,  $Ni(II)$ ,  $Cu(II)$  and  $Zn(II)$ . The analytical, magnetic, spectral (ir and drs) and thermogravimetric studies of the complexes are being described.

## Experimental

**Materials:** Terephthalaldehyde bis-(semicarbazone) was prepared by the reported method<sup>5</sup>. The solvents and metal salts used were as described earlier<sup>4</sup>.

**Preparation of the complexes:** 2.48 g (0.01 M) TBSC dissolved in DMSO was added to a metal salt solution (0.01 M) [containing 1.98 g of  $MnCl_2 \cdot 4H_2O$ , 2.49 g of  $Co(CH_3COO)_2 \cdot 4H_2O$ , 2.49 g of  $Ni(CH_3COO)_2 \cdot 4H_2O$ , 2.00 g of  $Cu(CH_3COO)_2 \cdot H_2O$  or 2.20 g of  $Zn(CH_3COO)_2 \cdot 2H_2O$ ] in DMSO. The mixture was stirred and refluxed on a sand bath for ca 2 hr and left overnight. The resulting solid was filtered, washed successively with DMSO, ethanol, hot water and ether and dried.

The complexes are coloured, powdery, air stable and insoluble in water and common organic solvents viz. ethanol, acetone, benzene, chloroform, nitrobenzene, carbon tetrachloride, THF, DMF and DMSO. The physico-chemical measurements were done as described earlier<sup>1</sup>.

## Results and Discussion


The analytical data of the complexes (Table 1) agree with the general formula  $(-ML_2H_2O)_n$  [where  $M = Mn(II)$ ,  $Co(II)$ ,  $Ni(II)$ ,  $Cu(II)$  or  $Zn(II)$ ;  $L = C_{10}H_{10}N_4O_4$ ].

TABLE 1 - ANALYTICAL DATA OF THE COMPLEXES

Empirical formula	Colour	Analysis % Found (Calcd)			
		Metal	O	H	N
$MnL_2H_2O$	Yellow	15.86	35.04	4.68	24.27
		(16.32)	(35.60)	(4.16)	(24.92)
$CoL_2H_2O$	Red	17.86	34.95	4.17	24.80
		(17.30)	(35.15)	(4.10)	(24.68)
$NiL_2H_2O$	Yellow	17.00	34.40	4.35	24.48
		(17.20)	(35.28)	(4.11)	(24.35)
$CuL_2H_2O$	Greenish yellow	17.79	34.88	4.08	23.93
		(18.38)	(34.78)	(4.06)	(24.31)
$ZnL_2H_2O$	Yellow	17.28	32.49	3.67	22.55
		(17.89)	(32.85)	(3.83)	(22.99)



Semicarbazones ( $=N-NH-CO-NH_2$ ) exhibit tautomerism due to the presence of  $C=O$  group in the neighbourhood of  $NH$ ,  $H$  being enolizable. Thus, semicarbazones may coordinate with metals in both keto (I) or enolic (II) form.



The ir spectrum (wave numbers in  $cm^{-1}$ ) of TBSC (Table 2) shows the band at 3140 assignable to  $NH$  stretching. The bands appearing at 1670, 1645 and 1590 are due to  $C=O$ ,  $C=N$  and  $C=C$  stretching frequencies, respectively. The mixed  $NH_2$  deformation and  $C-N$  stretching frequency,  $N-N$  stretching, and  $C=O$  in-plane deformation bands occur at 1510, 925 and 750, respectively. These observations indicate that TBSC in solid state exists in keto form<sup>6</sup>.

In the spectra of the complexes,  $C=O$  stretching band disappears and new bands appearing at 1570-1550 and 1290-1285 are assigned to  $C=N-N=C$  stretching and  $C-O$  stretching at  $C-O-M$


\* For correspondence.



TABLE 2—CHARACTERISTIC BANDS OF IR SPECTRA OF TBSC AND ITS COMPLEXES

TBSC	Mn(II)	Fe(II)	Co(II)	Ni(II)	Cu(II)	Zn(II)	Assignment
...	8450	8960	8480	8460	8400	8420	$\nu$ O-H
8140	8120	8100	8120	8120	8110	8120	$\nu$ N-H
9020	8000	9980	8090	8090	8020	9990	$\nu$ C-H
1670	...	...	...	...	...	...	$\nu$ C=O
...	1680	1695	1685	1680	1685	1680	$\delta$ H <sub>2</sub> O
1645	1630	1630	1635	1630	1680	1635	$\nu$ C=N
...	1570	1550	1550	1550	1550	1560	$\nu$ C=N-N=O
1510	1520	1510	1510	1520	1510	1515	$\nu$ C-N
...	...	...	...	...	...	...	$\nu$ C-N-H
...	1280	1290	1290	1280	1285	1285	$\nu$ C-O
...	520	520	515	515	510	520	$\nu$ M-O
...	455	460	455	465	460	450	$\nu$ M-N

site, respectively, indicating coordination of the ligand in enolic form to the metals. A negative shift in the stretching frequency of C=N (azomethine) group suggests the coordination of azomethine nitrogens. The coordination of azomethine nitrogen is also supported by a positive shift in the stretching vibrations of N-N group<sup>7</sup> in the spectra of the complexes. The coordination through oxygen and nitrogen is further confirmed by the occurrence of new bands at *ca* 520-510 and 460-450 in the spectra of the complexes, which may be assigned to M-O and M-N stretching frequencies, respectively<sup>8</sup>. The strong bands observed in the complexes in the region 3500-3300 and *ca* 1960 may be assigned to  $\nu$  OH(H<sub>2</sub>O) and  $\delta$  H<sub>2</sub>O respectively, and indicate the presence of lattice and/or crystallization and/or coordination water in the complexes<sup>9</sup>.



Thus, the TBSC acts as tetradentate chelating agent, coordinating through the enolic oxygens and azomethine nitrogens, and polymeric complexes are formed (structure III) as the steric factors prevent the coordination of all the donor groups to the same metal ion.

TBSC is yellow in colour and therefore severely restricts the utility and accuracy of the electronic spectral studies, since intraligand bands interfere with the d-d bands of transition metal ions in the electronic spectra of the complexes.

The drs of TBSC shows strong band with its  $\lambda_{\max}$  at 380 nm (26,300  $\text{cm}^{-1}$ ) with a minor peak on the lower wavelength side at 270 nm (37,000  $\text{cm}^{-1}$ ). On the higher side absorption decreases more rapidly but it does not disappear up to 840 nm. The bands in the ligand may be assigned to the intraligand transitions,  $\pi \rightarrow \pi^*$ ,  $n \rightarrow \pi^*$ .

The observed magnetic moment of Mn(II)-complex is 5.89 B.M. which is in accordance with the value expected for spin only value for five

unpaired electrons in an octahedral Mn(II)-complex involving  $sp^3d^2$  hybridization. The reflectance spectrum shows weak bands at 16,130, 21,740, 27,780, 29,410 and 31,000  $\text{cm}^{-1}$ . The three higher bands have been assigned to  ${}^6A_{1g} \rightarrow {}^4T_{1g}$  (G),  ${}^6A_{1g} \rightarrow {}^4T_{2g}$  (G) and  ${}^6A_{1g} \rightarrow {}^4E_g$  (G) and the two lower bands to the transitions  ${}^6A_{1g} \rightarrow {}^4T_{1g}$  (D) and  ${}^6A_{1g} \rightarrow {}^4E_g$  (D) respectively, in an octahedral field of Mn(II) ion<sup>10,11</sup>.

The observed magnetic moment of Co(II)-complex is 4.87 B.M. In drs of Co(II)-complex, two bands appear at 10,000 and 22,900  $\text{cm}^{-1}$  which may be assigned to  ${}^4T_{1g}$  (F)  $\rightarrow$   ${}^4T_{2g}$  (F) ( $\nu_1$ ) and  ${}^4T_{1g}$  (F)  $\rightarrow$   ${}^4T_{1g}$  (P) ( $\nu_2$ ). However, the  ${}^4T_{1g}$  (F)  $\rightarrow$   ${}^4A_{1g}$  (F) ( $\nu_3$ ) transition is not observed, since it is a two electron process and has a much lower oscillator strength than the other two transitions, and is therefore much weaker. The values of 10 Dq and  $\nu_3$  have been calculated to be 11,350 and 21,350  $\text{cm}^{-1}$ , respectively. The  $\nu_3/\nu_1$  ratio, which is found to be 2.13, lies within the limit (2.1-2.2) reported for octahedral Co(II)-complexes<sup>12</sup>.

The electronic spectrum of Ni(II)-complex shows three d-d transition bands at 10,526, 15,652 and 26,319  $\text{cm}^{-1}$  which correspond to the transitions  ${}^3A_{2g} \rightarrow {}^3T_{2g}$  (F) ( $\nu_1$ ),  ${}^3A_{2g} \rightarrow {}^3T_{1g}$  (F) ( $\nu_2$ ) and  ${}^3A_{2g} \rightarrow {}^3T_{1g}$  (P) ( $\nu_3$ ), respectively. The  $\nu_3/\nu_1$  ratio is 1.50. The magnetic moment value (2.94 B.M.) together with drs data shows the octahedral geometry of Ni(II)-complex.

Cu(II)-complex has a magnetic moment value of 1.79 B.M. The electronic configuration  $3d^9$  gives rise to  ${}^2D$  free ion term which splits in a regular octahedral environment into a lower doublet  ${}^2E_g$  and an upper triplet  ${}^2T_{2g}$  levels. In electronic spectrum, only one band due to  ${}^2E_g \rightarrow {}^2T_{2g}$  transition is expected but true octahedral structures are uncommon. Here, three bands appear as shoulders at 10,000, 11,110 and 15,150  $\text{cm}^{-1}$  which may be assigned to  ${}^2B_{1g} \rightarrow {}^2A_{1g}$ ,  ${}^2B_{1g} \rightarrow {}^2B_{2g}$  and  ${}^2B_{1g} \rightarrow {}^2E_g$  transitions, respectively in a distorted octahedral geometry of Cu(II) ion<sup>14</sup>.

The thermal stability data of the complexes show that the initial weight loss is probably due to the loss of water molecules present in the complexes. The weight loss at the temperatures between 180-220° corresponds closely to water content of the chelates. On further heating, the organic component of the complexes decomposes leading to the formation of metal oxides. The order of thermal stability is  $\text{Zn} > \text{Ni} > \text{Co} > \text{Mn} > \text{Cu}$ .

The geometry of the ligand, composition, insolubility and thermal stability of complexes indicate that they are polymeric in nature<sup>1-4</sup>.

#### Acknowledgement

The work was carried out under a project sponsored by the Ministry of Defence, Government of India and the authors thank the Ministry for financial assistance and for the permission to publish the results.

# References

1. P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *Polymer Bull.*, 1979, **1**, 681.
2. P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *J. Indian Chem. Soc.*, 1980, **57**, 275.
3. B. SINGH, V. BANERJEE, B. V. AGARWALA and A. K. DEY, *J. Indian Chem. Soc.*, 1980, **57**, 865.
4. B. SINGH, P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *J. Indian Chem. Soc.*, 1981, **58**, 541.
5. P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *J. Indian Chem. Soc.*, 1978, **55**, 418.
6. T. MIYAZAWA, T. SHIMANOUCHI and S. MIZUSHIMA, *J. Chem. Phys.*, 1958, **29**, 64.
7. P. A. GIGURE and I. D. LIU, *J. Chem. Phys.*, 1959, **30**, 136.
8. K. NAKAMOTO, "Infrared and Raman Spectra of Coordination Compounds", Wiley, New York, 1978.
9. G. DEVOTO, M. MASSACCHI, G. PONTICELLI and C. PRETI, *J. Inorg. Nuclear Chem.*, 1977, **39**, 271.
10. J. W. STOUT, *J. Chem. Phys.*, 1959, **31**, 709.
11. M. GOODGAME and F. A. COTTON, *J. Phys. Chem.*, 1961, **65**, 791.
12. F. A. COTTON and M. D. MEYER, *J. Amer. Chem. Soc.*, 1980, **82**, 5028.
13. A. B. P. LEVINE, *Coord. Chem. Rev.*, 1968, **3**, 119.
14. I. M. PROCTER, B. J. HYTHAWAY and P. NICHOLIS, *J. Chem. Soc.*, 1968, 1678.

# Stability and Related Thermodynamic of Chelation of Zn(II) with Thiodiacetic Acid (TDAA), Thiodipropionic Acid (TDPA), Iminodiacetic Acid (IDAA), Dithiodiacetic Acid (DTDAA) and Diglycolic Acid (DGA)

S. N. DUBBY\*, R. K. BAWIA and D. M. PURI

Department of Chemistry, Kurukshetra University, Kurukshetra-131 119

Manuscript received 19 December 1981, accepted 21 July 1982

The chelation of Zn(II) with TDAA, TDPA, IDAA, DTDAA and DGA has been studied potentiometrically in aqueous medium at different ionic concentrations (0.1, 0.2 and 0.3 M NaClO<sub>4</sub>) and different temperatures (25, 35 and 45°) using Calvin-Bjerrum pH titration technique as modified by Irving and Rossotti. The thermodynamic stability constants and thermodynamic functions ( $\Delta G$ ,  $\Delta H$  and  $\Delta S$ ) have been reported.

It appears from a survey of literature<sup>1-4</sup> that no effort has been made to determine the thermodynamic stability constants of the complexes formed by Zn<sup>2+</sup> ions with TDAA, TDPA, IDAA, DTDAA and DGA. It was therefore considered of interest to study these systems potentiometrically. The thermodynamic stability constants of Zn(II) complexes were obtained by extrapolating the determined stability constants at various ionic strengths (0.1, 0.2 and 0.3 M; 25°) to zero ionic strength. The thermodynamic functions ( $\Delta G$ ,  $\Delta H$  and  $\Delta S$ ) were also calculated at 0.1 M. The titration technique was that of Calvin and Wilson as modified by Irving and Rossotti<sup>5-7</sup>.

## Experimental

**Materials :** The solutions of TDAA, TDPA and DTDAA (Evan's Chemicals), IDAA (Sigma Chem), DGA (John Backer Inc.) and zinc sulphate (ZnSO<sub>4</sub>·7H<sub>2</sub>O) were prepared in double distilled water. Perchloric acid (0.04 M) solution was prepared from the stock solution by dilution with double distilled water and standardized against standard NaOH solution. Other chemicals used were of A.R. grade. The stock solution of zinc sulphate was standardized gravimetrically as ZnNH<sub>4</sub>PO<sub>4</sub>.

**Apparatus :** A Philips pH meter (PR 9405 M) with glass and calomel electrodes assembly was used to measure the pH. The instrument was calibrated at pH 4.0 and 9.2 using buffer tablets.

**Procedure :** The experimental procedure used was the same as reported earlier<sup>8</sup>. The three solutions (total volume 50 ml in each case) were prepared as follows :

- (i)  $4 \times 10^{-3}$  M perchloric acid,
- (ii)  $4 \times 10^{-3}$  M perchloric acid +  $3 \times 10^{-3}$  M ligand, and
- (iii)  $4 \times 10^{-3}$  M perchloric acid +  $3 \times 10^{-3}$  M ligand +  $5 \times 10^{-4}$  M zinc ion solutions.

The concentration of the common ingredients in the solutions were identical in all the cases. An appropriate quantity of sodium perchlorate (0.2 M) was added to maintain the desired ionic concentrations of 0.1, 0.2 or 0.3 M. These solutions were titrated against a solution of 0.4 M caustic soda.

## Results and Discussion

The pH range investigated for different systems were as follows :

System	pH range
Zn(II)-TDAA	2.9-5.4
Zn(II)-TDPA	4.1-5.0
Zn(II)-IDAA	5.3-7.8
Zn(II)-DTDAA	3.7-4.7
Zn(II)-DGA	2.4-3.5

The proton-ligand stability constants of TDAA, TDPA, IDAA, DTDAA and DGA and the stepwise formation constants of their chelates with Zn(II) were determined at  $25 \pm 0.5^\circ$ ,  $35 \pm 0.5^\circ$  and  $45 \pm 0.5^\circ$  (Table I) using Irving-Rossotti technique, and the values were further refined using the computational techniques<sup>9,10</sup>, (i) curve fitting method and (ii) pointwise calculation method.

In Zn(II)-TDPA, Zn(II)-DTDAA and Zn(II)-DGA systems, the  $\bar{n}$  values vary between 0.1 and 0.9, thereby indicating the formation of only 1 : 1 complex. In Zn(II)-TDAA and Zn(II)-IDAA, values of  $\bar{n}$  vary between 0.2 and 1.9, indicating the formation of 1 : 1 as well as 1 : 2 complexes. The data in Table I reveal that stability constants decrease with increase in temperature and thus, lower temperature is favourable for complex formation. Metal-ligand stability constants increase with an increase in the ionic strength of the media. The thermodynamic stability constants ( $\log K_1^{p=0}$  and  $\log K_2^{p=0}$ ) have been evaluated at the standard state of infinite dilution and the values are given in Table I.

\* Author for correspondence.

TABLE 1—PROTON-LIGAND STABILITY CONSTANTS OF TDAA, TDPA, IDAA, DTDAA AND DGA AND FORMATION CONSTANTS OF THEIR CHELATES WITH Zn(II)

Systems	Stability Constants	Temperature					
		25°C		35°C		45°C	55°C
		$\mu=0.1$	$\mu=0.2$	$\mu=0.3$	$\mu=0.1$	$\mu=0.1$	$\mu=0.0$
TDAA	$\text{Log } K_1^H$	4.83	4.25	4.18	4.22	4.17	4.40
	$\text{Log } K_2^H$	8.14	8.11	2.95	8.09	2.87	3.23
TDPA	$\text{Log } K_1^H$	4.80	4.83	4.86	4.61	4.51	4.77
	$\text{Log } K_2^H$	8.63	8.66	8.74	8.54	8.58	8.58
IDAA	$\text{Log } K_1^H$	9.86	9.25	9.05	8.88	8.79	9.51
	$\text{Log } K_2^H$	2.74	2.56	2.58	2.40	2.32	2.82
DTDAA	$\text{Log } K_1^H$	8.96	8.82	8.66	8.98	4.16	4.11
	$\text{Log } K_2^H$	2.82	2.66	2.62	2.83	2.88	2.92
DGA	$\text{Log } K_1^H$	4.05	3.94	3.84	4.06	4.18	4.16
	$\text{Log } K_2^H$	2.83	2.49	2.42	2.64	2.85	2.73
Zn(II)-TDAA	$\text{Log } K_1$	8.20	8.80	8.88	8.12	8.08	8.14
	$\text{Log } K_2$	2.67	2.70	2.76	2.66	2.65	2.62
Zn(II)-TDPA	$\text{Log } K_1$	8.01	8.11	8.20	8.97	2.94	2.91
	$\text{Log } K_2$	5.95	6.82	7.70	5.92	5.89	5.08
Zn(II)-IDAA	$\text{Log } K_1$	4.43	4.92	5.42	4.42	4.41	3.96
	$\text{Log } K_2$	2.73	2.93	3.15	2.72	2.70	2.52
Zn(II)-DTDAA	$\text{Log } K_1$	8.79	8.87	8.94	8.75	3.72	3.71
	$\text{Log } K_2$						

TABLE 2—THERMODYNAMIC PARAMETERS OF Zn(II) COMPLEXES ( $\mu=0.1 M$ )

Ligand	Temp. °C	$-\Delta G(\text{Kcal.mole}^{-1})$		$-\Delta H(\text{Kcal.mole}^{-1})$		$\Delta S(\text{Cal.mole}^{-1}.\text{deg}^{-1})$	
		$-\Delta G_1$	$-\Delta G_2$	$-\Delta H_1$	$-\Delta H_2$	$\Delta S_1$	$\Delta S_2$
TDAA	25	4.36	8.64				
	35	4.40	8.75	2.77	0.80	5.16	9.22
	45	4.48	3.86				
TDPA	25	4.11	—				
	35	4.19	—	1.47	—	8.57	—
	45	4.28	—				
IDAA	25	8.12	6.03				
	35	8.35	6.23	1.98	1.01	21.87	16.29
	45	8.57	6.42				
DTDAA	25	3.72	—				
	35	3.83	—	0.86	—	9.28	—
	45	3.93	—				
DGA	25	5.17	—				
	35	5.20	—	1.68	—	11.99	—
	45	5.42	—				

The thermodynamic functions  $\Delta G$ ,  $\Delta H$  and  $\Delta S$  were calculated at different temperatures using the standard equations<sup>11</sup> and are given in Table 2.  $\Delta H$  values were calculated by plotting the values of  $\log K_n$  at different temperatures as a function of  $(1/T)$  and equating the gradient of this plot with  $-\Delta H/4.57$ . Chelates of Zn(II) with TDAA, TDPA, IDAA, DTDAA and DGA are formed spontaneously as evinced by the negative values of  $\Delta G$ . The overall changes in the values of  $\Delta H$  and  $\Delta S$  indicate that the complexes are both enthalpy and entropy stabilized. The negative values of  $\Delta H$  ensure that the reactions are exothermic. The relatively smaller values of  $\Delta H$  as compared to  $\Delta S$  indicate that entropy is the principal driving force for the complex formation in aqueous solution, i.e. increase in randomness in the systems

will increase the stability of complex because entropy is a solvent property.

#### Acknowledgement

The authors are thankful to Prof. H. K. Pujari, Head, Chemistry Department, Kurukshetra University, Kurukshetra for facilities.

#### References

1. M. YASADA, K. YAMASAKI and H. OHTAKI, *Bull. Chem. Soc. Japan*, 1960, 33, 1067.
2. K. S. RAJAN and A. E. MARTELL, *J. Inorg. Nuclear Chem.*, 1964, 26, 789.
3. S. CHABERNEK and A. E. MARTELL, *J. Amer. Chem. Soc.*, 1962, 74, 6052.
4. G. SCHWARZENBACH, H. ACKERMANN and P. RUCKSTUHL, *Helv. Chim. Acta*, 1949, 32, 1175.

5. J. BJERRUM, "Metal Ammine Formation in Aqueous Solution", P. Haase and Son., Copenhagen, 1941.
6. M. CALVIN and K. W. WILSON, *J. Amer. Chem. Soc.*, 1945, **67**, 2009.
7. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
8. B. ARORA, H. L. KALRA, S. N. DUBEY and D. M. PURI, *J. Indian Chem. Soc.*, 1978, **55**, 445.
9. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1958, 3397.
10. S. N. DUBEY and R. C. MEHROTRA, *Indian J. Chem.*, 1987, **5**, 327.
11. K. B. YATSIMIRSKII and V. P. VASIL'EV, "Instability Constants of Complex Compounds", Pergamon Press, London, 1960, p. 69.

# Ion-exchange Equilibria of $\text{Na}^+ \text{-} \text{Ca}^{2+} / \text{Cl}^-$ and $\text{Na}^+ \text{-} \text{Mg}^{2+} / \text{Cl}^-$ from Concentrated Solution

L. D. DAVE and H. M. TRIVEDI

Department of Chemistry, Bhavnagar University, Bhavnagar-364 002

Manuscript received 3 August 1981, revised 3 April 1982, accepted 21 July 1982

The ion exchange of alkaline earth metal ions from their concentrated mixtures with alkali metal ions is studied. It is observed that as the concentrations of  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  in the solution increase, their uptake becomes smaller on the sodium form of Zeocarb-225. The no-selectivity line is reached when their concentrations reach 4.0 N.

THE behaviour of ions on exchange from concentrated solutions of  $\text{Cu}^{2+}/\text{Na}^+$  on Dowex 50 $\times$ 8 was found by Subbarao and David<sup>1</sup> to be different from that from dilute solutions. They observed that the selectivity of ions by this exchanger decreases in concentrated solutions. However, the extent of such a decrease in selectivity is not known for alkali/alkaline earth metal ions by synthetic resins.

Bokil<sup>2</sup> found that when schoenite,  $\text{K}_2\text{SO}_4 \cdot \text{MgSO}_4 \cdot 6\text{H}_2\text{O}$ , was added to soils with varying ion-exchange capacity e.g. red soil from Coimbatore, black soil from Bhavnagar and lateritic soil from Bangalore there was, in all cases, a reversal of uptake of  $\text{Mg}^{2+}$  beyond a certain concentration of schoenite and that  $\text{K}^+$  was preferred by these clays. Hence we decided to inquire whether commercially available synthetic resins also show similar exchange behaviour in concentrated solutions.

We report here the results of our investigation on the behaviour of the strong acid exchanger, sodium form of zeokarb-225, from concentrated solutions of  $\text{Na}^+ \text{-} \text{Ca}^{2+}$  and  $\text{Na}^+ \text{-} \text{Mg}^{2+}$  as chlorides

## Experimental

Na-form of zeokarb-225 resin was equilibrated with the solution mixtures ( $\text{Na}^+/\text{M}^{2+}$  ratios 1 : 9 to 9 : 1) of chlorides of  $\text{Na}^+ \text{-} \text{Ca}^{2+}$  and  $\text{Na}^+ \text{-} \text{Mg}^{2+}$  of different concentrations (1.0 N to 4.0 N).

After 24 hr, the concentration of divalent ion was estimated by EDTA titration<sup>3</sup> and fractions of metal ions in solutions and on the exchanger were calculated by difference. Results are given in Tables 1A and 1B. Equilibrium isotherms of  $\text{Na}^+ \text{-} \text{Ca}^{2+}$  and  $\text{Na}^+ \text{-} \text{Mg}^{2+}$  systems in three different concentrations (1.0, 2.0 and 4.0 N) were drawn by plotting equivalent ionic fractions of metal ions in

TABLE 1A— $\text{Na}^+ \rightleftharpoons \text{Mg}^{2+} (\text{Cl}^-)$  ION EXCHANGE EQUILIBRIA WITH ZEOKARB-225 AT  $27 \pm 2^\circ$

(i) 25.0 ml 1.0 N mixture of 1.0 N NaCl + 1.0 N $\text{MgCl}_2$ + 1.0 g zeokarb-225 in $\text{Na}^+$ form. (ii) 25.0 ml 2.0 N mixture of 2.0 N NaCl + 2.0 N $\text{MgCl}_2$ + 2.0 g zeokarb-225 in $\text{Na}^+$ form. (iii) 25.0 ml 4.0 N mixture of 4.0 N NaCl + 4.0 N $\text{MgCl}_2$ + 4.0 g zeokarb-225 in $\text{Na}^+$ form.							
Proportion of $\text{Na}^+$	Concentration of solns.	Fraction of $\text{Na}^+$ in solns.	Fraction of $\text{Na}^+$ on resin	Proportion of $\text{Na}^+$	Concentration of solns.	Fraction of $\text{Mg}^{2+}$ in solns.	Fraction of $\text{Mg}^{2+}$ on resin
$\text{Na}_{10}$	1.0 N	0.1995	0.088	$\text{Na}_{10}$	1.0 N	0.8005	0.9120
$\text{Na}_{20}$		0.3815	0.1754	$\text{Na}_{20}$		0.6185	0.8246
$\text{Na}_{30}$		0.5476	0.2608	$\text{Na}_{30}$		0.4524	0.7392
$\text{Na}_{70}$		0.7499	0.5069	$\text{Na}_{70}$		0.2500	0.4931
$\text{Na}_{90}$		0.9185	0.7730	$\text{Na}_{90}$		0.0815	0.2270
$\text{Na}_0$	2.0 N	0.1230	0.055	$\text{Na}_0$	2.0 N	0.8870	0.9450
$\text{Na}_{10}$		0.2268	0.1061	$\text{Na}_{10}$		0.7732	0.8939
$\text{Na}_{20}$		0.4137	0.2368	$\text{Na}_{20}$		0.5863	0.7614
$\text{Na}_{30}$		0.5923	0.4100	$\text{Na}_{30}$		0.4077	0.5900
$\text{Na}_{70}$		0.7398	0.5900	$\text{Na}_{70}$		0.2602	0.4100
$\text{Na}_{90}$	4.0 N	0.9101	0.8295	$\text{Na}_{90}$	4.0 N	0.0899	0.1705
$\text{Na}_0$		0.1279	0.0842	$\text{Na}_0$		0.8721	0.9158
$\text{Na}_{10}$		0.3103	0.2105	$\text{Na}_{10}$		0.7897	0.7895
$\text{Na}_{20}$		0.5869	0.4340	$\text{Na}_{20}$		0.6131	0.5660
$\text{Na}_{30}$		0.5608	0.5150	$\text{Na}_{30}$		0.4392	0.4850
$\text{Na}_{70}$		0.7464	0.7335	$\text{Na}_{70}$		0.2536	0.3665
$\text{Na}_{90}$		0.9114	0.9115	$\text{Na}_{90}$		0.0886	0.0885
$\text{Na}_0$		0.1205	0.1155	$\text{Na}_0$		0.8795	0.8850

$\text{Na}_{10}$  means 10.0 ml of NaCl solution mixed with 90.0 ml of  $\text{MgCl}_2/\text{CaCl}_2$ . Similarly for  $\text{Na}_{20}$ ,  $\text{Na}_{30}$ , etc.

TABLE 1B— $\text{Na}^+\rightleftharpoons\text{Ca}^{2+}(\text{Cl}^-)$  ION EXCHANGE EQUILIBRIA WITH ZEOKARB-225.

(i) 25.0 ml 1.0 N mixture of 1.0 N NaCl + 1.0 N $\text{CaCl}_2$ + 1.0 g zeokarb-225 in $\text{Na}^+$ form.							
(ii) 25.0 ml 2.0 N mixture of 2.0 N NaCl + 2.0 N $\text{CaCl}_2$ + 1.0 g zeokarb-225 in $\text{Na}^+$ form.							
(iii) 25.0 ml 4.0 N mixture of 4.0 N NaCl + 4.0 N $\text{CaCl}_2$ + 4.0 g zeokarb-225 in $\text{Na}^+$ form.							
Proportion of $\text{Na}^+$	Concentration of solns.	Fraction of $\text{Na}^+$ in solns.	Fraction of $\text{Na}^+$ on resin	Proportion of $\text{Na}^+$	Concentration of solns.	Fraction of $\text{Ca}^{2+}$ in solns.	Fraction of $\text{Ca}^{2+}$ on resin
$\text{Na}_{1.0}$	1.0 N	0.2055	0.0460	$\text{Na}_{1.0}$	1.0 N	0.7985	0.9540
$\text{Na}_{2.0}$		0.3689	0.1074	$\text{Na}_{2.0}$		0.6811	0.8926
$\text{Na}_{3.0}$		0.5522	0.2306	$\text{Na}_{4.0}$		0.4378	0.7694
$\text{Na}_{7.0}$		0.7308	0.4054	$\text{Na}_{7.0}$		0.2692	0.5946
$\text{Na}_{9.0}$		0.9095	0.6273	$\text{Na}_{9.0}$		0.0905	0.3727
$\text{Na}_0$	2.0 N	0.1163	0.0269	$\text{Na}_0$	2.0 N	0.8837	0.9731
$\text{Na}_{1.0}$		0.2193	0.1384	$\text{Na}_{1.0}$		0.7807	0.8616
$\text{Na}_{2.0}$		0.3995	0.2422	$\text{Na}_{2.0}$		0.6005	0.7578
$\text{Na}_{3.0}$		0.5920	0.4070	$\text{Na}_{4.0}$		0.4080	0.5930
$\text{Na}_{7.0}$		0.7381	0.5910	$\text{Na}_{7.0}$		0.2619	0.4790
$\text{Na}_{9.0}$	4.0 N	0.9102	0.8335	$\text{Na}_{9.0}$	4.0 N	0.0898	0.1665
$\text{Na}_0$		0.1309	0.0710	$\text{Na}_0$		0.8691	0.9290
$\text{Na}_{1.0}$		0.2103	0.2105	$\text{Na}_{1.0}$		0.7897	0.7895
$\text{Na}_{2.0}$		0.3969	0.3340	$\text{Na}_{2.0}$		0.6131	0.6060
$\text{Na}_{3.0}$		0.5608	0.5150	$\text{Na}_{4.0}$		0.4392	0.4850
$\text{Na}_{7.0}$		0.7464	0.7235	$\text{Na}_{7.0}$		0.2536	0.2765
$\text{Na}_{9.0}$		0.9166	0.8658	$\text{Na}_{9.0}$		0.0834	0.1842
$\text{Na}_0$		0.1176	0.0955	$\text{Na}_0$		0.8824	0.9045

solutions against equivalent ionic fractions of metal ions on exchanger and are shown in Figs. 1 and 2.




Fig. 1.  $\text{Na}^+\rightleftharpoons\text{Mg}^{2+}(\text{Cl}^-)$  exchange isotherm for zeokarb-225 in  $\text{Na}^+$  form with 1.0, 2.0 and 4.0 N metal ion solutions at  $27 \pm 2^\circ$ .

○ =  $\text{Na}^+$     ⊗ =  $\text{Mg}^{2+}$

It can be seen from the results in Table 1A that fraction of  $\text{Na}^+$  on the resin from  $\text{MgCl}_2$  solution is 0.055, 0.0842 and 0.1150 meq, respectively with the 1.0, 2.0 and 4.0 N metal ion concentrations. Similarly, corresponding fraction of  $\text{Mg}^{2+}$  on resin is 0.9455, 0.9158 and 0.8850 meq from 1.0, 2.0 and 4.0 N metal ion concentrations. The fraction of




Fig. 2.  $\text{Na}^+\rightleftharpoons\text{Ca}^{2+}(\text{Cl}^-)$  exchange isotherm for zeokarb-225 in  $\text{Na}^+$  form with 1.0, 2.0 and 4.0 N metal ion solutions at  $27 \pm 2^\circ$ .

○ =  $\text{Na}^+$     ⊗ =  $\text{Ca}^{2+}$

$\text{Ca}^{2+}$  on the exchanger is also found to decrease as 0.9731, 0.9290 and 0.9045 meq with the respective concentrations of solution of  $\text{Mg}^{2+}$ .

Thus, both  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  are exchanged on resins to a lesser extent from more concentrated solutions. The difference between the exchange of  $\text{Mg}^{2+}$  and  $\text{Ca}^{2+}$  on the resin is small,  $\text{Ca}^{2+}$  being exchanged to a slightly greater extent. Thus, a striking fact emerges that both  $\text{Mg}^{2+}$  and  $\text{Ca}^{2+}$  are exchanged less and less from concentrated solutions.

can, therefore, be stated that a greater concentration of a bivalent ion results in lower exchange of that ion.

The decreasing exchange of bivalent metal ions by sodium form of zeokarb-225 from their increasingly more concentrated solutions can be explained on the following two grounds<sup>4</sup>.

(1) *Donnan equilibrium* : The Donnan potential set up by a resin is directly proportional to the ionic molality in the resin and is inversely proportional to the solution concentration. Thus, with large concentrations, the Donnan potential driving the counter ion into the resin is weaker. This results in a lower exchange from concentrated solutions.

(2) *Ion-pair formation* : The concentrated solutions, dissociation of a salt into ions becomes smaller. Ion-pairs are found to be present in an increasingly large amount as the concentration of the electrolyte increases<sup>5</sup>. The ion-pair formation is greater in ions of larger valency. Hence,  $Mg^{2+}$  and  $Ca^{2+}$  ions form ion-pairs to a greater extent than alkali metals.

Equilibrium isotherms, which are shown in Figs. 1 and 2 suggest that as the concentration of the solution increases, the uptake of bivalent metal ions on the  $Na^+$  form of the exchanger decreases. At about 4.0 N concentration of equilibrated solution, the equilibrium isotherms tend to coincide with the line of zero-selectivity showing thereby that the exchanger has practically no preference

for either the bivalent or the monovalent cations. Between  $Ca^{2+}$  and  $Mg^{2+}$ ,  $Ca^{2+}$  is preferred to a slightly greater extent. This is because, as the concentration increases and the water activity falls,  $Ca^{2+}$  begins to gradually lose its hydration and tends to go into the resin phase and is found to be preferred<sup>6</sup> to  $Mg^{2+}$ . The effect, however, is very small as far as  $Ca^{2+}$  and  $Mg^{2+}$  are concerned.

It can be deduced from the above data obtained by batch experiments that in column operation, the conversion of the resin from the monovalent to the bivalent metal form (i.e. exhaustion cycle) can be achieved very well by employing dilute solutions of the bivalent metal ion concerned, whereas the regeneration cycle i.e. conversion of the exchanger from bivalent to monovalent form can be achieved by the use of concentrated solution of monovalent ions. Dilute solutions of such monovalent ions will also be more effective for the regeneration cycle.

#### References

1. H. C. SUBBARAO and M. M. DAVID, *A. I. Ch. E. Journal*, 1957, 3, 187.
2. K. K. BOKIL, Ph.D. Thesis, Gujarat University, 1970.
3. A. I. VOGEL, "Quantitative Inorganic Analysis", Longman, Green and Co. Ltd., 1964, p. 434.
4. FRIEDRICH G. HELFFERICH, "Ion Exchange", McGraw-Hill Book Co. Inc., New York, 1962, p. 185.
5. RAO, PATEL and N. T. COLEMAN, *Sov. Sc. Soc. Am. Proc.*, 1968, 82.
6. JACOB, A. MARINSKY, "Ion Exchange", Marcel Dekker Inc., New York, 1966, Vol. 1, 337.



# The Alkaline and Acid Hydrolysis of *n*-Butylacetate in Methanol-Water Mixtures

I. M. SIDAHMED, S. M. SALEM and F. M. ABDEL HALIM

Chemistry Department, Faculty of Science, Moharram Bey, Alexandria, Egypt

Manuscript received 2 December 1980, revised 9 February 1982, accepted 8 July 1982

Alkaline and acid hydrolysis of *n*-butylacetate was carried out in aqueous methanol at 10-25° for the alkaline and at 25-50° for the acid hydrolysis. In alkaline hydrolysis the reaction was irreversible and the bimolecular rate constants decreased steadily with progressive increase of the organic solvent in the reaction medium. In the acid hydrolysis, the reaction attained an equilibrium which depended upon the solvent composition. With progressive additions of methanol to the acidic ester solution, the overall and reverse reaction rates increased gradually while the forward reaction rate decreased. The characteristic kinetic behaviours are discussed in the light of the 'Back-Strain' effect and solvation phenomena. The effect of dielectric constant on reaction rate is interpreted by the treatment of Amis, based on simple electrostatic consideration of ion-dipole interactions. The isocomposition, isodielectric energy and logarithm of the Arrhenius frequency factor are also calculated and interpreted in terms of solvation effects. Mechanisms for alkaline and acidic hydrolyses are proposed which account for the role and the effects of the solvent on the reaction rate. The thermodynamic parameters  $\Delta G^\ddagger$ ,  $\Delta H^\ddagger$ ,  $\Delta S^\ddagger$  are calculated as a support to the proposed mechanisms.

**A**LKALINE and acidic ester hydrolysis has been studied earlier<sup>1,2</sup>. Costeanu and Mateescu<sup>3</sup> studied the alkaline hydrolysis of *n*-butylacetate, propionate and butyrate in aqueous acetone. It was found that the rate of alkaline hydrolysis decreased with a decrease in the dielectric constant of the medium. Using acetone of mole fractions ranging from 0.124 to 0.377, the variation in the hydrolysis rate constant was found to follow the order  $\text{MeCO}_2\text{Bu} > \text{EtCO}_2\text{Bu} > \text{PrCO}_2\text{Bu}$ , i.e. it decreased with the decreasing dipole moment of the esters. The acid hydrolysis of butylacetate in different  $\text{H}_2\text{O}$ -acetone mixtures has been studied at 40, 50 and 60°. The reaction rate constant was correlated with the dielectric constant and the viscosity of the mixed solvent. The values of the rate constants at every temperature passed through a minimum for a mole fraction of 0.4 of acetone. These data at different mole fractions of acetone permitted the calculation of the values of activation energy, frequency factor and thermodynamic parameters, which all show a maximum at the same mole fraction. The characteristic kinetic behaviours were discussed in the light of the solvation phenomena. In the present study, the alkaline and acidic hydrolysis of *n*-butylacetate in various methanol-water mixtures are investigated. The calculated thermodynamic data and other parameters are discussed as evidence supporting the proposed mechanism.

## Experimental

**Materials:** *n*-Butylacetate (B. D. H.) was further purified by drying over sodium sulphate for

24 hr followed by fractional distillation. The fraction distilling at 124-125°/760 mm was collected and used. Methanol (E. Merck) was also purified as reported in literature<sup>4</sup>. Conductivity water was used for the different preparations and kinetic runs.

**Preparation of solutions:** An appropriate amount of the organic solvent was introduced in a measuring flask containing an weighed amount of *n*-butylacetate, affording a 0.05 *M* for the alkaline and 0.1 *M* for the acid hydrolysis. After attainment of thermal equilibrium the requisite quantity of NaOH solution, corresponding to 0.05 *M* for the alkaline hydrolysis, and that of HCl solution, corresponding to 0.1 *M* for the acid hydrolysis, was added to the ester solution. The volume was then made up to the mark and the flask placed in a thermostat at a temperature held constant within  $\pm 0.05^\circ$ .

**Rate determination:** The rate of the alkaline hydrolysis was followed by withdrawing 5 ml samples of the reaction mixture. These were allowed to flow through an ion exchanger containing the cation Amberlite resin, IR-120 (H). The liberated acetic acid was determined by titration. The estimated infinity values in methanol-water mixtures indicated that the reaction is not of the reversible type. The values of the specific velocity constant  $k_s$  were calculated using the second-order rate equation:

$$k_s = \frac{x}{a(a-x)t} \quad \dots (1)$$

where *a* is the initial concentration of both ester and alkali and *x* is the amount decomposed in

time  $t$ . In the acidic hydrolysis the reaction followed a first order law and was found to be of reversible nature. The rate constants were determined by titrating the liberated acetic acid with standard alkali. The effect of temperature on the position of equilibrium was investigated. No change in the equilibrium concentration was detected with change in temperature. So the infinity or equilibrium values were determined by heating the samples in sealed ampoules at  $70^\circ$  for 2-4 days until two successive values were identical. The rate constants  $k'_1$  and  $k'_2$  of the forward and backward reactions, respectively were calculated using the kinetic equation :

$$\frac{dx}{dt} = k'_1 (a - x_\infty) - k'_2 x_\infty \quad (2)$$

The backward rate is assumed to obey a first order law, since the concentration of the acetic acid liberated by the forward reaction is small compared to the concentration of the total alcohol in the medium. Integration of equation (2) gives the expression,

$$(k'_1 + k'_2)t = 2.303 \log x_\infty / (x_\infty - x) \quad (3)$$

where  $x_\infty$  is the equilibrium value. It follows, therefore, from equation (3) that the plot of  $\log x_\infty / (x_\infty - x)$  versus  $t$  should give a straight line with a positive slope which is equal to  $(k'_1 + k'_2) / 2.303$ , and that :

$$k'_1 = (k'_1 + k'_2) \cdot x_\infty / a \quad (4)$$

where  $a$  is the infinity value for the complete reaction.

## Results and Discussion

1. *Effect of temperature* : Interpolated values of  $k_2$  (in  $l. \text{mole}^{-1} \text{sec}^{-1}$ ) for the alkaline hydrolysis of  $n$ -butylacetate in presence of methanol-water mixtures in the temperature range  $10$ - $25^\circ$  are given in Table 1, while the corresponding values

TABLE 1—INTERPOLATED VALUES OF  $k_2$  (in  $l. \text{mole}^{-1} \text{sec}^{-1}$ ) FOR THE ALKALINE HYDROLYSIS OF  $n$ -BUTYLACETATE IN PRESENCE OF METHANOL-WATER MIXTURES

Wt. % of Solvent	$10^\circ \text{K}_2$			
	$10^\circ$	$15^\circ$	$20^\circ$	$25^\circ$
15	4.420	6.800	8.675	11.500
20	8.625	5.125	7.000	9.650
25	2.925	4.100	5.750	7.875
30	2.850	3.350	4.650	6.500
35	1.800	2.550	3.650	5.100
40	1.375	2.050	2.925	3.975
45	1.025	1.575	2.225	3.050
50	0.750	1.200	1.720	2.800
55	0.575	0.900	1.340	1.800
60	0.420	0.650	1.000	1.325
65	0.300	0.500	0.750	0.950
70	0.225	0.400	0.560	0.700
75	0.175	0.325	0.450	0.525
80	0.140	0.250	0.350	0.400

for the overall, forward and backward reactions, ( $k_{\text{obs}}$ ,  $k'_1$  and  $k'_2$ ) respectively, for the acid hydrolysis are recorded in Table 2. Arrhenius equation is strictly obeyed. Good straight lines are obtained on plotting  $\log k_2$  versus  $1/T$ , for alkaline hydrolysis as shown in Fig. 1. The values of the isocomposition activation energy,  $E_0$ , and frequency factor  $\log A$  were calculated by the least square method and are compiled in Table 3. For the acid hydrolysis, good straight lines were obtained on plotting the  $\log k'$  versus  $1/T$ . The values of the forward  $E_{1c}$ , backward  $E_{2c}$ , observed  $E_{\text{obs}}$  activation energies, and the frequency factor  $\log A$  for the forward reaction are also calculated by the least square method and recorded in Table 3. However, to obtain a more precise treatment of the results, the temperature dependence of the dielectric constant should be eliminated. This is achieved by calculating the isodielectric activation energies,  $E_d$ , from the corresponding rate constants in isodielectric solutions. The values of  $E_d$  for alkaline hydrolysis and the values of  $E_{1d}$ ,  $E_{2d}$  and  $E_{d \text{ obs}}$  for the acid hydrolysis are given in Table 4.

TABLE 2—INTERPOLATED VALUES OF RATE CONSTANTS ( $k \times 10^4 \text{ sec}^{-1}$ ) FOR THE ACID HYDROLYSIS OF  $n$ -BUTYLACETATE IN PRESENCE OF METHANOL-WATER MIXTURES

Wt % Solvent	$25^\circ$			$30^\circ$			$40^\circ$			$50^\circ$		
	$10^4 k_{\text{obs}}$	$10^4 k'_1$	$10^4 k'_2$	$10^4 k_{\text{obs}}$	$10^4 k'_1$	$10^4 k'_2$	$10^4 k_{\text{obs}}$	$10^4 k'_1$	$10^4 k'_2$	$10^4 k_{\text{obs}}$	$10^4 k'_1$	$10^4 k'_2$
15	1.700	0.900	0.800	2.850	1.680	1.170	6.800	3.740	3.060	14.000	7.220	6.780
20	1.800	0.815	0.985	3.000	1.560	1.440	6.900	3.380	3.520	14.400	6.920	7.480
25	1.875	0.760	1.115	3.200	1.415	1.785	7.000	3.040	3.920	15.000	6.580	8.420
30	1.900	0.705	1.195	3.350	1.290	2.060	7.100	2.850	4.250	15.800	6.270	9.530
35	2.050	0.655	1.395	3.550	1.170	2.380	7.300	2.650	4.650	17.000	5.980	11.320
40	2.175	0.610	1.565	3.750	1.057	2.683	7.550	2.500	5.150	18.600	5.690	12.910
45	2.350	0.575	1.775	4.000	0.990	3.010	8.050	2.370	5.680	20.600	5.420	15.180
50	2.550	0.547	2.003	4.250	0.925	3.325	8.700	2.280	6.420	22.900	5.180	17.720
55	2.740	0.523	2.217	4.600	0.875	3.727	9.500	2.200	7.300	25.800	4.960	20.940
60	3.000	0.505	2.495	4.950	0.835	4.115	10.600	2.240	8.460	29.200	4.750	24.450
65	3.400	0.493	2.907	5.150	0.800	4.650	13.000	2.080	10.920	33.600	4.570	29.080
70	3.875	0.487	3.388	6.200	0.775	5.425	18.600	2.040	11.560	39.000	4.430	34.570
75	4.650	0.482	4.168	7.200	0.765	6.435	15.800	2.000	13.800	46.000	4.340	41.680
80	5.725	0.475	5.250	8.550	0.760	7.790	19.600	1.980	17.620	55.800	4.275	51.525
85	7.275	0.473	6.802	10.650	0.755	9.895	25.400	1.960	23.440	69.000	4.240	64.760
90	9.250	0.470	8.780	13.750	0.750	13.000	33.800	1.950	31.860	88.400	4.200	79.200




Fig. 1. Determination of activation energy in methanol-water mixtures.

TABLE 3—ISOCOMPOSITION ENERGIES OF ACTIVATION (in Kcal mole<sup>-1</sup>) AND FREQUENCY FACTORS IN METHANOL-WATER MIXTURES

Wt % solvent	Alkaline hydrolysis		Acid hydrolysis			
	$E_a$	$\log A$	$E_{1c}$	$E_{2c}$	$E_{c \text{ obs}}$	$\log A$
15	10.61	9.90	15.67	19.34	16.12	12.48
20	10.89	9.96	15.99	15.75	15.84	12.67
25	11.07	10.03	16.16	15.38	15.71	12.75
30	11.29	10.08	16.40	15.55	15.88	12.90
35	11.55	10.17	16.67	15.58	15.90	13.05
40	11.87	10.31	16.91	15.65	16.02	13.20
45	12.13	10.39	17.05	15.87	16.18	13.27
50	12.19	10.53	17.16	16.18	16.41	13.33
55	12.81	10.67	17.23	16.66	16.75	13.36
60	13.01	10.68	17.32	17.04	17.08	13.38
65	12.98	10.52	17.17	17.49	17.46	13.28
70	12.58	10.10	17.08	17.43	17.40	13.21
75	12.20	9.71	17.00	17.34	17.31	13.14
80	11.70	9.22	16.98	17.22	17.30	13.13
85	—	—	16.95	17.17	17.26	13.10
90	—	—	16.93	16.95	16.95	13.08

TABLE 4—ISODIELECTRIC ACTIVATION ENERGIES (in Kcal mole<sup>-1</sup>) FOR METHANOL-WATER MIXTURES

D	Alkaline hydrolysis		Acid hydrolysis	
	$E_d$	$E_{1d}$	$E_{2d}$	$E_{d \text{ obs}}$
40	—	17.34	9.19	13.86
50	18.54	17.79	12.91	14.40
55	18.23	—	—	—
60	17.81	18.00	12.98	14.40
65	17.25	—	—	—
70	16.59	18.37	13.37	14.29

Both of velocity constants in the alkaline hydrolysis and the forward reaction for the acid hydrolysis are found to decrease with the progressive addition of methanol. This trend is ascribed to the decrease of water concentration as well as to the lowering of the dielectric constant of the medium. On the other hand, the isocomposition activation energy,  $E_a$ , increases to a maximum value for both alkaline and acidic hydrolysis, while isodielectric activation energies,  $E_d$ , increase with the decrease of the dielectric constant in alkaline hydrolysis and pass through maximum in case of acid hydrolysis. This may be due to the solvation of the activated complex to a less extent than that of the reactants. Although the changes in  $\log A$  are generally more sensitive to solvent composition, the variation of the activation energy with solvent composition is more pronounced than that of  $\log A$ .

#### Thermodynamic data of the activated complex :

The effect of changes in solvent composition on the rate constant of the reaction is conveniently verified in terms of the thermodynamic parameters of activation. These are calculated at different temperatures for different solvent composition in both alkaline and acidic hydrolysis and are compiled in Tables 5 and 6.

In both alkaline and acidic hydrolysis, the data of  $\Delta G^\ddagger$  indicate that solvation of the reactants is more than that of the activated complex which is in agreement with the decrease of the bimolecular rate constant in alkaline hydrolysis and the forward rate constant in acidic hydrolysis as the concentration of the methanol in the mixture increases. The heat content change  $\Delta H^\ddagger$ , shows a maximum in both alkaline and acidic hydrolysis. This may be a direct consequence of the behaviour of the isocomposition activation energy with the increasing organic solvent content. The non-linear relation between  $\Delta S^\ddagger$  and the solvent composition in alkaline and acidic media indicate specific solvation and hence a non-random distribution of the solvent molecules<sup>9</sup>.


**Effect of dielectric constant :** Akerlof's data<sup>9</sup> are used to obtain the dielectric constant values for the mixtures under investigation by interpolation. For the alkaline hydrolysis, the plots of  $\log k_a$  against  $1/D$  (Fig 2) give straight lines with negative slopes. Deviation from this linearity are observed at high solvent concentration (region of low dielectric constant). These deviations are probably due to the preferential solvation of the activated complex by water, the higher dielectric constant component. Consequently the distribution of the solvent molecules will be less random, and the values of  $D$  in the immediate vicinity of the ion will diverge considerably from that in the bulk, which is the value measured experimentally. This effect becomes larger as the dielectric constant becomes lower. In the acidic hydrolysis, an increase of the dielectric constant of the mixtures is found to lead to an increase in the rate of the forward reaction. However, the rate of the overall and reverse

TABLE 5—THERMODYNAMIC DATA IN METHANOL-WATER MIXTURES  $\Delta G^\circ$  AND  $\Delta H^\circ$  IN KCAL/MOLE,  $\Delta S^\circ$  IN CAL/MOLE/DEGREE

Wt % Solvent	15	20	25	30	35	40	45	50	55	60	65	70	75	80
10° $\Delta G^\circ$	18.800	18.412	18.532	18.655	18.805	18.957	19.122	19.298	19.448	19.624	19.814	19.976	20.117	20.243
10° $\Delta H^\circ$	10.130	10.825	10.529	10.795	10.986	11.308	11.570	11.929	12.261	12.449	12.418	12.091	11.686	11.197
10° $-\Delta S^\circ$	28.884	28.561	28.264	28.006	27.618	27.014	26.671	26.026	25.889	25.340	26.190	28.095	29.952	32.160
15° $\Delta G^\circ$	18.430	18.548	18.676	18.792	18.926	19.073	19.224	19.380	19.545	19.791	19.881	20.009	20.128	20.278
15° $\Delta H^\circ$	10.120	10.315	10.519	10.715	10.975	11.298	11.560	11.719	12.251	12.489	12.408	12.011	11.526	11.127
15° $-\Delta S^\circ$	28.839	28.672	28.908	28.031	27.599	26.982	26.597	25.893	25.313	25.306	25.984	27.766	29.506	31.758
20° $\Delta G^\circ$	18.574	18.699	18.814	18.944	19.079	19.208	19.367	19.517	19.662	19.823	20.001	20.171	20.298	20.445
20° $\Delta H^\circ$	10.110	10.305	10.500	10.906	10.965	11.289	11.550	11.909	12.241	12.429	12.398	12.001	11.616	11.117
20° $-\Delta S^\circ$	28.873	28.694	28.330	28.101	27.679	27.018	26.666	25.953	25.315	25.223	26.936	27.870	29.616	31.820
25° $\Delta G^\circ$	18.733	18.837	18.958	19.071	19.215	19.368	19.520	19.687	19.832	20.014	20.211	20.392	20.562	20.728
25° $\Delta H^\circ$	10.100	10.295	10.490	10.696	10.955	11.279	11.540	11.899	12.231	12.419	12.388	11.991	11.606	11.107
25° $-\Delta S^\circ$	28.955	28.650	28.372	28.090	27.704	27.114	26.765	26.121	25.494	25.474	26.298	28.177	30.039	32.252

TABLE 6—THERMODYNAMIC DATA IN METHANOL-WATER MIXTURE  $\Delta G^\circ$  AND  $\Delta H^\circ$  IN KCAL/MOLE,  $\Delta S^\circ$  IN CAL/MOLE/DEGREE

Wt % Solvent	15	20	25	30	35	40	45	50	55	60	65	70	75	80	85	90
25° $\Delta G^\circ$	24.389	24.397	24.439	24.489	24.527	24.569	24.604	24.634	24.660	24.681	24.695	24.708	24.709	24.717	24.720	24.724
25° $\Delta H^\circ$	15.079	15.893	15.570	15.810	16.073	16.318	16.464	16.568	16.633	16.628	16.576	16.490	16.407	16.387	16.362	16.385
25° $-\Delta S^\circ$	31.057	30.200	29.745	29.091	28.355	27.674	27.135	27.053	26.925	27.012	27.231	27.544	27.848	27.940	28.085	28.187
30° $\Delta G^\circ$	24.381	24.425	24.484	24.540	24.599	24.654	24.699	24.740	24.774	24.802	24.828	24.847	24.855	24.859	24.863	24.867
30° $\Delta H^\circ$	15.069	15.983	15.660	15.800	16.063	16.308	16.444	16.558	16.623	16.618	16.566	16.480	16.397	16.377	16.352	16.325
30° $-\Delta S^\circ$	30.717	29.828	29.438	28.831	28.157	27.532	27.232	26.931	26.848	26.998	27.252	27.559	27.898	27.978	28.075	28.177
40° $\Delta G^\circ$	24.707	24.770	24.824	24.876	24.922	24.958	24.991	25.015	25.037	25.055	25.072	25.084	25.097	25.103	25.109	25.113
40° $\Delta H^\circ$	15.049	15.963	15.640	15.780	16.043	16.288	16.424	16.538	16.603	16.598	16.547	16.461	16.377	16.357	16.332	16.305
40° $-\Delta S^\circ$	30.841	30.039	29.658	29.048	28.352	27.686	27.357	27.070	26.935	27.006	27.226	27.539	27.844	27.928	28.089	28.126
50° $\Delta G^\circ$	25.094	25.131	25.151	25.185	25.215	25.247	25.278	25.307	25.335	25.363	25.388	25.408	25.421	25.431	25.436	25.442
50° $\Delta H^\circ$	15.029	15.844	15.521	15.700	16.023	16.268	16.401	16.518	16.583	16.578	16.527	16.441	16.358	16.337	16.312	16.285
50° $-\Delta S^\circ$	31.145	30.258	29.810	29.164	28.444	27.785	27.460	27.198	27.081	27.186	27.421	27.749	28.047	28.139	28.234	28.337

Fig. 2. Variation of  $k$  with dielectric constant in methanol-water mixtures.

reactions decrease with increasing dielectric constant. Plots of  $\log k_2$  against  $1/D$  give straight lines with negative slopes in the high dielectric range, but deviations from linearity become evident as the dielectric constant decreases. This deviation is probably due to the preferential solvation of the activated complex by water.

**Effect of solvent composition:** In the alkaline hydrolysis, the rate constants are found to decrease with the decrease of water concentration in the medium. The plots of  $\log k_2$  versus  $\log C_w$  give straight lines having a positive slope in water-rich mixtures, followed by a curvature in the regions of solvent-rich mixtures (Fig. 3). The slopes obtained are found to vary slightly with temperature, and have a mean value of 3.15 in the water-rich mixtures. These slopes represent the number of water molecules involved in the formation of the activated complex.

The variation of the rate constant as a function of the concentration of alcohol in the solvent mixture is attributed to many factors<sup>10,11</sup>, concerning the nucleophile and the substrate. It has been reported that when sodium hydroxide is dissolved in ethanol (or methanol) the solution would mainly contain ethoxide (or methoxide) rather than hydroxide ions<sup>12-14</sup> and many puzzling facts have been explained in the light of this assumption<sup>15,16</sup>.





Fig. 8. Variation of  $k_2$  with water concentration in methanol-water mixtures

The extensive investigations done by Brown *et al.*<sup>17</sup> on the steric effects on equilibria were extended to the study of "back strain" effects on the basicity of alkoxide<sup>18</sup>. It was concluded that the basicity of methoxide ion is less than that of hydroxide ions. Since the rate of the reaction is dependent on the stoichiometric concentration of the base anion, it is expected that the rate will decrease due to the decrease in the stoichiometric concentration of the hydroxide ion by the addition of the organic solvent component, according to the equation :



Thus, it would not be surprising in this case that the rate constant decreases continuously by the successive addition of methanol to the reaction medium although the dielectric constant of the medium decreases.

In the acidic hydrolysis, the overall and reverse rate constants are found to increase as the water concentration in reaction medium decreases. However, the forward rate is found to decrease with decreasing water concentration. The plot of  $\log k'_1$  against  $\log C_w$  gives straight lines of mean value unit slope. These slopes represent the number of water molecules involved in the formation of the activated complex. The lines are straight in the range of high concentration of water but deviations from linearity become evident as the water concentration decreases.

It is clear that the decrease of the forward rate constant with the progressive addition of alcohol

is harmonic with the decrease of water concentration and the decrease of the dielectric constant of the medium, also the decrease of acidity of hydrochloric acid (the increase of basicity of water) accompanying the addition of alcohol. This has been attributed<sup>19</sup> to the progressive breakdown of the tetrahedral structure of water. Thus, instead of having the structure  $(\text{H}_2\text{O})_4\text{H}^+$  one may have the species  $(\text{H}_2\text{O})_3\text{H}^+$  besides, since the proton affinity in the open structure  $(\text{H}_2\text{O})_3\text{H}^+$  is less than that in the compact structure, the latter will be holding the proton more firmly and hence in the presence of alcohol, water will be more basic, and thus the net result is a decrease in rate.

**Proposed mechanism :** In the alkaline hydrolysis, the change in the relative concentrations of the hydroxide and alkoxide ions due to the change in the solvent composition is accommodated by the equilibrium represented by equation (5). Accordingly, the overall reaction rate may be represented by equation (6);

$$\text{Rate} = k_2 [\text{Ester}] [\text{Base}] \quad (6)$$

$$\text{where } [\text{Base}] = [\text{OH}] + [\text{RO}] \quad \dots (7)$$

accordingly, equation (6) becomes,

$$\text{Rate} = [\text{Ester}] \{k' [\text{OH}] + k'' [\text{RO}]\} \quad \dots (8)$$

Substituting for OH in equation (8) from equilibrium (5) and rearranging, we obtain,


$$\text{Rate} = [\text{Ester}] [\text{RO}] \left\{ \frac{k' [\text{H}_2\text{O}]}{K [\text{ROH}]} + k'' \right\} \quad \dots (9)$$

therefore,


$$k_{obs} = \frac{k' [\text{H}_2\text{O}]}{K [\text{ROH}]} + k'' \quad (10)$$

where  $k'$  and  $k''$  are the specific rate constants for the reaction catalysed by OH and RO ions, respectively and  $K$  is the equilibrium constant represented by equation (5). The increase of methanol content will cause a decrease in the first term of the right hand side of equation (10) as well as in  $k''$  due to the increase in RO concentration according to equation (5) and hence  $k_{obs}$  will also decrease.


In acidic hydrolysis the forward rate of reaction decreases with increase in the methanol concentration. It is known that<sup>19</sup> the proton is hydrated by four water molecules and it has the structure  $(\text{H}_2\text{O})_4\text{H}^+$  in the cluster shape. In mixed solvents, the net reaction actually taking place is the substitution of water by alcohol in the cluster, for example :



Hence, the following reactions mechanism is proposed.



(Fast pre-equilibrium)



where  $S$  is a solvent molecule and  $T^+$  stands for the solvated transition state in which the solvation is maintained through H-bonding.

Assuming a steady state approximation,

$$K'_1 [\text{Ester}][H_2O^+] = K'_1 [T][S] + K_s [T][H_2O] \\ = [T]\{K'_1[S] + K_s[H_2O]\} \quad (14)$$

$$[T] = \frac{K'_1 [\text{Ester}][H_2O^+]}{K'_1[S] + K_s[H_2O]} \quad (15)$$

The rate of reaction is given by

$$= K_s [T][H_2O] \quad (16)$$

$$= \frac{K_s K'_1 [\text{Ester}][H_2O^+][H_2O]}{K'_1[S] + K_s[H_2O]} \quad (17)$$

$$= \frac{K_s K'_1 [\text{Ester}][H_2O^+]}{K'_1 \frac{[S]}{[H_2O]} + K_s} \quad (18)$$

since  $K_s$  is small in comparison to  $K'_1$ , thus the

$$\text{rate} = \frac{K'_1 K_s}{K'_1} \frac{[\text{Ester}][H_2O^+][H_2O]}{[S]} \quad (19)$$

This mechanism verifies the direct dependence of the rate on the water concentration and the inverse proportionality of the rate with the organic solvent concentration.

#### References

1. E. S. AMIS, "Solvent Effect on Reaction Rate and Mechanism", Academic Press Inc., London, 1966.
2. H. SADEK, M. S. ABU ELAMAYEM and A. S. EL KHOLY, *Suomen Kemistilehti*, 1967, B40, 111.
3. H. SADEK and F. Y. KHALIL, *Z. Physik. Chem.*, 1968, 57, 806, *Z. Physik. Chem.*, 1970, 73, 77.
4. G. OOSTENAU and C. MATRESCU, *Rev. Roum. Chim.*, 1972, 17, 95.
5. G. OOSTENAU, O. LANDAUER and C. MATRESCU, *Rev. Roum. Chim.*, 1969, 14, 845.
6. A. I. VOGEL, "A Text-Book of Practical Organic Chemistry", 3rd Edn., 1971, p. 166.
7. H. SADEK, F. KHALIL and M. HANNA, *Z. Ilysk. Chem.*, 1970, 73, 77.
8. R. F. HUDSON and B. J. SAVILLE, *J. Chem. Soc.*, 1955, 4114.
9. G. AKERLOF, *J. Amer. Chem. Soc.*, 1932, 54, 4125.
10. A. SYRRETTWIKER, Jr., "Solvolytic Displacement Reactions", McGraw-Hill, New York, 1962.
11. J. F. BUNNETT, *Ann. Rev. Phys. Chem.*, 1968, 14, 271.
12. D. F. CALDIN and G. LONG, *J. Chem. Soc.*, 1964, 3737.
13. R. F. CALDIN and J. C. TRICKETT, *Trans. Faraday Soc.*, 1963, 49, 772.
14. J. W. BAKER and A. J. NEALE, *Nature*, 1953, 172, 583.
15. J. F. BUNNETT and R. E. ZAHLER, *Chem. Rev.*, 1961, 48, 389, 340, 348.
16. LANDOLT-BORNSTEIN, "Tabellen", Springer, Berlin, 5th Edn., 1931, p. 1110, Erg. Iib, 1932, p. 1068.
17. H. C. BROWN and R. B. TOHANNSEN, *J. Amer. Chem. Soc.*, 1953, 75, 16, G. S. HAMMOND, "Steric Effects in Organic Chemistry", Newman Wiley, Inc., 1955, p. 454.
18. J. HINE and M. HINE, *J. Amer. Chem. Soc.*, 1952, 74, 5266.
19. C. F. WELLS, *Discuss. Faraday Soc.*, 1965, 39, 132, C. F. WELLS, *Trans. Faraday Soc.*, 1965, 61, 2194, *Trans. Faraday Soc.*, 1966, 62, 2815.

# Thermal Degradation of *p*-Anisic Acid-Formaldehyde Condensation Product

RAMESH PATEL, RAJNI PATEL and KANTI PATEL

Department of Chemistry, Sardar Patel University, Vallabh Vidyanagar-388 120

Manuscript received 20 November 1981, revised 11 June 1982, accepted 21 July 1982

*p*-Anisic acid has been condensed with formaldehyde and the thermal properties of the resin obtained have been studied by differential thermal analysis (DTA), and thermogravimetry (TG). Kinetics parameters for the decomposition reaction have been determined by different methods.

A survey of literature<sup>1-4</sup> reveals that products resulting from the condensation of benzoic acid and substituted benzoic acid with formaldehyde are industrially important. The present paper describes an attempt to study the thermal behaviour of such a condensation product using thermogravimetry (TG) and differential thermal analysis (DTA) techniques.

## Experimental

**Preparation of *p*-anisic acid-formaldehyde condensation product:** *p*-Anisic acid (15.2 g), paraformaldehyde (3.0 g), glacial acetic acid (50 ml) and conc. sulfuric acid (1.0 ml) were mixed and heated at 120° for 2 hr. The reaction mixture was poured into cold distilled water. The solid was dried in vacuum at room temperature.

The Linsesis thermo-balance for thermogravimetry and a micro cell<sup>5</sup> for differential thermal analysis were used for the kinetics of decomposition using 25 or 50 mg of the resin for TG and 3 mg of the resin mixed with aluminium oxide for DTA studies at different heating rates in static air.

## Results and Discussion

The condensation product did not soften at 240°. It started to decompose at higher temperature. The kinetics parameters were obtained using Chatterjee<sup>6</sup> (Table 1a), Anderson-Freeman<sup>7</sup>, Broido<sup>8</sup> and Flynn and Wall<sup>9</sup> methods from the TG-study (Table 1b) and using Reich<sup>10</sup> and Kissinger<sup>11</sup> method from DTA (Table 2). When the samples were heated at different rates (R.H.) for the TG study, the degradation occurred in two stages (Fig. 1). Major decomposition (60%) took place in the second step. The decomposition started at ~245° and ended at ~600°. The activation energy,  $E_a$ , obtained from the TG-study using the Chatterjee method for the first and the second stage of decomposition respectively ranged from ~15 to ~26 Kcal mol<sup>-1</sup>. The decomposition followed a first order kinetics for both steps. The starting temperature of decomposition increased with increasing heating rate

TABLE 1a—KINETICS PARAMETERS (TG)

R.H. (°C min <sup>-1</sup> )	Amount mg	Decomposition temp. °C	ΔT °C	Weight loss %	Chatterjee method $E_a$ (Kcal mol <sup>-1</sup> )	Order of reaction <i>n</i>
1.0	50	245-300		40	20.0	0.8
		300-570	325	60	25.5	1.1
		245-300		40	19.5	0.8
2.5	50	300-570	325	60	25.0	1.1
		260-320		40	18.0	1.0
		320-580	320	60	24.8	1.1
4.0	50	260-320		40	18.3	1.0
		320-580	320	60	25.0	1.1
		270-335		40	16.5	0.9
6.5	50	335-590	320	60	24.0	1.0
		270-335		40	16.8	0.9
		335-590	320	60	23.5	1.0
25	50	290-340		40	15.0	1.3
		340-600	310	60	20.2	1.1
		290-340		40	15.8	1.3
		340-600	310	60	20.5	1.1

TABLE 1b—KINETICS PARAMETERS (TG)

R.H. (°C min <sup>-1</sup> )	Amount mg	Energy of activation $E_a$ (Kcal mol <sup>-1</sup> )			Order of reaction <i>n</i>	
		Broido method	Flynn-Wall method	Anderson-Freeman method	Broido method	Anderson-Freeman method
1.0	50	18.1	33.1	29.5	1.0	0.8
	25	18.9	27.5	31.5	1.0	0.8
2.5	50	16.5		26.3	1.0	0.9
	25	15.9		27.8	1.0	1.0
4.0	50	14.8		25.1	1.0	0.9
	25	14.3		25.5	1.0	1.1
6.5	50	12.9		21.8	1.0	0.8
	25	13.5		22.6	1.0	1.3

TABLE 2—KINETICS PARAMETERS (DTA)

R.H. (°C min <sup>-1</sup> )	Peak temperature (°C)	Energy of activation, $E_a$ (Kcal mol <sup>-1</sup> )		Order of reaction <i>n</i>	
		Reich method	Kissinger method	Reich method	Kissinger method
1.0	480	43.0	37.8	1.3	0.8
2.5	490	38.1		1.2	0.9
4.0	495	35.5		1.0	1.1
6.5	505	30.1		1.2	0.9

(Table 1a). The Anderson-Freeman method gave an  $E_a$  in the range of ~22 to ~32 Kcal mol<sup>-1</sup>.

Fig. 1. TG




Fig. 2 DTA

TG and DTA curves of p-anisic-formaldehyde condensate product at various heating rate (R.H.),  
 1—6.5°/min      2—4.0°/min  
 3—0.5°/min      4—1.0°/min

That obtained from the Broido method varied from ~13 to ~19 Kcal mole<sup>-1</sup>. The Flynn and Wall method gave a slightly higher  $E_a$  value compared to the other methods. In general, the decomposition followed first order kinetics.

The thermal parameters resulting from the DTA study using the method of Reich and Kissinger are given in Table 2. The degradation is exothermic

(Fig. 2). The temperature for the peak maxima varied from ~480 to ~505° for different R. H. The activation energy obtained employing the Reich method varied from ~30 to ~43 Kcal mole<sup>-1</sup> with the decreasing R.H. The Kissinger method yielded an  $E_a$  value of ~38 Kcal mole<sup>-1</sup>. This value represents the overall degradation process. The evaluation of the data by this method involves many thermograms at different heating rates and assumes  $E_a$  to be the same for the degradation of the sample.

The  $E_a$  values from the DTA study are higher in comparison to those obtained from TG study. This could be ascribed to the retardation of decomposition of the polymer sample, which is sandwiched between neutral media in a narrow cavity of the DTA-micro cell, compared to the decomposition in a shallow boat of the TG sample holder.

The values of activation energy resulting from different methods are different, indicating that they depend on the heating rate and the method of calculation; different methods involving different limitations.

#### References

1. F. D. CHATTWAY and L. FARINHOLT, *J. Chem. Soc.*, 1931, 1737.
2. L. H. BOCK, U. S. 2284118 (1926), *Chem. Abs.*, 1942, 36, 62722.
3. S. K. CHATTERJEE, *J. Polym. Sci., A-1*, 1970, 8, 1299.
4. Fuji Photo Film Co. Ltd., Brit. 1 137580 (Cl. G. 03a) (1968), *Chem. Abs.*, 1969, 70, 82991f.
5. D. H. DESAI, C. K. PATEL, K. O. PATEL, and R. D. PATEL, *Stärke*, 1972, 24, 42.
6. P. K. CHATTERJEE, *J. Polym. Sci., A-2*, 1965, 4353.
7. D. A. ANDERSON and E. S. FREEMAN, *J. Polym. Sci.*, 1961, 54, 253h.
8. A. BROIDO, *J. Polym. Sci., A-2*, 1969, 1761.
9. J. H. FLYNN and L. A. WALL, *J. Polym. Sci., B-1*, 1966, 323.
10. J. REICH, *Makromol. Chem.*, 1969, 123, 42.
11. H. E. KISSINGER, *J. Res. Nat. Bur. Stand.*, 1959, 57, 217h.



# Thermal Decomposition of Irradiated Strontium Nitrate

S. M. K. NAIR\*, M. S. KRISHNAN and C. JAMES

Department of Chemistry, University of Calicut, Kerala-673 685

Manuscript received 1 September 1981, revised 27 May 1982, accepted 25 August 1982

The influence of  $\gamma$ -irradiation on the kinetics of thermal decomposition of strontium nitrate has been studied over the temperature range 580-625°. Decomposition occurs in the molten state in four stages, viz., (i) initial gas evolution, (ii) induction, (iii) acceleratory and (iv) decay. The kinetics of stages (i) and (ii) could not be studied with any degree of certainty. The acceleratory and decay stages analyse according to the Prout-Tompkins relationship. Activation energies for these two stages calculated from the Prout-Tompkins constants are 102.9 and 26.3 kcal mole<sup>-1</sup>, respectively. Irradiation increases initial gas evolution and shortens the induction period. It also enhances the rate constants in the acceleratory and decay stages. The activation energy for the acceleratory stage is diminished while that for the decay stage is increased.

THE role of irradiation in the thermal decomposition of inorganic salts has been studied and it has been observed that preirradiation with energetic radiations shortens the period of induction, if any, and enhances the rate constants for both the acceleratory and the decay stages<sup>1-3</sup>. Production of chemical damage, displacements and extended lattice defects are the predominant effects of irradiation on systems containing molecular ions<sup>4-6</sup>. The influences of irradiation on solid decomposition are therefore ascribed to these effects which provide as well as facilitate formation and growth of nucleation centres<sup>7</sup>. In the earlier work<sup>1-3</sup> the relative contribution of crystal defects and chemical damage fragments was not ascertained. It was therefore of interest to irradiate a substance in the solid state generating both crystal defects and chemical damage and to subsequently follow its decomposition in the molten condition when the crystal defects no longer exist but the chemical damage persists. Strontium nitrate has been chosen for this study because the substance decomposes at temperatures well above the melting point and moreover because the kinetics of thermal annealing of irradiation damage in the substance below its melting point has been studied in detail recently<sup>8,9</sup>.

## Experimental

**Material:** AR grade strontium nitrate was used in the form of fine powder. It was dried *in vacuo* over phosphorus pentoxide.

**Irradiation:** Samples sealed in glass ampoules were irradiated with <sup>60</sup>Co  $\gamma$ -rays to different doses between 100 and 400 Mrad at the dose rate of 0.2 Mrad hr<sup>-1</sup>. The irradiated samples were also preserved over phosphorus pentoxide before thermal decomposition studies.

**Decomposition apparatus and procedure:** The decomposition apparatus and procedure employed were the same as those reported earlier<sup>1</sup>. Fluorolube HO oil was used as manometric liquid and Kel-F grease as lubricant for stopcocks. In making a run, about 50 mg of strontium nitrate, accurately weighed, was decomposed in a thermostatically controlled electric furnace at temperature in the range 580-625° ( $\pm 0.5^\circ$ ) and the pressure, *p*, of the evolved gases developed at different time intervals was measured at each temperature with a cathetometer. The final pressure *P*<sub>f</sub> was obtained by heating at 800° till there was no further pressure rise and then cooling to the respective temperature of each run. The data have all been normalized to a mass of 50 mg. From the pressure values the fractional decomposition  $\alpha = p/P_f$  was computed.

**Estimation of damage:** The nitrite produced by irradiation was estimated spectrophotometrically<sup>10</sup>.

**Isothermal annealing:** Irradiated crystals were annealed in air isothermally at  $300 \pm 1^\circ$  in a thermostatic electric hot air oven for different time intervals and the extent of annealing determined. The thermal decomposition behaviour of the partially preannealed samples was studied at 600°.

## Results and Discussion

Data for the dependence of fractional decomposition,  $\alpha$ , for unirradiated strontium nitrate on the heating time, *t*, at different temperatures in the range 580-625° are contained in Fig. 1. The curves are sigmoid in nature, as are characteristic of autocatalytic type reactions, the decomposition proceeding mainly through four stages, viz., (i) initial rapid gas evolution corresponding to  $\alpha = 0$ , (ii) an

\* Author for correspondence.




Fig. 1. Thermal decomposition of unirradiated strontium nitrate at different temperatures.

induction period followed by (iii) acceleratory and (iv) decay stages, respectively.

The initial evolution of gas was extremely rapid and was complete in the first min of heating. It was not possible therefore to determine the kinetics and activation energy of the process. Although the initial reaction in solid decomposition can be ascribed to either physical desorption or to true surface decomposition depending on the activation energy of the process, in decompositions occurring in the molten state, as in the present case, it would only be due to release of occluded air.

The kinetics operating in the induction period also could not be determined with any reasonable degree of certainty. The induction period itself decreases markedly with rise in temperature (Fig. 1).

The  $\alpha$ - $t$  curves have been analysed according to the Prout-Tompkins relationship<sup>10</sup> (Fig. 2)

$$\log [\alpha/(1-\alpha)] = k_{1,2} t + c$$

$k$  has two values corresponding to the acceleratory and the decay stages of the reaction. The Arrhenius




Fig. 2. Prout-Tompkins analysis of the kinetics of thermal decomposition of unirradiated strontium nitrate.

plots for the Prout-Tompkins constants  $k_1$  and  $k_2$  are linear and yield activation energies  $E_1$  and  $E_2$  of 102.9 and 26.3 kcal for the acceleratory and the decay stages, respectively (Table 1).

TABLE 1—ACTIVATION ENERGIES FOR THE DECOMPOSITION OF STRONTIUM NITRATE (kcal mole<sup>-1</sup>)

Sample	$E_1$	$E_2$
Unirradiated	102.9	26.3
100 Mrad	100.1	30.9
400 Mrad	88.9	39.1

The relation between the measure of the chemical damage<sup>8</sup> in terms of %NO<sub>2</sub> induced in strontium nitrate in the present experiments and the dose of  $\gamma$ -irradiation is given in Fig. 3. The chemical damage induced is susceptible to thermal recovery. The fraction annealed<sup>8</sup> at 300° during different time intervals from 0-100 hr in the case of strontium nitrate irradiated to 400 Mrad <sup>60</sup>Co  $\gamma$ -rays are also shown in Fig. 3.




Fig. 3. The dependence of chemical damage in strontium nitrate on the irradiation dose and the time dependence of annealing

Comparison of the  $\alpha$ - $t$  characteristics at 600° for the decomposition of strontium nitrate irradiated to 100, 200, 300 and 400 Mrad <sup>60</sup>Co  $\gamma$ -rays with those for the unirradiated material (Fig. 4) shows that pronounced changes are brought about in the




Fig. 4. Effect of  $\gamma$ -irradiation dose on the thermal decomposition of strontium nitrate at 600°.

nature of the decomposition by irradiation, particularly at the higher  $\gamma$ -ray doses employed. The induction period is shortened and is virtually absent in the material irradiated to 400 Mrad.

Data for the decomposition of strontium nitrate irradiated to 100 and 400 Mrad over a temperature range 580-625° presented in Figs. 5 and 6 are best fitted by the Prout-Tompkins relationship. The activation energies  $E_1$  and  $E_2$  for the Prout-Tompkins constants are given in Table 1. The results,




Fig 5 Thermal decomposition of 100 Mrad  $\gamma$ -irradiated strontium nitrate at different temperatures




Fig 6 Thermal decompositions of 400 Mrad  $\gamma$ -irradiated strontium nitrate at different temperatures.


which are accurate to  $\pm 5\%$ , show that whereas the activation energy in the acceleratory stage ( $E_1$ ) decreases to a small extent on irradiation, that in the decay stage ( $E_2$ ) increases. That the change upon irradiation is small suggests that the same chemical processes govern the decomposition of both the unirradiated and the irradiated salt. The velocity constants  $k_1$  and  $k_2$  are found to increase with the irradiation dose as seen in Table 2.

TABLE 2 - PROUT-TOMPKINS CONSTANTS FOR DIFFERENT  $\gamma$ -IRRADIATION DOSES

Dose, Mrad	Unirad.	100	300	500	600
$k_1(\text{min}^{-1} \times 10^3)$	1.143	1.481	1.667	1.905	2.051
$k_2(\text{min}^{-1} \times 10^3)$	2.50	8.34	4.17	7.69	8.38

It is known that radiation damage, including chemical damage, anneals on gentle heating of the irradiated crystals<sup>9,10</sup>. But preannealing at 300° for a period upto 100 hr does not change significantly the decomposition characteristics of the irradiated material.

Strontium nitrate melts<sup>14</sup> at 570°, but it is only above 600° that the salt decomposes at a measurable rate<sup>15,16</sup>. It may therefore be assumed that the entire extent of the reaction takes place in the liquid phase. The overall decomposition of the substance occurs as follows :



The autocatalytic nature of the decomposition is attributable to the product SrO. The catalysing action of the nitrite ion in the decomposition of nitrates may be envisaged as follows. The  $\text{NO}_2$  produced during irradiation may act as electron donors and attract oxygen atoms from the neighbouring nitrate ions. The resulting nitrate would then decompose spontaneously.

The Prout-Tompkins<sup>10</sup> analysis for solid decomposition was originally derived on the basis of branching reaction nuclei, i.e., molecules of reactant situated at lattice imperfections mainly on the surface of the solid and possessing a low energy of activation for decomposition<sup>10,11</sup>. Acceleration of the decomposition occurs when these branching chain nuclei form reactive planes in the material producing mechanical strain which may result in the actual disruption of the crystals. Eventually, these planes interfere with one another and after the time of maximum velocity the reaction rate is controlled by the number of undecomposed molecules present in the system. The situation in the autocatalytic decomposition of strontium nitrate occurring in the melt is similar to the above mechanism and thus the Prout-Tompkins analysis is applicable. In fact, autocatalytic reactions of the Prout-Tompkins type require that all the solid products shall be in a position to catalyse all reactant molecules equally throughout the entire course of the reaction, which is not feasible in a solid because of the low mobility of the reacting constituents but is entirely valid for decompositions occurring in the liquid state as in the present case.

Considerable work has been done on the influence of irradiation on the thermal decomposition of solid substances<sup>17</sup>. Generally, the effect of irradiation is to decrease the induction period, if any, and increase the velocity constants for both the acceleratory and decay stages<sup>1,2</sup>. These effects arise from the chemical damage fragments produced by irradiation constituting decomposition nuclei by themselves or from decomposition nuclei formed as a result of the Wigner energy released on recombination of interstitials and vacancies during the period of initial slow reaction. Subsequently, the centres of decomposed material grow and decomposition spikes create strain sufficient to ultimately fracture the crystal, thus creating new reactive

surface where after the reaction proceeds in an acceleratory manner. No such mechanism can be envisaged for liquid phase decompositions. The  $\text{NO}_2$  formed under irradiation catalyse the decomposition of strontium nitrate occurring in the melt. In consequence the induction period is shortened and the velocity constants of both the acceleratory and the decay stages enhanced as in the influence of irradiation on solid decomposition.

#### Acknowledgement

The authors are indebted to Professor S. R. Mohanty, Head, Department of Chemistry, Utkal University, and to M/s Western India Plywoods, Baliapattam, Kerala, for carrying out the irradiations. They also gratefully acknowledge gifts of Fluorolube HO oil and Kel-F grease from the respective manufacturers, viz. Hooker Electrochemical Co., Niagra, N. Y., U. S. A. and Minnesota Mining & Manufacturing Co., St. Paul, Minnesota, U. S. A.

#### References

1. M. N. RAY and S. R. MOHANTY, *Indian J. Chem.*, 1968, 6, 819.
2. S. R. MOHANTY and M. N. RAY, *Indian J. Chem.*, 1969, 7, 264.
3. S. R. MOHANTY and S. K. PATNAIK, *Indian J. Chem.*, 1973, 11, 981.
4. S. R. MOHANTY, *J. Sci. Res., B. H. U.*, 1961-62, 12(2), 299.
5. L. T. CHADDERTOW, "Radiation Damage in Crystals", Methuen & Co., London, 1966.
6. E. B. JOHNSON, "The Radiation-Induced Decomposition of Inorganic Molecular Ions", Gordon and Breach Science Publishers, London, 1970.
7. E. G. PROUT, *J. Inorg. Nuclear Chem.*, 1958, 7, 868.
8. M. S. KRISHNAN and S. M. K. NAIR, *J. Indian Chem. Soc.*, 1979, 56, 805.<sup>1</sup>
9. A. JOHN, M. S. KRISHNAN and S. M. K. NAIR, *J. Indian Chem. Soc.*, 1981, 58, 520.
10. E. G. PROUT and F. C. TOMPKINS, *Trans. Faraday Soc.*, 1944, 40, 488.
11. P. W. M. JACOBS and F. C. TOMPKINS, "Chemistry of the Solid State", (Ed.) W. E. GARNER, Butterworths Scientific Publications, London, 1955, p. 184-213.
12. F. SOLYMOSI, *Acta Chem. Acad. Sci. Hung.*, 1968, 57, 11.
13. S. D. BHATTAMISRA and S. R. MOHANTY, *Rad. Effects*, 1976, 29, 41.
14. C. D. HODGMAN (Ed-in-Chief), "Handbook of Chemistry and Physics", Chemical Rubber Publishing Co., Cleveland, 88th Edn., 1966, p. 607.
15. C. DUVAL, *Inorganic Thermogravimetric Analysis*, Elsevier Publishing Co., Amsterdam, 2nd Edn., 1963, p. 489.
16. W. W. WENDLANDT, *Texas J. Sci.*, 1958, 10, 892.
17. D. A. YOUNG, "Decomposition of Solids", Pergamon Press, Oxford, 1966.

# Isomerization of $\beta$ -pinene in the Vapour Phase over Alumina Catalyst : Influence of Partial Pressure of Nitrogen and Pyridine

V. KRISHNASAMY

A. C. College of Technology, Anna University, Madras-600 095

and

P. RATANSAMY

National Chemical Laboratory, Pune-411 008

Manuscript received 14 September 1981, accepted 21 July 1982



The isomerization of  $\beta$ -pinene in the vapour phase over alumina catalyst has been studied in the presence of nitrogen and pyridine. The isomerization proceeds via two parallel paths, one giving bicyclic products such as  $\alpha$ -pinene and camphene and the other giving rise to monocyclic menthadienes such as dipentene, terpinolene,  $\alpha$ -terpinene and  $\gamma$ -terpinene. Nitrogen acts as a diluent while pyridine functions as a diluent and as a poison. As a result, it affects the formation of different products to different extent.

The isomerization of  $\beta$ -pinene over alumina follows a second order kinetics. Based on the experimental facts a tentative mechanism, in terms of carbonium ion intermediates, has been proposed.

$\beta$ -PINENE is a bicyclic mono-olefinic mono-terpene and occurs along with  $\alpha$ -pinene in varying proportions in a majority of essential oils derived from Coniferae<sup>1</sup>. The first quality Indian turpentine from *Pinus longifolia* contains about 10%  $\beta$ -pinene, the rest being  $\alpha$ -pinene (40%) and 3-carene (50%)<sup>2</sup>.

Steinbach *et al*<sup>3</sup> reported the thermal isomerization of  $\beta$ -pinene at 160°, while Sully<sup>4</sup> effected a near quantitative conversion of it into myrcene in the temperature range of 580-750°. Isomerizations of  $\beta$ -pinene over minerals, salts and acids are patented<sup>5</sup>. Verghese<sup>6</sup> investigated the transformations of  $\beta$ -pinene into monocyclic compounds using phosphoric acid.

The present investigation was undertaken to study the influence of nitrogen and hydrogen on the isomerization of  $\beta$ -pinene over alumina, to determine the kinetics of isomerization and to suggest a tentative mechanism for the formation of the various products.

## Experimental

### Preparation of materials :

**Alumina :** Alumina was prepared by hydrolyzing aluminium isopropoxide with distilled water<sup>7</sup>. The precipitated aluminium hydroxide was filtered through a Buchner funnel, washed thoroughly with water, cut into cakes, dried at 120° for 24 hr. The material was activated at 550° in a stream of dry air for 24 hr. The activated material was crushed and ground into powder and sieved. The 40-60 mesh fraction was used for all purposes.

**$\beta$ -Pinene :**  $\beta$ -Pinene (Hercules Powder Co., USA) was further fractionated and the liquid distilling at 165°/760 mm was collected and stored in brown bottles. The purity was established to be better than 99% by gas chromatography.

**Pyridine :** Pyridine (B. D. H. AnalaR) was refluxed over KOH pellets and distilled through an efficient fractionating column with careful exclusion of moisture and the material distilling at 115.5° was collected. The purity was checked by gas chromatographic analysis.

***n*-Butylamine :** *n*-Butylamine used was obtained from B.D.H. It was purified by fractional distillation (b.p. 78°).

**Butter yellow :** This was prepared by diazotization of aniline and coupling with dimethylaniline at 4°. The dye was purified by column chromatography, crystallized and recrystallized from *iso*-octane.

**Nitrogen :** Nitrogen (Indian Oxygen Co.) was purified by passing successively through a silica gel drying tower, a tube containing freshly reduced copper turnings kept at 400°, another silica gel tower and finally through a trap cooled in liquid oxygen.

**Apparatus and procedure :** The reactions were carried out at atmospheric pressure in a fixed bed pyrex flow type reactor, 50 cm long and 1.5 cm internal diameter. The pre-heater was made in the form of a spiral wound uniformly around the reactor covering half of its length, to ensure complete vapourisation of the liquid before entering

the reactor tube. Above the catalyst (5 g) bed pyrex glass beads (4 mm diameter) were placed to a height of 5 cm. The reactor tube was inserted into a furnace, a cylindrical steel tube of internal diameter 4 cm, coated with a thin layer of asbestos, wound uniformly with a nichrome wire and heated electrically to the requisite temperature.

Nitrogen was carefully metered through a precision Hoke valve and its flow rate was measured with a soap film flow meter. Various partial pressures of pyridine were achieved by mixing it with  $\beta$ -pinene in different proportions.

To regenerate and activate the catalyst, it was heated prior to each run for 8 hr in a current of air at 500° until no oxides of carbon were detected in the exit gas. The reactant liquid was fed into the reactor by a constant speed infusion pump. The liquid products collected for the first 15 min of each run (which normally covers 1 hr) were discarded and analysis was made only of the products collected after this time. This was to ensure the attainment of steady state over the catalyst and also to set right any temperature fluctuations.

The liquid products were identified using a Perkin-Elmer infracord spectrophotometer Model-137 and a Perkin-Elmer Vapour Fractometer Model-154 D. They were estimated using a Perkin-Elmer column K, consisting of a two meter column of carbowax on chromosorb. The column temperature for the best resolution within a reasonable time was found to be 115° with hydrogen inlet pressure of 15 psi with TCD detector.

For the identification of different peaks in the chromatogram, retention times for the different compounds were found by introducing authentic samples. For quantitative analysis, synthetic mixtures containing the compounds in varying proportions were introduced and calibration curves relating the concentration with peak heights were drawn. Since the peaks obtained were sharp and symmetrical, peak heights were used as a measure of concentration. All chromatograms for calibration purposes were taken on the same day as a special precaution. Various compounds identified in this investigation are  $\alpha$ -pinene, camphene, dipentene, terpinolene,  $\alpha$ - and  $\gamma$ -terpinenes. Since the concentration of individual menthadienes is too small, they are grouped together as menthadienes.

The surface area (BET), pore volume, and the average pore radius of the catalyst were determined from low temperature adsorption of nitrogen<sup>8</sup>. The pulse flow technique of Eberly<sup>9,10</sup> was used to measure the heat of adsorption of pyridine in the temperature range of 180-250°. The total acidity of the catalyst was determined by *n*-butylamine titration method using butter yellow as indicator. All these values are given in Table 1.

## Results and Discussion

**Influence of particle size :** In order to evaluate the influence of transport processes on the rate of

TABLE 1—SURFACE PROPERTIES OF ALUMINA

Surface properties	Values
Surface area (BET), m <sup>2</sup> /g	180.00
Pore volume, ml/g	0.4580
Average pore radius, $\mu$ A	55.00
Heat of adsorption of pyridine, kcal/mole	17.60
Total acidity, meq/g	0.6450

isomerization of  $\beta$ -pinene, the reaction was studied over three different particle sizes and the results are presented in Table 2. This table illustrates the particle size of the catalyst, their corresponding activities in the isomerization of  $\beta$ -pinene, and the measured values of the effectiveness factor, which is equal to the ratio of the actual reaction rate to the reaction rate with no diffusion limitation, obtained on the smallest catalyst particle size of 60-80 mesh.

TABLE 2—INFLUENCE OF PARTICLE SIZE ON THE OVERALL CONVERSION OF  $\beta$ -PINENE

Particle size	Activity of the catalyst (% mole of $\beta$ -pinene converted)	$\eta$ measured
Pellets, 6 $\times$ 5 mm	66.00	66/78 = 0.85
Powder, 40-60 mesh	76.00	76/78 = 0.96
Powder, 60-80 mesh	78.00	78/78 = 1.00

It has been pointed out by Weisz<sup>11</sup> that diffusion effects are negligible when  $\eta$  exceeds 0.95. The catalyst of particle size 40-60 mesh for which  $\eta$  equals 0.96 is almost completely free from diffusion limitation (Table 2). Since the 60-80 mesh catalyst gave rise to large pressure drop across the catalyst bed causing operational difficulties, all the runs were carried out using 40-60 mesh catalyst.

**Effect of partial pressure :** The overall conversion of  $\beta$ -pinene at various partial pressures of pyridine at 232° is illustrated in Fig. 1. The results obtained in presence of inert diluent nitrogen are also plotted in the same figure for comparison. The distribution of products in the presence of nitrogen and pyridine is given in Figs. 2 and 3 respectively. In the presence of nitrogen, the overall conversion of  $\beta$ -pinene increases with increasing partial pressure of  $\beta$ -pinene upto 0.8 atm (Fig. 1). Above this value the conversion is independent of partial pressure. The catalytically active sites are incomplete filled below 0.8 atm and saturated with respect to  $\beta$ -pinene molecules beyond this value and hence increase of partial pressure of  $\beta$ -pinene has no effect on the rate.

Pyridine suppresses the rate of isomerization more significantly than nitrogen. For instance, the amount of  $\beta$ -pinene undergoing conversion in the absence of pyridine is 80%. At a partial pressure of 0.8 atm, the amounts reacted are reduced to 77% and 52% by nitrogen and pyridine, respectively. Nitrogen acts only as a diluent. Pyridine being a base adsorbs preferentially to  $\beta$ -pinene over both Brönsted and Lewis acid sites with chemical




Fig. 1. Effect of partial pressure of nitrogen and pyridine on the overall conversion of  $\alpha$ -pinene. Temp.  $232^\circ$ , contact time = 0.70 hr.

reactions. It is presumed that it neutralizes the Brönsted acid sites with the formation of pyridinium ion and coordinates with the electron deficient aluminium atom (Lewis acid). As a result of these two reactions, the active sites essential for the isomerization of  $\beta$ -pinene are not available and therefore the conversion falls significantly.

Increase of partial pressure of nitrogen affects the formation of products almost equally (Fig. 2). As the conversion of  $\beta$ -pinene decreases with increasing partial pressure of nitrogen, the concentration of products falls.




Fig. 2. Effect of partial pressure of nitrogen on formation of products. Temp.  $232^\circ$ ; contact time = 0.70 hr.

Pyridine, unlike nitrogen, suppresses the formation of different products differently (Fig. 3). For




Fig. 3. Effect of partial pressure of pyridine on the formation of products. Temp.  $232^\circ$ , contact time = 0.70 hr.

instance, in the absence of pyridine the concentrations of  $\alpha$ -pinene, menthadienes and camphene in the liquid products are 27, 24 and 38%, respectively. Increase in the partial pressure of pyridine from 0 to 0.15 atm decreases these products to 11, 4 and 28%, respectively. Pyridine inhibits the formation of menthadienes to a greater extent than the other two products. From these observations it may be concluded that pyridine inhibits the skeletal isomerization of  $\beta$ -pinene (leading to the formation of menthadienes) more significantly than the double bond isomerization (that gives rise to  $\alpha$ -pinene). Camphene formation involving the bridged ring structure is also less affected.

**Kinetics.** The kinetics of isomerization of  $\beta$ -pinene over alumina has been found to follow a second order kinetics by plotting  $\left(\frac{1}{1-x_2}\right)$  against

contact time,  $W/F_A$ , where  $W$  is the weight of catalyst and  $F_A$  is the flow rate of  $\beta$ -pinene per gram of the catalyst (Fig. 4). The rate constants computed from the slopes of the straight line plots are 187.15 and 547.33 litres mole<sup>-1</sup> hour<sup>-1</sup> at 180 and  $232^\circ$ , respectively. The activation energy was calculated to be 5.1 kcal/mole.

**Mechanism.** It has been well established that alumina surface contains both Brönsted and Lewis acid sites. Several mechanisms have been proposed for the isomerization of olefins over solid acid catalysts. These include the carbonium ion theory of Whitmore<sup>12</sup> and hydrogen switch mechanism of Turkevich and Smith<sup>13</sup>. Pines and Haag<sup>14</sup> have proposed that the isomerization proceeds through an intermediate  $\pi$ -complex of the olefin and a proton from the catalyst. All these mechanisms assume proton addition to the olefinic double bond accompanied by a subsequent or simultaneous proton elimination from another part of the carbonium ion thus formed.





Fig. 4. Second order plots, temp. 180° and 232°.

Carbonium ions on the surface of solid acid catalysts have been identified by Leftin and Hermans<sup>15</sup>. Osaki and Kimura<sup>16</sup> have suggested a proton donor-acceptor mechanism for butene isomerization over solid acid catalysts, either by Brønsted acid sites on the surface of the catalysts or by the carbonium ions formed by the adsorption of olefins on the Lewis sites serving as proton donors.

The isomerization of  $\beta$ -pinene (1) over alumina will be interpreted in terms of carbonium ion intermediates adsorbed on the catalyst surface. It undergoes three types of reactions as outlined in the scheme. Initially the catalyst surface interacts with the double bond of  $\beta$ -pinene molecule resulting in the formation of the carbonium ion (2). This stable tertiary carbonium ion rearranges to a less stable secondary carbonium ion (3) by ring expansion. Carbonium ion (3) undergoes Wagner-Meerwein rearrangement resulting in the formation of camphene (5) through a stable tertiary carbonium ion (4).

Carbonium ion (2) changes into a stable allylic system by elimination of a proton leading to the formation of  $\alpha$ -pinene (6). Carbonium ions (2) and (3) may also rearrange to monocyclic carbonium ion (7) by ring opening. This on subsequent elimination of a proton from the appropriate carbon atom gives dipentene (8) and/or terpinolene (9). The exocyclic double bond in terpinolene further isomerizes to endocyclic positions giving rise to  $\alpha$ -terpinene (10) and  $\gamma$ -terpinene (11).



Scheme

## References

1. J. L. SIMONSEN, 'The Terpenes', Cambridge University Press, 1949, Vol. II, p. 105.
2. J. VERGHESE and L. M. YEDDANAPALLI, *Chem. Age India*, 1959, 103.
3. L. STEINBACH, E. T. THEIMER and B. M. MITZNER, *Canad. J. Chem.*, 1964, 42, 959.
4. B. D. SULLY, *Chem. and Ind.*, 1963, 268.
5. ERNEST GUENTHER, 'Essential Oils', Van Nostrand Co., 1959, Vol. 2.
6. J. VERGHESE, *J. Indian Chem. Soc.*, 1959, 36, 155.
7. H. PINES and W. O. HAAG, *J. Amer. Chem. Soc.*, 1961, 83, 2847.
8. P. H. EMMETT, 'Catalysis', Reinhold Pub. Co., 1954, Vol. I, 81.
9. P. E. EBERLY, JR., *J. Phys. Chem.*, 1961, 65, 1261.
10. P. E. EBERLY, JR., *Trans. Faraday Soc.*, 1961, 57, 289, 1169.
11. P. B. WEISZ and C. D. PRATER, *Adv. Catalysis*, 1954, 6, 143.
12. F. C. WHITMORE, *Chem. Eng. News*, 1948, 26, 668.
13. J. TURKEVICH and R. K. SMITH, *J. Chem. Phys.*, 1948, 16, 466.
14. H. PINES and W. O. HAAG, *J. Amer. Chem. Soc.*, 1960, 82, 2488.
15. H. P. LEFTIN and T. E. HERMANS, *Proc. 3rd Intern. Congr. Catal.*, Amsterdam, 1964, I, 81.
16. A. OSAKI and K. KIMURA, *J. Catal.*, 1964, 3, 395.



# Vibrational Analysis of Glyoxal-h<sub>2</sub>-d<sub>2</sub> and hd

A. NATARAJAN and P. KOLANDAIVELU

Department of Physics, Autonomous Post-graduate Centre, Tiruchirappalli-620 023

and

A. SAVARIANANDAM

Department of Physics, St. Joseph's College, Tiruchirappalli-620 002

A complete vibrational analysis has been made for glyoxal-h<sub>2</sub>, -d<sub>2</sub> and hd. A reasonable set of force constants has been obtained using the general valence force field by the Wilson's F-G matrix method. Using these values other important molecular constants such as mean amplitudes of vibration, generalised mean-square amplitudes of vibration, shrinkage constants, Coriolis coupling constants, centrifugal distortion constants and thermodynamic properties have been computed and presented. A comparison is made between the values obtained in the present investigation and the values available in literature.

TRAMER and co-workers<sup>1</sup> recorded gas phase emission spectra of glyoxal-h<sub>2</sub> and -d<sub>2</sub>, presenting in the case of the deuterated species some weak bands not reported earlier. From the frequency of combination bands of the ir spectrum of these molecules by Cole and Osborne<sup>2</sup>, several bands can be assigned. Cossart-Magos<sup>3</sup> has made the normal coordinate analysis of these molecules on the basis of valence force field. A previous calculation<sup>4</sup> of the fundamental frequencies of glyoxal-h<sub>2</sub> and -d<sub>2</sub> used a modified Urey-Bradley force field. Cossart-Magos<sup>3</sup> has introduced two more interaction constants which were absent in the Urey-Bradley force field. The structural parameters used for the present investigation have been taken from the work of Kuchitsu *et al*<sup>5</sup> conjugating electron diffraction and spectroscopic data. The normal modes of vibration are distributed among the two symmetry species as 5A<sub>g</sub> + 4B<sub>g</sub>. However, potential energy constants have been reinvestigated using the general valence force field. On the basis of GVFF, the mean square amplitudes of vibration, the generalised mean square amplitudes of vibration, shrinkage constants, Coriolis coupling constants, centrifugal distortion constants and thermodynamic quantities have been computed for these molecules.

The molecular configuration, numbering of atoms and the orientation of the Cartesian coordinate axes are shown in Fig. 1.

## Methods of calculation :

The potential energy matrix F has been derived relating to the general valence force field. The kinetic energy matrix G has been obtained by making use of the geometrical parameters according to the relation  $G = BM^{-1}B'$ , where  $M^{-1}$  is a diagonal matrix of the reciprocal masses and B is the transformation matrix from Cartesian displacement coordinates to internal coordinates. By solving the




Fig. 1. The molecular configuration, numbering of atoms and the orientation of the Cartesian coordinate axes of glyoxal-h<sub>2</sub>, -d<sub>2</sub> and hd.

secular equation  $|FG - E\lambda| = 0$ , a reasonable set of force constants has been evaluated.

The symmetrised mean square amplitude matrix  $\mathcal{E}$  has been calculated by L-matrix method<sup>7</sup>. The generalised mean square amplitudes  $\langle(\Delta x)^2\rangle$ ,  $\langle(\Delta y)^2\rangle$  and  $\langle(\Delta z)^2\rangle$  have been computed by deriving relevant expressions following the method of Morino and Hirota<sup>8</sup>. The shrinkage constants have been determined from the perpendicular mean square amplitudes by the method suggested by Morino *et al*<sup>9</sup>.

Applying Jahn's rule<sup>10</sup>, the non-vanishing zeta values are found to be of the type  $\zeta^a$  arising from the coupling  $A_2 \times A_2$  and  $B_2 \times B_2$ . These constants have been estimated using the matrix relation,

$$\zeta^a = L^{-1}C^a\tilde{L}^{-1}$$

where L is the normal coordinate transformation matrix and  $C^a$  ( $a=x, y, z$ ) is the skew symmetric matrix obtained by the vector method of Meal and Polo<sup>11</sup>.

Since the bonds between the atoms in a molecule are not rigid, the interatomic distances will vary

with the speed of rotation giving rise to centrifugal distortion. The centrifugal distortion constants have been computed with the aid of the relations given by Kivelson and Wilson<sup>12</sup> and by Cyvin *et al*<sup>13</sup>.

### Results and Discussion

The internal force constants obtained using GVFF are presented in Table 1 along with the

TABLE 1—THE INTERNAL FORCE CONSTANTS OF GLYOXAL AND ITS ISOTOPES

Designation	(m.dyne/A)	values	values from Ref. (3)
$f_r$		4.890	4.896
$f_d$		12.695	12.668
$f_R$		4.700	4.700
$f_{rr}$		0.010	
$f_{dd}$		-0.175	
$f_{\beta}$		0.588	0.548
$f_{\beta\beta}$		-0.018	
$f_{\alpha}$		0.472	0.551
$f_{\alpha\alpha}$		-0.018	
$f_{d\beta}$		-0.495	
$f_{d\alpha}$		0.809	
$f_R$		-0.094	-0.128
$f_{R\alpha}$		0.260	0.884

values calculated by Cossart-Magos<sup>9</sup> for comparison. The agreement is found to be quite satisfactory. The force constant  $f_r$  is found to be about three times the force constant  $f_d$ . Also the force constant  $f_{\alpha}$  is smaller than  $f_{\beta}$ . It has been shown by Ohwada<sup>14</sup> that the interaction force constant of highly delocalised bond molecule tends to take a large +ve value while that of highly localised bond molecule, a -ve value. Hence the sign of the force constant is a measure of the electron localization or delocalization in a molecule. The values evaluated in the present investigation are made use of for the calculation of other molecular constants.

The mean square amplitude quantities calculated at 300 K are given in Table 2. The generalised mean square amplitudes of vibration and the shrinkage constants are listed in Table 3. The

TABLE 2—MEAN-SQUARE AMPLITUDES OF VIBRATION OF GLYOXAL AND ITS ISOTOPES AT 300 K ( $\text{\AA}^2$ )  $\times 10^{-4}$

Designation	$\text{C}_2\text{H}_2\text{O}_2$	$\text{C}_2\text{D}_2\text{O}_2$	$\text{C}_2\text{HDO}_2$
$\sigma_r$	69.201	54.958	66.610
$\sigma_d$	14.479	21.672	17.687
$\sigma_R$	25.836	29.037	25.617
$\sigma_{\beta}$	111.870	75.878	102.810
$\sigma_{\alpha}$	56.899	67.458	45.076
$\sigma_{rr}$	-1.689	4.987	25.770
$\sigma_{dd}$	0.340	-2.119	-0.520
$\sigma_{\alpha\alpha}$	16.340	22.195	1.770
$\sigma_{\beta\beta}$	-29.818	11.197	32.859
$\sigma_{rd}$	-1.180	-5.500	-7.570
$\sigma_{r\beta}$	4.860	-10.004	-14.148
$\sigma_{Rr}$	-2.170	-4.780	-1.900
$\sigma_{rd}$	2.850	26.540	-3.480
$\sigma_{d\beta}$	7.260	8.760	9.880
$\sigma_{Rd}$	-5.990	-4.980	-5.810
$\sigma_{d\alpha}$	-4.880	-15.880	-2.870
$\sigma_{R\alpha}$	-7.260	-6.830	-4.900
$\sigma_{\beta\alpha}$	-4.100	-25.801	-13.582
$\sigma_{R\beta}$	-9.760	-5.590	-9.080

parallel mean square amplitudes  $\langle(\Delta z)^2\rangle$  compare very well with the mean square amplitude quantities  $\langle\sigma\rangle$ . Since  $f_r \langle f_d, \sigma_r \rangle \sigma_{\alpha}$ . It can also be seen that since  $f_d$  is very large, the mean square amplitude  $\sigma_d$  is found to be very small. Also the natural and practical shrinkages are found to be equal.

The Coriolis coupling coefficients are presented in Table 4. These coefficients facilitate the analysis of vibration-rotation spectra. The following zeta square sum rule is found to be satisfied for the  $A_s \times A_s$  coupling :

$$\zeta_{1,2}^2 + \zeta_{1,3}^2 + \zeta_{1,4}^2 + \zeta_{2,3}^2 = 1$$

The centrifugal distortion constants are listed in Table 5. As there is no experimental data available

TABLE 3—GENERALISED MEAN-SQUARE AMPLITUDES OF VIBRATION ( $\text{\AA}^2$ )  $\times 10^{-4}$  AND SHRINKAGE CONSTANTS (A) OF GLYOXAL AND ITS ISOTOPES

Atom pair	Designation	$\text{C}_2\text{H}_2\text{O}_2$	$\text{C}_2\text{D}_2\text{O}_2$	$\text{C}_2\text{HDO}_2$	Shrinkage constants
C—O	$\langle(\Delta z)^2\rangle$	14.471	21.414	17.720	
	$\langle(\Delta y)^2\rangle$	39.248	66.828	62.437	
	$\langle(\Delta x \Delta y)^2\rangle$	0.616	-9.700	2.683	
C—H	$\langle(\Delta z)^2\rangle$	69.109	54.960	66.010	
	$\langle(\Delta y)^2\rangle$	240.180	140.070	170.668	
	$\langle(\Delta x \Delta y)^2\rangle$	-8.879	-4.936	6.436	
C—C	$\langle(\Delta z)^2\rangle$	25.980	29.037	25.617	
	$\langle(\Delta y)^2\rangle$	107.891	97.638	102.814	
	$\langle(\Delta x \Delta y)^2\rangle$	-0.494	-4.218	-6.194	
C—H	$\langle(\Delta z)^2\rangle$	52.429	26.188	64.899	
	$\langle(\Delta y)^2\rangle$	145.984	90.008	167.778	
	$\langle(\Delta x \Delta y)^2\rangle$	61.702	50.856	110.872	
C...O	$\langle(\Delta z)^2\rangle$	22.672	20.078	23.884	$\delta\text{C}_2\cdots\text{O}_2 = -0.04039 - 0.04565 - 0.05991$
	$\langle(\Delta y)^2\rangle$	85.186	55.467	28.742	$\delta\text{O}_2\cdots\text{H}_2 = -0.03078 - 0.03588 - 0.03616$
	$\langle(\Delta x \Delta y)^2\rangle$	17.854	21.629	11.889	

TABLE 4—CORIOLIS COUPLING CONSTANTS OF GLYOXAL AND ITS ISOTOPES

Designation	Coupling $A_2 \times A_2$		
	$C_2H_2O_2$	$C_2D_2O_2$	$C_2HDO_2$
$\nu_{12}^a$	0.22978	0.26674	0.26178
$\nu_{13}^a$	0.22960	0.74499	0.72619
$\nu_{14}^a$	-0.00470	-0.09529	0.04925
$\nu_{15}^a$	0.28923	0.60438	0.63350
$\nu_{21}^a$	-0.02588	0.80994	-0.17987
$\nu_{22}^a$	0.69161	0.59106	0.83305
$\nu_{23}^a$	-0.25844	-0.84665	-0.31335
$\nu_{24}^a$	0.05024	0.27566	0.11695
$\nu_{25}^a$	0.16566	0.23569	0.58959
$\nu_{26}^a$	0.66714	0.55609	0.48699
Coupling $B_2 \times B_2$			
$\nu_{37}^a$	0.16286	0.21054	0.29526
$\nu_{38}^a$	0.96171	0.97132	0.95413
$\nu_{39}^a$	-0.30432	0.02406	-0.04679
$\nu_{40}^a$	-0.64662	0.02416	-0.04674
$\nu_{41}^a$	-0.98818	-0.97041	-0.97074
$\nu_{42}^a$	0.16473	0.24003	0.29764

for centrifugal distortion constants, on comparison could be attempted.

TABLE 5—CENTRIFUGAL STRETCHING COEFFICIENTS (M Hz) OF GLYOXAL AND ITS ISOTOPES

	$C_2H_2O_2$	$C_2D_2O_2$	$C_2HDO_2$
$D_J$	0.021006	0.018905	0.019379
$D_K$	0.023445	0.021074	0.021620
$D_{JK}$	-0.043856	-0.039030	-0.039978
$R_A$	-0.004201	-0.003795	-0.003930
$R_B$	-0.002038	-0.001355	-0.001559
$\delta_J$	-0.011451	-0.010688	-0.010706

Tables 6-8 give the values of the heat capacity, free energy, heat content, and entropy computed from the observed vibrational frequency data, over

TABLE 6—THERMODYNAMIC FUNCTIONS OF  $C_2H_2O_2$ 

T(K)	S	F	$C_p$	H
100	52.27162	44.28551	8.15252	7.98611
200	58.15651	49.89556	8.92176	8.26095
273	61.01304	52.50782	9.45042	8.51022
300	61.91487	53.31010	9.66482	8.60478
400	64.79958	55.83408	10.44552	8.96550
500	67.21454	57.87513	11.21869	9.33941
600	69.32876	59.61470	11.99254	9.71506
700	71.20927	61.18487	12.54190	10.06840
800	72.92414	62.50314	13.10920	10.42100
900	74.50392	63.75563	13.58370	10.74890
1000	75.96185	64.90725	13.99180	11.05610

TABLE 7—THERMODYNAMIC FUNCTIONS OF  $C_2D_2O_2$ 

T(K)	S	F	$C_p$	H
100	52.52730	44.52850	8.20558	8.00080
200	58.46980	50.18779	9.05582	8.31176
273	61.38438	52.78566	9.72457	8.59868
300	62.31168	53.60936	9.96858	8.70981
400	65.80819	58.18677	10.88919	9.14141
500	67.88095	58.25348	11.75101	9.57747
600	70.02051	60.01901	12.58400	10.00150
700	72.02529	61.61139	13.18480	10.41890
800	73.82231	63.02866	13.74195	10.79580
900	75.46180	64.31400	14.31080	11.14760
1000	76.98467	65.50957	14.88600	11.47510

TABLE 8—THERMODYNAMIC FUNCTIONS OF  $C_2HDO_2$ 

T(K)	S	F	$C_p$	H
100	53.78674	45.79274	8.13181	7.99400
200	59.70412	51.41496	8.99163	8.28915
273	62.53887	54.07270	9.58574	8.55567
300	63.50303	54.84456	9.81822	8.65847
400	66.44200	57.39019	10.66900	9.05401
500	68.91188	59.45503	11.47710	9.45680
600	70.62555	60.99957	12.00542	9.82608
700	72.00495	62.76175	12.87090	10.24820
800	74.78152	64.15462	13.42370	10.60890
900	76.97686	65.42886	13.89590	10.95000
1000	77.89043	66.59188	14.28710	11.28860

the range 100-1000K at intervals of 100K. The calculations are all based on a rigid rotor harmonic oscillator model with no interaction between the vibrational and rotational energies. The quantities evaluated are the combined translational rotational and vibrational contributions.

## References

1. C. COSSART-MAGOS, A. FRAD and TRAMER, *Spectrochim. Acta*, 1978, 34A, 195.
2. A. B. H. COLE and G. A. OSBORN, *Spectrochim. Acta*, 1971, 27A, 2461.
3. C. COSSART-MAGOS, *Spectrochim. Acta*, 1978, 34A, 415.
4. T. FUKUYAMA, K. KUCHITSU and Y. MORINO, *Bull. Chem. Soc. Japan*, 1968, 41, 8019.
5. K. KUCHITSU, T. FUKUYAMA and Y. MORINO, *J. Mol. Struct.*, 1967-68, 1, 463.
6. E. B. WILSON, JR., *J. Chem. Phys.*, 1939, 7, 1047; 1941, 9, 76.
7. S. J. OYVIN, *Acta Polytech. Scand.*, 1960, Ph 6, 279.
8. Y. MORINO and E. HIROTA, *J. Chem. Phys.*, 1955, 23, 737.
9. Y. MORINO, J. NAGAMURA and P. W. MOORE, *J. Chem. Phys.*, 1952, 36, 1050.
10. H. A. JAHN, *Phys. Rev.*, 1939, 56, 680.
11. J. H. MEAL and S. R. POLO, *J. Chem. Phys.*, 1956, 24, 1119.
12. D. KIVELSON and E. B. WILSON, JR., *J. Chem. Phys.*, 1952, 20, 1575; 1953, 21, 1229.
13. S. J. OYVIN, B. N. OYVIN and G. HAGEN, *Z. Naturforsch.*, 1968, 23a, 1649.
14. K. OKAWADA, *Spectrochim. Acta*, 1978, 4, 147.

# Behaviour of Vanadyl Porphyrin Complexes on TLC

(Miss) S. CHAKRABORTY and V. K. BHATIA\*

Indian Institute of Petroleum, Dehra Dun-248 006

Manuscript received 23 April 1980, accepted 7 June 1982

The behaviour of a vanadium porphyrin complexes concentrate obtained from Darius crude oil has been studied on tlc using a variety of solvent combinations and silica gel as the adsorbent. Reasonably good separation has been achieved with three solvent combinations in one dimensional run. Acetonitrile and acetonitrile, benzene, cyclohexane (3 : 5 : 11.3) afforded the best results in a double run.

**E**XTENSIVE work has been done on the behaviour of porphyrins from biological sources on paper and thin layer chromatography. Various solvent systems have been recommended for the separation of porphyrin dicarboxylic acids and methyl esters of porphyrins, chlorins and related compounds on tlc<sup>1-7</sup>. Two dimensional chromatography was successfully carried out by Elder on porphyrin methyl esters which were poorly differentiated in one dimensional systems<sup>8</sup>. Besides silica gel, other adsorbents tried were talc<sup>9-10</sup> and cellulose<sup>11</sup>. Application of paper and thin layer chromatography in the study of porphyrins has been reviewed by Falk<sup>12</sup> and Doss<sup>13</sup>, respectively. Work on the tlc behaviour of metal porphyrin complexes, on the other hand, has been limited to the study of chlorophylls, Cu and Zn complexes of certain porphyrins<sup>4</sup> and synthetic samples of V, Ni and Cu-complexes of tetraphenyl porphins<sup>14</sup>.

As regards petroporphyrins, paper chromatography has been frequently employed for understanding the composition of porphyrin aggregates (demetallated porphyrins)<sup>15,16</sup>. Little information, however, is available about the behaviour of these porphyrins on tlc. Only recently Didyk *et al*<sup>17</sup> have reported the isolation of five porphyrins from La Paz, a cretaceous crude oil, using this technique. To the best of the present authors' knowledge there is no report on the behaviour of petroporphyrins (metal porphyrin complexes from petroleum) on tlc. In course of our work on the isolation of metal porphyrin complexes from Darius crude, a crude from off-shore field in Iran, a study of the behaviour of petroporphyrins concentrate on tlc was necessary for understanding its composition.

## Experimental

**Materials :** The vanadium complex concentrates were prepared from Darius crude (Table 1). This crude is from off-shore field in Iran and has the highest metal content [vanadium : 25 and nickel : 10 ppm (Table 2)] among all the crude oils presently

TABLE 1—CHARACTERISTIC OF DARIUS CRUDE

Density, d <sub>4</sub> <sup>15</sup>	0.852
API gravity	34.49
RVP at 37.8°, Kg/cm <sup>2</sup>	0.84
Kinematic viscosity, cS at 37.8°	5.06
50°	3.98
Pour point, °C	-30
Carbon residue Conradson, %wt	3.8
Sulphur, total %wt	2.4
Characterisation factor	11.9
Water content, %v	Trace
Sediment, %wt	0.0007
Salt content, %wt	0.0008
Tls/1000 bbl	1.0
Ash, %wt	0.006
Calorific value, cal/g	10.800

TABLE 2—METAL CONTENT OF THE CRUDE (ppm)


Vanadium	25.0
Nickel	10.0
Iron	2.0
Copper	0.5
Magnesium	Not detected

being processed in India. The crude, topped upto 140°, was deasphalted using propane. The asphalt, thus obtained, was adsorbed on kieselguhr and preferentially extracted with acetonitrile containing small amounts of benzene affording the initial metal porphyrin complexes concentrate. The vanadium porphyrin complex concentrate (Conc. D<sub>1</sub>; Fig. 1) was prepared by elution chromatography using silica gel. Vanadium porphyrin complexes have characteristic visible spectra<sup>18,19</sup>. This property has been used to determine the presence of these complexes in various fractions. Similar techniques for isolation and characterisation have been used by earlier workers as well<sup>20,21</sup>. Fig. 2 illustrates the visible spectrum of the concentrate prepared.

All the solvents used were of L. R. quality. TLC plates (5×20 cm; thickness 0.3 mm) were prepared by using a slurry of silica gel G (E. Merck) in water and later activated at 110-20° for 1 hr. The oxalic acid coated plates were prepared by

\* Author for correspondence.

# CHAKRABORTY & BHATIA : BEHAVIOUR OF VANADYL PORPHYRIN COMPLEXES ON TLC



\* VPC VANADIUM PORPHYRIN COMPLEXES, NIPC NICKEL PORPHYRIN COMPLEXES, NON MPC NON METAL PORPHYRIN COMPLEXES  
 \* ADSORBENT FOR CHROMATOGRAPH SILICA GEL, A/S IN BRACKET M-MAJOR, S SMALL, T TRACES

Fig. 1. Preparation of VPO concentrate from asphalt.




Fig. 2. V-Prophyrin complexes concentration in benzene. conc. 0.68% (w/v) conc. 0.68% (w/v)

making the slurry in 0.5 N oxalic acid solution and for buffered plates in acetic acid (0.2 M; 48 ml) and sodium acetate (0.2 M; 12 ml) [pH 4.05]. The sample was applied in acetone or benzene solution. The time for saturation of the chamber and development of the plate was 30 and 10 min, respectively. The temperature varied from 25 to 30°. The solvent was allowed to run only 8 cm from the base. The air dried developed plates were sprayed with cyclohexane and viewed under uv light (350 nm). Esterification of the sample (in methanol) was carried out using ethereal solution of diazomethane.

Tables 3 and 4 list the various solvent systems tried, the resolution obtained and the colour and R<sub>f</sub> values of the spots. Fig. 3 shows how the spots appeared on the chromatograms.

## Results and Discussion

Use of solvent combinations already reported in the literature as developing solvents for porphyrins did not yield encouraging results. It was soon




Fig. 3.

TABLE 3—TLC of VOPO CONC.

Solvent system	Composition	TLC Pattern	R <sub>f</sub>	Appearance under uv light
A	Acetone (1)- n-Heptane (1)	4 spots and residue	0.88	Yellow
			0.87	Red
			0.83	Violet
			0.91	Blue
B	Acetonitrile (8)- Benzene (5) Cyclohexane (11.2) in NH <sub>3</sub> -atmosphere	4 spots, 1 tail and residue	0.55	Yellow
			0.68	Pink
			0.80	Brown
			0.92	Blue
C	Acetonitrile	5 spots, 2 tails and a residue (on oxalic acid coated plate)	0.27	Blue
			0.49	Blue
			0.62	Violet
			0.73	Yellow
			0.88	Yellow

TABLE 4—TLC OF ESTERIFIED VOPO CONC.

Solvent system	Composition	TLC pattern	R <sub>f</sub>	Appearance under uv light
D	Acetone (1)- n-Heptane (1)	4 spots, 1 tail and residue	0.46	Yellow
			0.66	Red
			0.80	Violet
			0.91	Blue
E	Acetonitrile (8)- Benzene (9)- Cyclohexane (7.2)	4 spots, 2 tails and residue	0.09	Yellow
			0.36	Yellow
			0.45	Pink
			0.87	Blue
F	Acetonitrile	6 spots, 2 tails and residue	0.21	Blue
			0.37	Yellow
			0.67	Blue
			0.75	Violet
			0.84	Blue
			0.96	Pink
G	Cyclohexane (8)- Ethanol (1)	6 spots, 2 tails and residue	0.24	Blue
			0.54	Violet
			0.62	Yellow
			0.74	Violet
			0.87	Yellow
			0.96	Blue
H	Cyclohexane (3)- Benzene (1)- Ethanol (1)	7 spots, 1 tail and residue	0.84	Yellow
			0.43	Violet
			0.53	Blue
			0.60	Violet
			0.68	Blue
			0.76	Pink
I	(C) Acetonitrile (B) Acetonitrile (8)- Benzene (5)- Cyclohexane (11.3)	7 spots, 3 tails and residue	0.91	Blue
			0.36	Yellow
			0.51	Violet
			0.70	Blue
			0.78	Violet
			0.85	Blue
			0.90	Pink
			0.96	Blue

realized that solvent combinations, degree of saturation of the chamber, amount of the sample spotted and the distance moved by it were the various factors affecting the separation. Moreover, the metal porphyrin complexes lacked the sensitive fluorescence of the uncomplexed pigments and their characteristic colour could be detected at relatively high levels of concentration where the danger of tailing exists. Use was, therefore, made of an indirect method of spying the air dried developed plates with cyclohexane before viewing them under uv light. *Iso*-octane or a dilute solution

of fluoranthene in cyclohexane<sup>18</sup> was found to be equally effective amongst the various solvent combinations attempted for studying the behaviour of the petroporphyrins concentrate on tlc. The best resolution, however, was obtained with acetone-*n*-heptane (1:1), affording four spots and a residue. The solvent was allowed to move a distance of only 8 cm as beyond this distance the spots had a tendency to diffuse. The spots were blue, brown, pink and yellow in colour with R<sub>f</sub> values of 0.91, 0.83, 0.67 and 0.53, respectively. The major problem in the chromatography of the metal porphyrin complexes was their tendency to tail. To overcome this difficulty ammonia atmosphere<sup>22</sup> and oxalic acid coated plates<sup>23</sup> were tried. Acetonitrile-benzene-cyclohexane (3:5:11.3) and acetonitrile gave satisfactory results with the former and the latter systems, respectively but were in no way superior to acetone-*n*-heptane (1:1) (cf. Table 3). Sodium acetate buffered plates<sup>24</sup> did not bring results.

As petroporphyrins are known to occur sometime as carboxylic acids<sup>18</sup>, the esterified sample (diazomethane) was subjected to extensive thin layer chromatography using a number of solvent combinations. Table 2 lists the various solvent systems affording a reasonably good resolution of the esterified petroporphyrin concentrate. Resolution was greatly improved by the use of solvents systems like acetonitrile; cyclohexane-ethanol (2:1) and cyclohexane-benzene-ethanol (2:1:1) resolving the starting material into seven spots, two tails and a residue. The spots were of different colours and nicely distinguishable from one another. The last two solvent combinations probably gave the best resolution but suffered from homogeneity problem at lower temperature.

Another attempt to further improve the resolution, if possible, was made by running the tlc plates in two solvent systems. The sample was run in the first solvent system (8 cm with respect to the solvent), the plate air dried and return the same distance in the second solvent in the same direction. Acetonitrile (in the first run) and acetonitrile-benzene-cyclohexane (3:5:11.3) in the second run resolved the esterified concentrate into seven spots, three tails and a residue. This combination was found to be the best among all the solvent systems tried.

**Conclusion:** The petroporphyrins concentrate prepared from Darius crude could be resolved satisfactorily on silica gel plates using acetone-*n*-heptane (1:1) as the developing solvent. Degree of saturation of the chamber, amount of the sample spotted and the distance moved by it were the various factors affecting the separation. The resolution could be improved considerably by running the esterified sample in acetonitrile; cyclohexane-ethanol (2:1) and cyclohexane-benzene-ethanol (2:1:1) in one dimension. Best results were, however, obtained with acetonitrile and acetonitrile-benzene-cyclohexane (3:5:11.3) in a double run.

## References

1. N. ELFPOLK and G. SIMVERS, *J. Chromatogr.*, 1966, 25, 878.
2. O. B. SCOTT, R. P. LABBE and J. NUTTER, *J. Clinchem.*, 1967, 13, 498; *Chem. Abs.*, 1967, 67, 40876d.
3. M. DOSS, B. ULSHOFFER and B. QUAST, *J. Chromatogr.*, 1969, 41, 386.
4. T. O. CHU and E. J. CHU, *J. Chromatogr.*, 1968, 21, 46.
5. D. SCHMIDT, W. STICH and G. DECH, *Aerall. Lab.*, 1972, 18, 386; *Chem. Abs.*, 1972, 78, 107818k.
6. M. KALAB, M. JIRSA and V. KORDAC, *Čas. Lek. Česk.*, 1976, 115, 894; *Chem. Abs.*, 1976, 85, 589816.
7. H. MUNDSCHEK, *J. Chromatogr.*, 1966, 25, 880.
8. G. H. ELDER, *J. Chromatogr.*, 1971, 59, 284.
9. T. K. WITB, *J. Chromatogr.*, 1969, 45, 389.
10. T. K. WITB, *Clin. Biochem.*, 1967, 1, 80; *Chem. Abs.*, 1968, 69, 93504a.
11. O. S. RUSSELL, *J. Chromatogr.*, 1966, 25, 163.
12. J. E. FALK, *J. Chromatogr.*, 1961, 5, 277.
13. M. DOSS, *Progr. Thin Layer Chromatogr. Relat. Methods*, 1972, 3, 145, (Ed.) A. NIEDERWIESER, Ann Arbor Sci Publ., Ann Arbor, Mich., *Chem. Abs.*, 1972, 77, 44912t.
14. M. SATO and T. KWAN, *Chem. Pharm. Bull.*, 1972, 20, 840; *Chem. Abs.*, 1972, 77, 34462.
15. M. BLUMER, *Anal. Chem.*, 1956, 28, 1640.
16. H. N. DUNNING and J. K. CARLTON, *Anal. Chem.*, 1956, 28, 1862.
17. B. DIDYK, Y. I. A. ATTURKI, O. T. PILLINGER and G. EOLWNTON, *Chem. Geol.*, 1974, 15, 193.
18. H. N. DUNNING in "Organic Geochemistry", (Ed.) I. A. BERGER, Pergamon Press, London, 1968, p. 867.
19. P. GLEBOVSKAYA and V. V. VOLKENSHTEN, *Zhurobshen Khim.*, 1948, 18, 1440; *Chem. Abs.*, 1950, 44, 2309a.
20. V. BERTI, A. M. ILARDI and M. NUZZI, *World Petrol Cong. Proc.*, Seventh Congr., Mexico, 1967, Vol. IX, p. 149.
21. J. R. MORANDI and H. B. JENSEN, *J. Chem. Eng. Data*, 1966, 11, 81.
22. E. A. MITRYUKOV, *J. Chromatogr.*, 1952, 9, 314.
23. B. STAHL, *Arch. Pharm.*, 1960, 293, 581; cf. J. M. BOBBITT, "Thin Layer Chromatography", Reinhold Publishing Corporation, New York, 1963, p. 20.
24. H. K. MANGOLD, *J. Amer. Oil Chemists Soc.*, 1961, 38, 708, 91.

# Kinetics of Chromic Acid Oxidation of Phenacyl Bromides ( $\omega$ -Bromoacetophenones)

R. C. MOHAPATRA and N. C. KHANDUAL\*

Department of Chemistry, Khallikote College, Berhampur-760 001;

Manuscript received 18 December 1979, revised 18 April 1982, accepted 26 August 1982

The kinetics of the oxidation of phenacyl bromide ( $\omega$ -bromoacetophenone) and several substituted phenacyl bromides by chromic acid have been investigated in 90% acetic acid (v/v). The reaction rate is first order with respect to the [oxidant] as well as to the [substrate]. A decrease in the proportion of acetic acid in the reaction mixture decreases the rate. The reaction rate decreases in the presence of added Mn(II) ions. The presence of complexing agents like succinic acid and piperidine also decrease the rate. The value of  $\rho^+$  has been found to be  $-0.20$  from a linear correlation of the rate constants with Brown's  $\sigma^+$  parameter. The data conform to the mechanism involving an enol intermediate.


CHROMIC acid is one of the most versatile oxidising agents<sup>1</sup>. Kinetics of oxidation of many alicyclic and aliphatic ketones by chromic acid have been reported by a number of workers<sup>2-5</sup>. Similar studies on  $\alpha$ -haloketones are not found in the literature. This prompted us to study the kinetics of oxidation of phenacyl bromide and substituted phenacyl bromides to obtain more informations on the mechanism of oxidation.

## Experimental

**Materials and method:** The substrates employed were unsubstituted, *p*-methoxy, *p*-methyl, *m*-nitro and *p*-nitro phenacyl bromide. These were prepared and purified by the methods available in literature<sup>6-7</sup>. Perchloric acid (60% Baker, AnalaR) was used as a source of  $H^+$ . Pure acetic acid (b.p. 118°), free from oxidisable impurities, was obtained by warming acetic acid (AnalaR, 40 g) and acetic anhydride (AnalaR, 160 ml) slowly to just below the reflux temperature for 0.5 hr, the mixture was then heated under reflux for 0.5 hr and then distilled through a fractionating column containing glass helices. The ionic strength was maintained by adding sodium perchlorate (AnalaR, B.D.H.). Triple distilled water was used for dilution.

**Kinetic measurements:** Rate measurements were carried out at constant temperature ( $\pm 0.1^\circ$ ). The solvent used was 90% aqueous acetic acid (v/v) containing 0.2M  $HClO_4$ . The reaction was followed by withdrawing aliquots of the reaction mixture at known intervals of time, quenching the reaction by adding slight excess of ferrous ammonium sulphate and titrating the residual Fe(II) against standard  $K_2Cr_2O_7$  solution using barium diphenyl sulphate as an indicator. Diffused light did not affect the rate constants. The rate constants were computed with an accuracy of 1-2% in duplicate runs.

**Stoichiometry:** The stoichiometry of the reaction was determined by allowing reaction mixtures containing excess of chromic acid to stand for 3 to 4 days at 30° until there was no change of Cr(VI) concentration. The unreacted oxidant was then estimated by the usual procedure. The stoichiometry is represented by equation (1).



The tlc pure product isolated was characterised as phenyl glyoxal<sup>8</sup>, yellow liquid, b.p. 96°.

**Rate law:** The reaction is first order with respect to the [phenacyl bromide] as well as the [oxidant] (Table 1). The rate of the reaction increases with the increase in  $[HClO_4]$  (Table 2). Under the condition of constant ionic strength the first order rate constant ( $k_1$ ) is proportional to  $[H^+]$ .

TABLE 1—DEPENDENCE OF RATE ON  $[CrO_3]$  AND  $[m$ -NITRO PHENACYL BROMIDE]

$[HClO_4] = 0.2 M$ ,  $\mu = 1 M$ , Solvent = 90% Acetic acid (v/v), Temp.  $-35^\circ$

$[m$ -Nitrophenacyl bromide] $\times 10^3 M$	$[CrO_3] \times 10^4 M$	$k_1 \times 10^4 \text{ sec}^{-1}$	$k_1 \times 10^4 \text{ mole}^{-1} \text{ sec}^{-1}$
			$[m$ -Nitrophenacyl bromide]
10.0	1.0	3.17	
10.0	2.0	4.50	
10.0	4.0	5.80	
10.0	5.0	7.90	
10.0	10.0	8.82	
10.0	15.0	8.40	
10.0	20.0	8.65	
10.0	25.0	8.70	
10.0	30.0	8.75	
5.0	10.0	4.30	8.40
10.0	10.0	8.82	8.82
20.0	10.0	16.90	8.45
30.0	10.0	24.80	8.36
40.0	10.0	33.10	8.27
50.0	10.0	42.20	8.27

\* Present address: Department of Chemistry, Ravenshaw College, Cuttack-753 003.



TABLE 2—DEPENDENCE OF RATE ON [ACID]

[CrO<sub>3</sub>]=0.001 M; [m-Nitro phenacyl bromide]=0.01 M, Solvent=90% Acetic acid (v/v),  $\mu=1$  M, Temp.=35°

[HClO <sub>4</sub> ]M	$k_1 \times 10^3 \text{ sec}^{-1}$	$k_1/[H^+] \times 10^4$
0.1	4.25	0.425
0.2	8.92	0.441
0.3	13.03	0.434
0.4	17.28	0.433
0.5	21.46	0.430
0.6	25.90	0.447
0.7	28.45	0.441
0.8	33.76	0.442
0.9	40.80	0.447

**Solvent effect:** The reaction was studied in various acetic acid-water binary mixtures. An increase in the proportion of acetic acid increases the rate of oxidation (Table 3). This is probably due to the lowering of dielectric constant (D) of the medium<sup>9</sup>, which favours reaction involving protonation. In acetic acid medium, H<sub>2</sub>CrO<sub>4</sub> exists as acetochromic acid, CH<sub>3</sub>COOCrO<sub>3</sub>H, or its protonated form CH<sub>3</sub>COOCrO<sub>3</sub>H<sub>2</sub><sup>+</sup> which are assumed to be strong acids and much more powerful oxidising agents than chromic acid<sup>10-12</sup>. The plot of log  $k_1$  versus 1/D is linear as expected for ion-dipole reactions. The same argument has also been advanced by Venkatasubramanian<sup>13</sup>. Further, the extent of enolization of the ketone is enhanced by increasing the proportion of acetic acid and hence the rate increases.

**Effect of added Mn(II).** The reaction rate decreases in the presence of added Mn(II) ions (Table 4). The same observation has been noted

TABLE 3—EFFECT OF SOLVENT COMPOSITION ON THE RATE OF CHROMIC ACID OXIDATION OF PHENACYL BROMIDE

[CrO<sub>3</sub>]=0.001 M, [m-Nitro phenacyl bromide]=0.01 M, [HClO<sub>4</sub>]=0.4 M,  $\mu=1$  M, Temp.=35°

% HOAc (v/v)	$k_1 \times 10^3 \text{ sec}^{-1}$
70	4.79
75	5.02
80	6.90
85	8.05
90	17.28
95	20.72

TABLE 4—EFFECT OF Mn(II) IONS ON THE RATE OF OXIDATION OF PHENACYL BROMIDE

[CrO<sub>3</sub>]=0.001 M, [m-Nitro phenacyl bromide]=0.01 M, [HClO<sub>4</sub>]=0.4 M, Solvent=90% Acetic acid (v/v), Temp.=35°

[Mn(II)] $\times 10^3$ M	$k_1 \times 10^3 \text{ sec}^{-1}$
—	17.28
10	3.50
15	2.25
20	1.80
25	0.90

by Westheimer and Watanabe<sup>14</sup> for isopropanol oxidation. This is probably due to the Mn(II) catalysed disproportionation of intermediate valence states of [Cr(IV)]. It may be reasonable

to propose the following reaction in the presence of Mn(II) ions.



**Effect of complexing agent on reaction rate:** The rate of the reaction decreases in the presence of certain dibasic acids and organic bases (Table 5). This may be due to complex forming ability of intermediate stages of the oxidant.

**Effect of substituents on rate:** The effect of substituents on the benzene ring of phenacyl bromide shows that electron donating groups enhance the reaction rate while electron withdrawing groups retard it (Table 6). The order of reactivity of different substituents is  $p\text{-OCH}_3 > p\text{-CH}_3 > \text{H} > m\text{-NO}_2 > p\text{-NO}_2$ . The log  $k_1$  values for different substituted phenacyl bromides have been plotted against Brown's  $\sigma^+$  values<sup>15</sup>. The value of  $\rho^+$  was computed to be -0.20.

TABLE 5—EFFECT OF ADDED COMPLEXING AGENTS ON THE REACTION RATE

[CrO<sub>3</sub>]=0.001 M, [m-Nitro phenacyl bromide]=0.01 M, [HClO<sub>4</sub>]=0.4 M, Solvent=90% Acetic acid (v/v), [Complexing agent]=0.01 M, Temp. 35°

Complexing agent	$k_1 \times 10^3 \text{ sec}^{-1}$
NH	17.28
Succinic acid	5.60
Adipic acid	4.50
Piperidine	5.05
Pyridine	4.02
Diethylamine	3.30

TABLE 6—REACTION RATES AND ARRHENIUS PARAMETERS FOR CHROMIC ACID OXIDATION OF SUBSTITUTED PHENACYL BROMIDES

[CrO<sub>3</sub>]=0.001 M, [Substrate]=0.01 M, [HClO<sub>4</sub>]=0.2 M,  $\mu=1$  M, Solvent=90% Acetic acid (v/v)

Substituent	$k \times 10^5 \text{ sec}^{-1}$ at °C			E	$-\Delta S^\ddagger$
	30	35	40	k.cal/mole	e.u.
p-OCH <sub>3</sub>	9.21	13.05	17.25	11.25	40.89
p-CH <sub>3</sub>	8.20	12.04	16.15	12.46	38.08
H	7.60	10.80	13.55	13.12	36.03
m-nitro	5.44	8.82	12.80	15.36	33.59
p-nitro	4.44	7.75	10.85	17.06	24.04

**Isokinetic relationship.** A linear relationship between the entropy of activation ( $\Delta S^\ddagger$ ) and the enthalpy of activation ( $\Delta H^\ddagger$ ) has been observed for the oxidation<sup>16</sup>. The data can be fitted in the equation,

$$\Delta H^\ddagger = \Delta H_0^\ddagger + \beta \Delta S^\ddagger$$

$\Delta H_0^\ddagger$  has the value 25.5 kcal mole<sup>-1</sup> and  $\beta$ , the isokinetic temperature, is 381K for the reaction. The linear relationship shown by the majority of phenacyl bromides indicates that apparently the same mechanism prevails in all cases<sup>17</sup>.

## Discussion

The aliphatic haloketones undergo hydrolysis in acid and alkaline medium. But phenacyl bromides are found to resist hydrolysis even upto an acid concentration of 0.9 M HClO<sub>4</sub>.

The oxidation of phenacyl bromides by  $H_2CrO_4$  shows that, (i) the oxidation rate is first order with respect to the haloketone, (ii) the rate at which  $Cr(VI)$  disappears also follows first order rate laws, (iii) the reaction is acid catalysed and (iv) the value of  $\rho^+$  is negative showing that electron donating groups enhance the reaction rate. The value of  $\Delta S^\ddagger$  is negative indicating a rigid transition state.

The formation of free radicals was not indicated in the present investigation since polymerization with acrylonitrile or reduction of  $HgCl_2$  could not be observed. Therefore the oxidation reaction is believed to proceed through an ionic intermediate.

As pointed out by Best *et al.*<sup>2</sup>, the rate of chromic acid oxidation of cyclohexanone by chromic acid is slower than its rate of enolization at the same acidity. Thus one cannot say whether the ketone molecule or its enol form is being attacked by the chromic acid. However, Rocek and Riche<sup>3</sup> have advanced different views which contradict the views suggested by Best *et al.*<sup>2</sup>. The latter workers observed that the rate of oxidation is close to the enolization as determined by bromination measurement, demonstrating that the oxidation of ketones proceeds through the enol intermediate. Nayak *et al.*<sup>1a</sup> have studied the bromination of a large number of acetophenones. The present experimental condition is very much close to the bromination experiment. Various substituents change the rate in the same direction in both the reactions as evidenced by the magnitude and size of the Hammett  $\rho$  value. Thus it seems likely that the oxidation proceeds through an enol intermediate. This receives support from the DMSO oxidation of phenacyl bromide<sup>1b</sup> and  $SeO_2$  oxidation of a number of ketones<sup>20</sup>.

### Acknowledgement

The authors are grateful to the University Grants Commission, New Delhi for financial support.

### References

1. K. B. WIBERG, "Oxidation in Organic Chemistry", Academic Press, Inc., New York, 1966, p. 69.
2. P. A. BEST, J. S. LITTLE and W. A. WATERS, *J. Amer. Chem. Soc.*, 1962, 84, 822.
3. J. ROCEK and A. RICHE, *J. Amer. Chem. Soc.*, 1967, 89, 6691.
4. S. K. TONDON, K. K. BANARJEE and G. V. BAKORE, *Indian J. Chem.*, 1971, 9, 877.
5. (a) N. C. KHANDUAL, K. K. SATPATRY and P. L. NAYAK, *Indian J. Chem.*, 1973, 11, 770.  
(b) N. C. KHANDUAL, K. K. SATPATRY and P. L. NAYAK, *J. C. S., Perkin Trans., II*, 1974, 828.
6. P. A. RATHER and P. REID, *J. Amer. Chem. Soc.*, 1919, 41, 75.
7. P. L. NAYAK, Ph.D. Thesis, Utkal University, 1967.
8. E. H. RODD, "Chemistry of Carbon Compounds", Elsevier Publishing Co., Amsterdam, 1966.
9. M. COHEN and F. H. WESTHEIMER, *J. Amer. Chem. Soc.*, 1953, 75, 4887.
10. Q. T. E. GRAHAM and F. H. WESTHEIMER, *J. Amer. Chem. Soc.*, 1958, 80, 8080.
11. K. B. WIBERG and H. SCHAFER, *J. Amer. Chem. Soc.*, 1969, 91, 927.
12. J. ROCEK, *Colln. Czech Chem. Commun.*, 1957, 22, 1509.
13. S. SUNDARAN and N. VENKATASUBRAMANIAN, *Indian J. Chem.*, 1971, 9, 1102.
14. F. H. WESTHEIMER and W. WATANABE, *J. Chem. Phys.*, 1949, 17, 61.
15. H. O. BROWN and Y. OKAMATU, *J. Amer. Chem. Soc.*, 1958, 80, 4979.
16. J. E. LEFFLER and E. GRUNWALD, "Rates and Equilibria of Organic Reactions", John Wiley and Sons, Inc., New York, p. 815.
17. K. BOWDEN, N. B. CHAPMAN and J. SHURTER, *J. Chem. Soc.*, 1964, 337.
18. L. N. PATNAIK, P. L. NAYAK and M. K. ROUT, *J. Indian Chem. Soc.*, 1967, 44, 668.
19. N. KORNBLUM, W. J. POWERS, J. G. ANDERSON and W. JONES, *J. Amer. Chem. Soc.*, 1957, 79, 6562.
20. J. CORRY and J. P. SAHAFER, *J. Amer. Chem. Soc.*, 1960, 82, 918.

# Synthesis of Some 3-Arylimino-5-(N-Methylanilino)-1,2,4- $\Delta^4$ -Dithiazolines

MOHAMMAD RAMZAN ALI and V. K. VERMA\*

Applied Chemistry Section, School of Applied Sciences, Institute of Technology, Banaras Hindu University, Varanasi-221 006

Manuscript received 30 November 1981, revised 27 May 1982, accepted 25 August 1982


Some new 3-arylimino-5-(N-methylanilino)-1,2,4- $\Delta^4$ -dithiazolines have been synthesised by the oxidative debenylation and cyclisation of the corresponding 5-aryl-1,1-methylphenyl-2-S-benzyliso-4-thiobiurets. The characterisation of these compounds have been achieved by the direct oxidation of the corresponding 2,4-dithiobiurets and also by infrared spectra.

**O**XIDATION of 2,4-dithiobiurets has been a well studied method<sup>1-5</sup> for the synthesis of the related 1,2,4-dithiazolines/dithiazolidines. In the recent past we reported that substituted 1,2,4-dithiazolines/dithiazolidines could also be synthesised by the oxidative dealkylation of the related isodithiobiurets<sup>6-10</sup>. In the light of these observations, it was considered of interest to explore the potentiality of oxidative debenylation and cyclisation reaction for the synthesis of certain hitherto unreported 3-arylimino-5-(N-methylanilino)-1,2,4- $\Delta^4$ -dithiazolines.

The present communication describes the synthesis of certain new 3-arylimino-5-(N-methylanilino)-1,2,4- $\Delta^4$ -dithiazolines by the oxidative debenylation and simultaneous ring closure of the corresponding 5-aryl-1,1-methylphenyl-2-S-benzyliso-4-thiobiurets.

N-Methylphenyl thiourea was benzylated with benzyl chloride. The expected 1,1-methylphenyl-2-S-benzylisothiourea free base (I) thus obtained was condensed with the appropriate arylisothiocyanate to yield the desired 5-aryl-1,1-methylphenyl-2-S-benzyliso-4-thiobiurets (II). These isodithiobiurets (II), on oxidation with molecular bromine in chloroform, gave the related 3-arylimino-5-(N-methylanilino)-1,2,4- $\Delta^4$ -dithiazolines (IV). These have also been obtained by the direct oxidation of the related 5-aryl-1,1-methylphenyl-2,4-dithiobiurets (III). Compounds (III) were obtained by the reductive debenylation of the corresponding isodithiobiurets (II) with dry hydrogen sulphide in pyridine-triethylamine medium and also by the reduction of the related dithiazolines (IV) with ethanolic ammoniacal hydrogen sulphide.

In all the cases the structure of the compounds (III) and (IV) were confirmed by their synthesis through alternative route as described above and also by mixed melting point, elemental analysis and identical ir spectra. The scheme of the reaction can be represented as follows.



## Experimental

Melting points of the compounds are recorded on Kofler hot stage apparatus and are uncorrected. Infrared spectra were recorded in Nujol on Perkin-Elmer spectrophotometer, Model-720. N-Methylphenyl thiourea was prepared according to known procedure<sup>11</sup> and its S-benzyl derivative (I) was obtained by benzylation<sup>12</sup> with benzyl chloride.

**5-Aryl-1,1-methylphenyl-2-S-benzyliso-4-thiobiurets (II):** The details of a typical experiment is as follows. The 1,1-methylphenyl-2-S-benzylisothiourea, m.p. 70° (5.0 g; 0.019 mole) was refluxed with *m*-methoxyphenyl isothiocyanate (3.21 g; 0.019 mole) in dry benzene for 4 hr on a water bath. The excess of benzene was evaporated and the semi-solid product, on washing with petroleum ether and treatment with a little ethanol, afforded 5-*m*-methoxyphenyl-1,1-methylphenyl-2-S-benzyliso-4-thiobiuret as a crystalline product. It was recrystallised from ethanol, m.p. 90°, yield 6.16 g (75%). The results of such experiments are summarised in Table 1.

TABLE 1—PHYSICAL DATA OF 5-ARYL-1,1-METHYLPHENYL-2-S-BENZYLISO-4-THIOBIURETS II (a-f)

Com- pound	Molecular formula	m.p. °C	Yield %	Analysis %			
				Calcd.		Found	
				C	H	C	H
IIa	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> OS	188	75	65.55	5.46	65.90	5.50
IIb	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	127	74	68.14	5.67	68.30	5.71
IIc	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> OS	90	75	65.55	5.46	65.80	5.53
IId	C <sub>18</sub> H <sub>17</sub> ClN <sub>2</sub> S	118	69	62.04	4.70	62.38	4.91
IIe	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	122	64	68.14	5.67	68.21	5.71
IIf	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	88	50	68.14	5.67	68.20	5.73

Typical IR frequencies (cm<sup>-1</sup>) of 5-m-methoxyphenyl-1,1-methylphenyl-2-S-benzyliso-4-thiobiuret, 3300cm<sup>-1</sup> NH stretching (lit. 3400-3100)<sup>13</sup>, 1125m, 1140vs, 1200w N-O(=S)-N grouping (lit. 1100-1200)<sup>14a</sup>, 1600w N-C=N grouping (lit. 1686-1582)<sup>14b</sup>.

### 3-Arylimino-5-(N-methylanilino)-1,2,4-Δ<sup>4</sup>-dithiazolines (IV) :

(i) *Oxidative debenzoylation of 5-aryl-1,1-methylphenyl-2-S-benzyliso-4-thiobiurets* : The experimental details of a typical experiment follows : The 5-m-methoxyphenyl-1,1-methylphenyl-2-S-benzyliso-4-thiobiuret (2 g), made into a paste with chloroform, was treated with molecular bromine with vigorous stirring until the colour of bromine persisted. The reaction mixture warmed up appreciably evolving lachrymatory fumes of benzyl bromide. After 1 hr the semi-solid product was first washed with ether and the addition of a little ethanol thereafter gave the hydrobromide of the oxidation product which separated out as a crystalline product. On treatment with aqueous ammonia 3-m-methoxyphenylimino-5-(N-methylanilino)-1,2,4-Δ<sup>4</sup>-dithiazoline was obtained, which was thoroughly washed with ether and crystallised from ethanol, m.p. 168°, yield 1.06 g (68%).

The dithiazoline bases so obtained showed no depression in m.p. when mixed with authentic samples obtained by the oxidation of the corresponding 1,1,5-trisubstituted-2,4-dithiobiurets (Table 2).

TABLE 2—PHYSICAL DATA OF 3-ARYLIMINO-5-(N-METHYLANILINO)-1,2,4-Δ<sup>4</sup>-DITHIAZOLINES IV (a-f)

Com- pound	Molecular formula	m.p. °C	Yield %	Analysis %			
				Calcd.		Found	
				C	H	C	H
IVa	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> OS	110	78	58.35	4.55	58.61	4.49
IVb	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	94	71	61.84	4.79	61.54	4.83
IVc	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> OS	168	68	58.35	4.55	58.63	4.56
IVd	C <sub>18</sub> H <sub>17</sub> ClN <sub>2</sub> S	85	70	53.97	3.59	54.02	3.71
IVe	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	110	72	61.84	4.79	61.79	4.82
IVf	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	125	50	61.84	4.79	61.80	4.79

Typical IR frequencies (cm<sup>-1</sup>) of 3-m-methoxyphenylimino-5-(N-methylanilino)-1,2,4-Δ<sup>4</sup>-dithiazoline, C=N 1625<sup>15</sup>, ring S-S-linkage 488<sup>16</sup>, the absence of IR band for N-H is remarkable.

(ii) *Oxidation of 5-aryl-1,1-methylphenyl-2,4-dithiobiurets (III) with bromine in ethanol* : 5-m-Methoxyphenyl-1,1-methylphenyl-2,4-dithiobiuret (2 g), listed in Table 3, was oxidised with bromine in ethanolic solution. The excess of ethanol was

evaporated and the resultant mass washed with ether when hydrobromide of the 3-m-methoxyphenylimino-5-(N-methylanilino)-1,2,4-Δ<sup>4</sup>-dithiazoline was obtained. The free base was obtained by the treatment of the hydrobromide with aqueous ammonia and it was crystallised from ethanol, m.p. 168°, yield 1.5 (80%) (Table 2).

### 5-Aryl-1,1-methylphenyl-2,4-dithiobiurets (III) :

(i) *Reductive debenzoylation of 5-aryl-1,1-methylphenyl-2-S-benzyliso-4-thiobiurets (II) with hydrogen sulphide in pyridine-triethylamine medium* : Through a solution of 5-m-methoxyphenyl-1,1-methylphenyl-2-S-benzyliso-4-thiobiuret (5 g) in pyridine (50 ml) and triethylamine (6 ml), a stream of dry hydrogen sulphide was passed for 4 hr. The reddish brown viscous liquid so obtained was poured over crushed ice, acidified with dilute hydrochloric acid and diluted with water. On standing for about 1 hr, 5-m-methoxyphenyl-1,1-methylphenyl-2,4-dithiobiuret was obtained as a granular solid. Purification was effected by dissolving the product in dilute aqueous sodium hydroxide solution and reprecipitation with hydrochloric acid followed by crystallisation from ethanol, m.p. 132°, yield 61% (Table 3).

TABLE 3—PHYSICAL DATA OF 5-ARYL-1,1-METHYLPHENYL-2,4-DITHIOBIURETS III (a-f)

Com- pound	Molecular formula	m.p. °C	Yield %	Analysis %			
				Calcd.		Found	
				C	H	C	H
IIIa	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> OS	160	69	58.00	5.13	58.18	5.39
IIIb	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	169	63	60.95	5.39	61.10	5.43
IIIc	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> OS	132	61	58.00	5.13	58.29	5.17
IIId	C <sub>18</sub> H <sub>17</sub> ClN <sub>2</sub> S	102	59	53.65	4.17	53.71	4.19
IIIe	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	110	58	60.95	5.39	61.00	5.25
IIIf	C <sub>18</sub> H <sub>17</sub> N <sub>2</sub> S	98	60	60.95	5.39	61.21	5.41

Typical IR frequencies (cm<sup>-1</sup>) of 5-m-methoxyphenyl-1,1-methylphenyl-2,4-dithiobiurets, 3385w NH-stretching<sup>17</sup>, 1155m N-C(=S)-N-grouping<sup>14a</sup>.

(ii) *Reduction of 3-arylimino-5-(N-methylanilino)-1,2,4-Δ<sup>4</sup>-dithiazolines with ethanolic ammoniacal hydrogen sulphide* : 3-m-Methoxyphenylimino-5-(N-methylanilino)-1,2,4-Δ<sup>4</sup>-dithiazolines (4 g) was dissolved in hot ethanolic ammoniacal hydrogen sulphide solution and a stream of hydrogen sulphide passed for 3 hr. The clear solution thus obtained on dilution with water or acidification with dilute hydrochloric acid afforded 5-m-methoxyphenyl-1,1-methylphenyl-2,4-dithiobiuret. It was crystallised from ethanol, m.p. 132°, yield 61% (Table 3).

### Acknowledgement

The authors are thankful to the Director, I.T., B.H.U. for necessary facilities and to the Head, Deptt. of Chemistry, B.H.U. for the microanalysis and spectra recording. Financial assistance from U.G.C., New Delhi to one of the authors (M.R.A.) is also gratefully acknowledged.

References

1. E. FROMM, R. HEYDER, A. JUNG and M. STRUM, *Annalen*, 1913, 394, 258.
2. E. FROMM and E. J. JUNIUS, *Ber.*, 1895, 28, 1099.
3. E. FROMM and H. B. AUMHAUER, *Annalen*, 1908, 361, 319.
4. F. H. S. CURD, D. G. DAVEY, D. N. RICHARDSON and R. B. ASHWORTH, *J. Chem. Soc.*, 1949, 1739.
5. S. N. DIXIT, *J. Indian Chem. Soc.*, 1961, 38, 46.
6. C. P. JOSHUA and V. K. VERMA, *J. Indian Chem. Soc.*, 1961, 38, 986.
7. V. K. VERMA, *J. Sci. Ind. Res.*, 1962, 21B, 491.
8. V. K. VERMA, *Indian J. Chem.*, 1963, 1, 116.
9. S. N. DIXIT and V. K. VERMA, *Indian J. Chem.*, 1963, 1, 487.
10. R. SINGH and V. K. VERMA, *Acta Chem.*, 1977, 93, 409.
11. G. VIJAY KUMAR NAIR, *J. Indian Chem. Soc.*, 1963, 40, 968.
12. E. A. WERNER, *J. Chem. Soc.*, 1890, 299.
13. A. R. KATRITZKY, "Physical Method in Heterocycle Chemistry", Academic Press, New York, 1963, p. 325.
14. N. B. COLTHOP, L. H. DAILY and S. E. WISELY, "Introduction to Infrared and Raman Spectroscopy", Academic Press, New York, 1964, (a) p. 323, (b) p. 284.
15. M. G. PARANJPE, *Indian J. Chem.*, 1968, 6, 182.

# Preparation, Synthesis and Mass Spectral Studies of 3-(*p*-Nitrophenyl)-thiazolo-[2,3,*c*][1,2,4]-triazepine Derivatives


B. V. ALAKA\*, D. PATNAIK and M. K. ROUT\*\*

Department of Chemistry, Ravenshaw College, Cuttack-8


Manuscript received 17 August 1981, revised 14 June 1982, accepted 12 August 1982

Preparation of 3-(*p*-nitrophenyl)-thiazolo[2,3-*c*][1,2,4]-triazepine derivatives (I, II and III) through the condensation of 2-hydrazino-4-(*p*-nitrophenyl)-thiazole with *o*-benzoyl acetophenone, acetylacetone and ethylacetoacetate and their mass spectral analysis is reported.

THE importance and extensive use of seven membered heterocyclic compounds like Serax and Megadon<sup>1</sup> as psychoedative and tranquilising agents prompted us to prepare similar seven membered ring system fused to thiazole nucleus and we have prepared the following three compounds, I, II and III.



Condensation of 2-hydrazino-4-(*p*-nitrophenyl)-thiazole<sup>2</sup>, prepared from 2-chloro-4-(*p*-nitrophenyl)-thiazole, with *o*-benzoyl acetophenone, acetyl acetone and ethylacetoacetate gave I, II and III, respectively. The intermediates (IV) were also isolated from the reactions. All attempts for cyclisation of the intermediate failed, even after prolonged heating with glacial acetic acid.



IR spectrum of IVb showed absorption at 1725 cm<sup>-1</sup> (CO<sub>2</sub>Et) while that of III showed a band at 1640 cm<sup>-1</sup> (>C=O). IR spectrum of IVa showed

absorption at 1640 cm<sup>-1</sup> (-C=C<sub>6</sub>H<sub>5</sub>) while that of I and II showed the absence of this band. The mass spectra of I-III confirmed their structure.




Chart 1





Chart 2

\* Author for correspondence.

\*\* Present address: Vice Chancellor, Utkal University, Bhubaneswar.

TABLE I

Compound	Crystallising solvent	Molecular formula	m.p. °C	Yield %	Analysis% Found (Calcd.)			
					C	H	N	S
I	Chloroform-Pet. ether	C <sub>11</sub> H <sub>11</sub> N <sub>4</sub> O <sub>2</sub> S	240	50	67.89 (67.92)	3.76 (3.77)	18.01 (18.20)	7.53 (7.54)
II	Pet. ether	C <sub>11</sub> H <sub>11</sub> N <sub>4</sub> O <sub>2</sub> S	196-200	70	55.98 (56.0)	4.34 (4.33)	18.65 (18.66)	10.60 (10.66)
III	Ethanol	C <sub>11</sub> H <sub>10</sub> N <sub>4</sub> O <sub>2</sub> S	220-21	60	51.60 (51.65)	3.29 (3.31)	18.50 (18.54)	10.56 (10.50)
IVa	Ethanol	C <sub>11</sub> H <sub>11</sub> N <sub>4</sub> O <sub>2</sub> S	228-30	40	55.05 (55.15)	4.01 (4.07)	10.36 (10.40)	7.30 (7.33)
IVb	Ethanol	C <sub>11</sub> H <sub>11</sub> N <sub>4</sub> O <sub>2</sub> S	235-37	40	51.70 (51.72)	4.32 (4.31)	16.0 (16.09)	9.89 (9.91)



The melting points are uncorrected. The purity of the compounds were routinely checked by tlc. IR spectra were recorded in KBr on a Perkin-Elmer Infrared spectrophotometer. Mass spectra were determined on a Varian Mat CH-7 instrument at 70 e.v. using direct inlet.

**General procedure for the synthesis of 3-(p-nitrophenyl)-thiazole-[2,3-c][1,2,4]-triazepine derivatives (I-III):** A mixture of 2-hydrazino-4-(p-nitrophenyl)-thiazole (2.36 g; 0.01 mole),  $\omega$ -benzoylacetophenone/acetylacetone/ethylacetoacetate (0.01 mole) and glacial acetic acid (10-35 ml) was heated under reflux for 2 hr. The solid obtained on cooling was filtered, washed and dried. The intermediate products (IV) were isolated by fractional crystallisation of this solid with suitable solvents. All the compounds (I-IV) were purified by repeated crystallisation (Table I).

#### References

1. M. A. SCHWARTZ and E. POSTMA, *J. Pharm. Soc.*, 1966, 55, 1358.
2. D. S. BARIANA, H. S. SACHADEVA and K. S. NARANG, *J. Indian Chem. Soc.*, 1955, 23, 427.

# Studies on Heterocyclic Compounds. Part—V : Synthesis and Antimicrobial Activities of N-Bridged Thiazole and Imidazole Derivatives

S. N. DEBURI and A. NAYAK

Department of Chemistry Sambalpur University, Burla, Sambalpur-768 017

Manuscript received 28 October 1981, revised 7 June 1982, accepted 14 August 1982


Several benzoxazolo[3,2-b]thiazolium, benzothiazolo[3,2-b]thiazolium and pyridino[2,1-b]thiazolium perchlorate salts, thiazolo[3,2-a]pyrimidine and several of their higher homologues as hydrobromides (IV) and free bases, were synthesised by reacting the respective mercapto compounds with  $\alpha$ -bromoketones. The free bases as well as the hydrobromides of 1,3,4-thiadiazolo[3,2-b]imidazoles (VI) and 1,3,4-oxadiazolo[3,2-b]imidazoles (VII) were synthesised by the reaction of aminoazoles with the same bromoketones. Besides these, the synthesis of a few reduced N-bridged thiazole compounds (V) prepared by reacting the mercapto compounds with dihaloalkanes has been described. The structures of these compounds have been confirmed from spectral and analytical data and their bactericidal and fungicidal potencies have been evaluated.

**T**HE versatile use of thiazole and imidazole compounds possessing -N-C-S-, -N-C-N- grouping respectively as antitubercular<sup>1</sup> and anti-radiation<sup>2</sup> agents and their applications as anthelmintics<sup>3</sup>, nematocides<sup>4</sup> and vulcanisation accelerators<sup>5</sup> have stimulated considerable interest to explore the possible synthesis of new potential compounds in which the thiazole or imidazole ring is fused with another biologically active nucleus through nitrogen atom. In the present communication, the synthesis of three types of such N-bridged thiazole derivatives in which the thiazole ring is fused to another heterocyclic ring such as benzothiazole, benzoxazole, pyridine, reduced pyrimidine and its higher homologues, imidazoline, thiadiazole and oxadiazole has been reported.

The N-bridged compounds (III), isolated as perchlorate salts were obtained by reacting the sodium salt of the mercapto compounds with  $\alpha$ -bromoketones. The ketosulphides (I), isolated as intermediates, were cyclised in the presence of conc  $H_2SO_4$ . The uv spectrum of the ketosulphide (I; A = benzothiazolyl-2, R = phenyl) showed a broad band at 290 nm correspondingly to  $\pi \rightarrow \pi^*$  transition whereas its cyclised products (III) showed a bathochromic shift and the band appeared at 312 nm due to the extensive conjugation of the  $\pi$  bonds. Similarly the ir of the same ketosulphide gave a sharp carbonyl absorption at  $1730\text{ cm}^{-1}$  which was absent in the cyclised product. The second type of N-bridged thiazolo compounds (IV), isolated as the hydrobromides, were prepared by reacting the cyclic thioureas with bromoketones by following the general procedure reported by Chadha *et al.*<sup>6,7</sup>. The free bases of the hydrobromide salts have also been isolated after neutralising the aqueous solution either with  $K_2CO_3$  or

ammonia. The third type of fused thiazole derivatives (V) in which thiazole or thiazine moieties are partially saturated were synthesised by reacting the alkylhalides (1,2-dichloroethane, 1,3-dibromopropane and 1,4-dibromobutane) with a few cyclic thioureas.

Besides these, the N-bridged imidazole derivatives (VI and VII) in which the ring is fused with either 1,3,4-thiadiazolyl or 1,3,4-oxadiazolyl moiety have been synthesised by reacting the 2-amino-5-substituted thiadiazoles and oxadiazoles respectively with bromoketones.



**Antimicrobial tests:** The bactericidal activities of the compounds were evaluated by agar plate



technique using *S. aureus* and *B. subtilis* and fungicidal tests were carried out using *A. niger* and *C. albican* in Sabouraud's broth medium.

### Experimental

All melting points are uncorrected. IR spectra of the compounds were taken on KBr disc in Perkin-Elmer 293 spectrophotometer.

**Benzoxazolyl-2-phenacyl sulphide** (I;  $A = \text{benzoxazolyl-2}$ ,  $R = C_6H_5$ ): 2-Mercaptobenzoxazole (3 g, 0.02 mole) in methanol (70 ml) was taken in a 500 ml round bottomed flask provided with a mechanical stirrer. Metallic sodium (0.02 mole) was added to it proton wire. To the resulting clear solution phenacylbromide (2.0 g) was added in portions with stirring and the mixture was allowed to stand at room temperature overnight. The needle-shaped crystals were filtered off, m.p. 115-116°, yield 2.0 g (70%). (Found: S, 12.90.  $C_{18}H_{11}O_2NS$  requires S, 12.89%);  $\lambda_{\text{max}}^{\text{EtOH}}$  (nm): 276 ( $\epsilon = 5 \times 10^4$ );  $\nu_{\text{max}}^{\text{KBr}}$  ( $\text{cm}^{-1}$ ): 2845, 1750, 1690.

**3-Phenylbenzoxazol[3,2-b]thiazolium perchlorate** (III;  $A = \text{benzoxazolyl-2}$ ,  $R = C_6H_5$ ): The above ketosulphide (1.35 g) was dissolved in ice cold conc  $H_2SO_4$  (12 ml) and the mixture was allowed to stand at room temperature for 24 hr. The resulting solution was then poured cautiously to 300 ml of ice cold anhydrous ether and the mixture was kept in the refrigerator for 2 days. The ether layer was decanted off from an oil. The ether was evaporated at room temperature and the residue was dissolved in small quantity of water and filtered. The solution was treated with 35%  $HClO_4$  (5 ml) and kept overnight during which the perchlorate salt precipitated out. It was filtered, washed several times with cold ether and dried in air, m.p. 202-3°, yield 62%. (Found: S, 8.85.  $C_{18}H_{11}NO_4S$  requires 9.10%);  $\lambda_{\text{max}}^{\text{EtOH}}$  (nm): 307 ( $\epsilon = 4 \times 10^4$ );  $\nu_{\text{max}}^{\text{KBr}}$  ( $\text{cm}^{-1}$ ): 1685, 1206.

**Benzothiazolyl-2-phenacyl sulphide** (I;  $A = \text{benzothiazolyl-2}$ ,  $R = C_6H_5$ ): This was prepared as colourless needles by taking 2-mercaptobenzothiazole (0.42 g), metallic sodium (0.05 g) and phenacylbromide (0.5 g) in methanol (20 ml) by following the above procedure, m.p. 207°, yield 350 mg (50%). (Found: S, 22.18.  $C_{18}H_{11}NS_2O$  requires S, 22.45%);  $\lambda_{\text{max}}^{\text{EtOH}}$  (nm): 290 ( $\epsilon = 3.2 \times 10^4$ );  $\nu_{\text{max}}^{\text{KBr}}$  ( $\text{cm}^{-1}$ ): 2910, 1750, 1685, 1305.

**3-Phenylbenzothiazol[3,2-b]thiazolium perchlorate** (III;  $A = \text{benzothiazolyl-2}$ ,  $R = C_6H_5$ ): The above ketosulphide (0.28 g) was cyclised with ice cold conc  $H_2SO_4$  (5 ml) and the product was isolated as perchlorate salt by following the general work up procedure, m.p. 221°, yield 50%. (Found: S, 17.19.  $C_{18}H_{11}O_4NS_2Cl$  requires S, 17.42%);  $\lambda_{\text{max}}^{\text{EtOH}}$  (nm): 310 ( $\epsilon = 6 \times 10^4$ );  $\nu_{\text{max}}^{\text{KBr}}$  ( $\text{cm}^{-1}$ ): 1690, 1460, 1300.

**Pyridyl-2-phenacyl sulphide** (I;  $A = \text{pyridyl-2}$ ,  $R = C_6H_5$ ): This was prepared from 2-mercaptopyridine (1.1 g) and phenacylbromide (2.0 g) in methanol and metallic sodium (0.2 g) by following the general procedure as colourless needles, m.p. 107°, yield 1.4 g (65%). (Found: S, 13.97.  $C_{18}H_{11}NSO$  requires S, 13.84%).

**3-Phenyl-pyridino[2,1-b]thiazolium perchlorate** (III;  $A = \text{pyridyl-2}$ ,  $R = C_6H_5$ ): The above thio-ketone (1.15 g) was cyclised using conc  $H_2SO_4$  and the product was isolated as the perchlorate salt, m.p. 207 (d). (Found: S, 14.02.  $C_{18}H_{11}NOS$  requires S, 13.97%).

**3-Phenyl-4,5,6,7-tetrahydrothiazolo[3,2-a]pyrimidine hydrobromide** (IV;  $N=3$ ,  $R = C_6H_5$ ): A mixture of 2-mercapto-3,4,5,6-tetrahydropyrimidine (1.16 g; 0.01 mole) and phenacylbromide (2 g) in ethanol (25 ml) was heated under reflux on a water bath for 12 hr. Dirty white crystals separated after concentrating the solution. It was filtered and recrystallised from ethanol as white crystals, m.p. 258°, yield 2.1 g (70%). (Found: S, 10.75; Br, 26.62.  $C_{18}H_{15}N_2SBr$  requires S, 10.77; Br, 26.93%).

The free base was obtained after neutralising the aqueous solution with  $K_2CO_3$  in almost quantitative yield, m.p. 139°. (Found: S, 14.43.  $C_{18}H_{15}N_2S$  requires S, 14.81%).

**3-Phenyl-5,6,7,8-tetrahydrothiazolo[3,2-a](1,3)diazepine hydrobromide** (IV;  $n=4$ ,  $R = C_6H_5$ ): It was prepared by taking 2-mercaptodiazepine (1.30 g; 0.01 mole) and phenacylbromide (2 g) in ethanol (20 ml) following the general work up procedure mentioned earlier, m.p. 246°, yield 1.2 g (35%). (Found: S, 11.80.  $C_{18}H_{15}N_3SBr$  requires S, 10.29%).

The free base was obtained as crystalline needles after neutralisation with aqueous ammonia, m.p. 111°. (Found: S, 13.63.  $C_{18}H_{14}N_3SBr$  requires S, 13.91%).

**2,3,5,6-Tetrahydrothiazolo[3,2-a]imidazole hydrochloride** (V;  $n=m=2$ ): Ethylene thiourea (0.4 g) and 1,2-dichloroethane (0.4 g) in absolute alcohol (20 ml) were refluxed on a water bath for 6 hr. After cooling, fine crystals of thiazoloimidazole hydrochloride separated, m.p. 196°, yield 0.5 g (63%). (Found: S, 19.04.  $C_8H_8N_2S_2Cl$  requires S, 19.45%).

The other compounds prepared by the above procedure are V ( $n=3$ ,  $m=2$ ,  $X=Cl$ ), m.p. 206°. (Found: S, 17.86.  $C_8H_{11}N_2S_2Cl$  requires S, 18.13%); V ( $n=4$ ,  $m=2$ ,  $X=Cl$ ), m.p. 217°. (Found: S, 17.54.  $C_7H_{10}N_2S_2Cl$  requires S, 17.68%); V ( $n=2$ ,  $m=4$ ,  $X=Br$ ), m.p. 208 (d). (Found: S, 13.44.  $C_7H_8H_2S_2Br$  requires S, 13.67%); V ( $n=m=3$ ,  $X=Br$ ), m.p. 214°. (Found: S, 13.51.  $C_7H_{11}N_3S_2Br$  requires S, 13.67%).

**2,5-Diphenyl-1,3,4-oxadiazolo[3,2-b]imidazole hydrobromide** (VII;  $X=R=C_6H_5$ ): A mixture of 2-amino-5-phenyl oxadiazole (0.16 g) and phenacylbromide (0.2 g) in alcohol (15 ml) was heated under reflux on a water bath for 6 hr. The colourless solid separated after cooling was filtered,

TABLE I—ANALYTICAL DATA AND TEST RESULTS OF PERCHLORATE SALTS (III)

A	R	m.p. °C	%S Found (Calcd.)	SA	BS	OA*	AN*
Benzoxazolyl-2	Phenyl	—	—	+	+	50	50
—do—	p-Chlorophenyl	223	8.15 (8.29)	+	2+	50	50
—do—	p-Anisyl	246	8.21 (8.38)	+	+	—	—
—do—	Thienyl-2	214	18.61 (18.74)	2+	+	100	100
—do—	Furyl-2	197	9.70 (9.88)	+	+	—	—
Benzothiazolyl-2	Phenyl	—	—	2+	2+	50	50
—do—	p-Chlorophenyl	226	15.65 (15.92)	2+	2+	100	100
—do—	p-Anisyl	218	16.06 (16.10)	+	—	—	—
—do—	Thienyl-2	205	26.78 (26.85)	2+	+	—	100
—do—	Furyl-2	187	9.25 (9.37)	+	—	—	—
Pyridyl-2	Phenyl	—	—	+	—	—	—
—do—	Thienyl-2	176	20.00 (20.15)	+	+	—	100
—do—	Furyl-2	144	10.29 (10.61)	—	—	—	—

SA = *S. aureus*, BS = *B. subtilis*, OA = *C. albicans*, AN = *A. niger*, + = zone size 6-8 mm, 2+ = zone size 9-14 mm, — = inactive.  
\*The number indicates minimum inhibitory concentration in µg/ml.

TABLE 2

n	R	Hydrobromide (IV)						Free base	
		m.p. °C	%Br Found (Calcd.)	SA	BS	OA*	AN*	m.p. °C	%S Found (Calcd.)
3	Phenyl	—	—	—	+	100	—	—	—
	p-Chlorophenyl	250	—	+	—	—	—	150	12.42 (12.74)
	Thienyl-2	296	26.15 (26.40)	+	2+	50	50	144	28.56 (28.82)
	Furyl-2	285	27.64 (27.87)	+	+	—	—	123	15.34 (15.53)
	p-Nitrophenyl	250	—	+	—	—	—	165	11.70 (11.98)
4	Phenyl	246	—	+	+	100	—	—	—
	p-Chlorophenyl	213	—	+	2+	100	—	120	11.68 (12.07)
	Thienyl-2	176	25.16 (25.23)	2+	—	—	100	164	27.16 (27.11)
	Furyl-2	189	26.30 (26.57)	+	—	—	—	150	—
	p-Nitrophenyl	193	—	—	—	—	—	129	11.25 (11.38)
5	Phenyl	213	22.24 (24.61)	+	—	—	—	130	13.10 (13.11)
	p-Chlorophenyl	212	—	+	+	—	—	146	12.23 (12.35)
6	Phenyl	209	24.46 (24.31)	+	—	—	—	117	12.29 (12.40)
7	Phenyl	200	23.10 (23.32)	+	+	—	—	106	—
8	Phenyl	207	22.24 (22.40)	+	+	—	—	111	11.12 (11.18)

SA = *S. aureus*, BS = *B. subtilis*, OA = *C. albicans*, AN = *A. niger*, + = zone size 6-8 mm, 2+ = zone size 9-14 mm, — = inactive.  
\*The number indicates minimum inhibitory concentration in µg/ml.

washed with ether and dried, m.p. 226°, yield 150 mg (70%). (Found: Br, 23.18.  $C_{10}H_{11}N_2OBr$  requires Br, 23.32%).

The above hydrobromide was dissolved in water and neutralised by conc  $NH_4OH$  during which the free base separated in quantitative yield. It was

TABLE-3

X	R	Hydrobromide (VI)						Free base		
		m.p. °C	%Br Found (Calcd.)	SA	BS	CA**	AN**	m.p. °C	%S Found (Calcd.)	BS
H	Phenyl	235	28.48 (28.27)	2+	—	—	—	198	15.52 (15.76)	+
—do—	p-Chlorophenyl	238	—	2+	—	—	—	198	15.45 (15.58)	—
Phenyl	Phenyl	254	22.72 (22.88)	—	—	100	—	192	11.32 (11.52)	—
—do—	p-Chlorophenyl	237	—	—	+	—	—	172	—	—
p-Anisyl	Phenyl	218	20.48 (20.67)	2+	+	50	—	252	10.09 (10.23)	+
—do—	p-Chlorophenyl	235	—	—	—	—	—	244	9.18 (9.32)	—
p-Chlorophenyl	Phenyl	250	20.13 (20.38)	+	+	50	—	216	10.98 (10.89)	+
—do—	p-Chlorophenyl	250	—	—	—	50	—	282	—	+
Hydrobromides (VII)										
Phenyl	Phenyl	225	23.18 (23.82)	+	+	—	—	208	15.76* (15.03)	+
—do—	p-Chlorophenyl	222	—	—	—	—	—	198	—	—
p-Chlorophenyl	Phenyl	281	21.12 (21.19)	—	+	—	—	142	—	—
—do—	p-Chlorophenyl	227	—	—	—	—	—	118	12.46* (12.66)	—
p-Anisyl	Phenyl	220	21.28 (21.45)	—	—	100	—	258	—	+
—do—	p-Chlorophenyl	284	—	—	—	—	—	234	—	—

\* indicates estimated sulphur percentage.

filtered, washed with water and recrystallised from ethanol, m.p. 208°. (Found : N, 15.78.  $C_{16}H_{12}N_2O$  requires N, 16.03%).

3-Phenyl-(1,3,4-thiadiazolo)[3,2-b]imidazole hydrobromide (VI;  $X=H$ ,  $R=C_6H_5$ ): It was obtained as crystalline needles from 2-aminothiadiazole (0.5 g) and phenacylbromide (0.5 g) by following the above procedure, m.p. 235°, yield 400 mg (60%). (Found : Br, 28.30.  $C_{16}H_{12}N_2Br$  requires Br, 28.27%).

The free base was obtained after neutralisation with ammonia as pale yellow solid, m.p. 198°, yield 58%. (Found : S, 15.52.  $C_{16}H_{12}N_2S$  requires S, 15.76%).

The physical and analytical data and antimicrobial test results of various perchlorate salts, thiazolopyrimidine and their higher homologues and thiazolo thioxadiazolo derivatives have been presented in Tables 1, 2 and 3, respectively.

#### Acknowledgement

The authors are grateful to C.S.I.R., New Delhi for a Research Fellowship to one of them (S.N.D.).

#### References

1. R. H. MIZZONI and P. C. EIDMAN, *J. Amer. Chem. Soc.*, 1958, 80, 3471.
2. (a) G. R. HANDRICK, E. R. ALKINSON, F. E. GRANCHELLI and R. J. BRUNI, *J. Med. Pharm. Chem.*, 1965, 8, 762.  
(b) F. KURTZER, "Sulphur, Selenium and Tellurium", The Chemical Society, (Special Periodical Reports), 1970, Vol. 1.
3. (a) T. BACTELTI, U. S. Pat., 2,784,196, May 5, 1957.  
(b) C. O. WILSON, O. GIVOLD and R. F. DOMER, "Text-book of Medicinal and Pharmaceutical Chemistry", Pitman, London, 1966.
4. J. R. GEIGY, *Fr. Pat.*, 1,395,069, April, 1965.
5. (a) F. A. V. SULLIVAN and A. C. LINDAW, *Belg. Pat.*, 640,429, May 26, 1964.  
(b) F. KURTZER, "Sulphur, Selenium and Tellurium", The Chemical Society, (Special Periodical Reports), 1973, Vol. 2.
6. V. R. CHADHA, K. S. SHARMA and H. K. PUJARI, *Indian J. Chem.*, 1971, 9, 1216.
7. V. R. CHADHA, *J. Indian Chem. Soc.*, 1977, 54, 878.



# Synthesis of 3-(p-Fluoro)benzoylhydrazono-5-substituted-2-indolinones as Potential Biologically Active Agents<sup>†</sup>

RAJENDRA S. VARMA and RAJNISH K. PANDEY

Department of Chemistry, Lucknow University, Lucknow-226 007


Manuscript received 30 September 1981, accepted 25 August 1982

Different 5-substituted isatins have been condensed with p-fluoro benzoic acid hydrazide to furnish 3-(p-fluoro)benzoylhydrazono-5-substituted-2-indolinones (I). Similarly, reaction of N-methyl-5-substituted isatins with p-fluorobenzoic acid hydrazide yielded 1-methyl-3-(p-fluoro)benzoylhydrazono-5-substituted-2-indolinones (II). When I were subjected to Mannich reaction 1-aminomethyl-3-(p-fluoro)benzoylhydrazono-5-substituted-2-indolinones (III) were obtained. These compounds were screened for antibacterial activity against *B. megaterium*, *X. malvacearum*, *E. coli* and *B. subtilis* as well as for CNS activity.

ISATINS are known for their antiviral<sup>1</sup>, antibacterial<sup>2,3</sup>, anthelmintic<sup>4</sup> and herbicidal<sup>5</sup> properties. In addition, cysticidal<sup>6</sup>, hypotensive responses and anticonvulsant activity<sup>7</sup> have also been reported in certain isatin derivatives. The antibacterial activity of different benzoic acid hydrazides is well established<sup>8,9</sup>. Certain organofluorine compounds have been reported as antibacterial<sup>10,11</sup> and CNS active agents<sup>12,13</sup>. In view of all these, it was considered of interest to synthesise certain fluorine containing acid hydrazide incorporated isatins and to evaluate them for their antibacterial activity and CNS activity.

For the synthesis of I, II and III, the starting materials, 5-substituted isatins, were prepared via Sandmeyer reaction<sup>14</sup>. p-Fluorobenzoic acid hydrazide was prepared from the methyl ester of p-fluoro benzoic acid and hydrazine hydrate. Condensation of various p-substituted isatins with p-fluorobenzoic acid hydrazide yielded 3-(p-fluoro)benzoylhydrazono-5-substituted-2-indolinones (I). I were also prepared successfully by amine exchange reaction i.e., refluxing 5-substituted-3-arylimino-2-indolinones (IV) with p-fluorobenzoic acid hydrazide. Identity of both the products was checked by tlc, m.p., mixed m.p. and ir data. Mannich condensation on I, obtained via both the routes, yielded the same Mannich base which indicated that I prepared via both the route was the same. Treatment of 5-substituted isatins with dimethyl sulphate in ethanolic potassium hydroxide yielded N-methyl-5-substituted-2-indolinones, which on treatment with p-fluorobenzoic acid hydrazide yielded N-methyl-5-substituted-3-(p-fluoro)benzoylhydrazono-2-indolinones (II). Mannich condensation of I with amines furnished III. All the synthesised compounds gave satisfactory elemental analysis. Further support for their structures was derived from ir, nmr and mass spectral data. With a view to rule out the possibility of aminomethylation at -NH of benzoylhydrazono group in I during

Mannich condensation, II (R = Cl) was heated with morpholine and formalin. In this reaction II was



recovered unchanged and its identity was established on the basis of m.p., mixed m.p., ir and tlc.

## Experimental

Melting points were taken in open capillaries and are uncorrected. IR spectra were taken in KBr and were as expected. NMR spectra were taken in CDCl<sub>3</sub> at 90 MHz. Mass spectra were recorded at 70 eV.

### 3-(p-Fluoro)benzoylhydrazono-5-substituted-2-indolinones (I) :

**Method A :** A mixture of isatin (4.4 g; 0.03 mole) and p-fluorobenzoic acid hydrazide (4.2 g; 0.03 mole) in ethanol (25 ml) was refluxed for 4 hr in presence of 2-3 drops of glacial acetic acid. The reaction mixture was then cooled to room temperature and the solid product was filtered and washed with ethanol (Table I).

TABLE I—3-(p-FLUORO)BENZOLHYDRAZONO-5-SUBSTITUTED-2-INDOLINONES (I)

Sl. No.	R	Yield %	m.p. °C	Molecular formula
1.	H	78	>270	C <sub>18</sub> H <sub>10</sub> FN <sub>2</sub> O <sub>3</sub>
2.	CH <sub>3</sub>	76	>260	C <sub>19</sub> H <sub>11</sub> FN <sub>2</sub> O <sub>3</sub>
3.	Cl	70	>260	C <sub>18</sub> H <sub>8</sub> ClFN <sub>2</sub> O <sub>3</sub>
4.	Br	82	>260	C <sub>18</sub> H <sub>8</sub> BrFN <sub>2</sub> O <sub>3</sub>

<sup>†</sup> Part XXXIII of the series Potential Biologically Active Agents.

TABLE 2—AMINOMETHYL-3-(*p*-FLUORO)BENZOYLHYDRAZONO-5-SUBSTITUTED-2-INDOLINONES (III)

Sl. No.	R	X	Yield %	m.p. (°C)	Molecular formula	Analysis%	
						Calcd.	Found
9.	H	OH <sub>2</sub>	62	268-269	C <sub>11</sub> H <sub>11</sub> FN <sub>2</sub> O <sub>2</sub>	N, 14.78	14.48
10.	H	O	65	207-208	C <sub>10</sub> H <sub>11</sub> FN <sub>2</sub> O <sub>2</sub>	C, 62.82	62.95
11.	OH <sub>2</sub>	OH <sub>2</sub>	68	195-196	C <sub>11</sub> H <sub>11</sub> FN <sub>2</sub> O <sub>2</sub>	H, 4.97	5.01
						C, 67.00	66.73
						H, 5.83	5.51
						N, 14.21	13.81
12.	OH <sub>2</sub>	O	68	217-218	C <sub>11</sub> H <sub>11</sub> FN <sub>2</sub> O <sub>2</sub>	C, 63.68	62.98
13.	Cl	OH <sub>2</sub>	62	190d	C <sub>11</sub> H <sub>10</sub> ClFN <sub>2</sub> O <sub>2</sub>	H, 5.30	5.13
						C, 60.79	60.95
14.	Cl	O	62	215	C <sub>10</sub> H <sub>11</sub> ClFN <sub>2</sub> O <sub>2</sub>	H, 4.82	5.45
						C, 57.62	57.80
						H, 4.33	4.25
						N, 13.44	13.16
15.	Br	OH <sub>2</sub>	64	197-198	C <sub>11</sub> H <sub>10</sub> BrFN <sub>2</sub> O <sub>2</sub>	N, 12.20	12.20
16.	Br	O	68	218-214	C <sub>10</sub> H <sub>11</sub> BrFN <sub>2</sub> O <sub>2</sub>	C, 62.06	61.60
						H, 8.90	8.71
						N, 12.14	11.88

 Mass spectra No. 11—M<sup>+</sup>, m/e 394

 No. 16—M<sup>+</sup>, m/e 460/462

 PMR (δ value): 15, 1.42 (6H, -OH<sub>2</sub>CH<sub>2</sub>-), 2.35/4H, N<CH<sub>2</sub>OH<sub>2</sub>)  
 4.85 (2H, N-OH<sub>2</sub>N), 6.80-7.40 (4H, -O<sub>2</sub>H<sub>2</sub>-F),  
 7.81-7.96 (3H, remaining Ar-H).

**Method B:** I were also prepared successfully by amine exchange reaction in which 3-arylimino group of 5-substituted-3-arylimino-2-indolinones was replaced by (*p*-fluoro)benzylhydrazono group. 5-Substituted-3-arylimino-2-indolinone (0.005 mole) was refluxed with *p*-fluoro benzoic acid hydrazide (0.005 mole) in ethanol (10 ml) for 6 hr. The solid obtained after cooling the reaction mixture was filtered, washed well with ethanol. Identity of I, prepared by method B, was checked by m.p., mixed m.p., tlc and ir spectral data. Identical Mannich bases (III) obtained from I, prepared by methods A and B, further established their identity.

**N-Methyl-3-(*p*-fluoro)benzoylhydrazono-5-substituted-2-indolinones (II):** 5-Chloro-N-methyl-isatin (1.95 g; 0.01 mole) was refluxed with *p*-fluorobenzoic acid hydrazide (1.55 g; 0.01 mole) in ethanol (20 ml) for 4 hr in presence of 2-3 drops of glacial acetic acid. The reaction mixture was cooled to room temperature and the resultant product was filtered, washed well with ethanol and recrystallised from ethyl acetate (Table 2).

 TABLE 2—N-METHYL-3-(*p*-FLUORO)BENZOYLHYDRAZONO-5-SUBSTITUTED-2-INDOLINONES (II)

Sl. No.	R	Yield %	m.p. °C	Molecular formula	Analysis%	
					Calcd.	Found
5.	H	89	218-220	C <sub>16</sub> H <sub>11</sub> FN <sub>2</sub> O <sub>2</sub>	C, 64.64	64.21
6.	OH <sub>2</sub>	75	206-207	C <sub>17</sub> H <sub>14</sub> FN <sub>2</sub> O <sub>2</sub>	H, 4.01	3.89
					N, 13.50	13.61
7.	Cl	72	208-204	C <sub>16</sub> H <sub>11</sub> ClFN <sub>2</sub> O <sub>2</sub>	C, 57.91	57.72
					H, 8.31	8.31
8.	Br	70	213-214	C <sub>16</sub> H <sub>11</sub> BrFN <sub>2</sub> O <sub>2</sub>	N, 12.66	12.61
					N, 11.17	10.84

 Mass spectra; No. 7—M<sup>+</sup>, m/e 381/383.

**Reaction of II (R-Cl) with morpholine and formalin:** II (0.005 mole) (R=Cl) was suspended in 10 ml of warm ethanol. Morpholine (1 ml) and formalin (1 ml) was added and the mixture stirred at 80° for 30 min. Working up the reaction mixture yielded a solid which was recrystallised from ethyl acetate. Its mixed m.p. with compounds 7 showed no depression. The product was identical with compound\*.

**1-Amino-3-(*p*-fluoro)benzoylhydrazono-5-substituted-2-indolinones (III):** I (0.005 mole) was suspended in 10 ml of ethanol. To this suspension 1 ml of 37% formalin and amine (0.005 mole) were added with vigorous stirring. The mixture was heated on a water bath for 10 min and thereafter allowed to stand at room temperature overnight. The product thus deposited was filtered, washed well with ethanol and petroleum ether (60-80°) and dried well in air. It was finally recrystallised from chloroform or carbon tetrachloride and petroleum ether (60-80°) or ethyl acetate (Table 3).

**3-Arylimino-2-indolinones (IV):** Isatin (0.01 mole) was taken in 25 ml of absolute ethanol containing 2-3 drops of glacial acetic acid and aryl amine (0.01 mole) was added to it. The reaction mixture was refluxed for 5 hr. The product was recrystallised from ethyl acetate.

#### Pharmacology:

**CNS activity:** Thirteen compounds out of the 16 synthesised were examined for their toxicity tests and the gross CNS activity at 1/5th of ALD<sub>50</sub> by the method of Wiel<sup>12</sup> (Table 4).

The compounds have been found to be non-toxic and psychotropic agents. Compound No. 4

TABLE 4—CNS ACTIVITY

Compound No.	ALD <sub>50</sub>	SMA	Gross effect at 1/5th of ALD <sub>50</sub>		
			SA Reactivity	Writhing	Body temp.
2	895	—	—	(+)	—
4	681	↓	↓	(+)	0.2°
6	1000	—	—	(+)	—
6	1000	—	—	(+)	—
7	681	—	—	(+)	0.2°
8	1000	↑	↑	(-)	(-)
9	1000	↑	↑	(-)	(-)
10	1000	↑	↑	(-)	(-)
11	1000	↑	↑	(-)	(-)
13	1000	↑	↑	(-)	(-)
14	1000	↑	↑	(-)	0.6°
15	681	↑	↑	(-)	0.2°
16	1000	↑	↑	(-)	0.4°

and 5 have been found to be CNS depressant whereas the remaining tested compounds have shown an increase in SMA and reactivity to sound and touch. Compound No. 2 and 4 to 7 have induced writhing, showing some muscle relaxant effect on belly muscles. Compound No. 4, 7 and 14 to 16 have induced hypothermia ranging between 0.2 to 0.6°. Rest of the compounds were ineffective towards body temperature.

**Antibacterial activity:** The method of Varma and Nobles<sup>10</sup> was employed for determining the antibacterial spectrum of all the compounds. The test organisms included *Bacillus megaterium*, *Xanthomorphus malvacearum*, *Escherichia coli* and *Bacillus subtilis*. Sterile filter paper discs (5 mm diam), saturated with solution of the test com-

pounds were placed on the agar [1.5% (w/v) agar; 0.5% (w/v) NaCl; 0.5 (w/v) glucose and 2.5% (w/v) peptone, pH 6.8-7.0] plates after drying up the solvent. The plates were incubated at 37° for 24 hr and zones of inhibition around the discs were measured. Bacterial cultures maintained at Public Analyst Laboratory, U. P. Government, Lucknow, were used (Table 5).

Compound No. 9, 10, 13 and 14 were found to be most active against *B. megaterium* and *X. malvacearum*.

#### Acknowledgement

Thanks of the authors are due to the Head of the Department for facilities and to Dr. B. N. Dhawan, Head of Pharmacology Department, C.D.R.I., Lucknow, for the pharmacological screening. Thanks are also due to Prof. Dr. W. Pfeleiderer, Faculty of Chemistry, University of Konstanz, W. Germany and Dr. R. S. Kapil for analytical/spectral data.

#### References

1. Z. HOLZBECHER, *Chem. Listy*, 1950, 44, 126, *Chem. Abs.*, 1951, 45, 8005.
2. S. KOSHIMURA, A. HAMADA, T. OTAKI and K. DROUCHI, *Ann. Rept. Research Inst. Tuberc.*, *Kansaiawa Univ.*, 1954, 12, 9, *Chem. Abs.*, 1955, 49, 9159.
3. R. S. VARMA and W. L. NOBLES, *J. Pharm. Soc.*, 1976, 64, 881.
4. F. KONTZ, *Sci. Pharm.*, 1973, 41, 128, *Chem. Abs.*, 1973, 79, 99152.
5. E. MAMERSCH, German Patent No. 1, 018, 459, 1957, *Chem. Abs.*, 1960, 54, 16735.
6. R. S. VARMA and I. A. KHAN, *Indian J. Med. Res.*, 1978, 67, 315.
7. John Wyeth and Brothers Ltd., *Brit.*, 1,240, 648, 1971 *Chem. Abs.*, 1971, 75, 118342.
8. R. S. VARMA, Possible Antituberculous Compounds, Ph.D. Thesis, Lucknow University, 1968.
9. S. BHADUR, S. P. SINGH and R. S. VARMA, *Indian J. Chem.*, 1980, 19B, 826.
10. KRISHNA C. JOSHI, VIJAI N. PATHAK and PRAMILA ARYA, *Agric. Biol. Chem.*, 1979, 43, 199.
11. KRISHNA C. JOSHI, VIJAI N. PATHAK, PRAMILA ARYA and POORAN CHAND, *Agric. Biol. Chem.*, 1979, 43, 171.
12. KRISHNA C. JOSHI, VIJAI N. PATHAK and RAJPAL SINGH, *Indian J. Exp. Biol.*, 1974, 12, 46.
13. KRISHNA C. JOSHI, VIJAI N. PATHAK and POORAN CHAND, *Agric. Biol. Chem.*, 1978, 42, 1723.
14. I. A. KHAN, Ph.D. Thesis, Lucknow University, 1977.
15. C. S. WEIL, *Biometrics*, 1953, 9, 249.
16. R. S. VARMA and W. L. NOBLES, *J. Pharm. Sci.*, 1973, 61, 113.

TABLE 5—ANTIBACTERIAL ACTIVITY

Sl. No.	<i>B. mag.</i>	<i>X. m.</i>	<i>E. coli</i>	<i>B. subtilis</i>
1.	+	+	+	+
2.	+	++	+	++
3.	++	+++	+	++
4.	+	++	+	+
5.	—	+	++	+
6.	—	+	++	+
7.	+	+	+	+
8.	—	+	+	++
9.	++++	++	+	+
10.	++++	+++	+	+
11.	++	+++	++	+
12.	++	—	—	—
13.	++++	++	+	+
14.	++++	+	—	+
15.	+++	+	—	+
16.	++	—	+	—

— = No inhibition, + = Zone size 6-8 mm, ++ = Zone size 8-10 mm, +++ = Zone size 10-15 mm, ++++ = Zone size > 15 mm.

# Extraction and Spectrophotometric Determination of Vanadium(V) as Mixed Ligand Complexes of Various Hydroxyamidines and Thiocyanate\*\*


(Miss) ABHA RANI JHA and RAJENDRA KUMAR MISHRA\*

Department of Chemistry, Ravishankar University, Raipur-492 010, M. P.

Manuscript received 31 December 1981, revised 26 May 1982, accepted 21 August 1982

A simple and selective method for the extractive spectrophotometric determination of vanadium(V) in various alloy steels at micro-gram level has been developed. The method is based on the chloroform extraction of vanadium(V) with eleven newly synthesized hydroxyamidines (HOA) and thiocyanate. The molar absorptivities of the complexes lie between  $3.30-6.25 \times 10^3 \text{ l. mol}^{-1} \text{ cm}^{-1}$  at 595-610 nm with Sandell's sensitivities in the range 0.008-0.015  $\mu\text{g}$  of metal per  $\text{cm}^2$ . In present investigation N-hydroxy-N-p-chlorophenyl-N'-(2,3-dimethyl)phenylbenzamidines hydrochloride was selected for a detailed study. It forms a deep green complex in the pH range 1.7-3.0 having the ratio 1 : 2 : 2 (V : SCN<sup>-</sup> : HOA). Fe(III), Cu(II), Ni(II), Co(II), Zn(II), Cd(II), Mn(II), Cr(III), Ti(IV), Zr(IV), Nb(V), Mo(VI), W(VI), fluoride, iodide, thio-sulphate, oxalate, phosphate etc. do not interfere.

N-Hydroxy-N,N'-diarylbenzamidines (HOA) and its derivatives have been recently explored as potential reagents for the determination of various d-group elements<sup>1-5</sup>. HOA is a better reagent than other well known organic reagents<sup>6-8</sup>, because of its high molecular weight and selective colour reaction towards the metal ions. However, there is considerable scope for improvement in the structural features of such a molecule to make it more suitable as an analytical reagent, as substitution is possible in three phenyl rings. The objective of the present communication is to study the colour reaction of even newly synthesized N-hydroxy-N,N'-diarylbenzamidines (I), with vanadium(V) in presence of thiocyanate with a view to study the effect of substituents on the complexing properties of the  $\sim \text{N}=\text{C}-\text{N}(\text{OH})-$  group.



X=H-  
Y=H-, o-OH-, m-OH-, p-OH-, 2,3-(OH)<sub>2</sub>-,  
2,6-(OH)<sub>2</sub>-, 2,4,6-(OH)<sub>3</sub>- or p-OCH<sub>3</sub>-  
Z=H-, m-Cl-, p-Cl- or p-OH<sub>2</sub>-

N-Hydroxy-N-p-chlorophenyl-N'-(2,3-dimethyl)-phenylbenzamidines hydrochloride was found to be the most sensitive reagent in the present investigation and hence selected for the detailed study.

The advantages of the proposed method over the recommended methods<sup>9-12</sup> are that the colour reaction is simple, rapid, sensitive and fairly selective. The ions Mn<sup>2+</sup>, Co<sup>2+</sup>, Ni<sup>2+</sup>, Pb<sup>2+</sup>, Cr<sup>3+</sup>, Ti<sup>4+</sup>, Zr<sup>4+</sup>, Mo<sup>6+</sup> and oxidizing agents do not interfere and there is no possibility of reduction of vanadium(V).

## Experimental

Absorptiometric and pH-metric measurements were made with an ECIL, UV-VIS spectrophotometer, model GS-865 with matched 1 cm quartz and silica cells and Systronic pH-meter, type-322, respectively.

Vanadium(V) solution was prepared from ammonium metavanadate (B.D.H., AnalaR) and standardized volumetrically using potassium permanganate<sup>14</sup>. The reagent was prepared by the condensation of equimolar quantities of N-arylbenzimidoylchloride and N-arylhydroxylamine in ether medium<sup>1</sup>.

A 0.1% (w/v) solution of hydroxyimidine in chloroform and 5% (w/v) solution of potassium thiocyanate in water were used for the extraction work.

**Procedure:** An aliquot of the vanadium(V) solution (100  $\mu\text{g}$  V) and 2 ml of thiocyanate solution were taken in a 125 ml separatory funnel and the pH was maintained at 2.2 in final dilution of 15 ml using HCl-KCl buffer. The aqueous layer was equilibrated with 15 ml chloroform solution of the reagent for 1 min. The organic layer was transferred over anhydrous sodium sulphate in a

\* Author for correspondence.

\*\* Presented at Annual Convention of Chemists, 1980, held at Bombay.

50 ml beaker. The aqueous phase was washed with 2×4 ml portions of chloroform. The combined extracts, after drying, were transferred to a 25 ml volumetric flask and the volume was made up to the mark with chloroform. The absorbances were measured at 605 nm against chloroform as a blank.


### Results and Discussion

The absorption curve of reagent and its metal chelate showed that the reagent has negligible absorption in the region 450-700 nm, while the complex has a broad  $\lambda_{\max}$  between 595-610 nm.

**Effect of variables:** Chloroform was chosen as a diluent for this study because of higher extractability of the complex and the reagent in it than other solvents (benzene, carbon tetrachloride and 2,4-dichlorobenzene). The pH of the aqueous phase was maintained with 1 M hydrochloric acid and dilute ammonia. The optimum pH range for complete extraction of metal was found to be 1.7-3.0. At least 8 and 10 fold molar excess of hydroxyamidine and thiocyanate respectively were necessary for complete extraction of the metal. Addition of more reagent caused no adverse effect either in the position of  $\lambda_{\max}$  or on the absorbance value of the complex. The order of addition of reagents was not critical. A time of 1 min was sufficient for complete extraction of vanadium(V). The complex was stable for at least 40 hr at room temperature. Variation in temperature from 20 to 40° and volume of the aqueous phase from 15 to 60 ml had no effect on the nature of the complex. No effect of electrolytes (i.e. NaCl, KCl and  $\text{NH}_4\text{Cl}$ ) upto 3 M on the distribution coefficient of the metal was observed.

**Effect of substituents:** The influence of substituents on the complexing properties of the ligand was studied by preparing eleven new analogues of N-hydroxy-N',N'-diarylbenzamidines and testing their potentialities in the extractive separation and spectrophotometric determination of vanadium(V). The molar absorptivities of the mixed ligand complexes were calculated on the basis of vanadium content at respective  $\lambda_{\max}$  as shown in Table I. It is observed that the position of  $\lambda_{\max}$  is not appreciably effected by the substitution of N-phenyl or N'-phenyl ring. However, the absorptivity of the complex is affected markedly by the substitution of both phenyl rings. An alkyl group, introduced in the N'-phenyl ring, greatly affected the absorptivity of the complex. The substitution of this phenyl ring resulted into hyperchromic shift, the order being 2,4-( $\text{CH}_3$ )<sub>2</sub> > 2,3-( $\text{CH}_3$ )<sub>2</sub> > o- $\text{CH}_3$  > p- $\text{CH}_3$  > m- $\text{CH}_3$  (Comp. 1-4, 6 and 8), and hypochromic shift in the order 2,6-( $\text{CH}_3$ )<sub>2</sub> > p-( $\text{OCH}_3$ ) (Comp. 1, 5 and 7). The substitution of N-phenyl ring also showed hyperchromic shift in the order p-Cl > m-Cl > p- $\text{CH}_3$  (Comp. 8-11).

TABLE I—SPECTRAL DATA OF VANADIUM (V)-THIOCYANATE COMPLEXES WITH HYDROXYAMIDINES IN CHLOROFORM



Sl. No.	X	Y	$\lambda_{\max}$ nm	$\epsilon$ 1.mol <sup>-1</sup> cm <sup>-1</sup>	Sandell's sensitivity $\mu\text{g V cm}^{-2}$
1.	H -	m-Cl -	595	4800	0.01061
2.	o- $\text{CH}_3$ -	m-Cl -	600	5400	0.00948
3.	m- $\text{CH}_3$ -	m-Cl -	600	4800	0.01061
4.	p- $\text{CH}_3$ -	m-Cl -	595	4800	0.01061
5.	p- $\text{OCH}_3$ -	m-Cl -	595	4700	0.01088
6.	2,5-( $\text{CH}_3$ ) <sub>2</sub> -	m-Cl -	600	6100	0.00835
7.	2,6-( $\text{CH}_3$ ) <sub>2</sub> -	m-Cl -	600	3800	0.01548
8.	2,3-( $\text{CH}_3$ ) <sub>2</sub> -	m-Cl -	600	6000	0.00849
9.	2,3-( $\text{CH}_3$ ) <sub>2</sub> -	H -	600	5250	0.00970
10.	2,3-( $\text{CH}_3$ ) <sub>2</sub> -	p- $\text{CH}_3$ -	610	5650	0.00901
11.	2,3-( $\text{CH}_3$ ) <sub>2</sub> -	p-Cl -	605	6250	0.00815

No. 1, 4 and 5 are free bases.

As expected from the above observation, N-hydroxy-N'-p-chlorophenyl-N''-(2,3-dimethyl)phenylbenzamidinium hydrochloride is found to be the most sensitive reagent in the present investigation.

**Concentration ranges, molar absorbance, sensitivity and precision of the method:** The effective molar absorptivities of the coloured complexes lie in the range of  $3.30 - 6.25 \times 10^3$  l. mol<sup>-1</sup> cm<sup>-1</sup> and the sensitivities<sup>16</sup> of the reaction lie between 0.003-0.015  $\mu\text{g V cm}^{-2}$  as shown in Table I. The method obeys Beer's law upto 7.2 ppm of vanadium. The optimum concentration range on the basis of Ringbom plot<sup>10</sup> lie between 1.2-6.8 ppm of the metal. The mean absorbance value and relative standard deviation of the method are found to be 0.490 and  $\pm 0.67\%$ , respectively (results of 10 measurements, each containing 100  $\mu\text{g V/25 ml}$ ).

**Composition of the complex:** The ratio of vanadium(V) to hydroxyamidine of thiocyanate was studied by mole ratio<sup>17</sup>, slope ratio<sup>18</sup> and Job's method of continuous variation<sup>19</sup>. The results obtained indicated that the complex consists of 2 molecules each of hydroxyamidine and thiocyanate for each molecule of vanadium. The probable composition of the neutral mixed complex is  $\text{VO}_2\text{SCN.OA.HOA}$ .

**Effect of diverse ions:** The effect of various ions in the separation and subsequent spectrophotometric determination of vanadium(V) was studied, following the recommended procedure. Chloride, bromide, nitrate, sulphate, borate, phosphate, triethanolamine, alkali and alkaline-earth elements did not interfere upto 2000 ppm. Fe(III) interfered due to coextraction of its ternary complex but its interference could be eliminated by masking it with trisodium phosphate. Mo(VI) is also coextracted



as a binary yellowish complex but did not interfere at the absorption maxima. The interference of Cu(II) was eliminated by masking it with thiourea. The tolerated amount\* of other ions (in ppm), in the determination of 4 ppm of vanadium(V) are shown in parenthesis: Cd<sup>2+</sup>, Zn<sup>2+</sup> (1000); Cu<sup>2+</sup> (1200); Ni<sup>2+</sup> (500); Co<sup>2+</sup> (400); Mn<sup>2+</sup> (600); Cr<sup>3+</sup> and Al<sup>3+</sup> (500 ppm); Cs<sup>+</sup>, Rb<sup>+</sup>, La<sup>3+</sup> (1000); Fe<sup>3+</sup>, Bi<sup>3+</sup>, Th<sup>4+</sup> (800); Zr<sup>4+</sup> (80), Ti<sup>4+</sup> (80); Nb<sup>5+</sup> (60); Mo<sup>6+</sup> (80); W<sup>6+</sup> (40); U<sup>6+</sup> (400); F<sup>-</sup> (400); I<sup>-</sup> (500); IO<sub>3</sub><sup>-</sup> (100); arsenate (400).

**Application of the method:** The method has been applied successfully to three BCS steels, two V-W steels (64a and 241/1) and one tungsten free steel (252). The results of the determinations are summarized in Table 2.

TABLE 2—DETERMINATION OF VANADIUM IN VARIOUS BCS STEELS

Sample	Vanadium found <sup>a</sup> %	Certified %	Standard deviation
64a Alloy steel	1.553	1.57	± 0.0005
241/1 High speed steel	1.551	1.57	± 0.0051
252 Low alloy steel	0.450	0.46	± 0.0064

<sup>a</sup> = An average of six determinations

BCS = British Chemical Standard, Bureau of Analysed Samples Ltd, Newham Hall, Middlebrough, Yorks.

The sample containing about 2 mg of vanadium was dissolved in dilute nitric acid and oxides of nitrogen were removed by boiling. The insoluble matters were removed by filtration. The filtrate was made up to 250 ml in a volumetric flask and vanadium content of the sample was determined as mentioned in the recommended procedure.

\* Error less than 2%.

#### Acknowledgement

Thanks of the authors are due to Prof. S. G. Tandon, Head, Dept. of Chemistry, Ravishankar University, Raipur for facilities and to C.S.I.R., New Delhi, for awarding a Senior Research Fellowship to one of them (A.R.I.).

#### References

1. K. SATYANARAYANA and R. K. MISHRA, *Anal. Chem.*, 1974, 46, 1809
2. K. S. PATEL and R. K. MISHRA, *J. Indian Chem. Soc.*, 1979, 55, 469, 773.
3. K. S. PATEL, K. K. DEB and R. K. MISHRA, *Sepa. Sci.*, 1979, 14, 393, 815.
4. A. R. JHA and R. K. MISHRA, *Analyst*, 1981, 106, 1150.
5. R. S. KHARSEN and R. K. MISHRA, *Z. anal. Chem.*, 1979, 295, 415.
6. I. M. KOLTHOFF and E. B. SANDELL, "A Text Book of Quantitative Inorganic Analysis", The Macmillan Co., New York, 1952, p. 86.
7. S. C. SHOME, *Analyst*, 1950, 75, 27.
8. N. C. SOGANI and S. C. BHATTACHARVA, *Anal. Chem.*, 1956, 28, 81.
9. U. PRIYADARSHINI and S. G. TANDON, *Anal. Chem.*, 1961, 33, 435.
10. H. GOTO and Y. KAKITA, *Bunseki Kagaku*, 1961, 10, 904.
11. A. D. SHENDRIKAR, *Talanta*, 1969, 16, 51.
12. V. P. R. RAO and Y. ANJANEYULU, *Mikrochim. Acta*, 1973, 4, 491.
13. E. M. DONALDSON, *Talanta*, 1975, 17, 583.
14. G. CHARLOT and D. BRIZIER, "Quantitative Inorganic Analysis", John Wiley, New York, 1967.
15. E. B. SANDELL, "Colorimetric Determination of Traces of Metals", Interscience Publishers Inc., New York, 1959, p. 936.
16. A. RINGBOM, *Z. anal. Chem.*, 1939, 115, 393.
17. A. E. HARVEY and D. L. MANNING, *J. Amer. Chem. Soc.*, 1950, 72, 4488.
18. J. H. YOE and A. L. JONES, *Ind. Eng. Chem. Anal. Ed.*, 1944, 16, 111.
19. P. JOB, *Ann. Chim., (Paris)*, 1928, 9, 113.

# NOTES

## A Study of the Decomposition Patterns of Some Transition Metal Complexes Derived mainly from the Heterocyclic Ligands viz., Furan-2-carboxaldoxime and 3-Methyl-4-arylazopyrazole-5-one using Thermo-gravimetric Analysis

(Mrs.) P. R. SHUKLA, CHANDRESHWARI SRIVASTAVA

and

V. K. SINGH

Department of Chemistry, University of Lucknow, Lucknow  
and

GOPAL NARAIN

Department of Chemistry, University of Sagar, Sagar

Manuscript received 23 November 1981, revised 30 April 1982,  
accepted 21 July 1982

AMONG the methods finding extensive use in characterisation of transition metal complexes, TGA is one of the most recent methods. Besides indicating the presence of coordinating groups in a complex molecule, it describes in detail the decomposition pattern for the complex. In the present paper the TGA data in the temperature range 20-800° of some complexes of Cu(II), Ni(II) and Co(II) containing either of the two title ligands along with one or more water molecules and an heterocyclic amine or diamine, are described.


## Experimental


The two types of complexes used in the study are derived from either the neutral or the anionic form of antifuran-2-carboxaldoxime or 3-methyl-4-(*p*-methylphenylazo)pyrazole-5-one as primary ligand and water, pyridine (py), picoline (pic), aniline (an), ethylenediamine (en), propylenediamine (pn), 2-2'-bipyridyl (bipy) or *o*-phenanthroline (phen) as secondary ligand. The preparation and characterisation of the complexes were reported in a previous communication<sup>1-3</sup>. The Cu(II) complexes were assigned planar and Ni(II) and Co(II) complexes octahedral structure, respectively.

## Results and Discussion

**Complexes derived from antifuran-2-carboxaldoxime:** The various complexes which have been subjected to TGA study are of the type [Co or Ni(FDH)<sub>2</sub>dam]Cl<sub>2</sub>; [Co(FDH)<sub>2</sub>](NO<sub>3</sub>)<sub>2</sub>; [Ni(FD)<sub>2</sub>dam] where FDH and FD refer to the neutral and the anionic form of the oxime and dam stands for ethylenediamine (en), propylenediamine (pn), 2-2'-bipyridyl (bipy) or *o*-phenanthroline (phen)<sup>1-3</sup>. The general decomposition pattern of some of the complexes of different categories is as given below.

It appears from the above equations that in most of the complexes a slight decomposition











begins at 80 or 100° and continues up to 120° and corresponds to the loss of water. This is the range in which the lattice water is lost and hence these water molecules are not coordinated as indicated in the formulae of complexes. No decomposition occurs between 120-180°. The two chloride ions are lost between 180-200°. From 220° to 280° there is a very sharp decrease in weight due to the loss of oxime and different amines. The complex is

changed to the simple metal oxide above 500° and the curve then becomes a straight line.

*Complexes derived from 3-methyl-4-(p-methylphenylazo)pyrazole-5-one:* The TGA studies of the free azo compound (PyrH  $\text{C}_{11}\text{H}_{11}\text{N}_4\text{O}$ ), its two complexes with Cu(II) and Ni(II) sulphates, free Cu(II) and Ni(II)-3-methyl-4-(p-methylphenylazo)-5-pyrazolonates  $[\text{M}(\text{C}_{11}\text{H}_{11}\text{N}_4\text{O})_2]$  and their complexes<sup>4,5</sup> with different amines are described in the following equations.



It appears from the above equations that the lattice water is lost between 80-120°, while the co-ordinated water is lost at slightly higher temperature around 280°. The coordinated amine usually decomposes in the range 140-200°, the individual temperature, however, varies with the nature of amine and complex. The azo groups are lost completely around 380° and thereafter, the formation of the metal oxide occurs and no decomposition takes place upto 1000°.

#### References

1. P. R. SHUKLA and V. K. SINGH, *J. Indian Chem. Soc.*, (accepted).
2. P. R. SHUKLA, V. K. SINGH and J. BHARGAVA, *J. Indian Chem. Soc.*, 1982, 59, 620.
3. P. R. SHUKLA and V. K. SINGH, *J. Indian Chem. Soc.*, (communicated).
4. P. R. SHUKLA and O. SRIVASTAVA, *J. Indian Chem. Soc.*, 1981, 58, 937.
5. P. R. SHUKLA and C. SRIVASTAVA, *J. Indian Chem. Soc.*, (communicated).

### Mixed Ligand Complexes of Zinc(II) with Dibasic Acids and Nitrogen Donor Ligands

P. C. PADHW and R. N. PATEL\*

Department of Chemistry, Regional Engineering College,  
Bourkela-796 008

Manuscript received 7 August 1981, revised 22 January 1982,  
accepted 8 July 1982

As a part of the programme on d<sup>10</sup> metal complexes, some penta-coordinated zinc(II) complexes with nitrogen and sulphur donor ligands were reported<sup>1-3</sup> earlier from this laboratory. More recently Sharma and Jain reported<sup>4</sup> some mixed ligand complexes of nickel(II) with dibasic acids and primary and heterocyclic amines as secondary ligands. This communication reports some penta-coordinated mixed ligand complexes of zinc(II) succinate, malonate, glutarate or adipate with

thiocyanate and nitrogen donor ligands like  $\alpha$ -picoline and morpholine.

#### Experimental

Ethanolic solutions of zinc chloride, the organic acid and potassium thiocyanate were mixed in stoichiometric ratio and filtered directly into an ethanolic solution of  $\alpha$ -picoline or morpholine. The resulting precipitate was suction filtered, washed with ethanol and ether, recrystallised from carbon tetrachloride/methanol and dried *in vacuo*.

Zinc, thiocyanate and nitrogen were estimated by standard methods. Carbon and hydrogen were microanalysed. The conductance measurements were carried out on 10<sup>-3</sup> M solutions in pyridine using Toshniwal conductivity bridge, type CL 0102, with a dip type cell. Infrared spectra were recorded in the region 4000-400 cm<sup>-1</sup> by Perkin Elmer spectrophotometer in KBr pellets. Thermogravimetric studies<sup>5</sup> were carried out in a manually operated thermobalance. Analytical and physical data for the complexes are recorded in Table I.

As the  $\alpha$ -picoline complexes take up moisture and decompose due to hydrolysis, these were kept in a desiccator over anhydrous CaCl<sub>2</sub>.

#### Results and Discussion

The molar conductance values (Table I) of all the compounds indicate them to be 1 : 1 electrolytes. In the ir spectra, the stretching bands due to C=C of malonic, succinic, glutaric and adipic acids at 1724, 1730, 1695 and 1700 cm<sup>-1</sup>, respectively have been lowered to 1630, 1635, 1630 and 1610 cm<sup>-1</sup> in the corresponding complexes indicating the coordination of acids through carboxylate oxygen<sup>6</sup>. The bands appearing at 2050-2080 and 785-860 cm<sup>-1</sup> due to  $\nu$  (C-N) and  $\nu$  (C-S), respectively indicate the presence of N-bonded thiocyanate group<sup>7</sup>. The bands at  $\sim$ 3210 and  $\sim$ 1115 cm<sup>-1</sup>, due to

TABLE I—ANALYTICAL AND PHYSICAL DATA OF MIXED LIGAND ZINC(II) COMPLEXES


Compound	m.p. °C	%Zn	%thio- cyanate	%N	%C	%H	$\Delta$ M mhos <sup>‡</sup>
K[Zn( $\alpha$ -pic)M.H <sub>2</sub> O(NOS)]	210(d)	17.23 (17.41)*	15.2 (15.45)	7.55 (7.41)	81.81 (81.78)	3.01 (2.93)	66
K[Zn( $\alpha$ -pic)S.H <sub>2</sub> O(NOS)]	200(d)	16.52 (16.79)	14.76 (14.83)	7.00 (7.17)	33.67 (33.88)	3.42 (3.36)	68
K[Zn( $\alpha$ -pic)G.H <sub>2</sub> O(NOS)]	230(d)	16.02 (16.20)	14.27 (14.37)	6.78 (6.90)	35.34 (35.51)	3.90 (3.72)	74
K[Zn( $\alpha$ -pic)A.H <sub>2</sub> O(NOS)]	250(d)	15.41 (15.65)	13.76 (13.90)	6.42 (6.57)	37.00 (37.18)	3.8 (4.0)	70
K[Zn(moph)M.H <sub>2</sub> O(NOS)]	112	17.42 (17.69)	15.58 (15.73)	7.67 (7.57)	26.74 (26.98)	3.62 (3.54)	71
K[Zn(moph)S.H <sub>2</sub> O(NOS)]	105	16.88 (17.05)	15.01 (15.12)	7.29 (7.30)	27.98 (28.16)	4.08 (3.94)	69
K[Zn(moph)G.H <sub>2</sub> O(NOS)]	138	16.27 (16.45)	14.51 (14.60)	6.86 (7.04)	30.00 (30.19)	4.50 (4.31)	78
K[Zn(moph)A.H <sub>2</sub> O(NOS)]	172	15.66 (15.89)	14.00 (14.10)	6.57 (6.80)	31.84 (32.08)	4.74 (4.65)	75

\* Figures in parentheses indicate calculated values. M=malonate, S=succinate,  
G=glutarate and A=adipate.  $\alpha$ -pic= $\alpha$ -picoline, moph=morpholine, d=decomposed.

‡ Based on theoretical values of molecular weight.

$\nu(\text{N}-\text{H})$  stretch and  $\nu(\text{C}-\text{O}-\text{C})$  stretch show -ve and +ve shift respectively with respect to free morpholine and indicate morpholine coordinates through nitrogen atom<sup>6</sup>. Similarly, the sharp bands at  $\sim 2940$  and  $\sim 1040\text{ cm}^{-1}$  are attributed to the presence of N-coordinated  $\alpha$ -pic<sup>7</sup>. The broad band at  $\sim 3400\text{ cm}^{-1}$  and sharp band at  $\sim 870\text{ cm}^{-1}$  in both the complexes indicates the presence of coordinated water molecule<sup>8</sup>.

**Thermal decomposition:** Thermal decomposition of morpholine complexes reveals no weight loss at  $100^\circ$  indicating that the water molecules are not in the lattice. The different products from the weight loss obtained by thermal decomposition are as follows:



where L = anion of dibasic acids.

In the light of the above evidences, it is suggested that all the complexes are five coordinated anionic complexes.

#### Acknowledgement

One of the authors (P. C. P.) is grateful to the management of Rourkela Steel Plant for kind help.

#### References

1. B. K. MOHAPATRA and D. V. RAMANA RAO, *Z. anorg. allg. Chem.*, 1970, 372, 332
2. B. K. MOHAPATRA and D. V. RAMANA RAO, *Indian J. Chem.*, 1973, 11, 284
3. B. PRADHAN and D. V. RAMANA RAO, *Indian J. Chem.*, 1976, 14A, 535.
4. O. L. SHARMA and P. K. JAIN, *J. Indian Chem. Soc.*, 1979, 56, 756.
5. K. NAKAMATO, "Infrared Spectra of Inorganic and Coordination Compounds", John Wiley and Sons, New York, 1970.
6. G. MARCATRIGIANO, Q. BAITISTUZZI and G. G. PELLACANI, *Canad. J. Chem.*, 1971, 50, 2257.
7. N. N. GREEN and K. WADA, *J. Chem. Soc.*, 1958, 1667.

### Mixed Ligand Complexes of Cobalt(II) and Cadmium(II) with Oxine as Primary Ligand and Heterocyclic and Aromatic Amines as Secondary Ligands

BIPIN B. MAHAPATRA and S. K. PUJARI

Department of Chemistry, G. M. College, Sambalpur, Orissa

Manuscript received 12 November 1981, revised 11 June 1982, accepted 21 July 1982

**O**XINE is known to possess both antifungal and antibacterial properties<sup>1-3</sup>. It also behaves as an uninegative bidentate chelating ligand having ON potential donor sites. The present note describes the synthesis and characterisation of some

mixed ligand complexes of cobalt(II) and cadmium(II) with nitrogen donor heterocyclic and aromatic bases.

#### Experimental

All the chemicals used were of A.R. grade.

**Preparation of metal oxinates:** To an aqueous solution of metal chloride (2.36 g in case of cobaltous chloride and 2.01 g in case of cadmium chloride), sodium acetate (5 g) was added and warmed to  $65-70^\circ$ . The ethanolic solution of oxine (3.0 g) was added to it separately when light brown amorphous cobalt oxinate or light yellow amorphous cadmium oxinate separated out immediately. The metal oxinates thus formed were allowed to stand overnight and then filtered, washed with ethanol followed by ether and dried *in vacuo*.

**Preparation of mixed ligand complexes:** To an ethanolic suspension of metal oxinate nitrogen donor ligands were added separately and refluxed for 1-2 hr. The compounds were then filtered, washed with ethanol, ether and dried *in vacuo*.

The metal contents of the complexes were estimated by EDTA titration method and nitrogen by microanalytical method. Conductance of the complexes was measured in  $10^{-3}\text{ M}$  acetone solution using a Toshniwal conductivity bridge. IR spectra were recorded on KBr phase using Beckman IR-20 spectrophotometer. Electronic spectra of cobalt(II) complexes were recorded in  $10^{-3}\text{ M}$  DMF-base solution using Hilgerwatt Uvispeck spectrophotometer. Analytical data of the complexes prepared are given in Table 1.

#### Results and Discussion

Complexes reported in the present investigation are of the type  $[\text{ML}_2\text{L}']$  and  $[\text{ML}_2\text{L}']$  where M = cobalt(II), cadmium(II); LH = oxine; L' = pyridine,  $\beta$ -picoline,  $\gamma$ -picoline, quinoline, piperidine, 2,6-lutidine, 4-aminopyridine, quinaldine, morpholine; L' = o-phenylenediamine, 1,10-phenanthroline or 2,2'-bipyridine. The complexes show low conductance values in acetone medium ( $\Delta_M$  ranges from 8.5 to 15 mhos  $\text{cm}^2$ ) indicating their non-electrolytic nature.

IR spectra of the ligand, metal oxinate and mixed ligand complexes are informative. The IR active bands at 1500, 1280 and  $900\text{ cm}^{-1}$  can be assigned to the phenolic OH deformation modes coupled with C-O stretching modes ( $\nu_{\text{CO}} + \nu_{\text{OH}}$ ) and to the out of plane deformation vibration ( $\sigma_{\text{OH}}$ ), respectively. The absence of these bands in the spectra of the metal oxinates indicates that the proton of the hydroxyl group is replaced by the metal ions. The bands at 1450, 1260, 1095 and  $1060\text{ cm}^{-1}$  in the spectra of both heterocyclic ligands and mixed ligand complexes are characteristic of substituted pyridine ring vibration<sup>4</sup>. A medium broad band appears at  $\sim 3450\text{ cm}^{-1}$  region in case of metal oxinates assignable to  $\nu(\text{O}-\text{H})$  or

TABLE 1—ANALYSIS AND MAGNETIC SUSCEPTIBILITY DATA

Sl. No.	Compound	% Metal	% N	$\mu_{\text{eff}}$ B.M.
		Found (Calcd.)	Found (Calcd.)	
1.	$\text{CoL}_2(\text{Py})_2$	11.59 (11.56)	10.97 (11.09)	4.9
2.	$\text{CoL}_2(\beta\text{-Pic})_2$	11.00 (11.09)	10.48 (10.54)	5.1
3.	$\text{CoL}_2(\gamma\text{-Pic})_2$	10.97 (11.09)	10.52 (10.54)	4.9
4.	$\text{CoL}_2(\text{Q})_2$	9.68 (9.73)	9.20 (9.25)	4.9
5.	$\text{CoL}_2(\text{Pip})_2$	11.95 (11.79)	10.73 (10.82)	4.9
6.	$\text{CoL}_2(2,6\text{-Lut})_2$	10.48 (10.57)	10.02 (10.06)	5.0
7.	$\text{CoL}_2(\text{Quin})_2$	9.27 (9.30)	8.76 (8.84)	4.8
8.	$\text{CoL}_2(4\text{-AP})_2$	10.94 (11.01)	10.38 (10.48)	4.9
9.	$\text{CoL}_2(\text{Mor})_2$	11.26 (11.30)	10.63 (10.75)	4.9
10.	$\text{CoL}_2,o\text{-PhDA}$	12.88 (12.94)	12.27 (12.81)	4.9
11.	$\text{CoL}_2,1,10\text{-Phe}$	11.08 (11.17)	10.58 (10.62)	5.0
12.	$\text{CoL}_2,2\text{-}2'\text{-bipy}$	11.68 (11.71)	11.10 (11.13)	5.0
13.	$\text{CdL}_2(\text{Py})_2$	19.95 (20.12)	9.97 (10.02)	—
14.	$\text{CdL}_2(\beta\text{-Pic})_2$	19.17 (19.23)	9.51 (9.58)	—
15.	$\text{CdL}_2(\gamma\text{-Pic})_2$	19.15 (19.23)	9.48 (9.58)	—
16.	$\text{CdL}_2(\text{Q})_2$	16.94 (17.07)	8.43 (8.50)	—
17.	$\text{CdL}_2(2,6\text{-Lut})_2$	18.28 (18.41)	9.12 (9.17)	—
18.	$\text{CdL}_2(\text{Pip})_2$	19.68 (19.70)	9.76 (9.81)	—
19.	$\text{CdL}_2,o\text{-PhDA}$	22.04 (22.10)	10.97 (11.01)	—

Py = pyridine,  $\beta$ -Pic =  $\beta$ -picoline,  $\gamma$ -Pic =  $\gamma$ -picoline,  
Q = quinoline, Pip = piperidine, 2,6-Lut = 2,6-lutidine,  
Quin = quinaldine, 4-AP = 4-amino-pyridine, Mor = morpholine,  
o-PhDA = o-phenylenediamine, 1,10-Phe = 1,10-phenanthroline,  
2-2'-bipy = 2-2'-bipyridine.

coordinated water molecules and its conspicuous absence in the mixed ligand complexes support the coordination of nitrogen donor ligands to the metal ions.

In the electronic spectra the cobalt(II) complexes in DMF solution give rise to two absorption bands with maxima around 8.6 and 19.7 kK region which can be assigned\* to  ${}^4\text{T}_{1g} \rightarrow {}^4\text{T}_{2g}$  (F) and  ${}^4\text{T}_{1g} \rightarrow {}^4\text{T}_{1g}$  (P) transitions. These absorption bands along with its magnetic moment values indicate a high-spin octahedral configuration for cobalt(II) complexes.

All the cadmium(II) complexes are six-coordinated on the basis of analysis, conductance and ir spectral studies.

#### References

1. A. ALBERT, "Selective Toxicity", Methuen, London, 1960.
2. A. ALBERT, "The Strategy of Chemotherapy", Symposium, Soc. Gen. Microbiol., 1958, 8, 112.

3. R. C. CHARLES, H. FREISER, R. FRIEDAL, L. E. HILLARD and W. D. JOHNSTON, *Spectrochim. Acta*, 1966, 8, 1.
4. H. SHINDO, *Pharm. Bull.*, 1957, 5, 472.
5. I. GAMO, *Bull. Chem. Soc.*, 1961, 34, 760.
6. A. B. P. LEVER, "Inorganic Electronic Spectroscopy", Elsevier, Amsterdam, New York.

### Complexes of Co(II), Ni(II), Cr(III), Mn(III) and Fe(III) with Schiff Bases Derived from Bis-p(Aminophenyl) Sulphide and 2-Acetyl Thiophene Glyoxal

H. S. VERMA\* and ANANG PAL

Department of Chemistry, J. V. College, Baraut-250 611


and

R. C. SAXENA and J. L. VATS

Department of Chemistry, M. M. College, Modinagar-201 204

Manuscript received 11 September 1980, revised 5 December 1981  
accepted 1 May 1982

IN continuation to our work<sup>1-3</sup> on Schiff base complexes, present note describes the preparation and characterisation of complexes of Co(II), Ni(II), Cr(III), Mn(III) and Fe(III) with the Schiff base (I). Conductance, magnetic moment, electronic and infrared spectra of the complexes have been studied.



I

#### Experimental

The ligand was prepared by taking the bis-p(aminophenyl) sulphide and 2-acetyl thiophene glyoxal in dioxane in equimolar quantities and refluxed for about 1 hr. The refluxed mass was poured into ice cold water when an orange coloured mass separated out. It was dried in a vacuum desiccator and recrystallised from ethanol. Bright orange coloured fine crystals, m.p. 186°, were obtained.

A general procedure was adopted to synthesise the complexes by mixing Co(II), Ni(II), Cr(III), Mn(III) and Fe(III) chloride (10 m mole each) in 25 ml acetone with 10 m mole of the ligand separately. The reaction mixture was refluxed for 30 min and concentrated in a vacuum desiccator, yielding the coloured crystalline material. The crystals were washed with ether and dried.

The analysis of carbon, nitrogen and sulphur were done at the micro analytical section of C. D. R. I., Lucknow. The chloride was estimated by Volhard's method. The metal contents in all

\* Author for correspondence.

## NOTES

TABLE 1—ANALYTICAL DATA, FORMULAE AND OTHER PROPERTIES OF THE COMPLEXES

Complex	Colour	m.p. °C	Analysis %					$\mu_{\text{eff}}$ B.M.
			M	O	N	S	Cl	
[CoLCl <sub>2</sub> .H <sub>2</sub> O]	grey	199d	12.47 (12.12)*	43.20 (44.45)	5.38 (5.76)	13.38 (13.17)	14.90 (14.61)	4.89
[NiLCl <sub>2</sub> .H <sub>2</sub> O]	dark green	167d	12.32 (12.08)	45.50 (44.47)	5.80 (5.76)	13.42 (13.17)	14.87 (14.50)	2.98
[CrL <sub>2</sub> ]Cl <sub>2</sub>	black	189d	6.52 (6.23)	50.20 (51.76)	6.92 (6.71)	15.58 (15.33)	13.00 (12.76)	3.86
[MnL <sub>2</sub> ]Cl <sub>2</sub>	grey	200d	6.60 (6.56)	51.42 (51.58)	6.70 (6.68)	14.20 (14.09)	12.76 (12.71)	4.80
[FeL <sub>2</sub> ]Cl <sub>2</sub>	dark	208d	6.90 (6.66)	50.30 (51.53)	6.43 (6.67)	15.41 (15.26)	12.56 (12.30)	5.84

\* Figures within the parentheses are Calcd. values L-C<sub>12</sub>H<sub>14</sub>N<sub>2</sub>S<sub>2</sub>O. d—decomposed.

TABLE 2—ELECTRONIC SPECTRA AND LIGAND FIELD PARAMETERS

Complex	Bands cm <sup>-1</sup>	Assignments	10Dq cm <sup>-1</sup>	B cm <sup>-1</sup>	$\beta$	L.F.S.E. Kcal/mole
[CoLCl <sub>2</sub> .H <sub>2</sub> O]	9700	<sup>4</sup> T <sub>1g</sub> (F)→ <sup>4</sup> T <sub>2g</sub> (F)	—	843	0.76	13.86
	17680	→ <sup>4</sup> A <sub>1g</sub> (F)				
	22000	→ <sup>4</sup> T <sub>1g</sub> (P)				
[NiLCl <sub>2</sub> .H <sub>2</sub> O]	10000	<sup>3</sup> A <sub>1g</sub> (F)→ <sup>3</sup> T <sub>2g</sub> (F)	10000	886	0.82	34.28
	17756	→ <sup>3</sup> T <sub>1g</sub> (F)				
	20090	→ <sup>3</sup> T <sub>1g</sub> (P)				
[CrL <sub>2</sub> ]Cl <sub>2</sub>	14250	<sup>4</sup> A <sub>1g</sub> (F)→ <sup>3</sup> E <sub>g</sub>	18400	700	0.82	31.54
	18400	→ <sup>4</sup> T <sub>2g</sub> (F)				
	23270	→ <sup>4</sup> T <sub>1g</sub> (F)				
	38400	→ <sup>4</sup> T <sub>1g</sub> (P)				
[MnL <sub>2</sub> ]Cl <sub>2</sub>	17980	<sup>6</sup> B <sub>1g</sub> → <sup>6</sup> T <sub>2g</sub>	17980	832	0.73	30.82
	13200	→ <sup>6</sup> A <sub>1g</sub>				
	11000	→ <sup>6</sup> B <sub>2g</sub>				
	29580	→ <sup>6</sup> E <sub>g</sub>				
[FeL <sub>2</sub> ]Cl <sub>2</sub>	11780	<sup>4</sup> A <sub>1g</sub> → <sup>4</sup> T <sub>1g</sub> (G)	11780	786	0.56	—
	19380	→ <sup>4</sup> T <sub>2g</sub> (G)				
	27010	→ <sup>4</sup> T <sub>1g</sub> (P)				

TABLE 3—IR SPECTRA (cm<sup>-1</sup>)

L	[CoLCl <sub>2</sub> .H <sub>2</sub> O]	[NiLCl <sub>2</sub> .H <sub>2</sub> O]	[CrL <sub>2</sub> ]Cl <sub>2</sub>	[MnL <sub>2</sub> ]Cl <sub>2</sub>	[FeL <sub>2</sub> ]Cl <sub>2</sub>	Tentative assignments
1250(w)	1245(w)	1246(w)	1220(w)	1220(w)	1230(w)	$\nu(\text{C}=\text{S})$
1650(s)	1630(s)	1635(s)	1590(s)	1610(s)	1610(s)	$\nu(\text{OH}=\text{N})$
1700(s)	1675(s)	1680(s)	1660(s)	1660(s)	1655(s)	$\nu(\text{C}=\text{O})$
—	485(m)	490(m)	460(m)	545(m)	540(m)	$\nu(\text{M}-\text{O})$
—	470(m)	475(m)	480(m)	470(m)	460(m)	$\nu(\text{M}-\text{N})$
—	350(s)	355(s)	375(s)	330(s)	325(s)	$\nu(\text{M}-\text{S})$
—	230(m)	275(m)	—	—	—	$\nu(\text{M}-\text{Cl})$

s=strong, m=medium and w=weak.

these complexes were estimated by complexometric titrations with EDTA<sup>4</sup>. The physical measurements viz., magnetic susceptibility (Gouy's balance), infrared spectra (Perkin-Elmer infrared spectrophotometer model-521, fitted with NaCl and KBr optics), absorption spectra (UNICAM SP-500 spectrophotometer) and molar conductance (Philips conductivity bridge, type LBRB) were recorded at room temperature.

### Results and Discussion

The complexes under investigation are listed in Table 1 along with their colour, analysis and other properties. The decomposition temperatures

indicate that the complexes are thermally stable. The values of observed magnetic moments show the paramagnetic nature of the chelate and are in agreement with the generally accepted values for high spin octahedral complexes, thus forming  $sp^3d^2$  type of bonding. The molar conductance of these complexes in DMF at  $10^{-3}$  M indicates the non-electrolytic nature of Co(II) and Ni(II) complexes and univalent nature of Cr(III), Mn(III) and Fe(III) complexes.

The electronic spectra (Table 2) of Co(II), Ni(II) and Fe(III) complexes show three bands appearing at  $9700\text{ cm}^{-1}$  [<sup>4</sup>T<sub>1g</sub>(F)→<sup>4</sup>T<sub>2g</sub>(F)],  $17580\text{ cm}^{-1}$  [<sup>4</sup>T<sub>1g</sub>(F)→<sup>4</sup>A<sub>1g</sub>(F)],  $22000\text{ cm}^{-1}$  [<sup>4</sup>T<sub>1g</sub>(F)→

${}^4T_{1g}(P)$ ,  $10000\text{ cm}^{-1}$  [ ${}^3A_{2g}(F) \rightarrow {}^3T_{2g}(F)$ ],  $17756\text{ cm}^{-1}$  [ ${}^3A_{2g}(F) \rightarrow {}^3T_{1g}(F)$ ],  $26030\text{ cm}^{-1}$  [ ${}^3A_{2g}(F) \rightarrow {}^3T_{1g}(P)$ ] and  $11780\text{ cm}^{-1}$  [ ${}^3A_{1g} \rightarrow {}^4T_{1g}(G)$ ],  $19380\text{ cm}^{-1}$  [ ${}^3A_{1g} \rightarrow {}^4T_{2g}(G)$ ],  $27010\text{ cm}^{-1}$  [ ${}^3A_{1g} \rightarrow {}^4T_{1g}(P)$ ], respectively. The complexes of Cr(III) and Mn(III) show four bands in their electronic spectra appearing at  $14250\text{ cm}^{-1}$  [ ${}^4A_{2g}(F) \rightarrow {}^6E_g$ ],  $18400\text{ cm}^{-1}$  [ ${}^4A_{2g}(F) \rightarrow {}^4T_{2g}(F)$ ],  $23270\text{ cm}^{-1}$  [ ${}^4A_{2g}(F) \rightarrow {}^4T_{1g}(F)$ ],  $38400\text{ cm}^{-1}$  [ ${}^4A_{2g}(F) \rightarrow {}^4T_{1g}(P)$ ] and  $11000\text{ cm}^{-1}$  [ ${}^3B_{1g} \rightarrow {}^3B_{2g}$ ],  $13200\text{ cm}^{-1}$  [ ${}^3B_{1g} \rightarrow {}^3A_{1g}$ ],  $17980\text{ cm}^{-1}$  [ ${}^3B_{1g} \rightarrow {}^3E_g$ ],  $29580\text{ cm}^{-1}$  [ ${}^3B_{1g} \rightarrow {}^3E_g$ ], respectively. The values of  $\beta$  of these complexes indicate the partial covalent character of the metal-ligand bond.

Infrared spectral data for the ligand and its complexes are given in Table 3.  $\nu(C-S)$ ,  $\nu(CH=N)$  and  $\nu(C=O)$  are lowered on complex formation by 15 to 45 units indicating that these groups are participating in chelation. Bands appearing at  $230\text{ cm}^{-1}$  and  $275\text{ cm}^{-1}$  in Co(II) and Ni(II) complexes, respectively are assignable to metal-chlorine stretching mode<sup>6</sup>.

#### References

1. R. O. SAXENA, O. L. JAIN, S. C. RASTOGI and H. S. VERMA, *Indian J. Chem.*, 1978, 16A, 167.
2. H. S. VERMA and R. O. SAXENA, *Z. Naturforsch.*, 1978, 33b, 1001.
3. H. S. VERMA and R. O. SAXENA, *Curr. Sci.*, 1978, 47, 791.
4. G. SCHWARZENBACK, "Complexometric Titrations", Interscience, New York, 1957.
5. D. P. MILLON and L. MALEY, *Nature*, 1948, 159, 370.

### Azo Complexes : Complexes of Alkali Metal Salts of Some Organic Acids with *o*-Hydroxybenzeneazo-2-Naphthol

A. K. BANERJEE, TARKESHWAR SINGH and S. K. ROY

Department of Chemistry, Patna University, Patna-800 005

Manuscript received 26 October 1981, accepted 8 July 1982

A series of mixed ligand adducts of alkali metal salts of different organic acids with *o*-hydroxybenzeneazo-2-naphthol, of the general formula

ML.OHBAN (M=Li, Na or K; L=deprotonated organic acids; 1-nitroso-2-naphthol, 8-hydroxyquinoline, *o*-nitrophenol, 2-hydroxy-3-naphthoic acid, salicylic acid, salicylaldehyde; OHBAN=*o*-hydroxybenzeneazo-2-naphthol), have been synthesised. The adducts have been judged by their analytical results and infrared spectra, and this throws light on the fact that one molecule of alkali metal salt of organic acid combines with one molecule of ligand OHBAN, suggesting coordination number five or six for the metal atom.

#### Experimental

The ligand OHBAN was prepared by standard method<sup>1</sup>, m.p. 194°. All the alkali metal salts used were prepared in 95% ethanol.

The general method of preparation was to take the hot absolute alcoholic solution of OHBAN and to add to it the alkali metal salts of organic acids in mono-molecular ratio. The whole mixture in solution was refluxed over water bath with stirring for about 1 hr. The solution, on keeping, yielded crystalline solid adducts. The crystals were filtered, washed with absolute alcohol and dried in an oven at 80°.

#### Results and Discussion

The adducts are stable when stored under dry condition e.g. in a desiccator. All the complexes are coloured (green, dark violet or brown). The compounds are thermally stable. When heated, they undergo a decomposition at a temperature higher than the melting point of the ligand. The adducts break on heating to form the simple salts and ligand, and this indicates that the bonding in these compounds is not strong. The colour, melting or decomposition temperatures and analysis of the complexes are given in Table 1.

The presence of two -OH groups in the *o*, *o'* positions to the azo group may increase the coordinating capacity of -N=N- group. It also suggests the possibility of intra-molecular hydrogen bonding due to which the metal is complexed in cyclic form.

TABLE 1

Compound	Colour	Melting / Decomp. temp °C	Found (%)				Calcd. (%)			
			O	H	N	M	O	H	N	M
OHBAN=L	Deep violet	194 m	72.69	4.56	10.61	—	72.72	4.54	10.60	—
Na1N2N.L	Dark violet	220 d	68.14	3.89	8.95	5.16	68.00	3.92	9.15	5.01
K1N2N.L	Dark violet	210 d	65.51	3.69	8.39	8.85	65.78	3.79	8.84	8.21
Na8HQ.L	Deep brown	280 d	70.48	4.10	9.51	5.09	70.40	4.06	9.48	5.19
K8HQ.L	Deep brown	215 d	67.92	3.94	9.48	8.14	68.00	3.92	9.35	8.50
NaONP.L	Green	223 d	62.09	3.81	9.95	5.40	62.12	3.76	9.88	5.41
KONP.L	Green	212 d	60.15	3.59	9.63	8.31	60.00	3.62	9.52	8.84
Na3H8NA.L	Brownish green	295 d	68.42	4.15	6.24	4.69	68.35	4.22	5.90	4.85
K3H8NA.L	Brownish green	280 d	66.43	3.91	6.11	7.59	66.12	3.88	5.71	8.00
Kacac.L	Green	208 d	62.92	4.45	5.82	9.95	62.68	4.72	6.96	9.70
Naanth.L	Deep red	220 d	65.41	4.04	9.99	5.04	65.24	4.25	9.90	5.43
Kanth.L	Green	210 d	62.66	4.22	9.79	8.22	62.87	4.10	9.57	8.68
NaSalH.L	Brown	255 d	67.82	4.09	6.91	5.31	67.64	4.16	6.86	5.62
KSalH.L	Brown	242 d	64.92	4.12	6.98	8.75	65.10	4.00	6.60	9.20

OHBAN=*o*-hydroxybenzeneazo-2-naphthol, 1N2N=1-nitroso-2-naphthol, 8HQ=8-hydroxyquinoline, ONP=*o*-nitrophenol, 3H8NA=2-hydroxy-3-naphthoic acid, acac=acetylacetone, anth=anthranilic acid, SalH=salicylaldehyde.



Conni *et al*<sup>2</sup> have reported that azo frequencies were usually observed in the range of 1570-1595  $\text{cm}^{-1}$ . Bands in the region 1472-1545  $\text{cm}^{-1}$  have been attributed to a number of aryl azo compounds of Mo by King<sup>3</sup>. In the ligand OHBAN, we obtain the  $-\text{N}=\text{N}-$  band at 1550  $\text{cm}^{-1}$ . In the adducts, this band shifts down to 1540-1515  $\text{cm}^{-1}$  suggesting that the  $-\text{N}=\text{N}-$  group is probably associated to the metal. These bands also split in the adducts which may be due to a change in symmetry. The  $-\text{N}=\text{N}=$  frequency of ligand and its compounds with alkali metal salts have been given in Table 2.

TABLE 2—SELECTED IR FREQUENCIES OF  
LIGAND AND ADDUCTS

Compound	$-\text{N}=\text{N}-$ frequency ( $\text{cm}^{-1}$ )
OHBAN=L	1550
NaINAN.L	1540, 1535
KINAN.L	1540, 1595
NaSHQ.L	1540, 1535
KSHQ.L	1535, 1570
NaONP.L	1540
KONP.L	1540
NaH3NA.L	1535
KH3NA.L	1535, 1530
Na.anth.L	1525, 1510
K.anth.L	1545, 1535
NaSalH.L	1540, 1525

The OH stretching frequency of the ligand has been observed at  $\sim 3360 \text{ cm}^{-1}$ . It shifts down to  $\sim 3220 \text{ cm}^{-1}$  in the compounds thereby showing the involvement of  $-\text{OH}$  in the formation of adducts. The  $\text{H}-\text{O}-\text{H}$  bending mode is seen at  $\sim 1300 \text{ cm}^{-1}$  in the ligand, while in the compounds two peaks at  $\sim 1320$ - $1310 \text{ cm}^{-1}$  and at  $\sim 1280 \text{ cm}^{-1}$  are observed. The extra peaks in complexes may justify their formation.

#### References

1. BRILSTRIN-FRAGER JACOBSON, "Org. Chemis", Band 16, System No. 9085-9858, 160.
2. CONNI *et al*, *J. Chem. Soc. (A)*, 1971, 3441
3. R. B. KING, *Inorg. Chem.*, 1966, 5, 800.

### Conductometric and Spectrometric Studies on Complexes of Ag(I) and Hg(II) Ions with N,N'-Diphenyl Thiourea

B. SINGH, UMA SHANKAR PRASAD SHARMA  
and

D. K. SHARMA

Department of Chemistry, Patna University,  
Patna-800 005

Manuscript received 3 June 1980, revised 25 March 1982,  
accepted 21 July 1982

SINCE N,N'-diphenylthiourea contains two phenyl substituent groups, the complexation behaviour of this ligand decreases<sup>1-3</sup> because of the electron withdrawing tendency of the phenyl group. In

view of this, complexing behaviour of this ligand with Ag(I) and Hg(II) ions have been investigated in solution by conductometric titration and in solid state by infrared spectroscopy and the results are reported here.

#### Experimental

All chemicals used were of AnalaR quality. N,N'-Diphenylthiourea was prepared by standard method<sup>4</sup>. The prepared compound gave satisfactory C, H and N analysis.

**Preparation of complexes:** The diaquo N,N'-diphenylthiourea silver(I) nitrate polymeric complex,  $\{[\text{Ag}(\text{H}_2\text{O})_2(\text{DPhTU})]\text{NO}_3\}_n$ , was prepared by simply mixing an aqueous solution of  $\text{AgNO}_3$  with ethanolic solution of N,N'-diphenylthiourea in 1:2 molar ratio. A green coloured precipitate formed immediately which was digested on water bath for 30 min. The complex was thereafter filtered, washed with ethanol and ether and dried at  $110^\circ$ . (Found: C, 35.90; H, 3.45; N, 9.41; Ag, 24.84. Calcd. C, 35.94; H, 3.69; N, 9.69; Ag, 24.90%).

The green aquochloro N,N'-diphenylthiourea mercury(II) chloride complex,  $\{[\text{Hg}(\text{H}_2\text{O})(\text{DPhTU})\text{Cl}]\text{Cl}\}_n$ , was prepared in the same manner as the Ag(I) complex. (Found: N, 5.84; Cl 13.43; Hg, 39.2%. Calcd. N, 5.41; Cl, 13.72; Hg, 38.8%).

**Physical methods:** The magnetic measurements were made at  $30^\circ$  using Guoy Balance. Both the complexes were found to be diamagnetic. The infrared spectra were recorded in KBr pellets using Perkin Elmer spectrophotometers, Model 521 and 621 in the range  $4000$ - $200 \text{ cm}^{-1}$ . Conductometric titrations were carried out by means of Toshniwal conductometric bridge, model 302 using a dip type cell (cell constant  $1.92 \times 10^{-3} \text{ mho/cm}^2$ ).

#### Results and Discussion

The analytical results indicate that empirical formula of the solid complexes are  $\text{Ag}(\text{H}_2\text{O})_2(\text{DPhTU})\text{NO}_3$  and  $\text{Hg}(\text{H}_2\text{O})(\text{DPhTU})\text{Cl}_2$ . The conductometric titrations of  $0.01 \text{ M AgNO}_3$  and  $0.01 \text{ M HgCl}_2$  solutions were conducted against  $0.005 \text{ M}$  diphenyl urea solution and inflexion points for both titrations indicate the formation of 1:1 complexes.

The Ag(I) complex contains ionic nitrate. This has been confirmed by chemical method as well as by the infrared spectra of the complex. The infrared spectra of this complex exhibit a strong band at  $1385 \text{ cm}^{-1}$  and a weak band at  $845 \text{ cm}^{-1}$ . These bands are not present in the spectra of the diphenylthiourea ligand or of the Hg(II) complex. Since ionic nitrates exhibit<sup>5</sup> strong infrared bands in the range of  $1340$ - $1410 \text{ cm}^{-1}$  and weak band in the range of  $800$ - $860 \text{ cm}^{-1}$ , it may be suggested that nitrate group is in the ionic form in the Ag(I) complex. But as the complex is insoluble in almost all organic solvents, it may be tentatively assigned a polymeric

formula,  $\{[Ag(H_2O)_2(DPhTU)]NO_3\}_n$ . Out of the two chlorine atoms in  $Hg(H_2O)(DPhTU)Cl_2$ , one is ionic. This is confirmed by the presence of  $Cl^-$  ion in the  $Na_2CO_3$  extract of the complex. The other Cl atom is covalently bonded. This is also confirmed by the presence of  $\nu(Hg-Cl)$  (terminal) band at  $325\text{ cm}^{-1}$  in the infrared spectra of this complex.  $\nu(Hg-Cl)$  (terminal) bands are generally observed<sup>8-9</sup> below this region in octahedral complexes. Thus, it may be concluded that  $Hg(II)$  ion is in tetrahedral coordination in this complex. But as the complex is insoluble in most organic solvents, the polymeric formulation,  $\{[Hg(H_2O)(DPhTU)Cl]Cl\}_n$ , may be suggested for it. The presence of coordinated water is confirmed<sup>9-10</sup> by the presence of bands at  $3440$ ,  $1640$ ,  $530$ ,  $515$  and  $505\text{ cm}^{-1}$  in the  $Ag(I)$  complex and at  $3500$ ,  $1645$ ,  $530$ ,  $515$  and  $505\text{ cm}^{-1}$  in the  $Hg(II)$  complex. Out of these five bands, the first two are assigned to  $\nu H_2O$  and  $\delta H_2O$  and the latter three to vibrational mode of coordinated water. More than one vibrational modes also confirm the polymeric nature of the complexes.

The diphenylthiourea ligand is bonded to the  $Ag(I)$  and  $Hg(II)$  ions in the two complexes through nitrogen as well as through thiocarbonyl sulphur. This is confirmed from the following considerations. (i) The splitting of  $\nu(N-H)$  band of the ligand ( $3210\text{ cm}^{-1}$ ) into two distinct bands at  $3300\text{ cm}^{-1}$  and  $3100\text{ cm}^{-1}$  indicating coordination through nitrogen. (ii) The bands of the ligand at  $1595$  and  $1540\text{ cm}^{-1}$  observed as strong bands are assigned to  $\delta NH + \nu CN$  modes. There is no change in intensity and position of these bands. This is possible only when there is no coordination or coordination occurs through both nitrogen and sulphur. (iii) The thioamide band II of the ligand is observed at  $1340\text{ cm}^{-1}$  and is mainly due to  $\nu(C=S)$  mode of vibration. This band has red shifted to  $1320\text{ cm}^{-1}$  in the  $Ag(I)$  complex and  $1315\text{ cm}^{-1}$  in the  $Hg(II)$  complex. This indicates coordination through sulphur. (iv) The thioamide band IV is observed at  $760\text{ cm}^{-1}$  as a weak band<sup>10</sup> in the infrared spectra of the ligand. This band is found at the same position in the spectra of the complexes but its intensity increases on coordination. As coordination through sulphur red shifts this band<sup>21-23</sup> and coordination through nitrogen blue shifts it<sup>21-23</sup>, it may be concluded that bonding has taken place both through sulphur and nitrogen. Increase in intensity may be due to polymeric nature of the complexes. (v) The far infrared spectra of the ligand contain only one weak band at  $485\text{ cm}^{-1}$ . But the infrared spectra of the  $Ag(I)$  complex contain weak bands at  $555$  and  $380\text{ cm}^{-1}$  which may be assigned to  $\nu Ag-OH_2$  and  $\nu(Ag-N)$  modes of vibration. The infrared spectra of the  $Hg(II)$  complex contain new weak bands at  $470$ ,  $325$  and  $300\text{ cm}^{-1}$ . These may be assigned to  $\nu Hg-OH_2$ ,  $\nu(Hg-Cl)$  and  $\nu(Hg-N)$  modes of vibrations, respectively. As  $325\text{ cm}^{-1}$  band is the strongest among the three bands, it has been assigned to  $\nu(Hg-Cl)$ . In monomeric tetrahedral

complexes,  $\nu(Hg-Cl)$  (terminal) is observed as a strong band in the  $370\text{ cm}^{-1}$  region<sup>20</sup> but in linear 4-coordinated polymeric complexes,  $\nu(Hg-Cl)$  (terminal) band is observed at  $328\text{ cm}^{-1}$  as a strong and broad band<sup>22</sup>. As the metal-N and metal-S bonds are approximately of the same strength as indicated by equal red and blue shifts of thioamide band IV,  $\nu$  (metal-S) mode is expected to be near  $200\text{ cm}^{-1}$ . Hence,  $\nu$  (metal-S) bands have not been observed.

Thus, the following tentative structures may be assigned to these complexes.




Fig. 1. Probable structure of  $\{[Ag(H_2O)_2(DPhTU)]NO_3\}_n$ .




Fig. 2. Probable structure of  $\{[Hg(H_2O)(DPhTU)Cl]Cl\}_n$ .

#### Acknowledgement

The authors are thankful to the authorities of Patna University for facilities and to the referee of this paper for constructive suggestion.

#### References

1. R. L. CARLIN and S. L. HOLT, *Inorg. Chem.*, 1963, 2, 849.
2. G. YAGUPSKY and R. L. HOLT, *Inorg. Chem.*, 1965, 4, 1589.
3. S. L. HOLT and R. L. CARLIN, *J. Amer. Chem. Soc.*, 1964, 86, 3017.
4. A. I. VOGEL, "Practical Organic Chemistry", Longmans Green & Co. Ltd., London, 1968, p. 642.
5. L. J. BELLAMY, "Infrared Spectra of Complex Molecules", John Wiley and Sons, Inc., New York, 1956, p. 249.
6. G. E. COATES and D. RIDLEY, *J. Chem. Soc.*, 1964, 166.
7. R. C. EVANS, F. G. MANN, H. S. PRISER and D. PURDIE, *J. Chem. Soc.*, 1940, 1809.
8. A. VINCIGUERRA, P. G. SIMPSON, Y. KAKIUTI and J. V. QUAGLIANO, *Inorg. Chem.*, 1963, 2, 286.
9. D. M. ADAMS, "Metal Ligand and Related Vibrations", Edward Arnold Ltd., London, 1967, p. 238.
10. J. VAN DER ELSEN and D. W. ROBINSON, *Spectrochim. Acta*, 1961, 17, 1249.
11. I. NAKAGAWA and T. SHIMANOUCHI, *Spectrochim. Acta*, 1964, 20, 429.
12. J. P. MATHIEU and M. TOBAILEM, *Compt. rend.*, 1960, 231, 187, 896.
13. B. E. HESTER and R. A. PLANE, *Inorg. Chem.*, 1964, 3, 768.
14. N. OHKAKU and K. NAKAMOTO, *Inorg. Chem.*, 1971, 10, 798.

15. D. E. OLMOG and J. R. HALL, *Spectrochim. Acta*, 1965, 21, 357.
16. Y. KERMARREC, *Compt. rend.*, 1964, 258, 5886.
17. G. BRINK and M. FALK, *Canad. J. Chem.*, 1970, 48, 2090.
18. P. C. RATH and B. K. MOHAPATRA, *J. Indian Chem. Soc.*, 1974, 51, 710.
19. P. C. RATH and B. K. MOHAPATRA, *J. Indian Chem. Soc.*, 1974, 51, 834.
20. B. SINGH, D. K. SHARMA, U. S. P. SHARMA and B. K. SHARMA, *J. Indian Chem. Soc.*, 1979, 56, 764.
21. G. CONTRERAS and R. SCHMIDT, *J. Inorg. Nuclear Chem.*, 1970, 32, 1295.
22. M. N. CHAMBERLAIN and J. O. BAILER, Jr., *J. Amer. Chem. Soc.*, 1959, 81, 6412.
23. P. C. MITCHELL and R. J. P. WILLIAMS, *J. Chem. Soc.*, 1960, 1912.
24. J. LEWIS, R. S. NYHOLM and P. W. SMITH, *J. Chem. Soc.*, 1961, 4590.
25. A. TURCO and C. PECILE, *Nature*, 1961, 191, 66.
26. I. BERTINI and A. SABATINI, *Inorg. Chem.*, 1965, 4, 1665.
27. C. PECILE, *Inorg. Chem.*, 1966, 5, 210.
28. A. SABATINI and I. BERTINI, *Inorg. Chem.*, 1965, 4, 359.
29. M. A. BENNET, R. J. H. CLARK and A. D. J. GOODWIN, *Inorg. Chem.*, 1967, 6, 1625.
30. A. TRAMER, *J. Chem. Phys.*, 1962, 59, 222.
31. I. BERTINI and A. SABATINI, *Inorg. Chem.*, 1966, 5, 1026.
32. M. MERTAN and A. B. P. LEYER, *Inorg. Chem.*, 1971, 10, 47.

### Determination of Stability Constants of 2-Hydroxy-1-naphthalidene-sulphafurazole Complexes with $\text{La}^{3+}$ , $\text{Y}^{3+}$ , $\text{Pr}^{3+}$ , $\text{Nd}^{3+}$ , $\text{Gd}^{3+}$ , $\text{Dy}^{3+}$

M. S. MAYADEO and S. BHATTACHARJEE

Department of Chemistry, Ramnarain Ruia College,  
Matunga, Bombay-400 019

Manuscript received 6 July 1981, revised 12 February 1982,  
accepted 21 July 1982


IN the present investigation, potentiometric studies on 2-hydroxy-1-naphthalidene-sulphafurazole and its complexes with some trivalent metal ions have been carried out. The dissociation constants ( $pK_1$  and  $pK_2$ ) of the reagent and the formation constants ( $\log K_1$  and  $\log K_2$ ) of its metal chelates have been determined potentiometrically following the Calvin-Bejerrum pH titration technique as adopted by Irving and Rossotti<sup>1</sup>.

The titrations were carried out in 75 : 25 % (v/v) dioxane-water medium at  $25 \pm 0.1^\circ$  and at a constant ionic strength of 0.1 M. Appropriate correction factor for pH meter readings (B values) in 75% (v/v) dioxane-water medium has been applied<sup>2</sup>.

#### Experimental

The ligand 2-hydroxy-1-naphthalidene-sulphafurazole was prepared by refluxing equimolar quantities of 2-hydroxy-1-naphthaldehyde and the amine in alcohol-DHF mixture for about 2 hr. The crude product was repeatedly crystallised from DMF to get an analytically pure compound with m.p.  $220^\circ$ . The purity of the compound was established by

tlc and elemental analysis. (Found : C, 63.21 ; H, 4.47 ; N, 10.24. Calcd. for  $\text{C}_{22}\text{H}_{16}\text{N}_2\text{O}_4\text{S}$  : C, 62.71 ; H, 4.51 ; N, 9.98%). The structure of the ligand is,



All the metal perchlorates used were prepared from metal carbonates and perchloric acid of A. R. grade. These were standardised complexometrically by EDTA titrations<sup>3</sup>.

Other experimental details were the same as in earlier communication<sup>4</sup>.

#### Results and Discussion

It may be mentioned here that the ligand did not undergo hydrolysis under the experimental conditions described. This was indicated by rapid attainment of equilibrium during the course of titration and by the absence of any significant drift in pH even after 2 hr. This was further confirmed by taking tlc of a sample titration mixture from time to time.

It is the phenolic (OH) group in the ligand which takes part in complex formation and the proton is replaced from it by the metal ion during chelation. As only one proton per ligand molecule is liberated, Y, the number of dissociable protons attached to each ligand molecule is one.

From the titration curves (Fig. 1),  $\bar{n}_A$  values at various B values (pH meter readings) were calculated and the formation curve (B vs  $\bar{n}_A$ ) was plotted. The  $pK_1$  corresponding to phenolic H was obtained by half integral method of  $\bar{n}_A = 0.5$ . This was further corroborated by plotting the graph of  $\log (\bar{n}_A / 1 - \bar{n}_A)$  vs B.

From the titration curves (Fig. 1),  $\bar{n}$  and  $pL$  values for metal-ligand systems were also determined. From the curves  $\bar{n}$  vs  $pL$ ,  $\log K_1$  and  $\log K_2$  values were determined by half integral method. As in the cases of  $\text{La}^{3+}$ ,  $\text{Gd}^{3+}$  and  $\text{Pr}^{3+}$  complexes, the difference between  $\log K_1$  and  $\log K_2$  was found to be less than 1.78 log units. These were computed by least square method and the same are reported in Table 1.

TABLE 1—STEPWISE STABILITY CONSTANTS OF  
VARIOUS COMPLEXES

	$t = 25^\circ$			$\mu = 0.1$			
Oxidation	$\text{H}^+$	$\text{Gd}^{3+}$	$\text{La}^{3+}$	$\text{Pr}^{3+}$	$\text{Nd}^{3+}$	$\text{Y}^{3+}$	$\text{Ly}^{3+}$
$\log K_1$	7.763	8.19	7.90	7.55	5.60	5.30	5.06
$\log K_2$	—	7.13	7.11	7.30	—	—	—

The order of stability of metal chelates is found to be  $\text{Gd}^{3+} > \text{La}^{3+} > \text{Pr}^{3+} > \text{Nd}^{3+} > \text{Y}^{3+} > \text{Dy}^{3+}$ .




Fig. 1. Titration curves of 2-hydroxy-1-naphthaldehyde-sulphafurazole.

### Acknowledgement

The authors record their sincere thanks to Dr. D. G. Vartak, B. A. R. C., Bombay for valuable suggestions.

### References

1. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
2. A. CORSINI and E. J. BILLO, *J. Inorg. Nuclear Chem.*, 1970, 32, 1449.
3. H. A. FLASCHKA, "EDTA Titrations", Pergamon Press, Inc., N. Y., 1969.
4. M. S. MAYADRO and H. S. HUSSAIN, *J. Indian Chem. Soc.*, 1979, 56, 143.

### Conductance of KCl and NaCl in Sucrose + Water, Glucose + Water and Urea + Water Mixtures at Different Temperatures

(Miss) S. MOHANTY and P. B. DAS\*

Department of Chemistry, Ravenshaw College, Cuttack-753 003

Manuscript received 4 February 1982, accepted 21 July 1982

**STRUCTURAL** interactions in ternary system comprising electrolyte-solvent-nonelectrolyte are gaining special attention in recent years. It has been

observed that nonelectrolyte molecules interact with the ions of the electrolytes in solution<sup>1-3</sup>. Several polyhydroxy compounds are known to interact with electrolytes in solutions<sup>4,5</sup>. Definite adducts of many carbohydrates with salts and hydrated oxides of alkali and alkaline earth metals have also been reported<sup>6,7</sup>. Conductance of electrolyte solutions in the presence of nonelectrolytes have been measured by several workers<sup>8-9</sup>. The changes in conductance of carbohydrate-electrolyte solutions<sup>10</sup> was attributed to the obstruction of electrical migration of ions by the environmental nonelectrolyte entities<sup>11,12</sup>.

In the present communication, the ion-solvent interaction of KCl and NaCl have been studied from conductivity data at weight percent of nonelectrolyte (sucrose, glucose) + water (5, 10, 15 and 20) mixtures at 30, 35, 40 and 45° and urea + water at 30 and 35°.

### Materials and methods :

The salts used were of E. Merck 'Extra Pure' grade. Sucrose, glucose and urea were of B.D.H. AnalaR grade. The methods for preparation of the solvents and solutions and a measurements were the same as reported earlier<sup>13</sup>. Conductance measurement was of an accuracy of  $\pm 2$  in 1000. The concentration range was from 0.01 to 0.001 equiv/lit. Studies above 35° could not be performed in case of urea + water because of hydrolysis.

### Results and Discussion

The equivalent conductivity of KCl and NaCl investigated at weight percent of nonelectrolyte (sucrose, glucose and urea) + water mixtures (5, 10, 15 and 20) are found to be linear with  $C^{1/2}$  in the concentration range 0.01 to 0.001 mol lit<sup>-1</sup>. This indicates that the salts are completely ionised. The limiting equivalent conductivity,  $\Lambda^\circ$ , for KCl and NaCl at different compositions and at different temperatures obtained from the usual extrapolation procedure are given in Table 1 along with the values in aqueous solution<sup>14</sup>.

From the determined  $\Lambda^\circ$  values, the theoretical slope,  $S_T$ , of the plot of  $\Lambda$  vs  $C^{1/2}$  at 35° for KCl and NaCl at different solvent compositions has been obtained and compared with the observed slope,  $S$  (Table 2). The  $S$  value is found to be greater than  $S_T$ , which indicates that the observed conductance is less than that of the theoretical value. This difference is of the order : sucrose + water > urea + water > glucose + water, which indicates the structure breaking order also.

The Walden product,  $\Lambda\eta_0$ , has been usually employed to study ion-solvent interaction in solution from the conductivity data.  $\Lambda\eta_0$  of both KCl and NaCl at different temperatures and at different solvent composition are given in Table 3. The results show that it is maximum in case of glucose +

\* Author for correspondence.

# NOTES

TABLE-1

$\Lambda/\Omega^{-1} \text{ cm}^2$

Temp. Mass fraction of nonelectrolyte	Sucrose + water				Glucose + water				Urea + water	
	30	35	40	45	30	35	40	45	30	35
KCl										
5	100.00	174.8	189.0	203.8	180.0	174.2	186.6	203.0	187.6	181.8
10	150.90	169.9	173.3	186.4	150.0	168.3	176.2	188.3	165.0	177.0
15	136.8	145.6	159.6	171.2	136.7	147.0	161.1	172.6	162.4	176.0
20	121.0	133.4	144.0	154.2	123.5	134.9	145.6	156.7	151.8	163.0
				*149.86						
NaCl										
5	139.5	153.8	169.0	181.6	141.4	153.4	169.0	183.3	149.0	161.8
10	129.4	142.8	154.0	167.6	131.5	144.4	156.2	169.2	145.0	158.8
15	114.2	135.6	136.8	146.6	116.4	127.6	138.8	149.6	137.8	150.6
20	103.2	113.8	123.9	134.6	105.4	115.7	126.6	137.0	130.4	142.9
				*126.46						

\* Values at 25°C

TABLE 2—SLOPE VALUES (at 35° only)/mol<sup>-1</sup>°cm<sup>1/2</sup>

	5% Sucrose		10% Sucrose		15% Sucrose		20% Sucrose	
	S	S <sub>T</sub>	S	S <sub>T</sub>	S	S <sub>T</sub>	S	S <sub>T</sub>
KCl	104.2	99.4	105.2	99.6	106.3	99.8	106.9	100.2
NaCl	100.9	95.2	101.4	96.2	103.3	97.4	103.4	98.3
	5% Glucose		10% Glucose		15% Glucose		20% Glucose	
	S	S <sub>T</sub>	S	S <sub>T</sub>	S	S <sub>T</sub>	S	S <sub>T</sub>
KCl	102.7	99.4	103.6	99.5	104.6	99.9	105.6	100.3
NaCl	99.6	96.2	99.9	96.2	100.8	97.4	101.6	98.2
	5% Urea		10% Urea		15% Urea		20% Urea	
	S	S <sub>T</sub>	S	S <sub>T</sub>	S	S <sub>T</sub>	S	S <sub>T</sub>
KCl	103.00	99.4	104.2	99.6	105.5	99.9	106.2	100.3
NaCl	100.40	96.0	100.8	96.0	101.2	97.3	102.6	97.8

TABLE 3— $\Lambda/\Omega^{-1} \text{ cm}^2 \text{ P}$

Temp. Mass fraction of nonelectrolyte	Sucrose + water				Glucose + water				Urea + water	
	30	35	40	45	30	35	40	45	30	35
KCl										
5	1.967	2.098	2.107	2.224	2.464	2.917	3.467	4.155	2.312	2.727
10	2.327	2.440	2.643	2.790	2.866	3.380	4.035	4.726	2.492	2.988
15	2.729	2.822	3.098	3.201	3.527	4.201	5.333	5.558	2.598	3.027
20	3.025	3.308	3.470	3.667	3.693	4.357	5.169	6.049	2.778	3.195
NaCl										
5	1.716	1.846	1.884	2.017	2.177	2.562	3.160	3.789	2.056	2.427
10	1.992	2.171	2.325	2.514	2.511	2.959	3.577	4.246	2.189	2.636
15	2.284	2.437	2.586	2.741	3.003	3.560	4.305	4.817	2.305	2.805
20	2.580	2.822	2.986	3.208	3.161	3.725	4.494	5.288	2.386	2.801

TABLE 4—DIFFERENCE IN  $\Lambda/\Omega^{-1} \text{ cm}^2$

Temp. Mass fraction of nonelectrolyte	Sucrose + water				Glucose + water				Urea + water	
	30	35	40	45	30	35	40	45	30	35
5	20.5	21.0	20.0	21.2	18.6	20.8	17.6	19.7	18.6	20.0
10	21.5	17.1	19.6	18.8	18.5	18.9	20.2	19.1	20.0	18.2
15	21.6	20.0	22.8	24.6	20.3	19.4	22.3	23.0	24.4	25.4
20	17.8	19.6	20.1	19.6	18.1	19.2	19.0	19.7	21.4	20.1

water and minimum in case of sucrose + water, urea + water being in between the two. Hence, the ion-solvent interaction is of the order :

sucrose + water > urea + water > glucose + water.

A better insight of the ion-solvent interaction can be obtained if the differences in the conductivity of KCl-NaCl at different compositions and at different temperatures be compared. These differences are recorded in Table 4. The differences are

not constant. The deviation from constancy in case of sucrose + water is maximum and least in case of glucose + water, whereas urea + water is in between the two. The more the deviation, the greater is the ion-solvent interaction<sup>1,2</sup>. So the order of ion-solvent interaction is sucrose + water > urea + water > glucose + water.

The above observations can be explained as follows. Sucrose contains more hydroxy groups than d-glucose and these hydroxy groups present in the compounds participate in the formation of hydrogen bonds with water molecules and hence the water structure breaks. Sucrose, therefore, is a stronger structure breaker than glucose. As regards urea, it can be said that urea is alkaline in water and acts both as a proton donor and acceptor, and hence in the mixture of urea and water, the structure is likely to be broken. Secondly, due to keto-enol tautomerism in solution urea may contain one hydroxy group which participates in the formation of hydrogen bond with water molecules and structure breaking is observed.

#### References

1. S. FRIEDRICKSON, *Acta Chem. Scand.*, 1969, 23, 1993.
2. P. Z. FISCHER and T. E. KOVAL, *Bull. Soc. Res. Chem.*, 1989, 4, 137.
3. O. H. HALL and D. VRIES, *J. Amer. Chem. Soc.*, 1948, 70, 3478.
4. L. G. LONGSWORTH, *J. Amer. Chem. Soc.*, 1947, 69, 1288.
5. J. A. REMDLERMAN, Jr., *Adv. Carbohyd. Chem.*, 1966, 21, 207.
6. S. P. MOULLICK and A. K. MITRA, *Carbohyd. Res.*, 1973, 28, 371.
7. J. STOKES and R. H. STOKES, *J. Phys. Chem.*, 1966, 60, 217.
8. B. J. STENL, J. M. STOKES and R. H. STOKES, *J. Phys. Chem.*, 1968, 62, 1514.
9. H. B. BULL, K. BRESE, G. L. FERGUSON and O. A. SWENSON, *Arch. Biochem. Biophys.*, 1964, 104, 29.
10. S. P. MOULLICK and A. K. MITRA, *Carbohyd. Res.*, 1973, 29, 509.
11. S. P. MOULLICK, *Electrochem. Acta*, 1972, 17, 1491.
12. S. P. MOULLICK, *Electrochem. Acta*, 1973, 18, 981.
13. N. C. DAS and P. B. DAS, *Electrochem. Acta*, 1978, 23, 191.
14. H. S. HARNED and B. B. OWEN, "Physical Chemistry of Electrolytic Solution", Reinhold Publishing Co., N. Y., 1969.
15. P. B. DAS, *Indian J. Chem.*, 1978, 16A, 624.

### Synthesis of Some 5-Arylazopyrimidine Derivatives


V. K. MAHESH, VIRENDRA KUMAR  
and  
OM PRAKASH\*

Chemistry Department, University of Roorkes, Roorkes

Manuscript received 14 June 1978, revised 28 January 1982,  
accepted 26 August 1982

IN continuation of our work on the synthesis of 5-arylazopyrimidine derivatives of biological interest<sup>1</sup>, we report here the synthesis of three

more series of compounds, namely 2-amino-5-aryazo-4-hydroxy-6-methylpyrimidines (I), 5-aryazo-2,4-dihydroxy-6-methylpyrimidines (II) and 5-aryazo-4,6-dimethyl-2-hydroxypyrimidines (III).



All the compounds (I, II and III) were synthesized in excellent yields by the reaction of different aryl diazonium chlorides with appropriately substituted pyrimidine derivatives. The structures of the compounds were confirmed by their elemental analysis and IR spectra (bands in the region 1630-1590  $\text{cm}^{-1}$  due to  $-\text{N}=\text{N}-$  stretching). The arylazo group at position-5 was further confirmed by reducing three arylazo derivatives (one from each series) with Zn and AcOH. 2-Amino-4-hydroxy-6-methyl-5-phenylazopyrimidine (I,  $\text{X}=\text{Y}=\text{H}$ ), on reduction, afforded 2,5-diamino-4-hydroxy-6-methylpyrimidine while II ( $\text{X}=\text{Y}=\text{H}$ ) and III ( $\text{X}=\text{Y}=\text{H}$ ) gave 5-amino-2,4-dihydroxy-6-methylpyrimidine and 5-amino-4,6-dimethyl-2-hydroxypyrimidine, respectively.

#### Experimental

Melting points were taken in open capillary in a sulphuric acid bath and are uncorrected. IR spectra were recorded on a Beckman IR-20 spectrophotometer as nujol mulls.

2-Amino-4-hydroxy-6-methylpyrimidine<sup>2</sup>, 2,4-dihydroxy-6-methylpyrimidine<sup>3</sup> and 4,6-dimethyl-2-hydroxypyrimidine<sup>4</sup> were prepared by the methods described in literature and coupled with different aryl diazonium chlorides according to the method reported earlier<sup>1</sup>. All the compounds were crystallized from DMF-ethanol mixture. The characteristics of compounds belonging to series I, II and III have been listed in Tables 1, 2 and 3, respectively.

TABLE 1—CHARACTERISTICS OF 2-AMINO-5-ARYLAZO-4-HYDROXY-6-METHYLPYRIMIDINES (I)

Sl. No.	X,Y	m.p. °C	Yield %	Analysis %	
				Calcd.	Found
1.	H	297 <sup>d</sup>	75	N, 30.57	30.34
2.	2-OH,	302	52	N, 28.80	28.64
3.	3-OH,	316 <sup>d</sup>	65	N, 28.80	28.68
4.	4-OH,	299	48	N, 28.80	28.89
5.	2-OOH,	307 <sup>d</sup>	63	N, 27.03	27.13
6.	3-OOH,	288	72	N, 27.03	27.00
7.	4-OOH,	298 <sup>d</sup>	70	N, 27.03	26.92
8.	4-OC <sub>2</sub> H <sub>5</sub> ,	206	50	N, 25.64	25.50
9.	2-Cl,	128	76	Cl, 18.47	18.38
10.	4-Cl,	288	80	Cl, 13.47	13.26
11.	2-Br,	266	76	Br, 26.00	26.10
12.	4-Br,	245	74	Br, 26.00	25.90
13.	2-NO <sub>2</sub> ,	301	80	N, 30.56	30.49
14.	3-NO <sub>2</sub> ,	314 <sup>d</sup>	81	N, 30.56	30.49
15.	4-NO <sub>2</sub> ,	319 <sup>d</sup>	81	N, 30.56	30.46
16.	3,5-(OH) <sub>2</sub> ,	316	61	N, 27.23	27.28
17.	2,4-(Cl) <sub>2</sub> ,	299	65	Cl, 23.82	23.78

d = melts with decomposition.

\* Author for correspondence. Present address: Department of Chemistry, Kurukshetra University, Kurukshetra, Haryana.

TABLE 2—CHARACTERISTICS OF 5-ARYLAZO-2,4-DIHYDROXY-6-METHYLPYRIMIDINES (II)

Sl. No.	X, Y	m.p. °C	Yield %	Analysis%	
				Calcd.	Found
1.	H	302-4	73	N, 24.35	24.87
2.	2-OH <sub>2</sub>	307-9	50	N, 22.95	22.85
3.	3-OH <sub>2</sub>	179 <sup>d</sup>	54	N, 22.95	22.91
4.	4-OH <sub>2</sub>	185 <sup>d</sup>	50	N, 22.95	22.07
5.	2-Cl	303-4	75	Cl, 13.42	13.49
6.	3-Cl	172	77	Cl, 13.42	13.28
7.	4-Cl	235 <sup>d</sup>	73	Cl, 13.42	13.44
8.	2-Br	305	78	Br, 25.89	26.10
9.	4-Br	280 <sup>d</sup>	75	Br, 25.89	24.92
10.	2-NO <sub>2</sub>	247-49	76	N, 25.45	25.40
11.	3-NO <sub>2</sub>	263	71	N, 25.45	25.53
12.	4-NO <sub>2</sub>	310	70	N, 25.25	25.58
13.	2,6-(Cl) <sub>2</sub>	303 <sup>d</sup>	63	Cl, 23.74	22.48
14.	2,6-(Br) <sub>2</sub>	300 <sup>d</sup>	65	Br, 41.24	41.09

d—melts with decomposition.

TABLE 3—CHARACTERISTICS OF 5-ARYLAZO-4,6-DIMETHYL-2-HYDROXYPYRIMIDINES (III)

Sl. No.	X, Y	m.p. °C	Yield %	Analysis%	
				Calcd.	Found
1.	H	239	70	N, 24.57	24.63
2.	2-OH <sub>2</sub>	257 <sup>d</sup>	51	N, 23.14	23.28
3.	4-OH <sub>2</sub>	242	55	N, 23.14	22.98
4.	2-OCH <sub>3</sub>	258 <sup>d</sup>	48	N, 21.71	21.55
5.	4-OCH <sub>3</sub>	288	57	N, 21.71	21.77
6.	2-OC <sub>2</sub> H <sub>5</sub>	318 <sup>d</sup>	55	N, 20.58	20.79
7.	2-Cl	230	65	Cl, 13.86	13.15
8.	3-Cl	210	72	Cl, 13.86	13.15
9.	4-Br	287	68	Br, 26.05	26.17
10.	2-NO <sub>2</sub>	298	70	N, 26.52	26.68
11.	3-NO <sub>2</sub>	304	78	N, 26.52	26.37
12.	4-NO <sub>2</sub>	308 <sup>d</sup>	69	N, 26.52	26.60
13.	2,6-(Br) <sub>2</sub>	308 <sup>d</sup>	77	Br, 41.45	41.80
14.	2,6-(Cl) <sub>2</sub>	284 <sup>d</sup>	79	Cl, 23.84	23.85

d—melts with decomposition.

**Method for reduction:** A solution of I (X=Y=H) (2.29 g; 0.01 g mole) in acetic acid (20 ml) was added to a suspension of pure zinc (1.31 g; 0.02 g atom) in water (10-15 ml) slowly and with constant stirring. The mixture was first stirred at room temperature for 30-40 min and then heated on boiling water bath for 2-3 hr. The reaction mixture was filtered and the residue washed twice with water. Combined filtrate was neutralized with dilute NaHCO<sub>3</sub> and solid separated was crystallized from ethanol to give crystals, m.p. 285° (d), (yield 51%) which was identified as 2,5-diamino-4-hydroxy-6-methylpyrimidine [lit. m.p.<sup>8</sup> 281-2° (d)]. (Found: N, 40.3. Calcd. for C<sub>6</sub>H<sub>8</sub>N<sub>4</sub>O; N, 40.01%).

Similarly II (X=Y=H) and III (X=Y=H) were reduced and characterised by m.p. and elemental analysis.

#### Acknowledgement

The authors are thankful to the Head, Department of Chemistry, University of Roorkee for facilities. One of the authors (V. K.) is thankful to

University Grants Commission, New Delhi for financial assistance.

#### References

1. V. K. MAHESH, R. N. GOYAL and (Mrs.) RAMA GUPTA, *J. Indian Chem. Soc.*, 1977, **54**, 788.
2. L. E. BRADY and R. M. HERBST, *J. Org. Chem.*, 1959, **24**, 922.
3. *Organic Syntheses*, John Wiley and Sons, Inc., New York, Collective Vol. II, p. 422.
4. G. M. KOSOLAPOFF and O. H. ROY, *J. Org. Chem.*, 1961, **26**, 1896.
5. KENZO SHIRAKAWA, *J. Pharm. Soc. Japan*, 1953, **73**, 685.

#### Search for New Hypoglycemic Agents.

##### Part—VII: Coumarinylsulphonyl Ureas,

##### Semicarbazides and Semicarbazones

M. IMTIAZ HUSAIN\* and (Miss) KIRAN BALA GUPTA

Department of Chemistry, Lucknow University,  
Lucknow-226 007

and

R. C. SRIVASTAVA

Division of Experimental Medicine, C. D. R. I., Lucknow

Manuscript received 9 March 1981, revised 18 March 1982,  
accepted 18 August 1982

**SULPHONYLUREAS**<sup>1,2,3</sup> have long been known in the therapy of diabetes. It has recently been reported that sulphonamido coumarins<sup>4</sup> possess antidiabetic activity comparable to that of chlorpropamide. Moreover, some sulphonyl semicarbazides<sup>5</sup> and semicarbazones have also exhibited marked hypoglycemic activity. Hence, the title compounds were prepared with a view to study their hypoglycemic efficacy.

4,5,7-Trimethylcoumarin on chlorosulphonation gave 4,5,7-trimethyl-8-coumarinylsulphonyl chloride, which on treatment with ammonia was converted to the corresponding sulphonamide. The latter was allowed to react with ethyl chloroformate in the presence of anhydrous K<sub>2</sub>CO<sub>3</sub> and dry acetone to yield ethyl N-(4,5,7-trimethyl-8-coumarinylsulphonyl) carbamate. The carbamate on condensation with various amines and hydrazines gave coumarinylsulphonyl ureas and coumarinylsulphonyl semicarbazides, respectively. Also, the treatment of the carbamate with hydrazine hydrate afforded a semicarbazide which was condensed with different aldehydes or ketones to furnish coumarinylsulphonyl semicarbazones.

#### Experimental

All melting points are uncorrected. The structures of compounds were confirmed by ir spectra and elemental analysis.

**4,5,7-Trimethylcoumarin**: It was prepared by the modification of the method reported earlier<sup>8</sup>. Polyphosphoric acid (174.5 g) was added to a solution of 3,5-dimethylphenyl (12.0 g; 0.1 mole) in ethylacetoacetate (12.7 ml). The resulting mixture was heated at 75-80° with stirring for 20 min and thereafter poured into ice cold water. A pale yellow solid, thus obtained crystallised from dilute ethanol, yield 40%, m.p. 175-176° (lit.<sup>9</sup> m.p. 176°).

**4,5,7-Trimethyl-8-coumarinylsulphonyl chloride**: 4,5,7-Trimethylcoumarin (18.8 g; 0.1 mol) was kept in a freezing mixture (8°) and chlorosulphonic acid (23.3 ml; 0.2 mol) was added to it dropwise. The resulting mixture was stirred for 30 min at room temp. It was subsequently heated on a water bath at 80° for a few min and then poured into crushed ice. The product crystallised from ethanol, m.p. 177-178°, yield 60%. (Found: C, 50.00; H, 3.44. Calcd. for C<sub>13</sub>H<sub>11</sub>O<sub>4</sub>SO<sub>2</sub>Cl: C, 50.26; H, 3.84%).


**4,5,7-Trimethyl-8-coumarinylsulphonamide**: 4,5,7-Trimethyl-8-coumarinylsulphonyl chloride (0.01 mol) was treated with an excess of aq. ammonia. The resulting mixture was heated on a water bath for a few min. The product obtained on addition of water to the mixture crystallised from water, m.p. 185°, yield 80%. (Found: N, 4.99. Calcd. for C<sub>13</sub>H<sub>11</sub>O<sub>4</sub>NS; N, 5.24%). NMR (CDCl<sub>3</sub>):  $\delta$  (ppm) 1.25-1.32 (6H, d, 2 CH<sub>3</sub>), 1.20 (3H, s, CH<sub>3</sub>), 6.2 (1H, s, H<sub>6</sub>), 7.4 (1H, s, H<sub>8</sub>) and 4.5-4.6 (2H, broad hump, NH<sub>2</sub>).

**Ethyl N-(4,5,7-trimethyl-8-coumarinylsulphonyl) carbamate**: A mixture of 4,5,7-trimethyl-8-coumarinylsulphonamide (21.2 g), anhydrous K<sub>2</sub>CO<sub>3</sub> (27.6 g) and dry acetone (25 ml) was refluxed on a water bath for 1 hr. Thereafter, ethyl chloroformate (23.6) was added to the refluxing mixture over 1-5 hr. It was further refluxed for 3 hr and then evaporated to dryness. The residue obtained was dissolved in 150 ml of water and 1 N HCl was added to the solution till pH 8-8.5 was attained. After standing overnight, the solution was filtered and the filtrate acidified with 5 N HCl to attain pH 4, when a precipitate was obtained. It was filtered and recrystallised from ethanol, m.p. 178°. (Found: N, 3.65. Calcd. for C<sub>18</sub>H<sub>17</sub>O<sub>6</sub>NS; N, 4.13%).

**N<sup>1</sup>-(4,5,7-Trimethyl-8-coumarinylsulphonyl)-N<sup>4</sup>-aryl/alkyl ureas**: Ethyl N-(4,5,7-trimethyl-8-coumarinylsulphonyl) carbamate (0.003 mole) and an appropriate amine (0.003 mole) were refluxed in anhydrous toluene or benzene (10 ml) for 4 hr on a water bath. A solid was obtained on cooling which crystallised from ethanol or methanol.

Melting points and pertinent data of the compounds thus prepared are recorded in Table 1.

**N<sup>1</sup>-(Phenyl/p-tolyl)-N<sup>4</sup>-(4,5,7-trimethyl-8-coumarinylsulphonyl) semicarbazides**: These were prepared analogously from ethyl N-(4,5,7-trimethyl-8-coumarinylsulphonyl) carbamate and phenyl/p-tolyl hydrazine. The two semicarbazides thus obtained are:

TABLE 1—N<sup>1</sup>-[(4,5,7-TRIMETHYL-8-COUMARINYL-SULPHONYL)]-N<sup>4</sup>-ALKYL/ARYL UREAS


Sl. No.	R	m.p. °C	Yield %	%N Found (Calcd.)	Reduction in blood sugar in rats %
1.*	p-CH <sub>3</sub> C <sub>6</sub> H <sub>4</sub>	182	88	6.55 (7.00)	15
2.*	C <sub>6</sub> H <sub>5</sub>	205	90	6.88 (7.35)	8
3.*	C <sub>6</sub> H <sub>5</sub>	181-183	80	7.94 (8.28)	8
4*	n-C <sub>4</sub> H <sub>9</sub>	174	90	7.99 (8.33)	10
5.	o-CH <sub>3</sub> C <sub>6</sub> H <sub>4</sub>	178	70	6.75 (7.00)	10
6.	p-CH <sub>3</sub> OC <sub>6</sub> H <sub>4</sub>	180	60	6.83 (6.78)	0
7.	o-CH <sub>3</sub> OC <sub>6</sub> H <sub>4</sub>	185	65	6.30 (6.73)	—
8.	p-ClC <sub>6</sub> H <sub>4</sub>	194	80	6.25 (6.66)	13
9.	2,4-Cl <sub>2</sub> C <sub>6</sub> H <sub>3</sub>	180	85	5.47 (6.17)	—
10.	C <sub>6</sub> H <sub>11</sub>	188	70	6.50 (7.14)	10
11.	p-ONC <sub>6</sub> H <sub>4</sub>	179-181	60	9.41 (9.72)	—
12.	2,4-(O <sub>2</sub> N) <sub>2</sub> C <sub>6</sub> H <sub>3</sub>	189	40	9.34 (9.70)	—
13.	2,3-Br <sub>2</sub> C <sub>6</sub> H <sub>3</sub>	188	50	5.14 (5.55)	—
14.*	p-BrC <sub>6</sub> H <sub>4</sub>	190	50	5.71 (6.00)	—

\* Showed IR spectral bands at 1190 cm<sup>-1</sup> (sec SO<sub>2</sub>NH-), 1700 cm<sup>-1</sup> (C=O) and 3250 cm<sup>-1</sup> (-NH-).

I. N<sup>1</sup>-(Phenyl)-N<sup>4</sup>-(4,5,7-trimethyl-8-coumarinylsulphonyl) semicarbazide, m.p. 200°, yield 50%. (Found: N, 10.00. Calcd. for C<sub>20</sub>H<sub>19</sub>O<sub>6</sub>N<sub>3</sub>S; N, 10.4%). IR frequencies (cm<sup>-1</sup>): 1700 (C=O), 1200 (sec SO<sub>2</sub>NH-) and 3200-3340 (-NH-NH-).

It caused reduction in blood sugar in rats by 5%.

II. N<sup>1</sup>-(p-Tolyl)-N<sup>4</sup>-(4,5,7-trimethyl-8-coumarinylsulphonyl) semicarbazide, m.p. 191°, yield 55%. (Found: N, 9.84. Calcd. for C<sub>20</sub>H<sub>21</sub>O<sub>6</sub>N<sub>3</sub>S; N, 10.12%). IR frequencies (cm<sup>-1</sup>): 1700 (C=O), 1160-1180 (sec SO<sub>2</sub>NH-) and 3100-3400 (-NH-NH-).

It reduced the blood sugar in rats by 11%.

**N<sup>4</sup>-(4,5,7-Trimethyl-8-coumarinylsulphonyl) semicarbazide**: A mixture of ethyl N-(4,5,7-trimethyl-8-coumarinylsulphonyl) carbamate (0.03 mol) and hydrazine hydrate (100%; 0.035 mole) was refluxed in absolute ethanol (25 ml) for 8 hr. The product crystallised from ethanol, m.p. 165°, yield 60%. (Found: N, 12.52. Calcd. for C<sub>18</sub>H<sub>17</sub>O<sub>6</sub>N<sub>3</sub>S; N, 12.92%).




## NOTES

TABLE 3—GROSS CNS OBSERVATIONS AND  $ALD_{50}$  OF SOME COMPOUNDS

Compd. No.	Gross CNS observations										ALD <sub>50</sub> mg/kg i.p.
	Dose 484 mg/kg i.p					Dose 1000 mg/kg i.p.					
	S.M.A.	Reactivity	Death	Writhing	Other effects	S.M.A.	Reactivity	Death	Writhing	Other effects	
1.	↓	↓	0/4	(+)	(-)	↓	↓	0/4	(+)	Respiration	1000
2.	↓	↓	0/4	(+)	Respiration	↓	↓	2/4	(+)	(-)	1000
3.	↓	↓	0/4	(+)	"	↓	↓	0/4	(-)	Respiration	1000
4.	↓	↓	0/4	(-)	(-)	↓	↓	0/4	(-)	(-)	660
14.	↓	↓	0/4	(-)	(-)	↓	↓	0/4	(-)	(-)	1000
17.	↓	↓	2/4	(+)	Respiration	↓	↓	0/4	(+)	(-)	870
18.	↓	↓	0/4	(+)	(-)	↓	↓	0/4	(+)	(-)	1000
19.	↑	↑	0/4	(+)	Respiration	↑	↑	0/4	(+)	Respiration	1000
21.	↑	↑	0/4	(-)	Respiration	↑	↑	0/4	(-)	(-)	1000
22.	↑	↑	0/4	(-)	(-)	↑	↑	0/4	(-)	(-)	1000

↓ = decreased, ↑ = increased, (+) = present; (-) = not affected.

\* Correspond to Tables 1 and 2.

TABLE 2— $N^4$ -(4,5,7-TRIMETHYL-8-COUMARINYLSULPHONYL) SEMICARBAZONES

Sl. No.	$R^1$	$R^2$	m.p. °C	Yield %	%N Found (Calcd.)
15.*	$C_6H_5$	H	180	65	9.64 (10.17)
16.*	$\alpha\text{-ClO}_2C_6H_4$	H	180	50	9.00 (9.39)
17.	$C_6H_5CH=CH$	H	146	50	9.41 (9.89)
18.	$p\text{-NH}_2C_6H_4$	$CH_3$	182	75	12.36 (12.67)
19.	$p\text{-OH}C_6H_4$	$CH_3$	176	40	9.32 (9.74)
20.	$C_6H_5$	$CH_3$	120	95	9.45 (9.88)
21.*	$C_6H_5$	$O_2C_6H_4$	152	50	8.14 (8.58)
22.	$C_6H_{10}$		175	50	10.31 (10.37)

\* Showed IR spectral bands at  $1200\text{ cm}^{-1}$  (sec  $SO_2NH-$ ),  $1700\text{ cm}^{-1}$  ( $O=O$ ),  $3100\text{--}3400\text{ cm}^{-1}$  ( $-NH$ ) and  $1600\text{--}1660\text{ cm}^{-1}$  ( $-N=O-$ ).

† Correspond to those in Table-1.

$N^4$ -(4,5,7-Trimethyl-8-coumarinylsulphonyl) semicarbazones: Equimolar amounts of  $N^4$ -(4,5,7-trimethyl-8-coumarinylsulphonyl) semicarbazide and an aldehyde/ketone were refluxed in absolute ethanol in the presence of a drop of glacial acetic acid for 4 hr. The product crystallised from ethanol.

Analysis, melting points and yield of the prepared semicarbazones are presented in Table 2.

#### Bioassay:

(a) *Hypoglycemic activity*: The two compounds (I and II above) and eight compounds (Table 1)

were tested for hypoglycemic activity. They showed very little activity.

(b) *CNS activity*: For studying their action on the central nervous system (CNS), the compounds were administered to albino mice in different doses and their behavioural changes in spontaneous motor activity and reactivity to sound and touch were noted. Ten compounds (Table 3) were screened for CNS activity. They showed very little CNS depressant or stimulant activity.

#### Acknowledgement

The authors are grateful to Dr. V. S. Misra, Head, Chemistry Department, Lucknow University, Lucknow for necessary facilities and to the Vice-Chancellor, Lucknow University for the award of a U. G. C., Junior Research Fellowship to one of them (K. B. G.).

#### References


1. J. MARCO and I. VALVERDE, *Diabetologia*, 1973, 9, (Suppl), 317, *Chem. Abs.*, 1974, 80, 116302.
2. E. MAUPT, W. KOEBERICH, C. ROSAK, J. BEYER and K. SCHOEFFLING, *Arzneim. Forsch.*, 1972, 22, 2198; *Chem. Abs.*, 1973, 78, 106198.
3. V. FITZEL, R. WEYER, W. PRATT and K. HEISSEN, *Ger. Offen.*, 2 720, 926, Nov. 23, 1978, *Chem. Abs.*, 1978, 90, 109843.
4. A. P. DELABY P. J. GABRIEL, Y. PASCAL, *Fr. Demande*, 2 184, 511, Feb. 1, 1974, *Chem. Abs.*, 1974, 80, 146020.
5. M. K. MADEOUR, M. M. HAMDY, A. M. AWAD and R. M. M. EL-ALLAWY, *J. Drug. Res.*, 1977, 9, 1, *Chem. Abs.*, 1978, 40, 406.
6. A. I. VOGEL, "A Text Book of Practical Organic Chemistry", 3rd Edn., 1956, p. 853.
7. BOLLESTEIN, 1983, 17, 344, *C.A. Soc.*, 2020, 08.
8. O. S. WEIL, *Biometrika*, 1952, 8, 249.

# Studies on Some Biologically Active Quinazolones Synthesis of 2-phenoxy methyl-3-N-substituted Amino Carbonyl methyl-8-substituted 4(3H) quinazolones as Anticonvulsant Agents

J. S. SHUKLA, SHRADHA SAXENA and RANJANA MISRA  
Chemistry Department, Lucknow University, Lucknow-226 007  
Manuscript received 3 August 1981, revised 18 December 1981,  
accepted 8 July 1982

**Q**UINAZOLONES and their derivatives have drawn attention because of their prodigious range of activity e. g., CNS depressant<sup>1</sup>, hypnotic<sup>2</sup>, anti-convulsant<sup>3,4</sup>, M.A.O. inhibitory<sup>5</sup>, etc. In the present paper we have described the synthesis of newer quinazolone derivatives with a view of getting enhanced anticonvulsant activity.

Substituted 4H-3,1 benzoxazines<sup>6</sup> (III) were synthesised by the cyclization of substituted phenoxy acetyl chlorides<sup>7</sup> with substituted anthranilic acids in pyridine. The compound III on condensation with glycine gave 2-phenoxy methyl-3-carboxymethyl-8-substituted 4(3H) quinazolones (IV). Acid chloride of (IV) on condensation with different amines in dry benzene and pyridine gave the desired product 2-phenoxy methyl-3-N substituted amino carbonyl methyl-8-substituted 4(3H) quinazolones (V).



Scheme I

## Experimental

Melting points were taken in open capillary and are uncorrected. Infrared spectra were recorded on a Perkin Elmer 137 spectrophotometer in KBr.

**2-(o-Methyl phenoxy methyl)-3-carboxymethyl-8-iodo-(3H)-4-quinazolones:** 2-(o-Methyl phenoxy methyl)-8-iodo anthranil (3.93 g; 0.01 mole) and glycine (0.8 g; 0.01 mole) were taken in 2:1 pyridine water mixture (30 ml) and refluxed on wire gauge for 5-6 hr. The solvent was distilled under reduced pressure. The residue was digested with 4 N HCl (100 ml) on a steam bath for 2-3 hr. The solid mass thus separated was filtered and crystallised from ethanol, m.p. 257°, yield 2.69 g (57%). IR (KBr)  $\nu_{\max}$  cm<sup>-1</sup>: 1695 (COOH), 1230 (C-O-C), 1660 (N-C=O) and 1610 (C=N).

Anal. Found: C, 47.64; H, 3.13; N, 6.01. C<sub>15</sub>H<sub>12</sub>N<sub>2</sub>O<sub>4</sub>I requires C, 48.1; H, 3.3; N, 6.02%. Other compounds of this series were similarly prepared and the results are recorded in Table 1.

TABLE 1—PHYSICAL DATA OF 2-(SUBSTITUTED)PHENOXY METHYL-3-CARBOXYMETHYL-8-SUBSTITUTED-4-QUINAZOLONE (IV)

Comp. No.	R	R <sub>1</sub>	m.p. °C	Molecular formula
Ia	H	H	209	C <sub>17</sub> H <sub>14</sub> N <sub>2</sub> O <sub>4</sub>
Ib	H	o-Cl	218	C <sub>17</sub> H <sub>12</sub> N <sub>2</sub> O <sub>4</sub> Cl
Ic	H	o-OOH	221	C <sub>18</sub> H <sub>14</sub> N <sub>2</sub> O <sub>5</sub>
Id	H	p-OH	199	C <sub>18</sub> H <sub>14</sub> N <sub>2</sub> O <sub>5</sub>
Ie	I	H	248	C <sub>17</sub> H <sub>12</sub> N <sub>2</sub> O <sub>4</sub> I

\* The compounds were obtained in about 66-70% yields. Elemental analyses of C, H and N were consistent.

**2-(o-Methyl phenoxy methyl)-3-N-morpholinyl carbonyl methyl-8-iodo-4(3H)-quinazolone:** A mixture of IV (2.25 g; 0.005 mole) and thionyl chloride (1.19 g; 0.01 mole) was refluxed in dry benzene (35 ml) for 5-6 hr. Excess of benzene was distilled under reduced pressure and morpholine (0.48 g; 0.005 mole) in pyridine (30 ml) added to the reaction mixture. The solution was refluxed for 2 hr. Excess of pyridine was removed and the residue poured in dil HCl and kept overnight. The solid thus separated was crystallised from ethanol to give V, m.p. 162°, yield 1.36 g (50%). Anal. Found: C, 50.52; H, 3.91; N, 8.01%. C<sub>22</sub>H<sub>20</sub>N<sub>4</sub>O<sub>4</sub>I requires C, 50.91; H, 4.054; N, 8.108%. IR (KBr)  $\nu_{\max}$  cm<sup>-1</sup>: 1630 (CON), 1670 (C-N). NMR (CDCl<sub>3</sub>)  $\delta$ : 7.77 (d, 1H, J=8Hz, C<sub>8</sub>-H), 7.31 (t, 1H, J=8Hz, C<sub>8</sub>-H), 6.92 (d, 1H, J=8Hz, C<sub>7</sub>-H), 8.12 (d, 1H, J=7Hz, C<sub>4</sub>-H), 7.64-6.82 (m, 2H, C<sub>5/6</sub>-H), 7.81 (d, 1H, J=7Hz, C<sub>4/1</sub>-H), 2.5 (s, 3H, CH<sub>3</sub>), 3.88 (t, 2H, J=6Hz, OCH<sub>2</sub>).

Other compounds of the series were prepared similarly and the results are shown in Table 2.

**Biological activity:** The compounds were administered i.p. in albino mice of either sex in different doses and approximate LD<sub>50</sub> values were determined by conventional procedure<sup>8</sup>. The results given in Table 2 indicate that the compounds were relatively nontoxic because their LD<sub>50</sub> values are quite high.

The anticonvulsant activity of V against pentylene tetrazole induced seizures was determined in mice<sup>9</sup>. The protection ability against pentylene tetrazole induced seizures ranged from 20-70% (Table 2). Maximum protection was observed in compound II<sub>1</sub> and minimum protection in compound II<sub>7</sub>. These results possibly indicate that the introduction of nucleophile in phenyl ring at position 2 reduced its protecting ability, while introduction of electrophile enhanced its activity.

TABLE 2—PHYSICAL DATA AND BIOLOGICAL ACTIVITY OF 2-PHENOXYMETHYL-8-N-SUBSTITUTED AMINO CARBONYL METHYL-8-SUBSTITUTED-4(8)-QUINAZOLONE (V)

Compound No.	R	R <sub>1</sub>	R <sub>2</sub>	m.p. °C	Molecular formula	LD <sub>50</sub>	Anticonvulsant activity	
							Protection (%)	Mortality (%)
Ila	H	H	morpholinyl	110-112	C <sub>21</sub> H <sub>21</sub> N <sub>3</sub> O <sub>4</sub>	1000	80	80
Ilb	H	o-Cl	thiazolyl	139-140	C <sub>20</sub> H <sub>14</sub> N <sub>3</sub> O <sub>4</sub> SOI	1000	80	80
Ilo	H	o-Cl	pyrrolidinyl	128-130	C <sub>21</sub> H <sub>20</sub> N <sub>3</sub> O <sub>4</sub> Cl	900	40	80
Ild	H	H	pyrrolidinyl	130-131	C <sub>21</sub> H <sub>21</sub> N <sub>3</sub> O <sub>4</sub>	980	80	80
Ile	H	o-Cl	cyclohexyl	145	C <sub>22</sub> H <sub>23</sub> N <sub>3</sub> O <sub>4</sub> Cl	1000	80	70
IIf	H	o-Cl	piperidinyl	105-107	C <sub>22</sub> H <sub>23</sub> N <sub>3</sub> O <sub>4</sub> Cl	850	20	80
Ilg	H	o-OH	thiazolyl	150-151	C <sub>21</sub> H <sub>15</sub> N <sub>3</sub> O <sub>4</sub> S	1000	60	40
Iih	H	H	thiazolyl	198-200	C <sub>20</sub> H <sub>14</sub> N <sub>3</sub> O <sub>4</sub> S	950	50	40
Ili	H	H	cyclohexyl	182	C <sub>22</sub> H <sub>23</sub> N <sub>3</sub> O <sub>4</sub>	1000	40	60
Ilj	H	o-OH	morpholinyl	201	C <sub>22</sub> H <sub>23</sub> N <sub>3</sub> O <sub>4</sub>	1000	60	40
Iik	H	H	thiazolyl	215	C <sub>20</sub> H <sub>14</sub> N <sub>3</sub> O <sub>4</sub> SI	980	50	40
Iil	H	o-OH	piperidinyl	195	C <sub>22</sub> H <sub>23</sub> N <sub>3</sub> O <sub>4</sub>	1000	30	70
Iim	H	H	piperidinyl	170	C <sub>22</sub> H <sub>23</sub> N <sub>3</sub> O <sub>4</sub>	900	40	50
Iin	H	H	morpholinyl	140	C <sub>21</sub> H <sub>20</sub> N <sub>3</sub> O <sub>4</sub> I	850	50	40

\* The compounds were obtained in about 60-64% yields.

Elemental analysis of C, H and N were obtained within  $\pm 0.4\%$ .

- Ilb NMR (CDCl<sub>3</sub>)  $\delta$  ppm, 8.33 (d, 1H, J=7Hz, O<sub>2</sub>-H), 7.63-6.85 (m, 2H, O<sub>2</sub>-H), 7.83 (d, 1H, J=7Hz, O<sub>2</sub>-H), 8.25 (d, 1H, J=7Hz, O<sub>2</sub>-H), 7.60-6.82 (m, 2H, O<sub>2</sub>-H), 7.80 (d, 1H, J=7Hz, O<sub>2</sub>-H), 3.88 (t, 2H, J=6Hz, OCH<sub>2</sub>), 8.30 (d, 1H, J=7Hz, O<sub>2</sub>-H), 7.61-6.81 (m, 2H, O<sub>2</sub>-H), 7.88 (d, 1H, J=7Hz, O<sub>2</sub>-H), 8.19 (d, 1H, O<sub>2</sub>-H), 7.64-6.82 (m, 2H, O<sub>2</sub>-H), 7.80 (d, 1H, J=7Hz, O<sub>2</sub>-H), 3.5 (s, 3H, OH), 3.88 (t, 2H, J=6Hz, OCH<sub>2</sub>), 3.83 (t, 2H, J=6Hz, OCH<sub>2</sub>).
- Ili 8.83 (d, 1H, J=7Hz, O<sub>2</sub>-H), 7.61-6.82 (m, 2H, O<sub>2</sub>-H), 7.81 (d, 1H, J=7Hz, O<sub>2</sub>-H), 3.72 (m, 5H, Arom), 3.83 (t, 2H, J=6Hz, OCH<sub>2</sub>).
- Ili 7.75 (d, 1H, J=8Hz, O<sub>2</sub>-H), 7.32 (t, 1H, J=8Hz, O<sub>2</sub>-H), 6.93 (d, 1H, J=8Hz, O<sub>2</sub>-H), 2.70 (m, 5H, Arom), 3.82 (t, 2H, J=6Hz, OCH<sub>2</sub>).

### Acknowledgement

The authors thank the C.D.R I., Lucknow for facilities for testing the biological activity of the compounds. Two of them (S.S. and R.M.) are grateful to C.S.I.R. and U.G.C. for the award of Postdoctoral Fellowship and Junior Research Fellowship, respectively.

### References

1. I. K. KACKER, S. H. ZAHNER, *J. Indian Chem. Soc.*, 1951, 28, 884.
2. M. L. GUJRAL, P. N. SAXENA and R. S. TEWARI, *Indian J. Med. Res.*, 1955, 43, 687.
3. P. K. SETH and S. S. PARMAR, *Canad. J. Phys. Pharmacol.*, 1965, 43, 1018.
4. J. S. SHUKLA and S. SAXENA, *Indian Drugs*, 1980, 17, 96.
5. J. P. BARTHWAL, S. K. TANDON, V. K. AGARWAL, K. S. DIXIT and S. S. PARMAR, *Pharm. Soc.*, 1973, 62, 618.
6. J. S. SHUKLA and S. SAXENA, *J. Indian Chem. Soc.*, 1979, 56, 1287.
7. J. W. WOOLF and T. D. FONTAINE, *J. Org. Chem.*, 1952, 17, 89.
8. D. R. VARMA, K. M. SARMM and M. L. GUJRAL, *Indian J. Physiol. Pharmacol.*, 1959, 3, 168.
9. R. P. KOHLI, T. K. GUPTA, S. S. PARMAR and R. C. ARORA, *J. Pharmacol.*, 1968, 17, 409.

### Synthesis of 1,2,4-Oxadiazolines Having Antifungal Activity


MANGAT RAI and (Miss) BALJIT KAUR

Department of Chemistry, Punjab Agricultural University,  
Ludhiana-141 004


Manuscript received 19 October 1981, accepted 12 August 1982

In continuation of our work on the synthesis of new heterocyclic compounds<sup>1,2</sup> having antifungal activity 1,2,4-oxadiazolines have been prepared by

the cycloaddition of benzonitrile oxide to 3,4-dimethoxybenzalanimines<sup>1</sup>. The cycloaddition of benzonitrile oxide to 3,4-dimethoxybenzalanimines has been carried out at 0° using different solvents like ether, chloroform, etc. depending upon the solubility of the Schiff bases. Benzonitrile oxide was generated *in situ* by the reaction of bases like triethylamine or 14% sodium hydroxide on the hydroxamoyl chloride<sup>3</sup>. A mixture of two products was obtained in each case. The major product has been found to be the cycloadduct (I) and the minor one is identified as dimer<sup>4</sup> (II) of the nitrile oxide through its m.p. and m.m.p. The cycloadducts can have a structure either Ia or Ib.



(Ia)




(Ib)

TABLE I

Sl. No.	R	m.p. °C	Molecular formula	N% Found (Calcd.)
1.	H	85	C <sub>22</sub> H <sub>20</sub> N <sub>2</sub> O <sub>2</sub>	7.75 (7.77)
2.	p-OH	81	C <sub>22</sub> H <sub>18</sub> N <sub>2</sub> O <sub>3</sub>	7.59 (7.49)
3.	m-Cl	67	C <sub>22</sub> H <sub>17</sub> N <sub>2</sub> O <sub>2</sub> Cl	7.08 (7.10)
4.	p-Cl	74	C <sub>22</sub> H <sub>17</sub> N <sub>2</sub> O <sub>2</sub> Cl	7.08 (7.10)
5.	p-Br	89	C <sub>22</sub> H <sub>17</sub> N <sub>2</sub> O <sub>2</sub> Br	6.89 (6.88)

The infrared spectrum of the cycloadduct showed bands at  $1680\text{ cm}^{-1}$  ( $-\text{CH}=\text{N}-$ ). NMR spectrum in  $\text{CDCl}_3$  of the cycloadduct (I,  $\text{R}=\text{H}$ ) showed six methoxy protons at  $6.1\tau$ , 13 aromatic protons on the  $\text{C}_6$  of the oxadiazoline ring at  $2.1\tau$ . Such a low field shift of  $\text{C}_6$  proton supported structure Ia rather than Ib in which proton is deshielded only by a nitrogen atom.



These 1,2,4-oxadiazolines (1 to 5) were tested for their antifungal activity against *Puccinia striiformis*, *Puccinia recondita*, *Alternaria trititica*, *Alternaria tenuis* and *Pestalotia psidii* by employing standard method of spore germination inhibition. Three concentrations, viz., 1000, 500 and 250 ppm of each of the compounds, have been tried against all the test fungi. All the compounds possessed promising antifungal activity against the above fungi and caused 100% spore germination inhibition even at 250 ppm. The study at still lower concentration is in progress. These observations confirmed our earlier results that presence of methoxy phenyl ring in a compound helps in increasing its activity<sup>1</sup>.

### Experimental

**1,2,4-Oxadiazoline (I,  $\text{R}=\text{H}$ ):** 3,4-Dimethoxybenzaldehyde (2.41 g; 0.01 mole) was dissolved in ether (100 ml) and cooled in an ice bath to  $0^\circ$ . Benzhydroxamoyl chloride (1.1 g; 0.01 mole) in ether (20 ml) was then added with constant shaking and the contents were kept at  $0^\circ$  for some time. Triethylamine (1.2 ml) in ether (20 ml) was then added at a very slow rate with continuous shaking. When the addition was complete the reaction mixture was allowed to stand at  $0^\circ$  for 2 hr. The ether layer was separated out and the residue was washed thrice with dry ether. The combined ether layer and the washings on evaporation of the solvent yielded crystalline solid which on recrystallization from benzene-petroleum ether mixture gave fine shining crystals, m.p.  $65^\circ$  (yield 85%).

**Testing of the compounds against fungus:** Three concentrations (250, 500 and 1000 ppm) of I ( $\text{R}=\text{H}$ ) were taken and treated against fungus *Puccinia striiformis*. The treated spores were incubated for 18 hr and percent spore germination inhibition was calculated by counting 200 spores of each treatment. Spores incubated in water + respective solvent in which the compound is dissolved were used as control. The following

formula is used to calculate % spore germination inhibition.

$$\% \text{ Spore germination inhibition} = \frac{\text{Spore germination inhibition} - \text{Control}}{\text{Control}} \times 100$$

Similarly, other 1,2,4-oxadiazolines were tested for their antifungal activity against *Puccinia striiformis* and other fungi viz., *Puccinia recondita*, *Alternaria trititica*, *Alternaria tenuis* and *Pestalotia psidii*.

### References

1. M. RAY, B. KAUR and B. S. DHIR, *J. Indian Chem. Soc.*, 1982, **59**, 416.
2. M. RAY, B. S. DHIR and P. S. KALSI, *J. Indian Chem. Soc.*, 1982, **59**, 901.
3. N. SINGH, J. S. SANDHU and S. MOHAN, *Tetrahedron Lett.*, 1968, **42**, 4455.
4. H. WIELAND, *Chem. Ber.*, 1907, **40**, 1671.

### Chemical Examination of *Medicago sativa* Seeds

S. P. SHRIVASTAVA\* and S. S. NIGAM

Department of Chemistry, University of Saugar, Saugar-470 008

Manuscript received 17 September 1981, revised 27 April 1982,

accepted 8 July 1982

**MEDICAGO sativa**<sup>1-3</sup> (Leguminosae), known as alfalfa or lucerne, is an erect, much branched annual herb. Its seeds are yellowish brown in colour, kidney shaped, rich in vitamin and enzyme. Looking to its nutritive value, it was thought interesting to investigate fixed oil and unsaponifiable matter from the seeds of this plant.

The crushed seeds of *Medicago sativa* were exhaustively extracted with pet. ether (60-80") and a yellowish brown coloured fixed oil (yield 8.50%) was obtained. The oil was found to have following physico-chemical values.

Specific gravity (25°)	0.9275
Refractive index	1.4624
Acid value	5.32
Saponification value	178.56
Iodine value	8.26
Acetyl value	99.50

100 g of the oil was saponified<sup>4</sup> and the mixed acids (38 g) obtained. The mixed acids were resolved into saturated (7.5 g) and unsaturated (41.5 g) fractions.

Paper and thin layer chromatographic studies showed the presence of palmitic, oleic, linoleic, linolenic and stearic acids.

The fatty acid methyl esters were analysed by gas liquid chromatography using a column of Rheoplex 400-15% supported by chrom-W acid

\* Author for correspondence.

washed of S.S. 4.5' XI/B.O.D. maintained at 180°. Injection port and detector block were maintained at 270° with a flow rate of 40 ml/min with a chart speed of 15 mm/min.

The percentage composition of the acids were calculated based on peak areas\* and it was found to be composed of palmitic (18.10%), oleic (17.60%), linoleic (60.60%), linolenic (2.20%) and small amount of stearic acids.

Chromatographic resolution of the unsaponifiable matter resulted in the isolation of  $\beta$ -amyrin, m.p. 197-98° and  $\beta$ -sitosterol, m.p. 136-37° which were identified by direct comparison with authentic samples.

#### Acknowledgement

One of the authors (S. P. S.) is grateful to Prof. S. S. Nigam for providing authentic samples of  $\beta$ -amyrin and  $\beta$ -sitosterol.

#### References

1. R. N. CHOPRA, I. C. CHOPRA and B. S. VARMA, "Supplement to Glossary of Indian Medicinal Plants", Publication and Information Directorate, Hill Side Road, New Delhi, 1969, p. 66.
2. "The Wealth of India, A Dictionary of Indian Raw Material and Industrial products", 1962, IV, 40.
3. WIT H. G. D. DE, "Plants of World, the Higher Plants", 1963, Vol. 1, p. 813.
4. T. P. HILDETH, "The Chemical Constitution of Natural Fats", Chapman Hall, 1966, p. 574.
5. H. M. MC NAIR and E. J. BANOLLI, "Basic Gas Chromatography", Berkeley, California, 5th Edn., 1969, p. 139.

#### Chemical Constituents of *Cephalotaxus griffithii*

MOHD. KAMIL, NOOR AHMAD KHAN, IQBAL AHMAD,  
MOHD. ILWAS and WASIUR RAHMAN

Department of Chemistry, A. M. U., Aligarh-202 001

Manuscript received 31 December 1981, accepted 8 July 1982

**CEPHALOTAXUS griffithii** HK (Fam. Cephalotaxaceae), collected from Nainital, has been investigated for its chemical constituents and led to the isolation of amentoflavone, sequoiavone, apigenin, ginkgetin, mono-O-methyl-C-methyl amentoflavone and quercitrin. 1,6-C-Methyl-1,7-O-methyl amentoflavone constitutes the second report of isolation and characterization of naturally occurring C-methyl biflavones.

Finely ground dried leaves of *Cephalotaxus griffithii* (3 kg) were successively extracted with petrol (40-60°), benzene, chloroform, ethyl acetate and finally with acetone. The last two extracts were concentrated and chromatographed over silicagel to furnish six bands labelled as CGI, CGII,

CGIII, CGIV, CGV and CGVI, in order of increasing  $R_f$  values. All these bands were separated by preparative tlc (BPF, 36:9:5)<sup>1</sup> and eluted by acetone mixed with pyridine (2%). CCI (0.2 g) obtained, gave a single spot on tlc,  $R_f$  0.18, m.p. 320°. The yellow solid mass (80 mg) was methylated to give hexa-O-methyl amentoflavone (50 mg), m.p. 173-74°,  $R_f$  0.40. Acetylation (Ac<sub>2</sub>O/pyridine) of yellow solid (80 mg) yielded a white solid which crystallized from CHCl<sub>3</sub>-MeOH to give amentoflavone hexaacetate, m.p. 242-43°.

The identity of sequoiavone and apigenin was established by direct comparison of their acetate and methylethers with those of authentic samples. (m.p., m.m.p., fluorescence in uv light and nmr data).

CGIV, m.p. 350° (decom), C<sub>28</sub>H<sub>18</sub>O<sub>8</sub>(OMe)<sub>8</sub>,  $\lambda_{max}$  (ethanol): 271 nm band I, 335 nm band II. Tetraacetyl derivative, C<sub>28</sub>H<sub>18</sub>O<sub>8</sub>(OMe)<sub>8</sub>(OAc)<sub>4</sub>, was prepared, m.p., 265-267°.  $\lambda_{max}$  (ethanol): 211, 248-258, 317 nm, finally confirmed as dimethylether of amentoflavone (ginkgetin) by comparison with an authentic sample.

CGV, m.p. above 338°,  $R_f$  0.39, C<sub>28</sub>H<sub>22</sub>O<sub>10</sub>, M<sup>+</sup>566. Mass spectrum of its methylether showed mol. ion peak at M<sup>+</sup>636 and base peak at m/e 621, m.p. 234,  $R_f$  0.45. The compound was finally established as 1,6-C-methyl-1,7-O-methyl amentoflavone by comparison (co.tlc, uv, nmr and mass) with authentic sample<sup>2</sup>.

CGVI, C<sub>28</sub>H<sub>20</sub>O<sub>11</sub>,  $\lambda_{max}$  275, 352 m $\mu$  was hydrolysed (10% HCl) and aglycone and sugar were chromatographed with authentic samples. The sugar was found to be rhamnose. The aglycone, m.p. 182-185° was identical in all respects with quercetin. The structure of CGVI was finally confirmed as quercetin 3-rhamnoside by comparison of its nmr spectral data with that of authentic sample.

#### Acknowledgement

The authors are grateful to Professor N. Kawano of Nagasaki University, Nagasaki, Japan and Prof. Dr. H. Wagner of Institut für Pharmazent Arznei-mittel-lehre, West Germany for spectral studies. Their thanks are also due to C.S.I.R., New Delhi and U.G.C., New Delhi for the award of research fellowships to two of them (N. A. K. and I. A.).

#### References

1. K. K. CHAKAL, B. K. HANDA and W. RAHMAN, *J. Chromatogr.*, 1970, 48, 484.
2. M. AGUIL and W. RAHMAN, *J. O. S. Parkin I*, 1981, 1889.

# Selective Microgram Detection of Iron(III) on Ion Exchange Resin Beads

SUVED A. NABI\*, AHSAN R. SIDDIQUI, M. ATHAR

and

N. AHMAD

Department of Chemistry, Aligarh Muslim University,  
Aligarh-202 001

Manuscript received 6 October 1980, accepted 21 July 1982

THE analytical importance of resin beads for the detection of inorganic and organic compounds have been well established<sup>1-3</sup>. The advantage of using resin spot test over detection techniques lies in the fact that it not only increases the sensitivity but also enhances the selectivity. Though a number of methods for the detection of iron(III) are available in the literature<sup>4-6</sup>, these are either insensitive or suffer from interferences of a large number of cations specially with Fe(II) and anions. We describe in this paper a sensitive and selective method for the detection of iron(III) on resin beads in microgram of the sample.

## Experimental

**Reagents:** All the reagents used were of analytical grade.

**Test solutions:** Solutions of Fe(NO<sub>3</sub>)<sub>3</sub> (0.001 M) and anisaldehyde antipyrine (0.5%) were prepared in distilled alcohol.

**Resin:** Dowex 50 W×8 (20-30 mesh) in H<sup>+</sup> form was used after regeneration and washing with demineralized water. The beads were soaked on a filter paper and used for the detection.

**Procedure:** 5-10 beads of ion-exchange resin in H<sup>+</sup> form were taken in a spot plate. To this one drop of anisaldehyde antipyrine solution was added. Then 0.1 ml of 0.001 M ferric nitrate (containing 5.6 µg of Fe) was added. The pH was maintained around 6. The beads turned pink after 2 min. The colour of the beads was compared by a simultaneous test in the absence of iron. With the successive increment in the iron content in the solution, the colour of the beads changes from pink to violet. The lower limit of the detection for iron(III) was found to be 1.12 µg.

**Interferences:** To show the analytical importance of the test, the detection of iron(III) (1.12 µg) was also performed in the presence of a large number of cations and anions using the above procedure. The limit of tolerance for each ion is given in Table 1.

The result of the above study reveals that iron in a sample can be successfully detected upto a limit of 1.12 µg using strong exchange resin in the H<sup>+</sup> form in the presence of anisaldehyde antipyrine as reagent. The procedure is simple and less time consuming. The advantage of using the ion exchange beads as a detection medium is that it

TABLE 1—EFFECT OF FOREIGN IONS IN THE DETECTION OF Fe(III); Fe(III)=1.12 µg.

Sl. No.	Foreign ions	Limit of tolerance (µg)
1.	VO <sup>+</sup>	500
2.	Cr <sup>3+</sup>	500
3.	Co <sup>3+</sup>	500
4.	Ni <sup>3+</sup>	500
5.	Cu <sup>2+</sup>	500
6.	Zn <sup>2+</sup>	500
7.	Zr <sup>4+</sup>	500
8.	Sn <sup>4+</sup>	500
9.	Bi <sup>3+</sup>	500
10.	Th <sup>4+</sup>	500
11.	Ce <sup>3+</sup>	500
12.	Pt <sup>4+</sup>	500
13.	UO <sub>2</sub> <sup>2+</sup>	500
14.	Na <sup>+</sup>	1000
15.	K <sup>+</sup>	1000
16.	Ca <sup>2+</sup>	1000
17.	Mg <sup>2+</sup>	1000
18.	Ba <sup>2+</sup>	1000
19.	Sr <sup>2+</sup>	1000
20.	Pb <sup>2+</sup>	1000
21.	Al <sup>3+</sup>	1000
22.	Gd <sup>3+</sup>	1000
23.	In <sup>3+</sup>	1000
24.	La <sup>3+</sup>	1000
25.	Hg <sup>2+</sup>	1000
26.	Ag <sup>+</sup>	1000
27.	Y <sup>3+</sup>	1000
28.	Acetate	250
29.	Molybdate	250
30.	Tungstate	250
31.	Phosphate	1000
32.	Bromate	1000
33.	Iodate	1000
34.	Chlorate	1000
35.	Sulphate	1000
36.	Chloride	1000
37.	Bromide	1000
38.	Iodide	1000
39.	Chromate	1000
40.	Vanadate	1000
41.	Fe(II)	2000

retains the colour for a fairly long time after the test is performed. The colour starts disappearing at once when the same test is performed in the absence of beads. An additional advantages of this procedure is that it distinguishes between Fe(III) and Fe(II) as in the latter case the test gives negative results.

## Acknowledgement

The authors are grateful to Professor W. Rahman, Head, Department of Chemistry, Aligarh Muslim University, Aligarh, for facilities and C.S.I.R., New Delhi for financial assistance to one of them (A. R. S.).

## References

1. M. FUJIMOTO, *Chemist-Analyst*, 1980, 49, 4.
2. A. TSUJI, *Nippon Kagaku Zasshi*, 1968, 84, 919.
3. J. H. YON, *J. Amer. Chem. Soc.*, 1952, 54, 4189.
4. M. FUJIMOTO, *Bull. Chem. Soc. Japan*, 1956, 29, 276.
5. V. ARMEANU, D. CAMBOLI and C. IANCU, *Anal. Abstract*, 1960, 7, 999.
6. E. SCHWIMMER, *Acta Chim. Acad. Sci. Hung.*, 1958, 14, 811.

## Colorimetric Estimation of Ce(IV) by Phenothiazines

R. T. SANE\* and A. B. AMBARDEKAR

Department of Chemistry, Ramnarain Ruia College, Matunga, Bombay-400 019

Manuscript received 6 March 1982, accepted 21 July 1982

SANKE Gowda and others<sup>1</sup> have reported a method of estimation of Ce(IV) by using fluphenazine hydrochloride as a complexing reagent. Our present investigation relates to the use of different phenothiazines as reagents for the spectrophotometric estimation of Ce(IV).

### Experimental

Standard solution of Ce(IV) (100 ppm) was prepared by dissolving requisite amount of ammonium ceric nitrate in distilled water and was standardised by the method given in literature<sup>2</sup>. 1% solutions of phenothiazines in methanol were prepared and used as reagents

**Procedure:** To a solution containing 100 µg of cerium(IV) is added 0.5 ml of 1% ligand solution and mixed. The acidity of the mixture is adjusted between 2.4 to 4.0 molar with orthophosphoric acid in a total volume of 10 ml. The solution is diluted to 10 ml with distilled water and absorbance of the solution is recorded after 5 min at 510 nm. The amount of metal present in the solution is then determined from the calibration curve drawn under identical conditions.

The colour of the complex attains stability 5 min after the addition of reagent and is stable upto 25 min.

Physico chemical constants of the complexes have been summarised in Table I. Molar composition of the complexes were determined by Job's method of continuous variation<sup>3</sup> and were found to be 1 : 1 (M : L) in all the cases.

TABLE I

Sl. No.	Reagent	Operative range from Ringbom's plot, µg/ml	Molar absorptivity $\times 10^{-3}$ lit. mole <sup>-1</sup> cm <sup>-1</sup>	Sandell's sensitivity µg/cm <sup>2</sup>
1.	Promethazine HCl	9.6 to 12.9	4.48	$9.1 \times 10^{-5}$
2.	Promazine HCl	5.6 to 12.9	5.61	$2.5 \times 10^{-5}$
3.	Chlorpromazine	4.0 to 14.1	6.73	$2.1 \times 10^{-5}$
4.	Thiopropazine mesylate	4.7 to 16.8	6.46	$2.2 \times 10^{-5}$

The tolerance limits of various cations and anions are: Cd<sup>2+</sup> (1 : 10); Ni<sup>2+</sup> (1 : 8); Zr<sup>4+</sup> (1 : 10); Cu<sup>2+</sup> (1 : 10); Pb<sup>2+</sup> (1 : 10); Fe<sup>2+</sup> (1 : 10); U<sup>6+</sup> (1 : 10); Mn<sup>2+</sup> (1 : 10); Be<sup>2+</sup> (1 : 10); Th<sup>4+</sup> (1 : 10); Zn<sup>2+</sup> (1 : 10); Ca<sup>2+</sup> (1 : 10); Ba<sup>2+</sup> (1 : 10); Cl<sup>-</sup> (1 : 10); Br<sup>-</sup> (1 : 10); SO<sub>4</sub><sup>2-</sup> (1 : 10); NO<sub>3</sub><sup>-</sup> (1 : 10); CH<sub>3</sub>COO<sup>-</sup> (1 : 10); ClO<sub>4</sub><sup>-</sup> (1 : 8); B<sub>4</sub>O<sub>7</sub><sup>2-</sup> (1 : 10); Mo<sub>7</sub>O<sub>4</sub><sup>2-</sup> (1 : 6); C<sub>2</sub>O<sub>4</sub><sup>2-</sup> (1 : 10).

It was found that cations such as Sn<sup>2+</sup>, Fe<sup>2+</sup>, As<sup>3+</sup>, V<sup>3+</sup> and anions such as NO<sub>3</sub><sup>-</sup>, Fe(CN)<sub>6</sub><sup>4-</sup>, CNS<sup>-</sup>, S<sub>2</sub>O<sub>3</sub><sup>2-</sup>, SO<sub>3</sub><sup>2-</sup>, BrO<sub>3</sub><sup>-</sup> interfere seriously with the reaction.

### Acknowledgement

The authors are grateful to Mr. A. Y. Dhamankar and Mr. U. R. Pandit for helpful discussions.

### References

1. H. S. GOWDA, K. N. THIMMAIAH and B. N. ACHAR, *Rev. Roum. Chim.*, 1977, 22, 745.
2. A. I. VOGEL, "Text Book of Quantitative Inorganic Analysis".
3. J. E. JOX and A. Z. JONES, *Ind. Eng. Chem., Anal. Ed.*, 1944, 16, 111.

## Spectrophotometric Determination of Ruthenium with Prochlorperazine Bismethanesulphonate

H. SANKE GOWDA\* and A. THIMME GOWDA

Department of Post-graduate Studies and Research in Chemistry, University of Mysore, Manasagangothri, Mysore-570 006

Manuscript received 27 July 1981, revised 18 March 1982, accepted 8 July 1982

DURING the investigation on the reaction of phenothiazines with metal ions, prochlorperazine bismethanesulphonate, (PCPMS) 2-chloro-10-[3-(4-methyl-1-piperiziny) propyl] phenothiazine bismethanesulphonate, was found to give red colour with ruthenium(III) in phosphoric, sulphuric or hydrochloric acid. This reaction is now utilized for rapid spectrophotometric determination of ruthenium(III). The proposed method offers the advantages of simplicity, rapidity, sensitivity, reasonable selectivity and determination at room temperature without the need for extraction.

### Experimental


**Reagents and apparatus:** A stock solution of ruthenium(III) was prepared by dissolving ruthenium(III) chloride (Johnson and Matthey, London) in dilute hydrochloric acid and diluting to 1 litre to give a solution of 1 M with respect to hydrochloric acid. The solution was standardized gravimetrically<sup>1</sup> and was further diluted to give a solution of 25 µg/ml. A 0.2% solution of PCPMS was prepared in double distilled water and stored in an amber bottle in a refrigerator. A Beckman Model DB spectrophotometer with matched 1 cm silica cells was used for absorbance measurements.

**Procedure:** An aliquot of the stock solution containing 5-205 µg of ruthenium(III) and 14 ml of 10 M phosphoric acid were transferred to a 25 ml volumetric flask, 3 ml of 0.2% PCPMS solution was added to this and the volume made upto the mark with double distilled water. The solutions were

mixed well and the absorbance was measured at 529 nm against the corresponding reagent blank prepared in the same manner. The amount of ruthenium in the sample solution was deduced from the standard calibration curve.

### Results and Discussion

PCPMS readily forms red species with ruthenium(III) at room temperature (27°) in phosphoric, sulphuric or hydrochloric acid. The study of the red species, which is believed to be a radical cation<sup>2,3</sup>, in sulphuric and hydrochloric acid media is not recommended because the reaction is less sensitive, less stable and many foreign ions interfere. Phosphoric acid was therefore selected for further studies. PCPMS and red species have the following structure.



The effect of varying the concentration of phosphoric acid was investigated. The rate of colour development and the sensitivity increase with increasing acid concentration from 0.5-5 M and then remain constant over the range 5-6 M (Fig. 1). The maximum colour development takes place instantaneously at room temperature in 5-6 M acid. An acid strength of 5.5 M of  $H_3PO_4$  was chosen for all subsequent work. The absorbance of the red species remains constant for 90 min.




Fig. 1. Effect of  $H_3PO_4$  concentration.

The absorption spectra of the reagent, ruthenium(III) and the red species in 5.5 M phosphoric acid are shown in Fig. 2. The red species exhibits maximum absorbance at 528-530 nm. The reagent and ruthenium(III) show little absorption at this wave length. Subsequent studies were made at 529 nm.

Beer's law was obeyed over the concentration range 0.2-7.3 ppm of ruthenium(III) with an optimum concentration range 0.7-6.9 ppm. The molar absorptivity was  $1.17 \times 10^4 \text{ l. mol}^{-1} \text{ cm}^{-1}$ . Sandell's




Fig. 2 Absorption spectra of reagent blank, ruthenium(III) and red species.

A. Reagent blank, B. Ruthenium(III) and C. Red species ( $Ru(III) = 3 \text{ ppm}$ ,  $H_3PO_4 = 5.5 \text{ M}$ ).

sensitivity was estimated to be  $8.6 \text{ ng cm}^{-2}$ . The standard deviation calculated from 10 determinations on a solution containing 3 ppm of ruthenium was  $\pm 0.025$ .

The effect of reagent concentration was examined by measuring the absorbance of solutions containing 3 ppm of ruthenium(III) and varying amounts of PCPMS. A 12-fold molar excess of the reagent was necessary to produce maximum colour intensity. The optimum amount of 3 ml of 0.2% of the reagent solution was used. There is no appreciable change in the absorbance if the order of addition of reactants is varied. The absorbance values are not affected over the temperature range 10-52°. Above

TABLE 1—EFFECT OF DIVERSE IONS IN THE DETERMINATION OF  $Ru(III)$  (AMOUNT OF  $Ru(III)$  TAKEN, 3 ppm)

Ion added	Tolerance limit* ppm	Ion added	Tolerance limit* ppm
$Fe(III)$	4000	$Pb(II)$	260
$Co(II)$	150	$V(V)$	0.1
$Cu(II)$	1100	$W(VI)$	800
$Ni(II)$	1000	$Ti(IV)$	700
$U(VI)$	1300	$Mn(II)$	600
$Zn(II)$	1800	$Ta(V)$	800
$Mg(II)$	9400	$F^-$	2800
$Ag(I)$	1.5	$Cl^-$	6000
$Pd(II)$	1.2	$Br^-$	4000
$Pt(IV)$	85.0	$I^-$	1.3
$As(III)$	0.8	$NO_3^-$	4800
$Os(VIII)$	0.8	$SO_4^{2-}$	10000
$Rh(III)$	24.0	Acetate	2800
$Ir(III)$	18.0	Chlorate	1800
$Al(III)$	1400	Oxalate	1500
$Mo(VI)$	800	EDTA	180
$Zr(IV)$	900	Tartrate	1600

\* Amount causing an error of less than 2%.



52', the absorbance gradually decreases with the rise in temperature.

The interference of several cations and anions which often accompany ruthenium were examined by carrying out determinations of 3 ppm of ruthenium(III) in the presence of each of these ions. Results in Table 1 show that PCPMS is selective for ruthenium(III), but Pd(II), Os(VIII), Au(III), V(V), Ag(I) and iodide interfere strongly. The nature of the red species was studied by passing an aliquot of the solution of the species through cation exchange resin, Dowex 50W-X8 and anion exchange resin Dowex 1-X8. The red species was retained by Dowex 50W-X8 and not retained by Dowex 1-X8. This indicated that the species is cationic.

#### Acknowledgement

The authors thank University Grants Commission, New Delhi, for the award of a Teacher Fellowship to one of them (A. T. G.) and Dr. B. Julou and Dr. J. Molle of Rhone-Poulenc Centre, Nicolas Grillet, Paris for the supply of pure PCPMS.

#### References

1. F. E. BRAMISH, "The Analytical Chemistry of Noble Metals", Pergamon Press, London, 1966, p. 260.
2. P. C. DWIVEDI, K. GURUDATH RAO, S. N. BHAT and C. N. B. RAO, *Spectrochim. Acta*, 1975, 31, 129.
3. A. B. KATRITZKY and A. J. BOULTON (Eds), "Recent Advances in Chemistry of Phenothiazines Advances in Heterocyclic Chemistry", Academic Press, New York, 1968, 9, 321

### An Indirect Method for Iodometric Microdetermination of Certain Organic Acids

M. G. PATERIA and R. M. VERMA\*

Department of Chemistry, University of Jabalpur, Jabalpur-482 001

Manuscript received 16 September 1981, revised 1 March 1982, accepted 8 July 1982

SINCE most carboxylic acids are weakly dissociated, their alkalimetry at micro level is confronted with two difficulties—poor inflection on the pH neutralisation curve which further contracts with increasing dilution of acid and alkali, and fading away of the phenolphthalein colour at the end-point<sup>1</sup>.

Potentiometric location of the end-point is hampered owing to the formation of a buffer<sup>2</sup>. The alkalimetry in non-aqueous medium has also been attempted using protophilic solvents, but in micro acidimetry the detection of the end-point is difficult.


Further, titrants such as sodium triphenylmethyl and lithium aluminium hydride are too unstable to be used as 0.01 N standards<sup>3</sup>.

The present communication describes a micro procedure which consists of heating the acid sample with iodide and a known excess of potassium iodate solution and subsequent iodometric determination of the surplus iodate. The quantity of acid present in the test solution is calculated from the amount of iodate consumed. The quantitative reaction is accomplished only in 3-5 min even with samples containing as low as 0.025 meq of the different organic acids studied. In order to ascertain suitable experimental conditions for the determination, the effect of change in the amount of iodide and iodate and in the reaction period in the case of each acid has also been investigated. On the basis of the results of these preliminary experiments a general procedure applicable for determining 0.025-0.1 meq of certain organic acids has been worked out.

#### Experimental

**Reagents:** The following solutions were prepared using analytical grade chemicals and conductivity water, 0.1 N (0.0166 M) potassium iodate, which was also used to standardize the sodium thiosulphate solution (0.1 N), 0.01 and 0.005 N solutions were obtained by suitable dilution of the 0.1 N solutions. 0.05 N solutions of mono-, di- and tri-chloroacetic, furoic, sulphamic,  $\beta$ -chloropropionic, isobutyric, fumaric and benzoic acids were prepared and standardized by alkalimetry and diluted suitably to prepare the test solutions. In addition, 10% potassium iodide, 4 N sulphuric acid and 1% aqueous starch solutions were also prepared.

**Procedure:** An aliquot of an acid solution containing 0.025-0.1 meq of the acid is pipetted into a 100 ml erlenmeyer flask and 10 ml of 10% potassium iodide and 5-20 ml of 0.01 N potassium iodate solution (about 100% excess) are added. The flask is then kept immersed in a boiling water bath for 3-5 min after which it is cooled immediately under tap. 1 ml of starch solution is introduced and thiosulphate solution is added dropwise with constant shaking until the decolourisation of the blue colour. About 2 ml of 4 N sulphuric acid is then added and the liberated iodine is titrated with 0.01 or 0.005 N thiosulphate. A blank is also run. The difference between the blank and the experimental titres gives the amount of iodate used up. From this, the quantity of the acid present in the assay solution is calculated using the following relationships.



1 ml of 0.01 N thiosulphate = 0.45 mg of COOH group.

\* Author for correspondence.

## Results and Discussion

The proposed iodometric method has been applied for the determination of certain organic acids of varied nature. The recovery studies have been performed at three different concentration levels of each acid and the results recorded in Table I are the average of 6 determinations. Table I also gives a comparative study of errors observed in the alkalimetric and the proposed method for different acids studied. The average deviation in the latter method is in the range of 0.1-0.3%.

According to Smith<sup>3</sup>, a neutralisation indicator works satisfactorily only when the inflection or the pH neutralisation curve is more than 2 pH units. In titrating organic acids at micro level using 0.01 N alkali as the titrant, the inflection range is small. The difficulty in the detection of the end-point is further accentuated by the fading away of the phenolphthalein colour at the end-point. The alkalimetry of weak acids at micro level, therefore, gives a considerable positive error<sup>4</sup>.

TABLE I—DETERMINATION OF CERTAIN ORGANIC ACIDS

Acid	Alkalimetry			Iodometry		
	Percent mg	Found mg	% Average deviation	Found mg	% Average deviation	
Acetic	6.000	6.080	+0.50	5.915	-0.08	
	3.000	3.080	+1.00	3.003	+0.10	
	1.500	1.527	+1.83	1.497	+0.20	
Monochloroacetic	9.450	9.488	+0.40	9.458	+0.08	
	4.725	4.764	+0.83	4.730	+0.10	
	2.363	2.398	+1.50	2.359	-0.18	
Dichloroacetic	12.000	12.041	+0.33	12.889	-0.08	
	6.450	6.504	+0.84	6.461	+0.17	
	3.225	3.268	+1.33	3.230	-0.15	
Trichloroacetic	16.850	16.377	+0.16	16.387	-0.08	
	8.175	8.216	+0.50	8.168	-0.08	
	4.088	4.186	+1.17	4.091	+0.16	
Furoic	11.209	11.245	+0.33	11.226	+0.16	
	5.604	5.651	+0.84	5.595	-0.16	
	2.802	2.844	+1.50	2.806	+0.16	
Sulphamic	9.709	9.768	+0.60	9.718	+0.12	
	4.855	4.887	+0.66	4.863	+0.16	
	2.427	2.468	+1.50	2.423	-0.16	
$\beta$ -Chloropropionic	10.853	10.889	+0.33	10.835	-0.16	
	5.426	5.480	+0.99	5.435	+0.16	
	2.713	2.751	+1.40	2.722	+0.33	
Isobutyric	8.810	8.869	+0.66	8.795	-0.16	
	4.405	4.449	+1.00	4.390	-0.33	
	2.203	2.240	+1.66	2.196	-0.33	
Fumaric	5.808	5.822	+0.23	5.793	-0.16	
	2.902	2.931	+1.00	2.897	0.16	
	1.451	1.470	+1.38	1.446	-0.33	
Benzoic	22.800	22.914	+0.50	22.819	+0.08	
	11.400	11.514	+1.00	11.382	-0.16	
	5.700	5.795	+1.66	5.681	-0.33	

\* Calculated from six determination.

In the case of titration with alkali the phenolphthalein colour fades rapidly at the end-point. The first appearance of the pink colour was noted.

Acids can also be determined by treating them with an excess of iodide and iodate solution followed by the titration of the liberated iodine

and this can be used as an alternative, often more accurate to alkalimetry<sup>5</sup>. The iodometric method works well with strong acids but failed when applied to weak acids owing to slow reaction rate so that the reaction was not complete in 24 hr<sup>6</sup>. The reaction mixture could not be heated to speed up the determination on account of volatility of iodine. Recently, the addition of solid iodide and iodate has also been suggested for a direct iodometric determination of some organic acids<sup>7</sup>. Kolthoff<sup>8</sup> suggested addition of a known excess of thiosulphate to acid solution containing iodide and iodate and subsequent back-titration of the surplus thiosulphate. But this procedure involves long reaction periods<sup>9</sup>. Moreover, there is a possibility of the thiosulphate reacting with the acid<sup>10</sup> thus vitiating the stoichiometry of the main reaction.

The proposed method is based on the measurements of the iodate consumed rather than on the titration of the liberated iodine when an acid sample is treated with iodide and iodate. With this changed approach it is possible to heat the reaction mixture when the quantitative reaction can be achieved in 3-5 min with acid samples containing 0.025-0.1 meq of the acid. The procedure thus becomes rapid and being iodometric gives sharp end-point even when 0.01 or 0.005 N thiosulphate solution is used for titration. This iodometric method can also be adopted for determining acid content in various natural products which are slightly coloured, thereby rendering the neutralisation indicator unsuitable. In evaluating acid content of substances<sup>11</sup> containing components capable of reacting with alkali, the alkalimetry cannot yield correct results. In such cases also the proposed iodometric method possesses a distinct advantage.

## Acknowledgement

The authors are grateful to the University Grants Commission, New Delhi for the award of a fellowship to one of them (M. G. P.).

## References

1. N. D. CHRONIS and T. S. MA, "Organic Functional Group Analysis by Micro and Semimicro Methods", Interscience, New York, 1964, p. 485, 402.
2. P. O. KOSONEN, *Finn. Chem. Lett.*, 1975, 5, 121.
3. T. B. SMITH, "Analytical Processes", 2nd Edn., Arnold, London, 1952, p. 228.
4. A. STEVERMARK, "Quantitative Organic Microanalysis", 2nd Edn., Academic Press, New York, 1961, p. 412.
5. M. R. F. ASHWORTH, "Titrimetric Organic Analysis", Interscience, New York, 1965, p. 477.
6. I. M. KOLTHOFF and R. BELCHER, "Volumetric Analysis", Interscience, New York, 1957, Vol. III, p. 276.
7. S. N. NEMA and R. M. VERMA, *Analyst*, 1976, 104, 691.
8. I. M. KOLTHOFF, *Chem. Weekblad*, 1926, 23, 360.
9. G. M. NARAR and C. V. PADMANABHAN, *Proc. Indian Acad. Sci.*, 1950, 31, 371.
10. G. W. LATIMER and E. I. STETCO, *Talanta*, 1967, 14, 984.
11. N. B. KAMATH and V. B. MAINKER, *Anal. Chem.*, 1950, 22, 734.

## OBITUARY



### Priyadarshan Ray

(Born : January 16, 1888 : Died : December 11, 1982)

On Saturday December 11, 1982 morning Professor Priyadarshan Ray passed away after protracted illness at the age of 95 years. An erudite scholar deeply dedicated to his profession, he imbibed in his life the best of Indian traditions and philosophy combined with scientific reasoning, analytical approach and a missionary zeal. In India, he was a pioneer in the field of researches in coordination chemistry in its various aspects and microchemical methods of analysis. His death has left a void in the field of chemical education and chemical research which would be difficult to fill in the near future. For many of us, whose joys and sorrows he used to share and who received all the inspiration and encouragement even in their futile efforts, his death is a great personal loss.

Priyadarshan Ray was born on January 16, 1888 in a well-known Zamindar (landlord) family in village Noapara in Chittagong district (now in Bangladesh). This Zamindar family was well-known for their benevolence, righteousness and endeavour in the promotion of education and learning.

Priyadarshan had his early education in his own village school from where he passed the Higher Primary Examination in the first division in the year 1898. The Headmaster of the school was Rashmohan Sen who was a teacher of repute and a man of profound honesty and integrity who influenced greatly young Priyadarshan. Having finished his primary education in the village school

Priyadarshan joined the Chittagong Collegiate School in 1899. He passed the Entrance Examination (i.e. Final High School Examination) in 1904 in the first division and secured a merit scholarship. In 1906, he passed the F. A. Examination (Intermediate College Examination) from the Chittagong Government College also securing a merit scholarship and a certificate for originality in Bengali composition, a talent which he further cultivated in his later life which produced many excellent scientific and philosophical writings and essays on various socio-economic problems, both in Bengali as well as in English.

In July, 1906 Priyadarshan came to Calcutta for higher education and joined the first year B. A. class in Presidency College. Here Priyadarshan came in contact with renowned teachers and educationists like H. M. Parcival, who was then the Principal of the College, Acharya Jagdish Chandra Bose (Sir J. C. Bose) and Acharya Prafulla Chandra Ray (Sir P. C. Ray), all of whom greatly influenced his future career. In 1908, he passed the B. A. Examination from Presidency College with Honours in Chemistry and Physics. In addition to studying Chemistry and Physics he studied and mastered well the three languages English, Bengali and Sanskrit in his B. A. course. Later, he attained proficiency in German language also. Acharya Prafulla Chandra Ray's inspiration took him to Chemistry for his M. A. Examination and he passed this examination from Presidency College in 1911

in the First Class having stood first in order of merit and secured the Calcutta University Gold Medal and Motilal Mullick Gold Medal.

Having received his M. A. degree, Priyadarajan started research work in Inorganic Chemistry in the Presidency College in Acharya Prafulla Chandra Ray's laboratory. However, on August 12, 1912, he met with a severe accident in the laboratory and as a result lost his left eye and suffered severe injuries to his right eye and other parts of the body for which he was hospitalized for quite some time. It was just before this accident that he had his first research paper published (*Die Einwirkung Von Hydrazin und Hydroxylamin auf Ferricyanide und neuer methoden Zur Bestimmung von Hydrazin und Ferricyaniden*), P. Ray and H. K. Sen, *Z. anorg. Chem.*, 1912, 76, 380).

The after effects of the accident and particularly frail vision in the injured right eye prevented him to carry on any work for nearly two years. In 1914 he joined the City College, Calcutta as a Professor of Chemistry and worked in this capacity upto 1918. At this time Sir Ashutosh Mookherjee, who was then Vice-Chancellor of the University of Calcutta, was looking for competent young teachers and research workers to join the newly established University College of Science, Calcutta, to help and assist Acharya Prafulla Chandra Ray, then Sir Tarak Nath Palit Professor and Head of the Department of Chemistry in the University College, to develop the institute to an advanced centre of scientific teaching and research in the country. Priyadarajan was one of those who was picked up by Sir Ashutosh for this purpose and in the year 1919 Priyadarajan joined the University College of Science, Calcutta, as Assistant Palit Professor of Chemistry. Here he devoted himself to teaching and research and he was given the charge of organising and developing the Inorganic Chemistry Division. It was by his devotion and perseverance that he soon succeeded, inspite of many odds, to establish a renowned school of modern Inorganic Chemistry in the University College of Science where he devoted the best part of his research career for nearly four decades till his retirement from this institute in December, 1952.

While working as Assistant Palit Professor of Chemistry in the University College of Science, Professor Ray published several original research papers which earned him an international fame. In the words of his *guru* (late) Acharya Prafulla Chandra Ray (1932). "He is regarded as an acknowledged authority on complexes and valency and also on Micro-chemistry and it is my practice to submit my own papers to his criticism and judgement before they are contributed to the Chemical Societies. My Presidential addresses at the annual meetings of the Indian Chemical Society of 1926 and 1929 are based mainly upon his ideas and suggestions. A more silent and unobtrusive worker is seldom to be met with. ...He has already published a score of papers, any one of which if

submitted to any University would win for him a doctorate. He has not, however, as yet been able to make up his mind to do this. Events are of two kinds—the silent and the noisy. Priyadarajan's work comes under the former category".

Priyadarajan has been a silent worker throughout his life who had no lust for glamour such as foreign travel even in his younger days. It was by much effort that his *guru* Acharya Prafulla Chandra could persuade him to go to Europe on a Ghose Travelling Fellowship of the University of Calcutta as a Visiting Professor to work in the laboratories of the renowned Inorganic Chemist, Professor Fritz Ephraim, in Berne in Switzerland and of the famous Micro-Chemist, Professor Frederic Emich, in Graz in Austria. During his stay abroad, he also visited a number of other research centres in different parts of Europe before returning to India towards the end of 1930.

Priyadarajan was elected the President of the Chemistry Section of the Indian Science Congress, 1932. In those days this was a unique recognition that could be achieved only by a distinguished chemist by virtue of his scientific contributions and by no other means. In the Bangalore Session of the Indian Science Congress in 1932 he delivered at the Chemistry Section his presidential address on "Doctrine of Valency and the Structure of Chemical Compounds" which was an authoritative account of the then prevailing views on valency and complex compounds, a field in which he had made significant contributions from studies on the magnetic properties of various compounds. In fact, Professor Ray is one of the earliest workers on the systematic application of magnetic properties in the elucidation of the structures of compounds including metal complexes and in determining the valency of a transition metal in its compounds. Professor Wilhelm Klemm (1950), Director, Anorganische-Chemisches Institut, University of Munster, West Germany, who is an acknowledged authority on magnetochemistry mentioned of Professor Ray's contributions as follows: "In giving an account of the modern developments in the field of Inorganic Chemistry I cannot conclude without referring to the contributions of the Indian workers in this field. Mention of names like Raman, Krishnan and P. Ray will in my opinion, suffice for the purpose". In 1932, he was elected an Editorial Collaborator for publication of a comprehensive and authoritative treatise on Analytical Chemistry named "Chemische Analyse" with Professor Wilhelm Botger of Leipzig as the Editor-in-chief. This was in recognition of his significant contributions in developing new analytical methods for detection and estimation, applicable in macro and micro scales, based on the use of new reagents including complexing ligands such as rubeanic acid (1926) which form characteristic complexes with metal ions and is infact the most sensitive reagent for the detection of copper(II) ion known till today. Analytical applications of bismuthiol, quinal-

dic acid, biguanides, etc. were developed by him later, as well as new colorimetric methods using various organic reagents. In due recognition of his contributions in microchemical and colorimetric methods, Professor Ray was elected (1951) one of the seven members of the Commission of New Reactions of the International Union of Pure and Applied Chemistry to prepare a comprehensive and critical report on the colorimetric methods of analysis which has been documented. He worked in this Commission for 8 years and when he was invited to be a member again he declined suggesting the appointment of a younger member. This is significant.

In 1935, Professor Ray was elected a Foundation Fellow of the then newly established National Institute of Sciences of India (now named Indian National Science Academy). In the year 1937, he was appointed the Khaira Professor of Chemistry, University of Calcutta and became Sir Tarak Nath Palit Professor and Head of the Department of Chemistry, University of Calcutta in 1946 from which post he retired in December, 1952. He had received invitations to attend various International Scientific Conferences in USA, UK, Germany, Sweden, etc. which he declined mainly because of his lack of interest in publicity.

For over 20 years since 1937 Professor Ray published a series of research papers on his studies on the nature of the complexes of different transition metal ions with biguanide and its derivatives. One such ligand has also been used to form a compound of Ag(III) which is the most stable compound of Ag(III) known so far. The results of these authoritative studies have been documented in an invited review article published in the Chemical Reviews in 1960. Professor M. T. Beck (Hungary) commented on it as follows (1961): "I am extremely interested in your work on the chemistry of biguanide complexes. So I was excited to read your impressive review which appears to me a real Gold-mine."

After his retirement from the University of Calcutta he joined the newly established department of Inorganic Chemistry of the Indian Association for the Cultivation of Science, Calcutta, the oldest research institution in India (founded by Dr. Mahendra Lal Sircar in 1886), as the Honorary Professor of Inorganic Chemistry. During his service in the University of Calcutta he was for several years the Hony. Secretary of this institution and was much responsible for its development into an institution of national importance. He was also the Hony. Director of this Institute (1956-58).

During his term as Director he donated a sum of Rs. 30,000/- out of his remuneration to the M. N. Saha Memorial Fund of the Association for the advancement of science and for perpetuating the memory of (late) Professor M. N. Saha. Since he left the Association in 1958 he ceased to be actively associated with any research laboratory. But after his retirement from the Association he

actively engaged himself as a Supervisor in charge of History of Science unit of the Indian National Science Academy and guided for several years valuable investigations by a team of workers on the progress of science in ancient India. The compilations on "*Charak-Sanghita*" and "*Susrut-Sanghita*" under his editorship are a few of the outcomes of such activities.

His interests in the History of Science are well-known and he edited "The History of Chemistry in Ancient and Medieval India" (Indian Chemical Society, 1956) which is a completely revised and enlarged version of the book "History of Hindu Chemistry" written by Acharya Prafulla Chandra Ray. He also edited "Fifty Years of Sciences in India—Chemistry" (Indian Science Congress Association, 1964).

Professor Ray is the author of several coveted endowment and memorial lectures of various scientific and national organisations in India.

Professor Ray served as the President of a national symposium on the "Chemistry of Coordination Compounds" held at Agra in 1959 under the auspices of the National Academy of Sciences. He was elected the President of the Indian Science News Association for the term 1958-59 and served for several years in the Editorial Board of the journal "Science and Culture".

He was elected the President of the Indian Chemical Society for the term 1947-48 and was an ex-officio Vice-President of the Society in his capacity as a past President during his lifetime. He had also served the Society and its Council in other capacities including Hony. Secretary (1933-36), Hony. Editor (1938-42) and Vice-President (1945-46). He was the President of the 20th International Conference on Coordination Chemistry held in India (1979).

He published nearly 200 original research papers in well-known journals and wrote innumerable articles, both in English and in Bengali, on various topics such as Science, Society, Religion, etc. He was one of those few of his time who was actively associated in the popularization of science through writings in Bengali language.

The Universities of Jadavpur, Burdwan and Calcutta honoured him by awarding the degree of Doctor of Science (*Honoris Causa*).

Apart from his personal scientific contributions Professor Ray also trained up for several decades a band of Inorganic Chemists who have occupied responsible and coveted positions in different educational, scientific and industrial organisations in the country. This creation of a school is no less significant than his own contributions in active research and he may aptly be called the doyen of Inorganic Chemistry in India and about him Professor John C. Bailar, Jr. (USA), a celebrated Inorganic Chemist, expressed (1961) as follows: "He has reasons to be proud of what he has done for the country".

Like his *guru* Acharya Prafulla Chandra Ray, Prof. Priyadarajan Ray was also a bachelor. In the words of (late) Prof. Pulin Behari Sarkar, "He (Priyadarajan) imbibed all the great qualities of his *guru* Acharya Ray, like him was a confirmed bachelor with a dedicated life, equally a linguist and nay even a better finished Chemist. He had an unflinching devotion to his *guru* and so worthily got his benedictions . He got by his steady persevering work, recognition not only in India but also abroad".

A man of few words, Professor Ray was always somewhat reserved but very compassionate and

honest in his assessments. He was greatly distressed about the present deterioration in research spirit and ethics in the country and had ventilated his views on several occasions in recent times. What pained him most was that while facilities and investments for research are increasing, the output has not been upto expectations. He considered devotion and dedication as the prior needs for any advancement of Science and Technology, since progress depends on men and not on materials and machinery which are merely the tools.

D. Banerjee

# Training and Research in Analytical Chemistry : An Interdisciplinary Science

R. C. MEHROTRA

University of Rajasthan, Jaipur-302 004

A brief survey of the work being pursued in India in the discipline of analytical chemistry has been presented. The need of developing novel directions of approach and the use of more sophisticated techniques has been highlighted. Research work in the field of analytical chemistry should be accompanied by a clear understanding of the tools, the limits of precision involved and the basic chemical principles of the process. There should be an active coordination between teaching and research.

IT is a matter of great pleasure for me to contribute this article to the special issue of the Journal of the Indian Chemical Society, being brought out on the occasion of the sixtieth birthday of my friend Professor Arun K. Dey. Prof. Dey's outstanding contributions in the field of Inorganic and Analytical Chemistry, ranging over approximately four decades, are too well known to be enumerated here. Beginning with novel methods<sup>1</sup> of calculation of formation constants of complex ions, Prof. Dey has made significant contributions in the fields of coordination chemistry of lanthanides<sup>2</sup> and inorganic polymers<sup>3</sup>; the applications of inorganic concepts to analytical chemistry has been his abiding interest and has resulted in internationally recognised contributions from his research school in the fields of chromatography<sup>4</sup>, ion exchange<sup>5</sup>, electrophoresis<sup>6</sup>, ring oven technique<sup>7</sup>, ion selective electrodes<sup>8</sup> and spectrophotometric determination of metal ions<sup>9</sup>. In view of his keen interest in teaching and research in analytical chemistry, it appears appropriate to present in this article a brief account of the development of this interdisciplinary field of science.

Analytical chemistry may be defined as the science of *chemical characterization and measurement*. With the merging boundaries of conventionally accepted disciplines of science, the meaning of the term *chemical characterization* has been changing and now covers many techniques which would have at one time been considered to belong to the domain of physical analysis or biological assay. Simultaneously, the instruments with which *measurements* are made have been constantly undergoing development. Efforts at improvements in the techniques of characterization and measurements to incorporate more and more complex situations (e.g., ultramicro quantities in large interfering preponderances) constitute major thrusts of research in analytical chemistry. However, fundamental progress in these demanding sophisticated techniques does require a very clear understanding of the theoretical principles involved. In addition, the analytical chemist in his efforts to enlarge the utility of the applications of his science for different disciplines (e.g., meteorology, geology and biology) has to develop a better

appreciation of the specific needs of these users and make the analytical procedures as foolproof as possible for those who are not highly trained in analytical chemistry.

Conversely, many types of scientists (including chemists of different specialisations) and engineers have been continuously making valuable contributions to analytical chemistry. A physical chemist, for example, may spend some time and effort in improving the time-, spatial- or frequency-resolution of his spectroscopic measurements to draw more reliable and penetrating conclusions in his current area of research. What distinguishes an analytical chemist is that he makes improvements in characterization and measurements his goal rather than means to an end.

*Growth of analytical chemistry and India's contribution to the field*: In his thought provoking special award address at the Society for Analytical Chemists at Pittsburgh in 1980, H. A. Laitinen<sup>10</sup> presented a graphic account of the phenomenal growth and importance of 'Analytical Chemistry in a Changing World', which makes it clear that analytical chemistry continues to occupy a central place in the overall growth of chemistry. This is depicted by the data in Table I<sup>11</sup> representing the percentage of chemical publications which were devoted to analytical chemistry.

TABLE I—RELATIONSHIP BETWEEN CHEMICAL AND ANALYTICAL CHEMICAL LITERATURE FOR 1970

Country	Analytical literature, % of total chemistry	Relative growth rate, T <sub>4</sub> Anal / T <sub>4</sub> Chem.
U S S R.	11.2	1.2
U S A.	5.1	0.9
Japan	9.8	0.8
Germany-East & West	6.7	1.2
U K.	10.3	1.1
France	7.1	1.5
The Netherlands	7.4	1.2
Italy	5.9	0.9
World's literature	8.2	1.0

In the above table, the data in the third column again show that the rate of growth of the analytical

chemistry literature is generally higher than the rate of growth of chemical literature as a whole. The comparatively faster growth of literature in analytical chemistry is again depicted by the concept of 'doubling periods' in Table 2<sup>12</sup>.

TABLE 2—DOUBLING TIME ( $d_2$ ) OF SCIENTIFIC LITERATURE

Discipline	$d_2$
<sup>a</sup> Analytical chemistry	13.9
<sup>a</sup> Chemistry	14.5
<sup>b</sup> Biology	16
<sup>b</sup> Physics	19
<sup>b</sup> Electrical engineering	20
<sup>b</sup> Psychology	25
<sup>b</sup> Economics	13

India's contribution in the realm of analytical chemistry has always been quite substantial, although a number of recent reports dealing with the growth of different branches of chemistry in this country have tended to ignore this. Starting with the highly significant contribution<sup>13</sup> to the list of organic reagents by demonstrating the use of dithio-oxamide (rubeanic acid) in 1926 by P. Ray for the detection of copper, cobalt and nickel, the research work in analytical chemistry has continuously progressed in this country and this has been summarised in two reviews<sup>14,15</sup> upto 1972.

Brooks and Smythe<sup>16</sup> recently reviewed the world progress of analytical chemistry in the period 1910-70. Building upon the previous accounts by Fischer<sup>17</sup> in 1965, these workers compared entries in *Analytical Abstracts* and *Chemical Abstracts* and were able to calculate the percentage of total activity of chemical research in different countries devoted to analytical chemistry (cf., Table 3).

TABLE 3—PERCENTAGE OF ANALYTICAL WORK CARRIED OUT IN VARIOUS COUNTRIES

Country	Year	
	1965	1970
U. S. S. R.	25.4	28.4
U. S. A.	15.8	17.7
Japan	11.0	7.7
Germany	6.4	6.1
U. K.	4.3	5.9
Czechoslovakia	5.3	5.6
France	3.5	2.6
India	3.5	2.6
Scandinavia	0.7	2.1
Romania	3.5	2.0
Poland	4.1	1.8
Spain	1.8	1.5
Netherlands	0.8	1.3
Italy	1.7	1.0
China	3.1	—
Rest of the world	9.1	11.1

In another analysis of *Analytical Abstracts* published in 1977, Braun and coworkers<sup>11</sup> concluded that there were 8311 papers distributed in 741 journals, although there was heavy concentration of 50% and 90% of the papers in only 3% and 36% of the journals respectively. Data for first 50 of the journals are given in Table 4. Two Indian journals, 'The Indian Journal of Chemistry' and the 'Current Science (India)' are included in this list. These workers further extended their analysis to a 'quality' indicator 'impact factor', which has been defined as the ratio of the number of citations made in any year (say 1978) to the material published in the previous two years (say 1976 and 1977) in a particular journal and the total number of articles published

TABLE 4—THE FIRST 50 LEADING JOURNALS ON ANALYTICAL CHEMISTRY COMPUTED FROM ANALYTICAL ABSTRACTS 1977, RANKED BY PRODUCTIVITY

Rank	Journal	No. of papers found	Rank	Journal	No. of papers found
1	J. Chromatogr.	710	26	Rev. Sci. Instr.	52
2	Anal. Chem.	511	27	Lab. Pract.	51
3	Anal. Chim. Acta	338	28	J. Clin. Chem. Clin. Biochem.	51
4	Zh. Anal. Khim.	315	29	Pharmazie	46
5	Anal. Biochem.	300	30	Appl. Spectrosc.	45
6	Fresenius Z. Anal. Chem.	212	31	Quim. Anal.	40
7	J. Assoc. Off. Anal. Chem.	206	32	Ukr. Khim. Zh.	37
8	Talanta	198	33	Environ. Sci. Technol.	37
9	Bunseki Kagaku	171	34	J. Electroanal. Chem. Interfacial Electrochem.	35
	Zavod Lab.	170			
10	Chem. Anal. (Warsaw)	169	35	Biochem. Med.	34
11	Clin. Chem.	161	36	Appl. Opt.	34
12	J. Radioanal. Chem.	147	37	J. Amer. Oil. Chem. Soc.	33
13	Analyst	146	38	Bull. Environ. Contam. Toxicol.	33
14	J. Pharm. Sci.	132	39	Int. J. Appl. Radiat. Isot.	32
15	Mikrochim. Acta	116	40	Z. Lebensm. -Unters.	31
16	Clin. Chim. Acta	109	41	X-Ray Spectrom.	31
17	Anal. Lett.	92	42	At. Absorpt. Newsl.	30
18	Chromatographia	91	43	J. Phys. Sci. Instrum.	29
19	Radiochem. Radioanal. Lett.	85	44	Nucl. Instrum. Methods	29
20	J. Chromatogr. Sci.	76	45	An. Quim.	29
21	Revista Chim. (Bucharest)	75	46	Yukugaku Zasshi	28
22	J. Agric. Food. Chem.	71	47	Curr. Sci. (India)	28
23	Indian J. Chem. Sect. A	60	48	Acta Pol. Pharm.	28
24	Farmatsiya (Moscow)	52	49	Z. Chem. (Leipzig)	27
25			50	Chem. Pharm. Bull. (Tokyo)	27



TABLE 5—IMPACT FACTOR OF LEADING JOURNALS ON ANALYTICAL CHEMISTRY (1978)

Rank	Journal	Impact factor	Rank	Journal	Impact factor
1	Clin. Chem.	3.106	21	X-Ray Spectrom	1.118
2	Anal. Chem.	3.058	22	Chem. Pharm. Bull	0.979
3	J. Chromatogr. Sci.	2.586	23	Fresenius Z. Anal. Chem.	0.930
4	Anal. Biochem.	2.309	24	J. Assoc. Off. Anal. Chem.	0.916
5	J. Chromatogr.	2.302	25	Int. J. Appl. Radiat. Isot.	0.790
6	Appl. Spectrosc.	2.161	26	J. Phys. Sci. Instrum.	0.714
7	Chromatographia	1.972	27	Mikrochim. Acta	0.697
8	Appl. Opt.	1.934	28	J. Radioanal. Chem.	0.685
9	Clin. Chim. Acta	1.676	29	Radiochem. Radioanal. Lett.	0.639
10	Analyst	1.666	30	Z. Chem. (Leipzig)	0.623
11	J. Electroanal. Chem. Inter-facial Electrochem.	1.525	31	Pharmazie	0.483
12	J. Agric. Food Chem.	1.503	32	Z. Lebensm. Unters. Forsch.	0.455
13	Environ. Sci. Technol.	1.436	33	Bunsek Kagaku	0.410
14	Anal. Chim. Acta	1.404	34	Zh. Anal. Khim.	0.403
15	Anal. Lett.	1.244	35	An. Quim.	0.393
16	Talanta	1.182	36	Indian J. Chem. Sec. A	0.322
17	J. Pharm. Sci.	1.171	37	J. Amer. Oil. Chem. Soc.	0.278
18	J. Clin. Chem. Clin. Biochem.	1.163	38	Acta Pol. Pharm.	0.262
19	Nucl. Instrum. Methods	1.141	39	Curr. Sci. (India)	0.221
20	Rev. Sci. Instr.	1.131	40	Ukr. Khim. Zh	0.145
			41	Yukugaku Zasshi	0.145
			42	Zavod. Lab.	0.117
			43	Revista Chim. (Bucharest)	0.082

in the same journal during the same two years. The actual data of 1978 impact factors for the top 43 journals are given in Table 5, in which both the Indian journals referred to in Table 4, do find a place *albeit* very low, almost at the bottom.

*Teaching and research in analytical chemistry:* Following the more advanced countries, the typical chemistry curriculum adopted by different universities in this country included qualitative group analysis, titrimetric procedures and gravimetric analysis of mixtures including complex materials such as cement, ores and alloys. In addition, courses in analytical aspects of organic analysis were also included at the higher levels. With the changing techniques actually used in analytical operations in academic and industrial laboratories, the curricula have undergone fast changes in developed countries by the introduction of more specialised courses, for example, in electrochemical and spectrochemical analysis, electronics as well as advanced methods of data acquisition and processing.

In view of the above trends, the observation of Herman Liebhafsky in his 1962 Fischer award address, "Like it or not, the chemistry is going out of analytical chemistry", appears to be quite relevant. While one may not agree with this sweeping statement, yet the pressure on the curriculum and available training time tends to make the learners less and less interested in the fundamental aspects of analytical chemistry, the understanding of which remains as essential as ever for practitioners as well as researchers in analytical chemistry.

In the history of analytical chemistry itself, recognition of the fact that analytical chemistry is not solely empirical in nature was only slowly realised. For example, it is only after many decades of 'empirical recommendations' on the temperature at which a precipitate should be heated in a gravimetric procedure that the matter was investigated by Duval and

others in a systematic manner leading to a new branch of study called 'Thermogravimetric Analysis'. The eloquent statement "theory guides, experiment decides" made by the grand analytical chemist of the century, Prof. I. M. Kolthoff is thus continuing to reveal its realism in an ever enhanced manner and hence the task of the teacher in analytical chemistry is becoming all the while more difficult and challenging.

A happy balance between theory and practice in the teaching of analytical chemistry has always been an intricate problem for the framers of curricula and continues to be increasingly so even in the more developed situations. For Universities like ours, the problem becomes even more complex. In the absence of actual sophisticated facilities the extent to which the theoretical features of the same should be taught to enable the learner to use them as these become available to him in later life remains a dilemma for the conscientious teacher, as too much emphasis on theoretical aspects without experimental follow up might give a wrong impression to the learner about the true spirit of this experimental science. Obviously, the resolution of the above dilemma would depend upon the facilities (physical as well as technical) available in any situation, but the following aspects (many of which represent points of special weakness in our system) deserve our special consideration:

- (i) training in instrumentation and fabrication of simple analytical equipments involving glass blowing or knowledge of basic electronics, i.e., inculcation of what is sometimes termed as 'instrumentation culture';
- (ii) a statistical analysis of the experimental data drawing out clearly the 'limits of error' involved in different steps and representing clearly the actual 'precision limits' of the final results. (The extent to which these

steps receive attention in modern analytical chemistry is illustrated by defining clearly the 'guidelines for data acquisition and data quality evaluation' in environment chemistry<sup>18</sup>;

- (iii) a comparative study of the accuracy of the results obtained by various (classical as well as modern) methods of analysis (the quality of contributions from our laboratories could have been enhanced considerably if this aspect was emphasized in studying the possible interferences as well as in representing the final results in significant figures);
- (iv) planning the exercises and problems at the teaching as well as research levels around real life situations rather than basing them only on artificial makeups (a close liaison and cooperation between university laboratories and industrial and other organisations requiring new analytical procedures could be of immense mutual benefit in this direction);
- (v) adequate theoretical background and clearer understanding of the basic principles involved in any analytical procedures;
- (vi) coordination between teaching and research should be encouraged by open ended exercises particularly at the post-graduate level and by formulating problems at the research level from the experiences gained and difficulties faced in such exercises in the teaching laboratories.

#### References

1. A. K. DEY, *Doklady Acad. Sci. (U.S.S.R.)*, 1947, 50, 1047.
- R. L. SETH and A. K. DEY, *J. Inorg. Nuclear Chem.*, 1961, 17, 312.
- A. K. MUKHERJI and A. K. DEY, *J. Inorg. Nuclear Chem.*, 1958, 6, 314.
2. A. K. DEY and R. NAYAN, "Proc. XII Rare Earth Res. Conf.," Vail, Colorado (U.S.A.), 1976.
3. P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *Inorg. Nuclear Chem. Lett.*, 1977, 13, 147.
- A. K. DEY, P. L. MAURYA, B. AGARWAL, V. BANERJEE and B. SINGH, "Proc. XXI Int. Conf. Coord. Chem.," Toulouse (France), 1980, p. 276.
4. E. J. SINGH and A. K. DEY, *Anal. Chim. Acta*, 1961, 25, 57.
5. L. C. T. EUSEBIUS, A. K. GHOSH and A. K. DEY, *Analyst*, 1981, 106, 529.
6. P. C. YADAV, A. K. GHOSH, K. L. YADAV and A. K. DEY, *Chromatographia*, 1976, 9, 410.
7. M. DEY, A. K. GHOSH and A. K. DEY, *J. Liquid Chromat.*, 1981, 4, 1577.
8. U. S. LAL, M. C. CHATTOPADHYAYA and A. K. DEY, *Mikrochim. Acta*, 1980, II, 417.
9. A. K. DEY, S. N. SINHA, S. P. SANGAL and K. N. MUNSHI, "Proc. V Rare Earth Res. Conf.," Ames, Iowa (U.S.A.), 1965.
10. H. A. LAITINEN, *Anal. Chem.*, 1980, 52, 605A.
11. T. BRAUN, E. BUDOSO and W. S. LYON, *Anal. Chem.*, 1980, 52, 620A.
12. CH. C. HOLT and W. E. SHIRANK, *Chem. Docum.*, 1968, 18, 18.
13. P. RAY and R. M. RAY, *J. Indian Chem. Soc.*, 1926, 3, 118.
14. P. RAY, "Fifty Years of Science in India—Progress in Chemistry", Indian Science Congress Association, 1964.
15. R. D. TIWARI and A. K. DEY, "A Decade (1963-72) of Science in India—Progress of Chemistry", Indian Science Congress Association, 1974.
16. R. R. BROOKE and L. E. SMYTHE, *Talanta*, 1975, 22, 495.
17. R. B. FISCHER, *Anal. Chem.*, 1965, 37, 27A.
18. D. MACDOUGALL and W. CRUMETT, *Anal. Chem.*, 1980, 52, 2242.

# Teaching Microchemistry in Industry Versus Teaching in a University

AL STEYERMARK

Department of Chemistry, Rutgers, The State University of New Jersey, Newark,  
New Jersey 07110, U.S.A.

In an industrial company, the beginner must be able to produce results in as short a time as possible so he or she is taught one determination at a time, whereas in a university, the student receives a full course.

**T**WO methods of teaching microchemistry are in general use. Industrial companies are interested in having the new employee to be able to produce results in as short a time as possible and concentrate on having he or she becoming efficient in one determination. Some companies employ persons having college or university degrees while others use persons who have no degree but who have had elementary courses in chemistry. In the author's laboratory at Hoffmann-La Roche, before he retired, he had all college or university graduates who have had courses in analytical chemistry (macro), organic chemistry and in some cases physical chemistry.

After being taught the use of the microchemical balance, the individual was allowed to determine metals by the ashing technique, which he continued to do for several days to gain more weighing experience.

The next step was the teaching of the determination of nitrogen by the Dumas method. After repeating this a number of times during the next few weeks, the beginner was experienced enough to be allowed to "graduate" from running known test compounds to do so on research samples, and was then kept doing this determination for several months.

Next followed, using the same procedure, the determinations of carbon-hydrogen by the classical method, halogens, sulfur, phosphorus, nitrogen by the Kjeldahl method, arsenic, automatic carbon-hydrogen-nitrogen, alkoxyl, molecular weight, etc., all of the determinations described in the author's text book<sup>1</sup>. Obviously, the more experienced the individual became, the less time and number of test compounds were needed when a new determination was done. Depending upon the person, one to two years was required before analysts were efficient in all types of determinations. In this way there could be rotation of the work, which was necessary to prevent monotony.

At the University, the author gives a one semester course in which the students spend six hours per week for fourteen weeks in the laboratory. Although there have been as many as twenty-six students taking the course at one time, the course is operated on a "by arrangement" schedule basis so that not more than four students are in the

laboratory at any one time. This allows for much individual attention so that the students receive the extra benefit. The object of the course is to teach students how to handle small amounts of material with accuracy and precision, rather than to create microchemists. The students must have passed courses in analytical chemistry (macro) and organic chemistry. A few of the students are third year undergraduates and a few are graduate students who are candidates for the master or doctor degree. The majority are in their last semester before receiving the bachelor degree.

Each student is required to determine (in duplicate) halogens by the Carius method<sup>1</sup> and the oxygen flask mercurimetric method<sup>2</sup>, nitrogen by both the Dumas<sup>1</sup> and Kjeldahl<sup>1</sup> methods, carbon-hydrogen by the classical method<sup>1</sup>, carbon-hydrogen-nitrogen by automatically, arsenic<sup>1</sup>, sulfur<sup>1</sup>, phosphorus gravimetrically<sup>1</sup> and titrimetrically<sup>3</sup>, alkoxyl<sup>1</sup>, molecular weight by the two isothermal distillation methods<sup>1</sup>, boiling points, melting points<sup>1</sup> and specific gravity<sup>1</sup>. The results obtained are unusually good. Some students obtain acceptable results<sup>1</sup> in as many as twenty-five out of twenty-six or twenty-seven determinations.

After having taken the regular course, some students do research, as for example the work done on the alkoxyl determination<sup>4</sup>, in which it was found that by using the regular apparatus and procedure<sup>1</sup>, the sample size could be reduced to as low as less than 100  $\mu$ g and acceptable results<sup>1</sup> obtained consistently.

After teaching the course for the past thirteen years, during which approximately two hundred students took the course only four have positions as microchemists. Many of the others repeatedly advise that, although they are not doing actual micro work, their micro training has been of extreme value to them in their fields.

## References

1. AL STEYERMARK, "Quantitative Organic Microanalysis", 2nd Edn., Academic Press, Inc., New York, 1961.
2. R. A. LALANCETTE and AL STEYERMARK, *J. Assoc. Offic. Anal. Chemists*, 1974, 57, 26.
3. R. A. LALANCETTE, AL STEYERMARK and N. C. CHERAPAK, *J. Assoc. Offic. Anal. Chemists*, 1976, 59, 835.
4. M. G. KOVALYCSIK and AL STEYERMARK, *Microchem. J.*, 1980, 25, 199.

# Some Interesting Aspects of the Chemistry of Platinum

JOHN C. BAILAR, JR.

University of Illinois, Urbana, IL 61801, U.S.A.

**P**LATINUM is one of the least reactive of metals. It does not tarnish and is insoluble in even the strongest of acids. Simple (hydrated) platinous and platinic ions are almost unknown. In spite of these limitations, the chemistry of platinum is extremely varied and interesting and offers a fertile field for investigation. The common oxidation states of platinum are +2 and +4, but compounds are known in which several other oxidation states are shown. Interesting examples are  $[\text{Pt}(\text{P}\phi_3)_2]$  and  $[\text{Pt}(\text{P}\phi_3)_4]$ , in which the metal is formally in the zero oxidation state, and in the first of which the metal has the unusual coordination number of three<sup>1</sup>. Even fractional oxidation states exist in such compounds as  $\text{Cs}_{1.78}[\text{Pt}(\text{CN})_4]\cdot 2\text{H}_2\text{O}$ ,  $\text{Rb}_{1.8}[\text{Pt}(\text{CN})_4]\cdot 2\text{H}_2\text{O}$ ,  $[\text{C}(\text{NH}_3)_5]_2[\text{Pt}(\text{CN})_4]\text{Br}_{0.88}\cdot \text{H}_2\text{O}$  and  $\text{K}_{1.64}[\text{Pt}(\text{C}_2\text{O}_4)_2]\cdot \text{H}_2\text{O}$ <sup>2</sup>. These are important because of their electronic properties. In compounds such as  $\text{Pt}_3\text{Sn}_2\text{Cl}_{10}$ <sup>3</sup>, it is futile to try to assign an oxidation state.

In this paper, we are concerned chiefly with the coordination compounds of platinum in the +2 and +4 oxidation states. In the former, platinum usually shows a coordination number of four, but in the trigonal bipyramidal ion  $[\text{Pt}(\text{SnCl}_3)_5]^{3-}$ , the coordination number is five<sup>4</sup>. Many of the compounds in which the coordination number is four have high catalytic power, especially for hydrogenation. In these complexes, there is one empty p orbital, through which a carbon-carbon double bond can attach itself to the metal.


Most of the soybean oil of commerce goes into food products such as oleomargarine and salad oils. The triply unsaturated linolenic ester, which is present in the oil to the extent of 7-10%, has an unpleasant taste, and many efforts have been made to hydrogenate one double bond in this ester without affecting the other double bonds in the molecule and without hydrogenating the linoleic or oleic esters. Complete saturation must be avoided at all costs, as the saturated esters are hard to digest.

In order to avoid the complication of having three acid chains (perhaps all different) in one molecule, it has been customary in research studies to replace the glyceride unit with methyl groups. My colleagues and I have made extensive studies of the selective hydrogenation of soybean oil, using as the hydrogenation catalyst, a mixture of bis-diphenylphosphine-dichloro platinum(II) and several equivalents of tin(II) chloride, thus generating the complex  $[\text{Pt}(\text{P}\phi_3)_2(\text{SnCl}_2)_2\text{Cl}]$ , which, upon hydrogenation, evidently becomes  $[\text{Pt}(\text{P}\phi_3)_2(\text{SnCl}_2)_2\text{H}]$ <sup>5</sup>. With this catalyst, it is easily possible to hydrogenate *all but one* double bond. When the catalyst is immobilized by attaching it to polystyrene, it is possible to hydrogenate one double bond of linolenic ester, leaving two, mostly, however, in the *trans*-form. The details of this work have been described recently and need not be repeated<sup>6</sup>. The subject is mentioned here only to call attention to the catalytic power of platinum(II) complexes.

Another important application of platinum complexes is in the treatment of cancer. In 1965, Barnett Rosenberg at Michigan State University observed that *cis*-dichlorodiammine platinum has the ability to inhibit the division of *Escherichia coli* into separated cells, though it does not inhibit the growth of the cells<sup>7</sup>. This led him to the suggestion that this compound might be effective in the treatment of cancer and, indeed, experiment showed this to be correct. The compound is now being used clinically, under the name cisplatin, in the treatment of certain cancers. Needless to say, Rosenberg's exciting discovery has stimulated a great deal of work in this field, and something over

	5d				6s	6p
$\text{Pt}^{(II)}$	0	0	0	0	—	—
$[\text{PtX}_4]^{2-}$	0	0	0	0	X	X


We have used this catalytic property in the selective hydrogenation of soybean oil, which is a mixture of glycerides of several long chain carboxylic acids, with all of the double bonds in the *cis* configuration :




twelve hundred compounds have now been synthesized and tested. Most of these contain platinum, but other metals of the platinum family have been tried too. Cisplatin is not an ideal drug, for it is not as effective as we might wish, it is only very slightly soluble and it is horribly toxic. From the many experiments that have been carried out, certain "rules" have been derived. First, the compound must contain two groups which are tightly bound to the platinum and two which are slowly hydrolyzed off. The tightly bound groups may be ammonia molecules, as in cisplatin, or they may be amine molecules of a wide variety. Evidently there must be at least one hydrogen atom on the ammine nitrogen. Second, the hydrolyzable groups must be displaced slowly. Nitrate groups will not do, for they are hydrolyzed off too rapidly; cyano groups are ineffective because they are not hydrolyzed off at all. Chloro groups are satisfactory, their hydrolysis in the body being somewhat inhibited by the presence of chloride ion in body fluids. Other groups that have been found to be effective include sulphato, gluconato and pyromellito. Supposedly, the non-ionic cisplatin dissolves to a slight extent in the fatty tissue of the body. It is held there until reaction with water converts it to the ionic aqua complex  $cis-[Pt(NH_3)_2(H_2O)_2]^{2+}$  or the hydroxo-aqua complex  $cis-[Pt(NH_3)_2(H_2O)(OH)]^+$ . These then attach themselves to the strands of the diseased DNA, the nitrogen atoms of the nucleic acid displacing the aqua and/or hydroxo groups. Compounds in which the hydrolyzable groups are *trans* to each other are completely ineffective.

It should be noted in passing that this picture does not tell the whole story, for some compounds that do not resemble cisplatin closely have been found to be effective. Such a one is the dimeric rhodium(II) acetate hydrate,  $[Rh_2(CH_3COO)_4 \cdot (H_2O)_2]^{2+}$ .

Optical isomers differ not only in the direction in which they rotate the plane of polarized light but also in their reactivity with other chiral substances. This suggests that the enantiomers of platinum compounds might have different effectiveness in the treatment of cancer. Optical activity of a planar platinum complex can be achieved by using an optically active ligand. Rosenberg tried the propylenediamine complex but found little




difference in the effectiveness of the two isomers<sup>9</sup>. Kidani used 1,2-cyclohexanediamine, of which the *trans* form is chiral<sup>10</sup>.




He found the *levo-trans* isomer to be more effective than the *dextro-trans* isomer, which, in turn, is more effective than the optically inactive *cis* isomer.

We have applied ourselves to this problem too. The first compounds which we made contained 2,2'-diaminobiphenyl as the ligand.




This compound owes its chirality to the fact that the two phenyl rings cannot lie in the same plane but must be tilted with respect to each other, thus assuming a propellor-like configuration. We did not separate the isomers but submitted the racemic material for testing. It has some effect but not enough to warrant further work. In the mean time we learned that aliphatic groups have been found to be better than aromatic ones, so we prepared the cyclohexane analogue.




The rings in this compound are not planar as they are in the biphenyl derivative, but they still must be held in "tilted" positions and the platinum compound should be optically active. The resolution of this compound is being studied by Dr. Masahide Noji, who prepared the compound in our laboratory and is now continuing the work in Japan.


Currently, we are working on this problem from two angles—altering the nature of the asymmetric ring and increasing the solubility of the complex. In some cases these objectives overlap. We have prepared 1,2-cyclooctanediamine, which is similar to Kidani's cyclohexanediamine, but because of its larger size, should be more flexible. We have considered going the other way too, to the cyclobutanediamine but have not attempted any syntheses. In each case there are symmetrical *cis* and chiral *trans* isomers



For increase in solubility, we are introducing functional groups, as with the ligands biguanide and 2-hydroxy-1,3-diaminopropane or by making the







complex ionic by using a bidentate, negative ion as the ligand.



The 2,3-diaminopropionic acid complex resembles the ethylenediamine complex, which has been shown to be effective against certain cancers but is insoluble. The presence of the carboxyl group gives good solubility but whether the chirality of the carbon atom will give the two isomers different physiological properties remains to be seen.

Quite a different kind of platinum chemistry is also underway in our laboratory. The famous Russian chemist Chugaev observed that some complexes containing platinum in both the cation and anion undergo an interesting disproportionation reaction when they are heated. Some examples are



Chugaev had no way to study the mechanism of these reactions, and we are interested in pursuing this part of the problem. All of the ions concerned, except those in the third example, are planar and are probably stacked, with cations and anions alternating (This has, however, not yet been proven




Fig. 1

experimentally in all cases). If that is the case, we can imagine that there are residual forces between the ligands in each plane and the platinum atoms in the adjoining planes (Fig. 1).

Upon heating, these residual forces may bring about the rearrangement. With the ammonia complex  $[\text{Pt}(\text{NH}_3)_4][\text{PtCl}_4]$ , these forces would be weak and in accordance with this, the disproportionation reaction in that case takes place at a much higher temperature than in the other cases.

For the fourth example above, we must have a slightly different picture, for the entire molecule of dithioether migrates from one platinum atom to the next (Fig. 2).

To determine whether the disproportionation takes place in steps Dr. Hideyoshi Morita, working in our laboratory, prepared the ions  $[\text{Pt}(\text{Me}_2\text{S})_2\text{Cl}]^+$  and  $[\text{Pt}(\text{Me}_2\text{S})_2\text{Cl}_3]^-$ . He expected, when he mixed solutions of these, to obtain the salt  $[\text{Pt}(\text{Me}_2\text{S})_2\text{Cl}][\text{Pt}(\text{Me}_2\text{S})_2\text{Cl}_3]$ . Much to our surprise, he obtained instead the final product of the disproportionation,  $[\text{Pt}(\text{Me}_2\text{S})_2\text{Cl}_2]$ . If the reaction takes place in steps, the second step must be very rapid. We do not yet know the mechanism of this reaction, but the work is still in progress.

No survey of the chemistry of platinum is complete without mention of the many isopolynuclear compounds which it forms. These contain




Fig. 2

from two to twenty six atoms of platinum per molecule<sup>1a</sup>. The most complex compounds which have yet been prepared are  $[\text{Pt}_{18}(\text{CO})_{36}]^{2-}$  and  $[\text{Pt}_{26}(\text{CO})_{52}]^{1a}$ .

## References

1. R. UGO, F. CARIATI and G. LAMONICA, *Inorg. Syn.*, 1968, 11, 103, 107 and many subsequent articles. See also, F. GORDON STONE, *Inorg. Chim. Acta*, 1981, 50, 32 and references therein.
2. R. L. MAFFLY, J. A. ABYS and J. M. WILLIAMS, *Inorg. Syn.*, 1979, 19, 6; T. R. KOCH, N. P. ENRIGHT and J. M. WILLIAMS, *Inorg. Syn.*, 1979, 19, 8; T. R. KOCH, J. A. ABYS and J. M. WILLIAMS, *Inorg. Syn.*, 1979, 19, 9; T. F. CORNISH and J. M. WILLIAMS, *Inorg. Syn.*, 1979, 19, 10; JOEL S. MILLER, *Inorg. Syn.*, 1979, 19, 13.
3. R. V. LINDSEY, Jr., W. G. PARSHALL and U. G. STOLBERG, *Inorg. Chem.*, 1966, 5, 109.
4. R. D. CRAMER, E. L. JENNER, R. V. LINDSEY, Jr and U. G. STOLBERG, *J. Amer. Chem. Soc.*, 1963, 85, 1691; R. D. CRAMER, R. V. LINDSEY, Jr., C. T. PREWETT and U. G. STOLBERG, *J. Amer. Chem. Soc.*, 1965, 87, 658.
5. H. A. TAYDA and JOHN C. BAILAR, Jr, *J. Amer. Chem. Soc.*, 1967, 89, 4300.
6. JOHN C. BAILAR, Jr., *J. Indian Chem. Soc.*, 1977, 54, 1.
7. B. ROSENBERG, L. VAN CAMP and THOMAS KRIGAS, *Nature*, 1965, 205, 698; B. ROSENBERG, E. RENSHAW, L. VAN CAMP, J. HARTWICK and J. DROBNICK, *J. Bacteriology*, 1967, 93, 716; B. ROSENBERG, L. VAN CAMP, J. E. TROSKO and V. H. MANSOIFR, *Nature*, 1969, 222, 385.
8. E. B. BOYAR and S. D. ROBINSON, *Platinum Met. Rev.*, 1982, 26, 26, 65.
9. Personal letter from Professor ROSENBERG to JOHN C. BAILAR, Jr.
10. Y. KIDANI, K. INAGAKI and S. TSUKAGOSHI, *Gann.*, 1976, 67, 921; Y. KIDANI, M. NOJI, S. TSUKAGOSHI and T. TASHIRO, *Gann.*, 1978, 69, 261; T. TASHIRO and Y. KIDANI, *Current Chemotherapy*, 1978, 1313.
11. I. A. CHUGAEV and N. K. PSHENICYN, *J. Russ. Phys. Chem. Soc.*, 1920, 52, 47.
12. I. A. CHUGAEV and W. SUBBOTIN, *Ber.*, 1910, 43, 1200.
13. I. A. CHUGAEV and I. BENEVOLENSKI, *Z. anorg. Chem.*, 1913, 32, 420.
14. I. A. CHUGAEV and D. FRAENKEL, *Compt. rend.*, 1912, 154, 33.
15. For a survey of this field see F. GORDON STONE, *Inorg. Chim. Acta*, 1981 50, 33 and references therein.
16. P. CHINI, G. LONGONI and V. G. ALBANO, *Adv. Organomet. Chem.*, 1976, 14, 285; P. CHINI, *J. Organomet. Chem.*, 1980, 200, 37.


# Intramolecular $\pi$ - $\pi$ Interactions in Metal "Capped" Porphyrins

P. N. VENKATASUBRAMANIAN and F. BASOLO\*

Department of Chemistry, Northwestern University, Evanston, Illinois 60201, U.S.A.

Soret maxima of  $Zn(C_1\text{-Cap})$ ,  $Zn(C_2\text{-Cap})$  and  $Zn(TPP)$  were recorded in cyclohexane and toluene. In cyclohexane, a progressive red shift in the order,  $C_2\text{-Cap} > C_1\text{-Cap} > TPP$ , is observed. This is attributed to the intramolecular interaction between the porphyrin plane and the aromatic cap of the capped porphyrins. Accordingly, the steric hindrance to  $O_2$  binding inside the cap is perhaps greater in  $C_2\text{-Cap}$  than in  $C_1\text{-Cap}$ . This is reflected in the lower oxygen affinity of  $Fe(C_2\text{-Cap})$  (1,2-Me<sub>2</sub>Im) relative to the  $C_1$  Cap analogue.

**M**ETAL complexes of "capped" porphyrins (Fig. 1), which are ortho-substituted tetraphenylporphyrins, have been prepared as model compounds for hemoglobin and myoglobin<sup>1,2</sup>. The two capped porphyrins,  $C_2\text{-Cap}$  and  $C_1\text{-Cap}$ <sup>3</sup>, differ only by one methylene group in each of the four chains linking the aromatic cap to the porphyrin plane. It had been assumed that the "tight"  $C_2\text{-Cap}$  would offer a greater steric barrier to the addition of  $O_2$  inside the cap than would  $C_1\text{-Cap}$ , but oxygenation studies of iron(II) complexes of  $C_2\text{-Cap}$  and  $C_1\text{-Cap}$  showed that  $Fe(C_2\text{-Cap})$  (1,2-Me<sub>2</sub>Im) has a lower  $O_2$  affinity than does  $Fe(C_1\text{-Cap})$  (1,2-Me<sub>2</sub>Im)<sup>4,5</sup>. Both capped complexes have a lower  $O_2$  affinity than the  $Fe(TPP)$  (1,2-Me<sub>2</sub>Im).



A  $[-(CH_2)_n-]$   $n=2$   $C_2\text{-Cap}$   
 $n=3$   $C_1\text{-Cap}$

Fig. 1 Zinc(II) "capped" porphyrins.

Porphyrins and metalloporphyrins have been shown to have a tendency to  $\pi$ -complex to  $\pi$ -donors and acceptors and even to aromatic hydrocarbons such as toluene<sup>6-9</sup>. We suggest that the aromatic cap in the capped porphyrins too have the potential to solvate the porphyrin. Our studies indicate that the two aromatic planes in  $C_2\text{-Cap}$  have greater  $\pi$ - $\pi$  interaction than does  $C_1\text{-Cap}$ , suggesting that the aromatic planes are closer together in  $C_2\text{-Cap}$ , perhaps due to the greater flexibility of the longer straps in this molecule. Evidence in support of this is provided by the observed red shift in the Soret maxima of  $Zn(II)$  complexes of  $C_2\text{-Cap}$  and  $C_1\text{-Cap}$  relative to  $Zn(TPP)$ .

## Experimental

$Zn(TPP)$ ,  $Zn(C_2\text{-Cap})$  and  $Zn(C_1\text{-Cap})$  were prepared following the methods of Baldwin and co-workers<sup>10</sup> from the free bases and characterized by mass spectrometric analysis. Aldrich spectrophotometric grade cyclohexane was stored over Linde 4A molecular sieves. Reagent grade toluene and benzene were distilled under  $N_2$  from sodium benzophenone ketyl.

Spectra of the  $Zn(Por)$  complexes in cyclohexane, benzene and toluene were recorded at room temperature on a Cary Model 14 UV-visible spectrophotometer using quartz cells with a 1 cm path length.

## Results and Discussion

The Soret maxima of  $Zn(C_2\text{-Cap})$  and  $Zn(C_1\text{-Cap})$  in aromatic and nonaromatic solvents are presented in Table 1. These may be compared with the corresponding values for the open complex,  $Zn(TPP)$ , as reference. Due to limited solubility of the complexes in cyclohexane, suitable high concentrations could not be obtained for significant absorbance in the visible region.

TABLE 1—SORET MAXIMA OF ZINC PORPHYRIN COMPLEXES IN DIFFERENT SOLVENTS

Zn(Por)	Position of Soret band (nm) in		
	Cyclohexane	Benzene	Toluene
$Zn(TPP)$	416	423.5	423.5
$Zn(C_2\text{-Cap})$	419	423.5	423.5
$Zn(C_1\text{-Cap})$	424	424	424

In order to look at the  $\pi$ - $\pi$  interactions between the aromatic top of the cap and the porphyrin plane in absence of axial ligands and solvent interactions, the noncoordinating and nonpolar solvent cyclohexane was used. The spectra show (Table 1) that the Soret band of  $C_2\text{-Cap}$  has been red shifted by 5 nm with respect to  $C_1\text{-Cap}$ , and the shift is 8 nm in comparison with TPP. For TPP and  $C_2\text{-Cap}$  there is a red shift in the aromatic solvents, whereas  $C_1\text{-Cap}$  does not exhibit any difference between



aromatic and nonaromatic solvents. Soret maxima of metal complexes of porphyrins are sensitive to differences in groups at the periphery of the porphyrin ring, in axial ligands and in solvents<sup>11</sup>. Lewis acid-base interactions of metalloporphyrins with neutral ligands cause a red shift in this spectral characteristic, and the shift increases directly with the magnitude of interaction<sup>12,13</sup>. Taking zinc mesoporphyrin IX dimethyl ester in cyclohexane as the reference (Soret 397 nm), Corwin and co-workers<sup>14</sup> observed a red shift of 5 nm in toluene for this compound. A variety of nonpolar solvents also cause similar red shifts due to adduct formation<sup>15</sup>. Interestingly,  $\pi$ -donors as well as  $\pi$ -acceptors shift the Soret band in the same direction.

Based on these observations and considering the aromatic nature of the cap, it seems reasonable to ascribe the red shifts in these compounds to  $\pi$ - $\pi$  interaction between the porphyrin and the aromatic top of the cap. The extent of this interaction in  $C_2$ -Cap is perhaps equivalent to the interaction between TPP and toluene. Hence in toluene, Zn(TPP) has a maximum which is the same as that for Zn( $C_2$ -Cap) in all the solvents.

A comparison of the Soret band positions of  $C_2$ -Cap and  $C_3$ -Cap with that of TPP shows, at least qualitatively, that the intramolecular  $\pi$ - $\pi$  interaction is greater in Zn( $C_3$ -Cap) than in Zn( $C_2$ -Cap). This is in accord with the observation<sup>4,5</sup> that the  $O_2$  affinity of Fe( $C_2$ -Cap)(1,2-Me<sub>2</sub>Im) is greater than that of the corresponding  $C_3$ -Cap complex, and that both have a lower dioxygen affinity than does the open analogue complex, Fe(TPP)(1,2-Me<sub>2</sub>Im).

#### Acknowledgement

This work was supported by the National Institutes of Health Grant HL-13412 (FB).

#### References

1. J. ALMOG, J. E. BALDWIN, R. L. DYER and M. J. PETERS, *J. Amer. Chem. Soc.*, 1975, 97, 226
2. J. ALMOG, J. E. BALDWIN and J. HUFF, *J. Amer. Chem. Soc.*, 1975, 97, 227.
3. Abbreviations:  $C_2$ -Cap, dianion of the capped porphyrin, 5,10,15,20-[pyromellitoyl(tetrakis-*o*-ethoxyphenyl)]porphyrin;  $C_3$ -Cap, dianion of the capped porphyrin, 5,10,15,20-[pyromellitoyl(tetrakis-*o*-oxypropoxyphenyl)]porphyrin; TPP, dianion of meso-tetraphenylporphine; Por, dianion of a porphyrin, 1,2-Me<sub>2</sub>Im, 1,2 dimethylimidazole
4. J. E. LINARD, P. E. ELIS, Jr, J. BUDGF, R. D. JONES and F. BASOLO, *J. Amer. Chem. Soc.*, 1980, 102, 1896.
5. T. HASHIMOTO, R. L. DYER, M. J. CROSSLEY, J. E. BALDWIN and F. BASOLO, *J. Amer. Chem. Soc.*, 1982, 104, 2101.
6. F. A. WALKER, *J. Mag. Res.*, 1974, 15, 201.
7. W. R. SCHEIDT, M. E. KASTNER and K. HATANO, *Inorg. Chem.*, 1978, 17, 706
8. W. R. SCHEIDT and C. A. RIED, *Inorg. Chem.*, 1978, 17, 710
9. F. A. WALKER and M. BENSON, *J. Amer. Chem. Soc.*, 1980, 102, 5530.
10. J. ALMOG, J. E. BALDWIN, M. J. CROSSLEY, J. F. DEBERNARDIS, R. L. DYER, J. R. HUFF and M. K. PETERS, *Tetrahedron*, 1981, 37, 1589.
11. J. N. PHILLIPS in "Comprehensive Biochemistry", (Eds.) M. HOSKIN and E. H. STOLTZ, Elsevier, New York, 1963, Vol. 9, p. 58.
12. B. D. MCLEES and W. S. CAUGHEY, *Biochemistry*, 1968, 7, 642
13. S. J. COLL, G. C. CURTHROYS, E. A. MAGNUSSON and J. N. PHILLIPS, *Inorg. Chem.*, 1972, 11, 1024.
14. A. H. CORWIN, D. G. WHITTEN, E. W. BAKER and G. G. KLEINSPLIN, *J. Amer. Chem. Soc.*, 1963, 85, 3621
15. G. C. VOGEL and R. STAHLBUSH, *Inorg. Chem.*, 1977, 16, 950.

# Chaotropic Ions and Acid Buffers as Eluents in Ligand Purification Using Semiautomated Affinity Chromatography

R. PRASAD and S. T. NERENBERG\*

Department of Pathology, University of Illinois, College of Medicine,  
Chicago, Illinois 60612, U S.A.

A semiautomated technique using the principle of affinity chromatography has been developed for large scale purification of biospecific ligands. Among chaotropic ions and acid buffers as eluents, NaSCN proved to be a better eluting agent for CEA (carcino-embryonic antigen). The chaotropic ions (MgCl<sub>2</sub> and NaSCN), in general, were better eluents than acid buffers. The study was extended using biogel P-60, P-200 and P-300, as immunoadsorbents. Binding capacity of the three gels were in the ratio of 1.0 : 2.0 : 2.38. Use of P-300 as immunoadsorbent helped in the recovery of high affinity antibody.

**A**DVANCES in the field of immunology and immunochemistry<sup>1</sup> during the past two decades have necessitated an increasing need for purified ligands for detection or quantitation of biological substances in body fluids. Insoluble immunoadsorbent, utilizing the principle of affinity chromatography, serves as an elegant purification technique<sup>2,3</sup>. It is based on the formation of an immune complex between ligand and receptor components formed by covalently linking proteins to each other or to insoluble supports such as agar or sephadex gel. After the formation of the complex, the gel is washed free of uncoupled proteins. Thereafter, the complex is dissociated yielding the desired substances in a highly purified state. This principle has been used by various workers<sup>4,5</sup> utilizing techniques like column or batch for ligand purification. Both of these techniques are cumbersome and time-consuming whenever a sizable quantity of purified ligand is needed. This report describes an effort to semi-automate the batch technique and the experience with the apparatus using different types of immunoadsorbents, ligands and ligand-dissociating fluids.

## Apparatus :

1. Amicon Company pressure dialysis units, Models No. 402 and 12 :

Amicon Model No. 12 was used for processing small amounts of immunoadsorbent (about 1.5-2.0 g), whereas Model No. 402 was used for larger quantities (about 75-100 g). The molecular membranes in the latter units were replaced by nylon polyester cloth (pore size 400×400 which allowed fluids to escape while retaining the immunoadsorbents). Positive pressure (2-5 pounds/in<sup>2</sup>) from a nitrogen tank was used to rapidly evacuate the fluids from the unit's chambers.

2. Home made elution unit :

The chambers of the units are constructed of tubular acrylic plastic measuring 10.5 cm in length and 7.5 cm in outside diameters. The walls measure 0.5 cm in thickness. Both ends are threaded for a




Fig. 1. Exploded view of the elution chamber.

\* Present address : Chief of Laboratories, V. A. Hospital, Long Beach, California,

distance of 1.5 cm. The ends are closed by threaded end pieces (cap and base) measuring 9 cm in diameter and 3 cm in depth, each of which contains an O-ring measuring 7.5 cm in diameter. The base is fitted with a porous filter support disc which, in turn, is covered with a nylon filter cloth secured in position by an O-ring. A discharge tube measuring  $2 \times 0.5$  cm (to drain the chamber) is included in the base as shown in Fig. 1.

A 2.6 cm hole to accommodate a No. 4 rubber stopper is drilled through the cap 2 cm from one edge. A teflon rod measuring 18 cm in length and 1 cm in diameter is suspended from the midportion of the upper cap by two tightly fitted grommets recessed in the inner and outer surfaces of the cap, respectively. A swivel, inserted into the lower end of the teflon rod, in turn, is fitted with a teflon-coated magnetic stirring bar measuring  $5.4 \times 1$  cm. Although airtight, the teflon rod may be raised or lowered.

The rubber stopper is inserted from the inside of the cap to prevent its displacement under pressure. A plastic Y-tube (size 5/16") contained in the stopper allows the latter to be displaced, but prevents it from falling into the chamber. One end (of the two external openings) in the Y-tube is connected to a two-part plastic connector; the wall of the outer portion of the connector is closed by fusing the edges with a flame. The other end of the Y-tube is connected to a common supply tube (C).




Fig. 2. Semiautomated batch elution from affinity type immunoadsorbent.

Four such elution units are normally positioned on multi-magnetic stirrer platform (Fig. 2); their respective discharge tubes are connected below to a closed, common plastic drainage tube (H) filled with a spout at one end. The tube ( $3.0 \times 3.5$  cm) is held at an angle of  $15^\circ$  to the table top by two feet, unequal in heights, measuring respectively 4 and 2 cm. Each of the elution units is connected above to the common supply tube (C) by plastic tubing (fitted with clamps).

The common supply tube containing four entry portals (labeled 1, 2, 3 and 4 in Fig. 2) is connected to a supply of saline, buffer No. 1, buffer No. 2 or chaotropic solution and to a nitrogen tank, respectively. Inserted between the buffer supply No. 1 and No. 2 are two disposable 100 ml plastic burettes. Clamps are attached to the tubing leading from the saline, buffers, chaotropic solution and  $N_2$  tank supplies. The apparatus between the salines and the elutions units are attached to a wooden back-board which can be tilted to completely empty the common supply tube when necessary. Operation of this home-made unit is essentially similar to the commercial units.

#### Materials and reagents :

**Immunosorbents :** Protein co-polymer, Sephröse and Biogel P-300, each containing a complexed monospecific antibody or antigen.

Phosphate buffer saline (PBS),

Glycine HCl 0.1 M pH 2.5,

Chaotropic ionic solution (3 M  $MgCl_2$  and 3 M  $NaSCN$ ),

Urine containing kappa L-chains obtained from patient with kappa-type myeloma, lyophilized and stored at room temperature until the kappa L-chains were purified,

Carcinoembryonic antigen was purified from a case of colonic carcinoma.

#### Experimental

**Radiolabeled studies (preliminary experiments) :** To avoid contamination of the apparatus by radioactive materials, the following preliminary experiments were carried out with radio-labeled materials in test tubes :

- 1) Capacity studies of different type gels (P-60, P-200, P-300).
- 2) Elution studies using acid buffer at different pHs.
- 3) Elution studies using chaotropic ions.

**Non radio-labeled studies :** Those studies were carried out using the apparatus as described earlier.

- a) Purification of kappa L-chains.

#### Preparation of immunoadsorbents :

Goat anti-human IgG and rabbit anti-CEA antibody ( $\gamma$ -fractions) respectively were covalently

bonded to Biogel P-60 (100-200 mesh), P-200 (100-200 mesh) and P-300 (-400 mesh) as directed by Avrameas and Ternyck<sup>6</sup> by first activating the gels by using 6% solution of glutaraldehyde in 0.1M phosphate buffer adjusted to pH 7.0. Thirty (30) mg of the antiserum was mixed with 10 ml of centrifuged and activated beads for sensitization.

Simultaneously 10 mg of  $\gamma$ -fractions of anti-IgG antibody and anti-CEA antibody were covalently bonded to 1 g of CNBr-activated Sephrose 4B as directed by Pharmacia<sup>7</sup>.

#### Preparation of antisera :

Antisera were produced in rabbits against kappa L-chains and carcinoembryonic antigen (CEA) as previously described<sup>8</sup>. The antisera were absorbed by insolubilized serum proteins, and in the case of anti-CEA, by insolubilized extracts of normal colon until they were monospecific. Their IgG fractions were then isolated as described earlier<sup>1</sup>.

#### Preparation of radio-labeled antigen :

One hundred (100) mg of chromatographically purified human IgG in 50 ml of 0.2 M phosphate buffer pH 7.2 was mixed with 10 ml of Na<sup>125</sup>I (1 mCi) and 25 ml of enzymebead and the reaction was allowed to proceed for 20 min at room temp using 1% beta D-glucose as suggested by Biorad<sup>9</sup>. <sup>125</sup>I tagged protein was separated from unattached <sup>125</sup>I by gel filtration in Sephadex G-50. <sup>125</sup>I-CEA was obtained from a commercial source (Hoffman-La Roche, Nutley, N. J. 07110).

#### Saturation of immunoadsorbents with radiotagged ligands (IgG and CEA) :

Radiolabeled antigens were incubated with their homologous immunoadsorbents monospecific for IgG and CEA, respectively. The incubations were allowed to continue overnight following which the gels were thoroughly washed with PBS. The radiolabeled ligands were then eluted with 0.1M acetate buffer pH 4.0 and 0.1M glycine-HCl buffers pH 3.5 to 1.4 and with chaotropic ionic solutions (3M MgCl<sub>2</sub> and 3M NaSCN).

#### Binding capacity of polyacrylamide gels :

Equal amounts of Biogel P-60, P-200 and P-300 were saturated with an excess of <sup>125</sup>I-IgG (11.5 mg). After overnight incubation, the gels were thoroughly washed, the radioactivity counted and the amount of protein associated with each gel was determined. Controls (unsensitized gels) were to react with equal amounts of labeled proteins under identical conditions and the nonspecific attached radioactivity was then to be determined.

#### Elution procedure :

In the preliminary experiment, equal amounts of complexed immunoadsorbents (Biogel and Sephrose 4B) were taken in different tubes coated with BSA, and mixed with equal volume of various ligand dissociating fluids at room temp. At a regular interval extending from 30 min to 92 hr, the tubes were centrifuged and radioactivity of an aliquot counted following which the beads were resuspended. Results are recorded in Tables 1 and 2.

The purification procedure was further extended using affinity chromatography. According to their binding capacities, amounts of P-60, P-200 and P-300 complexed immunoadsorbents containing equal amount of attached antigen were equilibrated in different columns and washed thoroughly with PBS till the washings were very near the background counts. Antigen (<sup>125</sup>I-CEA) was eluted with 3M NaSCN and the eluates counted.

Use of semi-automated technique was also made to study the purification of a protein on a mass scale. In one set, polymerized normal human serum was complexed with goat anti-human and a homologous purified antiserum was eluted by 3M MgCl<sub>2</sub>. In another set, human kappa light chain was isolated from anti-kappa chain immunoadsorbent and kappa chain lyophilized urine using 0.1M glycine-HCl pH 2.4 as the elution fluid.

#### Recovery of kappa L-chains :

Lyophilized urine containing kappa L-chains (78.6 mg) was incubated with 40 ml of P-300 sensi-

TABLE 1—ELUTION OF IgG (%) USING BATCH TECHNIQUE

Elution system	Time													
	30 min		60 min		120 min		180 min		20 hr		44 hr		68 hr	
	P-300	Seph 4B	P-300	Seph 4B	P-300	Seph 4B	P-300	Seph 4B	P-300	Seph 4B	P-300	Seph 4B	P-300	Seph 4B
0.1 M acetate pH 4.0	—	—	0.5	0.0	0.9	0.0	0.5	0.0	1.2	0.4	3.5	0.2	—	0.6
0.1 M Gly-HCl pH 3.5	—	—	7.7	10.6	10.5	9.6	12.3	9.7	27.9	13.0	42.9	23.6	—	33.3
0.1 M Gly-HCl pH 3.0	—	—	15.6	40.2	24.1	28.5	25.2	24.3	36.2	46.3	—	—	—	20.5
0.1 M Gly-HCl pH 2.5	—	—	33.8	56.8	41.1	53.6	49.8	53.1	59.2	64.3	—	—	—	43.8
0.1 M Gly-HCl pH 2.0	—	—	47.5	57.3	52.6	56.8	53.5	54.1	59.3	55.8	—	—	—	51.0
0.1 M NaCl-HCl pH 1.4	—	—	55.2	61.6	54.3	51.0	54.6	48.1	56.0	59.9	—	—	—	32.7
3 M MgCl <sub>2</sub>	—	—	19.2	74.9	25.6	72.0	37.4	76.2	37.7	88.0	52.8	82.4	—	80.0
3 M NaSCN	—	66.5	22.0	77.8	29.9	84.0	29.2	85.0	42.3	51.1	—	—	—	—
		70.7								91.2				

**TABLE 2—ELUTION OF CEA (%) USING BATCH TECHNIQUE**

Elution system	Time									
	30 min	60 min	120 min	240 min	20 hr	44 hr	68 hr	92 hr		
	P-300	P-300	P-300	P-300	P-300	P-300	P-300	P-300	P-300	P-300
	Seph 4B	Seph 4B	Seph 4B	Seph 4B	Seph 4B	Seph 4B	Seph 4B	Seph 4B	Seph 4B	Seph 4B
0.1 M acetate pH 4.0	1.0	1.0	7.3	6.8	10.5	35.0	32.4	32.5		
0.1 M Gly-HCl pH 3.5	2.4	2.4	4.0	3.8	18.2	37.5	25.3	28.8		
0.1 M Gly-HCl pH 3.0	7.2	8.3	21.3	22.8	43.1	55.6	49.5	53.4		
0.1 M Gly-HCl pH 2.5	11.6	16.0	33.5	37.1	53.8	52.1	47.1	47.1		
0.1 M Gly-HCl pH 2.0	22.7	26.5	28.0	39.3	40.8	57.4	58.1	58.1		
0.1 M NaCl-HCl pH 1.4	30.7	30.6	38.1	38.9	56.8	61.2	58.3	64.2	61.2	
3 M MgCl <sub>2</sub>	2.0	6.4	17.1	26.1	41.9	55.5	54.3	63.5		
3 M NaSCN	4.8	20.9	28.7	39.6	50.0	72.4	82.7	84.7		
		53.7	63.1	71.4	99.0					

tized with radio-tagged homologous antibody. The unbound protein in the supernatant was then determined. The immunoadsorbent was exhaustively washed until no further protein could be determined in the wash fluid at 280 nm. The immunoadsorbent was then transferred to the chamber of the apparatus and washed several times with 0.1 M phosphate buffer pH 7.0 followed by successive aliquots of 50 ml of 0.1 M glycine-HCl buffer pH 3.5 to elute attached proteins. The latter step was repeated until the O.D. was less than 0.5 at 280 nm (12 elutions).

### Purification of CEA :

58.2 mg of gamma fraction of homologous anti-CEA antiserum incorporated in biogel P-300 immunoadsorbent was incubated overnight at 45° with perchloric acid extract of colonic adenocarcinomatous tissue. Following incubation, the gel was thoroughly washed with 0.1 M ammonium acetate pH 6.25 and two washes of PBS. CEA was eluted with acid buffers and chaotropic ions.

## Results

With a little practice the apparatus proved to be simple to operate. The amount of ligand recovered depended on a variety of factors, viz, amount immunoadsorbent used, avidity of the antiserum, length of incubation period of the ligand with the immunoadsorbent, etc. Contamination of eluted ligand by extraneous proteins varied from a total absence to moderate depending on a number of factors, chief of which was the duration and effectiveness of the saline washing cycle. When the optical density at 280 nm of the wash fluid approached zero, contamination was usually negligible but not invariably so.

It proved to be expedient to follow the saline wash with an acidic wash which at times eliminated contaminants released by the more acidic eluting fluid. When a protein copolymer was used as the immunoadsorbent, albumin and prealbumin in small quantities were continuously leached into the ligand eluting fluid so that it had to be removed by Sephadex gel chromatography.

The chief advantage of the apparatus described here lies in the ability of the operator to rapidly carry out sequential steps in the attachment, washing and elution of the ligand *in situ*, repeating the cycle as often as necessary to obtain the desired amount of ligand. The concentration of the ligand in the solution is immaterial since the latter binds to the immunoadsorbent, with the result that very dilute solutions can readily be used to saturate the polymer.

For large scale purification of a ligand, it is necessary to optimize the elution conditions. Results on the purification of IgG and CEA using acid buffers and chaotropic ions have been recorded in Tables 1 and 2. The numbers represent the percent of the total ligand initially bound to the immuno-adsorbent.

**Dissociation using acid buffers :**

0.1 M acetate pH 4.0 and 0.1 M glycine-HCl pH 14 to 3.5 were used as the dissociating fluids. Recovery of IgG (Table 1) was 33.8% when pH 2.5 buffer was incubated for 1 hr with P-300 immuno-adsorbent. Under similar conditions, Sephrose 4B gel yielded 56.8%. Increase in the incubation time did not increase the yield but a lower pH increased the recovery as expected. Recovery from Sephrose 4B immuno-adsorbent, in general, was greater than from P-300 as is evident from Tables 1 and 2. Results on the recovery of CEA (Table 2) were similar to that of IgG.

**Dissociation using chaotropic ions :**

Tables 1 and 2 delineate the use of 3 M MgCl<sub>2</sub> and 3 M NaSCN as eluents for human IgG and CEA Sephrose 4B immunoabsorbent, in contact with the chaotropic ions for 3 hr, released 76.2 to 85% of the ligand (IgG), whereas under similar conditions P-300 complex yielded around 37%. Sephrose 4B complex, when incubated for 1 hr with either of the ions, yielded over 74%, whereas the recovery from P-300 complex was only around 22%. Recovery of CEA was similar to that of IgG. It is, however, interest-

ing to note that sodium thiocyanate recovered more CEA than  $\text{MgCl}_2$ .

#### Recovery using semi-automated affinity chromatography :

Results of previous experiments (Tables 1 and 2) helped set-up the final recovery experiments using semi-automated affinity technique. Table 3 presents two sets of data where 30 g and 50 g of immunoadsorbents were incubated with 10 ml of solution containing human antibody. Acid buffer pH 2.0 recovered 204 mg/ml of the ligand whereas with  $\text{MgCl}_2$ , the yield was 370.1. Sequential recoveries using different acid buffers and varying concentration of  $\text{MgCl}_2$  are also recorded in Table 3. Purity of the antibody was checked by radial immunodiffusion (RID) and immunoelectrophoresis (IEP).

TABLE 3—ELUTION OF ANTIHUMAN ANTIBODY USING SEMIAUTOMATED TECHNIQUE

Elution system	Kappa light chain	Antihuman antibody (mg/ml)	
		Immunosorbent : 30 g	Immunosorbent : 50 g
Glycine-HCl (0.1 M, pH 3.0)	+	97.8	120.0
Glycine-HCl (0.1 M, pH 2.5)	++	163.2	204.3
Glycine-HCl (0.1 M, pH 2.0)	++	204.0	217.5
$\text{MgCl}_2$ (1.0 M)	+	102.2	127.5
$\text{MgCl}_2$ (2.0 M)	++	125.3	156.3
$\text{MgCl}_2$ (3.0 M)	+++	370.1	462.5

CEA and kappa light chains were also purified in similar manner. Recovery of CEA was 22.5 mg/ml

and that of kappa light chain 16.7 mg/ml. In another experiment, human IgG was purified using DEAE Sephadex. 50 ml of normal human serum yielded 10 mg of the immunoglobulin. Purity of these proteins were also confirmed by RID and IEP.

#### Binding capacity of polyacrylamide gels :

Table 4 records the binding capacity of Biogel P-60, P-200 and P-300, where gamma globulin was covalently attached to the gel matrix using glutaraldehyde. Results have also been represented graphically in Fig. 3. In successive experiments where IgG (gamma globulin) was covalently bonded to P-60,

TABLE 4—BINDING CAPACITY OF POLYACRYLAMIDE GEL TO GAMMA GLOBULINS

Gel	Wet weight of gel (g)	Gamma globulin (mg)	Gamma globulin attached (mg)*	Binding capacity P-60 : P-200 : P-300
P-60	2.8	11.52	1.61	
P-200	3.0	11.52	3.23	1 : 2 : 2.38
P-300	2.3	11.52	3.83	

\* per wet weight (g) of gel.

P-200 and P-300, 4.0 mg of the protein could not saturate either of the gels (2.8 g of P-60, 3.0 g of P-200 and 2.3 g of P-300), 8.0 mg of IgG could saturate only P-60, whereas 11.5 mg of IgG saturated all the three gels. Capacity of the gels when calculated in terms of IgG/g was found to be in the ratio of 1 : 2 : 2.38 (Table 4) for P-60, P-200 and P-300, respectively. The capacity experiment aided in the establishment of three different affinity columns using P-60, P-200 and P-300 gels containing the same amount of antigen. On elution with 3 M NaSCN, 49.6% and 40.0% of the antibody was isolated in




Fig. 3. Recovery of CEA with P-60, P-200 and P-300 immunoaffinity columns.

void volumes of P-60 and P-200, whereas only 24.5% was isolated in the void volume of P-300 and 27% in the later fractions (Fig. 3).

### Comments and Conclusion

That the affinity type of adsorption and desorption applied to insolubilized immunoadsorbents is revolutionizing the purification of biospecific substances is attested to by the rapidly burgeoning mass of literature on the subject. Although the initial enthusiasm for this technique has been dampened somewhat by the realization that a number of shortcomings are inherent in the technique, particularly non-specific adsorption of contaminants, the deficiencies have been offset by expansion of the approach to different types of specimens. Because of the general utilitarianism and widespread use of affinity procedures, development of more rapid, semi-automated and automated techniques to reduce the expenditure of work and time associated with the procedure is of practical importance. The simple apparatus described in this communication provides the opportunity to effectively speed up the purification of substances on a preparative scale. With respect to the type of immunoadsorbent used, simple precipitation of the gamma fraction of a monospecific antiserum by 10% polyethylene glycol (PEG) followed by polymerization with glutaraldehyde provides a rapid, simple procedure for preparing efficient immunoadsorbents which are often preferable and more economical than commercially supplied pre-sensitized gels. Also, less complete but more frequent elution of a substance coupled to a ligand are more efficient than prolonged elution<sup>4</sup>. Our results have shown that ten to twenty elutions are required to release the major portion of a bound substance from its ligand. Finally, it is pertinent to point out that the apparatus may be used to advantage for purifying substances by the ion-exchange principle as described for IgG.

Although there is little doubt that sophisticated, automated equipment and techniques will be developed in the near future to deal with the purification of substances by the affinity principle, the simple approach described above is immediately available

for use. Recovery results of all the elutions have been reported in Tables 1, 2, 3 and Fig. 3. As expected, recovery is higher at a lower pH but it is also evident that chaotropic ions ( $MgCl_2$ ,  $NaSCN$ ) dissolve and dissociate antigen-antibody complexes. Dissociation of complexes with  $MgCl_2$ ,  $NaSCN$  occurs rapidly in contrast with acid dissociation, for which contact times of several hr are needed for a significant recovery. The protein immunospecifically purified by the chaotropic ions retained its ability to combine with ligand to form soluble and insoluble complexes. In 3M  $NaSCN$  and 3M  $MgCl_2$ , the concentration used for protein purification, no significant amount of irreversible gross structural changes was noted in any of the proteins. Saussure and Dandliker<sup>10</sup> observed that at 4.5 M and above, SCN caused changes in the sedimentation behaviour of gamma globulin, antigen and complexes. These changes were reversible by dialysis.

### Acknowledgement

The authors express their thanks to Dr. Truman O. Anderson, acting Head of the Department of Pathology for research facilities and to Pat Berg and Chris Gonzalez for secretarial assistance.

### References

1. D. M. WEIR, "Handbook of Experimental Immunology", Vol. I "Immunochemistry" and Vol. III "Application of Immunological Methods", Blackwell Scientific Publications, Oxford, 1978
2. S. T. NERENBERG and R. PRASAD, *J. Lab. Clin. Med.*, 1975, **86**, 887
3. S. T. NERENBERG and R. PRASAD, *Clin. Chim. Acta*, 1977, **74**, 237.
4. P. CUATRECASAS and C. B. ANFINSEN, "Methods in Enzymology", Vol. XXII, Academic Press, New York, 1971
5. Bio-Rad Laboratories; "Reference list on Affinity Chromatography", 1979.
6. T. TERNYCK and S. AVRAMEAS, *FEBS Letter*, 1972, **23**, 24.
7. M. STEVEN, I. PARIKH and P. CUATRECASAS, *Anal Biochem*, 1974, **60**, 149
8. S. T. NERENBERG, R. PRASAD, L. PEDERSEN, N. S. BISKUP and I. FAIFERMAN *Clin. Chem.*, 1980, **26**, 209.
9. M. MORRISON and G. S. BAYSE, *Biochem*, 1970, **9**, 2995.
10. V. A. DE SAUSSURE and W. B. DANDLIKER, *Immunochem.*, 1969, **6**, 77.

## Biochemical Fuel Cells

GIRJESH GOVIL\* and ANIL SARAN


Biochemical Fuel Cell Project, Tata Institute of Fundamental Research,  
Homi Bhabha Road, Bombay-400 005

The need for tapping sources of energy other than the conventional ones necessitates the development of biochemical fuel cells in which a large variety of biomass can be used as fuels. The present status of biochemical fuel cells is reviewed. The main drawback of such fuel cell is the slow transfer of electrons from the substrate to the electrodes. Both experimental and theoretical studies have been started to understand the basic processes underlying the electron transfer in such systems. Preliminary results of such studies are very encouraging and further work in the area is in progress


OUR energy demands are increasing and in view of the sky-rocketing price of petroleum products and the depletion of natural resources, it is becoming increasingly clear that sources of energy other than the conventional ones have to be tapped to meet the situation. The awareness of this situation and the possibilities of finding new sources of energy in the context of our own country have been highlighted recently<sup>1</sup>.

The main conventional sources of energy today are fossil fuels, hydroelectricity and nuclear energy. Each of these has its own limitations and associated hazards. The devices using fossil fuels like coal, gasoline, diesel etc. generally operate through a heat cycle (Carnot cycle). The fuel is oxidised (burnt) and the thermal energy produced is utilized either to drive mechanical engines or is converted into electrical energy. The efficiencies of such devices are, however, limited by Carnot cycle and one obtains efficiency upto about 20%. To increase the efficiency of these systems, one has to go to higher operating temperatures which is again restricted by technological difficulties. It is, therefore, logical to look for devices which can directly convert chemical energy into electrical energy. This is, basically, accomplished in a fuel cell and the efficiency in fuel cell can be as high as 50%.

A fuel cell (FC) is an electrochemical device in which part of the energy derived from chemical reaction maintained by a continuous supply of chemical reactants is converted into electrical energy. In a biochemical fuel cell (BFC) the oxidation (burning) of bioorganic materials (fuels) is catalysed by specific enzymes. The electrochemical reactions usually take place with air as oxidant at the cathode while the enzymes catalyse the oxidation of bioorganic material at the anode. In general, one uses hydrogen or hydrogen rich fuels ( $\text{SH}_2$ ) such as methane, methanol, ethanol, carbohydrates, etc. The energy producing reaction is the oxidation of hydrogen by oxygen



Such that the net reaction is



Each cell based on above reaction can produce few hundred watts of d.c. power. In a fuel cell power plant, several such cells can be stacked together.

Historically, the concept of biochemical fuel cell is not new. As far back as in 1911, Potter<sup>2</sup> observed that "disintegration of organic compounds is accompanied by the liberation of electrical energy". He constructed the first biochemical fuel cell and obtained voltages upto 0.35 volts from yeast-glucose systems. Cohen<sup>3</sup> in 1931 did more precise work on generation of electrical energy from various cultures and sterile media. There was then a period of relatively low activity until early 1960's when the interest in biochemical fuel cells revived<sup>4-6</sup>. This activity was also initiated by several governmental and non-governmental agencies in U.S. like NASA, Magna Corp., GEC, Ford Motors, Marquardt Corp., Electron Molecule Research Inc., General Scientific Corp., etc. but most of the outcome has remained classified for obvious reasons.

### Design of biochemical fuel cells :

Fuel cells are different from batteries. This is due to the fact that fuel cells can supply power intermittently (reactants are fed and products removed continuously) and that the electrodes are not consumed. Most of the inorganic fuel cells use either highly alkaline (30-80% KOH) or highly acidic electrolyte media<sup>7</sup>, oxidation of hydrocarbon, methanol, ammonia or hydrogen as fuels and relatively expensive metallic electrodes to stand highly corrosive conditions. One has also to use high temperature and pressure because the fuels have a high activation energy and do not oxidize under ambient conditions. It is here that the use of specific enzymes (or bacteria) helps by lowering the barrier to chemical reactions and thus making the electrochemical reactions feasible under milder conditions. It has been estimated that for a direct electron transfer process, a current of the order of  $10^{17}$  amp (at 1 volt) can be delivered by using 1 kg of enzyme<sup>8</sup>. For all practical purposes even a



millionth of the above current ( $10^{11}$  amp for 1 kg of pure enzyme) will be of valuable commercial application.

In the direct biochemical fuel cell, the oxidation of raw fuels such as starch, carbohydrate or protein is achieved with the help of bacteria via a stepwise transfer of protons involving several classes of enzymes and coenzymes (such as NAD), flavoprotein, cytochromes and coenzymes Q provided by the bacteria. The combustion rate in such cells is low since the reactions have to be carried out in a narrow range of pH and temperature.

The indirect biochemical cell works in two steps. The first step involves the conversion of raw fuel into simpler biochemical end products such as  $H_2$ ,  $CH_4$ ,  $NH_3$ ,  $CH_3OH$ , etc. with the help of suitable bacteria. The secondary fuel, thus generated, is transferred to a second compartment where the electrical power is generated in one step enzymatic oxidation of such products. While such systems are quite convenient and easier to optimize, there is an additional engineering problem which is the transfer of secondary fuel to the fuel cell compartment. Both types of biochemical fuel cells have been reported in the literature<sup>4-6,9-12</sup>.

Many organic waste materials or natural sources can be used as fuel in biochemical fuel cells. Sisler<sup>4</sup> reported a biochemical fuel cell which worked on undiluted sea water (which contains plant-carbohydrates synthesized by marine algae) through sulphate reducing bacteria, *Desulfovibrio desulfuricans* and obtained approx 0.5 volt with a current output of 1 milliamp. Colichman<sup>6</sup> extended Sisler's study to a much broader application by utilizing various bio-fuels and obtained a better power level with fresh mushrooms serving as fuel by the catabolic action of *Desulfovibrio desulfuricans*. Many other biochemical fuel cells have been reported and some of these are :

- (i) hydrocarbon (natural gas) as fuel and hydrocarbon oxidizing bacteria as catalyst<sup>10,14</sup>,
- (ii) urea (urine) as fuel and urease (*Bacillus pasteurii*) as catalyst<sup>9</sup>,
- (iii) glucose as fuel and glucose oxidase as catalyst<sup>11</sup>,
- (iv) organic materials and hydrogenase to produce  $H_2$  gas for use in the indirect fuel cells<sup>12</sup>.

#### Design difficulties :

There are several difficulties in designing biochemical fuel cells which provide challenges to technologists as well as to basic scientists. These systems have intrinsically low voltages (a typical redox system has voltage  $\sim IV$ ) and hence they have to operate at high current densities to be of any practical use. The following problems arise in operating the systems at high current densities :

- (i) The transfer of electrons from the enzyme-fuel system to electrode is rather slow. At present there is no obvious solution to this problem although several groups are interested in electron transfer from biological macromolecules to conductors,

- (ii) The electrolyte should have a low electrical resistance and the extreme pH conditions or salt concentrations which are needed to increase the electrical conductance are injurious to the bacterial system. This problem can be overcome by the use of indirect cell system,
- (iii) The electrodes have to be designed from expensive materials and they have relatively short life due to corrosion and bacterial contamination. This problem again can be avoided by the use of indirect fuel cell operating on pure enzyme systems,
- (iv) One should be able to produce stable enzymes with sufficient kinetic activity and in bulk quantity at relatively low cost. Several enzymes are now commercially available and their prices are also decreasing.

#### Coenzyme immobilised anodes for BFC :

Many biological oxidation-reduction reactions utilise a coenzyme as a proton and electron carrier which functions in conjunction with a covalently linked enzyme specific for the substrate used as fuel. A typical example is glucose oxidase which uses flavin adenine dinucleotide (FAD) as a coenzyme in the oxidation of glucose to gluconic acid. The




Fig. 1. The oxidation-reduction cycle of FAD which involves transfer of two protons and two electrons. Electrons are transferred to the electrode in step IV $\rightarrow$ I while the oxidised form is enzymatically reduced to FADH<sub>2</sub> (III) by the substrate which releases two protons and two electrons. The protons released in step III $\rightarrow$ IV are absorbed by the buffer and transported to cathode compartment.

complete redox cycle of this coenzyme is schematically represented in Fig. 1. The oxidation of fuel (SH<sub>2</sub>) in presence of the enzyme (E) liberate two protons and two electrons. These can be taken up by the oxidised FAD (I) to give FADH<sub>2</sub> (III). Likewise, the regeneration of oxidised form of FAD involves sequential release of two protons (IV) and two electrons (I). In the fuel cell (Fig. 2), the two protons have to be transported from the anode compartment to the cathode. Protons being water soluble, they can easily pass into the aqueous phase from the coenzyme and then to the cathode compart-

ment. On the other hand, the two electrons have to be passed on to the electrode by a suitable mechanism. Our approach to circumvent this problem is based on immobilisation of FAD on graphite through semiconducting linkages such that an electron transport bridge can be established for a direct passage of electrons to the graphite anode. Such an electrode can then serve as a bioanode. In conjunction with an oxygen electrode, the biochemical fuel cell can yield voltages of 1 V or higher<sup>12</sup>.




Fig. 2 The conceptual drawing of a biochemical fuel cell based on FAD. The FAD immobilized on graphite is used as a cathode. Protons are transferred from the anodic to cathodic compartment giving rise to an internal proton current as opposed to electron current in the external circuit.

We have made systematic molecular orbital studies of the electron-flow diagrams of riboflavin during its redox cycle. The calculations show, as expected for aromatic ring systems, that the charge

distributions in all the four states of FAD are highly delocalised. However, in the electron release step IV→I the largest electron flux occurs from the two carbonyl groups. These then should serve as ideal sites for immobilising flavin on graphite through semiconducting linkages. The chemical steps involved in this process involves creating active centres on the graphite surface which can then be condensed with FAD to form covalent linkages between the electrode and the coenzyme. Cyclic voltamograms of the modified electrode show that FAD is active and undergoes the expected redox cycles. Further work on the design of BFC based on this approach is in progress.

#### References

1. Physics News, Bulletin of the Indian Physics Association, Vol. 11, No. 4, December 1980.
2. M. C. POTTER, *Proc. Royal Soc. (London)*, 1911, B84, 260.
3. B. COHEN, *J. Bact.*, 1931, 21, 18.
4. F. D. SISLER, *New Scientist*, 1961, 12, 110.
5. B. J. WILSON, NRL Report 5998, Oct. 4, 1963.
6. E. L. COLICHMAN, *Proceedings of IEEE*, 1963, p. 812.
7. J. HOWARD, *New Scientist*, 1971, 48, 528.
8. I. V. BEREZIN and S. D. VARFOLMEEV, *Appl. Biochem. Bioeng.*, 1979, 2, 259.
9. K. LEWIS, *Bact. Rev.*, 1966, 30, 101.
10. F. D. SISLER, *Progr. in Industrial Microbiology*, 1971, 9, 1.
11. L. B. WINGARD, C. C. LIU and N. L. NADGA, *Biotechnol. Bioeng.*, 1971, 13, 629.
12. G. C. BLANCHARD and R. T. FOLEY, *J. Electrochem. Soc.*, 1971, 118, 1232.
13. W. VAN HEES, *J. Electrochem. Soc.*, 1965, 112, 258.
14. J. B. DAVIS and H. F. YARBROUGH, Jr., *Science*, 1962, 137, 615.
15. R. S. PHADKE, H. M. SONAWAT and G. GOVIL—to be communicated.

# Metal Ammine Formation in Solution. Part-XXIII: The Nickel(II)-Mono- and Diethanolamine Systems

JANNIK BJERRUM and FREDRAG DJURDJEVIC\*

Department I, Inorganic Chemistry, H. C. Ørsted Institute, University of Copenhagen,  
DK 2100 Copenhagen Ø, Denmark

This paper reports a potentiometric and spectrophotometric study of the nickel(II)-mono- and diethanolamine systems. The metal ammine formation was studied by glass electrode measurements in 2 M  $\text{amHClO}_4$  and 0.5 M  $(\text{amH. Na}) \text{ClO}_4$  solutions at 25° and the stability constants determined. The effect of the partly coordinated alcohol groups on the stability constants is considerable. The nickel(II) ion shows little tendency to bind more than two diethanolamine and three monoethanolamine molecules. Spectrophotometric measurements show that aqueous nickel(II) solutions with more than 60 weight per cent of monoethanolamine and  $\text{pH} > 12$  have unchanged absorption on further addition of amine. These solutions are presumed to contain a deprotonated species with less than four amino groups bound to nickel.

IN continuation of a paper by Agarwala and Bjerrum<sup>1</sup> on the nickel(II)-triethanolamine system the stability constants of the nickel(II)-mono- and diethanolamine complexes under the same experimental conditions are determined in the present paper. Potentiometric measurements of these systems have previously been made by the Russian authors<sup>2-4</sup> and spectrophotometric measurements in alcoholic and aqueous solutions have also been performed by them<sup>5-7</sup>. In the present paper spectrophotometric measurements have been made in 2 M ethanolammonium perchlorate solutions and in strong aqueous monoethanolamine solutions with up to 92 weight per cent of the amine.

## Experimental

**Reagents and solutions:** All reagents were of analytical grade. The monoethanolamine (Fluca, puriss) was distilled under atmospheric pressure and

the main fraction boiling at 165° was used without further purification. The diethanolamine (Fluca, puriss) was distilled at ~10 mm Hg and the main fraction boiling at 160-163° was used without further purification. The various solutions were prepared in volumetric flasks by weighing or pipetting from stock solutions. A 50 M stock solution of the ethanolammonium perchlorate was prepared by neutralizing 1 liter 5.00 M  $\text{HClO}_4$  with the amine and diluting to 2 liters. Complete equivalence between amine and perchloric acid was ensured as described earlier<sup>1</sup>. All mass action constants are concentration constants (mol/liter units) in the applied medium. Other experimental details were the same as in the preceding paper<sup>1</sup>.

**Discussion of pH measurements:** The results of some of the measured solutions are shown in Table 1. All concentrations are in M/l and the ligand number

TABLE 1—SELECTED RESULTS OF GLASS ELECTRODE MEASUREMENTS OF NICKEL(II)-MONO- AND DIETHANOLAMINE PERCHLORATE SOLUTIONS AT 25°

No.	$C_{\text{meOH}}$	$C_{\text{Na}}$	$C_{\text{Ni}}$	$C_{\text{mea}}$	$p[\text{mea}]$	$\text{pH}$	$n$
1	0.50	0	0.01046	0.00397	3.514	6.326	0.350
2	0.50	0	0.01046	0.0159	2.634	7.206	1.298
3	0.50	0	0.01046	0.0496	1.644	8.196	2.572
4	0.50	0	0.01063	0.0992	1.168	8.672	2.940
5	2.00	0	0.1154	0.0498	3.595	5.905	0.429
6 <sup>a</sup>	2.00	0	0.1154	0.1332	2.990	6.510	1.145
7 <sup>b</sup>	2.00	0	0.1154	0.1663	2.814	6.686	1.428
8	2.00	0	0.1154	0.3322	1.637	7.863	2.679
9	2.00	0	0.1154	0.4155	1.187	8.313	3.037
	$C_{\text{deaH}}$	$C_{\text{Na}}$	$C_{\text{Ni}}$	$C_{\text{dea}}$	$p[\text{dea}]$	$\text{pH}$	$\bar{n}$
10	0.100	0.400	0.0115	0.00536	2.960	5.980	0.370
11	0.100	0.400	0.0115	0.00965	2.631	7.309	0.636
12	0.100	0.400	0.0115	0.0268	1.924	8.016	1.296
13	0.100	0.400	0.0115	0.0386	1.680	8.260	1.530
14	0.50	0	0.0115	0.00643	2.858	6.372	0.438
15	0.50	0	0.0115	0.0107	2.570	6.660	0.697
16	2.00	0	0.0577	0.0215	3.380	5.650	0.365
17	2.00	0	0.0577	0.0322	3.107	5.923	0.345
18	2.00	0	0.0577	0.0859	2.248	6.782	1.391
19	2.00	0	0.0577	0.1502	1.409	7.621	1.927

<sup>a</sup> Calcd.  $\alpha_0 = 0.22$ ,  $\alpha_1 = 0.47$ ,  $\alpha_2 = 0.29$ ,  $\alpha_3 = 0.03$ ,  $\bar{n} = 1.14$

<sup>b</sup> Calcd.  $\alpha_0 = 0.13$ ,  $\alpha_1 = 0.42$ ,  $\alpha_2 = 0.39$ ,  $\alpha_3 = 0.06$ ,  $\bar{n} = 1.38$

\* On leave from Department of Chemistry, Svetozar Markovic University, Radoja Domanovic'a 12,  
34000 Kragujevac, Yugoslavia.

is calculated from the expression

$$\bar{n} = (C_{a,n} - [\text{am}] + [\text{H}^+])/C_{N_1}$$

where  $C_x$  represents the stoichiometric concentration of the species  $X$ . In Fig. 1 the formation curves are




Fig. 1. Formation curves ( $\bar{n}$  vs  $p[ m]$ ) at 25° for the three nickel(II)-ethanolamines. Experimental and calculated values for nickel(II) mono- and diethanolamine in 0.5  $M$  (amH, Na)ClO<sub>4</sub> and 2  $M$  amHClO<sub>4</sub>, compared with the calculated curve for nickel(II)-triethanolamine in 0.5  $M$  and 2  $M$  teaHClO<sub>4</sub><sup>1</sup> and with the nickel(II)-ammonia system in 0.5  $M$  and 2  $M$  NH<sub>4</sub>NO<sub>3</sub> at 25°. Signs used for 2  $M$  amHClO<sub>4</sub>: O ( $C_{N_1} \sim 0.01-0.02 M$ ), ● ( $C_{N_1} \sim 0.04-0.1 M$ ), and □ ( $C_{N_1} \sim 0.005 M$ ). Signs for 0.5  $M$  amHClO<sub>4</sub>: □ ( $C_{N_1} \sim 0.01-0.02 M$ ), ▤ ( $C_{N_1} \sim 0.04 M$ ) and ▥ ( $C_{N_1} \sim 0.005 M$ ) and for 0.1  $M$  amHClO<sub>4</sub>, 0.4 NaClO<sub>4</sub>: Δ ( $C_{N_1} \sim 0.01-0.02 M$ ).

plotted for the nickel(II)-monoethanolamine (mea) and diethanolamine (dea) systems in 0.5  $M$  (amH, Na)ClO<sub>4</sub> and 2  $M$  amHClO<sub>4</sub> solutions. For purposes of comparison, the curves determined by Agarwala and Bjerrum are also drawn for the triethanolamine system and those for the nickel(II)-ammonia system in 0.5  $M$  and 2  $M$  NH<sub>4</sub>NO<sub>3</sub> at 25°. The ethanolammonium concentrations are varied in the 0.5  $M$  (amH, Na)ClO<sub>4</sub> solutions as seen from Table 1 and indicated by the signs of the points in Fig. 1. Contrary to the triethanolamine system<sup>2</sup>, the influence of changing the meaH<sup>+</sup> and deaH<sup>+</sup> concentrations is found to be negligible. A change in  $C_{N_1}$ , from 0.005 to ~0.1  $M$  also has no influence on the formation curves within the uncertainty of the experiments. It can, therefore, be concluded that the metal ammine formation in the Ni(II)-mea and Ni(II)-dea systems is not interfered by hydrolysis and polymerization reactions.

The full drawn curves in Fig. 1 are calculated on the basis of the estimated constants shown in Table 2. The constants determined by the Russian authors<sup>2,6,10</sup> are also shown for comparison. The values determined by Sychev and Gerbeleu for the Ni(II)-mea<sup>9</sup> and Ni(II)-tea<sup>10</sup> systems are in reasonably good agreement with our values apart from their value for  $K_3$  in the Ni(II)-tea system which should have been corrected for hydrolysis. On the other hand, the values presented by Sklonskaya and Karapet-yants<sup>9</sup> for all three ethanolamines are not reliable.

The amines are bound to the metal through the nitrogen atom but it is obvious that the alcohol groups also take part in the complex formation. The large values of the ratios between successive constants and the decreasing number of ligands taken up with increasing number of alcohol groups involved show directly that chelation plays a role. It is therefore reasonable to assume that Ni(meas)<sup>2+</sup> and Ni(deas)<sup>2+</sup> to some extent, are octahedral complexes with three chelate bound, respectively two tridentate bound ligands. The small tendency of these complexes to take up further ligands and of Nitea<sup>2+</sup> to take up a second ligand supports these assumptions. However, the coordination of the alcohol groups must be weak for it had no observable effect on the enthalpy changes. Sychev and

TABLE 2—THE DETERMINED STABILITY CONSTANTS FOR THE THREE NICKEL(II)-ETHANOLAMINE SYSTEMS AND THE PROTONATION CONSTANTS OF THE AMINES IN ETHANOLAMMONIUM SALT SOLUTIONS AT 25°

	$K_n = \frac{[\text{Ni}(\text{am})_n]}{[\text{Ni}(\text{am})_{n-1}][\text{am}]}$				$\beta_n = \frac{[\text{Ni}(\text{am})_n]}{[\text{Ni}][\text{am}]^n}$			
	0.4 <sup>a</sup>	Mea 0.5 <sup>a</sup>	2 <sup>a</sup> M	0.43 <sup>c</sup>	Dea 0.5 <sup>a</sup>	2 <sup>a</sup> M	0.5 <sup>d</sup>	Tea 0.5 <sup>b</sup>
$pK_{\text{amH}}$	—	9.54	9.80	9.09	8.93	9.32	—	7.90
$\log K_1$	3.06	3.12	3.32	3.31	2.60	3.00	2.27	2.85
$\log K_2$	2.46	2.56	2.78	2.13	1.87	2.27	0.82	0.14
$\log K_3$	1.43	1.80	2.00	1.42?	—	—	—	—
$\log K_4$	—	(0.32)	(0.40)	—	—	—	—	—
$\log \beta_1$	5.52	5.68	6.10	—	4.47	5.27	—	2.99
$\log \beta_2$	6.95	7.48	8.10	—	—	—	—	4.29
$\log \beta_3$	—	(7.80)	(8.50)	—	—	—	—	—

<sup>a</sup> Values determined in this paper.

<sup>b</sup> Values determined by Agarwala and Bjerrum<sup>1</sup> in 0.5  $M$  (teaH, Na)ClO<sub>4</sub> and 2  $M$  teaHClO<sub>4</sub>.

<sup>c</sup> Values determined by Sychev and Gerbeleu<sup>9</sup> in 0.4  $M$  (meaH, K)NO<sub>3</sub> at 25°.

<sup>d</sup> Values determined by Sychev, Gerbeleu and Migal<sup>10</sup> in 0.5  $M$  (teaH, K)NO<sub>3</sub> at 25°.

<sup>e</sup> Values determined by Sklonskaya and Karapet-yants<sup>9</sup> in 0.43  $M$  (deaH, K)NO<sub>3</sub> at 25°.

Gerbeleu<sup>9,10</sup> have determined the enthalpy changes in the Ni(II)-mea system and found for the uptake of the first three ligands  $-\Delta H_1=3.35$ ,  $-\Delta H_2=3.90$  and  $-\Delta H_3=2.60$  kcal/mol, and for the first ligand in the Ni(II)-tea system  $-\Delta H_1=3.86$  kcal/mol. These values are of the same order as the average value 3.5 kcal/mol for the uptake of an  $\text{NH}_3$ -molecule in the Ni(II),  $\text{NH}_3$  system<sup>11</sup>.

Finally it should be noticed that the influence of the ethanolammonium concentrations on  $pK_{amH}$  and the stability constants is unusually high and increases in the order  $\text{tea} > \text{dea} > \text{mea} > \text{NH}_3$  (cf. Fig. 1 and Table 2).

**Discussion of Ni(II)-mea spectra:** Fig. 2 shows the absorption ( $\epsilon$ ,  $\lambda$ )-curves in the visible range for Ni(II)-mea solutions in 2 M  $\text{meaHClO}_4$  (curves 4-7) with  $\bar{n}$  varying from 0 to 1.42. On the basis of these data the position of the absorption maximum




Fig. 2. Spectra ( $\epsilon$ ,  $\lambda$ ) of nickel(II)-monoethanolamine perchlorate solutions at 22-23°. The composition of the solutions are as follows

1.  $C_{Ni} = 0.0418$  M,  $C_{mea} = 15.29$  M (92%)
2.  $C_{Ni} = 0.0418$  M,  $C_{mea} = 5.32$  M
3.  $C_{Ni} = 0.0418$  M,  $C_{mea} = 1.33$  M
4. Sol. 7 in Table I.  $\bar{n} = 1.428$ .
5. Sol. 6 in Table I.  $\bar{n} = 1.145$
6.  $C_{meaH} = 2.00$ ,  $C_{Ni} = 0.1154$ ,  $C_{mea} = 0.0200$ ,  $\bar{n} = 0.173$ .
7.  $C_{meaH} = 2.00$ ,  $C_{Ni} = 0.1154$ ,  $pH \sim 2$ ,  $\bar{n} = 0$ .  
Estimated for  $\epsilon_1$  - - - - -

of the mono-amine complex is estimated to be  $\lambda_{max}(\epsilon_2) = 642$  nm. This is a blue shift of 18 nm compared to that of the aqua nickel(II) ion with  $\lambda_{max}(\epsilon_0) = 660$  nm. A blue shift of this magnitude agrees well with what is found in the Ni(II)-tea<sup>1</sup> and in the Ni(II)- $\text{NH}_3$  system<sup>9</sup>.

The curves 1-3 in Fig. 2 show the absorption spectra of aqueous monoethanolamine nickel(II) perchlorate solutions with  $C_{mea} = 15.29$ , 5.32 and 1.33 M/l, respectively. Solutions with  $C_{mea} = 10.64$  and 11.97 M/l were also measured but their absorption curves were so close to that of the limiting curve with  $\lambda_{max}$  at 595 nm (and 92 weight per cent of monoethanolamine) that they are not plotted in the figure. Measurements were also made of two solutions with  $C_{mea} \sim 10$  M/l and added strong base:  $C_{NaOH} = 0.04$  and 0.4 M/l. The first solution had practically the same  $\lambda_{max}$  and  $\epsilon_{max}$  as the limiting curve, but for the stronger basic solution a small red shift of  $\lambda_{max}$  to 605 nm and a decrease of  $\epsilon_{max}$  from 10.0 to 8.8 were observed. The blue shift of  $\lambda_{max}$  from the aqua nickel ion to  $\lambda_{max}$  of the limiting curve is therefore found to be  $660 - 595 \approx 65$  nm. From this estimate it can be concluded that at the most  $65/18 \approx 3.6$  amine groups can be coordinated to the nickel ion. In these solutions with  $pH > 12$  it is reasonable to assume that deprotonated species such as  $\text{Ni}(\text{mea})_3^-$  are dominating. In solutions of higher basicity, it is possible that the amine ligands are exchanged with hydroxyl ions. The small red shift observed when the added concentration of NaOH is increased from 0.04 to 0.4 M/l seems to support this assumption.

#### References

1. B. V. AGARWALA and J. BJERRUM, *Acta Chem. Scand.*, 1982, A 36, 439.
2. A. YA. SYCHEV and A. P. GERBELEU, *Russ. J. Inorg. Chem.*, 1962, 7, 138.
3. E. V. SKLENSKAYA and M. KH. KARAPET-YANTS, *Russ. J. Inorg. Chem.*, 1966, 11, 1478.
4. S. V. GORBACHEV, T. G. MARCHENKOVA and E. G. TIMOFEEVA, *Koord. Khim.*, 1977, 3, 802.
5. V. V. UDOVENKO and YU. S. DUECHINSKII, *Russ. J. Inorg. Chem.*, 1966, 11, 1481; 1967, 12, 517.
6. YU. S. DUECHINSKII, *Russ. J. Inorg. Chem.*, 1968, 13, 974.
7. G. J. GALKINA and E. G. TIMOFEEVA, *Russ. J. Inorg. Chem.*, 1969, 14, 1745.
8. L. ILICHEVA and J. BJERRUM, *Acta Chem. Scand.*, 1976, A 30, 343.
9. J. BJERRUM, "Metal Ammine Formation in Aqueous Solution", P. Haase and Son, 1941, reprinted 1957.
10. A. YA. SYCHEV, A. P. GERBELEU and P. K. MIGAL, *Russ. J. Inorg. Chem.*, 1963, 8, 1081.
11. I. POULSEN and J. BJERRUM, *Acta Chem. Scand.*, 1955, 9, 1407.

## The Rare Earths. Part—XCII: Chelating Tendencies of 1-Methoxy-2,4-pentanedione

DEAN F. MARTIN<sup>a</sup>, THERALD MOELLER<sup>b\*</sup> and WILLIAM J. RANDALL<sup>c</sup>

School of Chemical Sciences, University of Illinois, Urbana, Illinois, U.S.A.

Chelating tendencies of 1-methoxy-2,4-pentanedione toward trivalent lanthanide ions were measured in 50% (v/v) dioxane-water media, and thermodynamic formation constants were obtained. In addition, enthalpy values were obtained by thermometric titrations using the same systems. The data obtained support the interpretation of an expanded solvation sphere through the lanthanide series. The use of the mixed solvent system permitted third formation constants to be obtained without concomitant problems of precipitation, although the possibility of dioxane coordination in the solvent sphere exists. Relatively large values of entropy of formation for the overall chelation processes imply an increase in the hydration number from lanthanum through lutetium. Anomalies in chelating tendencies at gadolinium and erbium are difficult to explain unambiguously. The values may indicate a type of cross-over point at which solvent-metal and ligand-metal interactions result in a break in the apparent continuity of the ligand-metal process through the series.

MANY studies of the chelating tendencies of lanthanide ions have involved a single chelating agent associated with a single metal ion, e.g., lanthanide-aminepolycarboxylate chelates and studies of the chelating tendencies of  $\beta$ -diketones have been limited<sup>1</sup> despite the advantages that these systems may offer. The present study was initiated to permit comparison of the effects of oxygen-oxygen coordination versus oxygen-nitrogen coordination, to make a comparison of inductive and steric effects of various substituents (R, R' and R'') in  $\text{RCOCH(R')COR''}$  of the  $\beta$ -diketonate chelating agent.

Some experimental difficulties and advantages were anticipated. A mixed-solvent system was required, because of the insolubilities of the metal chelates,  $\text{Ln(RCOCH}_2\text{COR')}_3$ , in water. The use of dioxane-water systems, however, for obtaining thermodynamic formation constants has been well established<sup>1</sup>. In addition, the study of lanthanide-acetylacetonate complexes made by Fernelius and co-workers<sup>2</sup> indicated that complexes of reasonable stabilities could be obtained.

It was also evident that 1-methoxy-2,4-pentanedione could offer the advantage of reasonable stability plus enhanced solubilities. Finally, the possibility of obtaining three stepwise equilibrium constants was attractive for several obvious reasons.

The use of enthalpy titration data seemed advisable for evaluating  $\Delta H_n$ , the change in enthalpy associated with a given stepwise chelation process, because the equilibria were established sufficiently rapidly and because data were not available to

permit thermodynamic formation constants to be determined for dioxane-water media at temperatures other than 30°.

### Experimental

**Materials:** 1-Methoxy-2,4-pentanedione from a commercial source was fractionally distilled under vacuum (52°/1 mm Hg),  $n_D^{20}$  1.4590 obs; 1.4590 reported<sup>3</sup>. Perchlorate solutions: solutions of scandium, yttrium and lanthanide metal perchlorates were prepared from weighed quantities of oxides (99+ % purity) by treatment with stoichiometric amounts of perchloric acid (G. F. Smith Chemical Co.; diluted and standardized to 0.1000 M). All perchlorate salt solutions were standardized titrimetrically using xylenolorange as an indicator<sup>4</sup>. The usual precautions were taken in preparing dioxane and water<sup>4</sup>.

**Dissociation constants** were determined in 50% dioxane-water, using tetramethylammonium hydroxide, as described elsewhere<sup>1</sup>.

**Formation constants:** Titration solutions consisted of  $5 \times 10^{-3}$  M chelating agent and  $4 \times 10^{-4}$  M trivalent metal perchlorate in appropriate dioxane-water solutions to give 50% (v/v) contained in a four-necked titration flask immersed in a bath maintained at  $30.00 \pm 0.02^\circ$ . The procedure used in the titration is described elsewhere<sup>1,5,6</sup>.

**Enthalpy titrations:** The enthalpy titration system consisted of five components: (1) a constant-temperature system, a Pyrex ball jar constant-temperature bath contained within a 350-L constant-temperature water bath, which resulted in the inner

<sup>a</sup> Present Address: Chemical and Environmental Management Services (CHEMS) Center, Department of Chemistry, University of South Florida, Tampa, Florida, 33620, U.S.A.

<sup>b</sup> Present Address: Department of Chemistry, Arizona State University, Tempe, Arizona, 85287, U.S.A.

<sup>c</sup> Present Address: Department of Chemistry, Lewis and Clark College, Portland, Oregon, 97219, U.S.A.

bath being stabilized to within  $\pm 0.001^\circ$ ; (2) a titrant delivery system, which consisted of a Sargent model "C" constant-rate buret; (3) a titration cell, which consisted of a Dewar flask constructed from a 60/50 outer joint with a total volume of about 200 ml; (4) a heating circuit; and (5) a cell-temperature monitor system. Full details are provided elsewhere<sup>8</sup>.

The enthalpy titration involved a continuous-addition technique: a  $100.0 \pm 0.1$  ml sample of metal perchlorate and chelating agent in appropriate solvents (50 vol% dioxane-water) was placed in the cell and, following thermal equilibration, was treated by the continuous addition of titrant (1.0 M KOH). The temperature evolved was recorded on a strip chart as a thermogram, a time-dependent curve which represents the temperature of the calorimeter at any instant of time, relative to the initial temperature. A number of corrections and calibrations were made, including correction for the cooling effect due to entering solvent, calibration of the titration cell, calibration of the strip chart to temperature, evaluation of the heat capacities of the solvents, determination of the heat of ionization of the chelating agent, calculations of concentrations of the species initially and at a given time,  $t_1$ , correction of species distributions as a function of ionic strength and, finally, calculation of the enthalpies for the stepwise equilibria. The detailed descriptions of these treatments, together with the computer programs which effect the calculations of the heat of complex-ion formation, are presented elsewhere<sup>8</sup>.

## Results

**Thermodynamic parameters for 1-methoxy-2,4-pentanedione:** Typically, the  $pK_D$  value of a  $\beta$ -diketonate is a linear function of the mole fraction of dioxane ( $N_2$ ) in a dioxane-water solution, and the same was true in this study [ $pK_D = 7.36 \pm 0.11 + (10.72 \pm 0.43) N_2$ ]. A polynomial least-squares treatment gives a better fit for the data, but either plot shows the increase in  $pK_D$  with a decrease in the dipole moment of the solvent. At  $N_2 = 0.173$  (50 vol% dioxane), the values of the thermodynamic constants

are  $\Delta G^\circ = 13.20 \pm 0.01$  kcal/mole;  $\Delta H^\circ = 0.99 \pm 0.08$  kcal/mole; and  $\Delta S^\circ = -40.3 \pm 0.1$  e.u. at  $30.0 \pm 0.01^\circ$ . These values indicate that ionization of the chelating agent is primarily an entropy controlled process. Since ionization diminishes the entropy of the system, ionization is favored in higher dielectric solvents (lower values of  $N_2$ ).

Other observations support this contention. Kido and Fernelius<sup>7</sup> observed little change in  $\Delta H_{\text{ionization}}$  as a function of  $N_2$ . This and the observations of the present study indicate that the bonding energy differences remain fairly consistent with  $N_2$ .

Several structural implications also result from these parameters. First, the hydrogen ion must form nearly identical aggregations regardless of  $N_2$  in the range studied. Also, the bulk solvent aggregation must be substantially diminished as the mole fraction of dioxane increases. Finally, water molecules remain the principal coordinating solvent species, and the dioxane molecules primarily affect the bulk solution properties. The importance of this view in extrapolating to a metal ion system is evident. Another supporting observation: the heat capacity of 50% (v/v) dioxane-water was determined to be 0.75 cal/ml- $^\circ\text{C}$ , whereas the value of pure water is 1.0 cal/ml- $^\circ\text{C}$ , at  $30^\circ$ , which is interpreted as indicating less aggregation in the mixed-solvent medium.

## Formation constants for selected lanthanide ions in different dioxane-water mixtures:

Thermodynamic formation constants, as  $\log K_f$ , were evaluated at four different mole fractions of dioxane in dioxane-water mixtures. Pertinent results are listed in Table 1.

An ionic relationship proposed by Born [ $\log K = C(1 - 1/D)$ ] was tested using the data in Table 1 and deviations from linearity were observed for all plots when  $N_2$  is less than about 0.1, although the degree of non-linearity is not substantial. A substantial deviation in linearity implies that either the metal ion solvation does not remain constant from one solvent system to another or that covalency

TABLE 1—THERMODYNAMIC FORMATION CONSTANTS OF  $\text{La}^{3+}$ ,  $\text{Gd}^{3+}$  and  $\text{Lu}^{3+}$ -1-METHOXY-2,4-PENTANEDIONE CHELATES AT SELECTED  $N_2$  VALUES AT  $30.00 \pm 0.02^\circ$

$M^{3+}$	$N_2$	0.0825 (30%) <sup>b</sup>		0.1735 (50%) <sup>b</sup>		0.2805 (65%) <sup>b</sup>		0.3864 (75%) <sup>b</sup>	
		$\log K_f$	$R_f^a$	$\log K_f$	$R_f^a$	$\log K_f$	$R_f^a$	$\log K_f$	$R_f^a$
$\text{La}^{3+}$	1	6.191	0.712	7.419	0.779	8.804	0.825	10.004	0.838
	2	4.675	0.537	5.828	0.612	7.267	0.681	8.496	0.711
	3	3.866	0.444	4.662	0.490	5.819	0.545	6.990	0.585
$\text{Gd}^{3+}$	1	7.113	0.818	8.348	0.877	9.678	0.907	11.048	0.925
	2	5.456	0.627	6.595	0.693	8.037	0.753	9.394	0.787
	3	4.206	0.483	4.898	0.515	5.985	0.561	7.329	0.614
$\text{Lu}^{3+}$	1	7.354	0.845	8.536	0.897	9.747	0.912	11.271	0.944
	2	5.715	0.657	6.795	0.714	8.339	0.782	9.614	0.805
	3	4.328	0.497	5.025	0.528	6.326	0.593	7.623	0.638
$D$		51.38		33.85		21.77		14.68	

<sup>a</sup>  $R_f = \log K_f / pTK_f$ .

<sup>b</sup> (XX%) represents XX% (volume dioxane)/(volume dioxane + volume water).

<sup>c</sup> The symbol  $D$  represents the solvent dielectric constant of the solvent system given at the top of the column.

exists in the metal-to-ligand bonding. Considering that the degree of deviation is small, we are led to the conclusion that there may not be a substantial change in the inner coordination sphere of solvated lanthanide ions in dioxane-water mixtures as compared with water as a solvent. The data for  $\log K_s$  for gadolinium show a notably linear Born plot; but whether this indicates a remarkably different process in comparison with those for lanthanum or lutetium remains uncertain, considering the small deviation from linearity. These results also indicated that studies using 50% (v/v) dioxane-water would provide results that would be representative of most mixtures (with  $N_s$  above 0.1).

#### Thermodynamic constants for chelating tendencies of lanthanide ions :

Pertinent data are summarized in Tables 2-4. The results can be considered in order.

The values of  $\Delta G_f^\circ$  are plotted in Fig. 1 using the data from Table 2. When this is done, a distinct break appears at gadolinium for the first, second, and perhaps, the third chelation process. Also, such a plot reveals that  $\Delta G_f^\circ$  is anomalous for lanthanum; otherwise results are consistent with what others have found for other systems including the observation of a so-called "gadolinium break". In addition, the magnitude of the overall process,  $\Delta G_{1-3}$ , is similar to the values obtained for other lanthanide complexes, e.g., 25 to 28 kcal/mole for  $\text{La}^{3+}$ — $\text{Lu}^{3+}$  versus 22-28 kcal/mole for DCTA complexes<sup>20</sup>. It must be recognized, however, that formation constants of complexes of EDTA and DCTA were determined in 0.1 M  $\text{KNO}_3$ , whereas the data for the  $\beta$ -diketone (Table 2) were obtained for 50% dioxane-water.

A similar problem occurs when the chelating tendencies of 1-methoxy-2,4-pentanedione toward lanthanide metal ions are compared with those of 2,4-pentanedione. The former were evaluated for 50% dioxane-water and the latter<sup>20</sup> for dilute aqueous solutions at an ionic strength of 0.1. The available data clearly show the greater stabilities of the 1-methoxy-2,4-pentanedione complexes ( $\log \beta_s =$




Fig. 1. Gibbs free energy of formation,  $\Delta G_f^\circ$ , Kcal/mole, as a function of atomic number,  $Z$ , for 1-methoxy-2,4-pentanedione chelates of the lanthanides. The value of  $l$  is 1 for  $\bigcirc$ , 2 for  $\bullet$  and 3 for  $\odot$ . The position of yttrium in the series is indicated by the symbol  $\Delta$ . The size of the circles approximates the standard deviation of the value.

ca 20) relative to those of 2,4-pentanedione ( $\log \beta_s \approx \text{ca } 11-12$ )<sup>20</sup>. A more reasonable comparison may result if the  $pK_D$  values are compared: the values for  $N_s=0.173$  are 10.37 for 2,4-pentanedione<sup>10</sup> and 9.52 for 1-methoxy-2,4-pentanedione. If the values of  $\log K$  parallel the  $pK_D$  values for closely related  $\beta$ -diketones as has been observed previously<sup>21</sup>, then the complexes of 2,4-pentanedione should be somewhat more stable than those of 1-methoxy-2,4-pentanedione.

TABLE 2—FREE ENERGY OF FORMATION OF  $\text{Ln}^{3+}$ -1-METHOXY-2,4-PENTANEDIONE CHELATES IN 50.0 (v/v) % DIOXANE-WATER MEDIUM AT  $30.00 \pm 0.01^\circ$

Z	M <sup>3+</sup>	$-\Delta G_f^\circ$ Kcal/mole	$-\Delta G_f^\circ$ Kcal/mole	$-\Delta G_f^\circ$ Kcal/mole	$-\Delta G_{1,2}^\circ$ Kcal/mole	$-\Delta G_{1,2,3}^\circ$ Kcal/mole
39	Y <sup>3+</sup>	$11.62 \pm 0.02^a$	$9.16 \pm 0.01$	$6.74 \pm 0.03$	$20.78 \pm 0.03$	$27.52 \pm 0.04$
57	La <sup>3+</sup>	$10.28 \pm 0.01$	$8.07 \pm 0.05$	$6.40 \pm 0.13$	$18.35 \pm 0.05$	$24.75 \pm 0.14$
58	Ce <sup>3+</sup>	$10.59 \pm 0.02$	$8.58 \pm 0.06$	$6.90 \pm 0.15$	$19.17 \pm 0.06$	$26.07 \pm 0.16$
59	Pr <sup>3+</sup>	$10.71 \pm 0.04$	$8.81 \pm 0.05$	$6.90 \pm 0.20$	$19.53 \pm 0.06$	$26.43 \pm 0.21$
60	Nd <sup>3+</sup>	$10.86 \pm 0.04$	$8.97 \pm 0.05$	$7.00 \pm 0.17$	$19.83 \pm 0.07$	$26.83 \pm 0.19$
62	Sm <sup>3+</sup>	$11.37 \pm 0.02$	$9.17 \pm 0.02$	$6.85 \pm 0.09$	$20.55 \pm 0.03$	$27.40 \pm 0.10$
63	Eu <sup>3+</sup>	$11.50 \pm 0.07$	$9.29 \pm 0.01$	$6.96 \pm 0.04$	$20.79 \pm 0.07$	$27.75 \pm 0.08$
64	Gd <sup>3+</sup>	$11.52 \pm 0.02$	$9.13 \pm 0.01$	$6.78 \pm 0.03$	$20.65 \pm 0.02$	$27.43 \pm 0.03$
65	Tb <sup>3+</sup>	$11.67 \pm 0.02$	$9.27 \pm 0.01$	$6.87 \pm 0.02$	$20.94 \pm 0.02$	$27.80 \pm 0.03$
66	Dy <sup>3+</sup>	$11.69 \pm 0.02$	$9.22 \pm 0.01$	$6.78 \pm 0.02$	$20.91 \pm 0.02$	$27.69 \pm 0.03$
67	Ho <sup>3+</sup>	$11.69 \pm 0.02$	$9.24 \pm 0.01$	$6.83 \pm 0.10$	$20.93 \pm 0.03$	$27.76 \pm 0.10$
68	Er <sup>3+</sup>	$11.72 \pm 0.02$	$9.26 \pm 0.01$	$6.83 \pm 0.02$	$20.98 \pm 0.02$	$27.81 \pm 0.03$
69	Tm <sup>3+</sup>	$11.76 \pm 0.02$	$9.33 \pm 0.01$	$6.92 \pm 0.03$	$21.09 \pm 0.02$	$28.01 \pm 0.03$
70	Yb <sup>3+</sup>	$11.82 \pm 0.02$	$9.40 \pm 0.01$	$6.91 \pm 0.01$	$21.22 \pm 0.02$	$28.13 \pm 0.02$
71	Lu <sup>3+</sup>	$11.79 \pm 0.03$	$9.44 \pm 0.01$	$7.04 \pm 0.02$	$21.23 \pm 0.03$	$28.28 \pm 0.03$

<sup>a</sup> Standard deviation of value.



TABLE 3—ENTHALPY OF FORMATION OF  $\text{Ln}^{3+}$ -1-METHOXY-2,4-PENTANEDIONE CHELATES IN 50.0 (v/v) % DIOXANE-WATER MEDIUM AT  $30.00 \pm 0.01^\circ$ 

Z	M <sup>3+</sup>	$\Delta H_f^\circ$ Kcal/mole	$\Delta H_f^\circ$ Kcal/mole	$\Delta H_f^\circ$ Kcal/mole	$\Delta H_f^\circ$ Kcal/mole	$\Delta H_f^\circ$ Kcal/mole
39	Y <sup>3+</sup>	$2.03 \pm 0.6^a$	$-2.89 \pm 1.0$	$-0.46 \pm 0.8$	$0.86 \pm 1.2$	$-1.32 \pm 1.4$
57	La <sup>3+</sup>	$2.25 \pm 0.2$	$-1.85 \pm 0.4$	$-3.39 \pm 1.1$	$0.40 \pm 0.4$	$-3.00 \pm 1.2$
58	Ce <sup>3+</sup>	$2.31 \pm 0.1$	$-3.36 \pm 0.7$	$-1.23 \pm 2.0$	$-1.05 \pm 0.7$	$-2.28 \pm 2.1$
59	Pr <sup>3+</sup>	$2.38 \pm 0.1$	$-3.66 \pm 0.5$	$-1.34 \pm 1.3$	$-1.28 \pm 0.5$	$-2.62 \pm 1.4$
60	Nd <sup>3+</sup>	$1.69 \pm 0.2$	$-2.73 \pm 0.5$	$-2.12 \pm 1.3$	$-1.04 \pm 0.6$	$-3.16 \pm 1.4$
62	Sm <sup>3+</sup>	$0.58 \pm 0.1$	$-0.76 \pm 0.5$	$-4.14 \pm 1.5$	$-0.19 \pm 0.5$	$-4.33 \pm 1.5$
63	Eu <sup>3+</sup>	$2.61 \pm 0.3$	$-2.82 \pm 0.5$	$-2.51 \pm 0.7$	$-0.21 \pm 0.6$	$-2.72 \pm 1.0$
64	Gd <sup>3+</sup>	$2.75 \pm 0.4$	$-0.35 \pm 0.7$	$-4.00 \pm 0.6$	$2.40 \pm 0.8$	$-1.61 \pm 1.0$
65	Tb <sup>3+</sup>	$0.93 \pm 0.5$	$-1.78 \pm 1.0$	$0.58 \pm 0.8$	$-0.84 \pm 1.1$	$-1.42 \pm 1.4$
66	Dy <sup>3+</sup>	$2.39 \pm 0.3$	$-2.79 \pm 0.6$	$-1.39 \pm 0.5$	$0.40 \pm 0.7$	$-1.79 \pm 0.9$
67	Ho <sup>3+</sup>	$2.60 \pm 0.2$	$-3.26 \pm 0.3$	$-0.62 \pm 0.3$	$-0.66 \pm 0.3$	$-1.28 \pm 0.4$
68	Er <sup>3+</sup>	$-0.69 \pm 0.2$	$3.77 \pm 0.6$	$-6.07 \pm 1.0$	$3.08 \pm 0.6$	$-2.99 \pm 1.2$
69	Tm <sup>3+</sup>	$-0.14 \pm 0.5$	$1.18 \pm 0.9$	$-1.64 \pm 0.7$	$1.04 \pm 1.0$	$-0.60 \pm 1.2$
70	Yb <sup>3+</sup>	$1.42 \pm 0.5$	$0.10 \pm 0.9$	$-0.92 \pm 0.8$	$1.52 \pm 1.0$	$0.60 \pm 1.3$
71	Lu <sup>3+</sup>	$-0.99 \pm 0.4$	$2.63 \pm 0.8$	$-2.32 \pm 0.7$	$1.64 \pm 0.9$	$-0.68 \pm 1.1$

<sup>a</sup> Standard deviation of the value.TABLE 4—ENTROPY OF FORMATION OF  $\text{Ln}^{3+}$ -1-METHOXY-2,4-PENTANEDIONE CHELATES IN 50.0 (v/v) % DIOXANE-WATER MEDIUM AT  $30.00 \pm 0.01^\circ$ 

Z	M <sup>3+</sup>	$\Delta S_f^\circ$ E. U.	$\Delta S_f^\circ$ E. U.	$\Delta S_f^\circ$ E. U.	$\Delta S_f^\circ$ E. U.	$\Delta S_f^\circ$ E. U.
39	Y <sup>3+</sup>	$45.0 \pm 1.8^a$	$20.7 \pm 3.3$	$20.7 \pm 2.6$	$65.7 \pm 3.8$	$86.4 \pm 4.6$
57	La <sup>3+</sup>	$41.3 \pm 0.5$	$20.5 \pm 1.3$	$9.9 \pm 3.6$	$61.8 \pm 1.4$	$71.8 \pm 3.9$
58	Ce <sup>3+</sup>	$42.6 \pm 0.4$	$17.2 \pm 2.1$	$18.7 \pm 6.1$	$59.8 \pm 2.1$	$78.5 \pm 6.5$
59	Pr <sup>3+</sup>	$43.2 \pm 0.3$	$17.0 \pm 1.6$	$18.4 \pm 4.2$	$60.2 \pm 1.6$	$78.5 \pm 4.5$
60	Nd <sup>3+</sup>	$41.4 \pm 0.7$	$20.6 \pm 1.7$	$16.1 \pm 4.2$	$62.0 \pm 1.8$	$78.1 \pm 4.6$
62	Sm <sup>3+</sup>	$39.4 \pm 0.4$	$27.7 \pm 1.6$	$8.9 \pm 4.7$	$67.2 \pm 1.6$	$76.1 \pm 4.9$
63	Eu <sup>3+</sup>	$46.6 \pm 0.9$	$21.3 \pm 1.9$	$14.7 \pm 2.2$	$67.9 \pm 2.1$	$82.5 \pm 3.1$
64	Gd <sup>3+</sup>	$47.1 \pm 1.2$	$28.9 \pm 2.2$	$9.2 \pm 2.0$	$76.0 \pm 2.5$	$85.2 \pm 3.1$
65	Tb <sup>3+</sup>	$41.6 \pm 1.7$	$24.7 \pm 3.2$	$20.7 \pm 2.5$	$66.3 \pm 3.6$	$87.0 \pm 4.4$
66	Dy <sup>3+</sup>	$46.4 \pm 1.0$	$21.2 \pm 1.9$	$17.8 \pm 1.6$	$67.7 \pm 2.2$	$85.4 \pm 2.7$
67	Ho <sup>3+</sup>	$47.1 \pm 0.5$	$19.7 \pm 0.9$	$20.5 \pm 0.9$	$66.9 \pm 1.1$	$87.3 \pm 1.4$
68	Er <sup>3+</sup>	$36.4 \pm 0.7$	$43.0 \pm 1.8$	$2.5 \pm 3.3$	$79.4 \pm 1.9$	$81.9 \pm 3.8$
69	Tm <sup>3+</sup>	$38.3 \pm 1.6$	$34.7 \pm 2.8$	$17.4 \pm 2.2$	$73.0 \pm 3.2$	$90.4 \pm 3.9$
70	Yb <sup>3+</sup>	$43.7 \pm 1.5$	$31.3 \pm 2.8$	$19.8 \pm 2.5$	$75.0 \pm 3.2$	$94.8 \pm 4.1$
71	Lu <sup>3+</sup>	$35.6 \pm 1.4$	$39.8 \pm 2.5$	$15.6 \pm 2.3$	$75.5 \pm 2.8$	$91.0 \pm 2.8$

<sup>a</sup> Standard deviation of the value.

Changes in the enthalpy and entropy of complex formation when plotted as a function of atomic number of trivalent lanthanide show a complex pattern, Fig. 2-4. The values for  $\Delta H_f^\circ$  and  $\Delta H_s^\circ$  decrease from Z=57 to 71 with notable breaks (minima) at Z=62-63, 64-65 and 68. The values of  $\Delta H_s^\circ$  show, in contrast, a general increase from Z=57-71 with notable deviations at Z=63 (minimum) and 68 (maximum). The significant common feature is the direct relationship between the change in enthalpy and change in entropy. Both tend to show parallel increases in the variations with atomic number of the lanthanide metal ion.

The latter observation is worth stressing that an interpretation may be made in terms of the structure of the reacting species.

#### Discussion

This study was the first application of a continuous addition technique to a lanthanide-ligand system in a mixed solvent system which permitted truly thermodynamic constants to be obtained. Although incremental addition techniques may be more accurate, the continuous addition technique affords the advantages of rapidity and convenience.

The chief problems, apart from experimental design, were the computations of species distributions as a function of addition of titrant. These were solved through the aid of appropriate programs for high-speed computers<sup>8</sup>.

The data presented here support an interpretation of an expanded solvation sphere through the lanthanide series. The nature of the solvation sphere is open to interpretation, owing to the mixed solvent system used, but it appears that dioxane has a greater role in the deaggregation of water molecules than as an actual solvation participant. Data obtained in this study, together with the data obtained by Kido and Fernelius<sup>9</sup>, amply support this view.

Anomalies in chelating tendencies at gadolinium and at erbium are still difficult to explain in an unambiguous manner. The anomalies may constitute a type of cross-over point at which the variations in solvent-metal and ligand-metal interactions result in a break in the ligand metal bonding process through the series. For example, if the  $\beta$ -diketone changes from terdentate to bidentate near gadolinium and erbium in the lanthanide series, then the observed entropy anomaly would be understandable; a




Fig. 2. Thermodynamic parameters,  $\Delta G^\circ_1$ ,  $\Delta H^\circ_1$ ,  $\Delta S^\circ_1$ ,  $\Delta G^\circ_1$ ,  $\Delta H^\circ_1$ ,  $\Delta S^\circ_1$ , Kcal/mole, E. U., as a function of atomic number,  $Z$ , for the first step of chelate formation for the lanthanide-1-methoxy-2,4-pentanedione system. If the standard deviation of the value exceeds the representative circle, it is indicated by a vertical bar. The position of yttrium in the series is represented by the symbol  $\Delta$ .

decrease in the entropy of chelation should result in a decrease in the enthalpy of chelation in as much as the bond not formed would involve the other oxygen atom of the ligand. There is evidence for this type of non-involvement in the complexes of lanthanides with pyrimidone<sup>12</sup>. With this system, chelation involves an amine nitrogen atom plus one ring nitrogen atom both, not the other. The second ring nitrogen atom presumably does not bond for steric reasons; the effect of solvent system was implied though not delineated<sup>13</sup>.

Possibly, higher coordination or solvation must be invoked to account for the small differences in the chelating tendencies of 1-methoxy-2,4-pentanedionate with trivalent lanthanides. If a solvent species is not held tenaciously in the second or third solvation spheres, the removal of this species should have less impact on macrochemical observations (e.g., formation constant, change in entropy, change in enthalpy) than the removal of the same solvent species from the first coordination sphere. The logic of this statement derives from the fact that  $\Delta G^\circ$ ,  $\Delta S^\circ$  and  $\Delta H^\circ$  are state functions that are subject to time averaging if a rapid exchange in the initial and final states exists. A more labile species possesses more energy ( $S^\circ$  initial) and is held less tenaciously (less  $H^\circ$  initial); thus the overall-state functions  $\Delta G^\circ$ ,  $\Delta S^\circ$  and  $\Delta H^\circ$  of chelation are less affected




Fig. 3. Thermodynamic parameters,  $\Delta G^\circ_{1,2}$ ,  $\Delta H^\circ_{1,2}$ ,  $\Delta S^\circ_{1,2}$ ,  $\Delta G^\circ_{1,2}$ ,  $\Delta H^\circ_{1,2}$ ,  $\Delta S^\circ_{1,2}$ , Kcal/mole, E. U., as a function of atomic number,  $Z$ , for the first and second steps of chelate formation for the lanthanide-1-methoxy-2,4-pentanedione system. If the standard deviation of the value exceeds the size of the representative circle, it is indicated by a vertical bar. The position of yttrium in the series is represented by the symbol  $\Delta$ .

ted by species in the second and third solvation spheres than those in the first sphere.

The results of this study, more specifically, are consistent with two processes (1) a decrease in the first solvation sphere around gadolinium and (2) an increased solvation of other lanthanide ions. The former process has been proposed and supported by Hoard<sup>14</sup> and by Grenthe<sup>15</sup>; the second by Padova<sup>16</sup>. The hypothesis that the coordination sphere is drastically disrupted by the first chelation process is supported by large values of  $\Delta S_1$  and the large positive values of  $\Delta H_1$ .

The final delineation of the solution structure of lanthanide ions may be completed through the use of several methods. Investigation of activity data for these ions in various solvents offers promise<sup>17</sup>. Another approach may be the use of radiation diffraction techniques in very concentrated solutions<sup>18</sup>. In any event, equilibrium data will contribute to the ultimate solution of the gadolinium break by pointing the way to more structurally oriented techniques. The fact that the observations made in this study support prevalent theories of coordination number change suggests that the true




Fig. 4. Thermodynamic parameters,  $\Delta G^\circ_{1,2,3}$ ,  $\Delta H^\circ_{1,2,3}$ ,  $\Delta S^\circ_{1,2,3}$ , Kcal/mole;  $\Delta H^\circ_{1,2,3}$ ,  $\Delta S^\circ_{1,2,3}$ , E. U., as a function of atomic number,  $Z$ , for the first, second and third steps of chelate formation for the lanthanide-1-methoxy-2,4-pentanedione system. If the standard deviation of the value exceeds the size of the representative circle, it is indicated by a vertical bar. The position of yttrium in the series is represented by the symbol  $\Delta$ .

interpretation is probably a synthesis of the two. The method used in this study is shown to be valid for a solvent system other than water, and for this the thermodynamic properties of the lanthanides may be investigated in a variety of closely related solvent systems with varying dielectric constants. This approach should permit the ultimate evaluation of the activity data needed to infer structural characteristics.

Ultimately, the problem of the gadolinium break and other apparent anomalies may be more a problem of the structure of water than a problem of the exact coordination tendencies of the lanthanides.

This possibility awaits the investigations of systems that involve much less hydrogen bonding and that are less polar than water. The present study indicated the direction and some of the methods that these studies may take.

#### Acknowledgement

One of the authors (W. J. R.) gratefully acknowledges two NSF Summer Fellowships, an August Kock Fellowship in Chemistry (sponsored by the Victor Chemical Company) and a Monsanto Chemical Fellowship in Chemistry.

#### References

1. D. E. GOLDBERG, *J. Chem. Educ.*, 1962, 39, 328.
2. a) I. GRENTHE and W. C. FERNELIUS, *J. Amer. Chem. Soc.*, 1960, 82, 6258.  
b) R. M. IZATT, W. C. FERNELIUS, C. H. HASS, Jr. and B. P. BLOCK, *J. Phys. Chem.*, 1955, 59, 170.
3. M. RENARD and A. MAGUINAY, *Bull. Soc. Chim. Belg.*, 1946, 55, 98.
4. a) A. J. BERNARD, Jr., W. C. BROAD and H. FLASHKA, *Chemist Analyst*, 1957, 46, 18.  
b) J. KINNENFEN and B. WENNERSTRAND, *Chemist Analyst*, 1957, 46, 92.  
c) J. KORBL and R. FRIBIL, *Chemist Analyst*, 1957, 45, 102.
5. W. J. RANDALL, Doctoral Dissertation, 1969, University of Illinois, Urbana, Illinois, U.S.A.
6. W. J. RANDALL, D. F. MARTIN and T. MOELLER, *Proc. Chem. Soc. (London)*, 1961, 340.
7. H. KIDO and W. C. FERNELIUS, *J. Phys. Chem.*, 1961, 65, 574.
8. DCTA = *trans*-1, 2-diaminocyclohexane-*N,N'*-tetra-acetic acid.
9. T. MOELLER and F. M. HSEU, *J. Inorg. Nuclear Chem.*, 1962, 24, 1635.
10. B. B. MARTIN and D. F. MARTIN, *J. Inorg. Nuclear Chem.*, 1975, 37, 1079.
11. I. G. VAN UITERT and W. C. FERNELIUS, *J. Amer. Chem. Soc.*, 1953, 75, 3862.
12. L. J. SAURO and T. MOELLER, *J. Inorg. Nuclear Chem.*, 1968, 30, 953.
13. a) J. L. HOARD, B. K. LEE and M. D. LIND, *J. Amer. Chem. Soc.*, 1965, 87, 1612.  
b) M. D. LIND, B. K. LEE and J. L. HOARD, *J. Amer. Chem. Soc.*, 1965, 87, 1911.
14. I. GRENTHE, *Acta Chem. Scand.*, 1963, 17, 2101, 2487, 1964, 18, 283, 293.
15. J. PADOVA, *J. Phys. Chem.*, 1967, 71, 2347.
16. R. A. ROBINSON and R. H. STOKES, "Electrolyte Solutions", 2nd Edn., Butterworths, London, 1959, p. 246.
17. R. D. LARSEN and G. H. BROWN, *J. Phys. Chem.*, 1964, 68, 3060.

# Coordination of Al(III), Be(II) and Cu(II) Ions with 1,7-Dihydroxy-4-sulfo-2-naphthoic and 3,5-Dihydroxy-7-sulfo-2-naphthoic Acids in Aqueous Sodium Perchlorate Medium

LAURI H. J. LAJUNEN

Department of Chemistry, University of Oulu, SF-90570 Oulu 57, Finland

The aluminium(III), beryllium(II) and copper(II) complex formation of sodium 1,7-dihydroxy-4-sulfonato-2-naphthoic and sodium 3,5-dihydroxy-7-sulfonato-2-naphthoic acids,  $\text{Na}^+\text{H}_2\text{L}^-$ , has been studied in aqueous solution at ionic strength 0.5 ( $\text{NaClO}_4$  as main electrolyte) and  $25.0 \pm 0.1^\circ$  by means of potentiometric pH titrations. The protonation of the ligand anions has been investigated by standard spectrophotometric and potentiometric methods under the same conditions.

In the metal-ligand equilibrium systems, the experimental data can be explained with the formation of the complexes  $\text{MHL}^-$ ,  $\text{ML}_2^{2-}$ ,  $\text{MH}_2\text{L}^-$ ,  $\text{MHL}_2^{2-}$  and  $\text{ML}_3^{3-}$  ( $\text{M} = \text{Cu}$  or  $\text{Be}$ ), and  $\text{AlHL}$ ,  $\text{AlL}^-$ ,  $\text{AlHL}_2^{2-}$ ,  $\text{AlL}_2^{2-}$  and  $\text{AlL}_3^{3-}$  when an excess of the ligand is present and  $\text{pH} < 9$ . Polynuclear complex compounds were not found in detectable amounts in potentiometric titrations. However, this might be only due to the experimental conditions, since accurate potential readings were available only with an excess of the ligand in the solutions to be titrated.

**POTENTIOMETRIC** and spectrophotometric studies on the complexes formed between beryllium(II), copper(II) and aluminium(III) and a number of aromatic sulfo-substituted *o*-hydroxy-carboxylic acids have been reported in our previous papers<sup>1-7</sup>. All the previous ligands have been mono- or disulfonic acid derivatives of salicylic, 1-hydroxy-2-naphthoic or 3-hydroxy-2-naphthoic acids, thus containing one hydroxyl group and one carboxyl group in *ortho*-positions to each other, and one or two sulfonato groups. 1,7-Dihydroxy-4-sulfo-2-naphthoic and 3,5-dihydroxy-7-sulfo-2-naphthoic acids are new reagents for investigation of metal complex formation and the number of hydroxyl groups is the main difference between these and the compounds studied earlier. The present investigation was undertaken to determine the composition and stability of the species formed in the equilibrium system:  $\text{H}^+$ -ligand,  $\text{Be}^{2+}$ -ligand,  $\text{Cu}^{2+}$ -ligand and  $\text{Al}^{3+}$ -ligand (where ligand is either 1,7-dihydroxy-4-sulfonato-2-naphthoic acid or 3,5-dihydroxy-7-sulfonato-2-naphthoic acid anion). A comparison of the results obtained with 1-hydroxy-4-sulfo-2-naphthoic, 1-hydroxy-7-sulfo-2-naphthoic, 1-hydroxy-4, 7-disulfo-2-naphthoic, 3-hydroxy-4-sulfo-2-naphthoic, 3-hydroxy-5-sulfo-2-naphthoic, 3-hydroxy-7-sulfo-2-naphthoic and 3-hydroxy-5,7-disulfo-2-naphthoic acids permits a discussion of the effects of the "lone" hydroxyl group (the hydroxyl group without neighbouring substituents) on the protonation and metal complex formation of the salicylic-type ligands of the naphthalene series. The stability constants of  $\text{Be}^{2+}$ ,  $\text{Cu}^{2+}$  and  $\text{Al}^{3+}$  com-

plexes with 1,7-dihydroxy-4-sulfo-2-naphthoic acid have been reported in an earlier paper<sup>8</sup>.

The experimental methods used in this investigation were the same as described in the earlier studies, i.e. standard potentiometric and spectrophotometric methods. All experiments were performed in a medium of ionic strength 0.5 *M*, with sodium perchlorate as the neutral salt. The temperature was  $25.0 \pm 0.1^\circ$ .

## Notations:

1,7-Dihydroxy-4-sulfonato-2-naphthoic acid and 3,5-dihydroxy-7-sulfonato-2-naphthoic acid anions  $[\text{C}_{10}\text{H}_6\text{SO}_3(\text{OH})_2\text{COOH}]^-$  are written as  $\text{H}_2\text{L}^-$ .  $C_M$ ,  $C_H$  and  $C_L$  denote the total concentrations of metal, free and dissociable hydrogen ions, and ligand anion, respectively.  $[\text{M}]$ ,  $[\text{H}^+]$  and  $[\text{L}]$  denote the concentrations of free metal ion, hydrogen ion and ligand anion respectively.

$\beta_{q,p,r}$  is the overall stability constant for the complex  $\text{M}_q\text{H}_p\text{L}_r$ , defined as

$$\beta_{q,p,r} = [\text{M}_q\text{H}_p\text{L}_r] / [\text{M}]^q [\text{H}]^p [\text{L}]^r \quad \dots (1)$$

where  $q \geq 0$ ,  $p \geq 0$ ,  $r \geq 0$ , and  $q + p + r \geq 2$ .

$$\bar{n}_H = (C_H - [\text{H}^+] + [\text{OH}^-]) / C_L \quad \dots (2)$$

$$\bar{n} = (C_L - \sum_{i=0}^{\infty} [\text{H}_i\text{L}]) / C_M \quad \dots (3)$$


$\bar{n}_H$  = the mean number of hydrogen ions bound per ligand anion, and

$\bar{n}$  = the mean number of ligand anions bound per metal ion.

## Experimental

**Reagents:** Sodium 1,7-dihydroxy-4-sulfonato-2-naphthoic and sodium 3,5-dihydroxy-7-sulfonato-2-naphthoic acids were prepared on alkali fusion from 1-hydroxy-4,7-disulfo-2-naphthoic acid and 1-hydroxy-5,7-disulfo-2-naphthoic acid, respectively. The purity of the compounds was checked by  $^1\text{H}$  and  $^{13}\text{C}$  nmr spectrometry.

**Potentiometric measurements:** The emf ( $E$ ) of galvanic cell of the following type was measured:



The system was calibrated before each titration by measuring the emf ( $E_R$ ) when the titration vessel contained a solution of known free hydrogen ion concentration,  $[\text{H}^+]_R$ . The unknown hydrogen ion concentration,  $[\text{H}^+]$ , was then calculated from the equation:

$$-2.303 RT/F \log ([\text{H}^+]/[\text{H}^+]_R) = (E_R - E) - (E - E'_j) \quad (4)$$

where  $R=8.314 \text{ JK}^{-1}\text{mol}^{-1}$ ,  $T=298.15 \text{ K}$  and  $F=96487 \text{ C mol}^{-1}$ .  $E'_j$  and  $E_j$  are the liquid junction potentials. The liquid junction potentials depend mainly on the free hydrogen ion concentration in the solutions, and  $E_j$  is then a linear function of  $\text{H}^+/\{E_j([\text{H}^+)] - j([\text{H}^+])\}$ , where  $j$  is a constant).

The potentiometric measurements were carried out with a Radiometer digital titration system DTS 533, consisting of an autoburette ABU 13 or 80, a pH meter, PHM 64, and a digital titrator, TTT 61, with an equal increment accessory constructed in his laboratory<sup>9</sup>.

The protonation constants of the ligand anions were determined in solutions without any metal present. In these measurements  $C_L$  was kept constant and  $C_H$  was varied by adding NaOH or  $\text{HClO}_4$  to the solution with different  $C_L : C_H$  ratios. The experimental data for evaluating the protonation constants consist of seven different emf titrations for each ligand acid, where  $C_L$  and  $-\log [\text{H}^+]$  varied between 0.001 and 0.03 M, and 2.3 and 12, respectively.

The stabilities of the beryllium(II), aluminium(III) and copper(II) complexes of 1,7-dihydroxy-4-sulfo-2-naphthoic and 3,5-dihydroxy-7-sulfo-2-naphthoic acids were determined by measuring the emf values in galvanic cells of the kind described above. During the titrations the ratio  $C_L : C_M$  was kept constant and  $C_H$  was varied by adding NaOH. The concentrations  $C_M$  and  $C_L$  in the starting solutions and the  $-\log [\text{H}^+]$  ranges for the  $\text{Be}^{2+}$ ,  $\text{Al}^{3+}$  and  $\text{Cu}^{2+}$  systems with 3,5-dihydroxy-7-sulfo-2-naphthoic acid are given in Table 1.

**Spectrophotometric measurements:** A Pye Unicam SP 8-100 UV-vis spectrophotometer, equipped with a 10 mm autocell and a superimpose accessory was used for the purpose. The absorbance readings were taken in the wavelength range 300–

TABLE 1—NUMBER OF POTENTIAL READINGS, INITIAL CONCENTRATIONS,  $C_M$  AND  $C_L$ , AND THE  $-\log [\text{H}^+]$  RANGES FOR THE TITRATIONS CARRIED OUT FOR EVALUATING THE STABILITY CONSTANTS OF THE BERYLLIUM(II), ALUMINIUM(III) AND COPPER(II) 3,5 DIHYDROXY-7-SULFONATO-2-NAPHTHOIC ACID COMPLEXES

Expt.	No of readings	Metal	$C_M/M$	$C_L/M$	$\log [\text{H}^+]$ range
1	47	Be	0.00096	0.0015	1.21–9.49
2	55	"	0.00096	0.00123	3.20–8.26
3	54	"	0.00096	0.00545	3.20–8.06
4	38	"	0.00192	0.00123	3.16–6.34
5	44	"	0.00192	0.00538	3.11–7.79
6	34	"	0.00184	0.00539	3.07–6.09
7	58	"	0.00384	0.02150	3.09–8.21
8	36	Al	0.00097	0.00330	3.10–6.03
9	44	"	0.00097	0.00550	3.10–8.42
10	57	"	0.00097	0.00770	3.13–8.13
11	47	"	0.00194	0.00704	3.07–8.07
12	53	"	0.00194	0.01408	3.07–8.21
13	58	"	0.00194	0.02816	3.04–8.11
14	57	"	0.00388	0.02820	3.00–8.07
15	33	Cu	0.00099	0.00218	3.18–9.98
16	41	"	0.00099	0.00327	3.40–9.08
17	45	"	0.00099	0.00545	3.44–8.25
18	51	"	0.00149	0.00545	3.41–8.15
19	55	"	0.00200	0.00545	3.36–8.91
20	53	"	0.00399	0.01090	3.32–8.75
21	55	"	0.00399	0.02180	3.00–8.80

420 nm with an interval of 5 nm.  $C_L$  was varied in these measurements between 0.00005 and 0.0003 M. In evaluating the protonation constants of the ligand anion, altogether 36 test solutions were prepared with varying pH values ( $2 < -\log [\text{H}^+] < 13.5$ ) for each  $\text{H}^+$ -ligand system.

**Calculations:** The equilibrium constants were calculated as overall stability constants (Equation 1) with the programme SCOGS<sup>10</sup> from the potentiometric data and with the programme SQUAD<sup>11</sup> from the spectrophotometric (absorbance-pH) data on a Univac 1100/20 computer.

## Results and Discussion

**The proton-ligand systems:** The search of the potentiometric data was initiated by drawing the




Fig. 1. Experimental (points) and calculated (solid line)  $\bar{n}_H$  values vs  $-\log [\text{H}^+]$  for 3,5-dihydroxy-7-sulfo-2-naphthoic acid at  $I=0.5$  ( $\text{NaClO}_4$ ) and  $t=25^\circ$ .

$\bar{n}_H$  vs  $(-\log [H^+])$  plots for both  $H_2L$ -ligand systems (Fig. 1). It can be seen from the figure that the  $\bar{n}_H$   $(-\log [H^+])$  function is independent of  $C_L$ , which would indicate that only a series of monomeric  $H_2L$  species is formed. These plots further suggest that these species are  $H_2L^-$ ,  $H_2L^{2-}$ ,  $HL^{3-}$  and  $L^{4-}$ , because the  $\bar{n}_H$  values are all between 2.4 and 0.9 and 2.8 and 0.7, respectively, for 1,7-dihydroxy-4-

sulfo-2-naphthoic acid and 3,5-dihydroxy-7-sulfo-2-naphthoic acid. A least-squares refinement of the potentiometric data gave the values of the protonation constants as shown in Table 2.

Fig. 2 and 3 show the uv-vis absorption spectra of 1,7-dihydroxy-4-sulfo-2-naphthoic and 3,5-dihydroxy-7-sulfo-2-naphthoic acids at various pH values

TABLE 2—THE PROTONATION CONSTANTS OF 3,5-DIHYDROXY-7-SULFO-2-NAPHTHOIC (1) AND 1,7-DIHYDROXY-4-SULFO-2-NAPHTHOIC (2) ACIDS AT  $I=0.5$  ( $NaClO_4$ ) AND  $25^\circ$ . THE QUOTED ERRORS ARE THREE TIMES THE STANDARD DEVIATIONS  $k_{0.2,1} = K(HL^{3-} + H^+ = H_2L^{2-})$  AND  $k_{0.3,1} = K(H_2L^{2-} + H^+ = H_2L^-)$ ,  $gl$  = POTENTIOMETRIC METHOD AND  $sp$  = SPECTROPHOTOMETRIC METHOD

Ligand/ method	$\log \beta_{0.1,1}$	$\log \beta_{0.2,1}$	$\log \beta_{0.3,1}$	$\log k_{0.2,1}$	$\log k_{0.3,1}$	Refs.
(1)/ <i>gl</i>	$12.355 \pm 0.015$	$20.809 \pm 0.018$	$23.314 \pm 0.003$	8.45	2.50	This work
(1)/ <i>sp</i>	$12.374 \pm 0.021$	$20.745 \pm 0.024$	$23.268 \pm 0.012$	8.37	2.52	"
(2)/ <i>gl</i>	$11.93 \pm 0.10$	$20.806 \pm 0.010$	$23.469 \pm 0.007$	8.88	2.66	"
(2)/ <i>sp</i>	$12.254 \pm 0.050$	$21.064 \pm 0.010$	$23.748 \pm 0.006$	8.81	2.68	8




Fig. 2. UV-vis absorption spectra of 1,7-dihydroxy-4-sulfo-2-naphthoic acid at various pH values between 2 and 13 ( $C_L=0.0002$  M) at  $I=0.5$  ( $NaClO_4$ ) and  $t=25^\circ$ .

between 2 and 13. As can be seen, there are three distinct pH regions displaying different patterns of change in the absorption spectra of the ligand acids: (1) about  $2 < pH < 5$ , (2)  $5 < pH < 10$  and  $pH > 10$ . In both systems isosbestic points appear at distinct pH regions, which also suggest that three different protonation reactions take place in the pH range studied. Spectral data for the ligand anions studied are compiled in Table 3, and the protonation constants, obtained spectrophotometrically in Table 2.

Comparison of the protonation constants obtained potentiometrically and spectrophotometrically shows that the values of each constant for 3,5-dihydroxy-7-sulfo-2-naphthoic acid and the values of the second and third protonation constants for 1,7-dihydroxy-4-sulfo-2-naphthoic acid are in fair agreement with each other, whereas the  $\log \beta_{0.1,1}$  value for 1,7-dihydroxy-4-sulfo-2-naphthoic acid evaluated potentiometrically is about 0.3 log units lower than that determined spectrophotometrically. Because the first protonation reaction takes place in very alkaline solutions, the spectrophotometric method (when buffer solutions are used) is more reliable than the potentiometric method




Fig. 3. UV-vis absorption spectra of 3,5-dihydroxy-7-sulfo-2-naphthoic acid at various pH values between 1 and 13.2 (A and B:  $C_L=0.000226$  M and C:  $C_L=0.000113$  M) at  $I=0.5$  ( $NaClO_4$ ) and  $t=25^\circ$ .

TABLE 3—THE SPECTRAL DATA FOR 1,7-DIHYDROXY-4-SULFO-2-NAPHTHOIC AND 3,5-DIHYDROXY-7-SULFO-2-NAPHTHOIC ACIDS IN AN AQUEOUS SOLUTION AT 25°


Species	$\lambda_{max}/nm$	$\epsilon^{max}/cm^{-1}M^{-1}$	Isosbestic points/nm
1,7-Dihydroxy-4-sulfo-2-naphthoic acid			
$H_2L^-$	358.5	3 840	} 358 and 392
$H_2L^{2-}$	336.5	4 000	
	346.5	4 040	} 314 and 354
$HL^{3-}$	360.0	3 400	
$L^{4-}$	359.0	4 000	
3,5-Dihydroxy-7-sulfo-2-naphthoic acid			
$H_2L^-$	364.5	1 860	} 360.0
$H_2L^{2-}$	355.0	1 850	
$HL^{3-}$	336.0	3 090	} 309.5
$L^{4-}$	314.0	5 800	
	334.0	5 700	} 381.0

(when the glass electrode is used). Hence the value obtained spectrophotometrically for  $\log \beta_{0.1,1}$  for 1,7-dihydroxy-4-sulfo-2-naphthoic acid was used in the calculations of the stability constants of the metal complexes.

The present ligands seem to be weaker as acids with respect to the neighbouring carboxyl and hydroxyl groups than the various mono- and disulfonate derivatives of 1- and 3-hydroxy-2-naphthoic acids studied earlier when the difference between the ionic strengths in the determinations has been taken into account<sup>1-9</sup>. Further, it can be noted that the protonation constants of the hydroxyl groups at carbons C-7 and C-4 are about the same as those of 1- and 2-naphtholsulfonates<sup>12</sup>. It is also worth adding that none of the studied sulfonated hydroxycarboxylic acids, including the present dihydroxy derivatives, dimerizes within the available concentration limits.

3,5-Dihydroxy-7-sulfo-2-naphthoic acid is a stronger acid than 1,7-dihydroxy-4-sulfo-2-naphthoic acid with respect to the "lonesome" hydroxyl group as well as the carboxyl group, whereas the acidity of the other hydroxyl group seems to be the reverse.

**The metal-ligand systems:** The search for the complex species in the different metal-ligand systems was begun as usual by drawing the Bjerrum plots,  $\bar{n}=f(-\log[L])$ , for each system. As can be seen from Fig. 4,  $\bar{n}$  is not only a function of  $-\log[L]$  for the copper-ligand equilibrium system, but depends

Fig. 4. Part of the experimental data presented as  $\bar{n}(-\log [L])$  curves for copper(II)-1,7-dihydroxy-4-sulfo-2-naphthoic acid equilibrium system.

as well on  $C_L$ . Thus, the formation of the complexes  $MH_pL_r$  ( $p \neq 0$ ) must be taken into consideration. The same observation was made for the other equilibrium systems. The highest experimental  $\bar{n}$  values for the beryllium or copper, and aluminium systems were under 2 and 3, respectively, indicating that complexes with at least two ligands per beryllium or copper ion and three ligands per aluminium ion must be formed. Several sets of constants of different  $MH_pL_r$  complexes were calculated for each metal-ligand equilibrium system. The reliability of the equilibrium constants obtained in these calculations was checked through comparison of the experimental and calculated  $\bar{n}$  values. The best explanations for the potentiometric data were the sets of the complexes  $MHL^-$ ,  $ML^{2-}$ ,  $MH_2L_2^{2-}$ ,  $MHL_2^{2-}$  and  $ML_2^{2-}$  ( $M=Be$  or  $Cu$ ) and  $AlHL_2^-$ ,  $AlL_2^-$ ,  $AlHL_2^{2-}$ ,  $AlL_2^{2-}$  and  $AlL_3^{3-}$  with the stability constants given in Table 4. It is reasonable to consider that the protons in the "acidic" complexes are those of the hydroxyl group at carbon C-7 or C-4, and that the  $ML_r$  species are formed either (a) via the dissociation of these protons or (b) via the direct reduction between metal and  $L^{4-}$  anions. Polynuclear complex compounds were not found in detectable amounts in potentiometric titrations. However, this might only be due to the experimental conditions, since accurate potential readings were available only with an excess of the ligand in the solutions to be titrated. Spectrophotometric

TABLE 4—THE STABILITY CONSTANTS FOR THE DIFFERENT METAL-3,5-DIHYDROXY-7-SULFO-2-NAPHTHOIC ACID AND METAL-1,7-DIHYDROXY-4-SULFO-2-NAPHTHOIC ACID EQUILIBRIUM SYSTEMS AT  $I=0.5$  ( $NaClO_4$ ) AND 25°

q, p, r	$\log \beta_{q,p,r}^{H_pL_r}$	$\log \beta_{q,p,r}^{H_pL_r}$	$\log \beta_{q,p,r}^{H_pL_r}$	Refs
Metal-3,5-Dihydroxy-4-sulfo-2-naphthoic acid system				
1,1,1	$20.651 \pm 0.026$	$20.004 \pm 0.015$	$17.805 \pm 0.018$	This work
1,0,1	$16.001 \pm 0.025$	$13.64 \pm 0.10$	$10.205 \pm 0.025$	"
1,2,2	—	$37.996 \pm 0.036$	$33.162 \pm 0.046$	"
1,1,2	$32.443 \pm 0.042$	$29.848 \pm 0.036$	$24.60 \pm 0.05$	"
1,0,2	$24.089 \pm 0.048$	$20.789 \pm 0.046$	$15.885 \pm 0.036$	"
1,0,3	$30.849 \pm 0.048$	—	—	"
Metal-1,7-Dihydroxy-4-sulfo-2-naphthoic acid system				
1,1,1	$20.001 \pm 0.022$	$20.327 \pm 0.015$	$18.576 \pm 0.030$	8
1,0,1	$14.952 \pm 0.030$	$14.43 \pm 0.05$	$11.79 \pm 0.06$	"
1,2,2	—	$38.762 \pm 0.025$	$35.56 \pm 0.05$	"
1,1,2	$30.80 \pm 0.08$	$30.11 \pm 0.05$	$27.06 \pm 0.05$	"
1,0,2	$22.14 \pm 0.09$	$20.854 \pm 0.030$	$17.418 \pm 0.040$	"
1,0,3	$28.21 \pm 0.08$	—	—	"

measurements confirmed the polymerization in acidic metal-ligand solutions where there was a large excess of metal ion with respect to the ligand (Fig. 5).




Fig. 5. Absorbance plot obtained by the continuous variation method for beryllium(II)-1,7-dihydroxy-4-sulfo-2-naphthoic acid system.

The stability of the present metal complexes follows the general order obtained many times earlier with related chelation agents containing oxygen-oxygen donor atoms, viz.  $AlL_n > BeL_n > CuL_n$ .

The beryllium and copper 1,7-dihydroxy-4-sulfo-2-naphthoic acid complexes are more stable than the corresponding 3,5-dihydroxy-7-sulfo-2-naphthoic acid complexes. In the case of the aluminium complexes the mutual stability order is reverse.

The present dihydroxy-2-naphthoic acid sulfonates form more stable 1:1 complexes than the different mono- and disulfonato derivatives of 1-hydroxy-2-naphthoic and 3-hydroxy-2-naphthoic acids. On the other hand, the addition of a second ligand molecule to the ML complexes is significantly more difficult when the sulfonato group at the carbon C-5 of 3-hydroxy-, 7-disulfonato-2-naphthoic acid or at carbon C-7 of 1-hydroxy-4,7-disulfonato-2-naphthoic acid is replaced with the hydroxyl group (the  $\log k_1/k_2$  values for the 1,7-dihydroxy-4-sulfonato-2-naphthoic acid and 3,5-dihydroxy-7-sulfonato-2-naphthoic acid complexes are about twice those for the 1-hydroxy-4,7-disulfonato-2-naphthoic acid and 3-hydroxy-5,7-disulfonato-2-naphthoic acid complexes).

TABLE 5—THE PROTONATION CONSTANTS OF ML AND  $ML_2$  (CHARGES ARE OMITTED) COMPLEXES OF 3,5-DI-HYDROXY-7-SULFO-2-NAPHTHOIC AND (1) AND 1,7-DIHYDROXY-4-SULFO-2-NAPHTHOIC ACID (2) AT  $I = 0.5$  ( $NaClO_4$ ) AND  $25^\circ$ .  $K_{1,1}^H = K(ML + H = MHL)$ ,  $K_{1,1,2}^H = K(ML_2 + H = MHL_2)$  AND  $K_{1,2,2}^H = K(MHL_2 + H = MH_2L_2)$

Metal	Ligand	$\log K_{1,1}^H$	$\log K_{1,1,2}^H$	$\log K_{1,2,2}^H$	Refs.
Al	(1)	4.65	8.35	—	This work
Be	"	6.36	9.06	8.15	"
Cu	"	7.60	8.72	8.56	"
Al	(2)	5.05	8.66	—	"
Be	"	5.90	9.26	8.65	"
Cu	"	6.79	9.64	8.50	"

Table 5 shows the protonation constants of the 1:1 and 1:2 complexes. The following conclusions can be drawn on the basis of these constants: (a) the acidity of the protons in the  $MH_nL_n$  complexes increases with the increasing stability of the




Fig. 6. Three-dimensional representation of the formation of the different aluminium species: (A)  $Al^{3+}$ , (B)  $AlHL$ , (C)  $AlL^-$ , (D)  $AlHL_2$ , (E)  $AlL_2^-$  and (F)  $AlL_2^-$  with 1,7-dihydroxy-4-sulfo-2-naphthoic acid.



$\text{ML}_2$  complexes, (b) the acidity of the hydroxyl group at carbon C-7 is significantly higher in the 1 : 1 complexes than in the free ligand anion and (c) the protonation constants of the 1 : 2 complexes are, on an average, of the same value as the second protonation constant of the ligand anion.

The aluminium(III), beryllium(II) and copper(II) complex formation of 1,7-dihydroxy-4-sulfo-2-naphthoic and 3,5-dihydroxy-7-sulfo-2-naphthoic acids depend on the free hydrogen ion and ligand anion concentrations if there is an excess of the ligand acid present in the solutions. Thus, all the present equilibrium systems can be displayed as a function of  $[\text{H}^+]$  and  $[\text{L}^{4-}]$ . Fig. 6 shows the formation of various aluminium species three-dimensionally for 1,7-dihydroxy-4-sulfo-2-naphthoic acid in the pH and  $-\log [\text{L}]$  ranges studied and assuming that there is an excess of the ligand present. For the sake of clarity, the formation of each species is presented in a separate figure

## References

1. L. H. J. LAJUNEN, *Ann. Acad. Sci. Fenn. Ser. A*, **11** 179, 1976.
2. L. H. J. LAJUNEN and M. TIKANMÄKI, *Finn. Chem. Lett.*, 1978, 96.
3. L. H. J. LAJUNEN, *Finn. Chem. Lett.*, 1978, 127.
4. L. H. J. LAJUNEN, *Finn. Chem. Lett.*, 1978, 129.
5. L. H. J. LAJUNEN, R. PETROLA, P. SCHLIDT, O. KORPPI-TOMMOLA and O. MAKITIE, *Talanta*, 1980, **27**, 75.
6. L. H. J. LAJUNEN and T. HILJANEN, *Acta Univ. Oul., A 105 Chem.*, **12**, 1980.
7. L. H. J. LAJUNEN, R. ANTTILA and T. HILJANEN, *Univ. Oulu. Report Series in Chem.*, 1981, 1.
8. L. H. J. LAJUNEN and V. KOPSA-MOILANEN, *Finn. Chem. Lett.*, 1982, 6.
9. L. H. J. LAJUNEN, J. ELORANTA and A. KUKKOHVI, *Finn. Chem. Lett.*, 1979, 11.
10. I. G. SAYCE, *Talanta*, 1968, **15**, 1397; *Talanta*, 1971, **18**, 653; I. G. SAYCE and V. S. SHARMA, *Talanta*, 1972, **19**, 831.
11. D. J. LEGGETT and W. A. E. MCBRYDE, *Anal. Chem.*, 1975, **47**, 1065.
12. "Stability Constants of Metal-Ion Complexes", The Chemical Society, *Spec. Publ.* **25**, London, 1971.

# A New Parameter in Astatistical Stabilization of Ternary Complexes

P. K. BHATTACHARYA\* and V. K. PATEL

Department of Chemistry, Faculty of Science, M. S. University of Baroda, Baroda-390 002

The formation constants of the complexes of the type  $[CuAL]$ , where A = 2,2'-bipyridyl (bipy), 1,10-phenanthroline (phen) and L = tryptophan have been determined in aqueous medium and  $\mu = 0.2 M$  ( $NaClO_4$ ) at  $30^\circ$ . The formation constant values have been determined by graphical method and further refined by using a computer program SCOGS. The value of  $\Delta \log K$ ,  $(\log K_{MAL}^M - \log K_{LL}^M)$ , is found to be positive in  $[CuAL]$  complexes even though L is coordinating through amino acid and just as glycine. The higher stabilization of the ternary complexes is mainly due to release of electron repulsion in the ternary complex. There is repulsion between  $Cu(II)$   $d\pi$  electrons and electrons delocalized over the indole ring in binary complex. In the ternary complex, due to  $M \rightarrow bipy \pi$  interaction, electrons pass over the bipyridyl molecule and there is less amount of electron repulsion leading to positive  $\Delta \log K$ .

VARIOUS aspects of the ternary complexes involving aromatic tertiary amines and various N-N, N-O<sup>-</sup> and O-O<sup>-</sup> coordinating ligands are being studied in detail because of the similarity of the aromatic tertiary amines with imidazole, which occurs commonly in biological systems. These complexes<sup>1-5</sup> provide models for metalloenzymes. Such complexes are also of interest as they exhibit an astatistical<sup>6,7</sup> stabilization due to special role of the aromatic tertiary amines. In the complexes  $[MAL]$ , where A is a tertiary amine like 2,2'-bipyridyl (bipy), it has been observed that the mixed ligand formation constant  $\log K_{MAL}^M$  is higher than that expected from statistical considerations<sup>4</sup>. This has been explained to be due to  $M \rightarrow bipy \pi$  interaction<sup>8,9</sup>. Consequently, effective electronegativity of  $[MA]^{2+}$  is almost the same as in  $[M(H_2O)_6]^{2+}$  and hence  $\log K_{ML}^M \approx \log K_{MAL}^M$ .

It has been further observed that  $[MA]^{2+}$  complexes discriminate between secondary ligand (L) with coordinating sites, N-N, N-O<sup>-</sup> and O-O<sup>-</sup><sup>6,7,10</sup>. In case where secondary ligand is malonate<sup>11</sup> coordinating through two oxygen atom,  $\Delta \log K$ ,  $(\log K_{MAL}^M - \log K_{LL}^M)$ , is positive. Sigel has attributed the greater stabilization of ternary complexes containing O-O<sup>-</sup> to an increase in class A character of  $[M.bipy]$ . In keeping with this concept we have extended an explanation in terms of electron repulsion<sup>12-14</sup>. In the formation of binary complexes, there is electron repulsion between the metal  $d\pi$  electrons and the lone pair of electrons (if any) present on the  $\sigma$  bonding ligand L. However, in the ternary complexes, due to back donation of electrons through  $\pi$  bonding from the metal ion to the molecule A, the electron density on  $[CuA]^{2+}$  is reduced. Therefore, the repulsion between the metal  $d\pi$  electrons and the additional lone pair of electrons over the secondary ligand L is less in the ternary complexes. There is no extra lone pair of electrons present on  $\sigma$  bonding N atom and hence this effect is not felt in N-N coordinating ligands. In ligands

coordinating through N-O<sup>-</sup> there is lone pair electrons over the carboxylate O<sup>-</sup>. Due to the increase of the electron repulsion in the ternary complexes,  $\Delta \log K$  is much less negative than in N-N coordinating ligands. In case of  $\pi$  coordinating ligand like malonate there are pairs of electrons over both carboxylate anions hence the effect is more pronounced leading to positive  $\Delta \log K$  in  $[CuAL]$ .

It has been further observed that in case where O-O<sup>-</sup> is an aromatic ligand like  $[Cu(bipy)]^{2+}$ ,  $\Delta \log K$  is more positive. This additional stabilization has been explained by Sigel<sup>15</sup> in terms of  $\pi$  ligand  $\pi$  interaction between two ligands through metal  $d\pi$  orbitals. However, Sigel presumed this interaction is not significant. Our studies of the electronic spectra of the complexes also do not indicate any significant inter-ligand  $\pi$  interaction. Hence an attempt has been made to explain stabilization in the ternary complexes involving aromatic O-O<sup>-</sup> also in terms of electron repulsion. Since the  $Cu(II)$  electrons are in  $t_{2g}$  orbitals with symmetry, the repulsion with the electrons on the  $p_z$  orbital of the coordinated O-O<sup>-</sup> (catechol) will be more in the binary complex. Hence, there will be greater release of repulsion and stabilization in the ternary complexes wherein  $d\pi$  electrons of  $Cu(II)$  pass over the bipyridyl molecule. Another important observation made by Sigel<sup>16</sup> and also by us<sup>17</sup>, is that electron withdrawing groups on L reduce the stability of ternary complexes while electron releasing groups on L increase the stability. This has also been explained<sup>17</sup> in terms of the proposed electron repulsion concept. The electron withdrawing groups lower the electron density on the ligand atom. Hence, the electron repulsion in the binary complex is less and corresponding release of electron repulsion in ternary complex and its stabilization is less.

Normally,  $\Delta \log K$  is found to be positive only

in cases where L is O<sup>-</sup>O<sup>-</sup> coordinating ligands. It has been observed by us<sup>12</sup> that  $\Delta \log K$  is positive in case of [CuAL] complex where A=2(2'-pyridyl)-benzimidazole and L=glycine having N-O<sup>-</sup> coordinating site. This was explained to be due to increased Cu→A $\pi$  interaction due to pyridyl and benzene rings of 2(2'-pyridyl)benzimidazole. Further, it has been observed by us<sup>12</sup> that  $\Delta \log K$  is positive in cases of [CuA] complexes, where A=bipy or phen and L=phenylalanine, tyrosine or dopa, coordinating from N-O<sup>-</sup> site as in the case of glycine. It has been shown that the aminocarboxylate end of phenylalanine, tyrosine or dopa coordinates with [CuA] and the phenyl, phenol or catechol part remains free and spreads over the [CuA] part. There may be an intermolecular stacking interaction between the tertiary amine and the aromatic ring of the secondary ligand as suggested by Sigel in case of [Cu(o-phen)(phenylacetate)] complexes<sup>13</sup>. However, construction of a model shows that the aromatic ring of the secondary ligand can spread only over the axial region of the Cu(II) and not beyond. The greater stability of these ternary complexes can be explained in terms of release of electron repulsion. There is repulsion in the binary complex between the Cu(II) electrons and  $\pi$  electrons of secondary ligand phenyl group which can come over the metal ion. But in the ternary complexes due to M→A $\pi$  interaction, the electron density over Cu<sup>2+</sup> ion is effectively reduced and hence repulsion is reduced leading to the formation of stable ternary complex. In order to confirm the observation further, in the present study mixed ligand complexes [CuA tryptophan], where A=bipy (A<sup>1</sup>) or phen (A<sup>2</sup>), have been studied.

### Experimental

All reagents used were of A.R. grade. The proton-ligand and metal-ligand formation constants were determined in aqueous medium and  $\mu=0.2$  M (NaClO<sub>4</sub>) at 30°. The values of  $\bar{n}$ H,  $K_1^H$ ,  $K_2^H$ ,  $\bar{n}$ ,  $p^L$ ,  $\log K_1$  and  $\log K_2$  were calculated by carrying out Irving-Rossotti titrations<sup>20,21</sup>. The formation constants of ternary complexes were determined by using a modified Irving-Rossotti titration technique<sup>6</sup>.

All the formation constants were subjected to refinement by using the computer program SCOGS<sup>22</sup>. Details of consideration of various species and use of computer program is as described in our earlier work<sup>12-14</sup>. The refined constants are tabulated in Tables 1 and 2. It is observed that

TABLE 1—PROTONATION CONSTANTS AND METAL LIGAND STABILITY CONSTANT OF COPPER COMPLEXES IN AQUEOUS MEDIUM, I=0.2 MOLE dm<sup>-3</sup> (NaClO<sub>4</sub>) AT 30°

Ligands	Protonation constant		Metal-ligand binary constant	
	$K_1^H$	$K_2^H$	$K_1$	$K_2$
A <sup>1</sup>	4.45 ± 0.01	1.5 ± 0.1	8.1 ± 0.01	5.5 ± 0.03
A <sup>2</sup>	4.96 ± 0.01	1.9 ± 0.1	9.25 ± 0.02	4.54 ± 0.09
Tryptophan (L')	9.06 ± 0.03	2.6 ± 0.04	8.19 ± 0.09	6.79 ± 0.07

TABLE 2—STABILITY CONSTANT OF TERNARY COMPLEX AND LOG K IN AQUEOUS MEDIUM, I=0.2 MOL dm<sup>-3</sup> (NaClO<sub>4</sub>) at 30°

	CuA <sup>1</sup> L <sup>1</sup>		CuA <sup>2</sup> L <sup>1</sup>	
	$\log K_{\frac{M}{ML}}$	$\Delta \log K$	$\log K_{\frac{M}{ML}}$	$\Delta \log K$
L <sup>1</sup>	9.75 ± 0.03	+1.56	9.32 ± 0.03	+1.13

the major species are [CuA] and [CuAL] as shown in Fig. 1.




Fig. 1 Variation of concentration of different species with pH

**Spectral measurement :** The spectra were recorded on a Carl Zeiss Specord UV visible spectrophotometer with 1 cm quartz cells using water as solvent. Solutions of concentration 10<sup>-4</sup> to 10<sup>-5</sup> mol dm<sup>-3</sup> were used for uv and visible regions, respectively. Spectra of free ligands, mixture of two ligands, [CuA<sub>2</sub>], [CuL<sub>2</sub>] and [CuAL], prepared by direct mixing of Cu(II) and ligands in required proportions, were obtained. The observed band positions are tabulated in Table 3.

### Results and Discussion

It is observed that tryptophan coordinates to the metal ion as bidentate ligand like glycine in binary complexes. The value obtained for  $\log K_{\frac{M}{ML}}$  in the present study is  $8.19 \pm 0.09$  (Table 1) and is very close to the reported value  $8.27 \pm 0.05$ <sup>23</sup>. The position of the d-d band also confirms that the coordination sites in [Cu(tryptophan)<sub>2</sub>] are N-O<sup>-</sup>. The observation of the d-d band in [Cu(tryptophan)<sub>2</sub>] at 714 nm is very close to the d-d band in [Cu(gly)<sub>2</sub>] (712.0 nm) and also confirms that the coordination sites are N-O<sup>-</sup>.

It is observed in the present study that  $\Delta \log K$  is positive in the ternary complexes even though the coordination of tryptophan is from aminocarboxylate end. The higher stability of these ternary complexes can be explained by considering following factors. The aminocarboxylate part of tryptophan coordinates with [CuA] and the indole part remains free. This can spread over the bipridyl base part and there may be intramolecular stacking interaction between these two parts which contributes to higher stability.

TABLE 3—ELECTRONIC SPECTRAL BANDS (nm) OF FREE LIGANDS AND BINARY AND TERNARY Cu(II) COMPLEXES IN AQUEOUS MEDIUM

A <sup>+</sup>	233.6	284.1			
A <sup>+</sup>	230.4	266.1			
Tryptophan (L <sup>+</sup> )	215.1	270.3	277.8	285.7 (sh)	
[CuA <sub>2</sub> ]	243.9	303.0	314.5	700	
[CuA <sub>2</sub> ]	231.5	275.5	298.5 (sh)	699	
[CuL <sub>2</sub> ]	209.2	270.3	277.8	285.7	714.3
A <sup>+</sup> + L <sup>+</sup>	218.6	244.0 (sh)	285.7	305.3 (sh)	492.0 (sh)
A <sup>+</sup> + L <sup>+</sup>	222.2	268.5	290.0 (sh)	322.6	496.0 (sh)
[CuA <sup>+</sup> L <sup>+</sup> ]	217.4 (sh)	244.0 (sh)	258.0 (sh)	287.8	298.5, 310.3, 457.0 (sh), 682.6
[CuA <sup>+</sup> L <sup>+</sup> ]	212.8	270.3	289.9 (sh)	466.0 (sh)	685.0

In mixed ligand complexes [Cu(ATP)(tryptophan)], it was observed by Sigel<sup>22</sup> that tryptophan coordinates through aminocarboxylate end. There is intramolecular stacking interaction between the indole moiety of tryptophan and purine moiety of ATP in these mixed ligand complexes i.e. these complexes can be considered as metal ion bridged stacking adducts. This contributes to the stability of ternary complexes. Due to this stacking interaction charge transfer band observed at 292 nm in a mixture of ATP<sup>4-</sup>+tryptophan is shifted to 295 nm (lower energy) in the ternary complex [Cu(ATP)-(tryptophan)]. Similar type of stacking interaction is also observed in [Cu(ATP)(bipy)] complexes<sup>24</sup>. In a mixture of ATP<sup>4-</sup>+bipy there is a new band at 295 nm, which is shifted to 313 nm (lower energy) in [Cu(ATP)(bipy)] ternary complex. This is due to stacking interaction between bipyridyl and the base part of ATP in the ternary complex.

In the present study, we observed a new band at 492 nm in a mixture of tryptophan and bipy. This is due to charge transfer interaction between base part of bipy and indole moiety of tryptophan. This new band is found to be shifted to 457 nm (higher energy) in mixed ligand complex [Cu(bipy)-(tryptophan)]. This indicates that there is charge transfer interaction between the indole and bipy moiety in the ternary complex also. However, in the mixed complex the charge transfer band is shifted to higher energy region unlike in [Cu(ATP)-(tryptophan)] and [Cu(ATP)(bipy)] complexes where charge transfer band moves to lower energy region. It can be explained by comparing with [Cu(bipy)-(phenylalanine)] wherein it was considered that the phenyl part of alanine can not reach over bipyridyl. In tryptophan also (CH<sub>2</sub>)<sub>2</sub> chain linking indole part with the nitrogen is as in phenylalanine. However, indole part has two rings. Hence, it may partly reach over bipyridyl and there may be a distant charge transfer interaction requiring higher amount of energy. This shows that the charge transfer interaction in the ternary complex [CuA-tryptophan] is reduced and hence may not contribute to the positive  $\Delta \log K$  value.

The positive  $\Delta \log K$  in this N-O<sup>-</sup> coordinating ligand can be explained by considering that there is repulsion in the binary complex between the Cu(II) electrons and the indole ring electrons of tryptophan which can come over the metal ion as in case of Cu-phenylalanine, Cu-tyrosine, Cu-dopa. But in ternary complexes due to M  $\rightarrow$  A  $\pi$  interaction the electron density over Cu<sup>2+</sup> ion is effectively

reduced and hence the repulsion is less in ternary complex. This lowering in electron repulsion stabilizes the complex formation and leads to positive  $\Delta \log K$  in these ternary complexes even though the coordination is from N-O<sup>-</sup> site<sup>18</sup>.

These ternary complexes, involving two ligands of biochemical importance, thus exhibit interesting structural feature leading to stabilization of the ternary complexes.

#### Acknowledgement

The authors thank Prof. K. N. Trivedi, Head, Chemistry Department for facilities and the C.S.I.R., New Delhi, for financial support.

#### References

1. H. SIGEL, "Metal Ions in Biological Systems", Marcel Dekker, Inc., New York, 1973, Vol. 2.
2. H. SIGEL, *Angew. Chem.*, 1975, 14, 394.
3. P. K. BHATTACHARYA, *J. Sci. Ind. Res.*, 1981, 40, 382.
4. G. A. L'HEUREX and A. E. MARTELL, *J. Inorg. Nuclear Chem.*, 1966, 28, 418.
5. R. GRISSE and H. SIGEL, *Inorg. Chem.*, 1970, 9, 1238.
6. M. V. CHIDAMBARAM and P. K. BHATTACHARYA, *J. Inorg. Nuclear Chem.*, 1970, 32, 3271.
7. H. SIGEL, *Inorg. Chem.*, 1980, 19, 1411.
8. H. SIGEL, *Chimia*, 1967, 21, 489.
9. P. J. PATEL, V. K. PATEL and P. K. BHATTACHARYA, *Indian J. Chem.*, (In press).
10. H. SIGEL and B. PRIJS, *Chimia*, 1975, 29, 134.
11. H. SIGEL, B. E. FISCHER and B. PRIJS, *J. Amer. Chem. Soc.*, 1977, 99, 4489.
12. P. J. PATEL, V. K. PATEL and P. K. BHATTACHARYA, *Inorg. Chem.*, (In press).
13. K. GOPALAKRISHNAN and P. K. BHATTACHARYA, *J. Chem. Soc., (Dalton)*, 1981, 543.
14. K. GOPALAKRISHNAN and P. K. BHATTACHARYA, *J. Chem. Soc., (Dalton)*, 1982, 353.
15. F. A. WALKER, H. SIGEL and D. B. MCCORMICK, *Inorg. Chem.*, 1972, 11, 276.
16. H. SIGEL, P. R. HUBER, R. GRISSE and P. PRIJS, *Inorg. Chem.*, 1973, 12, 1198.
17. V. K. PATEL and P. K. BHATTACHARYA, *Inorg. Chem.*, (Communicated).
18. V. K. PATEL and P. K. BHATTACHARYA, *Inorg. Chem.*, (Communicated).
19. H. SIGEL, in "Advances in Solution Chemistry", (Ed.) J. BERTINI, L. and A. DEI, 1981, 149.
20. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1953, 3397.
21. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
22. I. G. SAYCE *Talanta*, 1968, 15, 1397; 1971, 18, 653; I. G. SAYCE and V. S. SHARMA, *Talanta*, 1972, 19, 831.
23. H. SIGEL and C. F. NAUMANN, *J. Amer. Chem. Soc.*, 1976, 98, 730.
24. H. SIGEL and P. CHAUDHURI, *J. Amer. Chem. Soc.*, 1977, 99, 3142.

# Compatibility of Nitrilotriacetic Acid and 3-Acetyl-4-Hydroxy-6-Methyl-2-Pyrone in the Coordination Sphere of Lanthanum Ions

R. K. KADIAN, B. S. GARG and R. P. SINGH\*

Department of Chemistry, University of Delhi, Delhi-110 007

A study of the competition of 3-acetyl-4-hydroxy-6-methyl-2-pyrone (dehydracetic acid, DHA) and nitrilotriacetic acid (NTA) in the coordination sphere of lanthanum ions has been carried out by calculating reproporationation constant which relates the stability of the mixed ligand complex to those of the parent complexes formed by the same ligands. It has been found that NTA and DHA are incompatible ligands and mixed ligand complexes formed are less stable than either of the parent complexes. The fact is also supported by the observed change in free energy occurring during mixed ligand complex formation. All these studies have been carried out at  $30.0 \pm 0.5^\circ$  and  $\mu = 0.1$  ( $\text{NaClO}_4$ ) in 50% v/v aqueous dioxane medium.

3-Acetyl-4-hydroxy-6-methyl-2-pyrone (DHA) has an  $\alpha$ -pyrone structure and is a physiologically active compound. It has been used as fungistatic and fungicide, antibacterial agent, toxic and resistant to micro-organisms. 1 : 3 binary complexes of lanthanons with DHA and the mixed ligand complexes of these trivalent ions with DHA and NTA have been studied and the results reported in the present communication. The various metal ions investigated, required to calculate the reproporationation constant and the change in free energies which occurs during mixed ligand complex formation, are La(III), Pr(III), Nd(III), Sm(III), Gd(III), Dy(III), Yb(III) and Y(III).

## Experimental

DHA (Koch Light, England) solution was prepared in freshly distilled dioxane (E. Merck). NTA (Riedel) was dissolved in 3-equivalents of NaOH solution and was used as trisodium salt. All chemicals and solvents used were of A. R. quality and solutions were prepared in double distilled water. For ternary systems, the following solutions were titrated potentiometrically against a standard solution of tetramethylammonium hydroxide (TMAH) at  $30.0 \pm 0.5^\circ$  and ionic concentration of  $0.1 M \text{ NaClO}_4$ , maintaining 50% (v/v) dioxane-water medium: (i) 5.0 ml perchloric acid ( $0.04 M$ ), (ii) 5.0 ml perchloric acid ( $0.04 M$ )+0.5 ml NTA ( $0.02 M$ ), (iii) 5.0 ml perchloric acid ( $0.04 M$ )+1.0 ml DHA ( $0.01 M$ ), (iv) 5.0 ml perchloric acid ( $0.04 M$ )+0.5 ml NTA ( $0.02 M$ )+0.5 ml metal ion ( $0.02 M$ ), (v) 5.0 ml perchloric acid ( $0.04 M$ )+1.0 ml DHA ( $0.01 M$ )+0.5 ml metal ion ( $0.02 M$ ) and (vi) 5.0 ml perchloric acid ( $0.04 M$ )+0.5 ml NTA ( $0.02 M$ )+1.0 ml DHA ( $0.01 M$ )+0.5 ml metal ion ( $0.02 M$ ).

The binary systems were studied with 1 : 5 ratio of metal to ligand under identical conditions. For all calculations total volume was reduced from 20

ml to 19.7 ml due to contraction on mixing dioxane with water.

## Results and Discussion

**Formation constants:** The formation constants of the binary complexes of lanthanons with DHA calculated by weighted least squares method of Sullivan *et al*<sup>1</sup> are listed in Table I.

TABLE I—FORMATION CONSTANTS OF THE METAL COMPLEXES WITH DHA CALCULATED BY WEIGHTED LEAST SQUARES METHOD AT  $30.0 \pm 0.5^\circ$  AND  $\mu = 0.1 M \text{ NaClO}_4$

Ln(III)	$\log \beta_1$	$\log K_1$	$\log \beta_2$	$\log K_2$	$\log \beta_3$	$S_{\text{min}}$
H <sup>+</sup>	6.33	—	—	—	—	—
La	4.75	4.43	9.18	2.94	12.12	0.0468
Pr	4.88	4.55	9.43	3.15	12.58	0.0284
Nd	5.20	4.64	9.84	3.34	13.18	0.0188
Sm	5.44	4.74	10.18	3.49	13.67	0.0037
Gd	5.57	5.16	10.73	3.70	14.43	0.0092
Dy	5.81	5.30	11.11	4.14	15.25	0.0071
Yb	6.30	5.40	11.70	4.91	16.61	0.0580
Y	5.87	5.37	11.24	4.22	15.46	0.0477

In case of ternary systems, it was observed that NTA reacts with lanthanons at lower pH range as found from titration curves of (ii) and (iv) solutions. The titration curves of (iii) and (vi) solutions overlap in the lower pH range whereas at high pH there is divergence of the curves indicating the coordination of DHA with the species  $[\text{Ln-NTA}]$ . Also, the  $[\text{Ln-NTA}]$  species have much higher formation constants as compared to lanthanum-DHA complex and hence ligand exchange possibility is eliminated.

The overall reaction may thus be represented as



where  $K_{MAL}$  is the formation constant of the mixed species and is given by equation

$$K_{MAL} = \beta_{1,1} = \frac{[\text{Ln-NTA-DHA}]}{[\text{Ln-NTA}][\text{DHA}]}$$

$S_{min}$  values having the same significance as  $\chi^2$  with  $k$  degrees of freedom<sup>2</sup> have also been calculated for all systems.

**Reproportionation constants:** The stability of the mixed ligand complexes formed is related to the stability of the parent complexes formed by same ligands through reproportionation constant. This correlation is given by the following expression:

$$\beta_{i,j} = K_d \beta_{m,o}^{i,m} \beta_{o,m}^{j,m} [i+j=m]$$

Where  $K_d$  is reproportionation constant (Table 2). This constant is a measure of the compatibility of the various ligands in the coordination sphere of a given metal ion.

TABLE 2—FORMATION AND REPROPORTIONATION CONSTANTS AND  $S_{min}$  VALUES OF MIXED LIGAND COMPLEXES AT  $30.0 \pm 0.5^\circ$  AND  $\mu = 0.1 \text{ M NaClO}_4$

Ln(III)	$\log \beta_{1,0}^*$ (M-NTA)	$\log \beta_{0,1}$ (M-DHA)	$\log \beta_{1,1}$ (M-NTA-DHA)	$K_d$	$S_{min}$
La	17.65	9.18	13.35	0.871	0.0140
Pr	19.90	9.43	14.09	0.794	0.0465
Nd	19.36	9.84	14.57	0.933	0.0528
Sm	20.51	10.18	15.07	0.537	0.0952
Gd	20.79	10.73	15.67	0.813	0.1596
Dy	21.16	11.11	15.90	0.589	0.0870
Yb	21.73	11.70	16.63	0.832	0.1631
Y	21.73	11.24	15.64	0.144	0.0426

\* Values redetermined under present set of conditions<sup>7</sup>

**Formational energies:** The individual bond strengths M-A and M-L in the complex  $\text{MA}_i\text{L}_j$  can be calculated from the formation constant of the mixed ligand complex and the parent complexes  $\text{MA}_j$  and  $\text{ML}_i$  using the following equations:

$$F_A = \frac{RT}{4j} \ln \beta_{i,j} \frac{\beta_{1,0}}{\beta_{0,1}}$$

$$F_L = \frac{RT}{4} \ln \beta_{i,j} \frac{\beta_{0,1}}{\beta_{1,0}}$$

The bond strengths in the parent complexes  $\text{MA}_m$  and  $\text{ML}_m$  are calculated from the equations:

$$F'_A = \frac{RT}{2m} \ln \beta_{m,0}$$

$$F'_L = \frac{RT}{2m} \ln \beta_{0,m}$$

The differences in free energies calculated from these equations characterise the changes of M-A and M-L bond energies which occur during mixed ligand complex formation. The results of the present investigations are listed in Table 3.

## Discussion

Pure statistical consideration predicts  $\beta_{0,1}/\beta_{1,0}$  values as 3.27 and 4.92, respectively for a ligand

TABLE 3—FORMATIONAL ENERGIES OF VARIOUS COMPLEXES IN CALS/MOLE

Ln(III)	M-NTA (parent)	M-NTA (mixed)	Change in free energy	M-DHA (parent)	M-DHA (mixed)	Change in free energy
La	6115	6624	509	3182	2631	-551
Pr	6549	6950	401	3303	2818	-485
Nd	6708	7199	491	3411	2901	-510
Sm	7113	7452	339	3529	2995	-534
Gd	7210	7654	444	3719	3210	-509
Dy	7335	7712	377	3851	3310	-541
Yb	7532	8101	569	4056	3428	-628
Y	7532	7504	-28	3896	3338	-558

functioning as bidentate or tridentate in the presence of lanthanon ions<sup>8</sup>. Our results indicate that  $\beta_{0,1}$  values are larger than  $\beta_{1,0}$  values and their ratio is less than 3.27 in all the cases, suggesting the bidentate nature of DHA.

It may be noted from Table 1 that the value of formation constants for binary complexes increases regularly from lanthanum to ytterbium and no gadolinium break has been observed. Also, the value for yttrium complex is found to be quite close to the value of dysprosium. Depending upon the nature of the ligand, the formation constant values of yttrium complexes are at times close to those of dysprosium complexes and at others close to praseodymium. Because of its size, yttrium should be found near holmium except when lack of ligand field stabilization moves it closer to gadolinium. Probably polarizability effects or/and minor but variable contributions of covalent bonding are responsible for the erratic behaviour of yttrium<sup>4</sup>.

Results of the present investigations show that mixed ligand complexes formed are less stable than either of the parent complexes (Tables 2 and 3). M-NTA bond strengths increase while M-DHA bond strengths decrease. The lower stability of the mixed ligand complexes can be explained on the basis of electrostatic considerations. The driving force for the binding of secondary ligand  $\text{L}^-$  with  $[\text{MA}]$  should be less than that for the binding of  $\text{L}^-$  with  $[\text{M(aq)}]^{3+}$ . Further, NTA molecule with a bigger size is expected to produce a greater steric hindrance to the entry of the second ligand in the coordination sphere of the metal ion and decreases the stability to a great extent.

The lower stability of the mixed ligand complexes is also due to incompatible nature of NTA and DHA in the coordination sphere of lanthanon ions and is reflected in the values of reproportionation constant which is less than unity in all the cases. It has been observed that if the geometrical structures and bond types of the parent complexes differ from each other, the ligands are incompatible and the mixed ligand complexes formed are less stable than either of the parent complexes<sup>9</sup>. In such cases, the bonds between the metal ion and one of the ligands become more ionic and the bonds between the metal ion and the second ligand become

more covalent. These effects are of opposite sign and the net energy change may be positive or negative depending upon the nature of ligands and metal ion involved in complex formation<sup>6</sup>.

#### References

1. J. C. SULLIVAN, J. RYDBERG and W. F. MILLER, *Acta Chem. Scand.*, 1959, 13, 2023.
2. J. RYDBERG and J. C. SULLIVAN, *Acta Chem. Scand.*, 1959, 13, 2059.
3. J. E. POWELL and R. S. KOLAT, *Inorg. Chem.*, 1962, 1, 292.
4. L. EYRING, "Progress in Science and Technology of Rare Earths", Pergamon Press, 1964, p. 129.
5. S. KIDA, *Bull. Chem. Soc. Japan*, 1960, 33, 1365.
6. S. KIDA, *Bull. Chem. Soc. Japan*, 1961, 34, 962.
7. A. E. MARTELL and R. M. SMITH, "Critical Stability Constants", Plenum Press, New York, London, 1974, Vol. I.

# The Oxidation of Optically Active 3,4-Dihydroxyphenylalanine by Optically Active Cobalt(III) Complexes

YUZO YOSHIKAWA and KAZUO YAMASAKI\*

Department of Chemistry, Faculty of Science, Nagoya University, Nagoya, 464 Japan

Oxidation of  $(-)-D$ -3,4-dihydroxyphenylalanine (dopa) by  $(+)-$ ,  $(-)-$ , and racemic  $[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$  was studied by the measurement of oxygen absorbed, optical rotation, and absorption spectrum. The same intermediate which has a large  $(-)$  rotation was formed from three optical isomers of the above complex. The configuration of this intermediate is presumed to be a *trans-bis*(ethylenediamine) complex with one molecule of dopa or its oxidation product in the fifth coordination site. The oxidation scheme of dopa by cobalt(III) complexes is discussed.

IN 1920 Yuji Shibata and his elder brother Keita Shibata found an interesting phenomenon exhibited by some complexes of cobalt(III), nickel(II), copper(II) etc.<sup>1</sup>. These complexes showed oxidase-like oxidizing actions on some hydroxyflavones like myricetin and polyphenols like pyrogallol. A series of investigation on this subject executed by Y. and K. Shibata and their co-workers proved that these oxidation reactions had a catalytic nature and resembled enzyme actions from the view point of chemical kinetics<sup>2</sup>. During the course of studies Y. Shibata and his co-workers including R. Tsuchida reported that chiral organic compounds like  $(-)-D$ -3,4-dihydroxyphenylalanine (dopa)<sup>3</sup> and  $(+)-D$ -catechin (3, 3', 4', 5, 7-flavapentol)<sup>4</sup> were oxidized with different rates by  $(+)-$  and  $(-)-$  isomers of chiral cobalt(III) complexes, a phenomenon of so-called asymmetric oxidation. We have been interested in these important and interesting works, and wanted to study more extensively this asymmetric oxidation. Our results, which are different from theirs, are reported here<sup>5</sup>.

Since the work of Shibata and Tsuchida in 1929<sup>3</sup> Langenbeck *et al*<sup>6</sup> reported the asymmetric oxidation of dopa by copper chelates, and Hatano *et al*<sup>7</sup> studied catalytic oxidation of dopa by poly- $\alpha$ -amino acid-copper (II) complexes. Since dopa is a biologically important substance, there are many reports on it. Recently, Gergely and Kiss<sup>8</sup> studied equilibria of dopa with copper, nickel and zinc in solution and published an extensive review<sup>9</sup>.

## Experimental

### Materials :

The following cobalt(III) complexes were prepared according to the literature methods<sup>10</sup> :

*trans*- $[\text{CoCl}_2(\text{en})_2]\text{Cl}$ , *cis*- $[\text{CoCl}_2(\text{en})_2]\text{Cl}$ , *cis*- $[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$ , *cis*- $[\text{Co}(\text{NH}_3)(\text{en})_2(\text{H}_2\text{O})]\text{Br}_2 \cdot \text{H}_2\text{O}$ ,  $[\text{CoCl}(\text{NH}_3)_2]\text{Cl}_2$  and *cis*- $[\text{Co}(\text{NH}_3)_4(\text{H}_2\text{O})_2]\text{Cl}_2$ .

The resolution of *cis*- $[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$  was carried out by fractional crystallization of the

diastereoisomers with  $(+)-D$ -bromocamphor- $\alpha$ -sulfonate<sup>11</sup>. The specific rotations of the complex in 0.5% aqueous solutions were  $[\alpha]_D^{25} = +50.8 \pm 1.0^\circ$  (2 cm cell) and  $-50.9 \pm 1.0^\circ$  (2 cm cell), respectively.

The other chemicals including dopa, tyrosine, alanine and phenylalanine were commercial products.

### Measurements :

A mixed solution of the substrate, cobalt(III) complex, and phosphate buffer (pH 7.2) was kept at 25°. A portion of this reaction mixture was taken out at appropriate time intervals for the measurement of pH, absorption spectrum and optical rotation.

In the latter half of the oxidation reaction, the solution became dark brown in colour with black precipitates (melanin). The precipitates were filtered off and the filtrate was diluted, if necessary, two to four times, and the absorption was measured using quartz cells 2, 5 and 10 mm length. Optical rotatory dispersion (ORD) and circular dichroism (CD) were measured for the solutions prepared similarly. All the measurements were made at 25° on a JASCO ORD/UV-5 recording spectrophotometer equipped with a CD attachment.

The concentrations and amounts of the reaction solutions used were : dopa  $1.53 \times 10^{-2}$  mol/l, 100 ml; the complex  $3.06 \times 10^{-3}$  mol/l, 25 ml; phosphate buffer (pH 7.2) 0.2 mol/l, 5 ml, unless otherwise stated.

The amount of cobalt(II) ion formed during the reaction was colorimetrically determined after the following procedures. The solutions used were  $(-)-dopa$  ( $1.2 \times 10^{-2}$  mol/l, 50 ml), *r*- $[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$  ( $1.2 \times 10^{-2}$  mol/l, 50 ml) and phosphate buffer [0.2 mol/l (pH 7.2), 50 ml]. One ml of the reaction solution was taken out and mixed with 10 ml of ammonium thiocyanate (50 g/100 ml  $\text{H}_2\text{O}$ ) solution and 10 ml of an isoamyl alcohol-ethyl ether (3 : 1) mixture. The mixture was vigorously shaken for 10 min and the optical density of the organic



layer was measured at 610 nm using a quartz cell 1 cm thick.

The amount of oxygen gas absorption during the reaction was measured with Warburg manometer which has a 14–16 ml reaction vessel. The vessel was shaken at a rate of 60 strokes per min.

## Results and Discussion

### (1) Oxidation of racemic dopa :

Shibata and Tsuchida reported that when racemic dopa was oxidized by  $(-)-[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$  in an aqueous solution, the original negative rotation of the reaction mixture increased to a maximum, then decreased to zero and finally a positive rotation was observed. They interpreted the result in the way that the  $(-)$ -complex oxidized the  $(-)$ -component of dopa more easily than the  $(+)$ -component and a substance with  $(-)$ -rotation, an intermediate of the oxidation of dopa, was produced. The intermediate compound was further oxidized, losing its activity and the reaction mixture thus became gradually less negative and finally positive due to the remaining less oxidizable  $(+)$ -dopa.

We tried to reproduce the results of Shibata and Tsuchida\* and carried out the same oxidation reaction under the same experimental conditions but the result obtained (Fig. 1) was different. In our experiments the negative rotation due to the  $(-)$ -cobalt complex decreased to zero without showing a maximum. Before measuring the optical rotation a dilute (1 N) acetic acid solution was added to stop the reaction. When the  $(+)$ -complex was used, the same result was obtained with opposite rotation. No asymmetric oxidation was observed.




Fig. 1. Change of the angle of rotation during oxidation of r-dopa by  $(-)-[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$ . The angle of rotation of the complex solution alone is shown by  $\square$ . Cell : 1 cm.

### (2) Oxidation of optically active $(-)$ -dopa :

As the asymmetric oxidation of Shibata and Tsuchida could not be reproduced, we used  $(-)$ -dopa instead of racemic dopa and studied its oxidation by  $(+)$ -,  $(-)$ - and racemic  $[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$ . The concentrations of the reactants were the same as given in Measurements. Before measuring the optical rotation 1 ml of 1 N acetic acid solution was added to 2 ml of the reaction mixture to stop the oxidation. The change of the optical rotation observed at 600 nm is shown in

Fig. 2. During the reaction of about 20 hr the pH of the solution decreased from the initial 7.2 to 6.5. For three isomers of the complexes, optically active and inactive, the rotation of the reaction mixture always decreased with time to the zero value. The two curves shown by the reaction mixture containing the  $(+)$ - and  $(-)$ -complexes are almost symmetrical to each other in respect of the mixture containing the racemic complex. These results indicate simply loss of the optical activity of  $(-)$ -dopa by oxidation, showing no asymmetric oxidation.




Fig. 2. Change of the angle of rotation during oxidation of  $(-)$ -dopa by (O) $(+)$ -, (□) $(-)$ -, or (Δ)r- $[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$ . Cell : 1 cm

In the next experiment no acetic acid was added to the reaction mixture to stop the oxidation before measuring the optical rotation. The results obtained were entirely different from the previous experiments. In the course of the oxidation reaction an identical intermediate, which showed a large negative optical rotation, was formed for  $(-)$ -,  $(+)$ - and racemic complexes. The amount of the intermediate became maximum in about 10 hr and then gradually decreased (Fig. 3). This intermediate was obviously decomposed by acetic acid because such a large rotation was not observed when acetic acid was used to stop the oxidation.




Fig. 3. The same experiment as shown in Fig. 2. Acetic acid was not added to stop the reaction.

To characterize the intermediate further, the ORD curves were measured at several points during the reactions. The results are shown in Fig. 4 which indicates that all the three reactions proceed through the same intermediate with an identical ORD curve. As  $(+)$ -,  $(-)$ - and r- $[\text{CoCl}(\text{NH}_3)(\text{en})_2]\text{Br}_2$  react in the same way with  $(-)$ -dopa, the intermediate is concluded to have no chiral

structure about the cobalt atom and its optical activity should be due to the optically active ligand which is (–)-dopa itself or its partial oxidation product.




Fig. 4. ORD curves of the same reaction mixtures as shown in Fig. 3. The subscripts 1, 2 and 3 denote the values at 5 min, 4 hr and 10 hr from the beginning of the reaction. The (–), (+), r denote the rotation of the used complexes.

### (3) Determination of cobalt(II) ions formed during the oxidation reaction :

During the oxidation of (–)-dopa, cobalt(II) ions were detected after a few hr from the beginning. Its amount was determined for the reaction of (–)-dopa and  $r\text{-[CoCl(NH}_3\text{)(en)}_2\text{]Br}_2$ . The amount of cobalt(II) ions corresponds closely to the value of optical rotation (Fig. 5), suggesting that the optically active intermediate will be a cobalt(II) complex.




Fig. 5. Relationship between the amount of cobalt(II) ions formed and the angle of rotation during oxidation of (–)-dopa by  $r\text{-[CoCl(NH}_3\text{)(en)}_2\text{]Br}_2$ .

### (4) Oxidation of other substrates :

The interaction and reactivity of  $r\text{-[CoCl(NH}_3\text{)(en)}_2\text{]Br}_2$  with other substrates were examined spectrophotometrically using L- $\alpha$ -alanine, DL- $\beta$ -phenylalanine, and L-tyrosine instead of (–)-dopa. These amino acids have partial structures similar to dopa, but have no OH-groups in the *ortho* position.

The mixture of the racemic cobalt(III) complex and the amino acid gave the same absorption spectrum in the visible region during the reaction as that of the cobalt(III) complex alone, that is only the

spectral change due to aquation of the complex was observed, no special interaction between the cobalt complex and the substrate being found. This means that carboxylate and amino groups in the side chain of dopa have no effect on the oxidation by the cobalt(III) complex.

### (5) Oxidation of (–)-dopa by various cobalt(III) complexes :

The oxidation of (–)-dopa was further examined using other *bis*(ethylenediamine) cobalt complexes like  $cis\text{-[Co(NH}_3\text{)(en)}_2\text{(H}_2\text{O)}\text{]Br}_2$ ,  $cis\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$ , and  $trans\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$  (Fig. 6). The concentrations of the reactants were the same as given in *Measurements*. Clearly, the reaction rates depended on the kind of the cobalt complexes used and the oxidation of (–)-dopa was most rapid for  $trans\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$ . All the solutions showed the same characteristic ORD curve as  $\text{[CoCl(NH}_3\text{)(en)}_2\text{]Br}_2$  at the point of maximum optical rotation. This characteristic ORD curve was also obtained with opposite sign in the reaction of (+)-dopa and  $trans\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$ .

Even under nitrogen the reaction between (–)-dopa and  $trans\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$  took place and almost the same rotation and ORD curves as in air (Fig. 6) were observed, but the oxidation was suspended halfway without proceeding to the end.




Fig. 6. Oxidation of (–)-dopa by the optically inactive complexes, (1)  $trans\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$ ; (2)  $cis\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$ ; (3)  $cis\text{-[Co(NH}_3\text{)(en)}_2\text{(H}_2\text{O)}\text{]Br}_2$ ; (4)  $cis\text{-[CoCl(NH}_3\text{)(en)}_2\text{]Br}_2$  (reference). Cell : 1 cm.

Next, instead of a *bis*(ethylenediamine) complex, a mixture of  $\text{CoCl}_2$  and ethylenediamine solution in the ratio of 1 : 2 was tested for oxidation of (–)-dopa. The same characteristic ORD curve was again observed. Under nitrogen, however, oxidation did not occur and no such ORD curve was observed. This is because oxygen is necessary for the formation of the *bis*(en)cobalt(III) complex from  $\text{CoCl}_2$  and ethylenediamine and its formation is not possible under nitrogen.

The above fact that  $trans\text{-[CoCl}_2\text{(en)}_2\text{]Cl}$  reacts most rapidly with (–)-dopa indicates the structure of the intermediate to be *trans* in relation to the two ethylenediamine molecules. Complexes having the *cis-bis*(ethylenediamine) ligands are slow in oxidizing action because it takes some time to transform from the *cis* to the *trans* structure.

Further, cobalt(III) amines like  $\text{[CoCl(NH}_3\text{)}_4\text{]Cl}$ ,  $\text{[CoCl}_2\text{(NH}_3\text{)}_3\text{]Cl}$ , and  $cis\text{-[Co(NH}_3\text{)}_4\text{(H}_2\text{O)}\text{]Cl}$  were studied for

the reaction with (–)-dopa, which have four ammonia molecules instead of two ethylenediamine molecules in the bis(ethylenediamine) complexes. The concentrations of the reactants were the same as in *Measurements*. ORD curves, similar to those of the bis(ethylenediamine) complexes were observed (Fig. 7) but the peaks at 460 nm and 580 nm observed for bis(ethylenediamine) complexes shifted to 440–490 nm and ~550 nm (shoulder) in the ammine complexes, respectively.




Fig. 7. ORD curves of the reaction mixtures of (–)-dopa and [CoCl(NH₃)₅]Cl₂ (full line, 30 min from the beginning) and *cis*-[Co(NH₃)₄(H₂O)₂]Cl₂ (dotted line, 20 min).

(6) *Ratio of cobalt(II) to dopa in the reaction intermediate :*

The ratio of cobalt(II) to dopa or its oxidation product in the intermediate was determined using the so-called molar ratio method. First, the concentration of (–)-dopa was kept at  $2.94 \times 10^{-3}$  mol/l (after mixing) while changing the concentrations of *trans*-[CoCl₂(en)₂]Cl from  $0.75 \times 10^{-3}$  to  $12 \times 10^{-3}$  mol/l, and optical rotation at 460 nm was measured. Next, the concentration of the complex *trans*-[CoCl₂(en)₂]Cl was kept at  $2.94 \times 10^{-3}$  mol/l while changing the concentration of (–)-dopa from  $0.75 \times 10^{-3}$  to  $12 \times 10^{-3}$  mol/l. In both the cases, the 1 : 1 ratio of cobalt(II) to dopa was found in the intermediate.

In order to know the effect of phosphate buffer, a KOH solution was used to adjust the initial pH of the reaction solution of (–)-dopa and *trans*-[CoCl₂(en)₂]Cl at 7.2. The same ORD curve was observed, indicating that phosphate ion did not participate in the intermediate formation.

(7) *Oxygen uptake during oxidation of (–)-dopa :*

Fig. 8 shows the results of oxygen uptake during the reaction of (–)-dopa with (–), (+) and *r*-[CoCl(NH₃)(en)₂]Br₂. The solutions used were  $1.2 \times 10^{-3}$  mol/l, 1 ml for (–)-dopa,  $1.2 \times 10^{-3}$  mol/l, 1 ml for each cobalt complex, and 0.2 mol/l, 1 ml for phosphate buffer. Three curves agreed with each other within experimental errors and about 2.1 moles of oxygen were consumed for oxidation of one mole of (–)-dopa in 150 hr. No asymmetric oxidation was found.




Fig. 8. The oxygen uptake during the oxidation of (–)-dopa by (O)(+)-, (□)(–) and (Δ)*r*-[CoCl(NH₃)(en)₂]Br₂.

(8) *Circular dichroism of the intermediate compound :*

The circular dichroism spectra in the reaction of (+)-dopa with *trans*-[CoCl₂(en)₂]Cl and [CoCl(NH₃)₅]Cl₂ are shown in Fig. 9. The experimental conditions are the same as those in Figs. 6 and 7, where (–)-dopa was used as the substrate. Three peaks of the CD curve in Fig. 9 are in the longer wavelength region compared with the cobalt(III) complexes of similar types, but it is not yet possible to analyze the curve because information on the CD of optically active cobalt(II) complexes is scarce.




Fig. 9. Circular dichroism spectra observed during oxidation of (+)-dopa by *trans*-[CoCl₂(en)₂]Cl (full line, after 1 hr) and [CoCl(NH₃)₅]Cl₂ (dotted line, after 5 min). Cell : 1 cm.

( ) *The structure of the intermediate and the mechanism of the oxidation of (–)-dopa :*

On the basis of the results obtained, the oxidation intermediate of (–)-dopa with a characteristic ORD is presumed to have the following structure :

- i) a cobalt(II) complex.
- ii) two ethylenediamine ligands in the *trans* position.
- iii) ratio of (–)-dopa or its partial oxidation product to cobalt(II) is 1 : 1.

The presumed oxidation mechanism of (-)-dopa by the cobalt(III) complexes is summarized in Fig. 10. In the reaction, first dopa coordinates to the cobalt(III) complex with one of the OH groups of catechol component. The oxidation is initiated by an electron transfer from dopa to cobalt(III) forming a cobalt(II) complex which makes the dissociation of a proton from an OH group easier and increases the hydrogen ion concentration of the reaction medium. This process is possible even under nitrogen but further oxidation of dopa needs oxygen and under nitrogen the reaction stops at this point where a slightly yellow colour appears in the reaction solution.




Fig. 10. Oxidation reaction scheme of dopa by cobalt(III) complexes.

#### Conclusion :

In 1929 Shibata and Tsuchida reported the asymmetric oxidation of dopa by an optically active cobalt(III) complex<sup>3</sup>. Our experiments to reproduce

their results failed, but an interesting oxidation reaction of optically active dopa was found which includes the formation of an intermediate, a cobalt(II) complex coordinated by dopa or its partial oxidation product.

In addition to dopa, Shibata with his co-workers studied the oxidation of (+)-D-catechin (3,3',4',5,7-flavapentol) by optically active (+)- and (-)-[CoCl(NH<sub>3</sub>)(en)<sub>2</sub>]Br<sub>2</sub><sup>4</sup>. In this case they observed that oxygen was absorbed for the system (+)-D-catechin + (+)-complex more rapidly than for the system (+)-D-catechin + (-)-complex. This fact was confirmed by our unpublished experiments but it is not possible at present to study this problem further.

#### References

1. Y. SHIBATA and K. SHIBATA, *J. Chem. Soc. Japan*, 1920, 41, 35; *Acta Phytochimica*, 1929, 4, 363.
2. The studies published from 1920 till 1936 were translated and published in a book form. K. SHIBATA and Y. SHIBATA, "Katalytische Wirkungen der Komplexverbindungen", Tokyo, 1936.
3. Y. SHIBATA and R. TSUCHIDA, *Bull. Chem. Soc. Japan*, 1929, 4, 142.
4. Y. SHIBATA, YASUO TANAKA and SHIRO GODA, *Bull. Chem. Soc. Japan*, 1931, 6, 210.
5. A part of this work was presented in the 11th International Conference on Coordination Chemistry, Israel in 1968.
6. W. LANGENBECK *et al.*, *Chem. Ber.*, 1961, 94, 2271.
7. M. HATANO *et al.*, *Kogyo Kagaku Zasshi*, 1969, 72, 474; *Bull. Chem. Soc. Japan*, 1970, 43, 265; *Makromol Chem.*, 1971, 141, 11, 31.
8. A. GERGELY and T. KISS, *Inorg. Chim. Acta*, 1976, 16, 51.
9. A. GERGELY and T. KISS, "Metal Ions in Biological Systems", Marcel Dekker, Inc., New York and Basel, 1979, Vol 9, p. 144.
10. References cited in the Gmelins Handbuch der anorganischen Chemie, Kobalt, B, 1964.
11. A. WERNER, *Ber.*, 1911, 44, 1887.


# Optical Inversion of the *cis*(NO<sub>2</sub>), *trans*(N), *cis*(O)-bis(Aminocarboxylato)dinitrocobaltate(III) Ion\*\*

MILENKO B. ČELAP\*, LJERKA J. ALJANČIĆ and TOMISLAV J. JANJIĆ

Institute of Chemistry, Faculty of Sciences, University of Beograd, P.O. Box 550, 11001 Beograd, Yugoslavia

The inversion kinetics of optical isomers of *cis*(NO<sub>2</sub>), *trans*(N), *cis*(O)-dinitrobis(aminocarboxylato)cobaltate(III) ions, containing various α- and β-amino acid residues (glycine, S-aminobutyric acid, S-leucine and β-alanine) have been studied. The inversion process was followed polarimetrically in sodium nitrate solution, between 55 and 95° (I = 0.15). It was established that the inversion of the *cis*(NO<sub>2</sub>), *trans*(N), *cis*(O) optical isomer of the dinitro-bis(β-alaninato)cobaltate(III) ion, in which β-alanine forms six-membered ring, is faster than the inversion of all other corresponding isomers containing five-membered aminocarboxylato ligand rings. In addition, it was assumed that the *cis*(NO<sub>2</sub>), *trans*(N), *cis*(O) optical isomers of dinitrobis(aminocarboxylato)cobaltate(III) complexes containing α- and β-aminocarboxylato residues, respectively, rearrange via an intramolecular mechanism which involves the bond rupture between one end of the aminocarboxylato ligand and the central ion.

In our previous papers<sup>1</sup> the synthesis of several series of geometrical isomers of complexes of bis(aminocarboxylato)dinitrocobaltate(III) type, containing various α- and β-amino acid residues, respectively, were described. In another paper<sup>2</sup>, we also reported the studies on the isomerization reactions of four geometrical isomers of the diglycinatodinitrocobaltate(III) ion (Fig. 1). The results of experiments between 65 and 95° in neutral solution are consistent with the stoichiometric mechanism:



In addition, we investigated<sup>3</sup> the racemization of the isomer I, i.e. of (+)-*cis*(NO<sub>2</sub>), *cis*(N), *cis*(O)-diglycinatodinitrocobaltate(III) ion.

Continuing these investigations, the inversion reactions of the optical isomers of *cis*(NO<sub>2</sub>), *trans*(N), *cis*(O)-bis(aminocarboxylato)dinitrocobaltate(III) ions (IV) containing various α- and β-amino acid residues are described in the present communication. The inversion process was followed polarimetrically in sodium nitrate solution (I = 0.15) between 55 and 95°.

## Experimental

### Preparation of the complexes:

All the investigated optical isomers were prepared as described earlier: glycinate (gly) complexes<sup>1,2</sup>, β-alaninato (β-ala) enantiomers<sup>4</sup>, S-aminobutyrate (S-abu) diastereomers<sup>4</sup> and S-leucinato (S-leu) diastereomers<sup>1</sup>.




Fig. 1. The five geometric isomers of diglycinatodinitrocobaltate(III) ion. Isomers I-IV have been isolated. Isomer V has not been observed.

\*\*Part of these results was presented at the 8th Conference on Coordination Chemistry in Smolenice (Bratislava), Czechoslovakia, 1980.

**Kinetic experiments :**

Inversion reactions were studied by heating 0.5 cm<sup>3</sup> of aqueous solutions (having a concentration of 0.05 mol/dm<sup>3</sup>) of the corresponding enantiomer or diastereomer, in glass ampules placed in an ultrathermostat (Thermostat Type NBE, Medingen, Dresden). Since paper chromatographic studies had shown that the  $(-)-_{88}, \text{cis}(\text{NO}_2)\text{-trans}(\text{N})\text{-cis}(\text{O})$ -enantiomer of dinitrobis(*l*-alaninato)cobaltate(III) ion is partially decomposed at temperatures above 80°, the corresponding kinetic racemization experiments were carried out at 55, 65, 75 and 80°, respectively. The ionic strength was 0.15, adjusted with sodium nitrate. In course of the kinetic experiments the ampules were taken out from the thermostat at given time intervals and quickly cooled in ice water. Solutions from the ampules were quantitatively transferred into a 10 cm<sup>3</sup> volumetric flask, which was then filled up to the mark with distilled water. Optical rotations of the solutions obtained were measured in a Perkin Elmer 141 MC Digital Polarimeter at sodium line ( $\pm 0.002^\circ$ ).

In each experiment, it was checked whether the substance studied had either partially decomposed or isomerized in course of heating at the above mentioned temperatures. This was accomplished by paper chromatographing the heated solutions or by taking their visible spectra; the  $R_f$  values as well as the electronic spectra thus obtained were compared with those obtained with the samples of substances which had not been heated.

**Evaluation of the kinetic parameters :**

In case of a reversible first order reaction



the change of concentration of the component B with time is given by the equation :

$$[B] = [\bar{B}] / 1 + e^{-(k_1 + k_{-1})t} \quad \dots (1)$$

where  $[B]$  denotes the concentration of the component B, and  $[\bar{B}]$  its equilibrium concentration<sup>6</sup>.

Expanding  $e^{-(k_1 + k_{-1})t}$  as a power series, gives :

$$[B] = [\bar{B}] \left\{ \frac{(k_1 + k_{-1})t}{1!} - \frac{(k_1 + k_{-1})^2 t^2}{2!} + \dots \right\} \quad \dots (2)$$

Dividing the equation (2) with  $t$  the following is obtained :

$$\frac{[B]}{t} = [\bar{B}] \left\{ \frac{(k_1 + k_{-1})}{1!} - \frac{(k_1 + k_{-1})^2 t}{2!} + \dots \right\} \quad \dots (3)$$

The above equation shows that the graphic representation of  $\frac{[B]}{t}$  (the ordinate) as a function of  $t$  (the abscissa) in the beginning of the reaction, i.e. when in the equation (3) all the members except the first

two can be neglected, gives a straight line with the intercept  $[\bar{B}](k_1 + k_{-1})$  and the slope  $[\bar{B}] \frac{(k_1 + k_{-1})^2}{2}$ .

This procedure is analogous to that for irreversible first order reactions described by Hall *et al.*<sup>7</sup>

$$\text{Since } [A] + [B] = [A_0] \quad \dots (4)$$

(where  $[A_0]$  denotes the initial concentration of the component A), and

$$\frac{[\bar{B}]}{[\bar{A}]} = \frac{k_1}{k_{-1}} = K \quad \dots (5)$$

it follows that from the data obtained by the procedure described,  $k_1$ ,  $k_{-1}$  and  $[\bar{B}]$  can be calculated in the following manner :

$$k_1 = \frac{\text{intercept}}{[A_0]} \quad \dots (6)$$

$$k_{-1} = -\frac{2(\text{slope})}{\text{intercept}} - k_1 \quad \dots (7)$$

$$[\bar{B}] = -\frac{(\text{intercept})^2}{2(\text{slope})} \quad \dots (8)$$

The change in the concentration of the component B with time in course of the reaction was determined in the usual way by measuring the optical rotation of the solutions :

$$[B] = [A_0] \frac{(\alpha_A - \alpha_t)}{(\alpha_A - \alpha_B)} \quad \dots (9)$$

where  $\alpha_A$  and  $\alpha_B$  denote the optical rotations of the solutions of pure A and B components, respectively, and  $\alpha_t$  is the optical rotation of the investigated solution in course of the reaction.

**Chromatographic investigations :**

Paper chromatography of the investigated substances was carried out in a glass cylinder, height 50 cm, diameter 22 cm, by ascending method, on Whatman No. 1 paper strips (3 × 30 cm). The development was performed at  $20 \pm 2^\circ$ , the solvent system being placed into the cylinder 1 hr before development. The solvent system used was a mixture of ethyl acetate : ethanol : water (70 : 20 : 10). The solvent front travelled about 22 cm and the developing time was about 6 hr. The substances were detected by dipping the developed paper strips into ammonium sulphide solution ( $\sim 2$  mol/dm<sup>3</sup>).

**Absorption spectra :**

Absorption spectra of the investigated substances in the visible region were taken in aqueous solutions on a Perkin Elmer 137-UV spectrophotometer.

**Optical rotation :**

Optical rotation of the isomers obtained was measured at 589 nm on a Franz Schmidt & Haensch Model S Polarimeter; the measurements were performed at room temperature in 10 cm<sup>3</sup> cells with aqueous solutions, the concentrations ranging from 0.1 to 0.2 g per 100 cm<sup>3</sup>.

### Reagents :

All reagents used were of "puriss" reagent grade purity. Sodium hexanitrocobaltate(III) was a product of E. Merck, AG, Darmstadt, or Fluka AG, Buchs. S-Aminobutyric acid and S-leucine were the products of Fluka AG, Buchs, whereas glycine and  $\beta$ -alanine were obtained from Kemika, Zagreb.

### Results and Discussion

The observed first order rate constants are given in Table 1, and the corresponding activation enthalpies and entropies in Table 2 (see also Fig. 2 and 3).

( $\Delta S_{\ddagger}^{\circ} = -64.1 \text{ k cal mol}^{-1} \text{ K}^{-1}$ ) but that is not the case with the other isomer ( $\Delta S_{\ddagger}^{\circ} = -13.3$  to  $3.91 \text{ k cal mol}^{-1} \text{ K}^{-1}$ ). On the basis of these, one can conclude that the inversion mechanisms of the two isomers are different. As is known<sup>8</sup>, an intramolecular mechanism without bond rupture, the trigonal twist mechanism, might account for the low enthalpy and the highly negative entropy of activation. Because of this, we assumed in our earlier paper<sup>8</sup> such a mechanism for the racemization process of the *cis,cis,cis*-isomer. This hypothesis is supported by the fact that an examination of the stereochemistry of the two investigated isomers reveals that the *cis,cis,cis*-isomer can theoretically racemize by

TABLE 1—FIRST ORDER INVERSION RATE CONSTANTS ( $k_{\text{obs}} \cdot 10^4 \text{ sec}^{-1}$ ) OF OPTICAL ISOMERS OF *cis*(NO<sub>2</sub>),*trans*(N), *cis*(O)-bis(AMINOCARBOXYLATO)DINITROCOBALTATE(III) ION<sup>a</sup>

Complex	Temperature (°C)											
	40	45	50	55	60	65	70	75	80	85	90	95
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{[Co(NO}_2)_2\text{gly}_2]^{-}$	—	—	—	—	13±0.1	2.8±0.2	3.5±0.2	11±1	15±1	—	62±6	—
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-abu)}_2]^{-}$	—	—	—	—	—	2.1±0.5	—	5.4±0.2	—	14±1	—	43±1
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-leu)}_2]^{-}$	—	—	—	—	—	2.1±0.5	—	5.5±0.3	—	15±1	—	47±1
$\Delta^{-}(\text{-})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-abu)}_2]^{-}$	—	—	—	—	—	1.8±0.5	—	4.8±0.6	—	12±1	—	36±1
$\Delta^{-}(\text{-})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-leu)}_2]^{-}$	—	—	—	—	—	1.0±0.4	—	3.1±0.3	—	7.7±0.2	—	21±1
$\Delta^{-}(\text{-})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(}\beta\text{-ala)}_2]^{-}$	—	—	—	14±2	—	30±3	—	70±4	120±20	—	—	—
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{-cis, cis, cis- [Co(NO}_2)_2\text{gly}_2]^{-}$	120±5	140±10	150±5	170±10	—	—	—	—	—	—	—	—

\* The observed rate constants are given in the form of  $X \pm t(P; f) \frac{\sigma}{\sqrt{n}}$ , where X represents their mean values obtained by the least squares method,  $t(P; f)$  is student's factor for  $P=95\%$ ,  $f=n-2$  degrees of freedom and  $\frac{\sigma}{\sqrt{n}}$  standard deviation of the mean (J. M. Wilson *et al*, Experiments in Physical Chemistry, II Ed., Pergamon Press, Oxford, 1968, p 364)

TABLE 2—ACTIVATION PARAMETERS OF INVERSION REACTIONS OF OPTICAL ISOMERS OF *cis*(NO<sub>2</sub>),*trans*(N),*cis*(O)-bis(AMINOCARBOXYLATO)DINITROCOBALTATE(III) ION

Complex	$\Delta H^{\circ} \text{ k cal mol}^{-1}$	$\Delta S_{\ddagger}^{\circ} \text{ k cal mol}^{-1} \text{ K}^{-1}$
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{[Co(NO}_2)_2\text{gly}_2]^{-}$	29.7	3.91
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-abu)}_2]^{-}$	24.0	-11.9
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-leu)}_2]^{-}$	24.6	-10.1
$\Delta^{-}(\text{-})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-abu)}_2]^{-}$	23.6	-13.3
$\Delta^{-}(\text{-})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(S-leu)}_2]^{-}$	24.4	-11.8
$\Delta^{-}(\text{-})_{\text{ccc}}\text{[Co(NO}_2)_2\text{(}\beta\text{-ala)}_2]^{-}$	18.5	-24.6
$\Lambda^{+}(\text{+})_{\text{ccc}}\text{-cis, cis, cis- [Co(NO}_2)_2\text{gly}_2]^{-}$	3.87	-64.1 <sup>a</sup>

<sup>a</sup> For 45°

It can be seen from these data that the inversion rate of *cis, cis, cis*-isomer is very much greater than that of the *cis*(NO<sub>2</sub>),*trans*(N),*cis*(O)-isomer. This is in accordance with the rather low activation enthalpy of the former isomer, which amounts to  $3.87 \text{ k cal mol}^{-1}$  [the corresponding values for the *cis*(NO<sub>2</sub>), *trans*(N), *cis*(O)-complexes, which also contain  $\alpha$ -aminocarboxylato ligands, are between  $23.6$  to  $29.7 \text{ k cal mol}^{-1}$ ]. In addition, the *cis, cis, cis*-isomer has a highly negative activation entropy




Fig. 2. A typical plot of  $\log \alpha$  vs time [obtained during the racemization of  $\Delta^{-}(\text{-})_{\text{ccc}}\text{-cis(NO}_2\text{)-trans(N), cis(O)-bis(}\beta\text{-alaninato)dinitrocobaltate(III) ion}$ ].

a trigonal twist whereas the inversion of the *cis*(NO<sub>2</sub>),*trans*(N),*cis*(O)-isomer by a twist mechanism is not possible.

From the data obtained it can also be seen that the optical inversion of the *cis*(NO<sub>2</sub>),*trans*(N),*cis*(O)-complex containing  $\beta$ -alaninato ligands is considerably faster in comparison to the complexes




Fig. 3. A typical plot of  $\log k$  vs  $\frac{1}{T}$  [obtained for racemization process of  $\Delta(-)-cis(NO_2)-trans(N),-cis(O)-bis(\beta\text{-alaninato})dinitrocobaltate(III)$  ion].

of the same geometrical configuration containing  $\alpha$ -aminocarboxylato ligands. This is in accordance with its relatively lower activation enthalpy, as well as with the known fact<sup>9</sup> about greater stability of five-membered rings in comparison to six-membered ones. On the basis of this one could assume that the optical inversion of the investigated complexes takes place by bond rupture between aminocarboxylato ligand and Co(III). It is, however, unlikely that during this process a complete chelate ligand dissociation occurs because of relatively modest activation enthalpies (not higher than 30 k cal mol<sup>-1</sup>). In addition, if such a complete dissociation happens a noticeable complex decomposition would be expected. That was never observed. In this connection, it seems more probable that under the labilising influence of the *trans* NO<sub>2</sub>-group, the Co-O bond is broken rather than the Co-N bond (from aminocarboxylato ligand).

The assumed bond rupture intramolecular mechanism is supported by the fact that the activation energy for the substitution process of the NO<sub>2</sub>-groups in hexanitrocobaltate(III) ion by aminocarboxylato ligand, for which reaction a dissociation mechanism is accepted, amounts to about 37 k cal

mol<sup>-1</sup>, which is a much higher value compared to the values obtained in the present study. Finally, the proposed mechanism is also in accordance with the results obtained by York<sup>11</sup>, who established that an exchange involving <sup>15</sup>NO<sub>3</sub><sup>-</sup> and *cis*-Na[Co(acac)<sub>3</sub>(NO<sub>2</sub>)] is extremely slow.

#### Acknowledgment

The authors are grateful to the Serbian Republic Research Fund for financial support, and to Dr. Ruzica Tasovac and Mrs. Zorica Lukanic' for elemental microanalyses. The authors also thank Mr. P. N. Radivojša for help in typing the manuscript.

#### References

1. M. B. ČELAP, S. M. NEŠIĆ, M. J. MALINAR, T. J. JANJIĆ and P. N. RADIVOJŠA, *Glasnik Hem. društva Beograd*, 1974, 39, 559 and references therein.
2. M. B. ČELAP, J. K. BEATTIE, T. J. JANJIĆ and P. N. RADIVOJŠA, *Inorg. Chim. Acta*, 1974, 10, 21.
3. M. B. ČELAP, D. J. RADANOVIĆ and T. J. JANJIĆ, *Inorg. Chem.*, 1965, 4, 1494.
4. M. B. ČELAP, T. J. JANJIĆ and D. J. RADANOVIĆ, *Inorg. Synth*, 1967, 9, 173.
5. M. B. ČELAP, R. G. DENNING, D. J. RADANOVIĆ and T. J. JANJIĆ, *Inorg. Chim. Acta*, 1971, 5, 9.
6. N. M. EMANUEL and D. G. KNORRE, "Kurs Khimicheskoy Kinetiki", Vysshaya Shkola, Moscow, 1974, p. 143.
7. K. J. HALL, T. I. QUICKENDEN and D. W. WATTS, *J. Chem. Educ.*, 1976, 53, 493.
8. N. SERPONE and D. BICKLEY, *Prog. Inorg. Chem.*, 1972, 17, 391.
9. R. W. PARRY, "Chelation and the Theory of Heterocyclic Ring Formation Involving Metal Ions", in J. C. BAILAR, Jr. (Ed.), "The Chemistry of the Coordination Compounds", ASC Monograph, Ser. No. 131, Reinhold Publ. Corp., New York, 1956, p. 227.
10. M. B. ČELAP, T. J. JANJIĆ and P. N. RADIVOJŠA, *Rev. Chim. Min.*, 1973, 10, 607.
11. R. J. YORK, "A Synthetic, Structural and Kinetic Study of *bis* and *tris*  $\beta$ -Diketonato Cobalt(III) Complexes", Ph.D. Thesis, University of Massachusetts, 1969; *Dissertation Abst.*, 1970, 30B, 4031.



# The Deuterium Isotope Effect on the Pfeiffer Effect in Optically Labile Coordination Compounds

STANLEY KIRSCHNER and JOANNE GABAY

Department of Chemistry, Wayne State University, Detroit, Michigan 48202, U.S.A.

**T**HE Pfeiffer Effect<sup>1</sup> is the change in optical rotation of an optically active system (usually a solution of one enantiomer of an optically active compound, called the "environment substance"), upon the addition of a racemic mixture of a dissymmetric, optically labile coordination compound. Considerable work has been done on this effect by Brasted, Yoneda, Brittain, Kirschner and others<sup>2-11</sup>, and several proposed mechanisms to explain it have been described in an excellent review by Schipper<sup>12</sup>.

The Pfeiffer effect has been utilized for the study of the resolution and racemization of optically active coordination compounds<sup>13</sup> and for studies of the optical properties of complexes which are extremely labile and which racemize very rapidly<sup>14</sup>. Recent work<sup>15,16</sup> has also been done on applying the Pfeiffer effect to the determination of absolute configurations of optically active complexes which are also optically labile and organic compounds and on explaining the nature of the "equilibrium displacement" mechanism proposed for the effect. In this paper further work is described on the nature and mechanism of the Pfeiffer effect and on the utilization of the deuterium isotope effect to assist in the elucidation of the mechanism.

## The equilibrium displacement mechanism for the Pfeiffer effect:

It has been proposed by Dwyer *et al.*<sup>3</sup> that an equilibrium exists between the enantiomers of a racemic mixture of an optically labile, dissymmetric complex in solution, with the equilibrium constant being equal to unity. However, in the presence of an appropriate optically active environment substance (one which will cause the Pfeiffer effect to occur and which will not displace a coordinated ligand during the time required for the appearance of the Pfeiffer effect), this equilibrium is shifted toward one of the enantiomers, with the equilibrium constant becoming greater or less than 1, depending on the direction of the shift.

If such a shift occurs, it should be possible to identify the enantiomer produced in excess by means of techniques such as optical rotatory dispersion and circular dichroism, as well as by a "time" experiment (see below). For example, Fig. 1 shows the circular dichroism spectrum of (+)<sub>D</sub>[Cr(ox)<sub>3</sub>]<sup>3-</sup> in water along with the Pfeiffer circular dichroism spectrum of D,L-[Cr(ox)<sub>3</sub>]<sup>3-</sup> in water containing *d*-cinchonine hydrochloride as the environment substance ('ox' = oxalate anion). It can be seen that the two spectra are essentially the same, the difference in intensity

between them being due to the different concentrations of the optically active complex ion in solution in the two cases.




Fig. 1. (A) Circular dichroism spectrum of (+)<sub>D</sub>[Cr(ox)<sub>3</sub>]<sup>3-</sup> in H<sub>2</sub>O (B) Pfeiffer circular dichroism spectrum of D,L-[Cr(ox)<sub>3</sub>]<sup>3-</sup> in water containing *d*-cinchonine hydrochloride (all measurements at 23°).

The "time" experiment referred to above is described in Fig. 2. In this figure it can be seen that the optical rotation of *levo*-malic acid does not change with time. However, when D,L-[Ni(*o*-phen)<sub>3</sub>]<sup>2+</sup> is added to the solution (at time=0),




Fig. 2. The "time" experiment. The Pfeiffer effect and subsequent racemization in water of D,L-[Ni(*o*-phen)<sub>3</sub>]<sup>2+</sup> with *levo*-malic acid as the environment substance. (A) *Levo*-malic acid in water; (B) *Levo*-malic acid + D,L-[Ni(*o*-phen)<sub>3</sub>]<sup>2+</sup>; (C) the system in (B) + added *dextro*-malic acid after 123 hr; (D) Racemization of the system in (C) (of the excess L-[Ni(*o*-phen)<sub>3</sub>]<sup>2+</sup> produced via the Pfeiffer effect).

the Pfeiffer effect develops, with its maximum being attained at about 120 hr (*o*-phen = *ortho*-phenanthroline). If, at that time, exactly the same concentration of *d*-malic acid is added to the system, then this has the effect of eliminating or "optically neutralizing" the optically active environment, with the result that the excess of the *levo* enantiomer of

the complex undergoes racemization until the optical rotation of the substance disappears. Note however that the nickel-*ortho*-phenanthroline complex retains its integrity throughout the Pfeiffer effect experiment, as evidenced by the fact that there is no change in the uv-visible spectrum of the complex throughout the entire "time" experiment. All this provides considerable support for the mechanism which proposes that one enantiomer of the complex is produced in excess during the appearance of the Pfeiffer effect.

It should be noted that, in Fig. 2, if the *d*-malic acid had not been added, then curve B would continue parallel to the horizontal axis until decomposition begins. This permits the study of many optical properties of extremely labile complexes which heretofore could not be studied because the racemization rate is so rapid that any resolved compounds would racemize too quickly to be studied. With the displaced equilibrium mentioned above continuing for some time, the excess of one enantiomer can be studied with regard to racemization rate, optical rotatory dispersion, circular dichroism, etc. This has already been achieved with certain very optically labile complexes<sup>14</sup>.

A proposed explanation for the displacement of the equilibrium between the complex enantiomers, which is postulated to occur during the Pfeiffer effect, is that hydrogen bonding occurs preferentially between electronegative atoms of an environment substance of a given absolute configuration and the  $\pi$ -electron clouds of the ligands of one enantiomer of the complex<sup>15</sup>. Such hydrogen bonding interactions to  $\pi$ -electron clouds of aromatic and unsaturated systems are known to occur with organic molecules<sup>17,18</sup>.

This proposal is a most attractive one from several standpoints. First of all it provides an explanation for the chiral discrimination which is observed to occur for the Pfeiffer effect, since molecular models of the proposed system indicate that *S*-malic acid, for example, fits quite well into the  $\Delta_s$  propeller system of the  $[\text{Ni}(\text{o-phen})_2]^{2+}$  enantiomer with no strong non-bonded hydrogen interactions, whereas the *R* enantiomer of malic acid in the same propeller system shows two strong non-bonded hydrogen interactions. Consequently, the  $\Delta_s$  configuration is stabilized by *S*-malic acid, resulting in an equilibrium shift in favour of the  $\Delta_s$  enantiomer.

Also, the initially unexpected behaviour of Pfeiffer-active systems with pH changes is explained well by this proposal. One might expect that with increasing pH, Pfeiffer activity would increase, since chiral recognition by an optically active complex cation of an anionic environment substance (e.g., *levo*-malate ion) would be expected to be greater than that for the same complex cation and a neutral environment substance (e.g., *levo*-malic acid). In fact, the opposite behaviour is observed, with the Pfeiffer activity undergoing a marked decrease with an increase in pH. This can be explained by the

hydrogen bonding proposal, since an increase in pH will result in removal of the carboxylic hydrogens, thus diminishing the ability of the proposed hydrogen bonding to occur<sup>19</sup>.

#### The Deuterium isotope effect on the Pfeiffer effect:

If the hydrogen-bonding mechanism proposed above has validity, it should be possible to observe a deuterium isotope effect in the system which utilizes *S*-malic acid as an environment substance, since, in  $\text{D}_2\text{O}$ , the hydrogens of malic acid capable of undergoing hydrogen bonding would be exchanged for deuterium. The effects of "deuterium bonding" compared to hydrogen bonding should be observable in at least two ways—(a) an expected decrease in the rate of appearance of the Pfeiffer effect due to slower "deuterium bonding" effects, and (b) a diminution in the magnitude of the Pfeiffer effect because of the lesser ability of "deuterium bonding" to occur (compared to hydrogen bonding) because of weaker electrostatic interactions.

Consequently, the entire Pfeiffer effect experiment utilizing  $\text{D,L-}[\text{Ni}(\text{o-phen})_2]^{2+}$  and *S*-(-)-*D*-malic acid was performed using  $\text{D}_2\text{O}$  as a solvent in place of water. Fig 3 shows the results of this experiment. Curve B is the Pfeiffer effect for the system in water and curve A is that for the system in  $\text{D}_2\text{O}$ . It can be seen from Fig 3 that the rate of appearance of the effect in  $\text{D}_2\text{O}$  is significantly less than that observed in  $\text{H}_2\text{O}$ . It can also be seen that the magnitude of the effect in  $\text{D}_2\text{O}$  is considerably less than in  $\text{H}_2\text{O}$ —both results being in accord with what would be expected if hydrogen bonding plays a significant role in the Pfeiffer effect.




Fig. 3. The deuterium isotope effect on the Pfeiffer effect (A)  $\text{D,L-}[\text{Ni}(\text{o-phen})_2]\text{Cl}_2$  (0.05 M) + *levo*-malic acid (0.05 M) in  $\text{D}_2\text{O}$ ; (B)  $\text{D,L-}[\text{Ni}(\text{o-phen})_2]\text{Cl}_2$  (0.05 M) + *levo*-malic acid (0.05 M) in  $\text{H}_2\text{O}$ ; (C) *levo*-malic acid (0.05 M) in  $\text{H}_2\text{O}$ .

#### Experimental

ORD and CD spectra were determined on a Cary-60 spectropolarimeter using a CD attachment for the CD spectra. Optical rotations at single wavelengths were determined on a Perkin-Elmer 141

photoelectric polarimeter. The designations "R" and "S" refer to the absolute configurations of organic compounds using the system developed by Cahn, Prelog and Ingold<sup>19,20</sup>. The optically active organic compounds used as environment substances were purchased in the purest forms available and their optical rotations were checked against the literature values. The  $D,L$ -[Ni(*o*-phen)<sub>2</sub>]Cl<sub>2</sub> complex was synthesized according to the method of Kauffman and Takahashi<sup>21</sup>. The D<sub>2</sub>O was purchased as reagent grade material in greater than 99% purity. The Pfeiffer effect studies were carried out at room temperature in solutions in which the concentrations of the complex and environment substance were 0.02 *M* and 0.04 *M*, respectively (Fig. 2), and 0.05 *M* in each (Fig. 3)

#### Conclusions :

Evidence is presented herewith in support of a generalized "equilibrium displacement" mechanism for the Pfeiffer effect and for the "hydrogen bonding" mechanism to explain this proposed equilibrium displacement. In particular, the deuterium isotope effect on the Pfeiffer effect occurs in a manner consistent with the proposed hydrogen bonding between labile protons (or deuterons) of the environment substance and the  $\pi$ -electron clouds of the ligands of optically labile, racemic complexes, thus modifying their ability to undergo configurational changes and resulting in an equilibrium displacement between the enantiomers of the complex.

#### References

1. P. PFEIFFER and K. QUEHL, *Ber.*, 1931, 64, 2667; 1932, 65, 560.
2. F. P. DWYER, E. G. GYARFAS and M. F. O'DWYER, *Nature (London)*, 1951, 167, 1036, *J. Proc. R. Soc. N. S. Wales*, 1955, 89, 146.
3. S. KIRSCHNER and N. AHMAD, *J. Amer. Chem. Soc.*, 1968, 90, 1910; *Inorg. Chim. Acta*, 1975, 14, 215; R. J. POLLOCK, S. KIRSCHNER and S. POLICEC, *Inorg. Chem.*, 1977, 16, 522.
4. S. KIRSCHNER and N. AHMAD, in S. KIRSCHNER (Ed.), "Coordination Chemistry, Proc. JOHN C. BAILAR, Jr. Symp.," Plenum Press, New York, 1969.
5. E. C. GYARFAS, *Rev. Pure Appl. Chem.*, 1954, 4, 73; J. D. GUNTER and A. F. SCHREINER, *Inorg. Chim. Acta*, 1975, 15, 117.
6. S. KIRSCHNER and N. AHMAD, in M. CAIS (Ed.), "Progress in Coordination Chemistry", Elsevier, Amsterdam, 1968; *Rec. Chem. Progr.*, 1971, 32, 29, N. AHMAD, Ph.D. Dissertation, Wayne State University, 1969.
7. E. E. TURNER and M. M. HARRIS, *Q. Rev. Chem. Soc.*, 1948, 1, 299.
8. R. C. BRASTED, T. LANDIS, E. J. KUHAJEK, P. E. R. NORDBLUM and L. MAYER, in S. KIRSCHNER (Ed.), "Coordination Chemistry, Proc. JOHN C. BAILAR, Jr. Symp.," Plenum Press, New York, 1969; J. S. MADARAS and H. G. BRITTAIN, *Inorg. Chem.*, 1980, 19, 38; *Inorg. Chim. Acta*, 1980, 42, 109, 198; *Inorg. Chem.*, 1981, 20, 959, 3007, 4267, 4273.
9. S. KIRSCHNER and K. R. MAGNELL, in "Werner Centennial" Advances in Chemistry, Series No. 62, American Chemical Society, Washington, D.C., 1966, p. 366 ff.
10. K. MIYOSHI, Y. KURODA, J. TAKEDA, H. YONEDA and I. TAKAGI, in press; K. MIYOSHI, K. SAKATA and H. YONEDA, *J. Phys. Chem.*, 1976, 80, 69; 1975, 79, 1622; K. MIYOSHI, Y. KURODA and H. YONEDA, *J. Phys. Chem.*, 1976, 80, 270, 649; H. YONEDA et al., *Inorg. Chim. Acta*, 1978, 31, L453, 1978, 28, 211, *Chem. Lett. (J.)*, 1978, 763.
11. S. KIRSCHNER, R. MORASKI, C. MUNIR, N. AHMAD and R. POLLOCK, *Rev. Roum. Chim.*, 1977, 22, 1283.
12. P. E. SCHIFFER, *Inorg. Chim. Acta*, 1975, 12, 199.
13. S. KIRSCHNER and N. AHMAD, *J. Amer. Chem. Soc.*, 1968, 90, 1910.
14. S. KIRSCHNER and N. AHMAD, *Inorg. Chim. Acta*, 1975, 14, 215.
15. S. KIRSCHNER, N. AHMAD, C. MUNIR and R. POLLOCK, *Pure Appl. Chem.*, 1979, 51, 913.
16. S. KIRSCHNER and P. SERDIUK, in B. DOUGLAS and Y. SAITO (Eds.), "Stereochemistry of Optically Active Transition Metal Compounds", American Chemical Society, Washington, D.C., 1980, p. 239 ff.
17. H. IWAMURA, *Tetrahedron Lett.*, 1970, 2227, Z. YOSHIDA and E. O. OSAWA, *J. Amer. Chem. Soc.*, 1966, 88, 4019.
18. P. J. KRUEGER and H. D. METTE, *Tetrahedron Lett.*, 1966, 1587, M. OKO and H. IWANORA, *J. Amer. Chem. Soc.*, 1967, 89, 576.
19. R. S. CAHN and C. K. INGOLD, *J. Chem. Soc.*, 1951, 612.
20. R. S. CAHN, C. K. INGOLD and V. PRELOG, *Experientia*, 1956, 12, 81.
21. G. B. KAUFFMAN and L. T. TAKAHASHI, *Inorg. Synth.*, 1966, 8, 227.

## Coordination Chemistry of Technetium as Related to Nuclear Medicine

S. C. SRIVASTAVA\* and P. RICHARDS

Medical Department, Brookhaven National Laboratory, Upton, New York 11973, U.S.A.

Significant advances have been made in the area of technetium coordination chemistry during the last five years. The main driving force behind this recent surge of interest in the field has been due to the practical application of technetium-99m in the rapidly growing speciality of nuclear medicine. Technetium-99 is one of the products of nuclear fission reactions, but it was the development of the molybdenum-99-technetium-99m generator about two decades ago that provided the basis for the development of radiopharmaceuticals routinely used in modern diagnostic applications. The chemistry of this element has proven to be quite rich owing to its multiple oxidation states and variable geometry; this can be attributed to its position in the middle of the periodic table. Diagnostic radiopharmaceuticals comprise predominantly III, IV and V oxidation states of Tc and involve a variety of coordination complexes. Even though the chemistry of Tc has been slow to evolve, recent synthetic advances have provided a more scientific basis for the study of a number of compounds with diverse coordination geometries and structures. Ligands with oxygen, nitrogen, and sulfur donor atoms have been utilized to elucidate various aspects of the coordination chemistry of Tc. Single crystal X-ray structural analysis has been extensively used to characterize Tc complexes and thus construct a firm foundation for the study of synthetic and mechanistic aspects of the chemistry of this element.

**E**VEN though technetium has been observed in some stellar materials and despite some evidence suggesting that a continuous production of the element is taking place in the universe<sup>1</sup>, evidence for the occurrence of primordial terrestrial technetium has not yet materialized despite the extensive searches using sophisticated radiochemical procedures. On a geological time scale, all isotopes of this element are unstable and thus throughout the early history of chemistry, no technetium was available for study. Artificial production of technetium in minute quantities was reported by Perrier and Segre in 1937<sup>2</sup>, and chemical quantities became available in the early 1960's (ca \$3000/g). At the present time <sup>99</sup>Tc is produced in kilogram amounts as a fission product and is available at about \$50 per g. <sup>99</sup>Tc is a soft beta emitter ( $\beta^-$  max 0.292 MeV) with a  $2.13 \times 10^5$  yr half-life and thus presents only a minor radiation hazard. Milligram quantities can safely be manipulated by following a few simple precautions. Virtually all chemical studies so far have employed <sup>99</sup>Tc.

Since the mid 1970's there has been a dramatic surge of activity in the area of synthetic and structural chemistry of technetium. This is attributable to the desire of inorganic chemists to acquire a basic understanding of the chemistry of this sparsely studied element. A very great driving force has been provided by the widespread use of technetium-99m in diagnostic nuclear medicine procedures and by the ever growing realization that further advances in the area of <sup>99m</sup>Tc radiopharmaceuticals will greatly depend on basic research effort on solution chemistry, coordination complexes, and mechanistic studies of Tc compounds<sup>3</sup>.

### *Uses in nuclear medicine :*

To carry out diagnostic nuclear medicine procedures, a "radiopharmaceutical" (some chemical form of a gamma emitting radionuclide) is injected into a patient and the biodistribution of the radiopharmaceutical is monitored by suitable external imaging devices such as a gamma camera. Among the few radionuclides available for these applications, <sup>99m</sup>Tc has, by far, the optimum properties and is clearly the "ideal" radiotracer<sup>4</sup>. The monoenergetic gamma emission of 140 keV is well suited for use with the present day gamma cameras. This energy provides excellent penetration from deep seated organs in the body and the loss during collimation is minimal. A total lack of beta emission results in the absence of unnecessary absorbed radiation dose to the patient. The 6.02 hr half-life cuts down the radiation dose further by minimizing continued patient exposure after completion of the diagnostic procedure. Because of reduced radiation dose, large amounts of radioactivity can be administered in order to provide good resolution and increased information content in the collected images. Very frequent repetition of studies is also facilitated. <sup>99m</sup>Tc is inexpensive and is readily available as <sup>99m</sup>TcO<sub>4</sub><sup>-</sup> with the advent of the <sup>99</sup>Mo/<sup>99m</sup>Tc generator<sup>5,6</sup>. Of equal importance is the fact that the varied chemistry of technetium in its many oxidation states allows the incorporation of <sup>99m</sup>Tc into a variety of radiopharmaceuticals that are specific for different organs<sup>7</sup>. Without the possibility of appropriate chemical manipulations, the preeminence of <sup>99m</sup>Tc among the medically useful radionuclides would not have been established. The use of <sup>99m</sup>Tc for diagnosis has proven so successful

that in the U. S. alone at present more than 10 million nuclear medicine scans are conducted annually utilizing some chemical form of this radionuclide.

#### *Technetium-99m radiopharmaceuticals*

A variety of  $^{99m}\text{Tc}$  imaging agents are in current use. These are generally coordination complexes of technetium prepared at very dilute concentrations dictated by the use of generator produced "no-carrier-added"  $^{99m}\text{TcO}_4^-$ . The structure and chemical reactivity of these agents have only recently begun to be adequately characterized. Only nanogram quantities of  $^{99m}\text{Tc}$  are present in most formulations and this makes most chemical measurements difficult, if not impossible. The majority of clinically used agents are produced with the use of commercially available derivatizing "kits" that generally contain a reductant (usually  $\text{Sn}^{2+}$  ion) in the presence of a complexing agent. Based on their biological behaviour,  $^{99m}\text{Tc}$  labeled compounds can be categorized as belonging to two broad classes :

- (i) agents where  $^{99m}\text{Tc}$  functions as a true tracer, that is, the labeled compound retains its biodistribution after being tagged with  $^{99m}\text{Tc}$ . This category includes cells, particles, macromolecules and bioactive compounds. The presence of technetium produces small or no perturbation,
- (ii) compounds whose biodistribution to a large extent is determined by the properties of the complex itself and by the nature of the particular technetium center. This class comprises most low molecular weight technetium coordination complexes that are in use at the present time.

The lack of a clear understanding of the structure-activity relationships of technetium labeled compounds has greatly hampered the design of agents with predictable biological behaviour and that could be targeted to specific organs and tissues with a high degree of selectivity. A more rational approach (than the empirical ones used in the past) that is being followed to some extent presently involves first the preparation and chemical characterization of macroscopic amounts of a  $^{99}\text{Tc}$  complex and then the manipulation of preparative conditions to successfully synthesize an identical complex at the no-carrier-added levels of  $^{99m}\text{TcO}_4^-$  encountered in the generator eluates. The correspondence at the two concentration levels can usually be established by sensitive chromatographic methods (especially HPLC) and various other techniques including biological studies using small animals. Much concern has been expressed regarding the translation of results obtained at the carrier level of  $^{99}\text{Tc}$  to those at the no-carrier-added level of  $^{99m}\text{Tc}$ . In general, the differences are explainable and the correspondence is fairly satisfactory.

A number of agents labeled with  $^{99m}\text{Tc}$  including inorganic and organic ligands, colloids and particles, cellular elements of blood, and various biological macromolecules are routinely used in present day

diagnostic nuclear medicine<sup>3</sup>. A brief list which includes potential new radiopharmaceuticals as well is as follows :

- (i) phosphates, diphosphonates and imidodiphosphonates for the imaging of the skeletal system,
- (ii) EDTA, DTPA, gluconate, glucoheptonate, ascorbate, dimercaptosuccinic acid, citrate and cysteine for kidney imaging and for determination of renal function,
- (iii) iminodiacetate derivatives, especially acetanilido-IDA ligands, pyridoxylidene glutamate and other Schiff bases, 8-hydroxyquinoline derivatives, etc for hepatobiliary function studies,
- (iv) pyrophosphate, tetracycline and glucoheptonate for myocardial infarct localization,
- (v) ditertiary arsine and phosphine ligands for the imaging of myocardium,
- (vi) human serum albumin (HSA) for blood pool imaging and for determination of plasma volumes and fibrinogen and plasmin for clot localization,
- (vii) erythrocytes (red blood cells) for blood pool imaging, red cell mass determination, nuclear cardiology, detection of vascular malformations, spleen imaging and detection of gastrointestinal tract bleeding,
- (viii) sulphur colloid and phytate for the imaging of the reticuloendothelial system (liver, spleen, bone marrow) and antimony sulphide colloid for lymphoscintigraphy and
- (ix) macroaggregates and microspheres of HSA for evaluation of the lung arteriolar capillary bed and for blood perfusion of various organs including the heart.

It is only recently that concerted efforts have begun in order to characterize many of the above agents with respect to their purity, structure, chemical reactivity and various physico-chemical parameters<sup>3</sup>.

#### **Chemistry of Technetium**

The systematic chemistry of technetium is relatively unexplored although several advances have been made very recently. A number of reviews are available which summarize the existing knowledge on various aspects of the chemistry of this element and their interrelationships with nuclear medicine<sup>7-14</sup>. However, it should be noted that some of the earlier reviews contain incorrect results which no doubt were due to the difficulties inherent in working with small quantities of radioactive materials.


#### *Electrochemistry* :

The polarographic behaviour of technetium has been the subject of numerous studies. Techniques employed include classical d.c. polarography as well as a.c. polarography, chronopotentiometry, fast

polarography, pulse polarography and cyclic voltammetry, etc. In addition, allied techniques such as coulometry and amperometry have also been utilized. Despite the fact that most technetium reductions at the dropping mercury electrode are usually irreversible, polarographic techniques have afforded a means of establishing the oxidation states which are stabilized in various media. Despite a large early literature on the polarographic reduction of technetium<sup>8</sup>, considerable confusion exists as to the exact number of electrons involved in the various reduction processes. The initial 3- or 4-electron reduction waves occur in acidic media at sufficiently positive potentials providing satisfactory data. Results are unreliable in the presence of highly acidic solutions, especially HCl, because of the side reactions due to the dissolution of mercury and subsequent reduction of pertechnetate. The data obtained using hydrochloric acid at a concentration of 0.1 M or more as an electrolyte should thus be interpreted with caution. Reductions in buffered acidic media take place in multiple steps. A rather well formed first wave occurs for a diffusion controlled four-electron reduction and it shifts with pH approximately as follows :

$$E_{\frac{1}{2}} = A - 0.10 \text{ pH} \quad (\text{pH } 0-7) \quad \dots (1)$$

where A is +0.06, +0.05 and +0.12 V for perchloric, hydrochloric and sulphuric acids, respectively. A subsequent wave at -0.9 V corresponds to the three-electron reduction to the metal :



If the pre-contact of the solution with mercury has not been carefully avoided, the data in hydrochloric and sulphuric acid media often show equal intensity waves I (4e<sup>-</sup>) and II (3e<sup>-</sup>). The relative heights, however, are in better agreement in perchloric acid media. The half-wave potential for the first wave is not affected significantly by the presence of complexing agents, the rate-determining step being :



The HTcO<sub>4</sub><sup>-</sup> undergoes a rapid sequence of fast reactions to produce technetium(III). Using cyclic voltammetry or anodic-sweep pulse polarography, the technetium(III) can often be reoxidized to technetium(IV) or even technetium(V)<sup>15</sup>. The second wave at -0.9 V gives only an upper limit for *n* (electron change) because of the presence of a catalytic component. Further waves occurring at more cathodic potentials are very large and obviously catalytic.

In buffered alkaline media, several waves are also found but the wave heights do not often correspond to integral values of *n*. Several workers have found a rather well defined wave at -0.8 V regardless of the presence of complexing agents<sup>15</sup>. It was postulated that a one-electron change resulting in the formation of technetate ion, TcO<sub>4</sub><sup>2-</sup>, an unstable species in water, accounts for the rate-determining step. Non-integral values between 2 and 4 were

reported for the total number of electrons transferred. The second wave at about -0.0 V corresponds to a value of *n* of between 4 and 5. In unbuffered neutral or alkaline media, pertechnetate shows much more complicated behaviour though not too unsimilar to that in buffered alkaline media. It has been proposed that the alkaline environment produced at the electrode surface during pertechnetate reduction accounts for the similarity<sup>15</sup>.

#### Reducing agents :

With the exception of pertechnetate itself, and perhaps technetium-99m-labeled sulphur colloid, all other radiopharmaceuticals contain technetium in an oxidation state lower than seven. Reduction of pertechnetate is thus a prerequisite before achieving successful incorporation of technetium into any of a variety of useful ligands. Pertechnetate itself does not bind to complexing ligands or to any extent with molecules of biomedical interest. When injected intravenously, as for brain imaging, pertechnetate becomes weakly bound to albumin, largely through electrostatic interactions. This binding is not strong and pertechnetate thus bound can be easily displaced by anions such as perchlorate. Pertechnetate solutions can be reduced by many common reducing agents. In principle, any reductant with a reduction potential lower than that of pertechnetate (+0.738 V) is capable of performing the reduction. The pertechnetate ion is a mild oxidizing agent (unlike the strongly oxidizing permanganate) and its reduction is generally favoured in a number of media of interest in nuclear medicine. The production of the insoluble oxide, TcO<sub>3</sub>, or a hydrate thereof, however, is thermodynamically favoured in aqueous solutions except in highly acidic media, or in the presence of complexing agents. Formation of the oxide is a competitive pathway in all reduction reactions and has to be avoided in carrying out the preparation of soluble radiopharmaceuticals. Chemistry of the reducing agent also plays a very important role, especially when using metallic reducing agents.

The most frequently used reducing agents include stannous ion, ferric chloride and ascorbic acid, conc. HCl, borohydride and dithionite<sup>8</sup>. Others such as cuprous ion, formamidine sulphinic acid, and sulphhydryl compounds have also been employed. Electrolytic reduction using inert as well as tin or zirconium electrodes can also be employed in some systems. During the preparation of radiopharmaceuticals, reductions are generally carried out in the presence of a complexing ligand (often a compound that one wishes to label with <sup>99m</sup>Tc) that stabilizes the lower oxidation state of technetium and thus eliminates or minimizes subsequent hydrolytic reactions. Redox reactions involving pertechnetate most likely proceed via oxygen atom transfer to the reducing agent and are favoured with reductants that react by such a mechanism. The reductions are thermodynamically favoured in general but the kinetic parameters often assume a greater importance. Stannous compounds are employed as

reducing agents in most radiopharmaceutical preparations, despite the various reported problems<sup>12</sup>.

### Synthetic and Structural Studies

The last few years have experienced an intense surge of interest in the area of synthesis and structure elucidation of technetium coordination compounds. The fact that technetium has one of the most complicated and subtle chemistries compared to other elements used in nuclear medicine applications is not totally without advantage since the intricate chemistry also offers almost unlimited possibilities of manipulation in order to produce a wide range of complexes with tailor-made properties. Certain lower oxidation states of technetium can be stabilized against subsequent ligand substitution by choosing an appropriate coordination environment, which is expected to make the complexes retain their *in vivo* integrity. Accordingly, the areas of intense research effort recently in controlled syntheses of a wide variety of stable, substitution inert technetium complexes and the elucidation of their structure and chemistry promise to substantially add new and useful agents to our existing armamentarium of <sup>99m</sup>Tc radiopharmaceuticals. Additionally, a number of model technetium compounds that have been synthesized no doubt will permit a study of the *in vitro* and *in vivo* reaction mechanisms and thus provide a basis for elucidating structure-activity relationships and consequently aid in the development of new or improved agents for various applications in nuclear medicine. This intensified interest is exemplified by the fact that about five years ago, only a handful of simple technetium compounds had been synthesized and characterized. The structure of these compounds was poorly understood. A number of coordination compounds with technetium in oxidation states ranging from 1+ to 7+ and with coordination numbers from 4 to 8 have since been prepared and structurally characterized by definitive techniques such as single crystal X-ray analysis.

#### 1. Synthesis :

The predominantly used method so far for preparing technetium-99m radiopharmaceuticals is by the so-called redox route, for example, by the stannous reduction of pertechnetate in the presence of a potential complexing ligand. Despite the limitations involved in this method, it has allowed the development of a variety of extremely useful radiopharmaceuticals. Another possible approach is the synthesis of <sup>99m</sup>Tc-labeled compounds utilizing ligand substitution reactions, that is by substitution of the desired ligand onto a stable, characterized, prerduced technetium center. This approach is not without disadvantages; however, several advantages become obvious such as a control over the oxidation state and coordination environment of technetium in the final product, synthetic possibilities with a greater variety of ligands and the possibility of manipulating biological selectivity by retaining some ligands and changing others in a methodical manner. While examples of this having been accomplished at

the no-carrier-added level are so far relatively scarce, attempts at carrying out ligand substitution reactions at the carrier technetium level have met with considerable success<sup>3</sup>.

For macroscopic amounts, the substitution route for preparing Tc(V) and Tc(IV) complexes is convenient because of the availability of TcOX<sub>2</sub> and TcX<sub>3</sub> materials (X=halogen). These reactions are usually conducted in organic solvents such as ethanol or THF in order to prevent disproportionation and hydrolysis of the starting material. Due to the fairly labile nature of the d<sup>3</sup> center, the reactions proceed rapidly to yield five-, six- and seven-coordinate complexes with an intact TcO<sup>3+</sup> core. Under anhydrous conditions the octahedral d<sup>3</sup> center, however, is substitutionally inert and somewhat forcing conditions are required to drive the reactions to completion. TcCl<sub>3</sub> reacts more rapidly than TcI<sub>3</sub>; in aqueous media these compounds are quite labile and produce the insoluble TcO<sub>2</sub>. At the no-carrier-added level, well-defined TcOX<sub>2</sub> and TcX<sub>3</sub> species are not generally accessible. There are several poorly defined technetium-99m complexes however, that have been utilized as substrates for substitution syntheses to produce complexes with glucoheptonate, gluconate, DTPA, citrate and cyclam, etc<sup>14</sup>.

(i) *Simple salts and complexes with inorganic ligands*: The heptavalent state is normally most stable in simple salts (e.g. TcO<sub>7</sub><sup>-</sup>) followed by the tetravalent state (e.g. TcO<sub>4</sub>). The other oxidation states generally gain stability via complex formation. The oxides, sulphides and simple oxo-anions have all been well characterized. The weakly paramagnetic, volatile heptoxide has a structure consisting of two TcO<sub>4</sub> tetrahedra which share an oxygen atom in a linear Tc-O-Tc array<sup>14</sup>. The black TcO<sub>2</sub> with a distorted rutile structure is formed from reduction of TcO<sub>4</sub><sup>-</sup> by hydrolysis of hexahalogenotechnetate(IV) complexes, or by thermal decomposition of NH<sub>4</sub>[TcO<sub>4</sub>] at 950° in a nitrogen atmosphere. Several ternary oxides have also been reported, for example NaTcO<sub>3</sub>, M<sub>2</sub>TcO<sub>3</sub>, Li<sub>2</sub>TcO<sub>3</sub>, Li<sub>4</sub>TcO<sub>3</sub> and M<sub>2</sub>TcO<sub>3</sub>, etc.<sup>17</sup>. The sulphides Tc<sub>2</sub>S<sub>7</sub> and TcS<sub>8</sub> are isomorphous with the corresponding oxides. The heptasulphide is volatile and can be prepared by addition of H<sub>2</sub>S, thioacetamide or thiosulphate to acid solutions of pertechnetate.

Various halides, thiocyanates and oxohalides of technetium are known and have been studied extensively<sup>14</sup>. Most of these compounds are not stable in neutral aqueous media and the synthetic schemes involving these as starting materials are carried out in acidic solutions or in non-aqueous solvents. One of the important intermediates is square-pyramidal TcOX<sub>2</sub> which is produced upon reduction of TcO<sub>4</sub><sup>-</sup> with concentrated halogen acid<sup>18</sup>. Octahedral [Tc(NCS)<sub>6</sub>]<sup>3-</sup> and [Tc(NCS)<sub>5</sub>]<sup>2-</sup> have been prepared by the reaction of (NH<sub>4</sub>)SCN with a solution of (NH<sub>4</sub>)<sub>2</sub>[TcX<sub>6</sub>] compounds<sup>19</sup>. All SCN<sup>-</sup> ligands are N-bonded and a nearly perfect octahedral symmetry exists for (Bu<sub>4</sub>N)<sub>3</sub>[Tc(NCS)<sub>6</sub>], as demonstrated by X-ray structural studies. Various cyanide

complexes containing the  $\text{TcO}^{3+}$ ,  $tr\text{-TcO}_2^+$  and  $tr\text{-Tc(O)(OMe)}^{3+}$  cores have recently been prepared and characterized<sup>20</sup>. A variety of carbonyl, nitrosyl and organometallic compounds of technetium have been reported in the early as well as recent literature. Also, a range of mixed-ligand  $\text{Tc(II)}$  complexes of the type  $\text{Tc(CO)}_5\text{-}n\text{L}_n$  ( $\text{L}$ =monodentate organic ligand, e.g.  $\text{Py}$ ,  $\text{PR}_3$  or  $\text{AsR}_3$ ) have been synthesized and studied.

(ii) *Coordination complexes containing organic ligands:*

(a) *Oxygen donor ligands:* Complexes of technetium that have been prepared and characterized with this class of ligands include  $\beta$ -diketonates,  $[\text{TcCl}_4(\text{sal})]$ , diphosphonates, etc. The neutral complex  $\text{Tc(acac)}_3$  has recently been obtained by refluxing  $\text{TcO}_2$  in neat acetylacetone<sup>21,22</sup>. Earlier, it was prepared by refluxing  $\text{TcCl}_4(\text{PPh}_3)_2$  with the ligand in an analogous reaction<sup>23</sup>. Reaction of  $[\text{PPh}_4][\text{TcX}_6]$  or  $\text{TcX}_4(\text{PPh}_3)_2$  ( $\text{X}=\text{Cl}, \text{Br}$ ) with anhydrous acetylacetone under different conditions also produces mixed ligand  $\text{Tc(III)}$  and  $\text{Tc(IV)}$  complexes such as  $\text{Tc(acac)}_3\text{X}_2$ ,  $\text{PPh}_4[\text{Tc(acac)}_4\text{X}_2]$ ,  $\text{Tc(acac)}_2\text{-PPh}_3\text{X}$ , etc.<sup>22,25</sup>. The latter compound displays a *trans* configuration with a coordination polyhedron approximating  $D_{4h}$  symmetry based on X-ray structural studies. The reaction of excess methylene diphosphonate (routinely used skeletal imaging agent) with  $[\text{TcBr}_6]^{3-}$  produces a mixture of species. Purification yields a material that has been shown by X-ray analysis to be polymeric with a  $\text{Tc/MDP}$  ratio of 1.0<sup>24</sup>. Each  $\text{Tc}$  center has an octahedral coordination environment. Two symmetry related  $\text{Tc}$  atoms are bridged by each MDP ligand and each  $\text{Tc}$  atom is bound to two symmetry related MDP ligands. Even though the oxidation state of the  $\text{Tc}$  center cannot be assigned unambiguously,  $\text{Tc(IV)}$  or  $\text{Tc(V)}$  appear to be most likely present. Such structures are also likely with the other commonly used diphosphonate bone agents. The actual radiopharmaceuticals ( $^{99m}\text{Tc}$ -methylene diphosphonate,  $^{99m}\text{Tc}$ -ethylidenedihydroxy disodium phosphonate) have recently been shown using HPLC techniques to contain a mixture of species in solution<sup>25</sup>. The individual components all localize in bone but significant differences exist in their blood clearance, soft tissue uptake and excretion from the body.

(b) *Nitrogen donor ligands:* A variety of complexes of technetium with this class of ligands have recently been synthesized and studied. Examples are  $[\text{TcO}_2(\text{en})_2]\text{X}$  ( $\text{X}=\text{Cl}, \text{Br}, \text{I}$ ),  $[\text{TcO}_2(\text{cyclam})]\text{-ClO}_4\cdot\text{H}_2\text{O}$ , complexes with 1,2-diaminocyclohexane, 1,2-diaminopropane, several pyridine derivatives, and imidazole,  $\text{TcO}_2\text{XL}$  type compounds (where  $\text{L}=\text{bipy}$ ,  $\text{X}=\text{Cl}, \text{Br}$  or  $\text{L}=\text{phen}$ ,  $\text{X}=\text{Cl}$ ),  $[\text{TcO}(\text{HBPz}_2)\text{-Cl}_2]$  [where  $\text{HBPz}_2$ =hydrotris (1-pyrazolyl)borate] and  $[\text{Tc}(\text{DMG})_2\text{SnCl}_4(\text{OH})]\cdot 3\text{H}_2\text{O}$  ( $\text{DMG}$ =dimethylglyoxime)<sup>23,24,26,27</sup>. Both the ethylenediamine and cyclam complexes contain the  $tr\text{-TcO}_2^+$  core embedded in an approximately octahedral coordination environment provided by the four nitrogen donor atoms. The  $\text{Tc}=\text{O}$  bond length in both

complexes is considerably longer (ca 1.75 Å) than the average  $\text{Tc}=\text{O}$  length (ca 1.65 Å) observed in complexes that contain the  $\text{TcO}^{3+}$  core. The  $\text{Tc}=\text{O}$  ir stretching modes (790 and 834  $\text{cm}^{-1}$  for cyclam and en complexes, respectively) are below the range (1020 – 910  $\text{cm}^{-1}$ ) observed for  $\nu\text{Tc}=\text{O}$  in  $\text{TcO}^{3+}$  complexes. It appears that charge neutralization of the  $\text{Tc}$  center is one of the factors that governs whether a given  $\text{Tc(V)}$  complex will contain the  $\text{TcO}^{3+}$  or the  $tr\text{-TcO}_2^+$  core. The dimethylglyoxime complex is obtained upon the reduction of  $\text{TcO}_2$  by  $\text{Sn}^{2+}$  in the presence of the ligand. In this compound the tin and technetium are connected by a triple bridge, the separation between metal centers is 3.7 Å<sup>27</sup>. The tin atom can be viewed as "capping" the three oxygen atoms on one end of the  $\text{Tc-DMG}$  complex. The oxidation states of tin and technetium in this diamagnetic complex have been assigned as IV and V, respectively<sup>27</sup>. Mixed tin-technetium complexes could be present in radiopharmaceuticals that are usually prepared using  $\text{Sn(II)}$  as a reductant.

(c) *Sulphur donor ligands:* Since sulphur containing ligands are often used in  $^{99m}\text{Tc}$  radiopharmaceutical preparations, a number of workers have recently undertaken studies of the interaction of sulphur donor ligands with technetium. A variety of complexes have been prepared and characterized  $(\text{Ph}_4\text{As})[\text{TcO}(\text{dithiolate})_2]$ ,  $(\text{Bu}_4\text{N})[\text{TcO}[\text{SC}(\text{O})\text{CH}_2\text{S}]_2]$ ,  $[\text{TcO}(\text{C}_2\text{O}_2\text{S}_2)_2]^-$ ,  $[\text{TcO}(\text{S}_2\text{C}_2(\text{CN})_2)_2]^-$ ,  $[\text{TcO}(\text{tdt})_2]^-$  ( $\text{tdt}=3,4\text{-dimercaptotoluene}$ ) and  $\text{TcN}(\text{S}_2\text{CNet}_2)_2$ , etc<sup>24</sup>. Both dithiolate and thioglycolate materials contain the  $\text{TcO}^{3+}$  core in a distorted square pyramidal environment and the  $\text{Tc}$  is displaced about 0.76 Å above the plane of the sulphur atoms. The displacement of halide from  $[\text{TcOCl}_4]^-$  has led to a systematic synthesis of a large variety of *bis*(dithiolato) technetium(V) complexes mentioned above. All these compounds display square pyramidal geometries and exhibit  $\text{Tc}=\text{O}$  stretches in the ir region at 920–980  $\text{cm}^{-1}$ ; complexes that contain electron withdrawing substituents on the ligands exhibit  $\text{Tc}=\text{O}$  stretching frequencies towards the higher end of this range. Analogous square pyramidal complexes containing the O,S chelated ligand rather than the S,S chelated ethanedithiolato ligand have recently been prepared<sup>24</sup>. A technetium(V) complex containing the  $\text{Tc}=\text{N}^{3+}$  core has also recently been synthesized and characterized<sup>28</sup>. Hydrazine reduction of  $\text{TcO}_2$  followed by reaction with  $\text{Na}(\text{S}_2\text{CN Et}_2)$  gives the uncharged nitrido complex  $\text{TcN}(\text{S}_2\text{CNet}_2)_2$ . Analogous to the *bis*(dithiolato)  $\text{TcO}^{3+}$  complexes, the geometry of the nitrido complex is square pyramidal with an axial  $\text{Tc}=\text{N}$  bond and the  $\text{Tc}$  atom is 0.75 Å above the plane of the four sulphur atoms. This complex is isostructural with  $\text{ReN}(\text{S}_2\text{CNet}_2)_2$ .

(d) *Phosphorus and arsenic donor ligands:* A number of phosphine and arsine complexes have been described; these all contain (with a few exceptions) technetium in IV or lower oxidation states<sup>24</sup>. This is a reflection of both the reducing action of these ligands as well as the "softness"



of the donor atoms that favour stabilization of lower metal oxidation states. The exceptions involve the Tc(V) center which is stabilized either by the presence of special ligands such as diars or by the presence of oxo ligands, e.g., those that result in the formation of the  $\text{TcO}_4^+$  core, and thus decrease the effective formal charge on the central metal atom. The octahedral complexes  $[\text{Tc}(\text{PPh}_3)_3\text{Cl}_3]$  and  $[\text{Tc}(\text{AsPh}_3)_3\text{Cl}_3]$  are produced upon the reaction of  $\text{PPh}_3$  or  $\text{AsPh}_3$  with  $(\text{TcCl}_4)_n$  in refluxing ethanol. The magnetic moments are respectively 3.92 B.M. and 3.62 B.M. consistent with a Tc(IV) ( $d^2$ ) species. On the contrary, reaction of 1,2-bis(diphenylphosphine)ethane (dppe) under similar conditions gives the Tc(III) complex,  $tr\text{-}[\text{Tc}(\text{dppe})_2\text{Cl}_2]\text{Cl}$ . When excess dppe is used, further reduction leads to the formation of Tc(II) complexes,  $tr\text{-}[\text{Tc}(\text{dppe})_3\text{X}_3]$  ( $\text{X}=\text{Cl}, \text{Br}$ ); these readily oxidize in air to give the Tc(III) analogs. Many of these complexes have been prepared and structurally characterized. Potential use of  $^{99m}\text{Tc}$  analogs as heart imaging agents has recently been demonstrated<sup>29</sup>. The synthesis of  $[\text{Tc}(\text{diars})_2\text{Cl}_4]^+$ , an eight-coordinate technetium(V) complex by oxidative addition of molecular chlorine to  $tr\text{-}[\text{Tc}(\text{diars})_2\text{Cl}_2]^+$  was described as early as 1960. The diars ligand has previously been shown to stabilize higher coordination numbers. A variety of other complexes with phosphorus and arsenic donor ligands have been described in the literature<sup>24</sup>.

(e) *Mixed donor atom ligands*: Several technetium complexes with N,O chelating Schiff bases and aminopolycarboxylate ligands and with other mixed donor atom ligands have been prepared and studied<sup>24</sup>. The compounds include  $[\text{TcO}(\text{Ph-sal})_2\text{Cl}]$  and  $[\text{TcO}(\text{Ph-sal})\text{Cl}_2]^-$  ( $\text{Ph-salH}=\text{N-phenylsalicylideneimine}$ );  $(\text{H}_4\text{EDTA})\text{Tc}(\text{u-o})_2\text{Tc}(\text{H}_4\text{EDTA})\cdot 5\text{H}_2\text{O}$ ,  $\text{Ba}[\text{Tc}(\text{O})\text{EDTA}]_2$ ,  $[\text{Tc}_2(\text{OC}_2\text{H}_4\text{N})_4]^{n+}$  and  $(\text{Ph}_3\text{As}[\text{TcOL}])$  where  $\text{L}=\text{RCH}(\text{S})\text{COO}^-$ . In case of the Tc(V)  $\text{Ph-salH}$  complex, an octahedral structure was suggested in which a phenolic oxygen atom was situated *trans* to the  $\text{Tc}=\text{O}$  bond. The EDTA ligand, depending on reaction conditions forms several different complexes. For example, a strong Tc-Tc bond with a short 2.33 Å distance has been shown to be present in  $(\text{H}_4\text{EDTA})\text{Tc}(\text{u-o})_2\text{Tc}(\text{H}_4\text{EDTA})\cdot 5\text{H}_2\text{O}$  and each EDTA coordinates to one technetium by two nitrogen and two oxygen atoms<sup>30</sup>. Each technetium has an octahedral geometry and perhaps a 4+ oxidation state. Reaction of  $\text{H}_4\text{EDTA}$  with  $[\text{TcOCl}_4]^-$  in anhydrous DMSO gives  $[\text{Tc}(\text{O})\text{EDTA}]_2^{2-}$ , the barium salt of which contains two  $[\text{Tc}(\text{O})\text{EDTA}]^-$  anions, each coordinated to barium ions via four carboxylate bridges<sup>24</sup>. The barium is thus eight-coordinate and each technetium atom is seven-coordinate with a distorted pentagonal bipyramidal geometry and the EDTA ligand is hexadentate. This complex illustrates the structural flexibility of the  $d^2 \text{TcO}^{2+}$  core, which has recently been observed to occur in technetium complexes with 5, 6 and 7 coordination numbers.

## 2. Structural studies :

Various techniques that have been used for the structure elucidation of technetium compounds include X-ray analysis, elemental analysis and molecular weight determination, ir, Raman, nmr and vis/uv spectroscopy and mass spectroscopy. Definitive structures have been assigned to approximately 65 compounds using X-ray structural analysis<sup>21</sup>. A partial listing of these appears in Table 1. These

TABLE 1—TECHNETIUM COMPOUNDS STRUCTURALLY CHARACTERISED BY SINGLE CRYSTAL X-RAY ANALYSIS<sup>21, 22</sup>

Compound*	Oxidation state of technetium	Coordination number
$\text{K}_4\text{Tc}(\text{CN})_6$	I	6
$[\text{trans-Tc}(\text{NH}_3)_4(\text{NO})(\text{H}_2\text{O})]^{2+}$	I	6
$\text{TPP}[\text{Tc}(\text{CO})_3]_2$	I	6
$\text{TcCl}_3[(\text{EtO})_2\text{PPh}]_2$	II	6
$\text{Tc}(\text{diphos})_2\text{Cl}_2$	II	6
$[\text{Tc}(\text{NO})\text{Br}_4]^-$	II	5
$[\text{Tc}_2\text{Cl}_8]^{2-}$	II, III	6
$\text{TcCl}_3(\text{CO})(\text{Me}_2\text{PPh})_2 \cdot \text{EtOH}$	III	7
$[\text{Tc}(\text{diars})_2\text{Cl}_4]^+$	III	6
$\text{TcCl}_3(\text{Me}_2\text{PPh})_2$	III	6
$\text{TcCl}(\text{acac})_2(\text{PPh}_3)_2$	III	6
$\text{Tc}_2[\text{OOC Me}_2]_4\text{Cl}_2$	III	6
$[\text{Tc}(\text{dmpe})_2\text{Cl}_2]^+$	III	6
$[\text{Tc}(\text{diphos})_2\text{X}_2]^+$ , $\text{X}=\text{Cl or Br}$	III	6
$[\text{Tc}(\text{SCN})_6]^{2-}$	III	6
$\text{TcO}_2$	IV	6
$[\text{TcCl}_6]^{3-}$	IV	6
$[\text{TcOCl}_4]^-$	V	5
$tr\text{-}[\text{TcO}_2(\text{en})_2]^+$	V	6
$tr\text{-}[\text{TcO}_2(\text{Cyclam})]^+$	V	6
$[\text{TcO}(\text{EDTA})]^-$	V	7
$[\text{TcO}(\text{SCH}_2\text{CH}_2\text{S})_2]^-$	V	5
$[\text{TcO}(\text{SCH}_2\text{C}(\text{O})\text{S})_2]^-$	V	5
$[\text{TcO}(\text{SCH}_2\text{CH}_2\text{O})_2]^-$	V	5
$[\text{Tc}(\text{diars})_2\text{Cl}_2]^+$	V	8
$[\text{TcO}(\text{HBPz}_2)\text{Cl}_2]$	V	6
$\text{Tc}(\text{dmg})_2(\text{SnCl}_4)(\text{OH}) \cdot 3\text{H}_2\text{O}$	V	7
$[\text{TcOF}_6]$	VI	6
$(\text{Me}_2\text{N})_2[\text{TcO}_4]$	VI	4
$\text{Tc}_2\text{O}_7$	VII	4
$\text{Tc}_2\text{S}_7$	VII	4
$\text{Li}_2[\text{TcO}_6]$	VII	4
$\text{Na}_2[\text{TcO}_6]$	VII	4
$[\text{Tc}(\text{OH})(\text{MDP})]^-$	?	6

\*Abbreviations TPP, tetraphenylporphine, diphos, bis-(1,2-diphenylphosphino)ethane; diars, *o*-phenylenebis(dimethylarsine), acac, acetylacetonate monoanion; dmpe, bis-(1,2-dimethylphosphino)ethane; en, ethylenediamine; cyclam, 1,4,8,11-tetraazacyclotetradecane; EDTA, ethylenediaminetetraacetate; HBPz<sub>2</sub>, hydrotris-(1-pyrazolyl)borate monoanion, dmg, dimethylglyoxime in unknown protonation state, MDP, methylene diphosphonate in unknown protonation state; Me, methyl, Et, ethyl, Ph, phenyl

studies provide several results of considerable importance to the design and development of technetium radiopharmaceuticals: (i) A wide range of coordination numbers and geometries is exhibited by complexes of reduced technetium. Even though 6-coordination with an octahedral geometry is most common, the compounds are not restricted to only such structures as generally assumed in the early literature. In simple compounds, a coordination number of four is limited to the 7+ state in the

per salts and the oxide halides; 6-coordination can be assumed by most other lower oxidation states. Five-coordinate compounds with square pyramidal geometry and 7-coordinate compounds with a geometry approximating that of a mono-capped octahedron are quite often encountered. (ii) The 5+ oxidation state is more common than previously assumed, when the complexes are prepared using aqueous and aerobic conditions (iii) A number of complexes contain the  $Tc(V)=O$  center such as in  $TcOCl_2$  and in others, and often bridging oxygen atoms. The likely conclusion is that many technetium radiopharmaceuticals prepared by the reduction of pertechnetate in aqueous media may indeed contain one or two oxo ligands and the properties associated with the chemistry of such linkages. The oxo group in  $Tc=O$  compounds exerts a strong *trans*-labilizing effect with the result that the *trans* coordination site is vacant in compounds such as  $TcO(SCH_2CH_2S)^{2-}$ ,  $TcO[SCH_2C(O)S]^{2-}$ ,  $TcOCl_2$  etc., or is loosely occupied by a solvent molecule when the compounds are in solution. In  $Tc(HBPz_3)_2Cl_2O$ , five coordination is not favoured due to the tridentate nature of the  $HBPz_3$  ligand but the influence of the oxo group leads to a weak *trans* ligand-metal bond as reflected by the *trans* nitrogen atom being 0.2 Å further from technetium than are the two *cis* nitrogen atoms<sup>24</sup>. The four equatorial coordination sites *cis* to the oxo ligand are resistant to ligand substitution (in contrast to the labile *trans* site) and thus such structures should provide suitable templates about which to construct radiopharmaceuticals with maximum *in vivo* integrity. The occurrence of tightly bonded  $Tc(V)=O$  centers and the different bonding properties of the equatorial and axial sites within these centers may be more commonly involved in routine  $^{99m}Tc$  radiopharmaceuticals than generally recognized. (iv) Technetium can form complexes with metal-metal bonds as exemplified by the structures of  $Tc_2Cl_8^{2-}$  and  $Tc_2[OOC(Me)_3]_4Cl_2$  and this possibility should not be overlooked in the assignment of possible structures. (v) Analogous to the well known nitrosyl-ruthenium complexes, *trans*- $Tc(NH_3)_4(NO)(OH_2)^{3+}$  could represent a large class of nitrosyl-technetium complexes. By virtue of the fact that the NO ligand stabilizes low oxidation states, compounds with  $Tc-NO$  centers should be an interesting class to be exploited.

The solid state structure of  $[Tc(OH)MDP^-]_n$  (and perhaps other bone agent complexes such as pyrophosphate, polyphosphate etc.) shows the compound to be polymeric with technetium centers bridged by MDP and OH (or  $OH_2$ ) ligands, and MDP ligands in turn bridged by technetium centers. This would indicate that technetium phosphate radiopharmaceuticals may be polymeric mixtures in aqueous solution and not single well defined species. Ligands such as EDTA and DTPA are capable of forming dimeric metal complexes and can also simultaneously coordinate to more than one metal. With the use of tin(II) as a reducing agent in radiopharmaceutical formulations, the possibility of mixed

technetium-tin-ligand complexes cannot be ruled out completely.

### Conclusion

Technetium has played a vital role in the rapidly growing field of diagnostic nuclear medicine. A plethora of  $^{99m}Tc$ -labeled compounds is already available for various imaging applications, many others continue to be developed at a rapid pace. The lack of a proper understanding of the exact nature of most earlier technetium radiopharmaceuticals and their mode of action did not significantly hamper the practical usefulness of this radionuclide in diagnostic applications. The ultimate benefits to the patients have been immeasurable. Recently, however, a growing awareness of the need to systematically understand the chemistry and *in vivo* reaction mechanisms of technetium radiopharmaceuticals has resulted in a flurry of research activity in this area. The last five years have seen many important advances including those in the field of technetium coordination chemistry, and in the application of highly sensitive analytical techniques to the fractionation and characterization of complex technetium radiopharmaceutical mixtures. The knowledge that has been acquired will certainly add new and more efficacious  $^{99m}Tc$  radiopharmaceuticals to our existing arsenal and will also result in improvement of the existing agents. Many of the technetium labeled compounds developed earlier included particles and a prior understanding of factors such as the chemical state of technetium and various thermodynamic and kinetic parameters etc. were not crucial to the usefulness of these agents for the intended application. In contrast, effective development and use of many biological compounds and drug molecules labeled with technetium require a thorough understanding of the chemistry, the binding affinities and the effect of the metal on the biological properties of the substrate. Direct binding of technetium to bioactive molecules may be of limited usefulness since in most cases biological behaviour of the labeled compound is drastically altered. In this respect, some of the more recent approaches such as binding technetium to a chelate containing derivative of a biologically active molecule may be of particular value. Work in this direction is already underway and some success has been demonstrated. The major stumbling block has been the synthesis of derivatives of the parent molecule with retention of biological activity.

Recent renewed interest in the area of synthetic and structural coordination chemistry of technetium will undoubtedly play a very important role in the development of improved radiosciintigraphic agents. It will be necessary to understand the chemical mechanisms involved in many of these synthetic reactions especially with regard to ligand substitution and oxygen atom transfer redox processes. Such mechanistic studies will complement the large body of knowledge that has slowly been evolving on the synthetic and structural aspects of technetium chemistry.

## Acknowledgement

Preparation of this review was supported by the U. S. Department of Energy Contract #DE-ACO2-76CH00016 at the Brookhaven National Laboratory. Thanks of the authors are due to their colleagues who contributed significantly to the ideas and research presented in this review and also for providing results of their unpublished studies. The assistance of Mrs. Rae Bailey in preparing and typing the manuscript is gratefully acknowledged.

## References

1. B. T. KENNA, *J. Chem. Educ.*, 1962, 39, 436
2. C. PERRIER and E. SEGRE, *J. Chem. Phys.*, 1937, 5, 712, 1939, 7, 155.
3. S. C. SRIVASTAVA and P. RICHARDS, "Radiotracers for Medical Applications", CRC Press Inc., Boca Raton, Florida, 1982 (in press).
4. P. RICHARDS, "Trans Fifth Nucl. Congr., 7th Int. Electronic and Nuclear Symposium", Rome, 1960, p. 225.
5. P. RICHARDS, "Proc. Symp. Radioactive Pharmaceuticals", ORNL, 1965, p. 323.
6. P. RICHARDS, W. TUCKER and S. C. SRIVASTAVA, *Int. J. Appl. Radiat. Isotopes*, 1982, 33, 793.
7. R. COLTON, "The Chemistry of Rhenium and Technetium", Interscience, London, 1965.
8. R. D. PEACOCK, "The Chemistry of Technetium and Rhenium", Elsevier, London, 1966.
9. K. V. KOTEGOV, O. N. PAVLOV and V. P. SHVEDOV, in "Advances in Inorganic Chemistry and Radiochemistry", (Ed.) H. J. EMELEUS and A. G. SHARPE, Academic Press, New York, 1968, Vol. 11, p. 1.
10. A. K. LAVRUKINA and A. A. POZDNYAKOV, in "Analytical Chemistry of Technetium, Promethium, Astatine and Francium", Ann Arbor-Humphrey Science Publishers, Ann Arbor, Michigan, 1970.
11. R. D. PEACOCK, "Technetium", in "Comprehensive Inorganic Chemistry", (Ed.) J. BAILER *et al*, Pergamon, London, 1972, Vol 3 p. 871.
12. J. STEIGMAN and P. RICHARDS, *Sem. Nucl. Med.*, 1974, 4, 269.
13. M. J. CLARKE and P. H. FACKLER, "Structure and Bonding", Springer Verlag, Berlin, 1982, Vol 50, p. 57.
14. E. DEUTSCH, K. LIBSON, S. JURISSON and L. F. LINDOY, *Progr. in Inorg. Chem.*, 1982, 30 (in press).
15. C. D. RUSSEL, *Int. J. Appl. Radiat. Isotopes*, 1982, 33, 903.
16. S. C. SRIVASTAVA, G. E. MEINKEN, T. D. SMITH and P. RICHARDS, *Int. J. Appl. Radiat. Isotopes*, 1977, 28, 83.
17. C. KELLER and B. KENELLAKOPULOS, *J. Inorg. Nuclear Chem.*, 1965, 27, 787.
18. F. A. COTTON, A. DAVISON, V. W. DAY *et al*, *Inorg. Chem.*, 1979, 18, 3024.
19. H. S. TROP, A. DAVISON, A. G. JONES *et al*, *Inorg. Chem.*, 1980, 19, 1105.
20. H. S. TROP, A. G. JONES and A. DAVISON, *Inorg. Chem.*, 1980, 19, 1993.
21. A. B. PACKARD, S. C. SRIVASTAVA, P. RICHARDS and Y. HUNG, *J. Nucl. Med.*, 1981, 22, 70.
22. A. B. PACKARD, S. C. SRIVASTAVA, P. RICHARDS *et al*, *J. Nucl. Med.*, 1982, 23, 17.
23. U. MAZZI, E. RONCARI, G. BANDOLI and L. MAGON, *Trans. Metal Chem.*, 1979, 4, 151.
24. K. LIBSON, E. DEUTSCH and B. L. BARNETT, *J. Amer. Chem. Soc.*, 1980, 102, 2476.
25. S. C. SRIVASTAVA, D. BANDYOPADHYAY, G. MEINKEN and P. RICHARDS, *J. Nucl. Med.*, 1981, 22, 69.
26. S. A. ZUCKMAN, G. M. GREEMAN, D. E. TROUTNER *et al*, *Inorg. Chem.*, 1981, 20, 2386.
27. E. DEUTSCH, R. C. ELDER, B. A. LANGE *et al*, *Proc. Natl. Acad. Sci.*, 1976, 73, 4287.
28. J. BALDAS, J. BONNYMAN, P. M. POJEV *et al*, *J. Chem. Soc., Dalton*, 1981, 1798.
29. E. DEUTSCH, W. BUSHONG, K. A. GLAVAN *et al*, *Science*, 1981, 214, 85.
30. H. B. BURGH, G. ANDEREGG, P. BLAUNSTEIN, *Inorg. Chem.*, 1981, 20, 3829.
31. G. BANDOLI, U. MAZZI, E. RONCARI *et al*, *Coord. Chem. Revs.*, 1982 (in press).

# Mass Spectrometry of Transition Metal $\eta^5$ -Complexes. Part—VII. A Study of the Behaviour of Some Ruthenocene Derivatives†

REG DAVIS\* and DESMOND J. O'REARDON

School of Chemical and Physical Sciences, Kingston Polytechnic, Penrhyn Road,  
Kingston upon Thames KT1 2EE, U K.

The mass spectral fragmentation of  $(\eta^5\text{-C}_5\text{H}_5)_2\text{Ru}(\eta^5\text{-C}_5\text{H}_5\text{COR})$  ( $\text{R} = \text{CH}_3, \text{Ph}$ ) (I, II) and  $(\eta^5\text{-C}_5\text{H}_5\text{COCH}_3)_2\text{Ru}(\eta^5\text{-C}_5\text{H}_5\text{COCH}_3)$  (III) has been examined and compared with that of the ferrocene analogues. The higher metal-ligand bond strengths in the ruthenocene derivatives are reflected in much more extensive fragmentation of the metal-bound ligands compared to the behaviour of the ferrocenes. The ion,  $(\text{M}-\text{CH}_3)^+$  from (III) shows an unusual loss of two CO groups in a single step, a process believed to be under thermodynamic control and leading to  $[(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_5)]^+$ .

THE mass spectral behaviour of ferrocene derivatives has been the subject of extensive study and much of this work has been reviewed<sup>1</sup>. However, there has been no such studies on the ruthenocene analogues and only three studies have been reported on ruthenocene itself<sup>2-4</sup>. Of particular interest is the study of Müller and D'Or<sup>2</sup> which showed that 8.3% of the total metal-containing ion current of ruthenocene consists of ions of the type  $\text{MC}_5\text{H}_5^+$  and  $\text{MC}_5\text{H}_4^+$ , arising via successive loss of  $\text{C}_5$  units from the molecular ion, compared to 1.1% for ferrocene. Furthermore, 9.5% of total metal-containing ion current of ruthenocene consists of ions of the type  $\text{MC}_4\text{H}_5^+$ ,  $\text{MC}_3\text{H}_5^+$ ,  $\text{MC}_2\text{H}_5^+$  and  $\text{MCH}_5^+$ , arising principally by fragmentation of  $\text{MC}_5\text{H}_5^+$ , compared to 6.2% for ferrocene. The percentages of  $(\text{Metal})^+$  are 13.3% for ferrocene and 1.8% for ruthenocene. These small, but significant, differences are in accord with slightly higher  $\text{M}-\text{C}_5\text{H}_5$  bond dissociation energies in the ruthenium compound<sup>2-4</sup>. We were interested to see if these differences would also manifest themselves in the mass spectra of substituted ruthenocenes and report here the behaviour of monoacetyl- and monobenzoyl-ruthenocene (I and II) and 1,1'-diacetyl-ruthenocene (III).

## Results and Discussion

The spectrum of I is listed in Table 1 and is to be compared with that of monoacetylferrocene (IV) which has been previously reported<sup>5</sup>, but which was redetermined in this work (Table 2). Metastable peaks confirm only four fragmentations in IV. These are  $\text{M}^+ \rightarrow [\text{M}-\text{CH}_3]^+$ ,  $[\text{M}-\text{CH}_3]^+ \rightarrow [\text{M}-\text{CH}_2\text{CO}]^+$ ,  $\text{M}^+ \rightarrow [\text{M}-\text{CH}_2\text{CO}]^+$  and  $[(\text{C}_5\text{H}_5)_2\text{Fe}(\text{C}_5\text{H}_5)]^+ \rightarrow [\text{C}_5\text{H}_5\text{C}_5\text{H}_5]^+$ . The fragmentation of I (Table 1) is supported by only two metastable peaks which confirm the first two of these fragmentations.

Two additional fragmentations of the molecular ion of I are observed over those of IV. These are loss of  $\text{CH}_3\text{CO}$  yielding  $[(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_5)]^+$  and

TABLE 1—MASS SPECTRUM OF MONOACETYL RUTHENOCENE (I)

m/z <sup>+</sup>	Rel Abd (%)	I/II (%) <sup>*</sup>	Assignment
274	100	42	$(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_5\text{COCH}_3)^+$
254	21	9	$(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_5\text{CO})^+$
245	15	1	$\text{C}_5\text{H}_5\text{Ru}(\text{C}_5\text{H}_5)^+$
232	5	2	$(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_4)^+$
231	32	14	$(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_4)^+$
205	14	6	$(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_3)^+$
191	1	0.5	$(\text{C}_5\text{H}_5)_2\text{Ru}(\text{C}_5\text{H}_2)^+$
180	1	0.5	$\text{Ru}(\text{C}_5\text{H}_5)^+$
179	4	2	$\text{Ru}(\text{C}_5\text{H}_4)^+$
167	16	7	$\text{Ru}(\text{C}_5\text{H}_3)^+$
154	4	2	$\text{Ru}(\text{C}_5\text{H}_2)^+$
153	1	0.5	$\text{Ru}(\text{C}_5\text{H}_2)^+$
141	6	2.5	$\text{Ru}(\text{C}_5\text{H}_3)^+$
140	5	2	$\text{Ru}(\text{C}_5\text{H}_2)^+$
139	7	3	$\text{Ru}(\text{C}_5\text{H}_2)^+$
130	1	0.5	$\text{Ru}(\text{C}_5\text{H}_2)^+$
129	2	1	$\text{Ru}(\text{C}_5\text{H}_2)^+$
128	1	0.5	$\text{Ru}(\text{C}_5\text{H}_2)^+$
127	1	0.5	$\text{Ru}(\text{C}_5\text{H})^+$
114	8	4	$\text{RuC}^+$
102	4	2	$\text{Ru}^+$
92	2		$\text{C}_5\text{H}_5\text{CO}^+$
78	0.7		$\text{C}_5\text{H}_5^+$
77	1		$\text{C}_5\text{H}_4^+$
65	1.5		$\text{C}_5\text{H}_4^+$
64	2		$\text{C}_5\text{H}_4^+$
63	3		$\text{C}_5\text{H}_4^+$
52	1		$\text{C}_5\text{H}_4^+$
51	1.5		$\text{C}_5\text{H}_4^+$
50	1		$\text{C}_5\text{H}_4^+$
43	14		$\text{CH}_3\text{CO}^+$
39	7		$\text{C}_5\text{H}_5^+$

Metastable ions m/z 244.8 274 → 259  
m/z 206.0 259 → 231

<sup>+</sup> Based on <sup>103</sup>Ru

<sup>\*</sup> Metal-containing ions only. All percentages rounded to the nearest 0.5%.

Dedicated to Professor A. K. Dey on the occasion of his 60th Birthday

† Part VI, R. Davis, M. L. Webb, D. E. Millington and V. Parr, *Org. Mass Spectrom.*, 1979, 14, 289.

\* Author for correspondence.

TABLE 2—MASS SPECTRUM OF MONOACETYLFERROCENE (IV)

m/z	Rel. Abd. (%)	I/ $\Sigma$ I (%)*	Assignment
228	100	20	(C <sub>5</sub> H <sub>5</sub> )Fe(C <sub>5</sub> H <sub>4</sub> COCH <sub>3</sub> ) <sup>+</sup>
213	17	3	(C <sub>5</sub> H <sub>5</sub> )Fe(C <sub>5</sub> H <sub>4</sub> CO) <sup>+</sup>
185	83	17	(C <sub>5</sub> H <sub>5</sub> )Fe(C <sub>5</sub> H <sub>4</sub> ) <sup>+</sup>
163	14	3	Fe(C <sub>5</sub> H <sub>4</sub> COCH <sub>3</sub> ) <sup>+</sup>
129	77	15	(C <sub>5</sub> H <sub>5</sub> C <sub>5</sub> H <sub>4</sub> ) <sup>+</sup>
121	60	12	Fe(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
95	13	3	Fe(C <sub>5</sub> H <sub>4</sub> ) <sup>+</sup>
94	19	4	Fe(C <sub>5</sub> H <sub>3</sub> ) <sup>+</sup>
81	21	4	Fe(C <sub>5</sub> H) <sup>+</sup>
71	25	5	Fe(CH <sub>3</sub> ) <sup>+</sup>
56	69	14	Fe <sup>+</sup>
43	13	—	CH <sub>3</sub> CO <sup>+</sup>
39	16	—	C <sub>5</sub> H <sub>4</sub>

\* Metal-containing ions only

Metastable ions m/z 199 0 228 → 213  
 m/z 160 7 213 → 185  
 m/z 150 1 228 → 185  
 m/z 90 0 185 → 129

the unusual, although weak, loss of HCO. The product of this later reaction can be written in a number of ways, of which we chose [(C<sub>5</sub>H<sub>5</sub>)Ru(C<sub>5</sub>H<sub>4</sub>)]<sup>+</sup>, despite the fact that this involves a massive reorganisation of the ligand. We are encouraged to do this by the observation of the ions [Ru(C<sub>5</sub>H<sub>5</sub>)]<sup>+</sup>, [Ru(C<sub>5</sub>H<sub>4</sub>)]<sup>+</sup>, [C<sub>5</sub>H<sub>5</sub>]<sup>+</sup> and [C<sub>5</sub>H<sub>4</sub>]<sup>+</sup> as well as other expected fragments from these ions.

As with ruthenocene, the increase in metal-ligand bond strength in I over IV leads to 77% of metal-containing ions in the former containing greater than five carbon atoms, compared to 40% in IV. 23% of the metal containing ions in I contain five or less carbon atoms compared to 46% in IV and the (Metal)<sup>+</sup> ion accounts for 2% of this ion current in I, but 14% in IV.

A number of other differences are noteworthy. Firstly, while IV shows formation of both [(C<sub>5</sub>H<sub>5</sub>)Fe]<sup>+</sup> and [(C<sub>5</sub>H<sub>4</sub>COCH<sub>3</sub>)Fe]<sup>+</sup>, only the former is observed for I suggesting that the difference between the metal-ligand bond strengths in I is much greater than that in IV. IV also shows a prominent fragmentation, [(C<sub>5</sub>H<sub>5</sub>)Fe(C<sub>5</sub>H<sub>4</sub>)]<sup>+</sup> → [C<sub>5</sub>H<sub>5</sub> C<sub>5</sub>H<sub>4</sub>]<sup>+</sup> + Fe which is completely absent in I. Furthermore, no CH<sub>3</sub>-transfer to the metal appears to occur in I although this is observed for IV. The ion [RuC]<sup>+</sup> is observed and although there is no metastable ion to confirm its genesis, fragmentation of [Ru(C<sub>5</sub>H<sub>5</sub>)]<sup>+</sup> by loss of C<sub>5</sub>H<sub>5</sub> would seem an obvious route. Other steps involving C<sub>5</sub>H<sub>5</sub> loss are common in the spectrum of I.

A comparison of the behaviour of II and monobenzoylferrocene (V) shows a similar pattern to that established for the monoacetyl derivatives. The fragmentation of V has been reported by others<sup>5</sup> and is similar to that of IV except that the ion [(C<sub>5</sub>H<sub>5</sub>)Fe(C<sub>5</sub>H<sub>4</sub>)]<sup>+</sup> formed by loss of C<sub>5</sub>H<sub>5</sub>CO<sup>+</sup> is the most intense metal-containing fragment ion. In the case of the ruthenocene derivative (Table 3), the fragmentations M<sup>+</sup> → (M-CO)<sup>+</sup>, M<sup>+</sup> → (M-C<sub>5</sub>H<sub>5</sub>)<sup>+</sup> and M<sup>+</sup> → (M-C<sub>5</sub>H<sub>4</sub>CO)<sup>+</sup> are supported by metastable peaks. As observed above, II also forms the ion

[Ru(C<sub>5</sub>H<sub>5</sub>)]<sup>+</sup> but not [Ru(C<sub>5</sub>H<sub>4</sub>COCH<sub>3</sub>)]<sup>+</sup>. Fragment ions formed by phenyl transfer to the metal atom [(C<sub>5</sub>H<sub>5</sub>)Ru(C<sub>5</sub>H<sub>4</sub>)(C<sub>6</sub>H<sub>5</sub>)]<sup>+</sup> and [(C<sub>5</sub>H<sub>5</sub>)Ru(C<sub>5</sub>H<sub>4</sub>)]<sup>+</sup> are observed.

TABLE 3—MASS SPECTRUM OF MONOBENZOYLRUTHENOCENE (II)

m/z*	Rel. Abd. (%)	I/ $\Sigma$ I (Mo)*	Assignment
336	100	33	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>4</sub> COPh) <sup>+</sup>
308	18	6	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>4</sub> )Ph <sup>+</sup>
306	17	6	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>4</sub> ) <sup>+</sup>
259	24	8	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>4</sub> CO) <sup>+</sup>
244	20	7	(C <sub>5</sub> H <sub>5</sub> )RuPh <sup>+</sup>
231	24	8	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>4</sub> ) <sup>+</sup>
205	12	4	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>3</sub> ) <sup>+</sup>
203	17	6	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H) <sup>+</sup>
167	18	6	(C <sub>5</sub> H <sub>5</sub> )Ru <sup>+</sup>
154	7	2	(C <sub>5</sub> H <sub>4</sub> )Ru <sup>+</sup>
141	18	6	(C <sub>5</sub> H <sub>4</sub> )Ru <sup>+</sup>
139	20	7	(C <sub>5</sub> H <sub>3</sub> )Ru <sup>+</sup>
105	21	—	C <sub>5</sub> H <sub>5</sub> PhCO <sup>+</sup>
102	8	3	Ru <sup>+</sup>
77	42	—	C <sub>5</sub> H <sub>5</sub> <sup>+</sup>
65	17	—	C <sub>5</sub> H <sub>4</sub> <sup>+</sup>
64	16	—	C <sub>5</sub> H <sub>3</sub> <sup>+</sup>
63	25	—	C <sub>5</sub> H <sub>2</sub> <sup>+</sup>
51	42	—	C <sub>5</sub> H <sub>4</sub> <sup>+</sup>
50	29	—	C <sub>5</sub> H <sub>3</sub> <sup>+</sup>
39	33	—	C <sub>5</sub> H <sub>4</sub> <sup>+</sup>

Metastable ions m/z 282 3 336 → 308  
 m/z 199 6 336 → 259  
 m/z 177 2 336 → 244

\* Based on <sup>100</sup>Ru

\* Metal-containing ions only All percentages rounded to the nearest 1.0 %

71% of total metal-containing ion current of II contains more than five of the ten original cyclopentadienyl carbon atoms and 28% contain five or less carbon atoms. These figures are similar to those observed for I, but not dissimilar to those of V (73% and 27%, respectively). However, only 3% of metal-containing ion current consists of Ru<sup>+</sup> ions in II, whereas 13% of that of V consists of Fe<sup>+</sup>.

The mass spectrum of 1,1'-diacetylferrocene (VI) has also been examined in detail previously<sup>6</sup>. The main decomposition routes of the molecular ion, as evidenced by the observed metastable ions are M<sup>+</sup> → (M-CH<sub>3</sub>)<sup>+</sup>, M<sup>+</sup> → (M-CH<sub>3</sub>CO)<sup>+</sup>, (M-CH<sub>3</sub>)<sup>+</sup> → (M-CH<sub>3</sub>-2CO)<sup>+</sup> and (M-CH<sub>3</sub>CO)<sup>+</sup> → (M-CH<sub>3</sub>-2CO)<sup>+</sup> of which the loss of two CO groups in a single step is the most unusual. This behaviour has been observed in the fragmentation of some metal carbonyl complexes<sup>7</sup>. However, it is without precedent in the fragmentation of organic ketones, although it has been observed in the case of some ketone dimers<sup>8</sup>.

In the case of III, metastable ions confirm the fragmentation route, M<sup>+</sup> → (M-CH<sub>3</sub>)<sup>+</sup> → (M-CH<sub>3</sub>-2CO)<sup>+</sup> → [M(C<sub>5</sub>H<sub>5</sub>)]<sup>+</sup>. Thus the single step loss of two CO groups occurs with this molecule also. We propose that the driving force for this unusual fragmentation is formation of [(C<sub>5</sub>H<sub>5</sub>)Ru(C<sub>5</sub>H<sub>4</sub>)]<sup>+</sup> which must again involve a massive reorganisation of the organic ligands, but which is under thermodynamic control. The other fragmentations of III are all of low abundance (Table 4) and are broadly

in accord with those observed for I. Again, 75% of the total metal-containing ion current contains greater than five cyclopentadienyl ring carbon atoms and 25% contain five or less. The figures for VI are 62% and 38%, respectively.

TABLE 4—MASS SPECTRUM OF 1,1-DIACETYLRUTHENOCENE (III)

m/z*	Rel. Abd (%)	I/EI (%)*	Assignment
316	90	19	(C <sub>5</sub> H <sub>5</sub> COCH <sub>3</sub> )Ru(C <sub>5</sub> H <sub>5</sub> COCH <sub>3</sub> ) <sup>+</sup>
301	55	12	(C <sub>5</sub> H <sub>5</sub> COCH <sub>3</sub> )Ru(C <sub>5</sub> H <sub>5</sub> CO)
274	5	1	(C <sub>5</sub> H <sub>5</sub> COCH <sub>3</sub> )Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
259	4	1	(C <sub>5</sub> H <sub>5</sub> CO)Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
245	100	21	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
231	8	2	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
229	9	2	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
217	8	2	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
205	10	2	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
204	10	2	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H) <sup>+</sup>
191	8	2	(C <sub>5</sub> H <sub>5</sub> )Ru(C <sub>5</sub> H) <sup>+</sup>
180	15	3	Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
179	16	3	Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
178	15	3	Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
167	50	11	Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
154	8	2	Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
153	7	2	Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
139	9	2	Ru(C <sub>5</sub> H <sub>5</sub> ) <sup>+</sup>
137	11	2	Ru(C <sub>5</sub> H) <sup>+</sup>
114	14	3	RuC <sub>5</sub> <sup>+</sup>
102	12	2	Ru <sup>+</sup>
78	5		C <sub>5</sub> H <sub>5</sub> <sup>+</sup>
77	3		C <sub>5</sub> H <sub>5</sub> <sup>+</sup>
65	7		C <sub>5</sub> H <sub>5</sub> <sup>+</sup>
64	9		C <sub>5</sub> H <sub>5</sub> <sup>+</sup>
63	13		C <sub>5</sub> H <sub>5</sub> <sup>+</sup>
43	65		CH <sub>3</sub> CO <sup>+</sup>
39	14		C <sub>1</sub> H <sub>5</sub> <sup>+</sup>

Metastable ions m/z 286 7 316 → 301  
199.4 301 → 245  
113 8 245 → 167

\* Based on <sup>101</sup>Ru

\* Metal-containing ions only. All percentages rounded to nearest 10 %.

Thus, in summary, this preliminary study has demonstrated the rich variety of mass spectral fragmentations observed in the spectra of ruthenocene derivatives and further work is in progress in an effort to systematise this behaviour.

### Experimental

Ruthenocene was prepared by the method of Pertici *et al.*<sup>9</sup>. Mono- and diacetylruthenocene are prepared by the method of Hofler and Schlögl<sup>10</sup>. Monobenzoylruthenocene was prepared by a method exactly analogous to that of the mono-acetyl derivative. All gave satisfactory analytical data, nmr and infrared spectra.

Mass spectra were recorded on an ABI M.S.9, operating at 7 eV and 100 μA trap current and a source temperature of 50°.

### References

1. M. CAIS and M. S. LUPIN, *Adv. Organomet. Chem.*, 1970, 8, 211.
2. L. FRIEDMAN, A. P. IRSA and G. WILKINSON, *J. Amer. Chem. Soc.*, 1955, 77, 3689.
3. J. MÜLLER and L. D'OR, *J. Organomet. Chem.*, 1967, 10, 313.
4. G. D. FLESCHE, G. A. JUNK and H. J. SVEC, *J. Chem. Soc., Dalton Trans.*, 1972, 1102.
5. A. MANDELBAUM and M. CAIS, *Tetrahedron Lett.*, 1964, 3847.
6. C. F. SHELLEY and D. L. FISHEL, *Org. Mass. Spectrom.*, 1972, 6, 1131.
7. R. DAVIS, M. L. WEBB, D. S. MILLINGTON and V. PARR, *Org. Mass. Spectrom.*, 1979, 14, 289.
8. N. J. TURRO, D. C. NECKERS, P. A. LEERMAKERS, D. SELDNER and P. D'ANGELO, *J. Amer. Chem. Soc.*, 1965, 87, 4097.
9. P. PERTICI, G. VITULLI, M. PACI and L. PORRI, *J. Chem. Soc., Dalton Trans.*, 1980, 1961.
10. O. HOFLER and K. SCHLÖGL, *J. Organomet. Chem.*, 1968, 13, 443.

# Molecular Orbital Study of $[\text{BFe}(\text{CO})_3]^+$ , $\text{B}=(\text{C}_5\text{H}_5)$ , $(\text{C}_6\text{H}_7)$ and $(\text{C}_7\text{H}_9)$

D. A. BROWN\*, J. P. CHESTER and N. J. FITZPATRICK

Department of Chemistry, University College, Belfield, Dublin 4, Ireland

SCCC and CNDO calculations are reported for the title series of cations and trends are noted and compared with experimental results. The staggered conformation of tricarbonyl [(1,2,3,4,5- $\eta$ )-2,4-cycloheptadien-1-yl] iron(1+) is shown to be the most stable with a barrier to rotation of 1.8 eV. The deformations of  $(\text{C}_7\text{H}_9)$  and  $(\text{C}_6\text{H}_7)$  in the cations are considered. Using the SCCC method, the plane of the saturated carbons is  $45^\circ$  above the plane of the other carbon atoms in  $[(\text{C}_7\text{H}_9)\text{Fe}(\text{CO})_3]^+$ , while the CNDO value is  $42^\circ$ . For  $[(\text{C}_6\text{H}_7)\text{Fe}(\text{CO})_3]^+$  the corresponding angles are  $50^\circ$  (SCCC) and  $51^\circ$  (CNDO).

**M**OLECULAR orbital calculations have been useful in studying trends within a series of related molecules. Thus the series  $\text{AM}(\text{CO})_3$  [ $\text{AM}=(\text{C}_5\text{H}_5)\text{Cr}$ ,  $(\text{C}_5\text{H}_5)\text{Mn}$ ,  $(\text{C}_4\text{H}_4)\text{Fe}$ ,  $(\text{C}_5\text{H}_5)\text{Co}$  and  $(\text{C}_5\text{H}_5)\text{Ni}$ ] has been studied by the SCCC method considering  $\pi$  orbitals only in the hydrocarbon moiety<sup>1</sup>, considering  $\sigma$  and  $\pi$  orbitals<sup>2</sup> and using the CNDO method<sup>3</sup>. In the series  $[\text{BFe}(\text{CO})_3]^+$ ,  $\text{B}=(\text{C}_5\text{H}_5)$ ,  $(\text{C}_6\text{H}_7)$ , nucleophilic substitution has been correlated with the frontier electron density using the SCCC approach<sup>4</sup>. Using the INDO method, a correlation between the bond indices and the site of nucleophilic addition has been noted for tricarbonyl [(1,2,3,4,5- $\eta$ )-2,4-cyclohexadien-1-yl] iron(1+)<sup>5</sup>. The bonding in this cation has also been discussed by Hoffmann and Hoffmann<sup>6</sup>. In the calculations now reported the SCCC method, as used previously, was employed<sup>7</sup>. The experimental geometry of  $[(\text{C}_5\text{H}_5)\text{Fe}(\text{CO})_3]^+$  was considered<sup>7</sup>. The structure of  $[(\text{C}_6\text{H}_7)\text{Fe}(\text{CO})_3]^+$  was based on the analogous Mn compound<sup>8</sup> and the geometry of hexacarbonyl(transazulene)dimanganese<sup>9</sup> was modified to give the geometry of  $[(\text{C}_7\text{H}_9)\text{Fe}(\text{CO})_3]^+$ .

The moiety  $\text{Fe}(\text{CO})_3$  is considered to bond to a hydrocarbon by accepting electrons into the  $d_{xz}$  and  $d_{yz}$  orbitals of iron and donating them from the  $d_{xz}$ - $yz$  and  $d_{xy}$  orbitals<sup>10-14</sup>. Experimentally it is found that  $\text{Fe}(\text{CO})_3$  is a net electron donor. For example, by comparing the apparent  $pK_a$  values of para substituted anilines it was shown that  $\text{Fe}(\text{CO})_3$  has an electron donating capacity similar to phenyl<sup>15</sup>. Also coordination with  $\text{Fe}(\text{CO})_3$  increases the  $pK_a$  values of acids confirming the electron donating properties of tricarbonyl-iron<sup>10-16</sup>. The aromatic nature of  $(\text{C}_6\text{H}_5)\text{Fe}(\text{CO})_3$ , its ability to undergo electrophilic substitution, supports the electron donating ability of  $\text{Fe}(\text{CO})_3$ <sup>17</sup>, as does the increase in stability of carbonium ions following the introduction of tricarbonyliron<sup>18</sup>. From the charges reported in Table 1, it is seen that  $\text{Fe}(\text{CO})_3$ , in all cases, donates electrons to  $\text{B}^+$ . This is particularly evident from the CNDO results

where the hydrocarbon moieties are negatively charged. It may be noted that  $q_B$  increases across

TABLE 1—CHARGES, NORMALISED MULLIKEN POPULATIONS, NORMALISED WIERGO INDICES AND CARBONYL STRETCHING FREQUENCIES

	$[(\text{C}_5\text{H}_5)\text{Fe}(\text{CO})_3]^+$	$[(\text{C}_6\text{H}_7)\text{Fe}(\text{CO})_3]^+$	$[(\text{C}_7\text{H}_9)\text{Fe}(\text{CO})_3]^+$
SCCC $q_B$	0.272	0.314	0.325
$q_{Fe}$	0.595	0.613	0.627
$q_{(CO)_3}$	0.113	0.073	0.048
M. P. M-C(O)	1	0.963	0.885
C-O	1	1.001	0.996
CNDO $q_B$	-0.153	-0.107	-0.055
$q_{Fe}$	0.752	0.724	0.704
$q_{(CO)_3}$	0.401	0.383	0.351
WI M-C(O)	1	0.982	0.967
C-O	1	0.997	0.989
$\nu(\text{CO})^a$	2126 2078	2116 2066 1970	2116 2062 1970

<sup>a</sup> Values of F. M. Hussein in  $\text{cm}^{-1}$  measured in acetonitrile.

the series for both the SCCC and CNDO calculations and  $q_{(CO)_3}$  decreases using both methods. However  $q_{Fe}$  increases using the SCCC method and decreases using the CNDO method across the series though the percentage differences for the iron charges are the smallest. The variations in charge distributions correlate with the carbonyl frequencies as these decrease slightly across the series. Thus in  $[(\text{C}_7\text{H}_9)\text{Fe}(\text{CO})_3]^+$  the donation of electrons from iron to  $\text{B}^+$  is more significant than the donation to the carbonyls, relative to the later members of the series. Thus low positive charge on B and high positive charges on the carbonyl correspond to high frequencies. The metal in this model does not vary so much in charge. Therefore the model is adequate to interpret the carbonyl frequencies. In the  $[\text{BFe}(\text{CO})_3]^+$  series, the average charges on B, Fe and  $-(\text{CO})_3$  are 0.3, 0.6 and 0.1 and for the  $\text{AM}(\text{CO})_3$ , the corresponding values are -0.1, 0.4

and -0.3. In the latter case, more electrons are donated to the carbonyls, corresponding to the lower frequencies in this AM(CO)<sub>5</sub> series. It is interesting to note that in the CNDO study of AM(CO)<sub>5</sub>, maximum donation to A occurred in (C<sub>6</sub>H<sub>5</sub>)Fe(CO)<sub>5</sub>. Qualitatively by considering LUMO energies, Pettit and coworkers noted that pentadienyl type complexes with Fe(CO)<sub>5</sub> have higher frequencies predicted than other complexes with butadiene or non-conjugated dienes<sup>12</sup>.

For comparative purposes as both Mulliken population analyses and Wiberg indices are used, these values in the table were normalised to unity for [(C<sub>6</sub>H<sub>5</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup>. For the C-O values, in general, there is a decrease across the series, with the exception that there is a slight increase in going from [(C<sub>6</sub>H<sub>5</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup> to [(C<sub>6</sub>H<sub>7</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup> using the SCCC method. However the M-C values do not increase across the series. This is in contrast to the AM(CO)<sub>5</sub> series, where the M-C overlap populations decrease using both the SCCC (σ+π)<sup>8</sup> and SCCC (π)<sup>13</sup> methods, while the C-O experimental frequencies and corresponding overlap populations increase across the series. Also the M-C(O) Wiberg indices, in general, decrease and the C-O values increase across the AM(CO)<sub>5</sub> series<sup>8</sup>. The field absorption mass spectra of [(C<sub>6</sub>H<sub>7</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup> and [(C<sub>7</sub>H<sub>9</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup> have been reported and ions corresponding to the loss of one CO from the molecular ions were detected; the spectrum of tricarbonyl(benzene)-chromium consists of only the molecular ion<sup>10</sup>. These results agree with the more negative carbonyl charge in (C<sub>6</sub>H<sub>5</sub>)Cr(CO)<sub>5</sub> and its lower carbonyl frequencies.

In the figure the eclipsed and staggered conformers of [(C<sub>7</sub>H<sub>9</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup> are defined, together with the angle α. This angle was varied and it was found, using the SCCC method, that the preferred geometry was the staggered one (α=0°), in which there is a CO group below the midpoint of the saturated C-C bond in the hydrocarbon moiety. This result is in agreement with the experimental geometry<sup>9</sup>. The calculated difference between the two conformers is 1.8 eV. If one or more CO groups were replaced by larger groups it might be possible to observe the rotamers of such a molecule. A variable temperature <sup>13</sup>C nmr study of (C<sub>7</sub>H<sub>9</sub>)Fe(CO)<sub>5</sub>(CO<sub>2</sub>Et) showed some evidence for such rotamers by a broadening of the carbonyl shift as the temperature was lowered<sup>10</sup>. Also <sup>31</sup>P nmr studies detected rotamers of [BFe(CO)<sub>5</sub>-(EPTP)]<sup>+</sup>, B=(C<sub>6</sub>H<sub>7</sub>), (C<sub>7</sub>H<sub>9</sub>); x=1, 2; EPTP=4-ethyl-1-phospha-2,6,7-trioxabicyclo-[2.2.2] octane<sup>11</sup>.

Deformations of the (C<sub>7</sub>H<sub>9</sub>) and (C<sub>6</sub>H<sub>7</sub>) ligands may be discussed. The (C<sub>7</sub>H<sub>9</sub>)<sup>+</sup> ligand is predicted on symmetry grounds to be bent rather than planar by considering this ligand as formed from C<sub>2</sub>H<sub>5</sub><sup>+</sup> and C<sub>5</sub>H<sub>4</sub><sup>+</sup>. In the planar geometry, if the π orbitals of ethylene are in the plane of the pentadienyl carbons, there is no interaction. If all the π orbitals are parallel, the hydrogen atoms in C<sub>2</sub>H<sub>5</sub><sup>+</sup> and C<sub>5</sub>H<sub>4</sub><sup>+</sup>

would be sterically unsuitable. In the non-planar case the pentadienyl orbitals in increasing energy




Fig. 1. Staggered and eclipsed conformations of [(C<sub>7</sub>H<sub>9</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup>.

have symmetries S, A, S, A, S. In C<sub>2</sub>H<sub>5</sub><sup>+</sup> the lowest two are occupied. Thus the ethylene π(S) can interact with the S LUMO of C<sub>2</sub>H<sub>5</sub><sup>+</sup> and the A HOMO of C<sub>2</sub>H<sub>5</sub><sup>+</sup> can also interact with the π\*(A) of ethylene. The sum of the one electron energies of the [(C<sub>7</sub>H<sub>9</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup> cation was calculated by the SCCC method for different values of the angle between the C<sub>7</sub>H<sub>9</sub> plane and the plane of the saturated carbon atoms of the (C<sub>7</sub>H<sub>9</sub>)<sup>+</sup> ligand. The minimum energy, calculated by least squares fit, was at 49° while the experimental value is 39°. The calculations were repeated using the CNDO method and the minimum energy was at 42°, which is closer to the experimental value. Calculations by both the SCCC and CNDO methods confirm the non-planarity of (C<sub>7</sub>H<sub>9</sub>) in [(C<sub>7</sub>H<sub>9</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup>. The deformation angle was calculated to be 50° using the SCCC method and 51° using the CNDO approach, while the experimental angle is 43°. Thus, both the SCCC and CNDO methods predict that the deformation in [(C<sub>7</sub>H<sub>9</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup> is greater than in [(C<sub>6</sub>H<sub>7</sub>)Fe(CO)<sub>5</sub>]<sup>+</sup>, in agreement with experiment.

#### References

1. D. A. BROWN, N. J. FITZPATRICK and N. J. MATHEWS, *J. Organomet. Chem.*, 1975, 88, C27.
2. D. A. BROWN, J. P. CHESTER, N. J. FITZPATRICK and I. J. KING, *Inorg. Chem.*, 1977, 16, 2497.
3. N. J. FITZPATRICK, J. -M. SAVARIAULT and J. -F. R. LABARRE, *J. Organomet. Chem.*, 1977, 127, 325.
4. D. A. BROWN, J. P. CHESTER and N. J. FITZPATRICK, *J. Organomet. Chem.*, 1978, 155, C21.
5. D. W. CLACK, M. MONSHI and L. A. P. KANE-MAGUIRE, *J. Organomet. Chem.*, 1976, 107, C40.
6. R. HOFMANN and P. HOFMANN, *J. Amer. Chem. Soc.*, 1974, 96, 598.



7. M. E. GRESS and R. A. JACOBSON, *Inorg. Chem.*, 1973, 12, 1746.
8. M. R. CHURCHILL and F. R. SCHOLER, *Inorg. Chem.*, 1969, 8, 1950.
9. M. R. CHURCHILL and P. H. BIRD, *Inorg. Chem.*, 1968, 7, 1793.
10. M. ELIAN and R. HOFFMANN, *Inorg. Chem.*, 1975, 14, 1058.
11. R. PETTIT and G. F. EMERSON, *Adv. Organomet. Chem.*, 1964, 1, 1.
12. R. PETTIT, G. F. EMERSON and J. E. MAHLER, *J. Chem. Educ.*, 1963, 40, 175.
13. M. J. S. DEWAR, *Bull. Soc. Chim. Fr.*, 1951, 18, C79.
14. J. CHATT and L. A. DUNCANSON, *J. Chem. Soc.*, 1953, 2939.
15. J. M. LANDESSBERG and L. KATZ, *J. Organomet. Chem.*, 1971, 33, C15.
16. D. STIERLE, E. R. BIEHE and P. C. REEVES, *J. Organomet. Chem.*, 1974, 72, 221.
17. J. D. FITZPATRICK, L. WATTS, C. F. EMERSON and R. PETTIT, *J. Amer. Chem. Soc.*, 1965, 87, 3254.
18. R. E. DAVIES, H. D. SIMPSON, N. GRICE and R. PETTIT, *J. Amer. Chem. Soc.*, 1971, 93, 6688.
19. D. E. JAMES, A. H. JACKSON, L. A. P. KANE-MAGUIRE and K. TAYLOR, *J. Organomet. Chem.*, 1975, 88, 345.
20. F. M. HUSSEIN, Ph.D. Thesis, Nat. Univ. of Ireland, 1891.
21. T. H. WHITESIDES and R. A. BUDRIK, *Inorg. Chem.*, 1975, 14, 664.

# NMR Spectroscopy of Oriented Organoselenium Compounds

C. L. KHETRAPAL

Raman Research Institute, Bangalore-560 080

The use of nmr spectroscopy of oriented molecules in the determination of molecular structure and conformation of organoselenium compounds is presented. Determination of various spectral parameters including their anisotropic contributions is discussed. An up-to-date available information on the selenium compounds is included.

**E**XTENSIVE use of nmr spectroscopy of molecules oriented in liquid crystals has been made towards the determination of structure and conformation of small organic molecules<sup>1-5</sup>. To a much lesser extent, biologically important systems<sup>6</sup> and inorganic compounds<sup>7</sup> have been investigated using this method, probably due to structural complexities and relatively poor solubilities. On the other hand, the technique promises to provide such structural, conformational and functional information which is otherwise difficult to obtain. Various applications including those in inorganic chemistry have been reviewed from time to time<sup>1-7</sup>. The present report summarises some applications to organo-selenium compounds with emphasis on the work done by the Bangalore group

are performed under the conditions that the liquid crystal director is along or orthogonal to the direction of spinning. A typical spectrum of dimethylselenium is shown in Fig 1. Line-widths of around 1-5 Hz are usually obtained in the spectra of oriented molecules.

For the selenium compounds, <sup>77</sup>Se has a natural abundance of 7.58% and spin  $\frac{1}{2}$  and <sup>77</sup>Se-<sup>1</sup>H couplings can either be determined from studies of the selenium resonance or from the <sup>77</sup>Se-<sup>1</sup>H satellites in the proton spectra. The latter technique is more common due to larger sensitivity of protons compared to selenium and also because the normally available spectrometers with facilities to study protons can be used. Furthermore, studies of the satellite spectra have the advantage that the information on the H-H and Se-H couplings can be obtained from the same experiment and the errors arising from the change of experimental conditions are avoided. However, for the <sup>77</sup>Se-<sup>77</sup>Se couplings and the <sup>77</sup>Se-chemical shift anisotropy studies, <sup>77</sup>Se-nmr may be necessary.

## Experimental

NMR spectra of oriented molecules can be recorded on normal high resolution spectrometers. Suitable solutions<sup>1-5</sup> are prepared in liquid crystals and the spectra recorded with or without sample spinning depending upon whether the experiments




Fig. 1. NMR spectrum of oriented dimethylselenide. The spectrum is symmetrical about the dashed line and only half the spectrum to the right of the line shown. Liquid crystal solvent used: A mixture of N-(*p*-ethoxybenzylidene)-*p*-*n*-butylaniline and butyl-*p*-(*p*-ethoxyphenoxy-carbonyl)-phenylcarbonate. Solute concentration: 9 mole per cent; Temp.: 30°; Spectrometer frequency: 100 MHz.

### Basic principles

Though the basic principles of the technique are well known and documented, their brief presentation in this article is meaningful for the sake of completeness. Due to inherent molecular ordering and flow of the medium, the molecules dissolved in liquid crystal solvents show orientational effects and provide such information in the spectra which is otherwise not obtainable from the spectra in normal isotropic media. Such spectra for spin  $\frac{1}{2}$  nuclei (*i* and *j*) contain information not only on the average values of the chemical shift ( $\nu_i - \nu_j$ ) and indirect spin-spin ( $J_{ij}$ ) and direct dipole-dipole ( $D_{ij}$ ) coupling tensors but anisotropic contributions of these second rank tensors can also be derived from the spectra. Of these, the most important parameters from the structural and the conformational points of view are the direct dipolar couplings and chemical shift anisotropy. Their determination and use will, therefore, be discussed in detail with emphasis to organoselenium compounds.

Having obtained the spectra, they are analysed using the standard procedures reported in the literature<sup>1-5</sup>. The analysis procedures are usually similar to those for the analysis of the spectra in the isotropic media except that the Hamiltonian contains additional terms due to various anisotropic contributions. The computer programs such as LAOCOONOR<sup>6</sup> or LEQUOR<sup>7</sup> are normally used.

The direct dipole-dipole coupling derived from the spectra of oriented molecules is related to the internuclear distance ( $r_{ij}$ ) as in equation (1).

$$D_{ij} = \frac{\gamma_i \gamma_j}{4\pi^2} \cdot \frac{S_{ij}}{r_{ij}^3} \quad (1)$$

where  $\gamma$  is the magnetogyric ratio and  $S_{ij}$  is the degree of order of the axis *ij*.

The chemical shift anisotropy ( $\Delta\sigma_i$ ) for a nucleus in a 3-fold or higher symmetry axis is given by equation (2):

$$\Delta\sigma_i = \frac{3}{2} \cdot \frac{\sigma_{ia}}{S_{aa}} \quad (2)$$

where  $\sigma_{ia}$  is the chemical shift in the anisotropic medium with respect to that in the isotropic phase and  $S_{aa}$  is the order parameter of the symmetry axis.


Relations between other anisotropic and order parameters are reported in the literature<sup>1-5</sup>.

The direct dipolar couplings derived from the analysis of the spectra of oriented molecules are used to determine molecular geometries with the help of equation (1). However, since the order parameters also have to be determined from the spectra, the number of independent dipolar couplings must at least equal the sum of the required order and geometrical parameters so as to obtain the necessary geometrical information without making assumption.

Equation (1) shows that if the order parameter and  $\gamma_j$  are changed by a constant factor,  $D_{ij}$ 's

and hence the spectra of oriented molecules remain unchanged. Since the order parameter has to be determined from the same experiment, the method provides relative internuclear distances rather than their absolute values.

A typical illustration of the determination of the structure of selenophene<sup>10,11</sup> (Structure 1) is given below before describing results on some other selenium compounds.



The analysis of the  $^1\text{H}$ -nmr spectrum of selenophene with  $^{77}\text{Se}$ -H satellites and without  $^{13}\text{C}$ -H satellites provides four different interproton dipolar couplings, namely,  $D_{12}$ ,  $D_{13}$ ,  $D_{14}$  and  $D_{23}$  and two  $^{77}\text{Se}$ -H couplings, namely,  $D_{15}$  and  $D_{25}$ . On the other hand only 3 independent ratios of the internuclear distances are necessary to describe the relative interproton and proton-selenium distances. Even after the determination of the molecular order, the system provides one additional coupling than that necessary for the determination of molecular geometry. Hence, in such a case the relative internuclear distances, i.e.,  $r_{12}/r_{23}$ ,  $r_{13}/r_{23}$  and  $r_{15}/r_{25}$  are determined by a least-square-fit computer programme which provides the geometrical and the order parameters such that the sum of the squares of the deviations between the observed and the calculated dipolar couplings is minimum. A computer programme referred to as SHAPE<sup>12</sup> is the one which is most commonly used for such a purpose. The values determined are shown in Table 1, including those derived from microwave spectroscopic studies. It may be mentioned that the proton nmr spectrum of oriented selenophene including  $^{77}\text{Se}$ -H and  $^{13}\text{C}$ -H satellites has in fact been studied and the carbon positions have also been determined. They are not included in the table for the sake of simplicity.

TABLE 1—RATIOS OF THE INTERNUCLEAR DISTANCES IN SELENOPHENE DETERMINED FROM NMR SPECTROSCOPY

Parameter	Value	
	NMR	Microwave
$r_{12}/r_{23}$	$1.002 \pm 0.006$	0.997
$r_{13}/r_{23}$	$1.837 \pm 0.004$	1.785
$r_{15}/r_{25}$	$1.849 \pm 0.004$	1.802

It may be mentioned that nmr spectroscopy of oriented molecules provides values in the liquid phase whereas other techniques such as X-ray, electron and neutron diffractions and microwave spectroscopy values are in the solid or the gaseous phases.

### Applications


Selenium is an ideal nucleus from the point of view of nmr spectroscopy. The natural abundance of spin 1/2 isotope ( $^{77}\text{Se}$ ) is reasonably large (7.58%) and the compounds provide relatively sharp lines. The proton nmr spectra of 1,3-dithiole-2-selone, 1,3-thiaselenole-2-thione and 1,3-diselenole-2-selone oriented in the nematic phases of N-(*p*-methoxybenzylidene)-*p*-*n*-butylaniline (MBBA) or N-(*p*-ethoxybenzylidene)-*p*-*n*-butylaniline (EBBA) show lines with widths less than 1.5 Hz on a WH-270 spectrometer and hence the observation of  $^{77}\text{Se-H}$  and  $^{13}\text{C-H}$  satellites in these systems present no special difficulties<sup>18</sup>.

Several selenium compounds such as dimethylselenide<sup>14,15</sup>, difluorophosphine selenide<sup>16</sup>, selenophene<sup>10,11</sup>, 2,1,3-benzoselenadiazole<sup>17</sup>, benzo(b)selenophene<sup>22</sup>, 1,2,5-selenadiazole<sup>19</sup>, phenyl selenyl chloride and bromide<sup>20</sup>, 3-phenyl-1,2,5-selenadiazole<sup>21</sup>, tetraselenafulvalene<sup>22</sup>, selenophene-2-carbaldehyde<sup>23</sup>, 2,2'-biselenophene<sup>24</sup>, trimethylphosphine selenide<sup>25-27</sup> and triphenyl selenophosphine<sup>28</sup> have been investigated in order to derive structural and conformational informations, and chemical shift anisotropies. In addition, 2-dimensional proton nmr spectrum of oriented 1-thia-3-selenole-2-thione has also been studied without  $^{77}\text{Se-H}$  and  $^{13}\text{C-H}$  satellites for the unique determination of  $(J_{\text{HH}} + 2D_{\text{HH}})$ —an information which cannot be obtained from the single resonance 1-dimensional spectrum<sup>29,30</sup>.

From the analysis of the proton nmr spectrum of dimethyl selenide with  $^{77}\text{Se-H}$  satellites, the indirect spin-spin coupling between the protons of the two methyl groups has been determined as 0.1 Hz. A study of the spectrum including  $^{77}\text{Se-H}$  as well as  $^{13}\text{C-H}$  satellites has also been undertaken and the molecular structure derived. Assuming the internuclear (C-Se) distance ( $r_{\text{C-Se}}$ ) as 1.943 Å, a value of  $r_{\text{C-H}}$  as 1.073 Å has been obtained. The bond angles C-Se-C, H-C-Se and H-C-H have been derived as 95.7°, 106.22° and 110.14°, respectively. The  $C_2$ -symmetry axes of the methyl groups are displaced from the C-Se axes by 2.57° in such a way that the C-Se-C angle is reduced.

In difluorophosphine selenide, the SePF, FPF and SePH bond angles have been obtained as 116.8°, 98.1° and 118.6°, respectively.

The geometry-information in selenophene has been derived and the results are reported in the previous section. An interesting application has emerged from the studies on several heteroaromatic 5-membered ring systems (Structure 2).  $r_{14}/r_{22}$  has



X=O, N(H), C(H), S, P, Se, Te  
Structure 2

been found to vary inversely with the van der Waals or covalent radii<sup>31</sup>. Values of these quantities have been determined for X=O, S, CH, NH, P, Se and Te.

The structure of 2,1,3-benzoselenadiazole has been derived from the proton nmr spectrum. Values of the indirect proton-proton couplings and the relative interproton distances indicate considerable bond fixation in the 6-membered ring of benzoselenadiazole. In 1,2,5-selenadiazole, for which the  $^1\text{H}$ -nmr spectra including  $^{13}\text{C}$  and  $^{77}\text{Se}$ -satellites have been obtained, the interproton distance has been derived by assuming the ring geometry in addition to a scaling distance. The structure of the 6 and the 5 membered rings in benzo(b)-selenophene has been derived from its nmr spectrum in a lyotropic solvent.

Recently, very interesting new applications of nmr spectroscopy of oriented molecules have been discovered<sup>32</sup>. The studies involve recording the spectra in a mixture of 2 liquid crystals of opposite diamagnetic anisotropies. At a critical relative concentration of the two liquid crystals, it is possible to obtain spectra with two different types of molecular orientations if the temperature is suitably adjusted. The two orientations provide dipolar couplings in the exact ratio 1:2. The results are theoretically well understood<sup>33</sup>. These experiments provide spectral information which is otherwise not possible to derive from the spectra of oriented molecules. For example, separate determination of the indirect and the direct dipolar couplings between heteronuclei is possible only from such experiments. The method has been used to determine  $^{77}\text{Se-H}$  indirect couplings in phenylselenyl chloride and bromide. The structural information in these systems has also been determined.

The preferred conformation of 3-phenyl-1,2,5-selenadiazole has been found to be twisted around the bond between the two rings and the angle of twist is  $\approx 20^\circ$ . A comparison of the results with those in 3-phenyl-1,2,5-oxa and thiadiazoles in different solvents shows that the conformation is little influenced by the nature of the heteroatom at position 2 or the solvent. The molecule tetraselenafulvalene is shown to be either puckered in a boat form or possessing a broad potential function for the puckering motion. The dihedral angle between the  $\text{SeHC=CHSe}$  and  $\text{Se}_2\text{C=CSe}_2$  planes is  $15.5 \pm 0.6^\circ$ .

In selenophen-2-carbaldehyde, the conformational information is derived by assuming that the positions of the  $\beta$ -ring protons are the same as those in selenophene and considering either the existence of a single planar conformer or the *cis-trans* equilibrium. The existence of the Se-O *cis* conformer is confirmed though some evidence was also found for the presence of a small amount of Se-O *trans* conformer. 2,2'-Biselenophene has been shown to be present as an equilibrium between two twisted conformers, the *transoid* one being more abundant and the angle of twist being  $25 \pm 5^\circ$ .

The chemical shift and the indirect spin-spin coupling anisotropies have also been determined in some of the selenium compounds. The phosphorus-selenium indirect coupling constant in  $\text{PSe}(\text{CH}_3)_3$  has been measured as  $-704$  Hz. A comparison of the X-ray diffraction and nmr results in  $\text{PSe}(\text{CH}_3)_3$  shows that the phosphorus-selenium indirect coupling is highly anisotropic. The  $^{13}\text{C}$  and  $^{31}\text{P}$ -chemical shift anisotropies in  $(\text{CH}_3)_3\text{PSe}$  are  $18 \pm 10$  and  $99 \pm 15$  ppm, respectively. The C-P-C bond angle is  $105.0 \pm 0.2^\circ$ . The  $^{31}\text{P}$ -chemical shift anisotropy in triphenylphosphine selenide is determined as 103 ppm.

### Conclusion

The survey provides an up-to-date information available from the spectra of oriented selenium compounds. The technique is potentially useful in the structural and conformational problems in selenium chemistry.

### References

1. P. DIEHL and C. L. KHETRAPAL, in "NMR Basic Principles and Progress", (Ed.) P. DIEHL, E. FLUCK and R. KOSFELD, Springer-Verlag, Berlin, 1969, Vol 1
2. C. L. KHETRAPAL, A. C. KUNWAR, A. S. TRACEY and P. DIEHL, in "NMR Basic Principles and Progress", (Ed.) P. DIEHL, E. FLUCK and R. KOSFELD, Springer-Verlag, Berlin 1975, Vol 9.
3. J. W. EMSLEY and J. C. LINDON, in "NMR Spectroscopy Using Liquid Crystal Solvents", Pergamon Press, New York, 1975
4. C. L. KHETRAPAL and A. C. KUNWAR, in "Advances in Magnetic Resonance", (Ed.) J. S. WAUGH, Academic Press, New York, 1977.
5. C. L. KHETRAPAL and A. C. KUNWAR, in "Advances in Liquid Crystals", (Ed.) G. H. BROWN, Academic Press, New York, Vol 6 (in the press)
6. C. L. KHETRAPAL, *Int. J. Quan. Chem.*, 1981, 20, 485.
7. C. L. KHETRAPAL, *J. Indian Chem. Soc.*, 1982, 59, 164.
8. P. DIEHL, C. L. KHETRAPAL and H. P. KELLERHALS, *Mol. Phys.*, 1968, 15, 333
9. P. DIEHL, H. P. KELLERHALS and W. NIEDERBERGER, *J. Mag. Res.*, 1971, 4, 35
10. K. I. DAHLQVIST and A. B. HORNEFELDT, *Chem. Scripta*, 1971, 1, 125.
11. G. CHIDICHIMO, F. LELI, M. LONGERI, N. RUSSO and C. A. VERACINI, *J. Mag. Res.*, 1980, 41, 35.
12. P. DIEHL, P. M. HENRICHs and W. NIEDERBERGER, *Mol. Phys.*, 1971, 20, 139.
13. C. L. KHETRAPAL, A. C. KUNWAR, D. N. SATYANARAYANA and K. R. GAYATHRI DEVI, unpublished work.
14. C. L. KHETRAPAL, unpublished work
15. P. DIEHL, A. C. KUNWAR and H. BÖSINGER, *J. Orgomet. Chem.*, 1978, 145, 303.
16. A. S. F. BOYD, G. S. LAURENSEN and D. W. H. RANKIN, *J. Mol. Struct.*, 1981, 71, 217.
17. C. L. KHETRAPAL and A. C. KUNWAR, *J. Orgomet. Chem.*, 1981, 174, 343
18. W. E. BECHTOLD and J. H. GOLDSTEIN, *Org. Mag. Res.*, 1981, 16, 14
19. G. CHIDICHIMO, F. LELI, P. L. BARILI and C. A. VERACINI, *Chem. Phys. Lett.*, 1978, 55, 519.
20. N. SURYAPRAKASH, A. C. KUNWAR and C. L. KHETRAPAL, unpublished work
21. C. A. VERACINI, A. DE MUNNO, V. BERTINI, M. LONGERI and G. CHIDICHIMO, *J. Chem. Soc., Perkin II*, 1977, 561
22. T. C. WONG and E. M. ENGLER, *J. Mol. Struct.*, 1980, 67, 279.
23. P. BUCCI, G. CHIDICHIMO, F. LELI, M. LONGERI and N. RUSSO, *J. Chem. Soc., Perkin II*, 1979, 109.
24. G. CHIDICHIMO, F. LELI, M. LONGERI, N. RUSSO and C. A. VERACINI, *Chem. Phys. Lett.*, 1979, 67, 384
25. J. P. ALBRAND, A. COGNE and J. B. ROBERT, *Chem. Phys. Lett.*, 1977, 48, 524.
26. A. J. MONTANA, N. ZUMBULYADIS and B. P. DAILEY, *J. Amer. Chem. Soc.*, 1977, 99, 4290
27. A. COGNE, A. GRAND, J. LAUGIER, J. B. ROBERT and L. WIESENFELD, *J. Amer. Chem. Soc.*, 1980, 102, 2238
28. J. B. ROBERT and L. WIESENFELD, *J. Mag. Res.*, 1980, 38, 357
29. C. L. KHETRAPAL, ANIL KUMAR, A. C. KUNWAR, P. C. MATHIAS and K. V. RAMANATHAN, *J. Mag. Res.*, 1980, 37, 349.
30. C. L. KHETRAPAL, ANIL KUMAR, A. C. KUNWAR, P. C. MATHIAS and K. V. RAMANATHAN, "Proc. Int. Liquid Crystals Conf. Bangalore", Heyden & Son, 1980, p. 469
31. C. L. KHETRAPAL, A. C. KUNWAR and K. P. SINHA, *Chem. Phys. Lett.*, 1979, 67, 444.
32. C. L. KHETRAPAL and A. C. KUNWAR, *Chem. Phys. Lett.*, 1981, 82, 170.
33. R. SUBBURAM, K. P. SINHA and C. L. KHETRAPAL, unpublished work

# ESR Study of Cu(II)-N-Aryl Glycinates

L. J. BAI, Z. F. WANG and Y. T. CHEN\*

Department of Chemistry and Institute of Elemento-Organic Chemistry,  
Nankai University, Tianjin, P. R. China

Ten Cu(II) complexes of N-substituted phenylglycines,  $RC_6H_4NHCH_2COOH$ , have been synthesized (R = H, *p*-MeO, *p*-Me, *p*-Cl, *p*-NO<sub>2</sub>, *m*-MeO, *m*-Me, *m*-Cl, *m*-NO<sub>2</sub>, and *o*-Me). The powder esr spectra and magnetic susceptibility of these complexes have been measured and their structure and splitting of energy levels of Cu(II) ion in crystal field have been discussed in the light of the physicochemical data obtained

**E**SR study is a useful method to investigate crystal structure and to determine the ground state of electrons in the metal ion. For Cu(II) ion, its six coordinated compounds can not achieve the highest symmetry O<sub>h</sub> because of the Jahn-Teller effect; it can have only D<sub>4h</sub> or lower symmetry if some other unsymmetrical factors exist. If the unpaired electron of Cu(II) occupied the  $d_{x^2-y^2}$  orbital as the ground state, there would be elongated distortion of the electron density of Cu(II) ion and the esr spectra would show  $g_{\parallel} > g_{\perp}$ . On the other hand, if  $d_{z^2}$  is the ground state, there would be compressed distortion and the esr would show  $g_{\parallel} < g_{\perp}$ . The majority of Cu(II) complexes show  $g_{\parallel} > g_{\perp}$  which means that  $d_{x^2-y^2}$  is commonly the ground state. In some cases, however, for complexes of  $g_{\parallel} < g_{\perp}$  the ground state may still be  $d_{x^2-y^2}$ .

We have prepared ten Cu(II) complexes of N-substituted phenylglycines and have their powder esr spectra and magnetic susceptibility measured. Their structures and splitting of energy levels of the Cu(II) ion have been discussed.

## Experimental

### Preparation of N-arylglycines:

All chemicals were of reagent grade. The synthesis of N-phenylglycine and N-(*para*-substituted phenyl)glycines have been reported previ-

ously<sup>2</sup> and the N-(*meta*-substituted phenyl)glycines are reported elsewhere<sup>3</sup>. The *ortho* substituted isomer, N-(*o*-methylphenyl)glycine, was prepared by the method of Walls<sup>4</sup>.

### Preparation of Cu(II)-N-arylglycinates:

The ligand was dissolved in dilute NaOH solution and pH adjusted to 7-8. To the ligand solution was added a half-equimolar solution of  $Cu(NO_3)_2 \cdot 3H_2O$ . After 10 min of stirring the precipitate was filtered off and washed with water until free from nitrate ion. The solid product was dried below 70° for 8-12 hr. The results of chemical analysis of these Cu(II) complexes are given in Table 1.

### Physical measurements:

Magnetic susceptibilities of the complexes were measured in a Gouy balance at room temperature using double distilled water, aqueous nickel chloride solution and  $Ni(en)_3SO_4$  as the calibrants. The experimental and calculated magnetic moment values are also shown in Table 1.

The powder esr spectra of the complexes were measured at room temperature with a JES-3BX ESR spectrometer, equipped with 100 KHz field modulation unit. DPPH with  $g=2.0036$  and  $Mn^{2+}$  (MgO) were used as the standard field markers. The measured data of  $g_{\parallel}$  (or  $g_1$ ),  $g_{\perp}$  (or  $g_2$ ),  $g_3$  and  $g_{av}$  of these copper(II) complexes are given in Table 2.

TABLE I—ANALYTICAL DATA AND MAGNETIC MOMENTS OF Cu(II)-N-(SUBSTITUTED PHENYL) GLYCINATES

Substituent R	Molecular formula	Analysis %				Magnetic moment (B. M.)		
		Nitrogen		Copper		Temp. K	Found	Calcd.
		Calcd.	Found	Calcd.	Found			
H	CuL <sub>2</sub>	7.70	7.63	17.46	17.53	280	1.80	1.84
<i>p</i> -MeO	"	6.61	6.80	14.99	15.03	281	1.85	"
<i>p</i> -Me	"	7.15	7.19	16.21	16.76	290	1.99	"
<i>p</i> -Cl	"	6.47	6.55	14.68	14.88	291	1.88	1.85
<i>p</i> -NO <sub>2</sub>	CuL <sub>2</sub> ·4H <sub>2</sub> O	10.65	10.79	12.08	12.09	290	1.95	1.94
<i>m</i> -MeO	CuL <sub>2</sub> ·2H <sub>2</sub> O	6.09	6.24	13.82	14.16	285	1.88	1.85
<i>m</i> -Me	CuL <sub>2</sub>	7.15	7.44	16.21	16.15	284	1.94	"
<i>m</i> -Cl	CuL <sub>2</sub> ·2H <sub>2</sub> O	5.98	6.26	13.56	13.58	289	1.91	"
<i>m</i> -NO <sub>2</sub>	CuL <sub>2</sub> ·2H <sub>2</sub> O	11.44	11.43	12.97	13.16	281	1.85	1.84
<i>o</i> -Me	CuL <sub>2</sub>	7.15	7.00	16.21	16.14	285	1.85	"

TABLE 2—ESR DATA OF Cu(II)-N-(SUBSTITUTED PHENYL)GLYCINATES

Ligand	$g_1$ (or $g_1$ )	$g_2$ (or $g_2$ )	$g_3$	$g_{av}$	$\xi/\Delta_1$	$\xi/\Delta_2$	$\xi/\Delta_3$
PG	$2.2248 \pm 0.0020$	$2.0646 \pm 0.0003$		2.1191	0.02781	0.03115	
<i>p</i> -MeOPG	$2.2256 \pm 0.0030$	$2.0664 \pm 0.0003$		2.1208	0.02791	0.03205	
<i>p</i> -MePG	$2.2273 \pm 0.0020$	$2.0667 \pm 0.0005$		2.1216	0.02813	0.03220	
<i>p</i> -ClPG	2.2403	$2.0854 \pm 0.0005$		2.1383	0.02975	0.04155	
<i>p</i> -NO <sub>2</sub> PG	$2.4351 \pm 0.0040$	$2.0599 \pm 0.0030$		2.2421	0.05410	0.02880	
<i>m</i> -MeOPG	$2.2472 \pm 0.0030$	$2.0936 \pm 0.0004$	$2.0532 \pm 0.0004$	2.1330	0.03061	0.04565	0.02545
<i>m</i> -MePG	$2.2338 \pm 0.0010$	$2.0770 \pm 0.0010$		2.1305	0.02894	0.03735	
<i>m</i> -ClPG	$2.2488 \pm 0.0040$	$2.0787 \pm 0.0006$		2.1369	0.03081	0.03870	
<i>m</i> -NO <sub>2</sub> PG	$2.2037 \pm 0.0006$	$2.1151 \pm 0.0006$	$2.0715 \pm 0.0009$	2.1298	0.02480	0.05640	0.03460
<i>o</i> -MePG	$2.1756 \pm 0.0030$	$2.0657 \pm 0.0030$		2.1264	0.02166	0.03170	

## Results and Discussion

For copper(II) ion in a crystal field, the magnetic moment ( $\mu$ ) was calculated by the first approximation method<sup>5</sup>

$$\mu^2 = 3.4 g_{av}^2 \quad \dots (1)$$

$$g_{av}^2 = 1/3(g_1^2 + g_2^2 + g_3^2) \quad \dots (2)$$

In a  $D_{4h}$  field,  $g_1 = g_2$ ,  $g_3 = g_3 = g_3$ . By substituting the  $g$  values obtained from esr spectra into the above equations, the corresponding  $\mu$  values were calculated which are listed in the last column of Table 1.

It is seen from Table 2 that  $g_1 > g_2$  for all the copper(II) complexes of N-arylglycines, which implies that the 3d unpaired electron of Cu(II) ion should occupy the  $d_{x^2-y^2}$  orbital and it would have elongated distorted octahedral conformation. As  $d_{x^2-y^2}$  is the ground state, the  $g$ 's in a  $D_{4h}$  symmetry field should be

$$g_1 = g_e + \frac{8\xi}{\Delta_1} \quad (3)$$




Fig 1 Ligand field splitting of d-orbitals in Cu(II) complexes

were obtained which are shown in the last three columns in Table 2

The shapes of the esr spectra of the complexes are shown in Fig 2.




Fig 2

$$g_1 = g_e + \frac{2\xi}{\Delta_1} \quad \dots (4)$$

while in a  $D_{3h}$  symmetry field,

$$g_1 = g_e + \frac{8\xi}{\Delta_1} \quad (5)$$

$$g_2 = g_e + \frac{2\xi}{\Delta_2} \quad (6)$$

$$g_3 = g_e + \frac{2\xi}{\Delta_3} \quad (7)$$

where  $g_e$  is the  $g$  value of free electron ( $g_e = 2.0023$ ) and  $\xi$  is the spin-orbit coupling constant which is taken as  $830 \text{ cm}^{-1}$  for the free copper(II) ion. The significance of  $\Delta$  value is shown in Fig. 1.

The various  $g$  values were obtained from esr spectra. When these  $g$  values were substituted into the above equations, the corresponding  $\xi/\Delta$  values

In Fig. 2(a) shows an axial pattern which suggests that the four atoms (N, N, O, O) are coplanar and are about equidistant from copper atom. Since the powder technique is not sensitive enough to resolve the two planar components (Cu—O, Cu—N), so that, should the true symmetry of these complexes be  $D_{3h}$  (*trans* configuration with six- or four-coordination) or even lower (*cis* configuration or *trans* configuration with five-coordination), the poor resolution obtained would still justify the use of  $D_{4h}$  symmetry.

These complexes may be considered to have the normal amino acid chelate type of structure (I of Fig. 3) in which the aromatic nitrogen atom and one of the carboxyl oxygen atoms act as donors while additional water molecules or the C=O oxygen atoms of neighbouring molecules further coordinated along the axis normal to the molecular

plane to form an elongated octahedral or square-based pyramidal configuration.

It is seen from Table 2 that for these complexes  $\xi'/\Delta_1 < \xi/\Delta_1$  which means  $\Delta_1 > \Delta_2$  indicating the  $^2E_g$  level lies below the  $^2B_{2g}$  level, and the order of the energy levels is

$$^2B_{1g}(d_{x^2-y^2}) < ^2A_{1g}(d_{z^2}) < ^2E_g(d_{xz}, d_{yz}) < ^2B_{2g}(d_{xy})$$

When  $R = m\text{-MeO}$ ,  $m\text{-NO}_2$ , [(b) and (c) in Fig. 2], the esr spectra exhibit three g values which fact indicates that the symmetry of these two complexes is lower than  $D_{4h}$  and their molecules would show a rhombic distortion due to the difference in Cu-O and Cu-N bond lengths. It is interesting to note that, although  $m\text{-MeO}$  group has lower electron attracting ability than  $m\text{-Cl}$  group<sup>6</sup>, the esr spectra showed that the latter complex still has the same configuration as the unsubstituted Cu(II)-N-phenylglycine complex, which indicates that in addition to the effect of electron density change on the nitrogen atom of the ligand there must be some steric effect to elongate the Cu-N bond. It may also arise from different geometrical arrangement of the ligands in the complexes<sup>7</sup>.

A comparison of the  $\xi/\Delta$  values shows that the energy level sequences of these two complexes are as follows:

For Cu(II)- $m\text{-MeO}_2\text{PG}$  complex:

$$d_{x^2-y^2} < d_{z^2} < d_{xz} < d_{xy} < d_{yz}$$

For Cu(II)- $m\text{-NO}_2\text{PG}$  complex:

$$d_{x^2-y^2} < d_{z^2} < d_{xz} < d_{yz} < d_{xy}$$

The esr spectra of Cu(II)- $o\text{-MePG}$  complex [(d) in Fig. 2] are quite different from the above mentioned types, suggesting low symmetry of the molecule and presence of exchange coupling<sup>8</sup>. According to Graddon<sup>9</sup>, although there was no difficulty in making a four-coordinated model of chelate amino acid structure with *ortho* substituted N-aryl-glycinates, the substituents blocked access to the fifth and sixth coordination positions of the Cu(II) ion and also restricted the free rotation of the aryl group. Therefore, the *ortho* substituted ligand should form from different configuration with Cu(II) ion than the other ligands. However, because of its weak chelating ability the *ortho* substituted ligand can hardly form a square planar configuration but very likely form a flattened tetrahedron with the four atoms (N, N, O, O) sitting out of a plane. This is a model of complex compounds having lower symmetry than the rest of the above mentioned complexes.

The esr spectra of the Cu(II)- $p\text{-NO}_2\text{PG}$  complex [(e) in Fig. 2] is analogous to that of Cu(II)- $o\text{-MePG}$  but with broader shoulder. Its line intensity was too weak to compare with the others and it became necessary to use larger quantity of sample to run the spectra. This means that the density of unpaired electron is very small. It may be ascribed to the strong electron attracting power of the  $p\text{-nitro}$  group

that greatly reduces the electron density on the aromatic nitrogen atom of the amino acid and thus decreases its coordinating ability with Cu(II) ion. The complex can hardly be consistent with chelation of the amino acid type but most probably having a structure of the alkanoate type (II in Fig. 3) with




Fig. 3.

the aromatic nitrogen atom being non-donor. In this structure the distance between two copper atoms is short and exchange interaction exists so that a  $\delta$ -bond can form by lateral overlap of the  $3d_{x^2-y^2}$  orbitals of the adjacent copper atoms in the dimerized molecule.

An essential feature for interpreting the esr spectra of Cu(II)-amino acid complexes is the magnitude of parameter  $\Delta g_1$  ( $\Delta g_1 = g_1 - g_e$ ). From equations (2), (3) and (4) it is seen that the reduction in  $\Delta g_1$  values may be due to an increase in  $\Delta$  or a decrease in  $\xi$  or a combination of both. An increase in  $\Delta$  and (or) a decrease in  $\xi$  will lead to decrease in  $\Delta g_1$ ,  $\Delta g_2$  and  $\Delta g_{av}$ , which means an increase in covalency of the coordination bonding so as to increase the extent of delocalization of electrons from metal to ligand. On the other hand, a decrease in  $\Delta$  and (or) an increase in  $\xi$  will lead to increase in  $\Delta g_1$ ,  $\Delta g_2$  and  $\Delta g_{av}$ , which means increase in ionic character of the coordination bonding. Therefore, a plot of  $\Delta g_1$  against  $\Delta g_{av}$  may reflect the extent of covalency in the Cu(II) complexes formed with different N-aryl-glycines. Fig. 4




Fig. 4

1 Glycine, 2 PG, 3  $p\text{-MeOPG}$ , 4  $p\text{-MePG}$ , 5  $m\text{-MePG}$ , 6  $p\text{-ClPG}$ , 7  $m\text{-ClPG}$ .

shows such a plot, which indicates that an introduction of electron attracting group into the phenyl radical leads to increase ionic character of the metal-ligand bond. A comparison of Cu(glycine)<sub>2</sub><sup>10</sup> with



Cu(N-aryl-glycine)<sub>2</sub> shows that the former complex has higher covalency than the latter.

#### Acknowledgement

L. Tian, Y. X. Liu, B. Sen and Q. Wang have contributed partly to this work.

#### References

1. I. BERTINI, D. GATTESCHI and A. SCOZZARAVA, *Coord. Chem. Revs.*, 1979, **29**, 67
2. Y. T. CHEN and Y. Q. XIANYU, *Acta Chimica Sinica*, 1979, **37**, 157.
3. Y. T. CHEN and H. K. LIN, *Acta Chimica Sinica*, 1983, **41**, 87.
4. L. P. WALLS, *Brit. Pat.*, 1, 153, 883, May 29, 1969.
5. J. S. GRIFFITH, "The Theory of Transition-Metal Ions", Cambridge University Press, 1961, p. 281.
6. D. H. McDANIEL and H. C. BROWN, *J. Org. Chem.*, 1958, **23**, 420.
7. S. MISUMI, T. ISOBI and S. KIMOTO, *Bull. Chem. Soc. Japan*, 1972, **45**, 2695.
8. B. J. HATHAWAY and D. E. BILLING, *Coord. Chem. Revs.*, 1970, **5**, 143.
9. D. P. GRADDON, *J. Inorg. Nuclear Chem.*, 1961, **22**, 85.
10. B. N. MISRA, S. D. SHARMA and S. K. GUPTA, *J. Magn. Reson.*, 1974, **16**, 193.

# Infrared Spectra of Iron(II) Complexes with N,N-Dimethylformamide and N,N-Dimethylthioformamide\*

W. LINERT and V. GUTMANN

Institute for Inorganic Chemistry, The Technical University Vienna, Getreidemarkt 9, A-1060 Wien, Austria

Infrared spectra and assignment for the vibration frequencies are given for  $\text{Fe}(\text{DMF})_6\text{Cl}_2$ ,  $\text{Fe}(\text{DMF})_6\text{Br}_2$ ,  $\text{Fe}(\text{DMF})_6(\text{ClO}_4)_2$ ,  $\text{Fe}(\text{DMTF})_6\text{Cl}_2$ ,  $\text{Fe}(\text{DMTF})_6\text{Br}_2$ ,  $\text{Fe}(\text{DMTF})_6\text{I}_2$ ,  $\text{Fe}(\text{DMTF})_6(\text{ClO}_4)_2$  and compared with the spectra of the free DMF and DMTF. The results are found to be in agreement with the bond length variation rules.

**A**MIDES are coordinated to Lewis acids through the "hard" oxygen atoms of the C=O group whereas thioamides coordinate through the "soft" sulfur atoms of the C-S group. In order to compare the changes in bond lengths involved in coordination by both types of ligands the IR spectra of the following adducts of N,N-dimethylformamide (DMF) and N,N-dimethylthioformamide (DMTF) have been studied:  $\text{Fe}(\text{DMF})_6\text{Cl}_2$ ,  $\text{Fe}(\text{DMF})_6\text{Br}_2$ ,  $\text{Fe}(\text{DMF})_6(\text{ClO}_4)_2$ ,  $\text{Fe}(\text{DMTF})_6\text{Cl}_2$ ,  $\text{Fe}(\text{DMTF})_6\text{Br}_2$ ,  $\text{Fe}(\text{DMTF})_6\text{I}_2$  and  $\text{Fe}(\text{DMTF})_6(\text{ClO}_4)_2$ . In the  $\text{ClO}_4^-$  complexes the metal ions are in octahedral coordination by DMF and DMTF molecules, respectively and the anions are in outer sphere positions. On the other hand, in tetrahedral halide complexes the halide ligands are coordinated in the inner sphere of the central iron(II) ion<sup>1,2</sup>.

## Experimental

The preparation of the complexes has been described previously<sup>1</sup>. The infrared spectra were obtained on a Perkin-Elmer 180 IR spectrometer. KBr pellets were used to measure the infrared spectra in the range from 4000 to 300  $\text{cm}^{-1}$ , whereas Nujol mulls were used to obtain the spectra from 525 to 32  $\text{cm}^{-1}$ . The preparation of the pellets and the nujol mulls were performed with freshly prepared complexes in a dry box filled with dry nitrogen gas<sup>1</sup>. The infrared spectra were also recorded under dry nitrogen atmosphere to prevent slow decomposition of the substances in contact with air-oxygen and air-water<sup>1,3</sup>.

## Results and Discussion

IR spectra and assignments for DMF and DMTF as given by Durgaprasad<sup>4</sup> and other

TABLE I.—INFRARED ABSORPTION BANDS ( $\text{cm}^{-1}$ ) OF DMF AND THE IRON(II)-DMF COMPLEXES WITH THE ASSIGNMENT OF THE SIGNIFICANT VIBRATIONS

DMF (Lit. <sup>4</sup> )	DMF	$\text{Fe}(\text{DMF})_6(\text{ClO}_4)_2$	$\text{Fe}(\text{DMF})_6\text{Cl}_2$	$\text{Fe}(\text{DMF})_6\text{Br}_2$	Vibration.*
		645 s			$\text{ClO}_4^-$
660 s	655 s	685 s	680 s	685 s	$\nu(\text{O} \cdots \text{N})$
870 m	865 m	855 m	851 s	865 s	$\nu_\sigma(\text{C} \cdots \text{N})$
		860 m			$\text{ClO}_4^-$
	940 m				$\text{ClO}_4^-$
1067 m	1067 m		1053 m	1060 m	$\nu(\text{CH}_3)$
1099 vs	1090 s		1110 s	1113 s	$\nu(\text{CH}_3)$
	1150 **	1145 v			$\text{ClO}_4^-$
		1160 s			$\nu(\text{CH}_3)-$
		1170 s			$\nu(\text{CH}_3)-$
1268[s	1255 s	1250 m	1245 m	1250 m	$\nu_\sigma(\text{C} \cdots \text{N})$
1395 vs	1385 s	1370 s	1372 s	1380 s	$\delta_\sigma(\text{CH}_3), \nu(\text{CN})$
1410 s	1405 m	1415 m	1415 m	1405 v	$\delta(\text{CH})$
1410 **				1180 s	$\delta_\sigma(\text{CH}_3)$
1450 m	1440 s	1455 v	1430 s	1435 m	$\delta_\sigma(\text{CH}_3)$
1512 m	1500 m	1490 m	1492 m	1500 m	$\delta_\sigma(\text{CH}_3), \delta_\sigma(\text{CH}_3), \nu(\text{CN})$
1685 s	1675 s	1640 s	1640 s	1650 s	$\nu(\text{CO}), \nu(\text{CN})$
		1650s	1650 s		
		1655 s	1655s		

vs, s, m, w means very strong, strong, medium, weak, respectively.

\*  $\nu$ ,  $\delta$ ,  $\nu$ ,  $\sigma$  and  $\sigma$  mean stretching, bending, rocking, asymmetric, and symmetric, respectively.

\*\* not resolved.

\* Dedicated to Professor A. K. Dey on the occasion of his 60th birthday.

TABLE 2—INFRARED ABSORPTION BANDS (cm<sup>-1</sup>) OF DMTF AND THE IRON(II)-DMTF COMPLEXES WITH THE ASSIGNMENT OF THE SIGNIFICANT VIBRATIONS

DMTF(lit. <sup>1</sup> )	DMTF	Fe(DMTF) <sub>2</sub> (ClO <sub>4</sub> ) <sub>2</sub>	Fe(DMTF) <sub>2</sub> Cl <sub>2</sub>	Fe(DMTF) <sub>2</sub> Br <sub>2</sub>	Fe(DMTF) <sub>2</sub> I <sub>2</sub>	Vibration*
		625 s				ClO <sub>4</sub> <sup>-</sup>
		635 s				ClO <sub>4</sub> <sup>-</sup>
		680 w	680 w		680 w	
828 <sup>1</sup> s	820 m	820 m	825 m	825 m	815 w	$\nu_{\text{as}}(\text{C}'\text{N})$
		850 m				ClO <sub>4</sub> <sup>-</sup>
970 s	970 s	968 m	948 s	935 s	940 m	$\nu(\text{CS})$
1058 s	1050 s	1057 m	1050 w	1059 m	1059 m	$\tau(\text{CH}_2)$
		1110 s	1113 m		1110 m	$\tau(\text{CH}_2)$
1140 s	1128 s	1175 m	1136 s	1135 s		$\tau(\text{CH}_2)$
	1205 s	1200 m	1197 w	1195 w		$\nu_{\text{as}}(\text{C}'\text{N})$
		1250 w	1246 w	1240 w		
					1240 s	
					1353	
1405 m	1400 s	1405 s	1374 s	1378 m	1370 m	$\delta(\text{CH})$
1410 sh	1410 **		1406 <sup>1</sup> s	1408 m		$\delta_{\text{as}}(\text{CH}_2)$
1420 vs	1420 **	1440 m	1415 <sup>1</sup> s		1420 s	$\delta_{\text{as}}(\text{CH}_2)$
1450 s	1460 s	1460 m	1432 m	1432 m	1420 m	$\delta_{\text{as}}(\text{CH}_2)$
1472 s	1472 **		1462 m	1462 m		$\delta_{\text{as}}(\text{CH}_2)$
1560 s	1545 s	1570 s	1492 m			$\delta_{\text{as}}(\text{CH}_2)$
			1568 s	1570 s	1553 m	$\nu(\text{CN})$

\*, \*\* see table 1

 TABLE 3—INFRARED ABSORPTION BANDS IN THE REGION FROM 525 TO 32 cm<sup>-1</sup>

Compound	Absorption frequency cm <sup>-1</sup>									
DMF	403			353	318	255				
Fe(DMF) <sub>2</sub> (ClO <sub>4</sub> ) <sub>2</sub>	415	397 <sup>1</sup>	384			239	220			142
Fe(DMF) <sub>2</sub> Cl <sub>2</sub>	414		380	353	315	290	216			142
Fe(DMF) <sub>2</sub> Br <sub>2</sub>	413		386	360	320	280	220	190	163	143 104
DMTF	519	403			274	215				
Fe(DMTF) <sub>2</sub> (ClO <sub>4</sub> ) <sub>2</sub>	516	407	393		308		174	140	130	100
Fe(DMTF) <sub>2</sub> Cl <sub>2</sub>	505	403	343	325	295	215	190		136	117
Fe(DMTF) <sub>2</sub> Br <sub>2</sub>	512	405		328	270	214				90
Fe(DMTF) <sub>2</sub> I <sub>2</sub>	515	405	390	330	266			146		

authors<sup>4-6</sup> were confirmed. The data for the iron(II) complexes are given in Tables 1 and 2. The first bond length variation rule predicts<sup>9</sup> a lengthening of the bonds directly adjacent to the donor-acceptor interaction. In the complexes under study, these are the O=C and S=C bond in DMF and DMTF, respectively. The absorption line for DMTF at 970 cm<sup>-1</sup>, assigned as S-C stretching vibration, is strongly lowered in the tetrahydryl halide complexes and to a lesser extent in the octahydral perchlorate complex. The lowering of the O-C stretching frequencies of DMF at 1675 cm<sup>-1</sup> is well pronounced both in the halide and the perchlorate complexes.

The comparison of the results obtained for the perchlorate complexes reveals that changes in the C=S bond lengths are smaller than in the C=O bond lengths, although the Fe-S bond appears stronger than the Fe-O bond. As back donation seems involved in the Fe-S bond, the S-C bond should be lengthened to a lesser extent than the C-O bond. This also means that differences in the outer sphere interactions with the ClO<sub>4</sub><sup>-</sup> groups should exist. The changes in charge redistribution due to complex formation seem more strongly spread over the whole system in the DMTF complexes.

The second bond length variation rule<sup>9</sup> predicts a shortening of the C-N bond and a lengthening of the N-C' bonds. In DMTF, the N-C' stretching vibration at 1545 cm<sup>-1</sup> is seen to be increased and hence the C-N bond shortened. In DMF, the N-C' stretching vibrations are highly coupled so that the shifts due to complex formation could not be detected. Both, the symmetric as well as the asymmetric N-C' stretching frequencies are found to be lowered by complex formation with DMF and DMTF complexes, respectively.

In agreement with the second rule a shortening of the C-H bond length was found, as can be seen from the comparison of the C-H stretching frequencies at 1405 cm<sup>-1</sup> in DMF and at 1400 cm<sup>-1</sup> in DMTF and the corresponding absorption lines of the complexes.

The bond length variation concept leads to the suggestion of a terminating group effect: changes in charge distribution due to a donor-acceptor interaction should be smaller with increasing distance from the site of the interaction but again more developed at the end groups of the complex<sup>9</sup>. The frequencies of the rocking vibrations at the (CH<sub>2</sub>) groups in DMF and DMTF show indeed stronger changes than the frequencies of the C-H deformation frequencies.

The frequencies of the far-infrared absorption lines in the region of 525 to 32  $\text{cm}^{-1}$  are presented in Table 3.

The Fe-halide stretching frequencies lie at 325, 315 and 270  $\text{cm}^{-1}$  for  $\text{Fe}(\text{DMTF})_2\text{Cl}_2$ ,  $\text{Fe}(\text{DMF})_2\text{Cl}_2$  and the two bromide compounds, respectively. It can be seen, that the coordination of the Fe-central ion to the soft S-atom in DMTF leads to a weaker Fe-Cl bond than the coordination to the hard O-atom in DMF. Comparison of the ratio of the Fe-Br and the Fe-Cl frequencies with the square root of the atomic masses of Cl and Br show that the Fe-Br bond is by a factor of about 1.5 stronger than the Fe-Cl bond. Any differences between  $\text{Fe}(\text{DMTF})_2\text{Br}_2$  and  $\text{Fe}(\text{DMF})_2\text{Br}_2$  could not be resolved at the said line at 270  $\text{cm}^{-1}$ . The Fe-I stretching vibrations should be found at frequencies between 212 and 207  $\text{cm}^{-1}$ . Because of the very weak Fe-I bond in these complexes (decomposition of Fe-I complexes takes place readily<sup>8</sup>) the line at 146  $\text{cm}^{-1}$  should be assigned to this vibration. The Fe-S stretching vibrations are found between 343 and 393  $\text{cm}^{-1}$ , whereby the highest values are found for the perchlorate- and the iodo-complex. In DMTF, these vibrations vary to a greater extent than the corresponding Fe-O vibrations found between 384 and 386  $\text{cm}^{-1}$ <sup>10-12</sup>. The absorption lines at 220, 216 and 220  $\text{cm}^{-1}$  are assigned to the O-Fe-O deformation frequencies of  $\text{Fe}(\text{DMF})_6(\text{ClO}_4)_2$ ,  $\text{Fe}(\text{DMF})_2\text{Cl}_2$  and  $\text{Fe}(\text{DMF})_2\text{Br}_2$ <sup>12</sup>.

The lowering of the line at 519  $\text{cm}^{-1}$  at the DMTF complexes has been assigned to the lowering of the C-S stretching vibration (see Table 2) and not by the S-C deformation vibration which is

involved in this complex coupled vibration. This may be deduced because the line at 215  $\text{cm}^{-1}$  which is considered as the S-C-N deformation vibration is not significantly shifted. The line at 403  $\text{cm}^{-1}$  in both DMF and DMTF is assigned to the C'-N-C' deformation frequency.

#### Acknowledgement

Thanks of the authors are due to the Fonds zur Forderung der wissenschaftlichen Forschung in Österreich for financial support (Project 3004).

#### References

1. G. GRITZNER, W. LINERT and V. GUTMANN, *J. Inorg. Nuclear Chem.*, 1981, 43, 1193.
2. W. LINERT, G. WIESINGER, O. BAUMGARTNER and V. GUTMANN, to be published.
3. G. DURGAPRASAD, D. N. SATHANARAYANA and C. C. PATEL, *Bull. Chem. Soc. Japan*, 1971, 44, 316.
4. T. MIYAZAWA, T. SHIMANOUCHI and S. MIYASHIMA, *J. Chem. Phys.*, 1956, 24, 408.
5. J. E. KATON, W. R. FAIRHELLER and J. V. PUSTINGFR, *J. Anal. Chem.*, 1964, 36, 2126.
6. E. W. RANDALL, C. M. S. YODER and J. J. ZUCKERMAN, *Inorg. Chem.*, 1966, 5, 2240.
7. G. KAUFMANN and M. J. F. LEROY, *Bull. Soc. Chim. France*, 1967, 402.
8. V. V. CHALAPATHI and K. V. RAMAIAH, *Proc. Indian Acad. Sci.*, 1968, 68A, 109.
9. V. GUTMANN, "The Donor-Acceptor Approach to Molecular Interactions", Plenum Press, New York, 1978.
10. Y. MEADE, Y. SASAKE and Y. TAKASHIMA, *Inorg. Chim. Acta*, 1975, 13, 141.
11. C. PERTI and G. TOSI, *Z. anorg. Chem.*, 1975, 418, 188.
12. A. YU. TSIVADZE, L. VOLPONI, B. ZARLI, G. V. TSINT-SADZE, A. N. SMIRNOV and N. N. TERAZODZO, *Russ. J. Inorg. Chem.*, 1975, 20, 406.
13. C. PERTI and G. TOSI, *Canad. J. Chem.*, 1975, 53, 177.

# Synthesis and Characterisation of $\mu$ -Oxobis[oxotetrachlororhenates (VI)]

V. YATIRAJAM\* and (Miss) M. LAKSHMI KANTAM

Department of Chemistry, Kurukshetra University, Kurukshetra-132 119

(Ph<sub>4</sub>As)<sub>2</sub>Re<sub>2</sub>O<sub>2</sub>Cl<sub>8</sub> and (Tz)<sub>2</sub>Re<sub>2</sub>O<sub>2</sub>Cl<sub>8</sub> have been prepared by the reduction of perrhenate with acetyl chloride and characterised on the basis of chemical analysis, spectral, magnetic moment and conductivity studies

VERY few oxo-bridged complexes of Re(IV), Re(V) and Re(VI) are known. Rhenium(IV) forms  $K_4[Re_2OCl_{10}]$  in the reduction of potassium perrhenate by iodide in hydrochloric acid solution<sup>1</sup>. For Re(VI) and Re(V), only  $\mu$ -oxodioxo-complexes are known.  $Re_2O_2Cl_4(py)_4$  and  $Re_2O_2Cl_4(bipy)_4$  are prepared by reacting  $ReCl_5$  with the ligand in wet acetone<sup>2</sup> or by reacting  $ReOCl_3$  or  $ReOCl_3(Ph_3P)_2$  with the ligand in benzene<sup>3</sup>.  $Re_2O_2(R_2dtc)_4$  complexes are obtained by reacting  $ReOCl_3(Ph_3P)_2$  or  $Re_2O_2Cl_4(py)_4$  with the dithiocarbamate ligand<sup>4</sup>.  $Re_2O_2Cl_4(en)_4$  is obtained by standing  $ReO(OH)(en)_3$  in hydrochloric acid<sup>5</sup>. The  $Re_2O_2Cl_4(en)_4^{2-}$  anion is precipitated by partial hydrolysis on exposing chloroform solution of  $ReOCl_3$  and  $Ph_4As^+$  or  $Et_4N^+$  chloride to atmosphere<sup>6</sup>.  $Re_2O_2Cl_4(ReO_2Cl)_2$  is obtained<sup>7</sup> by uv irradiation of a mixture of  $ReOCl_3$ ,  $ReOCl_4 \cdot (H_2O)$  and  $ReO_2Cl$ .

We report here the synthesis of  $(Ph_4As)_2Re_2O_2Cl_8$  and  $(Tz)_2Re_2O_2Cl_8$  compounds in good yield from potassium perrhenate.

## Experimental

**Materials:**  $KReO_4$  (J.M.) was dried at 120°.  $Ph_4AsCl$  (Fluka) and 2,3,5-triphenyl tetrazolium chloride (Sisco) were dried over  $P_2O_5$  in vacuo. All the solvents and other chemicals were thoroughly dried by suitable methods. All experiments were carried out in glove box under oxygen-free dry nitrogen. Petroleum ether (60-80°) was used.  $AcOH-HCl$  was prepared by saturating acetic acid with hydrogen chloride gas.

### Preparation of the compounds :

**Tetraphenylarsonium salt :**  $KReO_4$  (0.400 g) was taken in acetyl chloride (10 ml) and kept for 40 hr.  $Ph_4AsCl$  (0.620 g) in  $AcOH-HCl$  (10 ml) was added to the red  $Re(VI)$  solution after filtration. The dark red precipitate formed was immediately filtered, washed with  $AcOH-HCl$  and dried in vacuo over  $NaOH$  for 6 hr.

**Tetrazolium salt :** To the clear red  $Re(VI)$  solution obtained as above were added 2,3,5-triphenyl tetrazolium chloride (0.482 g) in  $AcOH-HCl$  (5 ml) and acetyl chloride (5 ml). Shiny brown precipitate

was obtained, filtered, washed with  $AcOH-HCl$  and dried as above

The yield is 85% in both the cases.

**Elemental analyses and physical measurements :** After alkaline peroxide fusion of the sample, rhenium was determined as tetraphenylarsonium perrhenate<sup>8</sup> and chloride as silver chloride<sup>9</sup>. The uv-vis spectra of solution were taken on a Beckman DU-2 spectrophotometer using 1 cm silica cell. Infrared spectra were recorded with Beckman IR-20. Magnetic susceptibilities were determined by the Gouy method, packing the tubes under dry nitrogen in glove box. Molar conductances were measured with a Philips bridge PR950J/90 using a dip type microcell having a cell constant of  $0.14 \text{ cm}^{-1}$ .

## Results and Discussion

The red and brown compounds are soluble in dichloromethane, acetone, nitromethane, acetonitrile but insoluble in benzene and carbon tetrachloride. The present method enables preparation of  $Ph_4As^+$  and tetrazolium salts of  $Re_2O_2Cl_4^{2-}$  ion in a very pure form. Their molar conductances,  $150-180 \text{ ohm}^{-1}\text{cm}^2\text{mole}^{-1}$  in nitromethane, support their formulations as 2 : 1 electrolytes<sup>10</sup>. Their chemical analyses and other physical data are presented in Table 1.

The electronic spectra of the compounds in dichloromethane show the same peaks of  $Re(VI)$  as  $Re^{VI}OCl_3$  and also confirm the hexavalent state of rhenium. The  $\epsilon$ 's of the peaks are similar but less than those<sup>6</sup> of  $Ph_4AsReOCl_3$ .

The ir spectrum of the tetrazolium salt is reproduced in Fig. 1 ; that of the  $Ph_4As^+$  salt shows the same features. The  $\nu(Re=O)$  bands are listed in Table 1. Rest of the bands in the region  $4000-400 \text{ cm}^{-1}$  are due to the cation. The compounds show three main bands at  $\sim 970$ ,  $\sim 950$  and  $\sim 910 \text{ cm}^{-1}$ . In case of the arsonium salt, the two higher energy bands are split probably due to site symmetry. The above data suggest two possible structures I and II for the  $[Re_2O_2Cl_4]^{2-}$  ion with *cis* and *trans* terminal oxygens respectively to the oxo-bridge between the two rhenium atoms. A

TABLE 1—ANALYTICAL AND PHYSICAL DATA OF  $\mu$ -OXO BIS (OXOTETRACHLORORHENATE(VI))

Compound and colour	% Re	% Cl	$\lambda_{max}^a$ nm ( $\epsilon$ )		$\nu(\text{Re}=\text{O})^d$ ( $\text{cm}^{-1}$ )		$\nu(\text{Re}-\text{O}-\text{Re})^d$ ( $\text{cm}^{-1}$ )	$\Delta_{\text{O}}^d$	$\mu_{eff}^d$ (B.M.)	
(Ph <sub>4</sub> As) <sub>2</sub> Re <sub>2</sub> O <sub>2</sub> Cl <sub>6</sub> Dark red	24.87 (25.30) <sup>a</sup>	18.47 (19.31)	300 (1971)	440 (908)	550 (160)	900 (18)	935 m, 945 m 968 w, 955 w	905 s	190	1.46
(Tz) <sub>2</sub> Re <sub>2</sub> O <sub>2</sub> Cl <sub>6</sub> Brown	28.15 (28.59)	21.20 (21.82)	300	440	550 (117)	880 (6)	950 m, 975 m	915 s	176	1.48


a—values in parentheses are Calcd. values.

b—in dichloromethane.


c—in nujol.

d—molar conductance,  $\text{ohm}^{-1}\text{cm}^2\text{mole}^{-1}$ .

e—at R. T.

Fig 1. IR spectra (a) (TZ)Cl, (b) (TZ)<sub>2</sub>[Re<sub>2</sub>O<sub>2</sub>Cl<sub>6</sub>] in nujol

linear bridge is assumed as it would permit better Re-O  $\pi$ -bonding than the bent one



Structure

Structure II was assigned to the mauve products obtained by Brisdon and Edwards<sup>6</sup> on the basis of a doublet at  $970\text{ cm}^{-1}$  suggesting a bond with terminal oxygen and a band at  $730\text{ cm}^{-1}$  suggesting Re-O-Re, the lower value for the frequency indicating terminal oxygens in *trans* positions. This is supported by the weak paramagnetism of the compounds.

The antisymmetric Re-O-Re frequency for structure I is expected in the general range of frequencies, i.e.,  $800\text{--}950\text{ cm}^{-1}$ , found for oxygen-bridged halocomplexes<sup>6</sup>. Also, the reduced symmetry

of the unit of the dimer might lead to splitting of degenerate frequencies and appearance of forbidden frequencies. So the bands at  $\sim 970\text{ cm}^{-1}$  and at  $\sim 950\text{ cm}^{-1}$  of the red to brown dimers can be assigned to the bond with terminal oxygen and the strong and somewhat broader band at  $\sim 910\text{ cm}^{-1}$  to Re-O-Re bonding having terminal oxygens in *cis* positions. It is, therefore, reasonable to suggest that these dimers have structure I. They show slightly reduced paramagnetism compared to  $\text{Re}^{\text{VI}}\text{OCl}_5^-$  ion<sup>6,11</sup>, due possibly to the exchange interactions. The antiferromagnetic coupling is weaker than that found for the *trans*-isomer by Brisdon and Edwards<sup>6</sup>. The presence of oxygens in *cis* positions to the bridge seems to weaken the antiferromagnetic coupling.

#### Acknowledgement

The authors wish to thank the U.G.C. for a Senior Research Fellowship to one of them (M.L.K.).

References

1. J. C. BAILAR, Jr., H. J. EMELEUS, R. NYHOLM and A. F. TROTMAN-DICKENSON, "Comprehensive Inorganic Chemistry", Pergamon Press, New York, 1973, Vol 3, p. 976
2. N. P. JOHNSON, F. TAHA and G. WILKINSON, *J. Chem. Soc.*, 1964, 2614
3. A. GUEST and C. J. L. LOCK, *Can. J. Chem.*, 1971, 49, 603.
4. J. F. ROWBOTTOM and G. WILKINSON, *J. Chem. Soc., Dalton Trans.*, 1972, 826.
5. D. E. GROVE and G. WILKINSON, *J. Chem. Soc. A*, 1966, 1224
6. B. J. BRIDSON and D. A. EDWARDS, *Inorg. Chem.*, 1968, 7, 1898.
7. C. CAIVO, P. W. FRAIS and C. J. L. LOCK, *Can. J. Chem.*, 1972, 50, 3607
8. H. H. WILLARD and G. M. SMITH, *Ind. Eng. Chem. Anal. Ed.*, 1939, 11, 305
9. A. I. VOGEL, "A Text-book of Quantitative Inorganic Analysis", Longman, New York, 1975, pp 461, 568
10. W. J. GEARY, *Coord. Chem. Rev.*, 1971, 7, 81.
11. V. YATIRAJAN and HARJINDER SINGH, *J. Inorg. Nuclear Chem.*, 1976, 37, 2006.

# Synthesis of *p*-Phenylene-di-Acrylyl-*Bis*-N-Phenyl (PAPHA), Fumaryl-*Bis*-N-Phenyl (FPHA), Isophthalyl-*Bis*-N-Phenyl (IPHA) Hydroxamic Acids and Spectral and Magnetic Studies of their Polymers with Mn(II), Fe(II), Co(II), Ni(II), Cu(II) and Zn(II)

(MISS) N. R. GANDHI and K. N. MUNSHI

Department of Chemistry, Nagpur University, Nagpur-440 010

Three new *bis*-ligands, PAPHA, FPFA and IPHA have been synthesized and their polymers with Mn(II), Fe(II), Co(II), Ni(II), Cu(II) and Zn(II) have been prepared. The compositions of the polymers have been proposed on the basis of elemental analysis, and their infrared and electronic spectra and magnetic susceptibilities have been reported. On the basis of these observations, their structures have been discussed.

**E**XCEPT for a cryptic mention of *bis*-hydroxamic acid-metal polymers<sup>1</sup>, no other data appear to have been reported. A systematic study was therefore planned to undertake the synthesis of some *bis*-hydroxamic acids with the intention of studying their coordination polymers.

## Experimental

The chemicals used were of AnalaR or chemically pure grade.

### Preparation of the ligands

In present investigations a modified method by Priyadarshini and Tandon<sup>2</sup> was used for the preparation of hydroxamic acids. In this procedure, freshly prepared N-hydroxylamine and vacuum distilled acid chloride in stoichiometric proportions are reacted at low temperature (0° or lower) in diethylether medium containing aqueous suspension of sodium bicarbonate.

**Preparation of acid dichlorides** Dry acid (0.1 m) (*p*-phenylene-di-acrylic, fumaric- or isophthalic-) and phosphorus pentachloride (0.2 m) were taken in a dry 250 ml round bottomed flask fitted with an air condenser provided with a guard tube filled with anhydrous CaCl<sub>2</sub>. The mixture was heated on a water bath till a yellow pulverised mass in case of *p*-phenylene-di-acrylic acid (12 hr) and a clear liquid in case of fumaric (4 hr) or isophthalic (2 hr) acid was obtained. Phosphorus oxychloride was distilled off under reduced pressure and the acid chlorides extracted in ether. *p*-Phenylene-di-acrylyl chloride was a yellow solid, fumaryl chloride a liquid and isophthalyl chloride a colourless crystalline solid.

**Preparation of N-phenylhydroxylamine**: N-Phenylhydroxylamine was prepared by controlled reduction of nitrobenzene<sup>3</sup>.

**Synthesis of PAPHA, FPFA and IPHA**: Freshly prepared, crystallized, N-phenylhydroxylamine (0.25

m), diethylether (100 ml), sodium bicarbonate (0.3 m) and distilled water (30 ml) were taken in a 500 ml beaker and the mixture was cooled to 0° or below. To the above mixture, a solution of acid dichloride (0.1 m) in diethylether (150 ml) was added dropwise with constant stirring over about 1 hr. The product separated was filtered and washed thoroughly with saturated solution of NaHCO<sub>3</sub> to remove any acidic impurities.

These hydroxamic acids were crystallized from DMF-ethanol mixture. PAPHA and FPFA were yellow in colour (m.p.s. 225° and 194°, respectively), whereas IPHA was white (m.p. 180°). These hydroxamic acids have been reported for the first time in the present work and hence have been characterized on the basis of their elemental analysis and ir spectra. The results are given in Table 1 and Tables 5 to 7, respectively.

TABLE 1—ANALYTICAL DATA OF THE LIGANDS

Sl. No	Ligand	Analysis %		
		C Found (Calcd)	H Found (Calcd)	N Found (Calcd)
1.	PAPHA	71.4 (72.0)	5.11 (5.00)	6.84 (7.00)
2	FPFA	64.7 (64.4)	5.07 (4.69)	8.89 (9.39)
3.	IPHA	68.9 (68.9)	4.64 (4.59)	7.58 (8.04)

### Synthesis of coordination polymers:

**Polymers of PAPHA and FPFA with Mn(II), Co(II), Ni(II), Cu(II) and Zn(II)**: Metal solution prepared by dissolving metal acetate (0.01 m) in DMF (25 ml) was added to a solution of *bis*-hydroxamic acid prepared by dissolving the ligand (0.01 m) on DMF (25 ml). The reaction mixture was heated on a water bath with constant stirring till the polymer separated as an insoluble solid. It was



then digested on a water bath for about 2 hr. cooled to room temperature, filtered, washed thoroughly with DMF and ethanol and dried.

**Polymers of IPHA with Mn(II), Fe(II), Co(II), Ni(II), Cu(II) and Zn(II):** Zn(II) polymer was prepared by a method similar to the one described above. Other metals however failed to yield insoluble products with this ligand in DMF. These polymers were prepared by the following procedure.

**Metal solution,** prepared by dissolving metal acetate (0.01 m) [metal acetylacetonate in case of Fe(II)] in DMF (25 ml) was added to a solution of *bis*-hydroxamic acid prepared by dissolving the ligand (0.01 m) in dioxane (25 ml). The remaining procedure was the same as above.

**Polymers of PAPHA and FPFA with Fe(II):** Ligand (0.01 m), metal acetylacetonate (0.01 m), ethanol (25 ml) and DMF (25 ml) were taken in a 250 ml beaker. The remaining procedure was the same as above.

**Physical measurements:** Magnetic susceptibility measurements were made on the solid polymers at room temperature with Gouys balance, using mercury tetrathiocyanatocobalt(II) as standard. Diamagnetic corrections were calculated by the method given in literature<sup>4</sup>. Visible and ultraviolet spectra were recorded in 300-1000 nm range with Karl Zeiss USU-2-p spectrophotometer. Infrared

spectra of the ligands and the polymers were recorded on Specord-75 IR spectrophotometer in 400 to 4000  $\text{cm}^{-1}$  region using nujol mull technique.

## Results and Discussion

Tentative compositions for the polymers are proposed on the basis of elemental analysis. The proposed compositions, analytical data and colours of the polymers are reported in Tables 2 to 4. All polymers are insoluble in a wide variety of solvents and hence the products were purified by repeated washings with the solvents to remove all the unreacted metal ions and the ligand.

**Infrared spectra:** IR spectra of the polymers are practically identical. The frequency of some significant bands of the free ligand and of the metal-polymers are reported in Tables 5 to 7.

The free O-H stretching frequency appears at 3095  $\text{cm}^{-1}$  in PAPHA, 3100  $\text{cm}^{-1}$  in FPFA and at 3180  $\text{cm}^{-1}$  in IPHA. Sharp band at 1595  $\text{cm}^{-1}$  in PAPHA is assigned to C=O stretching vibration. Three consecutive bands at 1625, 1600 and 1570  $\text{cm}^{-1}$  in FPFA and two bands at 1590 and 1610  $\text{cm}^{-1}$  in IPHA are due to various resonating structures of R-N-OH. The N-O stretching vibration



TABLE 2—ANALYTICAL DATA AND COLOURS OF METAL-PAPHA(L) POLYMERS

Sl. No	Proposed composition of the polymer	Analysis %				Colour
		C Found (Calcd.)	H Found (Calcd.)	N Found (Calcd.)	M Found (Calcd.)	
1	$\text{Mn}_2\text{L}_2(\text{OH})_2(\text{H}_2\text{O})_2$	59.00 (59.48)	4.48 (4.03)	5.06 (5.78)	14.13 (14.18)	Dark brown
2	$(\text{FeL} \cdot 2\text{H}_2\text{O})_n$	62.50 (58.79)	5.27 (4.49)	4.96 (5.72)	10.80 (11.40)	Red
3	$(\text{CoL})_n$	59.00 (63.03)	3.78 (3.94)	5.21 (6.13)	12.60 (12.89)	Dark brown
4	$\text{Ni}_2\text{L}_2(\text{OH})_2(\text{H}_2\text{O})_2$	50.05 (49.19)	4.65 (4.10)	4.52 (4.78)	20.05 (20.06)	Greenish brown
5	$(\text{CuL})_n$	63.00 (62.40)	4.40 (3.90)	5.38 (6.07)	12.76 (13.77)	Green
6	$(\text{ZnL})_n$	61.10 (62.15)	4.18 (3.88)	5.75 (6.04)	13.23 (14.11)	Yellow

TABLE 3—ANALYTICAL DATA AND COLOURS OF METAL-FPFA (L) POLYMERS

Sl. No.	Proposed composition of the polymer	Analysis %				Colour
		C Found (Calcd.)	H Found (Calcd.)	N Found (Calcd.)	M Found (Calcd.)	
1.	$\text{Mn}_2\text{L}_2(\text{OH})_2(\text{H}_2\text{O})_2$	50.20 (50.24)	4.63 (3.53)	6.76 (7.33)	16.56 (17.97)	Green
2.	$(\text{FeL} \cdot 2\text{H}_2\text{O})_n$	50.35 (49.50)	4.26 (4.12)	6.76 (7.22)	13.87 (14.40)	Red
3.	$(\text{CoL})_n \cdot \text{H}_2\text{O}$	50.25 (51.48)	4.46 (3.75)	7.12 (7.51)	15.97 (15.80)	Brownish yellow
4.	$(\text{NiL} \cdot 2\text{H}_2\text{O})_n \cdot 2\text{H}_2\text{O}$	44.70 (44.99)	4.64 (4.67)	6.70 (6.56)	13.66 (13.76)	Yellow
5.	$(\text{CuL})_n$	52.80 (53.40)	3.84 (3.34)	7.78 (7.79)	17.27 (17.67)	Green
6	$(\text{ZnL})_n$	53.00 (53.13)	4.34 (3.32)	6.55 (7.75)	16.89 (18.09)	Yellow

TABLE 4—ANALYTICAL DATA AND COLOURS OF METAL-IPHA(L) POLYMERS

Sl. No	Proposed composition of the polymer	Analysis %				Colour
		C Found (Calcd)	H Found (Calcd)	N Found (Calcd)	M Found (Calcd)	
1.	$Mn_2L_2(OH)_2(H_2O)_2$	53.40 (54.23)	4.51 (3.61)	5.97 (6.33)	16.61 (16.55)	Greenish black
2.	$(FeL_2H_2O)_n$	54.30 (54.81)	4.61 (4.11)	5.14 (6.39)	12.41 (12.75)	Red
3.	$(CoL_2H_2O)_n$	53.00 (4.43)	5.58 (4.08)	5.64 (6.35)	12.87 (13.36)	Light pink
4.	$(NiL_2H_2O)_n \cdot 2H_2O$	49.90 (50.34)	4.16 (4.61)	5.35 (5.87)	12.06 (12.31)	Light green
5.	$(CuL)_n$	57.40 (58.60)	3.80 (3.42)	6.74 (6.84)	15.29 (15.51)	Green
6.	$Zn_2L_2(OH)_2(H_2O)_2$	49.65 (50.09)	4.14 (3.76)	5.16 (5.84)	20.84 (20.47)	White

TABLE 5—INFRARED SPECTRAL DATA (4000-400  $cm^{-1}$ ) OF PAPHA AND POLYMERS

PAPHA	Mn(II)-polymer	Fe(II)-polymer	Co(II)-polymer	Ni(II)-polymer	Cu(II)-polymer	Zn(II)-polymer	Assignment
—	3200-3600 b	3200-3600 b	—	3200-3500 b	—	—	H—O—H
3095 m 1595 s	1550 bsh	1510 sh 1585 s	1525 } 1545 } m	1540 m	1500 sh	1515 bsh	O—H C=O
970 s	950 s 450 s 555 m 615 m	955 s 480 m 545 s	955 s 510 s	940 w merged	950 s 570 s	950 s 520 m 555 w	N—O M—O

b—broad, s—strong, bsh—broad shoulder; m—medium, sh—shoulder, w—weak

TABLE 6—INFRARED SPECTRAL DATA (4000-400  $cm^{-1}$ ) OF FPFA AND POLYMERS

FPFA	Mn(II)-polymer	Fe(II)-polymer	Co(II)-polymer	Ni(II)-polymer	Cu(II)-polymer	Zn(II)-polymer	Assignment
—	3200-3600 b	3200-3600 b	3200-3600 b	3200-3600 b	—	—	H—O—H
3100 m 1570 } 1600 } s 1625 }	1530 } 1550 } s 1555 }	1510 } 1565 } s 1575 }	1530 s 1545 } 1575 } sh	1525 } 1540 } 1560 } s 1570 }	1535 } 1535 } s 1565 sh	1525 s 1560 m	O—H C=O
965 s	960 s 470 s 580 w	950 s 495 s 580 w	955 s 495 s 570 w	950 s 475 s	950 s 475 s	950 w 490 w 570 w	N—O M—O

b—broad, s—strong, sh—shoulder, m—medium, w—weak.

TABLE 7—INFRARED SPECTRAL DATA OF IPHA AND POLYMERS

IPHA	Mn(II)-polymer	Fe(II)-polymer	Co(II)-polymer	Ni(II)-polymer	Cu(II)-polymer	Zn(II)-polymer	Assignment
—	3300-3600 b	3250-3600 b	3200-3500 b	3200-3500 b	—	3200-3500 b	H—O—H
3180 m 1610 } 1590 } s	1540 } 1580 } s	1500 } 1520 } s 1570 sh	1520 } 1540 } s 1555 } 1570 }	1530 m	1530 } 1540 } m	1525 m	O—H C=O
950 s	970 s 460 w	970 w 540 m	960 w	960 w	960 s 510 s	970 w 500 bsh	N—O M—O

b—broad; s—strong; bsh—broad shoulder; m—medium; sh—shoulder; w—weak.

is observed at 970, 965 and 950  $\text{cm}^{-1}$  in PAPHA, FPFA and IPHA, respectively.

As anticipated, the O-H band disappears in the polymers. The carbonyl band is found to have been displaced towards lower frequency side indicating the formation of C—O...M coordinate bond.

N—O stretching band is reported to be shifted towards higher frequency side with an increase in intensity<sup>8</sup>. The same is observed in case of IPHA polymers. However, it is found to have been shifted towards lower frequency side in case of PAPHA and FPFA polymers. There is no significant increase in the intensity.

The presence of a band in the region 3200–3600  $\text{cm}^{-1}$  indicates the O-H stretching vibration of lattice or coordinated water wherever it is present.

In all the cases the evidence of metal to oxygen (of the ligand) bonding is observed by a frequency at 450 to 615  $\text{cm}^{-1}$  except in Co(II) and Ni(II)-IPHA polymers.

#### Electronic spectra and magnetic measurements

Electronic spectral data and magnetic data are summarised in Table 8

TABLE 8 —MAGNETIC AND ELECTRONIC SPECTRAL DATA OF POLYMERS

Sl No	Polymer	Effective magnetic moment B M	Absorption bands (kK)	Assignment
1	Mn-PAPHA	5.4187	28.57 23.80	${}^6A_1 \rightarrow {}^6E(D)$ ${}^6A_1 \rightarrow {}^6E(G)$
2	Mn-FPFA	5.1584	27.77	${}^6A_1 \rightarrow {}^6E(D)$
3	Mn-IPHA	5.2838	25.64	${}^6A_1 \rightarrow {}^6F(G)$
4	Fe-PAPHA	5.3197	18.51	C T
5	Fe-FPFA	5.3963	20.83	C T
6	Fe-IPHA	5.2510	17.85 14.49	C T C T
7	Co-PAPHA	5.1593	21.73 18.57	${}^4A_g \rightarrow {}^4T_1(P)$
8	Co-FPFA	4.5828	26.31	C T
9	Co-IPHA	4.9560	22.72 18.51	${}^4T_{1g} \rightarrow {}^4T_{1g}(P)$
10	Ni-PAPHA	3.1509	20.00 14.92 12.82	${}^3T_1 \rightarrow {}^3T_1(P)$ ${}^3T_1 \rightarrow {}^3T_1(P)$ ${}^3T_1 \rightarrow {}^3E$
11	Ni-FPFA	2.8866	26.31	${}^3A_{2g} \rightarrow {}^3T_{1g}(P)$ or C T
12	Ni-IPHA	3.7521	22.72 16.66	${}^3A_{2g} \rightarrow {}^3T_{1g}(P)$ ${}^3A_{2g} \rightarrow {}^3T_{1g}(F)$
13	Cu-PAPHA	1.9918	27.77 14.28	C T $d_{yz}, d_{xz} \rightarrow d_{x^2-y^2}$
14	Cu-FPFA	1.8823	27.77 16.66 12.82	C T $d_{yz}, d_{xz} \rightarrow d_{x^2-y^2}$ $d_{x^2-y^2} \rightarrow d_{z^2} - y^2$
15	Cu-IPHA	1.8096	32.72 13.33	C T $d_{yz}, d_{xz} \rightarrow d_{x^2-y^2}$

**Mn(II)-polymers:** In Mn(II)-PAPHA polymer, two strong bands are observed at 28.57 and 23.80 kK which are assigned to  ${}^6A_1 \rightarrow {}^6E(D)$  and  ${}^6A_1 \rightarrow {}^6E(G)$  excitations, respectively. Only one band appears in FPFA-polymer at 27.77 kK which can be assigned to  ${}^6A_1 \rightarrow {}^6E(D)$  excitation and one band at 25.64 kK in IPHA-polymer can be assigned to  ${}^6A_1 \rightarrow {}^6E(G)$  excitation.

Moderate intensity of these bands is indicative of tetrahedral geometry.

The values of magnetic moment correspond to  $d^5$ , Mn(II) in all the polymers as reported in the literature<sup>9</sup>

**Fe(II)-polymers:** One band at 18.51 kK in PAPHA-polymer and at 20.83 kK in FPFA-polymer may be conveniently assigned to charge transfer<sup>7</sup>. Two bands at 17.85 kK and 14.49 kK in IPHA-polymer may also be assigned to charge transfer.

The values obtained for the magnetic moment for all the polymers lie well within the range reported for octahedral high spin Fe(II) complexes.

**Co(II)-polymers:** Two bands at 21.73 kK and 18.57 kK in PAPHA-polymer are assigned to  ${}^4A_g \rightarrow {}^4T_1(P)$  excitation. Position of bands in the reflectance spectrum as well as magnetic moment of the Co(II)-PAPHA polymer suggest octahedral geometry. Elemental analysis, however, shows contradiction. Hence tetrahedral geometry is suggested for this polymer.

One band at 26.31 kK in FPFA-polymer can be assigned to charge transfer. The spectrum of this polymer surprisingly does not show any band in the near infrared or visible region which can be assigned to d-d transition. Magnetic moment, and composition proposed on the basis of elemental analysis suggest tetrahedral geometry.

Two bands at 22.72 kK and 18.51 kK in IPHA-polymer can be assigned to  ${}^4T_{1g} \rightarrow {}^4T_{1g}(P)$  transition suggesting octahedral geometry. Magnetic moment lies slightly lower than the calculated one which may be accounted for high orbital contribution.

**Ni(II)-polymers:** In FPFA-polymer a band appears at 26.31 kK which is assigned to  ${}^3A_{2g} \rightarrow {}^3T_{1g}(P)$  transition or charge transfer. A band at 22.72 kK in IPHA-polymer can be assigned to  ${}^3A_{2g} \rightarrow {}^3T_{1g}(P)$  transition and at 16.66 kK to  ${}^3A_{2g} \rightarrow {}^3T_{1g}(F)$  transition. This is in good agreement with Liehr and Ballhausen<sup>10</sup> energy level diagram for Ni(II) ion in octahedral geometry.

The magnetic moment for Ni(II)-FPFA polymer lies well within the range generally reported for octahedral Ni(II) complexes<sup>10</sup>. The higher value obtained for IPHA-polymer may be due to the departure from octahedral geometry towards tetragonal ( $D_{4h}$ ) geometry<sup>11</sup>.

In Ni(II)-PAPHA polymer, a shoulder at 20.00 kK and two bands at 14.92 kK and 12.82 kK are assigned to  ${}^3T_1 \rightarrow {}^3T_2(P)$ ,  ${}^3T_1 \rightarrow {}^3T_1(P)$  and  ${}^3T_1 \rightarrow {}^3E$  excitations, respectively indicating tetrahedral geometry. The value for magnetic moment lies lower than the value generally reported for tetrahedral Ni(II) complexes.

**Cu(II)-polymers:** In all the Cu(II)-polymers charge transfer bands are observed on higher frequency side of the spectra. Besides these, weaker bands are observed at 14.28 kK, 16.66 kK and 13.33 kK in PAPHA-, FPFA- and IPHA-polymers, respectively which are assigned to  $d_{yz}, d_{xz} \rightarrow d_{x^2-y^2}$

transition. One more band at 12.82 kK in FPHA-polymer is assigned to  $d_{xy} \rightarrow d_{x^2-y^2}$  transition.

From the reflectance spectra, all the Cu(II)-polymers can be assigned a distorted tetrahedral geometry. Magnetic data, however, show contradiction and suggest square planar geometry.

**Zn(II)-polymers:** These are diamagnetic and on the basis of elemental analysis, are suggested to be tetrahedral.

#### Proposed structures

The characterization of the polymers prepared in the present investigation is difficult because of their insolubility and intractability. Their formation as polymers from steric considerations and assignment of degree of polymerization on the basis of elemental analysis are tentative.













The composition has been suggested on the basis of elemental analysis (Tables 2 to 4), which is explained later with the help of IR spectra, magnetic

and reflectance studies and tentative structures have been proposed for these compounds.

The structures given for coordination polymers are always questionable. A simple linear, two dimensional planar or three dimensional structures are possible when the metal is coordinated to two, three or four ligand molecules, respectively. In the case of the polymer derived from methylene-bis-(5-salicylaldehyde) it has been suggested on the basis of some physico-chemical studies that two or three dimensional lattice structure predominates<sup>12</sup>. If the degree of polymerization is limited to certain extent then in such type of polymers the metal to ligand compositions may not correspond to that of linear chain polymer. Keeping these in view, linear chain unit structures proposed for the polymers may be taken as tentative ones.

Observations of the composition of some of the compounds lead to the conclusion that they should be simple polynuclear complexes, but their extreme

TABLE 9—PROPOSED STRUCTURES OF THE POLYMERS

Metal				Proposed structure	
Mn(II)	$n = 4$	Where $R =$			
Ni(II)	$n = 1$				
Mn(II)	$n = 3$	Where $R =$			
Mn(II)	$n = 3$	Where $R =$			
Zn(II)	$n = 2$				
Fe(II)		Where $R =$			
Fe(II)		Where $R =$			
Ni(II)					
Fe(II)		Where $R =$			
Ni(II)					
Co(II)					
Co(III)		Where $R =$			
Cu(II)					
Zn(II)					
Co(III)		Where $R =$			
Cu(II)					
Zn(II)					
Cu(II)		Where $R =$			

insolubility makes one believe in their polymeric nature with more complex features present. The association of these low molecular weight units through hydrogen bonding or polymerization, making use of hydroxyl as bridging groups, cannot be ruled out. The structures proposed in Table 9 should therefore be taken as tentative in the light of the above discussion.

#### References

1. W. C. FERNELIUS, M. SHAMMA, L. A. DAVIS, D. E. GOLDBERG, B. B. MARTIN, D. F. MARTIN and F. D. THOMAS, III WADC Tech. Rept. No. 56-203, Part III, 1958
2. U. PRIYADARSHINI and S. G. TANDON, *J. Chem. Engg. Data*, 1967, 12, 143.
3. S. G. TANDON and S. C. BHATTACHARYYA, *J. Chem. Engg. Data*, 1962, 7, 553
4. B. N. FIGGIS and D. J. MARTIN, *Inorg. Chem.*, 1960, 5, 100.
5. N. N. GHOSH and S. K. MUKHOPADHYAY, *J. Indian Chem. Soc.*, 1973, 50, 553.
6. F. A. COTTON, "Progress in Inorganic Chemistry", John Wiley and Sons, Inc., 1964, Vol. 6
7. A. B. P. LEVER, "Inorganic Electronic Spectroscopy", Elsevier, 1969, pp. 292, 299, 317, 333, 335.
8. S. P. GHOSH, P. BHATTACHARJEE and L. R. MISHRA, *J. Indian Chem. Soc.*, 1974, 51, 306
9. A. D. LIEHR and C. J. BALLHAUSEN, *Ann. Phys.*, 1969, 7, 134.
10. B. N. FIGGIS and J. LEWIS, *Prog. Inorg. Chem.*, 1964, 6, 37.
11. B. SINGH, LAKSHMI and U. AGARWALA, *Inorg. Chem.*, 1969, 8, 2341.
12. A. P. TERENT'EV, V. V. RODE and E. G. RUKHADZE, *Vysokomol. Soedin.*, 1966, 5, 1666, *Chem. Abs.*, 1964, 60, 659

# Anthranilic Acid Hydrazone Complexes of Aluminium(III) and Titanium(IV)


A. K. NARULA, B. SINGH and R. N. KAPOOR\*

Department of Chemistry, University of Delhi, Delhi-110 007

Anthranilic acid hydrazone (aaH) complexes of aluminium(III) and titanium(IV) have been synthesised by the reactions of isopropoxides and chlorides of aluminium(III) and titanium(IV) with anthranilic acid hydrazone in benzene. The complexes of the type  $[Al(OPr^i)_3-n(aa)_n]$ ,  $[AlCl_3-n(aa)_n]$  (where  $n=1$  or  $2$ ),  $[Ti(OPr^i)_4-n(aa)_n]$ ,  $[TiCl_4-n(aa)_n]$  (where  $n=1-3$ ) and (aa = anthranilic acid hydrazone anion) have been isolated. All these complexes are partially soluble in chloroform, benzene and have been characterised on the basis of elemental analysis, ir and nmr spectral studies and electrical conductance measurements.

THERE has been considerable interest in the chemistry of acid hydrazides and hydrazones because of their use in biological systems<sup>1-4</sup>. These hydrazides and hydrazones are versatile ligands due to several potential coordination sites<sup>5</sup>.

Several transition metals complexes of various acid hydrazides and hydrazones have been reported<sup>6,7</sup>. However, no attempt has been made to synthesise aluminium(III) and titanium(IV) complexes of acid hydrazides. Hence it was considered worthwhile to study the reactions of isopropoxides and chlorides of aluminium(III) and titanium(IV) with anthranilic acid which possesses labile protons attached to oxygen as well as nitrogen atoms. Such a study appears to be useful particularly because of the observations that 2-pyrrolidinone possessing  $-NH$  and  $>C=O$  group, forms adducts with titanium(IV) chloride whereas in the reactions with titanium isopropoxide, a substituted product was obtained<sup>8</sup>. In view of the above, anthranilic acid hydrazone was chosen whose structure is depicted below.



It is obvious from these structure that this ligand possesses one labile proton which is capable of undergoing amido-imido tautomerism.

## Experimental

Glass apparatus with standard quickfit joints were used throughout the experimental work and stringent precautions were taken to exclude moisture. Benzene (AR, BDH), isopropanol (BDH) *tert*-butanol (SD'S) were dried and purified by standard method.  $AlCl_3$  (BDH),  $TiCl_4$  (Riedel), methyl

anthranilate (Goldsun) and hydrazine hydrate (BDH) were used as supplied. Isopropoxides of aluminium(III) and titanium(IV) were prepared by standard methods<sup>9-11</sup>. Anthranilic acid hydrazone was prepared by usual method and recrystallised from chloroform.

The ir spectra were recorded on Perkin Elmer 621 spectrophotometer using nujol mulls, caesium iodide pellets or KBr pellets. The nmr spectra were recorded on Perkin-Elmer R-32 spectrometer. Isopropanol was estimated by oxidimetric method<sup>12</sup> using  $1N K_2Cr_2O_7$  in 12.5% sulphuric acid. Chloride was estimated gravimetrically as silver chloride and nitrogen was estimated by Kjeldahl's method.

Aluminium was estimated as aluminium oxinate. Titanium was estimated as  $TiO_2$  by direct ignition of compounds after digestion with ammonia and nitric acid in silica crucible. C and H were determined in the micro analytical laboratory of the Department of Chemistry, University of Delhi, Delhi.

## Reactions

**Reaction of isopropoxide of aluminium(III) with anthranilic acid hydrazone (molar ratio 1 : 1):** To a solution of  $Al(OPr^i)_3$  (0.40 g; 1.96 mmole) in benzene was added anthranilic acid hydrazone (0.30 g; 1.96 mmole). A yellow suspension appeared at the time of addition. The resulting mixture was refluxed for about 4 hr. The isopropanol liberated was collected azeotropically and estimated<sup>13</sup>. The excess of solvent was distilled off and the final product was dried under vacuum at  $40^\circ/0.5$  mm when a white solid was obtained. Found: Isopropanol in azeotrope, 0.12 g; Al, 8.6, N, 13.9. Calcd. for  $[Al(OPr^i)_2(aa)]$ ; isopropanol in azeotrope, 0.12 g; Al 9.1; N, 14.2%.

For the sake of brevity other reactions are given in Table I.

\* Author for correspondence.

TABLE 1—REACTIONS OF ISOPROPOXIDES OF ALUMINIUM(III) AND TITANIUM(IV)

Sl. No.	Alkoxide g (mmole)	Acid hydrazide g (mmole)	Molar ratio	Time of refluxing hr	Product and their state	Amount of isopropanol in the azeotrope (g) Found (Calcd.)	Analysis %			
							Metal Found (Calcd.)	N Found (Calcd.)	C Found (Calcd.)	H Found (Calcd.)
1.	Al(Pr <sup>t</sup> ) <sub>3</sub> 0.40 (1.95)	aaH 0.30 (1.95)	1 : 1	4	[Al(OPr <sup>t</sup> ) <sub>3</sub> aa] White solid	0.12 (0.12)	8.6 (9.1)	13.9 (14.2)	52.4 (52.9)	7.4 (7.8)
2.	Al(OPr <sup>t</sup> ) <sub>3</sub> 0.61 (2.98)	aaH 0.90 (5.96)	1 : 2	6	[Al(OPr <sup>t</sup> ) <sub>3</sub> (aa) <sub>2</sub> ] White solid	0.35 (0.36)	6.7 (6.9)	21.3 (21.7)	—	—
3.	Ti(OPr <sup>t</sup> ) <sub>4</sub> 0.49 (1.72)	aaH 0.26 (1.72)	1 : 1	4	[Ti(OPr <sup>t</sup> ) <sub>4</sub> (aa)] Dark brown solid	0.10 (0.10)	12.6 (12.8)	11.0 (11.2)	51.0 (51.2)	7.9 (8.0)
4.	Ti(OPr <sup>t</sup> ) <sub>4</sub> 0.58 (2.03)	aaH 0.62 (4.10)	1 : 2	6	[Ti(OPr <sup>t</sup> ) <sub>4</sub> (aa) <sub>2</sub> ] Dark brown solid	0.23 (0.24)	9.8 (10.3)	17.5 (18.0)	51.3 (51.5)	6.7 (6.8)
5.	Ti(OPr <sup>t</sup> ) <sub>4</sub> 0.31 (1.09)	aaH 0.50 (3.30)	1 : 3	12	[Ti(OPr <sup>t</sup> ) <sub>4</sub> (aa) <sub>3</sub> ] Dark brown solid	0.19 (0.20)	8.3 (8.6)	21.7 (22.6)	51.5 (51.7)	5.9 (6.1)

TABLE 2—ALCOHOLYSIS REACTIONS OF MIXED ISOPROPOXY ACID HYDRAZIDES DERIVATIVES OF ALUMINIUM(III) AND TITANIUM(IV) WITH TERTIARY BUTANOL (EXCESS)

Sl. No.	Mixed alkoxide derivatives (g)	Alcohol	Molar ratio	Time of refluxing (hr)	Product	Amount of isopropanol in the azeotrope (g) Found (Calcd.)	Metal % Found (Calcd.)
1.	[Al(OPr <sup>t</sup> ) <sub>3</sub> aa] (0.22)	Bu <sup>t</sup> OH	1 : excess	5	[Al(OBu <sup>t</sup> ) <sub>3</sub> (aa)]	0.09 (0.09)	7.9 (8.3)
2.	[Al(OPr <sup>t</sup> ) <sub>3</sub> (aa) <sub>2</sub> ] (0.36)	Bu <sup>t</sup> OH	1 : excess	3	[Al(OBu <sup>t</sup> ) <sub>3</sub> (aa) <sub>2</sub> ]	0.05 (0.05)	6.6 (6.7)
3.	[Ti(OPr <sup>t</sup> ) <sub>4</sub> (aa)] (0.25)	Bu <sup>t</sup> OH	1 : excess	6	[Ti(OBu <sup>t</sup> ) <sub>4</sub> (aa)]	0.12 (0.12)	11.4 (11.5)
4.	[Ti(OPr <sup>t</sup> ) <sub>4</sub> (aa) <sub>2</sub> ] (0.28)	Bu <sup>t</sup> OH	1 : excess	4	[Ti(OBu <sup>t</sup> ) <sub>4</sub> (aa) <sub>2</sub> ]	0.07 (0.07)	9.4 (9.7)
5.	[Ti(OPr <sup>t</sup> ) <sub>4</sub> (aa) <sub>3</sub> ] (0.40)	Bu <sup>t</sup> OH	1 : excess	4	[Ti(OBu <sup>t</sup> ) <sub>4</sub> (aa) <sub>3</sub> ]	0.04 (0.04)	8.1 (8.4)

TABLE 3—REACTIONS OF CHLORIDES OF ALUMINIUM(III) AND TITANIUM(V) WITH ANTHRANILIC ACID HYDRAZIDE

Sl. No.	Metal chloride g (mmole)	Acid hydrazide g (mmole)	Molar ratio	Time of refluxing (hr)	Product	Analysis %				
						Metal Found (Calcd.)	Cl Found (Calcd.)	N Found (Calcd.)	C Found (Calcd.)	H Found (Calcd.)
1.	AlCl <sub>3</sub> 0.48 (3.59)	aaH 0.54 (3.59)	1 : 1	20-22	[Al(Cl) <sub>3</sub> (aa)]	10.6 (10.8)	28.1 (28.6)	16.8 (16.9)	33.3 (33.9)	3.4 (3.6)
2.	AlCl <sub>3</sub> 0.28 (2.09)	aaH 0.63 (4.17)	1 : 2	24	[AlCl(aa) <sub>2</sub> ]	6.8 (7.4)	9.4 (9.7)	22.8 (23.1)	46.0 (46.3)	4.0 (4.9)
3.	TiCl <sub>4</sub> 0.54 (2.84)	aaH 0.43 (2.84)	1 : 1	16	[TiCl <sub>3</sub> (aa)]	15.1 (15.7)	34.6 (34.9)	13.2 (13.6)	27.2 (27.6)	3.0 (2.9)
4.	TiCl <sub>4</sub> 0.29 (1.52)	aaH 0.46 (3.04)	1 : 2	20	[TiCl <sub>3</sub> (aa) <sub>2</sub> ]	11.2 (11.4)	16.7 (16.9)	19.7 (20.0)	39.6 (40.0)	4.0 (4.2)
5.	TiCl <sub>4</sub> 0.38 (2.00)	aaH 0.91 (6.01)	1 : 3	25-26	[TiCl(aa) <sub>3</sub> ]	8.7 (8.9)	6.5 (6.6)	23.3 (23.6)	—	—

Reaction between bis-isopropoxy aluminium(III) anthranilic acid hydrazide complex with tertiary butanol: To a solution of Al(OPr<sup>t</sup>)<sub>3</sub>(aa) (0.22 g) in benzene was added tertiary butanol (excess) and

the mixture was refluxed at bath temperature of 110-120°. The isopropanol liberated was fractionated azeotropically with benzene at 72-80°. The excess of solvent and tertiary butanol was removed under

reduced pressure, leaving a white solid mass. Found : Pr<sup>4</sup>OH in azeotrope, 0.09 g ; Al, 7.9. Calcd. for [Al(OBu<sup>4</sup>)<sub>3</sub>(aa)] ; Pr<sup>4</sup>OH in azeotrope, 0.09 g ; Al, 8.3%.



The details of other reactions are given in Table 2.

**Reaction between aluminium trichloride and anthranilic acid hydrazide (aaH) (molar ratio 1 : 1) :** Anthranilic acid hydrazide (0.54 g ; 3.59 mmole) was added to a suspension of aluminium trichloride (0.48 g) in benzene (~50 ml). The mixture was refluxed in an oil bath for 20-22 hr when no more hydrogen chloride gas evolved. The reaction mixture was cooled at room temperature and excess of solvent removed under reduced pressure leaving behind a white compound. Found : Al, 28.1 ; Cl, 9.6 ; N, 16.8. Calcd for [AlCl<sub>3</sub>(aa)] ; Al, 28.6 ; Cl, 10.8 ; N, 16.9%.

The other reactions are given in Table 3

### Results and Discussion

A systematic study of reactions of isopropoxides and chlorides of aluminium(III) and titanium(IV) with anthranilic acid hydrazide in dry benzene has been carried out in different stoichiometric ratios. The reactions proceed according to following equations :




All these complexes are white to brown in colour and are soluble in dimethylsulphoxide and dimethylformamide. Electrical conductance, measured in dimethylformamide shows them to be non-electrolyte

Molecular weight could not be determined because of their insolubility in most of organic solvents. Only two of the isopropoxide or chloride groups are replaceable by anthranilic acid hydrazide in case of aluminium, whereas in the case of titanium three isopropoxide or chloride groups are replaced. This could be ascribed to steric hindrance or saturated coordination state of metals in these complexes, [AlX(aa)<sub>n</sub>] and [TiX(aa)<sub>n</sub>] (X=OPr<sup>4</sup> or Cl). These complexes tend to decompose when heated under reduced pressure (0.01 mm)

### IR spectra :


The important bands of the ligand are those which belong to amide, hydrazinic amino group vibrations. The amide group shows a number of bands due to combination of  $\nu(\text{C}=\text{O})$ ,  $\nu(\text{C}-\text{N})$  and  $\nu(\text{N}-\text{H})$  groups. In the spectra of ligand, the bands appearing in the regions ~1655-1645, 1560-1530, 1260-1250 may be assigned to amide I [ $\nu(\text{C}=\text{O})$ ], amide II [ $\nu(\text{CN}+\delta\text{NH})$ ], amide III [ $\nu(\text{CN}+\delta\text{NH})$ ] vibrations, respectively<sup>13,14</sup>. The appearance of all these bands shows that the amide group in anthra-

nilic acid hydrazide in solid state is present as such and not in its amido form. However, it may be pointed out that amide I absorbs at 1690-1650 cm<sup>-1</sup> and the lowering of amide I is due to hydrogen bonding between ketonic and amino groups of ligands as depicted below.



Accordingly, the amide group can coordinate to a metal atom through oxygen and secondary nitrogen atoms and it can also be involved in bond formation with metal atom through its imido oxygen or secondary nitrogen atom through deprotonation. The bands around 3160 and 3300 cm<sup>-1</sup> may be assigned to  $\nu_{\text{sym}}\text{NH}_2$  and  $\nu_{\text{asym}}\text{NH}_2$  vibrations. Additional bands at 1620-1605 and 870-865 cm<sup>-1</sup> may be assigned to  $\delta(\text{NH}_2)$  and  $\rho\text{NH}_2$  vibrations.

In the aluminium(III) and titanium(IV) anthranilic acid hydrazide complexes, the amide group vibration disappears on complexation and instead a strong band is observed at ca 1610 cm<sup>-1</sup>. It is likely that this band has its origin in  $\nu(\text{C}=\text{N})$  vibration which appears due to enolisation of the keto group, and the amide group



is involved in bonding with the metal atom through enolic oxygen of the amide group. The enolisation of amide group is also supported by the appearance of new bands in the region ~1580-1570 cm<sup>-1</sup> attributable to  $\nu(\text{NCO})$  vibrations. It is worth mentioning here that the  $\nu(\text{C}=\text{N})$  vibration has significant contribution from  $\delta(\text{NH}_2)$  vibration which occurs in the same region of the ligands. The involvement of enolic oxygen in anthranilic acid hydrazide complexes can be attributed to greater basicity of the ligand which facilitates the enolisation of amido group<sup>15</sup>. The coordination of amino group to metal atom in aaH complexes is indicated by a lowering of  $\nu(\text{NH})$  vibration (150 cm<sup>-1</sup>) and diminishing intensity or disappearance of  $\delta\text{NH}$  band occurring at 750 cm<sup>-1</sup>. The weak bands in the region 450-400 cm<sup>-1</sup> may be due to  $\nu\text{M}-\text{N}$  vibration. The changes observed in  $\nu(\text{NH})$  vibration in the complexes are not very conspicuous because of the presence of hydrazinic group which counterbalances any change occurring on coordination of amido group to metal. The strong band at ~535-550 cm<sup>-1</sup> may be assigned to  $\nu(\text{M}-\text{O})$  while a peak at 1285 cm<sup>-1</sup> may be assigned to geminal dimethyl moiety of isopropoxy group<sup>16</sup>. The  $\nu(\text{M}-\text{Cl})$  absorbs at ~360-380 cm<sup>-1</sup>.

### NMR spectra :

The nmr spectra of the ligand show a complex multiplet at  $\delta$ 7.3 ppm due to phenyl ring protons, a doublet at  $\delta$ (6.7-6.8) ppm assignable to protons of terminal hydrazinic amino group, doublet at  $\delta$ (4.35-4.42) ppm assignable to -NH protons of -CO.NH group and finally a singlet at  $\delta$ 3.9 ppm, possibly due to protons of amino group.



On account of poor solubility, the nmr spectra of anthranilic acid hydrazide complexes were taken in deuterated dimethylsulphoxides. The spectra of anthranilic acid hydrazide complexes of titanium (IV) isopropoxide show a signal at  $\delta 4.0$  ppm assignable to C-NH<sub>2</sub> group. This downfield shift indicates that the C-NH<sub>2</sub> group is deshielded. This is possible due to donation of lone pair of electrons by nitrogen to the titanium atom. The signal due to -NH protons of -CO.NH group  $\delta(4.35-4.42)$  ppm disappears altogether, indicating that deprotonation takes place through secondary amide nitrogen as a result of bond formation with nitrogen atom in enolic form. The position of the signal of protons due to the terminal hydrazinic group remains unperturbed ruling out the possibility of coordination of amino group. The 1:1, 1:2 and 1:3 anthranilic acid hydrazide complexes of titanium(IV) show two signals at  $\delta(1.20-1.52)$  ppm assignable to methyl protons of isopropoxy confirming the presence of isopropoxy group in these complexes.

Thus, it appears that anthranilic acid hydrazide acts as mononegatively charged bidentate chelating agents having coordination sites at amino and enolic oxygen atoms, respectively.

On the basis of the above studies, a polymeric structure can tentatively be assigned to these complexes. However, this may be confirmed by X-ray studies.

#### References

1. W. O. FOYE and R. N. DUVALL, *J. Amer. Pharm. Ass. Sci. Edn.*, 1958, 47, 285; E. SORKIN, W. A. LOTT, B. A. STEINBERG and H. L. YALE, *Amer. Rev. Tuberc.*, 1957, 65, 357.
2. J. R. DILWORTH, *Coord. Chem. Rev.*, 1976, 21, 29.
3. J. P. ALCOCK, H. J. BAKER and A. A. DIAMANTIS, *Aust. J. Chem.*, 1972, 25, 289.
4. M. KATYAL and Y. DUTT, *Talanta*, 1975, 22, 151.
5. S. K. SAHNI, S. P. GUPTA, S. K. SANGAL and V. B. RANA, *J. Inorg. Nuclear Chem.*, 1977, 39, 1098; *J. Indian Chem. Soc.*, 1977, 54, 200.
6. K. K. NARANG and R. C. AGGARWAL, *Inorg. Chim. Acta*, 1973, 7, 651; 1974, 9, 137; R. C. AGGARWAL and B. SINGH, *Trans. Met. Chem.*, 1975, 1, 161, 275.
7. D. K. RASTOGI, S. K. DUA, V. B. RANA and S. K. SAHNI, *J. Coord. Chem.*, 1979, 8, 97; *J. Inorg. Nuclear Chem.*, 1978, 40, 1323; *Trans. Met. Chem.*, 1978, 3, 56.
8. R. CHOUKRAVARTY and D. GERVAIS, *Inorg. Chim. Acta*, 1978, 26, 17.
9. W. G. YOUNG, W. H. HARTUNG and F. S. CROSSLEY, *J. Amer. Chem. Soc.*, 1936, 58, 100.
10. L. M. BROWN and K. S. MAZDIYASBI, *Inorg. Chem.*, 1970, 9, 2783.
11. D. C. BRADLEY, R. C. MEHROTRA and W. WARDLAW, *J. Chem. Soc.*, 1952, 2027.
12. D. C. BRADLEY, F. M. A. HALIM and W. WARDLAW, *J. Chem. Soc.*, 1950, 3450.
13. R. K. SHARMA, R. V. SINGH and J. P. TANDON, *Indian J. Chem.*, 1980, 19A, 378.
14. D. K. RASTOGI, S. K. DUA and S. K. SAHNI, *J. Inorg. Nuclear Chem.*, 1980, 42, 323.
15. L. SACCONNI, *J. Amer. Chem. Soc.*, 1952, 74, 4503; 1954, 76, 3400.
16. R. C. MEHROTRA, *J. Indian Chem. Soc.*, 1954, 31, 85.

# Phenyl-Tin Cleavage by Some Ferrocenyl Hydrazones

S. R. PATIL, U. N. KANTAK and D. N. SEN

National Chemical Laboratory, Pune-411 008

Ferrocenyl hydrazones of the type  $\text{FcCH}=\text{N}-\text{NH}-\text{C}-\text{Ar}$  [where  $\text{Fc}=\text{C}_5\text{H}_5\text{Fe}$

$\text{C}_5\text{H}_5$ ;  $\text{Ar}=\text{C}_6\text{H}_5$  (I),  $\text{C}_6\text{H}_4\text{Cl}$  (II),  $\text{C}_6\text{H}_4\text{NO}_2$  (III),  $\text{C}_6\text{H}_4\text{OH}$  (IV) and  $\text{C}_6\text{H}_4\text{N}$  (V)] form stable tin derivatives when reacted with triphenyltin acetate in benzene solution. Compound (I) gives hexacoordinated, octahedral tin(IV) complex, compound (II) gives penta-coordinated, trigonal bipyramidal tin(IV) complex, while compounds (III-V) give acetoxo bridged tin(IV) complexes which are dimeric in nature in solid form and monomeric in nature in chloroform solution. Evidences for their coordinated structures have been obtained from IR, PMR spectra and elemental analysis.

NELSON and Martin<sup>1</sup> have studied the interaction of chelating agents such as  $\beta$ -diketones, salicylaldehyde, 8-hydroxyquinoline with several organotin(IV) derivatives like tetraphenyltin, diphenyltin(IV) dichloride, triphenyltin chloride. They found that phenyl-tin cleavage is favoured at elevated temperatures, provided the ligand is present in high concentration. Such type of reactions can provide a convenient route for the preparation of new and interesting chelated tin compounds. Literature survey revealed no report on the interaction of chelating agents with triphenyltin acetate. In continuation of our studies on ferrocenyl hydrazones<sup>2</sup> we have investigated the reactions of some ferrocenyl hydrazones,  $\text{FcCH}=\text{N}-\text{NH}-\text{C}-\text{Ar}$  [ $\text{Fc}=\text{C}_5\text{H}_5\text{FeC}_5\text{H}_5$ ,  $\text{Ar}=\text{C}_6\text{H}_5$  (I),  $\text{C}_6\text{H}_4\text{Cl}$  (II),  $\text{C}_6\text{H}_4\text{NO}_2$  (III),  $\text{C}_6\text{H}_4\text{OH}$  (IV) and  $\text{C}_6\text{H}_4\text{N}$  (V)]

## Materials and Methods :

Ferrocenyl hydrazones were prepared by the procedure reported elsewhere<sup>2</sup>. Triphenyltin acetate was purchased from Aldrich Chemicals and used without further purification. All solvents were distilled and dried by standard procedures.

## Preparation of tin(IV) complexes :

All the tin(IV) complexes were prepared by the following general procedure :

Triphenyltin acetate and ferrocenyl ligand in equimolar ratio were taken in benzene and the solution refluxed for about 8 hr. The hot mixture was filtered to remove insoluble impurities and the filtrate was concentrated under vacuum at 50°. The solid product thus obtained in almost quantitative yield was recrystallized from either benzene or chloroform and dried under vacuum. The compounds prepared along with their melting points and elemental analyses are given in Table I.

## Spectroscopic methods :

Infrared spectra were recorded on a Perkin-Elmer model 283B spectrophotometer using caesium iodide optics. PMR spectra were recorded on a Varian Associates Model T-60 spectrometer using tetramethylsilane as an internal standard.

## Results and Discussion

Ferrocenyl hydrazones react with triphenyltin acetate in benzene at reflux temperature giving different kinds of tin derivatives. These tin deriva-

TABLE I—ELEMENTAL ANALYSES OF PHENYL TIN(IV) COMPLEXES OF SOME FERROCENYL HYDRAZONES

Sl. No.	Compound	Composition	Yield %	m. p. °C	Analysis %		
					C	H	N
1.	VI	$\text{C}_{18}\text{H}_{10}\text{N}_2\text{O}_2\text{Fe}_2\text{Sn}$	95	252	60.39 (61.67)*	4.69 (4.31)	6.12 (5.99)
2.	VII	$\text{C}_{18}\text{H}_9\text{N}_2\text{OClFeSn}$	85	255	61.39 (60.50)	4.96 (4.60)	4.40 (4.00)
3.	VIII	$\text{C}_{18}\text{H}_7\text{N}_2\text{O}_2\text{FeSn}$	90	235	54.48 (54.30)	4.10 (3.85)	6.18 (5.94)
4.	IX	$\text{C}_{18}\text{H}_9\text{N}_2\text{O}_2\text{FeSn}$	78	214	58.19 (58.65)	4.76 (4.16)	3.91 (4.13)
5.	X	$\text{C}_{11}\text{H}_9\text{N}_2\text{O}_2\text{FeSn}$	80	232	57.56 (56.69)	4.47 (4.24)	6.11 (6.32)

\* Figures with parentheses are Calculated values.

\* NCL Communication No. 2929.

tives are stable and soluble in common organic solvents.

The elemental analyses of these compounds clearly show that reaction of ferrocenyl hydrazone compound I and triphenyltin acetate gives tin(IV) complex of the formula  $(C_6H_5)_3Sn(L_2)$  (VI), (where  $L_2$ =ferrocenyl hydrazone anion). In this case both the phenyltin cleavage and elimination of acetoxy group have been observed. However, interaction of compound (II) with triphenyltin acetate is found to result in the elimination of acetoxy group only giving tin(IV) complex of the formula  $(C_6H_5)_3Sn(L)$  (VII). Yet, interaction of compounds (III-V) is found to proceed in a different manner giving novel acetoxy bridged tin(IV) complexes of the formula  $[(C_6H_5)_3SnL(OAc)]_2$  (VIII-X).

The infrared spectra of the ligands in Nujol<sup>2</sup> show strong N-H and C=O (amide I) stretching vibration bands around 3220 and 1650  $cm^{-1}$ , respectively. The  $\nu(N-N)$  band is found as a medium intense band around 920  $cm^{-1}$ . The spectra of chelated tin(IV) complexes (Table 2) show the absence of absorption bands due to  $\nu(N-H)$  and  $\nu(C=O)$ . Instead, two new bands are observed around 1605 and 1230  $cm^{-1}$  which can be assigned to the stretching vibrational modes of conjugate  $>C=N-N=C<$  and C-O groups<sup>3,4</sup>. A strong intense band around 1075  $cm^{-1}$  can be assigned to phenyltin vibration<sup>6</sup>. This observation suggests that ligands enolize in solution and then bond with metal ions through replacement of amide proton. In the spectra of all the metal complexes amide-II band is shifted to lower frequency by about 30  $cm^{-1}$  while  $\nu(N-N)$  band is shifted to a slightly higher frequency by ca 15  $cm^{-1}$ . The negative shift in amide-II and the positive shift in  $\nu(N-N)$  bands support the coordination through azomethine nitrogen atom. The characteristic bands of ferrocenyl moiety are observed as expected in the spectra. In the case of tin(IV) complex derived from compound

IV, broad and weak bands centered around 2930  $cm^{-1}$  attributable to the intramolecular -OH bonding are expected to be observed, but identification of these bands is not possible due to the presence of ligand vibrations in this region.

The spectra in the region 1600-1450  $cm^{-1}$  are complex for all these compounds due to overlapping of several absorption bands. Although acetoxy group frequencies are difficult to locate due to the complex pattern of the spectra, the presence of acetoxy group in compounds VIII-X has been indicated by elemental analysis and supported by pmr spectral data.

The metal-ligand vibrational modes are generally found to occur in the far infrared region between 600-200  $cm^{-1}$ . However, in the spectra of these complexes it is not easy to locate metal ligand vibrations because of the various skeletal vibrations of the ligands. In this study, the assignments made (Table 2) are purely tentative and based mainly on the information available in literature. The strong bands around 495  $cm^{-1}$  can be assigned<sup>6</sup> to  $\nu(Sn-O)$ . The bands in the range 380-335  $cm^{-1}$  and 610-600  $cm^{-1}$  can be assigned to  $\nu(Sn-N)$  and  $\nu(Sn-C)$ , respectively<sup>7-9</sup>.

The pmr spectral data of tin(IV) complexes (Table 3) show the presence of acetoxy groups in the complexes VIII and X (methyl group protons at 2.10 ppm). The proton integration ratio shows the presence of only two phenyl rings in the complexes which again supports the phenyltin cleavage. The spectrum of compound VI shows phenyltin cleavage as well as the absence of acetoxy group in this compound. However, the spectrum of compound VII shows only the absence of acetoxy group and no loss of phenyl group.

In the case of all these compounds phenyl group protons appear around 7.16-7.33 ppm and azomethine proton at 7.06-7.16 ppm which is shifted down-

TABLE 2—IMPORTANT IR FREQUENCIES ( $cm^{-1}$ ) OF PHENYL TIN(IV) COMPLEXES OF FERROCENYL HYDRAZONES IN NUJOL MULL

Sl. No.	Compound	-C-N-N-C-	C-O	Sn-C	Sn-O	Sn-N	Sn-phenyl
1.	VI	1610 (s)	1240 (s)	610 (m)	560 (m)	370 (s)	1075 (s)
2.	VII	1610 (s)	1245 (s)	610 (m)	560 (m)	340 (s)	1070 (m)
3.	VIII	1600 (s)	1240 (s)	610 (w)	580 (s)	335 (m)	1075 (m)
4.	IX	1600 (w)	1240 (m)	610 (m)	555 (m)	360 (m)	1075 (m)
5.	X	1615 (s)	1260 (s)	615 (s)	560 (m)	380 (s)	1080 (m)

TABLE 3—PROTON CHEMICAL SHIFTS ( $\delta$ ) OF COMPLEXES DERIVED FROM TRIPHENYL TIN ACETATE

Sl. No.	Compound	Ferrocenyl group		Azomethine proton	Aromatic	Phenyl group	OCH <sub>3</sub> protons
		Unsubstituted $C_6H_5$	Substituted $C_6H_4$				
1.	VI	3.9	4.33 4.86	*	8.23	7.4	—
2.	VII	3.9	4.4 4.9	7.16	8.23	7.4	—
3.	VIII	3.93	4.4 5.00	*	8.06	7.16	2.06
4.	X	3.91	4.23 4.83	7.06	8.00 8.66	7.33	2.12
5.	Triphenyltin acetate	—	—	—	—	7.43	2.00

\* Superimposed by peaks due to aromatic protons.




Fig. 1






Fig. 2

(Fc = Ferrocenyl group)



3a



3b

Fig. 3

field by an order of 1.00 ppm. This downfield shift is due to the chelation through azomethine nitrogen atom. Unsubstituted cyclopentadienyl protons appear as singlet at 3.8-4.3 ppm and protons of substituted cyclopentadienyl ring appear at 4.0-4.4 and 4.4-5.23 ppm as broad peaks as expected.

#### Structure of compounds VI and VII :

Elemental analysis and spectral studies indicate that compound VI may have the six coordinate, octahedral structure as shown in Fig. 1 and compound VII may have 5-coordinate trigonal bipyramidal structure (Fig. 2).

#### Structure of compounds VIII-X :

Although it is not possible to identify the characteristic acetoxy group absorption bands at 1540-1565  $\text{cm}^{-1}$  in the infrared spectra of compounds VIII, IX and X in Nujol mull, a new band is seen at 1610-1620  $\text{cm}^{-1}$  in the spectra of these compounds in chloroform solution. The appearance of this new band is indicative of some structural changes in solution, but still suggesting a non-ester type of acetoxy group<sup>10</sup>. Accordingly, structures 3a and 3b (Fig. 3) can be tentatively suggested for these compounds, the solid compounds existing in dimeric form.

The molecular weight determination in chloroform (vapour-pressure osmometric method) shows the molecular weight to be in between the monomer and dimer, which again suggests that in chloroform solution these compounds may dissociate to monomer and an equilibrium between monomer-dimer exists.

#### Acknowledgement

One of the authors (S.R.P.) is grateful to C.S.I.R., New Delhi, for a Research Fellowship.

#### References

1. W. H. NELSON and D. F. MARTIN, *J. Organometal. Chem.*, 1965, 4, 67.
2. S. R. PATIL, U. N. KANTAK and D. N. SEN, Communicated to *Inorg. Chim. Acta*.
3. R. G. R. BACON and W. S. LINDSAY, *J. Chem. Soc.*, 1958, 1382.
4. K. NAGANO, H. KINOSHITA and A. HIRAKAWA, *Chem. Pharm. Bull. Tokyo*, 1964, 12, 1198.
5. R. C. POLLER, *J. Inorg. Nuclear Chem.*, 1962, 24, 593.
6. K. KAWAKAMI and R. OKAWARA, *J. Organometal. Chem.*, 1966, 6, 249.
7. T. TANAKA, M. KOMURA, Y. KAWASAKI and R. OKAWARA, *J. Organometal. Chem.*, 1964, 1, 484.
8. R. A. CUMMINS, *Aust. J. Chem.*, 1963, 16, 985.
9. R. A. CUMMINS and J. V. EVANS, *Spectrochim. Acta*, 1965, 21, 1016.
10. M. WADA, M. SHINDO and R. OKAWARA, *J. Organometal. Chem.*, 1963, 1, 95.

# Metal Complexes as Ligands : Binuclear Alkali Metal Complexes with Copper(II)- and Nickel(II)-Salicylaldimines

A. K. BANERJEE, DHARMBIR PRASAD and S. K. ROY

Department of Chemistry, Patna University, Patna-800 005

The Schiff base complexes of nickel(II) and copper(II)-N,N'-disalicylidene ethylenedimine [M<sub>a</sub>ES] have been used as a bidentate ligand (complex ligand) in the synthesis of novel binuclear alkali metal complexes of the general formula [M<sub>a</sub>ES M<sub>b</sub>L], M<sub>a</sub>ES acting as a bidentate complexing agent, coordinating through two phenolic oxygens to alkali metal salts M<sub>b</sub>L (where, M<sub>b</sub>L = Li, Na or K salts of 1-nitroso-2-naphthol, 8-hydroxyquinoline, anthranilic acid as well as alkali metal salts KSCN, LiCl, NaBr and NaI). The phenolic C-O link retained a considerable amount of partial double bond character in these binuclear complexes. The structure has been substantiated by infrared, electronic spectra and magnetic studies.

IN recent years, the formation of oxygen bridged complexes containing two different ligands has become of interest to coordination chemists. Transition metal complexes having phenolic oxygen atoms or  $\beta$ -diketone have been used as a ligand to study oxygen bridged complexes. Since all of these studies involved only transition metals, we thought it of interest to study the same phenomenon with the alkali metals.

As regards the study of alkali metals with due reference to the chances of complex formation, we have selected [bis-N,N'-ethylenedis(salicylideneimino)copper(II)]<sup>1</sup> and [bis-N,N'-ethylenedis(salicylideneimino)nickel(II)]<sup>2</sup> denoted as CuES and NiES, respectively as 'metal complex' ligands, and studied their behaviour.

The formation of oxygen bridged binuclear complexes from metal salicylaldimines (i.e., CuES or NiES) has been well established by Gruber *et al.*<sup>3-5</sup> The CuES or NiES acts as a bidentate ligand in complexing with metal halides, M'X<sub>n</sub> (i.e., CuCl<sub>2</sub>, NiCl<sub>2</sub>, etc.), to which it coordinates through the two phenolic oxygen atoms. The crystal structure of the compound (CuES)<sub>2</sub>.NaClO<sub>4</sub> has also been reported by Truter and coworkers<sup>6</sup> showing attachment of sodium with phenolic oxygen.

In view of the above, it was decided to extend the investigation by a systematic examination of the complexes of CuES and NiES with alkali metal salts (both organic and inorganic), which may be useful in understanding the transport and absorption mechanism of alkali metal ions from soil to plant.

## Experimental

Our usual method of synthesis was to take CuES or NiES in a mixture of benzene and absolute ethanol (1 : 1), and to add alkali metal salts to it. The reaction mixture was then refluxed with constant stirring on a hot plate for about 12-16 hr. The whole thing went into solution and subsequently the

adducts were precipitated in hot condition during the process of refluxing. They were filtered, washed with a mixture of benzene and absolute ethanol (1 : 1) and dried in an air oven at 90°.

## Results and Discussion

The adducts are insoluble in benzene, ethanol and chloroform. They are stable under dry condition, but decompose on exposure to moisture; as such, they were kept in a desiccator over anhydrous CaCl<sub>2</sub>. The colour, decomposition temperature and analytical values of these complexes are given in Table I. Detailed discussions of infrared spectra, magnetic properties and electronic spectra of binuclear alkali metal adducts have been done to establish their structure and bonding.

### Infrared spectra :

Infrared spectra were recorded in Nujol mull for the ligands and the complexes between 4000-650 cm<sup>-1</sup>. Selected absorption bands in different regions are given in Table I and Table 2.

The most important feature is that while there are important differences between the infrared spectrum of CuES and NiES and the binuclear complexes formed when they act as ligand, the spectra of the various complexes are essentially the same, being independent of whether a transition or non-transition metal is bound to the complex ligand. The effect of coordination obviously will be the greatest for bands associated with the phenolic oxygen, and progressively less for linkages further from the coordination sites.

Table 2 gives the C=O infrared bands of CuES and NiES together with the binuclear transition metal complexes derived from them. Table I gives the C=O infrared bands of binuclear alkali metal complexes derived from CuES and NiES. Comparing the two tables for C=O infrared bands, we arrive at the conclusion that shifting of infrared bands for

TABLE 1

Compounds	Colour	Decomp. Temp. (°C)	% N		% Cu/Ni		% Alkali metal		C=O frequency near 1530 cm <sup>-1</sup>	Magnetic moment at 27°
			Found	Calcd.	Found	Calcd.	Found	Calcd.		
CuES	Green	322							1532	1.90
CuES.Li1N2N	Light green	225	8.41	8.50	12.86	12.48	—	1.37	1538	2.1
CuES.Na1N2N	Yellowish green	228	8.61	8.00	12.40	12.10	4.30	4.38	1538	2.2
CuES.K1N2N	Yellowish green	240	8.00	7.77	11.68	11.74	7.35	7.21	1540	—
CuES.Na8HQ	Brown	250	8.19	8.45	12.39	12.78	4.65	4.65	—	1.91
CuES.K8HQ	Brown	255	7.86	8.19	12.62	12.39	7.63	7.60	1538	2.2
CuES.LiAnth	Violet	240	8.46	8.88	13.37	13.43	—	1.48	1545	1.9
CuES.NaAnth	Violet	242	8.26	8.59	13.41	12.99	4.76	4.70	1542	2.1
CuES.KSCN	Reddish violet	280	8.97	9.86	13.90	14.80	9.22	9.14	1555	1.9
CuES.LiCl	Pink	290	7.12	7.51	16.30	17.06	—	—	1538	1.9
CuES.NaBr	Reddish violet	290	5.88	6.47	14.46	14.68	5.35	5.31	1538	2.2
CuES.NaI	Pink	300	5.32	5.84	13.41	13.24	4.82	4.79	1555	1.9
NiES	Bright red	330							1536	Diamag.
NiES.Li1N2N	Yellow	255	8.38	8.33	11.89	11.65	—	—	1550	"
NiES.Na1N2N	Yellow	260	8.40	8.08	11.00	11.29	4.51	4.42	1550	"
NiES.K1N2N	Yellow	262	7.26	7.84	11.10	10.95	7.31	7.28	1550	"
NiES.NaAnth	Reddish brown	252	8.65	8.68	12.81	12.13	4.80	4.75	1540	1.62
NiES.NaBr	Yellow	280	6.71	6.54	14.30	13.70	5.36	5.38	1543	1.92
NiES.NaI	Yellow	275	5.21	5.89	12.86	12.36	4.95	4.84	1550	Diamag

1N2N = 1-Nitroso-2-naphthol

8HQ = 8-Hydroxyquinoline

Anth = Anthranilic acid

TABLE 2—POSITION OF THE INFRARED BAND NEAR 1530 cm<sup>-1</sup> (ASSIGNED TO C=O STRETCHING FREQUENCY) IN VARIOUS TRANSITION METAL COMPLEXES<sup>1-11</sup>

Compound	Frequency (cm <sup>-1</sup> )
X = CuES	1532
X.CuCl <sub>2</sub>	1533
X.ZnCl <sub>2</sub>	1551
X <sub>2</sub> .Cu(ClO <sub>4</sub> ) <sub>2</sub> .3H <sub>2</sub> O	1556
X <sub>2</sub> .Ni(ClO <sub>4</sub> ) <sub>2</sub> .3H <sub>2</sub> O	1554
X <sub>2</sub> .Mg(ClO <sub>4</sub> ) <sub>2</sub> .3H <sub>2</sub> O	1555
X <sub>2</sub> .Sr(ClO <sub>4</sub> ) <sub>2</sub> .1½H <sub>2</sub> O	1549
X <sub>2</sub> .Ba(ClO <sub>4</sub> ) <sub>2</sub>	1549
X <sub>2</sub> .AgClO <sub>4</sub> .2H <sub>2</sub> O	1544
Y = NiES	1536
Y.CoCl <sub>2</sub>	1556
Y <sub>2</sub> .Ni(ClO <sub>4</sub> ) <sub>2</sub> .3H <sub>2</sub> O	1555
Y <sub>2</sub> .Co(ClO <sub>4</sub> ) <sub>2</sub> .3H <sub>2</sub> O	1556
Y <sub>2</sub> .Fe(ClO <sub>4</sub> ) <sub>2</sub> .2H <sub>2</sub> O	1553
Z = (ZnES) <sub>2</sub>	1552, 1533
Z.ZnCl <sub>2</sub>	1554
Z.ZnCl <sub>2</sub> .H <sub>2</sub> O	1538

both transition metal complexes and alkali metal complexes are virtually the same.

In the present complexes and bridged binuclear complexes derived from bidentate salicylaldehyde complexes, 1530 cm<sup>-1</sup> band was consistently shifted up by 15-30 cm<sup>-1</sup> (Table 1 and Table 2), suggesting that this band may be due to the C=O stretching frequency in these compounds, rather than the C=N. This upward shift is due to the maintenance of a ring current arising out of electron delocalisation in the chelate ring.

Due to the delocalization of electrons towards the benzene ring, the ν(C=O) (phenolic) stretch is expected to occur at higher energy in comparison to the ν(C—O) (alcoholic) stretch<sup>12</sup>. It is, therefore, suggestive that the phenolic C—O link attained a

considerable amount of partial double bond character in these complexes. This is what is to be expected from the readiness with which these binuclear complexes were formed.

The above assignments were also found compatible with those made for the C=O links in metalacetylacetonates<sup>13</sup>. This has also been supported by the observation that *bis*-(N-methylsalicylaldehyde)zinc(II), which is known to be dimeric with two bridging and two non-bridging molecules per dimer<sup>14</sup>, has a doublet band in this region (1534 and 1553 cm<sup>-1</sup>).

#### Magnetic property :

Magnetic measurements were taken on Cahn-Faraday electronic balance at 27°. The results are recorded in Table 1.

The magnetic moment of CuES has been found to be 1.90 B.M., suggesting their square planar structure with coordination number 4. The binuclear alkali metal complexes have magnetic moment values in the range of 1.90–2.24 B.M., suggesting the same geometry of CuES in the alkali metal adducts.


NiES is diamagnetic, suggesting a square planar geometry with a coordination number 4 for Ni<sup>2+</sup> ion. The binuclear complex compounds of alkali metal salts with NiES are also diamagnetic in nature (except NiES.NaBr and NiES.Na-Anth) suggesting the same stereochemistry of NiES in adducts. The slight deviation from strict diamagnetism in the case of NiES.NaBr and NiES.Na-Anth is generally indicative of one of the types of so called 'anomalous behaviour'.

Had Na.8HQ been attached to NiES through nitrogen of 8HQ and nickel ion, the Ni<sup>2+</sup> ion would

have assumed 5-coordination stereochemistry. This would have resulted in the formation of a paramagnetic compound. On the other hand, if Na.8HQ had been attached by oxygen and nitrogen atoms of 8HQ (with Na<sup>+</sup> outside the coordination sphere) to the Ni<sup>2+</sup> ion, the compound would have been a six coordinated octahedral nickel(II) complex, showing paramagnetism with a  $\mu_{eff}$  value ~3.2 B.M.

The  $\mu_{eff}$  value for NiES.NaBr and NiES.Na-Anth are 1.92 B.M. and 1.62 B.M., respectively, which are very low compared to 3.4 B.M. We therefore conclude that coordination number of NiES has not been raised even in the case of NiES.NaBr or NiES.Na-Anth.

It is interesting to note that CuES formed complexes with all the three alkali metals (e.g. LiCl, NaBr, NaI and KSCN), while NiES formed only with sodium (i.e. NaBr and NaI). This may be due

to the size of the metal ions and  distance of the ligand.

#### Electronic spectra :

All electronic spectra were recorded on Varian Cary-14 spectrophotometer in Nujol mull.

As a result of the distorted octahedral or square coordination of Cu(II), a detailed interpretation of its electronic absorption spectrum is somewhat complicated. We have not therefore studied the electronic spectra of alkali metal complexes derived from CuES. Study of magnetic properties of the adducts derived from CuES is itself a sufficient evidence to establish the structure of these compounds.

The absorption band of medium intensity at 450 nm in electronic spectra of NiES suggests the square planar structure of Ni<sup>2+</sup> with the coordination number 4, due to which it is bright red in colour. The absorption band of binuclear alkali metal complexes derived from NiES is found in the range of 450 nm to 500 nm, suggesting the same square planar geometry of NiES with coordination number 4 in all the alkali metal adducts. As the coordination number of Ni<sup>2+</sup> in NiES remains the same in the adducts, it is clear that alkali metal salts are not attached through Ni<sup>2+</sup> ion. No absorption band has been found in the range of 600 nm to 1200 nm in the binuclear alkali metal complexes. The absence of these bands in electronic spectra further confirms that the coordination number of Ni<sup>2+</sup> in NiES binuclear alkali metal complex compounds have not been raised, but remains 4 with square planar geometry.

#### Structure and bonding :

In the present complexes, the complex ligands have two phenolic oxygens in the *cis* position and are forced to act as bidentate. The bonding between the salicylaldehyde complex M<sub>a</sub>ES and the alkali metal is most likely to occur by dative bonding via the two phenolic oxygen atoms of the ligand which has been supported by the ir spectra, magnetic properties and electronic spectral studies of the adducts. The structure and bonding of the newly prepared compounds, of the general formula [M<sub>a</sub>ES. M<sub>b</sub>L], may be what is shown in Fig. 1.




Fig 1. M<sub>a</sub> = Cu(II) and Ni(II).  
M<sub>b</sub>L = Alkali metal salts of 1-nitroso-2-naphthol, 8-hydroxyquinoline, anthranilic acid and LiCl, NaBr, NaI and KSCN

#### Acknowledgement

The authors thank the C.S.I.R., New Delhi, for financing the research project.

#### References

1. P. PIFFER, E. BREITH, E. LUBBE and T. THUMAKI, *Ann.*, 1933, 84, 503.
2. J. V. DUBSKY and A. SOKOL, *Chem. Abs.*, 1932, 26, 1538.
3. S. J. GRUBER, C. M. HARRIS and E. SINN, *Inorg. Nuclear Chem. Lett.*, 1967, 3, 465.
4. S. J. GRUBER, C. M. HARRIS and E. SINN, *Inorg. Chem.*, 1968, 7, 268.
5. S. J. GRUBER, C. M. HARRIS and E. SINN, *Inorg. Nuclear Chem. Lett.*, 1968, 4, 107.
6. G. H. W. MILBURN, M. R. TRUTER and B. L. VICKERY, *Chem. Commun.*, 1968, 1188.
7. B. DAS SHARMA and J. C. BAILER, JR., *J. Amer. Chem. Soc.*, 1955, 77, 5476.
- 8a. A. SYAMAL and O. P. SINGHAL, *Trans. Met. Chem.*, 1979, 4, 179.
- 8b. G. E. BATLFY and D. P. GRADDOM, *Aust. J. Chem.*, 1967, 20, 877.
9. P. L. ORIOLI, M. DIVAIRA and L. SACCONI, *Inorg. Chem.*, 1966, 5, 400.
10. K. UENO and A. E. MARTELL, *J. Amer. Chem. Soc.*, 1956, 60, 1270.
11. P. L. TEYESSIE and J. J. CHARETTE, *Spectrochim. Acta*, 1963, 19, 1407.

# Application of Coordination Compounds of Silicon and Copper in Fiber and Fiber Reinforced Plastic Materials

O. P. BAHL, T. L. DHAMI, R. L. SETH\*, L. M. MANOCHA and R. B. MATHUR

Carbon Technology Unit, National Physical Laboratory, New Delhi-110 012

Some of the important characteristics of fiber reinforced plastic materials which make them significant as high specific strength, stiff, corrosion and fatigue resistant materials, have been described. Use of coordination compounds of copper and silicon has been particularly mentioned in view of their marked effect in increasing the strength of fibers in the case of carbon fibers and interfacial bonding between fiber and matrix for glass fiber reinforced plastics respectively. The coordination compounds of monovalent copper such as dichloro and diacetato and of silicon mainly aminosiloxanes help in cyclisation reaction resulting in considerable increase in the mechanical properties of carbon fibers formed which is ultimately reflected in the composite properties. The silicon coupling compounds having organic functional groups coordinated to silicon give, on treatment with a glass fiber, a relatively high surface energy which gives good wetting as well as bonding to the resinous matrix.

**F**IBER reinforced plastics<sup>1-5</sup> are finding increasing use as structural engineering materials because of their high strength and stiffness properties varying over a broad range. Carbon fibers and glass fibers have been extensively used in reinforced plastics for use in industrial applications such as aerospace, chemical, mechanical, marine, sports, agricultural and medical. The glass fiber reinforced composites are comparatively cheaper compared to carbon fiber reinforced plastics (CFRP) but have low specific stiffness. On the other hand CFRP have high specific stiffness which is maintained even at higher temperatures<sup>2-6</sup>. During the past two decades, tremendous efforts have been made to develop stiff reinforcing fibers and FRP materials<sup>7-10</sup>. New methods and techniques have been developed to make high strength high modulus carbon fibers. Newer compositions of thermosetting resins such as epoxy, phenolic and polyester and thermoplastic resins such as some polyester, polyethylene, polypropylene, nylon 6/6, etc have been made to suit specific requirements of FRP industry.

Carbon fiber is a newer form of carbon obtained by pyrolysing different organic fibers which are polymeric in character. Most extensively used precursors for carbon fiber preparation are polyacrylonitrile (PAN), jute, rayon, pitch etc<sup>10</sup>. The characteristics of carbon fibers produced depend on the nature of precursor and processing conditions. During the past decade considerable research and development activity have been going on in NPL for producing carbon fibers from different precursors.


Carbon fiber manufacture involves two main steps<sup>11</sup>:

1. Heat treatment in air or oxygen upto 300° to stabilize the precursor and convert the open chain structure of PAN to closed one.

2. Pyrolysis to 1000° in an inert atmosphere and heat treatment to 3000° in inert atmosphere, if desired.

The most critical step in the manufacture of carbon fiber is the oxidation step which controls the overall properties of the carbon fiber formed. For many years constant efforts are being made to control this step in order to cut short the treatment time and to save energy along with improvement in the mechanical properties of the ultimate carbon fibers<sup>3</sup>. This can be brought about by incorporation of metallic additives in the form of coordination compounds such as dichloro or diacetato complexes of monovalent copper and aminosiloxane<sup>1,3,14</sup>.


The oxidation step is done to produce thermally stable fibers so that they may not fuse when subjected to higher temperature. When pure PAN fiber is thermally treated in an inert atmosphere, the rearrangement of nitrile groups takes place at 200 to 300° giving a partially imperfect ladder type of cyclised structure represented by:



where *m* is generally in the range 0-2 and *n* in the range 0-5. This ladder type of structure is formed by free radical ionic mechanism. The free radicals are formed by the decomposition of defect structures in the precursor polymer. The amino radicals propagate and attack the next nitrile group or may abstract



a hydrogen atom terminating that particular sequence. Cyclisation takes place as indicated below :




resin has to be modified for effecting better adhesion and bonding. The study of adhesion is related to several known effects such as :

This rearrangement or oligomerization of nitrile groups can be initiated at a lower temperature and the cyclization reaction can be accelerated by incorporation of reagents such as organic acids, inorganic acids and bases and metallic salts.

These reagents broadly (i) lower the temperature of initiation of cyclisation reaction, (ii) convert the sharp and intense exotherm observed in case of pure PAN into broader one and the  $\Delta T$  is reduced to a much lower extent<sup>14</sup>, (iii) the reagents provide a large number of initiation centers for cyclisation reaction thereby the cyclisation takes place in a much shorter time and the extent of cyclisation is increased to a much larger value.

The cyclisation in presence of Lewis acids such as dichloro and diaceto monovalent copper ions takes place by ionic mechanism. The mechanism is shown below :



After the initiation, the reaction continues along the chain by stepwise ionic mechanism to produce ladder structure containing conjugated  $-C=N-$  sequences. The fact that Cu is found in carbon fibers heated upto 1000° indicates that Cu is an integral part of carbon fiber.


By use of dichloro Cu complex in the processing of carbon from PAN, the first step treatment time has been reduced to one third of the normal treatment time without the use of coordination compounds. Moreover, it has been found that the tensile strength increases by 30% while the Young's Modulus by 50%<sup>15</sup>. This clearly indicates the effective role of copper complex in improving mechanical properties of carbon fibers.

To make use of the excellent mechanical properties of the fibers, they have to be incorporated into a suitable matrix system. The interface between the filler such as carbon fiber or glass fiber and the

1. Surface chemistry and physics of the components ;
2. The action of water and other potential weak bonding layers at the interface ;
3. The morphology of the matrix and the interface and
4. Mechanical requirements of the interface to allow distribution of shrinkages at areas of stress concentration


In case of carbon fibers, oxide groups such as carbonyl, carboxyl, hydroxyl, etc. are incorporated on the fiber surface by surface treatment<sup>16,17</sup> of the fibers, dry as well as wet. It involves treatment with oxygen, ozone, nitric acid, sodium hydroxide, sulphuric acid/potassium permanganate and different electrolytes such as hypochlorous acid, sodium hydroxide, etc.

In glass reinforced plastics, marked improvement in properties is imparted by traces of appropriate reactive silanes at the interface. This indicates that the silane coupling agents<sup>18-22</sup> have an important role which improves the adhesion. The silane coupling agents are of the general structure  $X_3Si(CH_2)_n\gamma$  where  $n$  is 0-3,  $X$  is a hydrolysable group on silicon and  $\gamma$  is an organo functional group selected for compatibility with the given resin matrix. Most of the silane coupling agents are applied to glass fiber surface from aqueous solutions. The hydrolysable groups are therefore essential for generating intermediate silanols.




The compositions of silane coupling agents in dilute solutions depend on the organo functional groups and the pH of the solution. The silanes hydrolyse to give triols and then condense slowly to

oligomeric siloxanols.



Amino organo functional silane coupling agents show unique solution properties when nitrogen is on the 3-carbon atom. Since it is well known that the cyclic five or six membered chelate ring have extra stability, the low molecular weight siloxanes with internal cyclic zwitter ion structures are formed in aqueous solution of three amino substituted organic silanols.



Therefore, all commercial amino functional silane coupling agents have the nitrogen atom on the 3-carbon atom.

The silane coupling agents are not generally deposited on the fiber surface as simple oriented mono molecular films, but as multilayers with variable orientation depending upon condition of deposition<sup>10</sup>. A major portion of the deposited film is removed readily by water or organic solvents, but a small residue of the coupling agent is retained tenaciously by the surface which is effective in improving composite properties. Silanols, alkoxy silanes or chloro silanes applied to glass fiber under mild conditions are adsorbed physically through hydrogen bonding with surface silanol group. Under more strenuous conditions of temperature or catalyst the silanes bond chemically with the surface through siloxane linkages. These compounds are stable to air and water vapour. Another method of bonding chemically a coupling agent to the glass surface is to react with a difunctional Grignard reagent to give a firmly bonded organo functional group. Use of a flourinated glass surface is also known.

The chemical mobility of coupling agents attached to glass surface through hydrolysable bonds appears to be beneficial to composite properties. There is no correlation between polarity of silane or wettability of silane treated glass and the effectiveness of the silane coupling agent. For example, glass treated with chloropropyl silane coupling agent has a relatively high surface energy and is readily wetted by resins. Such treatment is ineffective with polyesters and phenolics but is quite effective with epoxides where chemical reaction is possible between the chloropropyl groups and the epoxy curing agent.

Wetting studies on silane treated glass are futile in arriving at the primary mechanism of adhesion through silane coupling agents since the interface

between coupling agent and resin disappears preparation of composites. Better wetting allow complete displacement of air from the surface and reduce the number of voids in composite. The amount of silane coupling required on a glass surface to impart good mechanical performance to a glass resin composite is small to be measured by analytical means. Use of radio active tracers has been made and has been confirmed that the amount required proper silane to function as coupling agent is less than the amount required of the silane to form a monomolecular layer on the glass surface. Silane coupling agents are equally effective when added in integral blends in resins. The silane, by coming in contact with the polymer, modifies the morphology of the interface to improve stress transfer at the interface and resistance to water. This almost always involves a tightening up of the polymer structure through increased crosslinks and rigidity. Therefore, the silane should have maximum reactivity with the polymer.

The silane coupling compounds can be prepared by a number of methods involving chemical reaction of silicon containing compounds with mineral acid and organic functional groups. Trichloro tetrachloro silanes have been extensively used as starting material for interaction with the coupling compounds for introducing organo functional groups in the structure. The conditions of reaction depend on the type of coupling agent required. Trichloro and tetrachloro silane have been prepared in NPL by interaction of ferro silane with mineral acid and then separating the silane by methods of fractional distillation. The products and purification techniques have been standard and the silanes have been prepared to the purity 99.9%. The silanes were treated with alcoholic compounds of general formula  $\text{Si}(\text{OR})_3\text{SiH}(\text{OR})_3$  were synthesised. The compounds are thermally stable. It is planned to prepare a series of organo-silicon derivatives from silane for use as coupling agents.

#### References

1. "Handbook of Fiber Glass and Advanced Composites", (Ed) G. LUBIN, Van Nostrand Reinhold Company, New York, 1969
2. JOHN DELMONTE, "Technology of Carbon and Carbon Fiber Composites", Van Nostrand Reinhold Company, New York, 1981.
3. R. LUCAS, "ICCM 3, 3rd International Conference on Composite Materials", Paris, 1980, Vol. 2, p. 1233.
4. L. M. MANOCHA, "ICCM 3, 3rd International Conference on Composite Materials", Paris, 1980, Vol. 2, p. 1280.
5. R. KITCHING and C. J. KIRK, "ICCM 3, 3rd International Conference on Composite Materials", Paris, 1980, Vol. 2, p. 1280.
6. E. FITZER and M. HEYM, *High Temperature Pressure*, 1978, 10, 29.
7. A. SHINDO, Rep. Govt. Ind. Res. Inst., Osaka (No. 317, 1961).
8. W. WATT, *Carbon*, 1972, 10, 121.
9. O. P. BAHL and R. B. MATHUR, *Fib. Sci. Tech.*, 12, 31.
10. O. P. BAHL, L. M. MANOCHA, G. C. JAIN, S. S. and G. BHATIA, *J. Sci. Ind. Res.*, 1979, 38, 53

BAHL, DHAMI, SETH, MANOCHA & MATHUR : APPLICATION OF COORDINATION COMPOUNDS ETC.

11. A. J. CLARKE and J. E. BAILEY, *Proc. Int. Conf. Plastic Inst.*, 1974, p. 12.
12. O. P. BAHL, R. B. MATHUR and D. KUNDRA, *Fib. Sci. Tech.*, 1980, 13, 155.
13. Jap. Exlan. Co. Ltd., *British Patent*, 1499085, 25 Jan., 1978.
14. N. GRASSIE and R. MCGUCHAN, *Europ. Polym. J.*, 1971, 7, 1503.
15. O. P. BAHL, L. M. MANOCHA, T. L. DHAMI and R. B. MATHUR, Presented at the International Symposium on Carbon, 1982, Toyohashi University of Technology, Japan.
16. J. B. DONNET and P. EHRBURGER, *Carbon*, 1977, 15, 143.
17. E. FITZER and R. WEISS, *Proc. Uses of Carbon Reinforced Plastics*, by Verein Deutscher Ingenieure, VDI Verlag, GmbH, Dusseldorf, 1981, p. 45.
18. J. L. PERRY and D. F. ADAMS, *Carbon*, 1976, 14, 61.
19. D. F. ADAMS, *Mater. Sci. Engg.*, 1975, 17, 139.
20. W. A. ZISMAN, *Ind. Eng. Chem. Prod. Res. Develop.*, 1969, 8, 98.
21. E. P. PLUEDDEMANN, *Appl. Polym. Symp. Adhesives*, Wiley Interscience, New York, 1972, p. 75.
22. E. P. PLUEDDEMANN, "Interfaces in Polymer Matrix Composites", Academic Press, 1974, Vol 6.
23. W. D. BOSCON and J. B. ROMANS, *Ind. Eng. Chem. Prod. Res. Develop.*, 1968, 7, 172.

# Mössbauer Spectra of Copper Nickel Ferrites

H. V. KIRAN, A. S. BOMMANAVAR\*, D. K. CHAKRABARTY\*\* and A. B. BISWAS\*\*\*

Solid State Laboratory, Chemistry Department, Indian Institute of Technology, Powai, Bombay-400 076

Mössbauer spectra of the compositions  $\text{Cu}_{1-x}\text{Ni}_x\text{Fe}_2\text{O}_4$  ( $0 \leq x \leq 1$ ) have been studied. For  $x \leq 0.2$ , the compounds are tetragonal and the rest are cubic spinels. Cation distribution obtained from the split lines of the Mössbauer spectra does not agree with that obtained from magnetisation data. The spectra seem to be complicated due to the presence of more than one hyperfine field at the B site  $\text{Fe}^{3+}$  owing to the distorting effect of the  $\text{Cu}^{2+}$  ion on the A sites. This leads to non-Lorentzian line shapes and excludes straight-forward calculation of cation distribution from relative areas under resonances.

**M**AGNETIC properties of spinel ferrites are strongly dependent on the nature of the cations and their distribution between the tetrahedral (A) and octahedral (B) sites in the cubic close packed oxygen lattice.  $\text{CuFe}_2\text{O}_4$  is particularly interesting in this respect because the distribution of  $\text{Cu}^{2+}$  ions between the nonequivalent sites is temperature sensitive. Moreover, the presence of  $\text{Cu}^{2+}$  ions leads to severe Jahn-Teller distortion making the nonequivalent sites more distinct than in other spinels<sup>1</sup>.

Nickel ferrite is an inverse spinel. It is interesting to see how the distribution of  $\text{Cu}^{2+}$  ions in the A and B sites are affected in the presence of  $\text{Ni}^{2+}$  ion which has a strong octahedral site preference. This prompted us to determine the cation distribution in the  $\text{Cu}_{1-x}\text{Ni}_x\text{Fe}_2\text{O}_4$  system ( $0 < x < 1$ ) by magnetisation measurements (Kiran *et al.*<sup>2</sup>). Several reports have appeared in the literature on the Mössbauer spectra of  $\text{CuFe}_2\text{O}_4$  and  $\text{NiFe}_2\text{O}_4$  (Evans and Hafner<sup>3</sup>, Yamadaya *et al.*<sup>4</sup>, Evans *et al.*<sup>5</sup>, Sawatzky *et al.*<sup>6</sup>, Morel<sup>7</sup>), but no report has been made on the Mössbauer study of the mixed ferrite system  $\text{Cu}_{1-x}\text{Ni}_x\text{Fe}_2\text{O}_4$ . This is being reported in this paper.

## Experimental

The compounds were prepared by mixing appropriate quantities of  $\text{CuO}$ ,  $\text{NiO}$  and  $\alpha\text{-Fe}_2\text{O}_3$  (all AR grade) and firing at 1320 K for 24 hr. The samples were then cooled slowly to 1020 K, annealed at this temperature for 48 hr and cooled to room temperature at 60°/hr. All the samples were characterised as monophasic solid solutions by X-ray diffraction (XRD).

Mössbauer spectra were recorded on a multi-channel analyser (MCA 38A of ECIL) in the constant acceleration mode. The source used was  $^{57}\text{Co}$  in rhodium matrix. The spectrometer was checked for velocity calibration by comparing the line positions of various standard absorbers (SS 310,

pure iron foil and  $\alpha\text{-Fe}_2\text{O}_3$ ). The spectra were analysed using a computer program which performs a least mean square fit of the Lorentzian lines to the experimental points.




Fig. 1. Mössbauer spectra of the system  $\text{Cu}_{1-x}\text{Ni}_x\text{Fe}_2\text{O}_4$ .

\*Physics Department, IIT, Bombay.

\*\*Author for correspondence.

\*\*\*since deceased.

TABLE 1—MÖSSBAUER SPECTRAL PARAMETERS<sup>†</sup>  
OF  $\text{Cu}_{1-x}\text{Ni}_x\text{Fe}_2\text{O}_4$ 

Composition x	Lattice parameter a (Å)		Hyperfine field $H_{\text{eff}} \pm 5\text{kOe}$		Isomer shifts IS (mm/sec)		Quadrupole splitting Qs (mm/sec)		Intensity ratio $I_B/I_A$	$[\text{Fe}^{3+}]_B/[\text{Fe}^{3+}]_A$ <sup>†</sup>
			A	B	A	B	A	B		
0.0	a=8.268 c=8.607	T	492			0.60		0.10	—	1.103
0.1	a=8.270 c=8.584	T	492			0.54		0.05	—	1.059
0.2	a=8.340 c=8.468	T	487			0.30		0.10	—	1.111
0.3	8.362	C	482			0.38		0.13	—	1.125
0.4	8.353		484	498	0.54	0.67	0.10	0.21	0.860	1.134
0.5	8.356		484	498	0.55	0.66	0.08	0.20	0.930	1.105
0.6	8.344		484	502	0.38	0.52	0.04	0.19	0.877	1.083
0.7	8.342		491	509	0.55	0.69	0.10	0.14	0.743	1.057
0.8	8.333		488	506	0.41	0.55	0.06	0.20	0.792	1.030
0.9	8.331		491	511	0.54	0.71	0.06	0.22	0.967	1.010
1.0	8.320		491	510	0.33	0.48	0.08	0.23	1.010	1.000


†—all values at 300 K, T—Tetragonal, C—Cubic; †—from magnetisation data.

## Results and Discussion

XRD patterns showed all the compositions as monophasic spinels. The compounds with  $x=0.0-0.3$  were tetragonal and all other compositions were found to be cubic spinels, with lattice parameter decreasing linearly with increasing  $x$ .

Mössbauer spectra are given in Fig. 1 and the relevant parameters in Table 1. The spectra for the compositions  $x=0.0-0.3$  are of simple six-line type. Although the lines are broad, they fitted well into six Lorentzians. The large line width seems to suggest that the spectra may be due to superposition of two six-line patterns whose envelope is also Lorentzians. For  $0.4 \leq x \leq 1$ , the spectra no longer correspond to a single six-line pattern, the extreme line (in some cases, the last two or all the lines) on the positive velocity are split. This is due to the superposition of two six-line patterns arising from  $\text{Fe}^{3+}$  ions at the two nonequivalent sites in the spinel structure. This was first proposed by Evans *et al.*<sup>2</sup> for  $\text{CuFe}_2\text{O}_4$  who assigned the pattern with larger hyperfine splitting to the B site  $\text{Fe}^{3+}$  and that with the smaller hyperfine split to  $\text{Fe}^{3+}$  at A sites. The same assignment may be accepted in the present case in view of the fact that isomer shift (IS) and quadrupole splitting (QS) of the latter are smaller. It is possible to resolve the Lorentzians corresponding to  $\text{Fe}^{3+}$  at A and B sites and compute the relative concentrations of  $\text{Fe}^{3+}$  in the two sites. The ratios of the areas under resonance  $I_B/I_A$  are given in Table 1 along with the ratio  $[\text{Fe}^{3+}]_B/[\text{Fe}^{3+}]_A$  obtained from magnetisation values (Kuan *et al.*<sup>3</sup>). It may be observed that the agreement between the two ratios is poor except for the compositions  $x=0.9$  and  $1.0$ . Such discrepancy has also been reported by Evans and Hafner<sup>1</sup> who observed that for  $\text{CuFe}_2\text{O}_4$  the intensity ratio was 0.6 and 0.7 for single crystal and ceramic samples, respectively, whereas expected cation ratio was between 1.22-1.33. Since the difference in recoilless fraction of  $\text{Fe}^{3+}$  at A and B sites is less than 10%, such large differences are unexpected. Since the assignment

of the A and B sites appears to be correct, we along with Evans and Hafner<sup>1</sup> are forced to conclude that the discrepancy in the  $I_B/I_A$  values are due to anomalous line shapes brought about by different QS, IS and magnetic hyperfine fields ( $H_{\text{eff}}$ ) at apparently equivalent sites. Local symmetry at the  $\text{Fe}^{3+}$  sites may be different depending upon the type and number of neighbouring cations. Distortions at these sites may be particularly important in copper containing ferrites because  $\text{Cu}^{2+}$  ions distort their environment severely. Symmetry of the iron site will then depend on the number of neighbouring  $\text{Cu}^{2+}$  ions which are randomly distributed. Overall absorption lines may become non-Lorentzian in shape or may even split into a number of lines.<sup>1</sup> The large line width may be

Fig. 2. Variation of hyperfine field ( $H_{\text{eff}}$ ) with  $x$  in the system  $\text{Cu}_{1-x}\text{Ni}_x\text{Fe}_2\text{O}_4$ .

suggestive of the presence of B site  $\text{Fe}^{3+}$  with different symmetry, although the overall spectra of B site iron fits into a set of Lorentzians.

The isomer shifts are all in the range 0.3-0.7 mm/sec with respect to  $^{57}\text{Co}/\text{Fe}$  and this corresponds to iron in the trivalent state only. There is no regular variation of IS as well as of QS with composition.

The variation of the hyperfine fields at the A and B sites ( $H_{\text{eff}}$  average in case of  $0 < x < 0.3$ ) with composition is given in Fig. 2. The hyperfine fields at both the sites increase with  $x$ . The relatively higher value of  $H_{\text{eff}}(\text{B})$  may be understood as follows. The average field for all the ions in a given sublattice is proportional to the average magnetisation of that sublattice. In an inverse ferrite, an  $\text{Fe}^{3+}$  ion at the B site will have all its nearest neighbouring A sites occupied by  $\text{Fe}^{3+}$  ions whereas the A site  $\text{Fe}^{3+}$  ion will have inter-sublattice bonds with  $\text{Cu}^{2+}$ ,  $\text{Fe}^{3+}$  and  $\text{Ni}^{2+}$ . Since  $\text{Fe}^{2+}-\text{O}^{2-}-\text{Fe}^{3+}$  is the strongest superexchange interaction, the  $H_{\text{eff}}$  of an  $\text{Fe}^{3+}$  ion surrounded in part by cations other than  $\text{Fe}^{3+}$  will be smaller than when surrounded by all  $\text{Fe}^{3+}$  ions only. The

increase in  $H_{\text{eff}}$  at A sites as  $x$  increases could be due to the fact that the interaction  $\text{Fe}^{3+}-\text{O}^{2-}-\text{Ni}^{2+}$  is stronger than  $\text{Fe}^{3+}-\text{O}^{2-}-\text{Cu}^{2+}$ . The increase in  $H_{\text{eff}}(\text{B})$  with  $x$  is due to the fact that as  $x$  increases from 0.4 onwards, the fraction of A sites occupied by the  $\text{Fe}^{3+}$  ions also increases as shown by the magnetisation data, and hence the number of  $\text{Cu}^{2+}$  ions on A sites decreases in these compositions<sup>6</sup>.

#### References

1. B. J. EVANS and S. S. HAFNER, *J. Phys. Chem. Solids*, 1967, 29, 1572.
2. T. YAMADAYA, T. MITSUI and T. OKADA, *J. Phys. Soc. Japan*, 1962, 17, 1897.
3. B. J. EVANS, S. S. HAFNER and G. M. KLAVIUS, *Phys. Lett.*, 1966, 23, 24.
4. G. A. SAWATZKY, F. VAN DER WOUDE and A. H. MORRISH, *Phys. Rev.*, 1969, 187, 747.
5. J. P. MOREL, *J. Phys. Chem. Solids*, 1967, 28, 629.
6. H. V. KIRAN, A. L. SASHI MOHAN, D. K. CHAKRABARTY and A. B. BISWAS, *Phys. Stat. Sol.*, 1981, 66A, 743.

# Cyclic Voltammetry of Thallium(I) in Different Supporting Electrolytes

R S SINDAL, K C K. MATHUR and R C KAPOOR

Department of Chemistry, University of Jodhpur, Jodhpur-342 001

The reduction of  $Tl(I)$  has been made in presence of various sodium salts as supporting electrolytes at a hanging mercury drop electrode (HMDE). The correlation of cathodic and anodic peak currents and the difference in cathodic and anodic peak potentials with the voltage scan rates indicate that the reduction of  $Tl(I)$  is not reversible.

WITH the help of the theory of stationary electrode voltammetry proposed by Nicholson and Shain<sup>1</sup>, it is possible to develop diagnostic criteria by correlating kinetic and experimental parameters so that unknown system can be characterized by studying the variations of peak current, half-peak potential, or ratio of anodic to cathodic peak currents as a function of rate of voltage scan.

For a reversible system the separation of peak anodic and cathodic potentials of the couple<sup>2</sup> is  $\frac{58}{n}$  mv and to a good approximation the formal electrode potential can be computed by averaging the two peak potentials. However, the peak to peak distance is larger for an irreversible system<sup>3</sup>.

The effect of a chemical reaction on the voltammetric wave will depend on its rate, as compared with the time required to perform the experiment. Taking irreversible succeeding chemical reaction as an example, if a very rapid reaction is studied with very slow scan rates, the stationary electrode voltammogram will reflect the characteristics of the chemical step almost entirely. On the other hand, if the rate of voltage scan is rapid compared to the rate of the reaction, the curves are identical to those for the corresponding uncomplicated charge transfer reactions. Hence in every kinetic case, the ratio of the rate constant to the rate of voltage scan appears in the kinetic parameter. This, in turn, makes it possible to use these relations to define diagnostic criteria for the investigation of unknown systems.

The relationship between scan rate ( $V$ ) and  $I_{pa}/I_{pc}$  or  $I_p/V^{1/2}$  is often used as a diagnostic criteria for identifying the nature of the electrode process. Here  $I_{pa}$  and  $I_{pc}$  are anodic and cathodic peak currents in a cyclic voltammogram.

The authors have used these criteria to investigate the reduction of  $Tl(I)$  in different supporting electrolytes.

## Experimental

Cyclic voltammogram CV-1, (Bioanalytical System Inc., U S A ), in combination with an X-Y recorder (Digilog) was used to record the cyclic voltammograms.

A special cell having three-electrode assembly was used. Hanging mercury drop electrode (HMDE)<sup>4-7</sup> was used as the working electrode while a platinum spiral was employed as the auxiliary electrode. All potentials were measured against a saturated calomel electrode (SCE) which was connected to the test solution through a sodium nitrate bridge. All experiments were carried out at  $35 \pm 0.1^\circ$  by immersing the cell and the reference electrode in a cryostat, type MK-70 (Web Mlv Prüfgerate Werk, GDR).

Reagent grade chemicals were used in all the experiments. The concentration of  $Tl(I)$  ion was kept at  $5 \times 10^{-4} M$ , while the supporting electrolytes used were  $NaNO_3$ ,  $NaClO_4$ ,  $NaCl$  and  $Na_2SO_4$ .



Cyclic voltammograms were taken at different scan rates varying from 0.02 to 0.1 volt/sec. The

TABLE 1—POTENTIAL VALUES OF  $Tl^+$  IN DIFFERENT SUPPORTING ELECTROLYTES (IN VOLTS vs SCE)

Sl. No.	Scan rate Volt/sec	0.1 M $NaNO_3$			0.1 M $NaCl$			0.1 M $NaClO_4$			0.1 M $Na_2SO_4$		
		$E_{pa}$	$E_{pc}$	$\Delta E_p$	$E_{pa}$	$E_{pc}$	$\Delta E_p$	$E_{pa}$	$E_{pc}$	$\Delta E_p$	$E_{pa}$	$E_{pc}$	$\Delta E_p$
1.	0.02	-0.47	-0.55	0.08	-0.48	-0.56	0.08	-0.47	-0.55	0.08	-0.49	-0.57	0.08
2.	0.03	-0.47	-0.55	0.08	-0.48	-0.55	0.07	-0.47	-0.55	0.08	-0.49	-0.57	0.08
3.	0.04	-0.47	-0.55	0.08	-0.47	-0.55	0.08	-0.47	-0.55	0.08	-0.49	-0.57	0.08
4.	0.05	-0.46	-0.55	0.09	-0.47	-0.55	0.08	-0.47	-0.54	0.07	-0.49	-0.57	0.08
5.	0.06	-0.46	-0.55	0.09	-0.47	-0.55	0.08	-0.47	-0.55	0.08	-0.48	-0.56	0.08
6.	0.07	-0.46	-0.55	0.09	-0.47	-0.55	0.08	-0.46	-0.54	0.08	-0.49	-0.57	0.08
7.	0.08	-0.46	-0.56	0.10	-0.47	-0.54	0.08	-0.47	-0.55	0.08	-0.49	-0.57	0.08
8.	0.09	-0.46	-0.56	0.10	-0.47	-0.55	0.08	-0.46	-0.55	0.09	-0.48	-0.56	0.08
9.	0.10	-0.45	-0.55	0.10	-0.46	-0.54	0.08	-0.46	-0.54	0.08	-0.49	-0.57	0.08

TABLE 2—VALUES OF CATHODIC AND ANODIC PEAK CURRENTS IN MICROAMPERES

Sl. No.	Scan rate Volts/sec.	0.1 M NaNO <sub>3</sub>			0.1 M NaCl			0.1 M NaClO <sub>4</sub>			0.1 M Na <sub>2</sub> SO <sub>4</sub>		
		<i>I</i> <sub>pa</sub>	<i>I</i> <sub>pc</sub>	<i>I</i> <sub>pa</sub> / <i>I</i> <sub>pc</sub>	<i>I</i> <sub>pa</sub>	<i>I</i> <sub>pc</sub>	<i>I</i> <sub>pa</sub> / <i>I</i> <sub>pc</sub>	<i>I</i> <sub>pa</sub>	<i>I</i> <sub>pc</sub>	<i>I</i> <sub>pa</sub> / <i>I</i> <sub>pc</sub>	<i>I</i> <sub>pa</sub>	<i>I</i> <sub>pc</sub>	<i>I</i> <sub>pa</sub> / <i>I</i> <sub>pc</sub>
1.	0.02	5.05	2.45	2.06	4.75	2.0	2.38	4.50	1.85	2.43	2.6	1.5	1.73
2.	0.03	5.6	3.4	1.64	5.0	2.8	1.79	4.7	2.65	1.74	3.05	1.9	1.6
3.	0.04	6.05	3.95	1.53	5.3	3.25	1.63	5.05	2.8	1.8	3.3	2.2	1.5
4.	0.05	6.0	4.05	1.48	5.45	3.45	1.58	5.05	3.3	1.53	3.5	2.5	1.4
5.	0.06	6.4	4.3	1.49	5.5	3.7	1.49	5.25	3.65	1.44	3.35	2.65	1.26
6.	0.07	6.75	4.95	1.57	5.75	4.05	1.42	5.65	4.0	1.41	3.85	2.8	1.37
7.	0.08	6.85	4.5	1.52	5.55	3.85	1.44	5.3	3.85	1.38	4.0	3.0	1.33
8.	0.09	7.5	5.4	1.5	5.90	4.35	1.36	5.8	4.35	1.33	4.1	3.25	1.26
9.	0.10	8.05	5.75	1.4	6.1	4.5	1.36	5.8	4.3	1.35	4.2	3.4	1.24

Fig. 1. Plot of  $I_{pa}/I_{pc}$  vs scan rate (V) in different supporting electrolytes: (I) 0.1M NaClO<sub>4</sub>; (II) 0.1M NaCl; (III) 0.1M NaNO<sub>3</sub>; (IV) 0.1M Na<sub>2</sub>SO<sub>4</sub>.Fig. 2. Plot of  $I_{pa}/V^{1/2}$  vs scan rate (V) in different supporting electrolytes: (I) 0.1M NaNO<sub>3</sub>; (II) 0.1M NaCl; (III) 0.1M NaClO<sub>4</sub>; (IV) 0.1M Na<sub>2</sub>SO<sub>4</sub>.

starting and returning potentials were  $-0.2$  and  $-1.0$  volt, respectively.

### Results and Discussion

The anodic and cathodic peak potentials ( $E_{pa}$  and  $E_{pc}$ ) and peak potential differences ( $\Delta E_p$ ) were calculated from the cyclic voltammograms obtained in different supporting electrolytes (Table 1).

One of the criteria for reversibility is that  $\Delta E_p = \frac{58}{n}$  mv. It is clear from Table 1 that the reduction of Tl(I) is not reversible in any of the supporting electrolytes, since  $\Delta E_p \approx 0.08$  volt in all the cases. It is further noted that  $\Delta E_p$  remains unchanged on increasing the scan rate. However, the values of  $E_{pa}$  and  $E_{pc}$  are more negative in 0.1M Na<sub>2</sub>SO<sub>4</sub> supporting electrolyte.



The cathodic and anodic peak currents were measured at different scan rates for various supporting electrolytes. Results are given in Table 2 in which the values of  $I_{pa}/I_{po}$  are also recorded. It is seen that the ratio  $I_{pa}/I_{po}$  is not unity in any case. On increasing the scan rate, the ratio decreases regularly due to the fact that the cathodic peak current is enhanced at high scan rates. The plot of  $I_{pa}/I_{po}$  vs  $V$  is shown in Fig. 1

for all the supporting electrolytes are given in Fig. 2. The plots yield almost horizontal lines.

All the above mentioned data indicate conclusively that the reduction of  $Tl(I)$  in the supporting electrolytes employed is not reversible at a mercury electrode. This conclusion appears contradictory to the accepted notion that the polarographic reduction of  $Tl(I)$  is reversible<sup>8</sup>. This clearly shows that the criteria of reversibility based on logarithmic plot analysis of polarographic curves is not reliable.

TABLE 3

Sl No	Scan rate Volts/sec V	0.1 M NaNO <sub>3</sub>	0.1 M NaCl	0.1 M NaClO <sub>4</sub>	0.1 M Na <sub>2</sub> SO <sub>4</sub>
		$I_{pa}/V^{1/2}$	$I_{po}/V^{1/2}$	$I_{pa}/V^{1/2}$	$I_{po}/V^{1/2}$
1.	0.02	17.4	14.2	13.1	10.6
2.	0.03	19.7	16.2	15.3	11.0
3.	0.04	19.8	16.3	14.0	11.0
4.	0.05	18.1	15.4	14.7	11.2
5.	0.06	17.6	15.1	14.9	10.8
6.	0.07	18.7	15.3	15.1	10.6
7.	0.08	15.9	13.6	18.7	10.6
8.	0.09	18.0	14.5	19.3	10.8
9.	0.10	18.2	14.2	18.4	10.8

The ratios of cathodic peak current and square root of scan rate, for different supporting electrolytes, are given in Table 3. The plots of  $I_{pa}/V^{1/2}$  vs  $V$

## References

1. R. S. NICHOLSON and I. SHAIN, *Analytical Chemistry*, 1964, 36, 706
2. R. N. ADAMS, "Electrochemistry at Solid Electrodes", Marcel Dekker, New York, N. Y., 1969, Chap. 5.
3. R. S. NICHOLSON, *Analytical Chemistry*, 1965, 37, 1351.
4. W. KEMULA and Z. KUBLIK, *Nature*, 1958, 182, 793.
5. W. KEMULA and Z. KUBLIK, *Roczniki Chem.*, 1958, 32, 941.
6. W. KEMULA, Z. R. GRABOWSKI and M. K. KALINOWSKI, *Naturwiss.*, 1960, 22, 1.
7. W. KEMULA, Z. KUBLIK and R. CYRANSKI, *Roczniki Chem.*, 1962, 36, 1339
8. J. HEYROVSKY, "Principles of Polarography", Academic Press, New York, 1966, p. 129.

# Hydrogen Ion Equilibria and Metal Binding Studies on Arachin

W. U. MAIK\*, R. BHUSHAN and ANITA AGARWAL

Department of Chemistry, University of Roorkee, Roorkee-247 672

Arachin, a protein with molecular weight 3,30,000, was isolated from defatted ground nut powder and purified to homogeneity. Hydrogen ion equilibrium studies were carried out and the number of binding sites in the protein molecule was calculated which were confirmed by calculating heat of ionization ( $H_{ion}$ ) on the basis of pH measurements at three different temp. The work also reports polarographic investigation of complexes formed by copper and zinc metal ions with arachin in the higher pH range. The results show that the amino groups of arachin bind copper ions more strongly than carboxyl groups.

IN view of its important contribution to the knowledge of molecular structures of proteins and their interaction with the environment, the hydrogen ion equilibrium of protein has been studied by a number of workers<sup>1-7</sup>. The present communication deals with the studies on hydrogen ion equilibria of arachin, which is isolated from ground nuts. The protein is edible and literature survey indicates no such studies on it.

The work also includes polarographic investigation of complexes formed by copper and zinc ions with arachin, in the higher pH range. Some of the results in the lower pH range have also been included but the binding is too weak to give useful quantitative results.

## Experimental

### Isolation of arachin :

Ground nuts (1 kg) were crushed finely and extracted with petroleum ether (40-60°). The defatted ground nut powder was dried in air, dipped in sodium chloride solution (10% ; 500 ml) overnight and filtered. Ammonium sulphate (A.R.) was added in the filtrate upto 0.2 saturation, when a white precipitate of arachin was obtained. It was filtered, washed free from salts and dried in vacuum (5 g). Further addition upto 0.8 saturation resulted in another white precipitate, which was of conarachin. The homogeneity of arachin was confirmed by circular paper chromatography using NaCl (10%) as the developing solvent and Solway purple (0.5%) containing H<sub>2</sub>SO<sub>4</sub> (0.5%) at 60°-70°, as the locating reagent. The chromatogram showed a single violet coloured patch for arachin only. The amino acid assay further confirmed the purity of arachin. Thus, the molecular weight of arachin was taken to be 3,30,000.

### Apparatus and technique :

pH meter (expanded scale) was used. The instrument was standardised with standard solution

of potassium hydrogen phthalate (pH 4.12) and borax buffer (pH 10).

### Reagents and solutions\*

A 4.8% solution of arachin was used. Solutions of HCl, KOH (carbonate free), KCl (all A.R.) were prepared with double distilled water in all glass apparatus.

### Procedure

Varying amounts of HCl, (26.04, 17.95, 13.06, 8.34, 6.49, 3.72 and  $1.82 \times 10^{-3} M$ ) and KOH ( $2.314$ ,  $4.629$ ,  $6.924$ ,  $13.887$  and  $23.14 \times 10^{-3} M$ ) were taken in 50 ml pyrex conical flasks and 2 ml of arachin solution was added to each of them. The total volume was made upto 10 ml by the addition of requisite amount of 1 M KCl ( $\mu=0.15$ ) and water.

TABLE I—pH MEASUREMENT RESULTS (WITH ACID)

Temp 24°, ionic strength 0.15, conc. of arachin 4.8 g/l				
H <sup>+</sup> added (Moles/ 1.10 <sup>3</sup> )	pH	Free H <sup>+</sup> (Moles/ 1.10 <sup>3</sup> )	Bound H <sup>+</sup> (Moles/mole protein)	Moles of H <sup>+</sup> dissociated per mole protein
26.04	1.7	19.95	420	0
17.09	2.0	10.00	488	0
13.06	2.1	7.94	353	67
8.34	2.3	5.011	229.1	190.9
6.49	2.4	3.981	173.1	246.8
3.72	2.6	2.512	83.45	336.5
1.82	3.0	1.0	56.55	363.45
0.00	6.5	0.0003	0	420

pH MEASUREMENT RESULTS (WITH ALKALI)

Temp. 24°, ionic strength 0.15, conc. of arachin 4.8 g/l				
OH <sup>-</sup> added (Moles/ 1.10 <sup>3</sup> )	pH	Free OH <sup>-</sup> (Moles/ 1.10 <sup>3</sup> )	Bound OH <sup>-</sup> (Moles/mole protein)	Moles of H <sup>+</sup> dissociated per mole protein
2.314	8.3	0.0019	159.2	579.2
4.629	10.2	0.15	308.2	728.2
6.924	11.3	1.99	341.58	761.58
13.887	11.9	7.9	412.4	832.4
23.14	12.25	17.78	369.65	789.65

\* Present Address : Vice-Chancellor, Kashmir University, Srinagar, (J.K.).

TABLE 2—pH MEASUREMENT RESULTS (WITH ACID)

Temp. 30°, ionic strength 0.15, conc. of Arachin 4.8 g/l

H <sup>+</sup> added (Moles/ 1.10 <sup>4</sup> )	pH	Free H <sup>+</sup> (Moles/ 1.10 <sup>4</sup> )	Bound H <sup>+</sup> (Moles/mole protein)	Moles of H <sup>+</sup> dissociated per mole protein
26.04	1.7	19.95	420	0
17.09	1.95	11.22	411.7	8.3
13.06	2.1	7.9	353	67
8.35	2.3	5.01	229.1	190.9
6.49	2.54	2.88	248.9	171.1
3.72	2.75	1.77	134.48	285.52
1.82	3.0	0.794	70.75	394.25
0.00	6.6	0.0002	0	420

## pH MEASUREMENT RESULTS (WITH ALKALI)

Temp. 30°, ionic strength 0.15, conc. of arachin 4.8 g/l

OH <sup>-</sup> added (Moles/ 1.10 <sup>4</sup> )	pH	Free OH <sup>-</sup> (Moles/ 1.10 <sup>4</sup> )	Bound OH <sup>-</sup> (Moles/mole protein)	Moles of H <sup>+</sup> dissociated per mole protein
2.314	8.1	0.013	159.3	579.3
4.629	9.9	0.79	313.7	733.7
6.943	11.2	1.58	369.7	789.7
13.887	11.8	6.30	523.24	943.24
23.145	12.25	17.78	369.65	789.65

TABLE 3—pH MEASUREMENT RESULTS (WITH ACID)

Temp. 40°, ionic strength 0.15, conc. of arachin 4.8 g/l

H <sup>+</sup> added (Moles/ 1.10 <sup>4</sup> )	pH	Free H <sup>+</sup> (Moles/ 1.10 <sup>4</sup> )	Bound H <sup>+</sup> (Moles/mole protein)	Moles of H <sup>+</sup> dissociated per mole protein
26.04	1.69	20.02	415.2	0
17.95	2.0	10.98	414	6.0
13.06	2.1	7.94	353	67
8.34	2.3	5.012	229.1	190.9
6.49	2.4	3.981	173.2	246.8
3.72	2.59	2.57	79.2	340.8
1.82	3.0	1.0	56.55	363.45
0.00	6.5	0.0002	0	420

## pH MEASUREMENT RESULTS (WITH ALKALI)

Temp. 40°, ionic strength 0.15, conc. of arachin 4.8 g/l

OH <sup>-</sup> added (Moles/ 1.10 <sup>4</sup> )	pH	Free OH <sup>-</sup> (Moles/ 1.10 <sup>4</sup> )	Bound OH <sup>-</sup> (Moles/mole protein)	Moles of H <sup>+</sup> dissociated per mole protein
2.314	8.3	0.0019	159.2	519.2
4.629	9.9	0.079	305.5	725.5
6.943	11.2	1.99	341.58	761.58
13.887	11.9	7.99	412.3	832.3
23.145	12.26	17.0	420.0	840

The pH measurements were carried out at three different temp viz., 24, 30 and 40° by keeping the cell in a water thermostat. Typical results are recorded in Tables 1 to 3 and are graphically represented (Fig. 1).

## Calculation :

The number of equivalent of H<sup>+</sup> ions which are bound when a protein is brought from the isoionic conditions to a state in which all dissociable groups have assumed their acidic forms is equal to the number of cationic acid groups in the molecule

while the equivalent of hydrogen ion dissociated between the isoionic and fully basic state of protein are equal to the number of anionic basic groups<sup>9</sup>.




Fig. 1. Titration curve of arachin at 24°, ionic strength 0.15.

The apparent heat of ionization ( $\Delta H_{ion}$ ) was determined according to Wyman's method<sup>10</sup> using the equation

$$H_{ion} = -2.303 RT^2 \left( \frac{dpH}{dt} \right)$$

The apparent heat of ionization,  $\Delta H_{ion}$ , was plotted against the number of protons dissociated per protein molecule (Fig. 2).




Fig. 2. The relation between the apparent heat of ionization and the number of protons dissociated per protein molecule.

### Discussion

The titration curve (Fig. 1) consisted of three main parts corresponding to the groups which titrate in the acid, neutral and alkaline regions.

The titration curve approached a limiting value of hydrogen ions bound at pH 2 where all carboxyl groups were in their acidic form. The pH 6.5 indicates that all carboxylic groups were in their basic forms. Thus the total number of carboxyl group is 420. It was interesting to note that the carboxyl region showed again a break at pH 3.2, since no other titrable groups except glutamic and aspartic acid, are expected<sup>11</sup>. The portion between pH 2 to 3.2 corresponded to aspartic acid residue (360) and that between 3.2 to 6.5 corresponded to glutamic acid (60) residue. These values were in agreement with those obtained from arachin assay<sup>12</sup> giving the value of 347 and 65 for aspartic and glutamic acid, respectively.

The second part of the titration curve from pH 6.5 to 8 corresponded to neutral region indicating the dissociation of imidazolium groups of histidine. The number of imidazolium groups is 130, which is a bit higher than that obtained from assay. This is perhaps due to the fact that

- (1) the maximum hydrogen ion binding capacity includes also the contribution of an uncertain fraction of the histidine residue,
- (2) the dissociations are not easily distinguishable from those of the phenoxyl group of tyrosine and sulphhydryl group of cystine, since they occur in overlapping range of pH, and

- (3) the titration with base is generally incomplete.

The third main part of the titration curve from pH 8 to 12 indicates the number of basic groups to be 230. It includes mainly lysine and arginine with side chain amino groups, with a contribution from phenolic, sulphhydryl, ammonium and guanidinium groups.

The plot of apparent heat of ionization  $\Delta H_{ion}$  against the number of proteins dissociated per protein molecule (Fig. 2) shows the expected range<sup>2,11</sup> of ionizable groups in arachin and lends support to the above results.

### Copper and zinc metal binding studies with polarography:

The manual polarograph was used. A H-shaped polarographic cell was found suitable for deaeration of protein solution without denaturation. Nitrogen gas (purified) was passed for about 15 to 20 min to ensure an inert atmosphere. Triply distilled mercury (A.R.) was used for dropping mercury electrode. The capillary used had a flow rate of about 2.2 mg/sec with a drop time of 3.5 sec.

Since the capillary characteristics ( $m, t$ ) have a marked effect on diffusion current (which is directly proportional to  $m^{2/3} t^{1/6}$ ), these factors were controlled carefully throughout these experiments.

The pH of the buffers and mixture of metal and protein solutions were measured by pH meter using a wide range glass electrode.




Fig. 3. Effect of protein concentration on diffusion current.

**Reagents and solutions :**

Solution of arachin was prepared by dissolving it in double distilled water. Copper sulphate and zinc sulphate (A.R.) were dissolved in double distilled water. Ammonia-ammonium chloride buffers were prepared from 10 M solutions of ammonia and ammonium chloride.

**Procedure :**

The following sets of solution were prepared for polarographic analysis :

- (1) Varying concentration of the protein (0.5, 0.75, 1.25, 1.75 and 2%) were taken in 50 ml conical flasks and 4.5 ml of 0.005M  $\text{Cu}^{2+}$  solution added. The total volume was made upto 12 ml by adding the requisite volume of water and 1.8 ml of 1M ammonia-ammonium chlo-

ride buffer ( $\mu=0.15$ ). The results, in the form of a graph of protein concentration (%) against  $(i_d)/(i_d)_0$ , where  $i_d$  and  $i_{d_0}$  are the diffusion currents of the metal ion, in the presence and absence of the protein, respectively, are shown in Fig. 3.

TABLE 4—CONC OF  $\text{Cu}^{2+}$ ,  $1.87 \times 10^{-3}$  M, pH 9.4

Conc. of protein (%)	$i_d$	$(i_d)_0$	$i_d/(i_d)_0$	$C_b$	$V_M$
0.50	4.6	9	0.51	1.14	76
0.75	3.6	9	0.40	1.37	62.2
1.25	2.5	9	0.28	1.67	42.4
1.75	2.0	9	0.22	1.82	34.3
2.00	1.8	9	0.20	1.86	31.0




Fig. 4. Effect of copper concentration on diffusion current depression (without protein)




Fig. 4.1. Effect of copper concentration on diffusion current depression.



- (2) 1 ml arachin, 1.8 ml buffer (pH 9.4) and varying concentration of  $\text{Cu}^{2+}$  ion, viz. 0.4166, 0.6249, 0.8332, 1.249 and  $1.874 \times 10^{-3} M$   $\text{Cu}^{2+}$  were used, keeping the total volume to 12 ml as before. Similar sets without protein were also prepared (Figs. 4 and 4.1)

TABLE 5—CONC. OF THE PROTEIN, 0.5%

Conc. of $\text{Cu}^{2+} \times 10^{-3} M$	$i_d$	$(i_d)_0$	$i_d/(i_d)_0$	$C_d$	$V_M$
0.520	2.2	1.8	0.4	0.520	34.6
0.624	2.8	2.3	0.6	0.416	27.4
0.833	3.3	2.7	0.8	0.277	18.4
1.24	4.8	3.0	0.85	0.31	20.6
1.87	6.9	3.3	0.9	0.311	20.6


- (3) Similarly, at a given concentration of copper sulphate ( $0.624 \times 10^{-3} M$ ) and the protein (0.5%), ammonium buffers of varying pH, viz. 11, 10, 9, 4, 6.1 and 2.6 were taken making the total volume 12 ml by the addition of water. The ionic strength was thus maintained at 0.15. Similar sets without protein were also prepared (Figs. 5 and 5.1).

- (4) (i) At pH 9.6, varying concentration of zinc sulphate, viz. 3.33, 5.66 and  $8.9 \times 10^{-4} M$  were taken with 2.5% protein in pyrex conical flasks. Another similar set without protein was also prepared. The total volume was made up to 15 ml with water and potassium chloride (to make ionic strength 0.15) solution (Fig 6).



Applied voltage →

FIG 5



Applied voltage →

Fig 5.1. Effect of pH on diffusion current depression.




Fig. 6. Effect of zinc concentration on diffusion current depression.

TABLE 6—CONC. OF THE PROTEIN 0.5%, CONC. OF  $\text{Cu}^{2+} 624 \times 10^{-3}$ 

pH	$i_d$	$(i_d)_0$	$i_d/(i_d)_0$	$C_b$	$V_M$
11	0.81	1.8	0.45	0.624	41.6
10	0.84	1.8	0.47	0.601	40.7
9.4	1.9	1.8	0.5	0.567	37.8
6.1	1.3	1.8	0.74	0.294	19.6
3.6	1.44	1.8	0.8	0.226	15.0

TABLE 7—CONC. OF THE PROTEIN 2.5%, pH 9.4

Conc. of $\text{Zn}^{2+} \times 10^{-4} M$	$i_d$	$(i_d)_0$	$i_d/(i_d)_0$	$C_b$	$V_M$
0.89	5.1	8.0	0.62	0.845	10.5
0.56	4.7	6.4	0.75	0.35	4.3
0.33	3.9	4.7	0.82	0.148	1.8

rent pHs from pH 2.6-11 were taken and the volume was made upto 15 ml by adding water and potassium chloride. Similar sets without protein were also prepared (Figs. 7 and 7.1).

(ii) Similarly, 1.5 ml of  $8.33 \times 10^{-4} M \text{Zn}^{2+}$  solution, 1 ml protein and 1.8 ml buffer of different




Fig. 7. Effect of pH on diffusion current depression (with protein).




Fig. 7.1. Effect of pH on diffusion current depression (without protein).

TABLE 8—CONC. OF THE PROTEIN 2.5%, CONC. OF  $Zn^{2+}$   $8.33 \times 10^{-4} M$ 

pH.	$i_d$	$(i_d)_0$	$i_d/(i_d)_0$	$C_b$	$V_M$
11	6.2	3.3	0.5	0.833	10.4
10	4.3	3.2	0.8	0.333	4.1
9.4	3.2	2.9	0.87	0.216	2.7
6.1	2.5	2.2	0.94	0.099	1.2
2.6	2.1	1.8	0.95	0.083	1.0

(iii) Varying concentrations of the proteins (0.5, 1.2, 2.0, 2.3 and 2.5%) were taken in 50 ml conical flasks and 4.5 ml of  $8.33 \times 10^{-4} M$   $Zn^{2+}$  solution were added. The total volume was made upto 15 ml by adding water and potassium chloride (Fig 8).




Fig 8. Effect of protein conc. on diffusion current.

TABLE 9—CONC. OF  $Zn^{2+}$   $8.33 \times 10^{-4} M$ , pH 9.4

Conc. of protein (%)	$i_d$	$(i_d)_0$	$i_d/(i_d)_0$	$C_b$	$V_M$
0.5	6.1	3.5	0.55	0.833	35
1.2	6.1	3.6	0.57	0.795	19.8
2.0	6.1	3.7	0.61	0.721	12.0
2.3	6.1	4.6	0.76	0.444	6.3
2.5	6.1	5.7	0.94	0.111	1.3

### Discussion

The usual polarographic method for the study of metal complexes from the shift in half wave potential of the metal ion<sup>15</sup> failed to give precise information regarding the metal protein interaction because of very small variations in  $E_{1/2}$  values of

the order of 0.01 V. Tanford's method<sup>14,16</sup>, with all its limitations, could however be advantageously employed. Since the copper arachin complex (blue in colour) and zinc arachin complex are formed only at higher pH ranges, the adsorption effects usually encountered could be assumed to exert the minimum influence and the decrease in the ratio  $i_d/(i_d)_0$  can be safely taken as a measure of the extent of metal ion complexed with the protein.

The decrease in the  $i_d/(i_d)_0$  values at pH 9.4, determined experimentally, provides enough information regarding the binding of  $Cu^{2+}$  and  $Zn^{2+}$  with arachin. From Tanford's equation

$$\frac{i_d}{(i_d)_0} = \frac{C + KC_0}{C_0}$$

where  $C$  and  $C_b$  are the conc. of free and bound copper or zinc,  $C_0$  its total concentration and  $K$  a constant which can be evaluated from the limiting values of  $i_d$  [ $K$  for set (a) is 0.2], the amount of bound copper can be found. The amount of bound zinc can also be obtained similarly. Taking the molecular weight of arachin to be 33,000, the amount of metal bound ( $V_M$ ) per mole of the protein could be determined. The results are summarised in Tables 4-9. From these, the values of  $V_M$  is seen to be approximately 34 at pH 9.4 for  $Cu^{2+}$  whereas for  $Zn^{2+}$  the value of  $V_M$  is 10 at pH 9.4.

Polarographic measurements carried out at different pH values show that the value of  $V_M$  ranges between 37-41.6 for the pH range 8.9-11, while at lower pH,  $V_M$  ranges between 15-19.6. These results are significant since they show that the amino groups of arachin bind copper ions more strongly than carboxyl groups

### References

1. R. K. CANNAN, A. C. KIBRICK and A. H. PALMER, *Ann. N. Y. Acad. Sci.*, 1941, 41, 243.
2. C. TANFORD, *J. Amer. Chem. Soc.*, 1950, 72, 441.
3. C. TANFORD, *J. Amer. Chem. Soc.*, 1956, 78, 5527.
4. C. TANFORD, *J. Phys. Chem.*, 1955, 59, 788.
5. W. U. MALIK and SALAHUDDIN, *J. Electroanal. Chem.*, 1963, 5, 68.
6. W. U. MALIK and H. S. RANDHAWA, *J. Indian Chem. Soc.*, 1972, 49, 1.
7. W. U. MALIK and H. S. RANDHAWA, *Studia Biophysica*, 1970, 143, 24.
8. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", 3rd Edn, ELBS, 1975.
9. "Advances in Protein Chemistry", (Eds.) M. L. ANSON, K. BAILEY and J. T. EDSALL, Vol 10, Academic Press, 1955.
10. J. WYMAN, *J. Biol. Chem.*, 1939, 127.
11. M. L. ANSON, K. BAILEY, J. T. EDSALL and E. B. ENFENSEN, "Advances in Protein Chemistry", Vol. 8, Academic Press, Inc., New York, N. Y., 1953.
12. I. M. KOLTHOFF and J. J. LINGANE, "Polarography", Interscience Publishers, Inc., New York, N. Y., 1952, 214.
13. C. TANFORD, *J. Amer. Chem. Soc.*, 1951, 73, 2066.
14. C. TANFORD, *J. Amer. Chem. Soc.*, 1952, 74, 211.
15. C. TANFORD, *J. Amer. Chem. Soc.*, 1952, 74, 6036.



# Metal-Polyalkoxylate Complexes and their Applications in Analytical Potentiometry

J D R. THOMAS

Applied Chemistry Department, Redwood Building, UWIST, Cardiff CF1 3NU, Wales

The complexation of polyalkoxylates with metals is discussed and preparation of tetraphenyl borates of the complexes summarized. The most appropriate methods for analyzing alkoxylates are based on their complexation reactions with metals in gravimetric, titrimetric and spectrophotometric procedures. Such reactions and the equilibrium between complexed metals and alkoxylates form the basis of membrane electrodes responding to various cations, especially with barium, lead and calcium ion selectivity, and to alkoxylates themselves. Among the applications for the barium and lead ion-selective electrodes are their use as endpoint indicators in the potentiometric titration of sulphate. The responses of the electrodes for polyalkoxylates may be used for evaluating critical micelle concentrations (CMCs) and analysis for these categories of non-ionic surfactants.

**S**TRONG stoichiometric complexes of metal ions with neutral molecules have been observed only in recent years, the main interest being with biological materials and macrocyclic polyethers. The essential complexing principle is that these neutral organic molecules carry a sequence of localised charges (usually lone-pair electrons) of sufficient energy to form ion-dipole ligands with appropriate cations. The conformation of the molecule is such that it forms a solvation type shell around the cation, effectively replacing the ion hydration shell. The charged cationic complex thus formed is electrically balanced by anions.

Apart from the macrocyclic types of polyethers, there are the acyclic polyalkoxylates whose complexing tendencies with various cations and associated analytical connotations have been much studied in the author's laboratories and by others. It is appropriate, therefore, that fulfilment of the privileged invitation to contribute a paper for this Commemoration Volume in honour of the 60th birthday of Professor Arun K. Dey, should centre on these complexes, especially in view of the tremendous current interest in analytical chemistry circles of the whole field of complexation between metal ions and neutral molecules.

## Nature of metal:alkoxylate complexes :

Polyalkoxylates are essentially acyclic polyethers with the  $-(CHCH_2O)-$  repeating unit. They

$$\begin{array}{c} R \\ | \\ -(CHCH_2O)_n- \end{array}$$

include polyethylene glycols (PEGs)  $[HO(CH_2CH_2O)_nH]$ , polyglycol dimethyl ethers (glymes)  $[CH_3O(CH_2CH_2O)_nCH_3]$ , polypropylene glycols (PPGs)  $[HO(CH(CH_3)CH_2O)_nH]$ , and alkylphenoxypolyethoxy-

$$\begin{array}{c} CH_3 \\ | \\ -(CHCH_2O)_n- \end{array}$$

lates of which the nonylphenoxypolyethoxylates (NPs)  $[C_9H_{19}O(CH_2CH_2O)_nH]$  are typical.

The materials have various applications. For example, the low molecular mass PEGs are solvents, while the NPs are important non-ionic surfactants and variation in the number of ethoxylate units can produce useful changes in wetting, detergency, emulsification, solubility and foam properties.

It is appropriate to note the evolution of an understanding of the nature of these complexes. The polyelectrolyte properties of polyalkoxylates in the presence of metal ions suggested an association, as was confirmed by nmr studies of ion-dipole interactions between potassium iodide and polyethoxylate<sup>1</sup>. Such interactions were, of course, evident from procedures for the analysis of alkoxylates. Also, there were the reaction between potassium alcoholate and polyalkoxylates<sup>2</sup>; spectrophotometric data on polyalkoxylates in the presence of sodium, potassium, and ammonium thiocyanates<sup>3</sup>; X-ray diffraction and other studies of complexes of mercury(II) halides with polyethoxylate<sup>4,5</sup> and related ethoxylate oligomers<sup>6</sup>; and also the temperature-dependent optical and nmr spectroscopic data on the effectiveness of glymes as coordinating agents for alkali metal ions and for the ion pairs of fluorenyl carbonium alkali metal ion salts<sup>7,8</sup>.

The tetraphenylborate salts of complexes between the NPs and other alkoxylates and alkaline earth and other metal cations, especially barium, have been exploited for their response in membrane electrode potentiometry<sup>9-24</sup>. This has led to rather direct interest in synthesising salts of the complexes.

Of the several methods for obtaining polyalkoxylate adducts, the conversion with tetraphenylborate ions is very convenient and an extended range of the tetraphenylborates of cation complexes with PEGs, PPGs and NPs has been prepared in the author's laboratories. These are summarised in Table 1.

The preparative method is simple and straightforward<sup>15,25,26</sup> and merely involves adding an

TABLE 1—TETRAPHENYLBORATES OF METAL CATION ADDUCTS OF POLYALKOXYLATES<sup>a, b</sup>

Polyalkoxylate	No. of AOU's	Stoichiometry of TPB precipitate	No. of AOU per cation	m.p. <sup>a</sup> °C
Antarox CO-880	30	Na(CO-880) <sub>0.111</sub> .TPB	8.4	98–100
		Mg(CO-880) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	40–45 with decomposition
		Ca(CO-880) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	185–190
		Sr(CO-880) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	197–200
		Ba(CO-880) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	215–217
		Cu(CO-880) <sub>0.111</sub> .TPB <sub>2</sub>	very unstable	(Ref. 26)
		Pb(CO-880) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	(Ref. 26)
Antarox CO-890	40	Na(CO-890) <sub>0.111</sub> .TPB	8.4	108–110
		Mg(CO-890) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	60–65
		Ba(CO-890) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	207–220
Antarox CO-850	20	Na(CO-850) <sub>0.111</sub> .TPB	8.4	55–60 with decomposition
		Ba(CO-850) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	210–215
PEG (1540)	34	Na(PEG-1540) <sub>0.111</sub> .TPB	8.5	150–155
		Mg(PEG-1540) <sub>0.111</sub> .TPB <sub>2</sub>	10.5	135–138
		Ba(PEG-1540) <sub>0.111</sub> .TPB <sub>2</sub>	10.5	225–230
PPG (1025)	17.36	Na(PPG-1025) <sub>0.111</sub> .TPB	8.5	—
		Mg(PPG-1025) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	—
		Ca(PPG-1025) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	70–75
		Sr(PPG-1025) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	105–110
		Ba(PPG-1025) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	140–145
PPG (2025)	34.56	Ca(PPG-2025) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	60–65
		Sr(PPG-2025) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	60–65
		Ba(PPG-2025) <sub>0.111</sub> .TPB <sub>2</sub>	12.0	55–60

<sup>a</sup> Poor stability and decomposition where m.p. data are not given [except for Pb(CO-880)<sub>0.111</sub>.TPB<sub>2</sub> where m.p. was not determined]. All the m.p.s. are irreversible with signs of charring at 5° below the minimum of the quoted ranges.

aqueous metal chloride solution (nitrate for lead) (10 cm<sup>3</sup> of 0.1M or 1M solution) to an aqueous solution (0.154 g 100 cm<sup>-3</sup>) of the appropriate polyalkoxylate (NP, PEG or PPG). The resulting oxonium ion may be precipitated with excess sodium TPB (10<sup>-3</sup>M), filtered, washed well with water and vacuum dried at 35–50°.

The waxy, thermally unstable magnesium and copper complexes need to be dried over phosphorus pentoxide.

Although the same general method applies to the TPB salts of sodium complexes, concentrated sodium chloride solutions (1M) are needed to coagulate the precipitates prior to final drying over phosphorus pentoxide.

Analytical and spectroscopic characterisation of the white products (pale blue for the copper complex) were in accord<sup>a, b, c</sup> for the complexes summarised in Table 1. The number of alkoxy units (AOU) per cation (Table 1) calculated from nmr spectra was deduced from the total number of protons of the alkoxy chain of each complex molecule as determined from the height of their integrated area in the nmr spectrum in relation to integrations of the TPB protons which were shifted far downfield from those of the alkoxy protons<sup>a</sup>. Due allowance was made for the phenyl protons associated with the NPs when deducing the number of TPBs associated with each polymer molecule of predetermined molecular mass<sup>a</sup>.

The number of alkoxy units associated with each metal ion obtained from nmr data in the above way was found to be similar to values obtained by chemical analysis. For the NP adducts with bivalent cations, the assessment of 12 alkoxy units per cation fully supports earlier assessments for calcium, strontium and barium complexes, respectively<sup>a, b, c</sup>. For the PEG complexes, the previously reported ratio of  $\approx 10.5$  alkoxy units per bivalent cation<sup>a, b</sup> has also been found to hold. The alkoxy:sodium ratios for the complexes in Table 1 are close to the figure of 8 required to wrap the sodium ion completely in order to promote maximum stability<sup>a, b, c</sup>.

#### Analysis of alkoxyates :

Coordination reactions between alkoxyates and metal cations form the basis of gravimetric, titrimetric and spectrophotometric analytical procedures for alkoxyates<sup>a, b</sup> (Table 2). Of these, the spectrophotometric methods are the most appropriate to date for analysing alkoxyate non-ionic surfactants in waters and effluents<sup>a, b</sup>. For the sake of completion, certain other methods for analysing alkoxyates are included in Table 2.

#### Membrane electrodes with sensors of polyalkoxylate : metal adducts :

##### Ion-sensing :

Several of the complexes listed in Table 1 form the basis of successful sensors in liquid<sup>a, b, c</sup> and

TABLE 2—METHODS OF ANALYSING ALKOXYLATES

Method type	Brief description	Reference
Gravimetry	Precipitation of metal ion-alkoxylate complex with potassium hexacyanoferrate(II) potassium tetraiodobismuthate(III) heteropolyacids sodium tetraphenylborate	31 32-34 35-39 40-44
Titrimetry	Metal ion-alkoxylate complex titrated with sodium tetraphenylborate using various methods of end-point detection, including visual indicator (Congo Red) <sup>16,17</sup> , potentiometry (with silver indicator electrode <sup>18</sup> ), indirect coulometry with biamperometric detection <sup>19</sup> and thermometric titration <sup>20</sup>	27, 28 45-47
Spectrophotometry	Solvent extraction of complexes of polyalkoxylates with metal ions using large polarisable ions like tetrathioisocyanatocobaltate(II) at 620 nm heteropolyacid (molybdenum complex at $\approx$ 650 nm) picrate (at 378 nm)	48-53 54 15, 55-58
Chromatography (GLC and TLC)	GLC may be used for lower polyalkoxylates by direct methods <sup>50,60,67</sup> , cleavage methods may also be employed <sup>60,61</sup> TLC may be used for higher, slightly volatile, oligomers <sup>60,68,69</sup> .	59-67
Spectroscopy	UV <sup>60,68</sup> and IR <sup>60,69,70</sup> , X-ray fluorescence <sup>60,70</sup>	15, 68-70
Indirect spectrophotometry	Solvent extraction into 1,2-dichlorobenzene of neutral adduct of non-ionic surfactant with potassium tetrathiocyanatocobaltate(II) Zinc(II) in the extract determined spectrophotometrically after adding 1-(2-pyridylazo)-2-naphthol and triethanolamine	71

PVC matrix membrane<sup>15-18,24</sup> ion-selective electrodes. A successful barium ion-selective electrode system<sup>15,16</sup> is based on the complex of a nonyl-phenoxypolyethoxylate containing 12 ethoxylate units and 2 mol of tetraphenylborate ion per mole of barium ions [Ba(Antarox CO-880)<sub>0.4</sub>.TPB<sub>2</sub>]. For use in PVC matrix membrane electrodes, this requires a more viscous solvent mediator than the 4-nitroethylbenzene used in liquid membrane electrodes<sup>18</sup>. Both 2-nitrophenyl phenyl ether and 2-nitrophenyl octyl ether satisfy this condition, but the former gives electrodes of superior lifetimes (about 30 days)

PVC matrix membrane electrodes<sup>15</sup> based on [Ba(Antarox CO-880)<sub>0.4</sub>.TPB<sub>2</sub>] sensor and 2-nitrophenyl phenyl ether solvent mediator have effective linear calibration ranges of  $10^{-1}$  to  $\approx 10^{-5}$  M barium ions, near-Nernstian slopes of 28 to 29 mV decade<sup>-1</sup>, response times of less than 1 min in normal ranges and  $\approx 5$  min near the detection limit, daily drifts of only 1 to 2 mV and long effective pH ranges (1.5 to 10). Selectivity coefficients,  $k_{Ba}^{X}$ , for barium over a large range of ions, B, (interferent, [B] =  $10^{-1}$  M) are less than  $1.8 \times 10^{-2}$  for B = Li, Na, K, Rb, Cs, Mg, Ca, Sr, Ni, or Cu

Among the possible applications of these PVC matrix membrane electrodes is the potentiometric titration of sulphate with barium ions. Such titrations of  $10^{-1}$  and  $10^{-3}$  M solutions of sodium sulphate and sulphuric acid with barium chloride and using the electrode with a calomel reference electrode<sup>15</sup> gave a coefficient of variation corresponding to the theoretical end-point of 0.1%. The break in emf at the end-point for the titration of 1.56 mg of sulphur from sulphate in 15 cm<sup>3</sup> solution exceeds 50 mV. Titrations of the sulphate following oxygen flask combustions of dibenzyl sulphide, S-benzylthiouronium chloride, dibenzyl sulphide+aniline phosphate (5+3) and triphenylphosphonic sulphide

gave average sulphur recoveries of 100.25 per cent, thus confirming the technique as a possible application for the barium ion-selective electrode<sup>15</sup>

Other potentiometric titration applications of the barium ion-selective electrode are the titration of sulphate in the presence of chromium(VI)<sup>24</sup> and in the determination of sulphate in sea water and certain natural waters with liquid membrane electrode<sup>25</sup>. The electrode has also been tested for determining sulphate by analate subtraction<sup>26</sup>.

In titration work, regard must be had to possible interferences by cations and anions. In this respect, cations, for example potassium, which can be sensed by the barium ion-selective electrode, give distorted titration curves, while pH values below 1.5 lead to electrode breakdown<sup>15</sup>. Cations, such as calcium, which interact with sulphate give low sulphate recovery, while anions that interact with the barium titrant lead to apparently high sulphate. Treatment of samples with cation-exchange resins in the sodium form can remove cation interferences, while acidification to pH 2 with hydrochloric acid prevents interference from anions, such as phosphate, carbonate, hydrogen carbonate and organic anions<sup>26</sup>.

Bauman<sup>15</sup> has successfully used a liquid membrane electrode based on the tetraphenylborate of the strontium-NP (30 ethoxylate units) complex for strontium ion determinations, but naturally barium was absent in these samples.

Tetraphenylborates of sodium and alkaline earth metal ion-complexes with a polypropoxylate [PPG(1025)] have been evaluated for ion-selective electrode qualities in conjunction with various solvent mediators<sup>15,17</sup>. From these a creditable PVC matrix-membrane calcium ion-selective electrode evolved. This was functional over a wide pH range (4.5 to  $> 10$ ) and was based on the Ca(PPG-1025)<sub>0.66</sub>.TPB<sub>2</sub> of Table 1 as sensor

and dioctylphenyl phosphonate as solvent mediator. Since the sensor starting materials are noted for their properties and as non-ionic surfactants or for altering the humectant properties of simple glycols and glycerine, they are readily available. This and the ease with which they can be complexed with certain cations, calcium in this case, and precipitated as tetraphenylborates render the sensors readily accessible for ion-selective electrode construction<sup>17</sup>. This can be advantageous when the, evidently much better, calcium ion-selective electrodes based on the more difficult to prepare organophosphate and neutral carrier sensor systems<sup>7,4</sup> are not at hand or if their enhanced selectivity is not required

#### Alkoxyrate sensing :

The barium ion-selective electrodes discussed above may be used in a converse potentiometric approach for sensing alkoxyrates in solution<sup>18</sup>. The observed potentiometric response is an increase of up to  $\approx 100$  mV in emf of the barium versus a calomel reference electrode according to the amount of added alkoxyrate in the  $2 \times 10^{-5} M$  to  $10^{-3} M$  range. The response is linear with  $\log[\text{alkoxyrate}]$ , but is characterised<sup>18</sup> by a break in the linearity which is attributed to the critical micelle concentration (CMC).

The alkoxyrate potentiometric response has been observed<sup>19</sup> for various members of the Antarox series of NPs, namely, CO-430 ( $n=4$ ), CO-630 ( $n=9$ ), CO-730 ( $n=15$ ), CO-850 ( $n=20$ ), CO-880 ( $n=30$ ) and CO-890 ( $n=40$ ). Other materials for which the response has been observed<sup>19</sup> include Antarox CA-620 and Triton X-100 (both are octylphenoxypolyethoxylates), Tween 80 (a sorbitan-9-octadecanoatepolyethoxylate) and several alkylpolyethoxylates (Dobanol 27-7, Lutensol AO7 and Synperonic 7). It is interesting to observe the good comparison between experimental (by electrode) literature and the calculated CMC for members of the Antarox series of NPs (Table 3).

TABLE 3—CRITICAL MICELLE CONCENTRATIONS OF ANTAROX NPs<sup>19</sup>

Antarox	Critical micelle concentration $\times 10^{-4} M$		
	Experimental by electrode	Literature	Calculated <sup>c</sup> in $CMC = A \frac{n}{n+1}$
CO-890	4.6 (0.38 sd)	—	4.5
CO-880	2.5 (0.24)	2.5 to 3.0 <sup>a</sup> 1.85 <sup>b</sup>	2.6
CO-850	1.4 (0.26)	1.35 to 1.75 <sup>a</sup> 1.40 <sup>b</sup>	1.5
CO-730	1.1 (0.056)	1.0 to 1.30 <sup>a</sup> 1.10 <sup>b</sup>	1.11
CO-630	0.83 (0.074)	—	0.80
CO-430	0.60 (0.055)	—	0.60

<sup>a</sup> Hsiao, Dunning and Lorenz, *J. Phys. Chem.*, 1956, 60, 657

<sup>b</sup> Schick, Atlas and Erlich, *J. Phys. Chem.*, 1962, 66, 1326.

<sup>c</sup> Equation obtained from Reference <sup>a</sup> with  $A = 0.056$  and  $B = 3.87$ .

Later research has shown that electrodes where the TPB of the barium complex of Antarox CO-880 in the membrane has been replaced by the TPB of the barium complex of Antarox CO-430, are superior in their response to the non-ionic polyalkoxyrates mentioned above. This indicates a further possible application for these electrochemical sensors, for polyalkoxyrates are widely used as non-ionic surfactants<sup>20,78</sup>.

The Antarox CO-430 electrode has been evaluated<sup>20</sup> for determining Dobanol 25-7, Synperonic 7 and Lutensol AO7 in detergent powder solutions of concentration 0.15% m/v (equivalent to  $\approx 0.015\%$  m/v or 150 ppm of the non-ionic surfactant). The recommended procedure is based on known (standard) addition<sup>20</sup>. In this test, 25 cm<sup>3</sup> of 0.15% fully-formulated detergent solutions, containing the non-ionic surfactant being determined, were spiked with non-ionic surfactant of known concentration<sup>20</sup>. Data obtained for Antarox CO-430 electrodes, calibrated by adding aliquots of Synperonic 7 solutions (1.0% m/v) to 25 cm<sup>3</sup> of a 0.15% m/v aqueous solution of fully formulated detergent base, are quoted in Table 4

With regard to more general application, there will be many situations when alkoxyrates will

TABLE 4—SOME KNOWN ADDITION DATA OF POLYALKOXYRATE TYPE NON-IONIC SURFACTANTS IN SOLUTIONS OF MODEL AND REAL SAMPLES OF DETERGENT POWDERS DETERMINED BY ANTAROX CO-430 ELECTRODE AND USING SYNPERONIC 7 SPIKES (ADAPTED FROM REF. 20)

Nature of sample and of polyalkoxyrate (all in fully formulated detergent base) in deionised water	Non-ionic surfactant in solution/% m/v			
	Expected	Found	s.d./10 <sup>-4</sup>	(n)
Synperonic 7 (model power)	0.0150 <sup>a</sup>	0.0151	1.2	(5)
Dobanol 25-7 plus (model)	0.0150	0.0150	1.7	(5)
Synperonic 7 (1 + 1) (powder)	0.0150	0.0150	1.7	(5)
Synperonic 7 (model powder)	0.0080	0.0079	0.8	(4)
Synperonic 7 (model powder)	0.0320	0.0321	5.4	(4)
Fully formulated detergent powder 'A' containing Lutensol AO7	0.0150	0.0146	2.5	(15)
Fully formulated detergent powder 'B' containing a non-ionic surfactant of unspecified alkyl	0.0150	0.0150	1.4	(12)

<sup>a</sup>: 0.0150% m/v = 150 ppm

be present at considerably lower levels than the examples of Table 4. In this respect, it should be noted that the Antarox CO-430 electrode will respond to less than 0.15 mg dm<sup>-3</sup> (10<sup>-7</sup> M) of Antarox CO-880 in deionised water<sup>20</sup>, but it is a pity that the electrode response times are so long ( $\approx 30$  min) at such low levels of alkoxylate.

#### Conclusion :

Complexes between metal ions and polyalkoxylates offer a new interesting area of study in chemistry of such considerable practical application that they also merit study with regard to ion-dipole interactions and structure, by those who are more theoretically oriented. The information so obtained can then be used to plan improved systems that can be applied to obtain better sensors and analytical methods and to enhance the use of these materials as selective extractants for metal ions.

#### References

1. K-J. LIU, *Macromolecules*, 1968, 1, 308
2. M. J. BECHET, *Bull. Soc. Chem.*, 1971, 3596.
3. S. L. DAVYDOVA, V. A. BARABANOV and N. A. PLATE, *Proc. XVI ICCO, Moscow*, 1973, p. 367
4. R. IWAMOTO, Y. SAITO, H. ISHIHARA and H. TADOKORO, *J. Pol. Sci., Part A-2*, 1968, 6, 1509
5. M. YOKOYAMA, H. ISHIHARA, R. I. IWAMOTO and H. TADOKORO, *Macromolecules*, 1969, 2, 184
6. R. IWAMOTO, *Bull. Chem. Soc. Japan*, 1973, 46, 1114, 1118, 1127, 1128
7. K. H. WONG, G. KONZIER and J. SMID, *J. Amer. Chem. Soc.*, 1970, 92, 666
8. L. L. CHAN, K. H. WONG and J. SMID, *J. Amer. Chem. Soc.*, 1970, 92, 1955
9. R. J. LEVINS, *Anal. Chem.*, 1971, 43, 1045
10. R. J. LEVINS, *Anal. Chem.*, 1972, 44, 1544
11. R. J. LEVINS, *Ger. Offen.*, 2, 264, 721, 1976.
12. E. W. BAUMAN, *Anal. Chem.*, 1975, 47, 959.
13. A. M. Y. JABER, G. J. MOODY and J. D. R. THOMAS, *Analyst*, 1976, 101, 179.
14. A. M. Y. JABER, G. J. MOODY and J. D. R. THOMAS, *Proc. Anal. Div. Chem. Soc.*, 1976, 13, 328.
15. A. M. Y. JABER, G. J. MOODY and J. D. R. THOMAS, *J. Inorg. Nuclear Chem.*, 1977, 39, 1689
16. A. M. Y. JABER, G. J. MOODY and J. D. R. THOMAS, "Conference on Ion-Selective Electrodes", Budapest 1977, (Ed.) E. PUNGOR, Akademiai Kiado, Budapest, 1978, p. 411
17. A. M. Y. JABER, G. J. MOODY and J. D. R. THOMAS, *Analyst*, 1977, 102, 943
18. D. L. JONES, G. J. MOODY, J. D. R. THOMAS and M. HANGOS, *Analyst*, 1979, 104, 973
19. D. L. JONES, G. J. MOODY and J. D. R. THOMAS, *Analyst*, 1981, 106, 439.
20. D. L. JONES, G. J. MOODY, J. D. R. THOMAS and B. J. BIRCH, *Analyst*, 1981, 106, 974
21. D. L. JONES, G. J. MOODY and J. D. R. THOMAS, *Proc. RSC Symp., Electroanal. Clinical, Environmental and Pharmaceutical Chem.*, UWIST, Cardiff, April 1981, paper 52.
22. J. D. R. THOMAS, *Proc. 2nd International Congress on Analytical Techniques in Environmental Chemistry, Barcelona, November 1981*, (Ed.) J. ALBAIGES, Pergamon Press, Oxford, 1982, p. 133.
23. S. K. A. G. HASSAN, C. G. D. JONES, D. L. JONES, G. J. MOODY and J. D. R. THOMAS, *Analytical Proceedings*, 1981, 18, 241.
24. R. PRASAD, *Analyst*, 1979, 104, 164
25. P. G. DELDUCA, A. M. Y. JABER, G. J. MOODY and J. D. R. THOMAS, *J. Inorg. Nuclear Chem.*, 1978, 40, 187
26. C. G. D. JONES, G. J. MOODY and J. D. R. THOMAS, unpublished data.
27. T. UNO and K. MIYAJIMA, *Chem. Pharm. Bull. (Tokyo)*, 1963, 11, 80
28. R. J. LEVINS and R. M. IKEDA, *Anal. Chem.*, 1965, 37, 671.
29. I. FRAVETTO, *Ann. Chim.*, 1976, 66, 621
30. I. FRAVETTO, *Ann. Chim.*, 1981, 71, 163.
31. N. SCHONFELDT, *J. Amer. Oil Chem. Soc.*, 1955, 32, 77.
32. H. BRUESCHWELER, V. SIEBLER and H. WISHAUPT, *Tenside Deterg.*, 1980, 17, 126
33. R. WICKBOLD, *Tenside Deterg.*, 1972, 9, 173.
34. S. GIACOBETTI, A. LAGANA and B. M. PETRONIO, *Riv. Ital. Sostanze Grasse*, 1978, 55, 176.
35. C. B. SHAFER and F. H. CRITCHFIELD, *Ind. Eng. Chem. Analyst. Edn.*, 1947, 19, 32
36. J. OLIVER and C. PRESTON, *Nature*, 1949, 164, 242
37. A. BARBER, C. C. T. CHINNICK and P. A. LINCOLN, *Analyst*, 1956, 81, 18
38. K. KIMURA and T. HARADA, *Fette Seifen Anstr. Mitt.*, 1959, 61, 930
39. W. B. SMITH, *Analyst*, 1959, 84, 77.
40. R. NEU, *Arzneimittel Forsch.*, 1957, 9, 585
41. R. NEU, *Fette Seifen Anstr. Mitt.*, 1957, 59, 585.
42. J. F. SINSCHIMER and F. SMITH, *J. Pharm. Sci.*, 1963, 52, 1080
43. A. SEHER, *Fette Seifen Anstr. Mitt.*, 1959, 61, 782.
44. A. SEHER, *Fette Seifen Anstr. Mitt.*, 1961, 63, 617
45. T. UNO and K. MIYAJIMA, *Chem. Pharm. Bull. (Tokyo)*, 1963, 11, 75
46. J. R. MOODY, G. D. CHRISTIAN and W. C. PURDY, *Anal. Chim. Acta*, 1968, 42, 153
47. K. Y. KHAIAR and T. W. GILBERT, *Analyst*, 1978, 103, 623
48. E. G. BROWN and T. J. HAYES, *Analyst*, 1955, 80, 755
49. M. KURATA, *J. Japan Oil Chem. Soc.*, 1955, 4, 293.
50. C. A. ANDERSON, LIPSON and G. F. WOOD, *J. Pharm. Pharmacol.*, 1966, 18, 809.
51. C. CALZOLARI, I. FAVRETTO and F. TUNIS, *Analyst*, 1974, 99, 171
52. D. W. F. TURPIN and I. T. VAN DER WAL, SAWTRI Technical Report, 1977, No. 353
53. K. W. PRITS and I. SINSKY, *Water Res.*, 1981, 15, 129
54. E. W. CLARK, *J. Soc. Cosmet. Chem.*, 1971, 22, 421
55. I. FAVRETTO and F. TUNIS, *Analyst*, 1976, 101, 198
56. I. FAVRETTO, B. STANCHER and F. TUNIS, *Analyst*, 1978, 103, 955
57. I. FAVRETTO, B. STANCHER and F. TUNIS, *Analyst*, 1979, 104, 241
58. I. FAVRETTO, B. STANCHER and F. TUNIS, *Analyst*, 1980, 105, 833.
59. I. FAVRETTO and B. STANCHER, *J. Chromatogr.*, 1975, 108, 183
60. B. STANCHER, I. FAVRETTO, GABRIELLI and L. FAVRETTO, *J. Chromatogr.*, 1975, 111, 459.
61. J. R. CHRISTOF and D. J. EVANS, *J. Pharm. Pharmacol.*, 1980, 32, 111.

62. G. LONGMAN, "The Analysis of Detergents and Detergent Products", Wiley-Interscience, London, 1975.
63. L. FAVRETTO, G. PERTOLDI MARLETTA and L. FAVRETTO GABRIELLI, *J. Chromatogr.*, 1970, 46, 255.
64. G. PERTOLDI MARLETTA and L. FAVRETTO GABRIELLI, *Tec. Ital.*, 1969, 34, 649.
65. L. FAVRETTO, *Riv Ital Sostanze Grasse*, 1970, 47, 187.
66. H. BRUESCHWEILER, V. SIEBER and H. WEISHAUPT, *Tenside Deterg*, 1980, 17, 126.
67. C. SCHAFFNER, E. STEPHENSON and W. GIGER, Paper presented at 2nd European Symposium on the Analysis of Organic Micropollutants in Water, Killarney, Ireland, 17-19 November 1981.
68. J. C. GRIFFITH, *Chem Ind (London)*, 1957, 1041.
69. H. HELLMANN, *Fresenius' Z. Anal. Chem.*, 1979, 297, 102.
70. H. HELLMANN, *Fresenius' Z. Anal. Chem.*, 1980, 300, 44.
71. D. T. CRISP, J. M. ECKERT, N. A. GIBSON and J. A. WEBSTER, *Anal. Chim. Acta*, 1981, 123, 355.
72. G. OUZOUNIAN and G. MICHARD, *Anal. Chim. Acta*, 1978, 96, 405.
73. G. J. MOODY and J. D. R. THOMAS, *Lab. Pract*, 1979, 28, 125.
74. G. J. MOODY and J. D. R. THOMAS, *Ion-Selective Electrode Revs*, 1979, 1, 3.
75. G. HOLLIS, "Surfactants UK: Directory of Surface Active Agents Available in the United Kingdom", Tergo-Data (34, Edinburgh Drive, Darlington DL3 8AT), 2nd Edn, 1979.

## The Cumulation of Methylmercury and Phenylmercury Species on Alga

I. STARÝ, K. KRATZER and J. PRÁŠILOVÁ

Department of Nuclear Chemistry, Technical University, Praha 1, Břichová 7, Czechoslovakia

The cumulation of methylmercury and phenylmercury species on the alga *Chlorella kessleri* has been radiometrically investigated as a function of algal cells, the species studied and hydrogen ion concentration, in the absence and presence of different metal salts and complexing agents. It has been found that the cumulation factor  $F$  decreases with the increase of methylmercury and phenylmercury concentration and with the increase of  $pH$ , but is not influenced by the presence of metal salts. Reagents forming negatively charged complexes with methylmercury and phenylmercury cations decrease the  $F$ -value. The cumulation of species studied was quantitatively described using the affinity constants.

**T**HE biotransformation of inorganic mercury, methylmercury and phenylmercury chlorides, has been investigated in our previous papers<sup>1,2</sup> using different types of algae. It has been found that all species studied were cumulated very rapidly in the algae. However, from the second day onwards methylmercury and phenylmercury changed into less toxic inorganic mercury. In continuation of these studies, the physico-chemical investigation of the cumulation of methylmercury and phenylmercury species has been carried out to describe quantitatively the cumulation of the above species

### Experimental

All reagent used, unless otherwise stated, were of A.R. quality. Hydrochloric acid and sodium hydroxide, (superpure, Merck) were used for adjusting the  $pH$ .

Solutions for radionuclides (Amersham, England) were prepared by dissolving methylmercury-203 chloride (specific activity 2.5 GBq/g Hg) and phenylmercury-203 acetate (specific activity 2 GBq/g Hg) in 0.01  $M$  NaOH.

Algologically and bacteriologically pure strains of the alga *Chlorella kessleri* were used in the experiments. The mean geometric volume of one cell,  $V_a = 3.5 \times 10^{-11} \text{ cm}^3$  and the mean geometric surface,  $S_a = 4.5 \times 10^{-7} \text{ cm}^2$  were calculated from measured size of the cells.

Well-type scintillation NaI(Tl) counter was used for the measurements of the radioactivity and Radiometer PHM-52 (Copenhagen, Denmark) for the determination of equilibrium  $pH$  values.

The cumulation of methylmercury and phenylmercury species was investigated in the manner described earlier<sup>3,4</sup>. An appropriate volume of alga suspension (containing a known amount of algal cells) was centrifuged and transferred into test tubes containing methylmercury or phenylmercury species (labelled with mercury-203), HCl (or NaOH),

different metal salts or reagents of known concentration (total volume 10 ml) and the mixture shaken for 1 hr. The equilibrium  $pH$  value, the radioactivity of algae ( $A_a$ ) and that of the medium ( $A_m$ ) were measured and the cumulation factor  $F$  (the ratio of the concentration of the species studied in alga and in aqueous phase) was calculated according to eq. (1)

$$F = \frac{A_a}{A_m} \frac{N_a}{N_m} \frac{V_a}{V_m} = \frac{D}{N_a \bar{V}_a} \quad \dots (1)$$

where  $N_a$  is the number of algal cells per  $\text{cm}^3$ ,  $V_a$  is the mean geometric volume of one cell in  $\text{cm}^3$ ,  $D$  is the distribution ratio of the species studied. All experiments were carried out at  $22 \pm 1^\circ$ .

### Results and Discussion

The influence of  $pH$  on the cumulation of methylmercury and phenylmercury species is illustrated in Fig 1. At  $pH < 7$ , the cumulation practically does not depend on  $pH$ ; in these conditions methylmercury and phenylmercury are present predominantly as  $\text{CH}_3\text{HgCl}$  and  $\text{C}_6\text{H}_5\text{HgCl}$  complexes. The decrease of the  $F$ -value at higher  $pH$  is probably connected with the formation of more soluble  $\text{CH}_3\text{HgOH}$  and  $\text{C}_6\text{H}_5\text{HgOH}$  complexes. This assumption was confirmed by the fact that the addition of NaCl into alkaline medium leads to the increase of  $F$ -value. The kinetics of the uptake is rather rapid; the equilibrium was reached in less than 1 hr shaking.

It has been found that the  $F$ -values (in otherwise constant conditions) does not depend on the concentration of algal cells ( $N_a = 7.5 \times 10^6 - 6 \times 10^8 \text{ cells.cm}^{-3}$ ). This allows the adjustment of the  $N_a$  value in such a manner that the measurement of distribution ratio is very precise.

The highest values of cumulation factor ( $F_0$ ) or distribution ratio ( $D_0$ ) were found at lowest concentrations of the species studied and at highest algal cells concentration. The increase of methylmercury




Fig 1. The dependence of the cumulation factor  $F$  of methylmercury (curve 1) and phenylmercury species (curve 2) on  $pH$  (total concentration  $3 \times 10^{-8}$  mol.  $dm^{-3}$ ,  $N_a = (3.5) \times 10^8$  cells.  $cm^{-3}$ , free points—1 hour shaking, full points—3 hours shaking).

and phenylmercury concentration leads to a decrease of the cumulation ( $F$  or  $D$ -values) because of the limited capacity of the algal cells to cumulate the species studied. Similar results were obtained in the study of the cumulation of alkali metals and alkali earths on alga<sup>4</sup>.

The cumulation of methylmercury chloride or phenylmercury chloride ( $RHgCl$ ) on alga can be quantitatively described using the affinity constant  $K_M$ <sup>4</sup>.

$$K_M = \frac{[RHgCl]_A}{[RHgCl] [A]} \quad (2)$$

where  $[RHgCl]_A$  and  $[RHgCl]$  denote the equilibrium concentration of the species studied in alga and in aqueous phase, respectively,  $[A]$  denotes the "free capacity" of algal cells to cumulate  $RHgCl$ .

The  $K_M$  value can be calculated from the following equations<sup>4</sup>

$$\frac{F_0}{F} - 1 = K_M [RHgCl] \quad (3)$$

or at constant  $N_a$  and  $V_a$

$$\frac{D_0}{D} - 1 = K_M [RHgCl] \quad (4)$$

The experimentally determined ratio  $D_0/D$  at different equilibrium concentration of  $RHgCl$  (determined from the radioactivity in the aqueous phase) was used for the calculation of  $K_M$  values (Table 1).

It has been found that the  $F$ -value of methylmercury chloride ( $pH \sim 5.2$  in the presence of  $0.004 M$   $NaCl$ ) also decreases in the presence of an excess of phenylmercury chloride. Similarly, the  $F$  value of phenylmercury chloride decreases in the presence of methylmercury chloride. On the other hand,  $F$  value of both the species is not influenced in the presence of  $0.005 M$   $Mg(NO_3)_2$ ,  $Sr(NO_3)_2$ ,  $ZnSO_4$ ,  $CdSO_4$  or  $0.001 M$   $CuSO_4$ ,  $Cr(NO_3)_3$ . It follows from these results that the mechanism of the

TABLE 1—AFFINITY CONSTANT  $K_M$  OF METHYLMEURGY AND PHENYLMERURY CHLORIDES IN  $0.004 M$   $NaCl$  ( $pH \sim 5.2$ )

Species	$\frac{D_0}{D}$	$-\log [RHgCl]$	$\log K_M$
$CH_3HgCl$	2.6	5.65	5.85
	4.6	5.40	5.96
	5.5	5.23	5.88
	14	4.85	5.96
	21	4.62	5.92
	50	4.50	6.19
		mean	$5.96 \pm 0.12$
$C_6H_5HgCl$	3.5	5.85	6.25
	4	5.55	6.03
	6	5.50	6.20
	9	5.00	5.90
	24	4.96	6.32
	40	4.69	6.28
		mean	$6.16 \pm 0.16$

cumulation of  $CH_3HgCl$  and  $C_6H_5HgCl$  is quite different from that of metal ions

The stability constant of methylmercury chloride ( $\log \beta_1 = 5.5$ )<sup>5</sup> and phenylmercury chloride ( $\log \beta_1 = 5.8$ )<sup>6</sup> is rather high and because of this the cumulation of these species can be decreased only in the presence of reagents forming very stable negatively charged complexes with  $CH_3Hg^+$  or  $C_6H_5Hg^+$  cations such as sodium thiosulphate ( $\log \beta_1 = 10.9$ )<sup>6</sup>.

#### References

1. B. HAVLÍK, J. STARY, J. PRÁŠILOVÁ, K. KRATZER and J. HANUŠOVÁ, *Acta Hydrochim. Hydrobiol.*, 1979, 7, 215.
2. J. HAVLÍK, J. STARY, J. PRÁŠILOVÁ, K. KRATZER and J. HANUŠOVÁ, *Acta Hydrochim. Hydrobiol.*, 1979, 7, 401.
3. J. STARY and K. KRATZER, *J. Environ. Anal. Chem.*, 1982, 12, 65.
4. J. STARY, K. KRATZER and J. PRÁŠILOVÁ, *J. Environ. Anal. Chem.*, 1983, 14, 161.
5. J. STARY, K. KRATZER and J. PRÁŠILOVÁ, *Anal. Chim. Acta*, 1978, 100, 627.



## Separation of Nickel by Solvent Extraction and Cation-Exchange. Determination of Nickel in Mineral Waters

J. KORKISCH\*, I. STEFFAN and H. STANIEK

Institute for Analytical Chemistry, University of Vienna, Währingerstrasse 38,  
A-1090 Vienna, Austria

A method for the isolation of nickel from mineral waters by solvent extraction and cation exchange is described. The nickel is first preconcentrated from the waters by chloroform extraction in its dimethylglyoximate form at pH 7.4-7.6. The chloroform extract is then mixed with THF and methanol containing hydrochloric acid, and passed through a column of Dowex 50-X8 ( $H^+$  form). After removal of dimethylglyoxime, chloroform and THF by washing the resin with methanol-HCl, nickel is eluted with 6M HCl and determined by a.a.s. with an air-acetylene flame. The method was successfully applied to determine nickel in bottled mineral waters in which nickel in the range from 0.3 to 30  $\mu g$  Ni/litre was found.

**T**HE determination of trace quantities of nickel in natural waters and waste waters is gaining increasing importance with the growing interest in pollution of the environment with this and other heavy metals.

Preconcentration of nickel, mainly together with several other metal pollutants, is carried out before its quantitative determination. For isolation of trace amounts of nickel from natural and waste waters the best separation methods are based on liquid-liquid extraction of nickel with dithiocarbamates or as other nickel complexes<sup>1-10</sup>.

In the present paper, a combination of separation techniques is described, which utilizes chloroform extraction of nickel dimethylglyoximate as the first preconcentration step followed by cation-exchange enrichment of nickel directly from the organic extract.

### Experimental

#### Apparatus and reagents :

The strongly acidic cation exchanger Dowex 50-X8 (Bio-Rad AG 50W-X8, 100-200 mesh ;  $H^+$  form) was used. A slurry of the resin (4 g) was prepared with a few ml of 6 M HCl and poured into the ion-exchanger column using 50 ml of the same acid as a rinse and to purify the exchanger. Subsequently, the resin was washed with tetrahydrofuran (THF) prior to pretreatment of samples.

Standard solutions of Ni(II) in 6 M HCl was prepared from a stock solution containing 1 mg Ni(II) per ml of 6M HCl. MeOH-HCl mixture with 1 M overall acidity was prepared by diluting 85 ml conc. HCl to 1 litre with methanol. 10 ml of this diluted to 100 ml with methanol gave the MeOH-HCl mixture of 0.1M overall acidity, which is used for the ion-exchange separation of nickel.  $CHCl_3$ -THF-MeOH solution of 0.1 M overall

acidity was prepared by mixing 30 ml of  $CHCl_3$  with 60 ml of THF and 10 ml of MeOH-HCl mixture of 1 M overall acidity. Other reagents used were 10% aqueous solution of hydroxylamine hydrochloride, aqueous ammonia (1:1) and a 10% solution of dimethylglyoxime in ethanol.

For the determination of nickel, a Perkin-Elmer Atomic absorption Spectrometer Model 303 was used with the following instrumental settings : uv grating ; wavelength 232.5 nm ; scale expansion up to 2X ; slit width 3 (0.3-0.2 nm bandpass) ; nickel hollow-cathode lamp at 25-40 mA ; standard burner head ; acetylene pressure 8 psig (7.0 on flow meter scale) ; air pressure 30 psig (9.0 on flow meter scale) ; noise suppression up to 2.

When the measurements were done with 6 M hydrochloric acid solutions, a sensitivity (1% absorption) of 0.24 ppm of nickel was obtained.

The ion-exchange columns used for the separation of nickel from the organic extracts were of the type and dimensions described earlier<sup>11</sup>.

**Determination of distribution coefficients :** The distribution coefficients ( $K_d$ -values) of nickel in the various media employed for the cation exchange separations were determined by using the batch method<sup>12</sup>.

#### Procedure :

To 0.5-1.0 litre of the water sample are added 10 ml of conc. HCl and 5 ml of the hydroxylamine hydrochloride solution. The pH of the mixture is adjusted to 7.4 to 7.6 by the addition of dilute ammonia solution (1:1) and it is transferred to a 2 litre separatory funnel using a few ml of water as a rinse. 5 ml of the dimethylglyoxime solution is added to the sample mixture and shaken for 1 min. The nickel dimethylglyoximate is extracted with 20 ml of chloroform using a shaking time of 5 min.

The extraction is repeated with two 20 ml portions of chloroform, shaking 2 min each time. The three extracts are combined.

To the combined chloroform extracts (about 60 ml) is added 20 ml of the MeOH-HCl mixture (overall acidity 1 *M*) and diluted with 120 ml of THF. The resulting solution (the sorption solution, overall acidity 0.1 *M*) is passed through a 4 g column of the cation exchanger (pretreated with 20 ml of the CHCl<sub>3</sub>-THF-MeOH solution) at a flow rate of about 1.7 ml/min. The resin bed is washed with 5 ml CHCl<sub>3</sub>-THF-MeOH solution, 10 ml of MeOH-HCl mixture (overall acidity 0.1 *M*) and 5 ml 0.1 *M* hydrochloric acid in this order. The nickel is then eluted with 100 ml of 6 *M* HCl.

The eluate is evaporated to dryness on a steam-bath and the residue is dissolved in 10 ml of 6 *M* hydrochloric acid. This solution is aspirated into the air-acetylene flame. Calibration curves are constructed by aspirating suitable standard solutions of nickel before and after each batch of samples.

## Results and Discussion

### Separation of nickel :

Atomic-absorption measurements of the nickel in the chloroform extracts did not give either the required sensitivity or reproducible results. The nickel was therefore stripped from the organic phase using dilute HCl and the assay was completed after wet-ashing of the co-extracted organic compounds. However, this very tedious procedure was abandoned in favour of the ion-exchange technique described in the procedure which in combination with the extraction step gave results of high accuracy and reproducibility. It is seen from Table 1 that this procedure allows the quantitative isolation of both  $\mu\text{g}$  and  $\text{mg}$  amounts of nickel.

TABLE 1—EFFECT OF CONCENTRATION ON NICKEL RECOVERY FROM TAP WATER

Amount of nickel added to 1 litre of water sample, $\mu\text{g}$	Nickel found $\mu\text{g/litre}$	%
12	11.8	98.5
100	103	103
500	512	102.5
1000	998	99.8

By means of the ion-exchange procedure the nickel is separated from the chelating agent dimethylglyoxime and chloroform without the need of evaporation or back-extraction and wet-ashing. The presence of tetrahydrofuran is necessary in the CHCl<sub>3</sub>-THF-MeOH solution to obtain a homogeneous solution, and methanol is the component regulating the flow rate through the ion-exchange column. In absence of methanol, the viscosity of the sorption solution is extremely low and a very

high flow rate is attained at which complete adsorption of nickel is not assured. Hydrochloric acid has to be present in the mixture so that the nickel remains in the ionic form which is adsorbed on the cation-exchanger during the sorption process. After adsorption, the residual chloroform, tetrahydrofuran and dimethylglyoxime are removed by washing the resin bed with the MeOH-HCl mixture.

The measurement of the batch distribution coefficients of nickel in all the media employed for the cation-exchange separation of this element gave the results for  $K_d$  as 1940 in CHCl<sub>3</sub>-THF-MeOH medium, 4380 in MeOH-HCl mixture, and 977 and <1 in 0.1 and 6 *M* HCl, respectively.

Nickel is thus found to be very strongly retained by the resin from the organic as well as aqueous 0.1 *M* hydrochloric acid solutions so that this method is suitable for the quantitative separation of both  $\mu\text{g}$  and  $\text{mg}$  amounts of this element.

TABLE 2—DETERMINATIONS OF NICKEL IN SAMPLES OF BOTTLED MINERAL WATER

Trade name	Nickel content $\mu\text{g/litre}$	
	A	B
Bonaqua	0.25	0.26
Petersquelle	0.34	0.34
Aussee Heilquelle	0.53	0.54
Romerquelle	1.30	1.33
Sixtina	2.89	2.99
Donat	3.49	3.51
Severinquelle	3.87	3.63
Gussinger	4.84	4.82
Vitusbrunnen	5.24	5.15
Radenska	5.22	5.38
Preblauer (Ebriachquelle)	29.9	29.8

\*A—Nickel contents determined by a.a.s. following solvent extraction and cation-exchange of nickel

B—Same as for A, but after deduction of 2.0  $\mu\text{g}$  Ni added to the sample before application of the procedure.

### Application to natural waters :

Table 2 gives the results obtained when this procedure was applied to the analysis of 11 mineral water samples.

Comparison of the results listed in columns A and B of Table 2 shows that the amounts of nickel added were recovered quantitatively in all cases, i.e. nickel is not lost during the separation procedures.

### Acknowledgement

This work was sponsored by the Fonds zur Forderung der Wissenschaftlichen Forschung, Vienna, Austria.

### References

1. A. DORNEMANN and H. KLEIST, *Z. anal. Chem.*, 1978, 291, 349.

KORKISCH, STEFFAN & STANIEK : SEPARATION OF NICKEL BY SOLVENT EXTRACTION ETC.

2. B. KASTERKA, R. PASTUSZAK and J. DOBROWOLSKI, *Chem. Anal. (Warsaw)*, 1978, 23, 149.
3. T. GOTO and N. UNOHARA, *Bunseki Kagaku*, 1978, 27, 264.
4. P. PAKALINS and Y. J. FARRAR, *Water Research*, 1977, 11, 145.
5. J. GOLIMOWSKI, S. RUBEL, E. STRYJWSKA and Z. VOR-BRODT, *Chem. Anal. (Warsaw)*, 1977, 22, 719.
6. J. GOLIMOWSKI and S. RUBEL, *Chem. Anal. (Warsaw)*, 1974, 19, 1155.
7. B. MAGYAR and F. I. LOBANOV, *Talanta*, 1973, 20, 55.
8. F. J. MARCIE, *Environ. Science and Technol.*, 1967, 1, 164.
9. D. PEPIN, A. GARDES, J. PETIT, J. A. BERGER and G. GAILLARD, *Analysis*, 1973, 2, 549.
10. A. L. WILSON, *Analyst*, 1968, 93, 83.
11. W. KOCH and J. KORKISCH, *Mikrochim. Acta (Wien)*, 1972, 687.
12. J. KORKISCH, "Modern Methods for the Separation of Rarer Metal Ions", Pergamon, Oxford, 1969, p. 7-8.

## Extraction of Zinc(II) as Chloride by High Molecular Weight Amine, Amberlite LA-1

ANIL K. DE, UDAY S. RAY and NARAHARI PARHI\*


Department of Chemistry, Visva-Bharati, Santiniketan-731 235

A rapid and selective method for the extraction of milligram amounts of Zn(II) from hydrochloric acid solution with liquid anion exchanger, Amberlite LA-1, in nitrobenzene has been proposed. Quantitative extraction has been achieved in the hydrochloric acid conc range 2-4 M. Diluents having high dielectric constant values show improved extraction results, compared to benzene, xylene, toluene, chloroform and carbon tetrachloride. The effect of such variables as hydrochloric acid conc., contact time, stripping time and extractant conc was studied and the effect of foreign ions investigated. The separation of zinc from several synthetic mixtures is also found quantitative. The probable composition of the extracted species has been deduced from the extraction data.

In recent years, solvent extraction with high molecular weight amines and quaternary ammonium compounds has been extensively used as a promising technique in industries and atomic energy programmes. The applications include the removal of toxic elements such as Hg, As, Cd, Zn, Cu, Pb, Cr etc. for pollution abatement from industrial effluents and recovery of fertile and fissionable materials from irradiated fuel elements at atomic energy centres.

The amines, due to their unique anion exchange ability, extract anionic metal complexes from the aqueous phase. Separation and estimation of such type of metals through liquid cation exchangers have been carried out in this laboratory<sup>1-5</sup>. The liquid anion exchanger, on the other hand, is the point of interest to explore in the extraction of toxic metals. The present work reports on the selectivity of Amberlite LA-1 for the extraction of zinc(II) chlorocomplex. No such work is reported in the literature<sup>6-9</sup>.

The mechanism of extraction of zinc from aqueous hydrochloric acid solution with the secondary amine, pretreated with hydrochloric acid, is of this type :



where o=organic phase and a=aqueous phase.

The secondary amine and its salt with anionic chlorocomplex of zinc are essentially insoluble in aqueous solutions but exhibit high solubility in organic solvents.

### Experimental

**Apparatus:** A single pan balance, SICO Popular Model, Scientific Instrument Co., Calcutta was used for taking weights. Separatory funnels (150 ml) were used for extraction experiments.

### Reagents :

The liquid anion exchanger, Amberlite LA-1, manufactured by the Rohm and Haas Co., Philadelphia, USA, and supplied by B.D.H., Poole, England was used without further purification. Nitrobenzene (Sarabhai M. Chemicals, GR) was used as diluent. The amine was suitably diluted with nitrobenzene and converted to its chloride form by equilibrating with hydrochloric acid for 5 min. The molar concentration of the amine was determined by stripping the chloride by sodium hydroxide solution and then titrating the chloride with standard silver nitrate solution using potassium chromate as indicator<sup>8,10</sup>.

$\text{ZnSO}_4 \cdot 7\text{H}_2\text{O}$  (B.D.H., A.R.) was used for analysis. A stock solution of zinc (6.5 mg/ml) was prepared in double deionised water and the solution standardized by complexometric titration with EDTA (disodium salt) using xylenol orange as an indicator<sup>11</sup>.

The chemicals and solvents used were all of analytical grade unless otherwise mentioned.

### General extraction procedure :

The procedure was based on solvent extraction technique. The ratio of the volumes of aqueous phase and the organic phase was maintained at 1 : 1. In a separatory funnel, the aqueous phase was made up from a portion of the solution containing 6.5 mg of zinc. Standard hydrochloric acid was added to maintain the required acid strength. The total volume of the aqueous phase was made up to 10 ml. The aqueous phase was equilibrated with 10 ml of 5% v/v Amberlite in nitrobenzene (amine : nitrobenzene = 1 : 20 by volume) for 5 min. The equilibration time was varied from 1-10 min and it was found that the distribution coefficient reached a constant value within 2 min. However, the equilibration time was fixed at 5 min. All the experiments were carried out at  $27 \pm 1^\circ$ . The two layers were

\* UGC Teacher Fellow on leave from U. N. College, Soro, Orissa.

allowed to settle for 10-15 min. The organic phase was then separated carefully to another separatory funnel. The aqueous phase was collected, the excess acid was neutralised by ammonia solution and the amount of zinc present in the aqueous phase was determined by EDTA titration. Then, 10 ml of 2M nitric acid solution was added to the organic phase and the mixture was shaken for 5 min. The two phases were allowed to settle, the organic phase was separated carefully and the corresponding aqueous phase (acid extract) was collected and neutralised by ammonia solution. The amount of zinc extracted in that phase was determined.

## Results and Discussion

### Hydrochloric acid concentration :

The extraction behaviour of zinc(II) with Amberlite LA-1 at various acid concentrations is given in Fig. 1. The experiments were performed with constant extractant concentration (5% v/v) and constant




Fig. 1. Extraction of Zn(II) with Amberlite LA-1 as a function of [HCl] in molarity

metal concentration ( $9.9 \times 10^{-3} M$ ). The extraction of zinc increases with increased hydrochloric acid concentration and becomes quantitative at 2M and onwards. The optimum hydrochloric acid range for quantitative extraction is therefore from 2M onwards. The distribution ratio was calculated from the extraction data using the relation

$$D = \frac{V}{V'} \left( \frac{100}{100-x} - 1 \right)$$

where V and V' are the respective volumes of the aqueous and organic phases, respectively and x is the percentage of zinc extracted<sup>1,2</sup>.

In order to evaluate the probable reaction mechanism of Zn(II) with chloride ion, the extraction, at constant ionic strength (2.3M), was carried out with varying amount of hydrochloric acid. Sodium sulphate was used to maintain the constant ionic strength. Plot of log D against log [Cl] produces a straight line (Fig. 2) with a slope of 2.1 indicating the formation of  $(ZnCl_4)^{2-}$  in the aqueous phase. At lower chloride concentration the formation of  $(ZnCl_3)^-$  is also expected. Therefore, the

reaction in the aqueous phase is proposed to be :




Fig. 2. Plot of log D against log [Cl] at constant [amine].

### Amberlite LA-1 concentration :

At constant concentration of zinc ( $9.9 \times 10^{-3} M$ ) and hydrochloric acid (2M), the extraction of zinc as a function of Amberlite LA-1 concentration in nitrobenzene was carried out. The extraction of zinc is quantitative provided the secondary amine : zinc molar ratio is  $\geq 2$ . Plot of log D against log [Amberlite LA-1] produces a straight line (Fig. 3) with slope 2. Hence the extraction mechanism of





Fig. 3. Plot of log D against log [Amberlite LA-1] at 2M HCl.

zinc(II) is proposed to be :



The zinc(II) : Amberlite LA-1 ratio in the extracted species is therefore 1 : 2.

#### Diluents :

Zinc was extracted with 5% Amberlite LA-1 solution in various diluents (Table 1). The results indicate quantitative extraction of zinc with nitrobenzene which has a high dielectric constant. But the extraction of zinc in benzene (a diluent of low dielectric constant) is more than that in other diluents of high dielectric constant. Hence a clear conclusion cannot be drawn for the diluents used for extraction. The dielectric constant is not the only factor involved.

TABLE 1—EFFECT OF DILUENTS ON EXTRACTION OF ZINC

Diluents	Dielectric constant	Metal extracted (%)	Distribution ratio ( $D_{Zn}$ )
n-Hexane	1.9	66.5	2.0
Carbon tetrachloride	2.2	30.6	0.4
Benzene	2.3	79.8	3.9
Xylene	2.4	75.7	3.1
Toluene	2.4	53.2	1.1
Chloroform	4.8	15.7	0.1
Butanol	16.1	59.0	1.4
Nitrobenzene	35.7	97.7	41.7

#### Equilibration time and stripping time :

The contact time was varied from 1 to 10 min. The distribution ratio reached a constant value after 2 min of shaking and back extraction was complete within 5 min. Therefore, the optimum equilibration period was chosen as 5 min in all the experiments.

#### Metal ion concentration :

Loading experiments, at constant concentration of both amine and hydrochloric acid, were carried out by varying amounts of zinc. More than 96.5% of zinc was extracted from 0.065 to 1.30 g/l under optimum extraction conditions. Fig. 4 shows

plot of  $\log [Zn^{2+}]_o$  against  $\log [Zn^{2+}]_a$ . The ratio of metal to amine concentration in organic phase is found to be 1 : 2 which again supports the proposed extracted species as  $[(R_2NH_2)_4(ZnCl_2)_2]^{2+}$ .

#### Extractive separations :

The effect of diverse ions on the quantitative extraction of Zn(II) at optimum condition is shown in Table 2. The metal ions like mercury, cadmium, lead, iron, bismuth and copper are coextracted. The tolerance limits for such ions as cobalt, aluminium, chromium, fluoride and iodide are low (shown in Table 2). Above these limits extraction decreases. Calcium, strontium, barium, magnesium, manganese, nickel, sulphate, phosphate and bromide do not interfere with the extraction of zinc.

TABLE 2—EFFECT OF DIVERSE IONS ON THE EXTRACTION OF Zn(II) WITH AMBERLITE LA-1  
[Zinc(II) 6.5 mg ; [HCl] 2 M]

Diverse ions	Amount added	Source	Zinc extracted (%)
Ca <sup>2+</sup>	350 mg	CaCl <sub>2</sub> ·2H <sub>2</sub> O	97.4
*Si <sup>4+</sup>	350 mg	SrCl <sub>2</sub> ·6H <sub>2</sub> O	97.4
*Ba <sup>2+</sup>	350 mg	BaCl <sub>2</sub> ·2H <sub>2</sub> O	97.4
Mg <sup>2+</sup>	200 mg	MgSO <sub>4</sub> ·7H <sub>2</sub> O	97.4
Mn <sup>2+</sup>	150 mg	MnCl <sub>2</sub> ·4H <sub>2</sub> O	97.6
Ni <sup>2+</sup>	120 mg	NiSO <sub>4</sub> ·7H <sub>2</sub> O	97.4
Co <sup>2+</sup>	15 mg	CoSO <sub>4</sub> ·6H <sub>2</sub> O	96.5
Al <sup>3+</sup>	5 mg	Al(NO <sub>3</sub> ) <sub>3</sub> ·9H <sub>2</sub> O	96.5
Cr <sup>3+</sup>	2 mg	Cr <sub>2</sub> (SO <sub>4</sub> ) <sub>3</sub> ·6H <sub>2</sub> O	96.0
SO <sub>4</sub> <sup>2-</sup>	800 mg	MgSO <sub>4</sub> ·7H <sub>2</sub> O	97.4
PO <sub>4</sub> <sup>3-</sup>	450 mg	Na <sub>2</sub> HPO <sub>4</sub>	97.4
Br <sup>-</sup>	250 mg	KBr	96.5
F <sup>-</sup>	40 mg	NH <sub>4</sub> HF <sub>2</sub>	96.5
I <sup>-</sup>	20 mg	KI	96.0

\* Zn(OAc)<sub>2</sub> was used instead of ZnSO<sub>4</sub>.

#### Separation of zinc from synthetic mixtures :

Quantitative separation of zinc from some synthetic mixtures was attempted and the results are shown in Table 3. Figures in parenthesis against an ion indicate the amount of the ion present in milligrams.




Fig. 4. Plot of  $\log [Zn^{2+}]_o$  vs  $\log [Zn^{2+}]_a$ .

TABLE 3—QUANTITATIVE SEPARATION OF ZINC(II) FROM SYNTHETIC MIXTURES USING AMBERLITE LA-1

Sample No.	[Zinc(II) 6.5 mg ; [HCl] 2M] Mixture taken (mg)	Zinc extracted (%)
*1.	Ca <sup>++</sup> (175)+Sr <sup>++</sup> (175)	96.5
*2.	Ca <sup>++</sup> (175)+Ba <sup>++</sup> (175)	98.6
3.	Ca <sup>++</sup> (175)+Mg <sup>++</sup> (100)	96.5
*4.	Ba <sup>++</sup> (175)+Sr <sup>++</sup> (150)	98.0
5.	Mn <sup>++</sup> (50)+Ni <sup>++</sup> (50)	97.4
6.	Mn <sup>++</sup> (60)+Co <sup>++</sup> (8)	96.5
7.	Mn <sup>++</sup> (60)+Al <sup>++</sup> (2)	97.4
8.	Ni <sup>++</sup> (50)+Co <sup>++</sup> (8)	97.4
*9.	Ca <sup>++</sup> (100)+Sr <sup>++</sup> (100)+Ba <sup>++</sup> (100)	97.4
10.	Mn <sup>++</sup> (20)+Ni <sup>++</sup> (20)+Co <sup>++</sup> (5)	96.5
11.	Mn <sup>++</sup> (15)+Ni <sup>++</sup> (15)+Al <sup>++</sup> (2)	96.0
12.	Ni <sup>++</sup> (10)+Co <sup>++</sup> (5)+Al <sup>++</sup> (2)	96.0

\* Zn(OAc)<sub>2</sub> was used instead of ZnSO<sub>4</sub>.

### Acknowledgement

One of the authors (N. P.) is grateful to the University Grants Commission, New Delhi for the award of a Teacher Fellowship and also to the Principal, U. N. College, Soro, Orissa for study leave.

### References

1. A. K. DE and U. S. RAY, *Sep. Sci.*, 1971, 6, 25
2. A. K. DE and U. S. RAY, *Sep. Sci.*, 1971, 6, 443.
3. A. K. DE and U. S. RAY, *Sep. Sci.*, 1972, 7, 449.
4. A. K. DE and U. S. RAY, *Sep. Sci.*, 1972, 7, 419.
5. U. S. RAY and S. C. MODAK, *Sep. Sci. Tech.*, 1981, 16, 81.
6. A. PUSPARAJA and M. SUDERSANAN, *Indian J. Chem.*, 1980, 19(A), 925.
7. H. A. MAHLMAN, G. W. LEDDICOTTE and F. L. MOORE, *Anal. Chem.*, 1954, 26, 1939
8. O. V. SINGH and S. N. TANDON, *J. Inorg. Nuclear Chem.*, 1977, 36, 2083
9. L. E. SCROGGIE and J. A. DEAN, *Anal. Chim. Acta*, 1969, 21, 282.
10. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", Longman, London, 3rd. Ed., 1962.
11. R. FRIBIL, "Chelometry, Basic Determinations", Chemapol, Prague, 1961.
12. A. K. DE, R. A. CHALMERS and S. M. KHOPKAR, "Solvent Extraction of Metals", Van Nostrand, London, 1970
13. G. H. MORRISON and H. FREISER, "Solvent Extraction in Analytical Chemistry", Wiley, New York, 1957.

# Solvent Extraction Studies on Thiocyanate Complexes of Zinc(II), Cadmium(II) and Mercury(II)

DEVENDRA SINGH, O. V. SINGH and S. N. TANDON\*

Department of Chemistry, University of Roorkee, Roorkee-247 667

The extraction behaviour of zinc(II), cadmium(II) and mercury(II) thiocyanate complexes has been studied in some oxygenated solvents, high molecular weight amines, tributyl phosphate and pyridine. The effect of different variables on extraction has been investigated. The extracting species have been identified using loading ratio data and by the method of slope analysis. On the basis of extraction data some mutual separations and separations from other commonly associated elements have been carried out. Relative merits and limitations of different extraction systems are discussed.

THE thiocyanate ion is a well known ligand and forms complexes with numerous metal ions which are usually stoichiometrically analogous to the corresponding halo complexes. In view of its strong complexing nature this ion has been widely employed in various areas of chemical analysis including solvent extraction of metal ions<sup>1</sup>. Earlier reports indicate that a large number of investigations have been carried out on the extraction of metal thiocyanate complexes in different extraction systems. However, not much work<sup>1,2</sup> was reported on the extraction of zinc(II), cadmium(II) and mercury(II) as thiocyanates. The separations involving cadmium and mercury are of particular interest to environmentalists as the two elements are serious pollutants of the biosphere.

Studies were initiated in this laboratory sometimes back on the extraction of Zn(II), Cd(II) and Hg(II) thiocyanate complexes in some oxygenated solvents<sup>3</sup>, high molecular weight amines (HMWA)<sup>4-7</sup> and in non-polar solvents in the presence of neutral donors like tri-*n*-butyl phosphate<sup>8</sup> and pyridine<sup>9</sup>. These investigations mainly dealt with the studies on the mechanism of extraction and utilized the extraction data for obtaining some typical separations of metal ions.

The present paper summarizes the results of these investigations on the extraction of thiocyanate complexes of Zn(II), Cd(II) and Hg(II). The extracting species have been mainly identified by the method of slope analysis. However, in the case of extractions in high molecular weight amines, the extracting species have also been identified by extraction isotherms and analysis of the organic extract at the maximum loading conditions. In Hg(II)-thiocyanate neutral ligand systems, the species could not be identified because of nonconclusive results. The extraction behaviour of some other commonly associated elements has also been studied under identical conditions and based on the extraction data some mutual binary separations have been proposed. Attempts have been made to compare the efficiency of different systems for attaining metal ion separations involving Zn(II), Cd(II) and Hg(II).

## Experimental

All inorganic chemicals and organic solvents used were of analytical grade. Primene JM-T and Amberlite LA-1 (Rohm and Haas Co., U.S.A.) and Alamine 336 and Aliquat 336 (General Mills, Inc., U.S.A.) were all practical grade materials and used without further purification. The metal ion solutions were generally prepared from sulphate salts and standardised by standard methods. <sup>54</sup>Mn, <sup>65</sup>Co, <sup>65</sup>Zn, <sup>110m</sup>Ag, <sup>114m</sup>In, <sup>115m</sup>Cd, <sup>203</sup>Hg and <sup>204</sup>Tl radioisotopes, procured from the Bhabha Atomic Research Centre, Bombay, were used as tracers for the distribution studies. The distribution ratio and percent extraction were determined by the usual method.

## Results and Discussion

### Extraction in oxygenated solvents :

The extraction behaviour of zinc(II), cadmium(II) and mercury(II) was studied from aqueous thiocyanate solutions into *n*-butanol, nitrobenzene and ethyl acetate (Fig. 1). Generally, the extractions are poor in nitrobenzene. The extraction of zinc(II) increases upto a thiocyanate concentration of 0.1M and thereafter becomes almost constant. On the other hand the extraction of mercury(II) decreases upto 0.1M and remains almost constant thereafter. Cadmium(II), thallium(I) and thallium(III) show negligible extraction in all the solvents.

Mercury(II) can be separated from cadmium(II), thallium(I) and thallium(III) by extracting it into *n*-butanol from  $\leq 0.02M$  thiocyanate solution. Zinc(II) can be separated from cadmium(II), thallium(I) and thallium(III) by extracting into *n*-butanol or ethyl acetate at thiocyanate concentration  $\geq 0.1M$ .

### Extraction of thiocyanate complexes of zinc(II), cadmium(II) and mercury(II) in HMWA :

The extraction behaviour of Zn(II), Cd(II) and Hg(II) from aqueous thiocyanate solutions, as studied in chloroform and benzene solutions of






Fig. 1. Extraction of Zn(II) and Hg(II) from thiocyanate solutions by oxygenated solvents Zn(II) x-n-butanol, □-ethyl acetate Hg(II) : ●-n-butanol (equilibrated), ---n-butanol (unequibrated), ○-nitrobenzene, Δ-ethylacetate.




Fig. 2. Extraction of Zn(II) from  $\text{NH}_4\text{SCN}$  solutions by various 0.1M amines in chloroform and benzene. Chloroform solvent : (1) Primene JM-T ; (2) Amberlite LA-1 ; (3) Alamine 336 ; (4) Aliquat 336. Benzene solvent : (5) Primene JM-T, (6) Amberlite LA-1 ; (7) Alamine 336 ; (8) Aliquat 336.




Fig. 3. Extraction of Cd(II) from  $\text{NH}_4\text{SCN}$  solutions by various 0.1M amines in chloroform and benzene. Chloroform solvent : (1) Primene JM-T ; (2) Amberlite LA-1 ; (3) Alamine 336 ; (4) Aliquat 336. Benzene Solvent : (5) Primene JM-T ; (6) Amberlite LA-1 ; (7) Alamine 336 ; (8) Aliquat 336.




Fig. 4. Extraction of Hg(II) from  $\text{NH}_4\text{SCN}$  solutions by various 0.1M amines in chloroform and benzene. Chloroform solvent: (1) Primene JM-T; (2) Amberlite LA-1; (3) Alamine 336; (4) Aliquat 336. Benzene solvent: (5) Primene JM-T; (6) Amberlite LA-1; (7) Alamine 336; (8) Aliquat 336.

different liquid anion exchangers, is shown in Figs. 2, 3 and 4, respectively. The extraction of all the three metal ions increases with decreasing thiocyanate concentration with a tendency to attain a limiting value. The effect of pH of the aqueous phase on the extractions was found to be negligible within the pH range 2.0 to 5.0. The extraction behaviour of these elements is more or less similar to their sorption on solid anion-exchange resins<sup>10</sup>. The extractive power of the various amines for all these elements follows the order:

primary < secondary < tertiary < quaternary. It is also apparent from these extraction studies that the extractions with benzene as diluent are, generally, higher than those obtained with chloroform diluent. The extractions of these elements in a particular amine-diluent system are in accordance with the stability<sup>11</sup> of their respective thiocyanate complexes in aqueous solutions i.e.  $\text{Cd} < \text{Zn} < \text{Hg}$ .

#### Identification of the extracted species:

The stoichiometry of the extracted species has been determined by extraction isotherms, log-log plots of amine concentration versus distribution ratio and analysis of organic extract at maximum loading conditions. The results on extracted species are summarized in Table 1. It is apparent from the results of the various methods employed to determine the nature of the extracting species that there is a fairly good agreement between the results of loading experiments and analysis data. But in some

TABLE 1—RESULTS ON IDENTIFICATION OF EXTRACTING SPECIES IN HMWA

Metal ion	Amine	Species identified by		
		Log-log plot	Extraction isotherm	Analysis of organic extract
$\text{Zn}^{++}$	Alamine 336	$\text{Zn}(\text{SCN})_2^-$ and $\text{Zn}(\text{SCN})_3^{2-}$	$\text{Zn}(\text{SCN})_2^-$	$\text{Zn}(\text{SCN})_2^-$
	Aliquat 336	$\text{Zn}(\text{SCN})_2^-$ and $\text{Zn}(\text{SCN})_3^{2-}$	$\text{Zn}(\text{SCN})_2^-$	$\text{Zn}(\text{SCN})_2^-$
$\text{Cd}^{++}$	Aliquat 336	$\text{Cd}(\text{SCN})_2^-$	$\text{Cd}(\text{SCN})_2^-$	$\text{Cd}(\text{SCN})_2^-$
$\text{Hg}^{++}$	Alamine 336	$\text{Hg}(\text{SCN})_2^-$	$\text{Hg}(\text{SCN})_2^-$	$\text{Hg}(\text{SCN})_2^-$
	Aliquat 336	$\text{Hg}(\text{SCN})_2^-$ and $\text{Hg}(\text{SCN})_3^{2-}$	$\text{Hg}(\text{SCN})_2^-$	$\text{Hg}(\text{SCN})_2^-$

cases the results of these two methods do not agree with those of log-log plots. This anomaly is, generally, attributed to the largely different experimental conditions existing in the two methods. In log-log plots, the metal ion concentration is extremely low ( $< 10^{-6}M$ ) whereas a much higher concentration has been used for extraction isotherms. Besides this, varying amine concentration, and higher amine to metal ratios have been used in log-log plots. The possibility of extraction of the different species at the different experimental conditions cannot be ruled out. However, more reliance can be placed on the results of the extraction isotherms because these results are confirmed by the analysis of the organic extract at the maximum loading conditions.

#### Separations:

In order to explore the thiocyanate-HMWA system for some useful separations, the extraction behaviour of indium(III) and thallium(III) has also been studied under identical experimental conditions. The best conditions of separation, based on the extraction data are given in Table 2. The efficiency of the different separations is indicated by the separation coefficients listed therein. In most of the cases the metal ion from the organic phase can be stripped by washing it with water or an appropriate concentration of nitric acid.

#### Extraction of zinc and cadmium thiocyanate complexes in benzene in the presence of tri-n-butyl phosphate and pyridine:

The extraction of zinc(II) and cadmium(II) thiocyanate complexes was studied by tributyl phosphate (TBP) and pyridine, diluted with benzene. The effect of pH on extraction was studied at 1.0 M  $\text{NH}_4\text{SCN}$  and a fixed concentration of TBP or pyridine. In TBP, the extraction of both the metal ions is almost independent of pH within the range 3.0-6.0. However, in the case of pyridine, the extraction increases with increasing pH of the aqueous phase and the plots of pH versus log D gave straight lines with slopes close to 1 for both the metal ions. At constant concentration of TBP or pyridine the extractions of  $\text{Zn}(\text{II})$  and  $\text{Cd}(\text{II})$

TABLE 2—MUTUAL BINARY SEPARATIONS OF Zn(II), Cd(II), Hg(II), In(III) AND Tl(III) BY VARIOUS AMINES (0.1 M) IN CHLOROFORM AND BENZENE



Metal ions separated	Extractant	Molarity of $\text{NH}_4\text{SCN}$	Separation coefficient ( $\beta$ )
Zn(II) from Cd(II)	Amberlite LA-1 in chloroform	0.1	$3.6 \times 10^3$
	Alamine 336 in chloroform	0.5	$1.3 \times 10^3$
Hg(II) from Cd(II)	Amberlite LA-1 in chloroform	0.5	$4.6 \times 10^3$
	Alamine 336 in chloroform	0.5	$2.8 \times 10^3$
Zn(II) from Tl(III)	Aliquat 336 in benzene	0.1–4.0	$>10^4$
	Aliquat 336 in chloroform	0.1–4.0	$>10^4$
H. (II) from Tl(III)	Aliquat 336 in benzene	0.1–4.0	$>10^4$
	Aliquat 336 in chloroform	0.1–4.0	$>10^4$
Cd(II) from Tl(III)	Aliquat 336 in benzene	0.1–4.0	$>10^4$
	Aliquat 336 in chloroform	0.1–4.0	$>10^4$
In(III) from Tl(III)	Aliquat 336 in benzene	0.1–4.0	$>10^4$

increase with increasing concentration of thiocyanate. The plots of  $\log D$  versus  $\log [\text{NH}_4\text{SCN}]$  are linear with slopes around 1, thus suggesting that  $[\text{M}(\text{SCN})]^+$  species are getting extracted into the organic phase. The existence of  $[\text{Zn}(\text{SCN})]^+$  and  $[\text{Cd}(\text{SCN})]^+$  species in aqueous solutions was reported by Chiang and Hsu<sup>19</sup> and Hume *et al.*<sup>18</sup>.

The dependence of extraction on the concentration of TBP or pyridine was studied at constant  $\text{NH}_4\text{SCN}$  concentration. The log-log plots of extractant concentration versus distribution ratio gave straight lines with slope around 2 and 4 for zinc and cadmium, respectively

On the basis of the above results, the species being extracted are inferred to be  $[\text{Zn}(\text{SCN})_2\text{TBP}]^+$ ,  $[\text{Zn}(\text{SCN})_2\text{py}]^+$ ,  $[\text{Cd}(\text{SCN})_4\text{TBP}]^+$  and  $[\text{Cd}(\text{SCN})_4\text{py}]^+$ . Such species should not be extracted into a non polar medium like benzene, since they are

charged. Therefore, it is assumed that some anion,  $\text{X}^-$ , is associated to make the species neutral and thus extractable into benzene. For pyridine system,  $\text{X}^-$  may be either  $\text{OH}^-$  or  $\text{ClO}_4^-$  but for TBP system the possibility of  $\text{OH}^-$  is ruled out because the extractions are almost independent of pH. The possibility of  $\text{ClO}_4^-$  has been suggested because it is present in larger excess in the aqueous phase as perchloric acid has been used for adjusting the pH.

Fig. 5. Extraction of different metals from aqueous  $\text{NH}_4\text{SCN}$  solutions by 1.0 M TBP in benzene.Fig. 6. Extraction of different metals from aqueous  $\text{NH}_4\text{SCN}$  solutions by 0.1 M pyridine in benzene.

The extraction behaviour of silver(I), manganese(II), cobalt(II), mercury(II) and thallium(III) in addition to zinc(II) and cadmium(II) has been studied as a function of  $\text{NH}_4\text{SCN}$  concentration keeping the concentration of TBP or pyridine constant (Figs. 5 and 6). On the basis of the extraction data it has been possible to achieve some typical separations of analytical and radiochemical interest. The conditions for various separations along with

separation factors are given in Tables 3 and 4. In all the cases, metal ion from the organic phase can be conveniently stripped by washing it with distilled water.

TABLE 3—SEPARATION OF Zn(II) FROM Ag(I), Mn(II), Co(II), Cd(II), Hg(II) AND Tl(III) FROM  $\text{NH}_4\text{SCN}$  SOLUTIONS BY TBP (1.0 M) IN BENZENE

Zn(II) separated from	Molarity of $\text{NH}_4\text{SCN}$	Separation coefficient ( $\beta$ )
Ag(I)	0.5	$9 \times 10^3$
Mn(II)	0.05	$3.4 \times 10^3$
Co(II)	0.1	$3 \times 10^3$
Cd(II)	0.05	$7.2 \times 10^3$
Hg(II)	0.5	$5 \times 10^3$
Tl(III)	0.01–1.0	$> 10^4$

TABLE 4—SOME BINARY METAL ION SEPARATIONS FROM  $\text{NH}_4\text{SCN}$  SOLUTIONS BY PYRIDINE (0.1 M) IN BENZENE

Metal ions separated	Molarity of $\text{NH}_4\text{SCN}$	Separation coefficient ( $\beta$ )
Mn(II)–Co(II)	0.5	$6.6 \times 10^3$
Zn(II)–Hg(II)	0.5	$2 \times 10^3$
Zn(II)–Ag(I)	0.5	$4 \times 10^3$
Cd(II)–Ag(I)	0.5	$2 \times 10^3$
Cd(II)–Hg(II)	0.5	$2 \times 10^3$
Cd(II)–Tl(III)	0.1–0.5	$> 10^4$

#### Conclusion :

The present studies on the extraction of metal ions as thiocyanate reveal that most of the metal ions investigated show negligible extraction in non-oxygenated solvents. Some of the metal ions are extracted by oxygenated solvents but the extractions, in general, are not quantitative. High molecular weight amines are better extractants for Zn(II), Cd(II), Hg(II) and In(III) from aqueous thiocyanate

solutions. These amine extraction systems are more useful for the separations and provide conditions for metal ion separations like Zn(II)–Cd(II), Cd(II)–Hg(II), Cd(II)–Tl(III), Hg(II)–Tl(III) and In(III)–Tl(III) (Table 2) with high separation factors. The tributyl phosphate system is only useful for the separation of Zn(II) from other metal ions, while the pyridine thiocyanate system is more versatile and offers conditions for a variety of binary metal ion separations, viz., Mn(II)–Co(II), Zn(II)–Hg(II), Zn(II)–Ag(I), Cd(II)–Ag(I), Cd(II)–Hg(II) and Cd(II)–Tl(III). To conclude, the thiocyanate-HMWA systems are more versatile and generally provide separations with higher separation factors.

#### References

1. C. ROZYCKI, *Chem. Anal.*, 1971, 16, 291 and references cited therein.
2. G. J. DE JONGE, U. A. TH. BRINKMAN and W. TH. KOK, *J. Radioanal. Chem.*, 1977, 35, 245.
3. C. B. GUPTA, Ph.D. Thesis, University of Roorkee, 1972.
4. D. SINGH, O. V. SINGH and S. N. TANDON, *Sep Sci and Tech.*, 1978, 13, 625.
5. D. SINGH and S. N. TANDON, *J. Inorg. Nuclear Chem.*, 1978, 40, 1803.
6. D. SINGH, O. V. SINGH and S. N. TANDON, *Z. anorg allg. Chem.*, 1978, 443, 279.
7. D. SINGH, O. V. SINGH and S. N. TANDON, *Chem. Anal.*, 1979, 24, 1055.
8. D. SINGH, O. V. SINGH and S. N. TANDON, *Anal. Chim. Acta*, 1980, 115, 369.
9. D. SINGH, J. M. SINGH, O. V. SINGH and S. N. TANDON, *J. Radioanal. Chem.*, 1979, 54, 69.
10. D. SINGH and S. N. TANDON, *Talanta*, 1979, 26, 161.
11. L. G. SILLEN and A. E. MARTELL, "Stability Constants of Metal Ion Complexes", Chem. Soc. (London), Special Publication No. 25, Supplement No. 1, 1971, p. 65,66.
12. H. C. CHIANG and K. H. HSU, *K. O. Hauch Tung Pao*, 1959, 11, 365.
13. D. N. HUME, D. D. DE FORD and G. C. B. CAVE, *J. Amer. Chem. Soc.*, 1951, 23, 5323.

# The Extraction of Chromium(VI) from Mineral Acid Solutions by Trilaurylamine-Oxide

M V N. MURTY, V. M. RAO and M. N. SASTRI

Department of Chemistry, Andhra University, Waltair-530 003

Extraction of chromium(VI) from hydrochloric, sulphuric, nitric and orthophosphoric acid solutions by trilaurylamine-oxide (TLAO) in chloroform has been studied. The nature of the extracted chromium(VI) species is established

**H**ELLER<sup>1</sup> was the first to point out the possibility of using amine-oxides as extracting agents, but was unable to carry out extraction because the self-synthesised compounds of uranyl nitrate with heterocyclic amine-oxides (pyridine-N-oxide and quinoline-N-oxide) were not soluble in organic solvents. Later, several workers<sup>2-7</sup> exploited the potentialities of these reagents as extractants for several metals. We report in this communication the extraction of chromium(VI) by trilaurylamine-oxide (TLAO) from hydrochloric, sulphuric, nitric and orthophosphoric acid solutions

## Experimental

**Materials:** Chromic acid (E Merck) was used for preparing chromium(VI) stock solution (0.1M) Chromium-51 in the form of sodium chromate in isotonic saline solution (15 mCi/mg specific activity) and Chlorine-36 as hydrochloric acid solution (5-25 mCi/g specific activity) were obtained from the Isotope Division, Bhabha Atomic Research Centre, Bombay. Trilaurylamine-oxide (TLAO) was synthesised by the method described by Davies and Hetzer<sup>8</sup>. Its purity was checked by determining the melting point (m.p. 72°) and molecular weight (cryoscopic method) and by identifying the characteristic IR absorption band for N→O at 965 cm<sup>-1</sup>. The sample was kept in dry atmosphere in a desiccator over silica gel and in a refrigerator when not in use.

A Single Channel Analyser SC 600 (ECIL, Hyderabad) coupled with a 3" Well type scintillation detector (Nuclear Chicago) was used for  $\gamma$ -activity measurements.  $\beta$ -Activities of the solutions were measured with a liquid G.M. counter.

**Procedure:** Aqueous solutions (10 ml) containing appropriate concentrations of chromic acid, added tracer and mineral acid were equilibrated for 3-5 min with an equal volume of 0.025M TLAO in chloroform. The two phases were then separated by allowing the mixture to settle for 5 min and centrifuging, if necessary. Equal aliquots (5 ml) of each phase were used to measure the activities from which the distribution coefficient ( $k_d$ ) was calculated. No volume change in the aqueous and organic phases was observed after equilibration.

## Results and Discussion

Bazinger *et al*<sup>9</sup> reported the extraction of acids by aliphatic amine-oxides as  $(R_3N \rightarrow O \cdot H \cdot O \leftarrow NR_3)^+ \cdot A^-$  and as  $2 R_3N \rightarrow OH^+ \cdot A^-$ , respectively from low and high acid media. The formation of such salts has been reported<sup>10</sup> in the case of heterocyclic amine-oxides.

The extraction of chromium(VI) (0.01 M) with TLAO/chloroform (0.025 M) was studied as a function of aqueous phase concentrations of hydrochloric, sulphuric, nitric and orthophosphoric acid solutions. The  $k_d$  values are independent of aqueous phase acidity upto 2 M in the case of hydrochloric and sulphuric acid solutions and upto 3 M with orthophosphoric acid, beyond which a gradual fall is noticed. On the other hand the extraction is comparatively much less in nitric acid solutions with a gradual fall in  $k_d$  with increasing acidity even in the 0.01-0.1M acidity range. The decrease in  $k_d$  with increasing acidity in all these systems can be explained [by analogy to the U(VI)-HCl-TOAO system<sup>2</sup>] as due to the decrease in the effective amine-oxide concentration by its bonding to the acid or a competitive extraction process in which the anionic part of the acid preferably gets extracted by the amine-oxide (e.g.  $RNOH^+A^-$ ). The extraction of chromium(VI) is nearly quantitative from hydrochloric acid medium (% extraction = 98.80 at  $\leq 2$  M HCl), as compared with sulphuric acid (% extraction = 99.80 at  $\leq 2$  M  $H_2SO_4$ ) and orthophosphoric acid (% extraction = 99.85 at  $\leq 3$  M  $H_3PO_4$ ) solutions. Addition of NaCl,  $Na_2SO_4$ ,  $NaH_2PO_4$  and  $NaNO_3$  to aqueous phases resulted in a significant decrease in extraction, the decrease being in the order  $HNO_3 > HCl > H_2SO_4 \approx H_3PO_4$ .

The extraction of chromium(VI) as a function of metal concentration [in the concentration range  $10^{-5}$ - $10^{-2}$  mg/ml of Cr(VI)] with TLAO/chloroform (0.025 M) was studied. The log-log plot of the equilibrium chromium(VI) concentration in the aqueous phase vs organic phase at initial aqueous phase acidities of 0.1 M and 1.0 M with respect to HCl,  $H_2SO_4$  and  $H_3PO_4$  gave straight lines of unit slope, indicating that the extracted chromium(VI) species is monomeric in nature. Under the experimental conditions [max. concentration of Cr(VI) employed is  $5.2 \times 10^{-3}$  mg/ml], chromium(VI) exists predo-

TABLE 1—DATA ON THE COMPOSITION OF THE ORGANIC PHASES OBTAINED AFTER EXTRACTION OF CHROMIUM(VI) FROM HCl SOLUTIONS WITH 0.025 M TLAO

Initial aqueous phase (M)		Equilibrium organic phase (M)			Molar ratio organic phase TLAO : Cr(VI) : Cl <sub>2</sub>
[Cr(VI)]	[HCl]	[Cr(VI)]	[Cl <sub>2</sub> ]	[Cl <sup>-</sup> ] (Blank)	
0.03	0.05	0.0250	0.0250	0.0244	1 : 1 : 0.024
0.03	0.10	0.0250	0.0260	0.0244	1 : 1 : 0.024
0.03	0.30	0.0250	0.0295	0.0248	1 : 1 : 0.188
0.03	0.50	0.0250	0.0348	0.0255	1 : 1 : 0.372
0.03	1.00	0.0250	0.0440	0.0260	1 : 1 : 0.720
0.03	2.00	0.0250	0.0450	0.0265	1 : 1 : 0.740
0.04	1.00	0.0250	0.0440	0.0260	1 : 1 : 0.720
0.05	1.00	0.0250	0.0440	0.0260	1 : 1 : 0.720

minantly as monomeric oxyanion<sup>11</sup> i.e.  $\text{HCrO}_4^-$  in the aqueous phase. Therefore the extraction of chromium(VI) as protonated oxyanion can be envisaged. This is in conformity with the observation that other elements which form oxyanions in their highest oxidation states are extracted as protonated oxyanions [e.g.  $\text{W(VI)}$ <sup>12</sup>,  $\text{Mo(VI)}$ <sup>13</sup>,  $\text{Re(VII)}$ <sup>14</sup> and  $\text{Te(VI)}$ <sup>15</sup>] by oxygen donor extractants

number is close to unity (1.05 at 0.1M HCl). As the concentration of the acid in the aqueous phase is increased, the stoichiometric ratio of the components in the organic phase increases gradually, indicating that different extraction mechanisms are operating probably due to the formation of a mixture of solvated chromium(VI) species. The extraction of chloride as a function of aqueous hydrochloric acid concentration (0.25–2.0 M) in the presence of chromium(VI) (0.03 M) was studied with TLAO/chloroform (0.025 M), using <sup>36</sup>Cl as radiotracer. The concentration of chloride in the organic phase increased with increasing acidity (Table 1) indicating that the extracted chromium(VI) is a mixture of species containing predominantly  $\text{HCrO}_4\text{Cl}$  at higher acidities. The extraction of protonated chromium(VI) species from mineral acid solutions by oxygen donor solvents TBP<sup>16,18</sup> and TOPO<sup>17</sup> was earlier reported. The existence of such species in aqueous acid systems at high acidities (> 2 M) was also reported by several workers<sup>19,20</sup>.

The observed Cr : TLAO mole ratio of 2, from sulphuric, nitric and orthophosphoric acid solutions could be explained as arising from the extraction of chromium(VI) species in the form of  $2\text{R}_3\text{NO} \cdot \text{H}_2\text{CrO}_4$ . On the other hand, the alteration of mole ratio from hydrochloric acid solutions with increasing acidity suggests extraction of a mixture of chromium(VI) species in the form of  $\text{R}_3\text{NO} \cdot \text{H}_2\text{CrO}_4$  and/or  $\text{R}_3\text{NO} \cdot \text{HCrO}_4\text{Cl}$  at higher acidities (> 0.1 M) and as  $\text{R}_3\text{NO} \cdot \text{H}_2\text{CrO}_4$  at lower acidities (< 0.1 M).

#### Acknowledgement

One of the authors (M. V. N. M.) is thankful to the University Grants Commission, New Delhi for the award of a Teacher Fellowship under the Faculty Improvement Programme.

#### References

1. A. HELLER, Israel At. Energy Comm. Rept. IA-601, 1960.
2. M. IJAZ, *Sepr. Sci.*, 1975, 10, 425.
3. M. IJAZ, *Anal. Chem.*, 1976, 48, 1158.
4. J. KENNEDY and R. PERKINS, *J. Inorg. Nuclear Chem.*, 1964, 26, 1601.
5. V. G. TORGOV, A. V. NIKOLOV, V. A. MIHAILOV and I. L. KOTYAREVSKI, *Dok. Acad. Nauk. SSSR*, 1964, 156, 616.
6. V. G. TORGOV and V. A. MAHAILOV, *Zh. Neorg. Khim.*, 1965, 10, 2780.




Fig. 1. Variation of the distribution coefficient ( $k_d$ ) for chromium(VI) ( $5.2 \times 10^{-3}$  mg/ml) in hydrochloric, sulphuric and orthophosphoric acid solutions as a function of TLAO concentration in chloroform.

The log-log plots of  $k_d$  vs (TLAO) (Fig. 1b) from invariable concentrations of sulphuric and orthophosphoric acid solutions (0.1M, 0.5M and 1.0M) gave a square law  $k_d$  dependence on the amine-oxide, irrespective of the acid concentration indicating the formation of disolvates. On the other hand, the slope analysis of the distribution data in hydrochloric acid system (Fig. 1a) indicates that the solvation number depends on the concentration of the acid. At low acid concentration the slope of the log  $k_d$  vs log (TLAO) plot shows that the solvation

MURTY, RAO & SASTRI : THE EXTRACTION OF CHROMIUM(VI) FROM MINERAL ACID SOLUTIONS ETC.

7. V. G. MAKSDIMOVIC and R. G. PUZIC, *J. Inorg. Nuclear Chem.*, 1972, 34, 1031.
8. M. M. DAVIES and H. B. HFTZER, *J. Amer. Chem. Soc.*, 1954, 76, 4247.
9. N. N. BAZINGER, G. D. GALPERN, N. G. IVANOVA and G. A. SEMESKHINA, *Zh. Anal. Khim.*, 1968, 23, 1538.
10. E. OCHAI, "Aromatic Amine-oxides", Elsevier, Amsterdam, 1967, p. 117, 322.
11. K. B. OLDHAM, *Educ. Chem.*, 1965, 2, 7.
12. H. AREND and H. SPECKER, *Z. anorg. allg. Chem.*, 1964, 333, 18.
13. J. J. BUCHER and R. M. DIAMOND, *J. Phys. Chem.*, 1969, 73, 675.
14. A. S. KERTES and A. BECK, *J. Chem. Soc.*, 1961, 1922.
15. D. G. TUCK and R. M. WAITERS, *J. Chem. Soc.*, 1963, 1111.
16. H. AREND and H. SPECKER, *Naturwiss.*, 1961, 48, 524.
17. M. V. N. MURTY, V. M. RAO and M. N. SASTRI, *J. Indian Chem. Soc.*, 1980, 57, 688.
18. G. P. HEIGHT, JR., C. RICHARDSON and N. H. COUBURN, *Inorg. Chem.*, 1964, 3, 1777.
19. D. G. LEE and R. STEWART, *J. Amer. Chem. Soc.*, 1964, 86, 3051 and references therein.

# Cation Exchange Chromatographic Separation of Manganese in Mixed Solvent Systems

A. G. GAIKWAD and S. M. KHOPKAR

Department of Chemistry, Indian Institute of Technology, Powai, Bombay-400 076

Cation exchange chromatographic behaviour of manganese(II) on Dowex 50W-X8 was studied in mixed solvent systems. Methanol, ethanol, 2-propanol, acetone, dioxane and tetrahydrofuran in conjunction with 2 M hydrochloric acid were used as eluants.

Amongst the non-aqueous solvents tested, acetone, methanol and ethanol proved to be efficient while 2-propanol, dioxane and tetrahydrofuran had no practical utility. The separation of manganese from binary mixture containing alkali metals, alkaline earth metals and some other associated elements was carried out by the process gradient elution as well as selective elution using combinations of different organic solvents. Similarly, separation of multicomponent mixtures of six elements commonly associated with manganese was done by sequential separation in the mixed solvent system.

**A**LTHOUGH cation exchange chromatographic<sup>1</sup> behaviour of manganese was studied on Dowex 50W-X8, such studies in the mixed solvent systems are lacking.

The exchange constant in methanol and ethanol media was determined<sup>2</sup> on cationite KU-2. The separation of manganese from nickel<sup>3</sup> was effected using this information. Similarly, manganese was separated from copper in acetone-hydrochloric acid solutions<sup>4</sup>. The cation exchange studies for manganese, cobalt and magnesium<sup>5</sup> was carried out in mineral acids containing alcohols. Manganese was separated from nickel<sup>6</sup> with glycine. However, cation exchange separations of manganese in mixed solvent systems such as methanol, ethanol, 2-propanol, acetone, dioxane and tetrahydrofuran are lacking. This paper presents such studies. Various interesting separations have also been achieved and reported.

## Experimental

### Apparatus and reagents :

The ion-exchange column (1.4 × 20 cm) was similar to the one described earlier<sup>7</sup>. A digital pH meter (ECIL India, type pH-822) with glass and calomel electrodes was used.

A stock solution of manganese was prepared by dissolving 4.5 g of manganese chloride tetrahydrate in 250 ml distilled water containing 1% hydrochloric acid. It was standardized complexometrically<sup>8</sup>, and was found to contain 5.10 mg/ml of manganese. Dowex 50W-X8 (Dow Chemical Co., Midland, Mich., U.S.A.) 20-50 mesh (H<sup>+</sup> form) was used.

### General procedure :

(a) *Procedure for cation exchange studies :* An aliquot of the stock solution, containing 10-20 mg of manganese, was sorbed on the column at flow rate

TABLE I—CATION EXCHANGE STUDIES OF MANGANESE WITH MINERAL ACIDS AS ELUANT

Eluant (M)	Peak elution volume $V_{max}$ , ml	Total elution volume $V_t$ , ml	Manganese recovery (%)	Elution constant (E)	Volume distribution coeff ( $D_v$ )	Weight distribution coefficient ( $D_w$ )
HCl	1	200	19.8	—	—	—
	2	200	100.0	0.58	1.74	1.21
	3-4	150	100.0	1.08	0.93	0.65
HNO <sub>3</sub>	1	200	17.4	—	—	—
	2	225	100.0	0.39	2.55	1.77
	3	175	100.0	0.58	1.74	1.21
	4	150	100.1	1.08	0.93	0.65
H <sub>2</sub> SO <sub>4</sub>	1	200	83.9	—	—	—
	2	150	100.1	1.08	0.93	0.65
	3-4	100	100.0	1.08	0.93	0.65
HClO <sub>4</sub>	1	200	88.4	—	—	—
	2	200	100.0	0.39	2.55	1.77
	4	175	100.1	0.58	1.74	1.21



TABLE 2—CATION EXCHANGE STUDIES OF MANGANESE(II) IN MIXED SOLVENT SYSTEMS

Mn(II) 10.2 mg	Weight of resin = 12.55 g	Column = 1.4 × 20 cm	Resin = Dowex 50 W - X8 (H <sup>+</sup> form)			
Organic solvents m (%) with 2 M HCl	Peak elution volume V <sub>max</sub> , ml	Total elution volume V <sub>t</sub> , ml	Manganese recovery (%)	Elution constant (E)	Volume distribution coefficient (D <sub>v</sub> )	Weight distribution coefficient (D <sub>w</sub> )
Methanol						
20	75	250	100.00	0.58	1.74	1.21
40	75	275	100.19	0.58	1.74	1.21
60	100	300	98.80	0.39	2.55	1.77
80	100	300	93.66	0.39	2.55	1.77
Ethanol						
20	75	250	100.05	0.58	1.74	1.21
40	75	275	99.84	0.58	1.74	1.21
60	100	300	97.06	0.39	2.55	1.77
80	100	300	84.66	0.39	2.55	1.77
2-Propanol						
20	75	250	100.00	0.58	1.74	1.21
40	75	275	99.82	0.58	1.74	1.21
60	100	300	85.17	0.39	2.55	1.77
Acetone						
20	75	250	100.00	0.58	1.74	1.21
40	75	275	100.00	0.58	1.74	1.21
60	100	300	99.95	0.39	2.55	1.77
80	50	225	100.01	1.08	0.93	0.65
1,4-Dioxane						
20	75	250	100.00	0.58	1.74	1.21
40	75	275	99.22	0.58	1.74	1.21
60	50	300	98.36	1.08	0.93	0.65
Tetrahydrofuran						
20	75	250	100.28	0.58	1.74	1.21
40	75	275	99.15	0.58	1.74	1.21
60	100	300	98.07	0.39	2.55	1.77
80	50	250	92.57	1.08	0.93	0.65




Fig. 1. Elution behaviour of manganese(II) on Dowex 50W-X8 with various mixed solvent systems. A : 2 M HCl in 20% non-aqueous solvent; B : 2 M HCl in 40% non-aqueous solvent; C : 2 M HCl in 60% non-aqueous solvent; D : 2 M HCl in 80% non-aqueous solvent.

of 1 ml/min. The column was washed with water. Manganese from the column was eluted with various mineral acids (Table 1) and with mixtures of 2 M hydrochloric acid with various concentrations of non-aqueous solvents like methanol, ethanol, acetone, 2-propanol, dioxane or tetrahydrofuran (Table 2; Fig. 1). The effluent lot was collected in 25 ml fractions and in each case ten to twelve fractions were collected. The fractions were evaporated almost to dryness prior to the determination of manganese by complexometric titration<sup>8</sup>.

(b) *Procedure for separations* : An aliquot of solution containing mixture of two or more cations along with manganese was passed on the column at the flow rate of 1 ml/min. The specific eluants as described under various separations, were then passed through the column to elute each element at the flow rate of 2 ml/min. The concentration of a particular element in the eluted solutions was determined quantitatively by an appropriate method, usually involving complexometric titration.




Fig. 2. Sequential separation of zinc, iron(III), copper(II), cobalt(II), manganese and nickel.

0.5 M HNO<sub>3</sub>(1)      0.1 M HCl in 90% Acetone(2)      1 M HCl 90% Acetone(3)      1.5 M HCl H<sub>2</sub>SO<sub>4</sub>(5)  
2 M HCl in 40% Ethanol(4)




Fig. 3. Sequential separation of vanadium(V), uranium(VI), manganese(II), titanium(IV) and scandium(III).

0.5 M HCl in 60% Propanol(Ce)      0.5 M HCl in 80% Acetone(Pb)      2 M HCl in 80% Acetone(Mn)      3 M HCl in 60% Methanol(Al)      3 M HCl(Ca)




Fig. 4. Sequential separation of cadmium, lead(II), manganese(II), aluminium and calcium.

## Results and Discussion

The elution constant (E) and distribution coefficients (D<sub>s</sub>, D<sub>w</sub>) were evaluated as described earlier<sup>1</sup>. From their knowledge, it was possible to have selectivity scale for mineral acids as eluants, as well as for non-aqueous solvents mixed with

2 M hydrochloric acid. The scale was H<sub>2</sub>SO<sub>4</sub> > HCl > HNO<sub>3</sub> > HClO<sub>4</sub> for mineral acids and acetone > ethanol > methanol > 1,4-dioxane > tetrahydrofuran > 2-propanol for non-aqueous solvents.

Amongst the eluants tested for manganese the complexing organic acids were found to be poor<sup>1</sup>. The mineral acids in the concentration range of 0 to 1 *M* were poor eluants, but at 2 *M* acidity elution was quantitative for all acids with the exception of perchloric acid. The optimum concentration of mineral acid was 2 *M*. The most practical eluant was hydrochloric acid. Hence it was used in all investigations along with non-aqueous solvents. A lower concentration of hydrochloric acid could be used provided it was used in conjunction with non-aqueous solvents.

There are several advantages of carrying out cation exchange chromatographic separations in mixed solvent systems as described earlier<sup>7</sup>. Among the various non-aqueous solvents used, it was noted that acetone was the most promising because the elution of manganese was quantitative with 20 to 80% acetone in 2 *M* hydrochloric acid. Ethanol and methanol were the next best from the view point of separation. With 2-propanol the flow rate was extremely low at higher concentrations. Though it was possible to get the separation with 1,4-dioxane, the problem of two phase formation was encountered. With tetrahydrofuran system, the extraction was not generally quantitative in higher concentration. Further, it was possible to elute manganese quantitatively with 0.75 to 2 *M* hydrochloric acid, only in the presence of 80 to 90% acetone. The methanol and ethanol system was effective for separation of multicomponent mixtures.

During ion exchange separation, it was noted that manganese was strongly bound to the resin in comparison to other elements and was therefore eluted later in certain separations. In the few instances where manganese was weakly bound to the resin, it was eluted first before elution of interfering ion and was thus separated in mixture. Few such separations are illustrated in the following part.

*Separation of manganese in acetone media:* Vanadium(V), mercury(II), indium(III), bismuth(III) and lithium were separated from manganese in acetone media by selective elution of these ions as they were weakly bound. On passing a binary mixture of manganese with any of these ions on the column, they were taken up by the resin. They were first eluted with 0.5 *M* hydrochloric acid, followed by the elution of manganese with 2 *M* hydrochloric acid in 80% acetone. Zinc and cadmium were separated from manganese by first eluting zinc and cadmium with 0.5 *M* hydrochloric acid in 80% methanol, with subsequent elution of manganese with 2 *M* hydrochloric acid in 80% acetone.

Uranium(VI), non(III), cobalt(II), copper(II), gallium(III) and lead(II) were separated from manganese by eluting these elements with 0.5 *M* hydrochloric acid in 80% acetone [0.5 *M* hydrochloric acid in 90% acetone for uranium(VI) and cobalt(II)], with subsequent elution of manganese with 2 *M* hydrochloric acid in 80% acetone.

TABLE 3—ION EXCHANGE SEPARATION OF MANGANESE(II) FROM VARIOUS OTHER ELEMENTS IN BINARY MIXTURES

Mn(II) = 5.1 mg

Foreign ion	Amount added mg	Manganese found mg	Recovery of manganese (%)	Eluant for other elements	Eluant for manganese
V(V)	50.00	5.0	98.0	0.5 <i>M</i> HCl	2 <i>M</i> HCl in 80% acetone
Hg(II)	35.00	5.1	100.0	"	"
In(III)	54.00	5.1	100.0	"	"
Bi(III)	65.00	5.1	100.0	"	"
Li	50.50	5.1	100.0	"	"
Fe(III)	62.40	5.1	100.0	0.5 <i>M</i> HCl in 80% acetone	"
Zn(II)	65.20	5.1	100.0	0.5 <i>M</i> HCl in 80% methanol	"
Cd(II)	60.50	5.1	100.0	"	"
U(VI)	45.30	5.1	100.0	0.5 <i>M</i> HCl in 90% acetone	"
Co(II)	12.00	5.0	98.0	"	"
Cu(II)	65.00	5.1	100.0	0.5 <i>M</i> HCl in 80% acetone	"
Ga(III)	45.00	5.1	100.0	"	"
Pb(II)	56.30	5.1	100.0	"	"
Na	45.00	5.0	98.0	4 <i>M</i> HCl	0.75 <i>M</i> HCl in 90% acetone
K	50.00	5.1	100.0	"	"
Rb	40.40	5.1	100.2	"	"
Cs	45.40	5.0	99.1	"	"
Be	30.40	5.1	100.0	"	"
Ca	65.00	5.1	100.0	"	"
Mg	50.40	5.1	100.0	"	"
Al	65.30	5.1	100.0	"	"
Ti(IV)	45.00	5.1	100.0	8 <i>M</i> HCl	"
Ni(II)	45.30	5.0	98.0	4 <i>M</i> HCl	"
Sc(III)	50.00	5.1	100.0	8 <i>M</i> HCl	3 <i>M</i> HCl in 60% ethanol
Y(III)	50.00	5.1	100.0	"	"
Zr(IV)	50.40	5.1	100.0	"	"
Th(IV)	60.80	5.1	100.0	"	"
Ce(III)	60.40	5.1	100.0	"	"
Sr(II)	60.00	5.1	100.0	"	"
Ba(II)	65.40	5.1	100.0	"	"

In contrast, in acetone media some elements were taken up strongly by the resin and were eluted later. Manganese was separated from sodium, potassium, rubidium, caesium, beryllium, calcium, magnesium, aluminium, titanium(IV) and nickel(II) by its elution with 0.75 *M* hydrochloric acid in 90% acetone, followed by elution of all the listed ions with 4 *M* hydrochloric acid. In case of titanium it was necessary to use 8 *M* hydrochloric acid (Table 3).

**Separation in ethanol media:** Since scandium(III), yttrium(III), zirconium(IV), thorium(IV), cerium(III), strontium(III) and barium(II) were strongly retained on the resin in comparison to manganese, the latter was first eluted with 3 *M* hydrochloric acid in 60% ethanol, followed by elution of all the elements with 8 *M* hydrochloric acid (Table 3).

**Separation of manganese from multi-component mixtures:** Manganese was separated from several multicomponent mixtures in the following manner:

A mixture of zinc, iron(III), copper(II), cobalt(II), manganese(II) and nickel(II) was sorbed

on the column. Zinc was first eluted with 0.5 *M* hydrochloric acid in 80% ethanol, then iron(III) was eluted with 0.2 *M* hydrochloric acid in 80% acetone, copper(II) with 0.5 *M* hydrochloric acid in 80% acetone, cobalt(II) with 0.3 *M* hydrochloric acid in 90% acetone, manganese with 0.75 *M* hydrochloric acid in 90% acetone and finally nickel(II) was eluted with 2 *M* hydrochloric acid.

A mixture of vanadium(V), uranium(VI), manganese(II), titanium(IV) and scandium(III) was sorbed on the column. Vanadium(V) was eluted with 0.5 *M* nitric acid, uranium(VI) with 0.3 *M* hydrochloric acid in 90% acetone, manganese with 1 *M* hydrochloric acid in 90% acetone, titanium(IV) with 2 *M* hydrochloric acid in 40% ethanol and finally, scandium(III) was eluted with 1.5 *M* sulphuric acid.

A mixture of cadmium(II), lead(II), manganese(II), aluminium and calcium was passed on the column. Cadmium was eluted with 0.5 *M* hydrochloric acid in 60% 2-propanol, lead(II) with 0.5 *M* hydrochloric acid in 80% acetone, manganese with




Fig. 5. Sequential separation of iron(III), manganese(II), magnesium and barium(II)

TABLE 4—SEPARATION OF MANGANESE FROM MULTICOMPONENT MIXTURES

Sl No.	Element	Amount added mg	Amount found mg	Recovery %	Eluant
1.	Zn(II)	10.00	10.00	100.00	0.5 <i>M</i> HCl in 80% methanol
	Fe(III)	9.20	9.20	100.00	0.2 <i>M</i> HCl in 80% acetone
	Cu(II)	10.06	9.90	99.00	0.5 <i>M</i> HCl in 80% acetone
	Co(II)	8.80	8.70	98.86	0.3 <i>M</i> HCl in 90% acetone
	Mn(II)	10.20	10.10	99.01	0.75 <i>M</i> HCl in 90% acetone
2.	Ni(II)	9.40	9.40	100.00	2 <i>M</i> HCl
	V(V)	10.00	10.00	100.00	0.5 <i>M</i> HNO <sub>3</sub>
	U(VI)	9.80	9.70	98.98	0.3 <i>M</i> HCl in 90% acetone
	Mn(II)	10.20	10.20	100.00	1 <i>M</i> HCl in 90% acetone
	Ti(IV)	9.60	9.50	98.96	2 <i>M</i> HCl in 40% ethanol
3.	Sc(III)	10.00	10.00	100.00	1.5 <i>M</i> H <sub>2</sub> SO <sub>4</sub>
	Cd(II)	10.00	10.00	100.00	0.5 <i>M</i> HCl in 60% 2-propanol
	Pb(II)	10.30	10.20	99.02	0.5 <i>M</i> HCl in 80% acetone
	Mn(II)	10.20	10.20	100.00	2 <i>M</i> HCl in 80% acetone
	Al(III)	9.40	9.40	100.00	3 <i>M</i> HCl in 60% methanol
4.	Ca(II)	10.50	10.40	99.05	3 <i>M</i> HCl
	Fe(III)	9.20	9.20	100.00	0.5 <i>M</i> HCl in 80% acetone
	Mn(II)	10.20	10.20	100.00	1 <i>M</i> HCl in 90% acetone
	Mg(II)	10.00	9.90	99.00	3 <i>M</i> HCl in 40% ethanol
	Ba(II)	10.40	10.30	99.03	3 <i>M</i> HNO <sub>3</sub>

2 M hydrochloric acid in 80% acetone, aluminium with 3 M hydrochloric acid in 60% methanol and finally calcium with 3 M hydrochloric acid.

A mixture of iron(III), manganese(II), magnesium and barium was passed on the column and elution was carried out for iron(III) with 0.5 M hydrochloric acid in 80% acetone, manganese(II) with 1 M hydrochloric acid in 90% acetone, magnesium with 3 M hydrochloric acid in 40% ethanol and finally, barium with 3 M nitric acid (Table 4 ; Fig. 5).

In all the above separations the total volume of the eluant used was 250 ml. Invariably, the analysis of elements was done by complexometry with the exception of alkali and alkaline earth elements which were determined by flame emission spectroscopy.

The separation of manganese from iron(III), cobalt(II), nickel(II), vanadium(V), titanium(IV), aluminium and lead(II) was significant as these are associated with it in alloys. The isolation of manganese from iron(III) and barium was important as it occurs with them in minerals.

The overall separations required 3 to 4 hr. The relative standard deviation was  $\pm 1.5\%$ .

#### Acknowledgement

The authors are thankful to the Science and Technology Cell of Ministry of Education, Government of Maharashtra for awarding a Senior Research Fellowship to (A. G. G.).

#### References

1. S. B. AKKI and S. M. KHOPKAR, *Chromatographia*, 1970, 3, 363.
2. I. K. TSITOVICH and ZH. N. GONCHARENKO, *Zh. analit. Khim.*, 1968, 23, 1778.
3. I. K. TSITOVICH, *Zh. analit. Khim.*, 1971, 26, 1908.
4. F. W. E. SIRELOW and A. H. VICTOR, *Anal. Chim. Acta*, 1972, 39, 389.
5. M. SIMEK, *Chemické Zvesti*, 1974, 28, 349; *Anal. Abst.*, 1974, 27, 3112.
6. M. N. ZVEREVA and N. K. GORNOVSK, *Vestn. Leningr. Univ.*, 1977, 4; *Anal. Abst.*, 1974, 27, 3112.
7. V. P. MEHTA and S. M. KHOPKAR, *The Bulletin of the Bismuth Inst.*, 1980, 28.
8. A. I. VOGEL, "Text Book of Quantitative Inorganic Analysis", Longmans Green Ltd, London, 1961, p. 536.

# Determination of Zinc with Cupric Ion-Selective Electrode and its Analytical Application in Fertilizers

LILIANA ILCHEVA\*, MARIA POLIANOVA, VICTORIA ADEWUYI and PESHO BOZADZIEV

Higher Chemico-Technological Institute, Sofia 1156, Bulgaria

The results of potentiometric titration of Zn(II) with cupric ion-selective electrode in the presence of ammonia buffer solution are recorded. The best results for determination of Zn(II) are obtained in 0.1 M ammonia buffer. Samples containing 1.5  $\mu$ moles in 5 ml to 6  $\mu$ moles in 10 ml solution could be analysed. Results compare favourably with other methods.

The application of the method for determination of zinc in fertilizers is demonstrated.

ONE of the main advantages of ion-selective electrode used in the potentiometric titrations lies in the development of indirect methods for determination of such anions or cations which themselves are not sensor of electrodes<sup>1-3</sup>.

In the course of our investigation with ion-selective electrode we tried to apply the method of Bauman and Wallace<sup>1</sup> for indirect determination of Zn(II) using cupric ion-selective electrode. However, the results obtained proved to be quite unsatisfactory. An equivalent part of the titration curve could not be obtained.

If  $\alpha$ -coefficient of the Zn(II) and Cu(II) side reactions in ammonia buffer<sup>4</sup> are taken into consideration, one could arrive at the conclusion that the inequality  $K'_{Zn-EDTA} > K'_{Cu-EDTA}$  remains valid ( $K'_{Zn-EDTA}$  and  $K'_{Cu-EDTA}$  are the adequate conditional constants). The chemical equilibrium accounting for the inflection point, which coincides with the equivalent point is presented in the reaction.



In an acidic medium where  $K'_{Zn-EDTA} < K'_{Cu-EDTA}$ , more of indicator Cu-EDTA might prove necessary for the reaction<sup>1</sup> and the curve is not well defined.

In ammonia medium, where  $K'_{Zn-EDTA} > K'_{Cu-EDTA}$ , a single drop of indicator Cu-EDTA is enough for the displacement of cupric ions.

## Experimental

**Apparatus:** All measurements were made using Seibold Cupric Ion Activity Electrode, Model 29-17, Ag/AgCl double junction reference electrode with 0.1 M KNO<sub>3</sub> in the outer compartment and the Seibold Model G 104 digital pH/mV meter. A glass electrode with the same reference was used to ascertain pH of the solutions.

**Reagents:** The indicator Cu-EDTA was prepared according to the reported method<sup>2</sup>. The final solution contained 0.5 M Cu-EDTA with pH 4.09. The titrant, 0.1 M Na<sub>2</sub>HEDTA was prepared from 0.14 M Na<sub>2</sub>H<sub>2</sub>EDTA.2H<sub>2</sub>O and 0.1 M NaOH. Buffer

solution NH<sub>4</sub><sup>+</sup>/NH<sub>3</sub> with concentrations 1 M, 0.1 M and 0.05 M were used for keeping the pH constant between 7.5 and 8. Ammonium nitrate containing microamount of zinc as ZnO was used. Zn(NO<sub>3</sub>)<sub>2</sub> and Cu(NO<sub>3</sub>)<sub>2</sub> were added to the impure carbamide.

**Determination of Zn(II) in solutions:** The diluted solution of zinc (10<sup>-3</sup> M) in ammonium medium was prepared just before the determination. An aliquot (3.00 to 10.00 ml) was drawn from this solution and transferred into a plastic beaker. One drop of 0.5 M indicator Cu-EDTA was added. The electrodes were immersed into the solution and the solution titrated with 0.01 M Na<sub>2</sub>HEDTA. A microburette of 2.000  $\pm$  0.005 ml was used. The rate of titration was 0.01 ml/10 sec with constant stirring (50 rev/min).

**Determination of Zn(II) in fertilizers:** To a sample containing ~1.0 g NH<sub>4</sub>NO<sub>3</sub> or 0.5 g CO(NH<sub>2</sub>)<sub>2</sub> were added 1-2 drops of HNO<sub>3</sub> (1:1) and 10.0 ml 1 M ammonia buffer. The mixture was diluted with double distilled water up to the mark. An aliquot of 5.00 ml was titrated in the presence of 1 drop of Cu-EDTA indicator with the cupric ion-selective electrode.




Fig. 1. Zn(II) titration with Cu-selective electrode at different concentration of the buffer (7.00 ml Zn(II) 0.563.10<sup>-3</sup> M).

TABLE 1—REPRODUCIBILITY AND ACCURACY OF THE RESULTS OBTAINED FROM POTENTIOMETRIC TITRATION OF Zn(II) WITH CUPRIC ION-SELECTIVE ELECTRODE, USING Cu-EDTA AS INDICATOR

Buffer concentration <i>M</i>	Zn(II) Taken $\mu$ moles	Mean, $\bar{x}$ $\mu$ moles	$d_t = \frac{\sum(x - \bar{x}_t)}{n}$	$S_x = \frac{\sqrt{\sum(x - \bar{x}_t)^2}}{n-1}$	$\%S = \frac{S_x}{\bar{x}} \cdot 100$
0.1	3.94	4.02	0.085	0.0106	0.26
0.5	4.26	4.33	0.121	0.1634	3.77
0.2	1.22	1.17	0.116	0.133	11.4

### Results and Discussions

The effect of concentration of the buffer solutions on the titration of Zn(II) is shown in Fig. 1. Statistical analyses of some of the results are presented in Table 1. It is shown that the concentration of the buffer solution of 0.1 *M* is the best medium for the titration.

TABLE 2—THE EFFECT OF INTERFERING IONS ON THE DETERMINATION OF Zn(II) BY POTENTIOMETRIC TITRATION WITH CUPRIC ION-SELECTIVE ELECTRODE

Interfering ions, <i>M</i>	<i>M</i> /Zn	Zn(II) $\mu$ moles	
		Obtained	Taken
K <sup>+</sup>	120	3.94	3.94
Ca <sup>2+</sup>	120	3.93	3.94
SO <sub>4</sub> <sup>2-</sup>	120	3.95	3.94
Cl <sup>-</sup>	100	3.95	3.94
NO <sub>3</sub> <sup>-</sup>	100	3.95	3.94
Ba <sup>2+</sup>	100	3.96	3.94
CO(NH <sub>2</sub> ) <sub>2</sub>	100	3.96	3.94



Fig. 2. Determination of Zn(II) in fertilizers with Cu-selective electrode in 0.1*M* ammonia buffer solution; Curve 1—Zn(II) in NH<sub>4</sub>NO<sub>3</sub> and Curve 2—Zn(II) in CO(NH<sub>2</sub>)<sub>2</sub>.

The effect of interfering ions on the equivalence point of titration curves are shown in Table 2. 120 times SO<sub>4</sub><sup>2-</sup> ion, present in excess does not affect the result using Cu electrode, but using Cd electrode<sup>6</sup>, only 10 times SO<sub>4</sub><sup>2-</sup> excess is tolerated.

TABLE 3—STATISTICAL ANALYSES OF THE RESULTS OF DETERMINATION OF Zn(II) IN FERTILIZERS

Statistical analyses	Zn(II) in NH <sub>4</sub> NO <sub>3</sub> %	Zn(II) in CO(NH <sub>2</sub> ) <sub>2</sub> mol/l $\times 10^6$
mean, $\bar{x}$	0.995	0.560
$d_t = \frac{\sum(x - \bar{x}_t)}{n}$	0.0008	0.002
$\%d_t = \frac{\bar{d}_t}{\bar{x}} \cdot 100$	0.084	0.036
$S_x = \frac{\sqrt{\sum(x - \bar{x}_t)^2}}{n-1}$	0.001	0.0025
$\%S = \frac{S_x}{\bar{x}} \cdot 100$	0.1	0.045
$1/4S_x$	0.00015	0.0006

The application of the method for determination of Zn(II) in fertilizers is shown in Fig. 2 and Table 3. Complexometric titration and atomic absorption were used as comparative methods.

### References

1. E. W. BAUMMAN and R. M. WALLACE, *Anal. Chem.*, 1969, 41, 2072.
2. J. W. ROSS and M. S. FRANI, *Anal. Chem.*, 1969, 41, 1900.
3. T. MITSUHIKO, M. MASAMI, Y. HITOSHI and H. SEI-CHIRO, *Bunseki Kagaku*, 1976, 25, 362.
4. A. RINGBOM in "Complexation in Analytical Chemistry", (Ed.) P. J. ERVING and I. M. KOLTHOFF, New York, London, 1963, Vol. 4, p. 75.

## Floatable Ion Associates Formed in the System Iridium(III)-Tin(II)-Chloride-Basic Dye

Z. MARCZENKO\* and K. KALINOWSKI

Department of Analytical Chemistry, Technical University, 00-664 Warsaw, Poland

Sparingly soluble (in aqueous solutions) ion associates of polyvalent anionic iridium complexes, formed in hydrochloric acid medium containing tin(II) with basic dyes (rhodamine 6G, malachite green or crystal violet) collect on the phase boundary or on the walls of the separatory funnel, when shaken with solvents of low polarity. The separated floatation compounds dissolve in polar solvents. Optimum conditions for complete floatation of iridium compounds are found. Molar ratios (Ir : Sn : dye) in these compounds are determined spectrophotometrically and suitable formulae are proposed.

**A**NIONIC complexes of many elements with appropriate ligands, formed with basic dye ion associates (ion pairs), and having a molar ratio anion : basic dye = 1 : 1, are extracted by nonpolar solvents. This has been utilized for a long time in extraction-spectrophotometric methods for determination of elements<sup>1,2</sup>. Some ion associates with basic dyes are not extracted when the aqueous phase is shaken with solvents of low polarity, but collect at the phase boundary or on the walls of the separatory funnel. In this case the anions are polyvalent and the number of monovalent cations of the dye in ion associates is more than one (2 to 5). This process is some kind of floatation of sparinglysoluble ion associate without participation of a surface active substance, usually added in typical floatation process. Precipitates separated from aqueous and organic solvent phases and washed are soluble in some polar solvents. The solutions obtained can form a basis of very sensitive, so called, floatation-spectrophotometric methods<sup>3</sup>.

It is known that most of the platinum metals form polyvalent anionic complexes in hydrochloric acid medium in presence of tin(II)<sup>4-6</sup>, forming mixed complexes with Cl<sup>-</sup> and SnCl<sub>2</sub><sup>+</sup> ligands. This work is devoted to a study of ion associates given by such complex of iridium with some basic dyes.

### Experimental

#### Apparatus and Reagents :

A Specord UV-VIS recording and a VSU-2P spectrophotometer with 1 cm cells were used for absorbance measurements. Standard iridium solution (1 mg/ml) was prepared by dissolving 0.5970 g of iridium(III) chloride (Koch-Light) in 2 M HCl with the addition of 5 ml of 5% NaCl solution. The solution was standardized gravimetrically with thionalide<sup>7</sup>. Working solutions were prepared by diluting with 2 M HCl.

Radioisotope <sup>192</sup>Ir, ammonium hexachloroiridate(IV) in 0.1 M HCl was employed. The dyes were purified by precipitation from ethanolic solutions by addition of a 5-fold excess of diethyl ether. The

strength of the dye solutions was rhodamine 6G (R6G)  $2 \times 10^{-3}$  M (approx. 0.1%), malachite green (MG) and crystal violet (CV)  $1 \times 10^{-3}$  M (about  $3.6 \times 10^{-3}\%$  and  $4.0 \times 10^{-3}\%$ , respectively). Stannous chloride was used as 10% solution of SnCl<sub>2</sub>·2H<sub>2</sub>O in 2 M HCl.

#### Procedure :

An acid (HCl) solution containing 10 µg of iridium is evaporated to dryness on a boiling water bath. Suitable volumes of SnCl<sub>2</sub> solution and HCl are added to obtain the appropriate acidity. The solution is heated on a boiling water bath for 10-15 min, allowed to cool to room temperature, transferred to a separatory funnel, the dye solution is added, volume made upto 20 ml and the acidity is adjusted. 5 ml of floating organic solvent is then added and shaken for 1 min. The water and organic phases are separated carefully and precipitate is washed and dissolved in the polar solvent. The absorbance of the solutions is measured at 530 nm in the case of the system with R6G, at 627 nm with MG, and at 595 nm with CV, against reagent blanks prepared in the same way

### Results and Discussion

#### Preliminary studies :

Preliminary experiments were carried out to find the basic dyes, which would form floatable ion associates with anionic iridium complex formed in SnCl<sub>2</sub>-HCl medium. The tests involved xanthene, triphenylmethane and azine dyes, commonly used in analytical chemistry<sup>1,2</sup>. The acidity in these experiments was fixed from 0.5 to 6 M HCl. A 30-60 fold molar excess of the basic dye with respect to iridium (10 µg) was used. The aqueous solutions were shaken with di-isopropyl ether, benzene toluene and chloroform.

Only ion associates of the anionic iridium complex with rhodamine 6G, malachite green and crystal violet are floated. The sparingly soluble compounds collect on the phase boundary or on the walls of the separatory funnel.



### Conditions of the floatation :

The floating solvents appeared the best are diisopropyl ether for the ion associates of iridium with rhodamine 6G and malachite green and benzene for ion associate with crystal violet. In these systems, the sparingly soluble compounds accumulate on the walls of the separatory funnel.

The phase volume ratio has no effect on complete separation of the iridium as ion associate. The iridium in separated compounds and in solutions was determined radiometrically. A relatively long shaking of phases in separatory funnel (about 1 min) is necessary. The best concentration of HCl in the aqueous phase during the floatation is 0.4-0.6 M, 2.0-2.4 M and 2.3-2.7 M for malachite green, crystal violet and rhodamine 6G, respectively.

For the complete separation of iridium during a floatation process in the form of a sparingly soluble ion associate, a 55-fold molar excess of rhodamine 6G (with respect to iridium) is necessary. In the cases of malachite green and crystal violet, these molar excesses are 60 and 12, respectively. These dependences are shown in Fig. 1.




Fig. 1. Dependence of the formation of iridium ion associate on the molar excess of basic dye 1—rhodamine 6G, 2—malachite green, 3—crystal violet. Absorbances of the solutions measured against the blanks.

The ion pair of the  $\text{SnCl}_4^-$  ion with rhodamine 6G separates together with the anionic iridium complex-basic dye associate. It is decomposed when the precipitate is washed with 2.5 M HCl. The excess of the dye can be removed nearly completely by shaking the precipitate and the diisopropyl ether with 3 portions of 2.5 M HCl. The floated ion associates of iridium with malachite green and crystal violet are less stable than the ion associate with rhodamine 6G. Washing the precipitates with solutions of similar acidity as that used during floatation leads to decomposition of the floated compounds. The isolated precipitates of iridium with MG and CV can be washed only by shaking with the floating solvents (diisopropyl ether and benzene, respectively).

Dissolution of the separated and washed ion associates in acetone, methanol, ethanol and

dimethylformamide (DMF) was examined. In the case of the system with rhodamine 6G the precipitate dissolves in the latter three solvents after a little shaking. The dissolution in acetone is immediate. The absorption spectra of the ion associate in these solvents differ insignificantly from the spectrum of the dye in water, with respect to the position of  $\lambda_{\text{max}}$ . The absorbance of the acetone solution does not change for a long time.

The ion associate with malachite green dissolves in DMF very slowly and in acetone after a little shaking. Dissolution in methanol and ethanol is immediate. The colour of these solutions does not change for several hours in darkness.

The ion associate with crystal violet dissolves readily in all solvents examined. It should be mentioned that in some preparations of DMF (presumably containing admixtures of reducing agents), the colour intensity of the dye decreases. The solutions of the crystal violet associate in various solvents exhibit small differences in the position of  $\lambda_{\text{max}}$ . The stability of the absorbance of solutions depends on the intensity and nature of the incident light.

### Composition of the floated compounds :

The molar ratios of iridium to dye in the isolated and washed compounds were determined with the aid of the logarithmic method of Bent and French<sup>6</sup> (Fig 2). The data obtained indicate the molar ratio of iridium to crystal violet as 1 : 1, to malachite green as 1 : 3, and to rhodamine 6G as 1 : 4. These results were confirmed by absorbance




Fig 2 Determination of the molar ratios Ir : basic dye in the floated compounds by the Bent and French method: 1—crystal violet, 2—rhodamine 6G, 3—malachite green

measurements of the ion associate solutions containing known amounts of iridium, and of solutions of the dye salts (taken in suitable amounts) in solvents used.

In order to determine the number of tin atoms per one iridium atom in the washed compounds, they were mineralized and the tin in solutions

obtained was determined spectrophotometrically with phenylfluorone<sup>9</sup>. The ratios Ir : Sn calculated on the basis of the average result of several tin determinations were 1 : 5.2, 1 : 4.2, and 1 : 4.3 in the compounds of rhodamine 6G, malachite green and crystal violet, respectively. The postulated ratios of metals in the compounds are 1 : 5 or 1 : 4. The higher experimental results are undoubtedly due to contamination of the precipitates with tin not bound in the iridium compounds.

Bearing in mind that the oxidation state of iridium in presence of tin(II) is 3 and the coordination number of iridium is 6, the formulae of the floated compounds can be proposed.

The compound with rhodamine 6G can be postulated to be  $[(R6G^+)_5IrCl_2(SnCl_3)_2]^{2-} \cdot [(R6G^+)(SnCl_3)]$ . It follows from this formula that the compound is not a simple ion associate but an adduct of the iridium ion associate and of the  $SnCl_3^-$  anion associate with dye. This adduct can be considered stable because it does not decompose during washing the precipitate.

The formula,  $[MG^+]_5[IrCl_2(SnCl_3)_2]^{2-}$  can be proposed for the malachite green compound. In the floated compound with crystal violet the ratio of components Ir : Sn : CV is 1 : 4 : 1. In this case it is difficult to suggest a probable formula.

When the floatation of the ion associates with malachite green and crystal violet (triphenylmethane dyes) is carried out in light, the results show poor reproducibility. The lower results (absorbances of ion associates in polar solvents) are due to

diminishing colour intensity of the pseudo solution prepared for floatation. The colour intensity decreases faster with higher concentration of tin(II). This effect is due to the photochemical reduction of malachite green and crystal violet to their inactive leuco forms. Light accelerates the reduction owing to polarization of electron structures of the dyes<sup>10</sup>.

Floatation of the ion associates in the systems iridium(III)-tin(II)-chloride-R6G (MG or CV) can form a basis for sensitive floatation-spectrophotometric determination of iridium.

#### References

1. I. A. BLUM, "Extractive-Photometric Methods of Analysis with use of Basic Dyes" (in Russian), Izd. Nauka, Moscow, 1970.
2. Z. MARCZENKO, *Mikrochim. Acta* [Wien], 1977, 11, 651.
3. Z. MARCZENKO, *CRC Crit. Rev. Analyt. Chemistry*, 1981, 11, 195.
4. C. FURLANI and A. ZINATO, *Atti. Accad. Naz. Lincei Rend. Sci. fis. mat. e natur.*, 1966, 41, 69; *Rof. Zh. Khim.*, 1967, 20B157.
5. J. F. YOUNG, R. O. GILLARD and G. WILKINSON, *J. Chem. Soc.*, 1964, 5176.
6. S. I. GINZBURG, N. A. EZERSKAYA, I. V. PROKOF'EVA, N. V. FEDORENKO, V. I. SHLENSKAYA and N. K. BELSKII, "Analytical Chemistry of Platinum Metals" (in Russian), Izd. Nauka, Moscow, 1972.
7. N. K. PSHENITSYN and I. V. PROKOF'EVA, *Zh. Inorg. Khim.*, 1957, 2, 569.
8. M. BENT and C. FRENCH, *J. Amer. Chem. Soc.*, 1941, 63, 568.
9. Z. MARCZENKO, "Spectrophotometric Determination of Elements", Ellis Horwood, Chichester, 1976, p. 547.
10. E. I. DODIN and I. P. KHARLAMOV, *Zh. Analit. Khim.*, 1982, 37, 14.

# A Simple Deviation Function to Summarize Data in Solvent Mixtures. The Standard Oxidation Potential of the Silver Chloride Electrode in Water-Ethylene Glycol Mixtures

ERIK HOGFELDT

Department of Inorganic Chemistry, The Royal Institute of Technology (KTH), S-100 44 Stockholm 70, Sweden

The data by Kundu *et al* on the standard oxidation potential of the silver chloride electrode in mixtures of water and ethylene glycol have been summarized using the simple deviation function introduced by the present writer. Over the whole range of concentration and temperature range studied the  $E^\circ$  values (molality scale) can be fitted to within  $\pm 1$  mV with six constants, of which two can be given theoretical meaning

**R**ECENTLY, a simple method to summarize thermodynamic data in solvent mixtures was devised<sup>1</sup>. In the paper the method is applied to some  $E_m^\circ$ -data in water-ethylene glycol mixtures<sup>2</sup>.

## The model :

The basis is the zeroth approximation by Guggenheim<sup>3</sup>. According to this model the number of A-A pairs, B-B and A-B(=B-A) pairs in a mixture of the two components A and B, are given by  $x_A^2$ ,  $x_B^2$  and  $2x_Ax_B$ . Here  $x_A$  and  $x_B$  are the stoichiometric mole fractions of A and B in the mixtures.

It is now assumed that any property  $Y$  can be split into three parts, ( $y_A$ ) which is a characteristic of solvent A, ( $y_B$ ) characteristic of solvent B, and ( $y'_{AB}$ ) characteristic of the mixtures. The following expression is thus obtained

$$Y = y_A x_A^2 + y_B x_B^2 + 2y'_{AB} x_A x_B \quad (1)$$

This homogeneous equation is related to


$$Y = y_A x_A + y_B x_B + y_{AB} x_A x_B \quad (2)$$

by  $y'_{AB} = \frac{1}{2}(y_A + y_B + y_{AB})$  (3)

From plots of  $Y$  vs ( $x_A$ ) or  $Y$  vs ( $x_B$ ), the quantities  $y_A$ ,  $y_B$  and  $y'_{AB}$  can be obtained using eqn (3). The use of these equations is illustrated below.

## Application :

Instead of the  $E_m^\circ$ -values use has been made of the equilibrium constant of the reaction



The equilibrium constant  $K_m$  is related to  $E_m^\circ$  by

$$\log K_m = nFE_m^\circ / RT \ln 10 \quad (5)$$

Application of eqn (2) to reaction (4) gives

$$\log K_m = \log K_{EG} x + \log K_{H_2O} (1-x) + Bx(1-x) \quad (6)$$

$x$  = the mole fraction of ethylene glycol (EG) in the mixture.

$\log K_{EG} = \log K$  of reaction (4) in pure ethylene glycol in molal units.

$\log K_{H_2O} = \log K$  of reaction (4) in pure water in molal units.

$B$  = deviation function, which generally is assumed to be a function of  $x$ , most often expressed as a power series in  $x$ , i.e.

$$B = -a + bx + cx^2 + \dots \quad (7)$$

At present only  $B=0$  and  $B=a$  can be given theoretical meaning. For  $B=0$ ,  $y'_{AB}$  is the arithmetic average of  $Y$  in the two pure solvents. For  $B=a$ ,  $y'_{AB}$  is constant and can be computed from eqn (3) provided  $y_A$  and  $y_B$  are constants. For  $B$  being a function of  $x$ , the approach is purely empirical, only offering a convenient way of summarizing experimental data.

The simplest way to approach a fitting of eqn (2) is to assume  $y_A$  and  $y_B$  to be correct and to evaluate  $B$ . In the present case it was thus found that eqn (7) could be reduced to

$$B = bx \quad (8)$$

i.e., only one empirical parameter. This implies that the data  $\log K(x)$  can be fitted by a third degree polynomial

$$\log K = a_0 + a_1 x + a_2 x^2 + a_3 x^3 \quad (9)$$

where  $\log K_{H_2O} = a_0$

$$\log K_{EG} = \sum_0^3 a_i \quad \text{and} \quad (10a-c)$$

$$B = -(a_2 + a_3) - a_3 x$$

By using eqns (10a-c), the constants in eqn (9) can be transformed into the parameters in eqn (2). Values for  $\log K$  at various concentrations computed from eqn (2) can then be transformed into  $E_m^\circ$ -values using eqn (5).

## Results and Discussion

In Table 1, experimental and computed  $E_m^\circ$ -values are compared. The first column gives  $w$ , the weight per cent of EG in the mixture, then follows

TABLE 1—EXPERIMENTAL AND COMPUTED  $E_m^0$ -VALUES FOR THE SILVER CHLORIDE ELECTRODE IN WATER-ETHYLENE GLYCOL MIXTURES AT VARIOUS TEMPERATURES. DATA FROM REF 2. THE POTENTIALS ARE GIVEN IN MILLIVOLT

w	x	5° $E_m^0$		15° $E_m^0$		25° $E_m^0$		35° $E_m^0$		45° $E_m^0$	
		exp	$b = 5.30$ 1 q	exp	$b = 5.07$ 1 q	exp	$b = 4.64$ 1 q	exp	$b = 4.17$ 1 q	exp	$b = 3.91$ 1 q
0	0	234.0	—	228.6	—	222.5	—	215.7	—	208.3	—
10	0.0312	226.7	228.4	221.2	222.8	215.1	216.4	208.2	209.6	200.9	202.0
30	0.1106	215.2	216.4	209.5	210.3	203.0	203.4	203.3	195.4	187.5	187.9
50	0.2249	202.8	203.2	196.5	196.4	189.6	188.4	188.8	181.0	179.8	180.3
70	0.4038	186.7	186.5	178.6	178.5	168.9	168.8	169.2	159.0	158.2	159.2
90	0.7232	141.5	140.4	129.8	130.5	118.3	118.3	118.3	106.4	105.2	106.4
100	1	46.0	—	34.9	—	23.5	—	23.5	—	11.8	—
	$\sigma(E_m^0)$	$\pm 1.2$	$\pm 0.5$	$\sigma(E_m^0)$	$\pm 1.0$	$\pm 0.6$	$\sigma(E_m^0)$	$\pm 0.9$	$\pm 0.6$	$\sigma(E_m^0)$	$\pm 1.0$

TABLE 2—COEFFICIENTS IN THE POLYNOMIAL GIVEN BY EQN (9) TOGETHER WITH LOG  $K$ - AND  $B$ -EXPRESSIONS OBTAINED FROM EQNS (10a-c)

°C	$a_0 = -\log K_{H_2O}$	$a_1$	$a_2$	$a_3$	$\log K_{EG}$	$B$
5	4.226	-3.455	5.619	-5.557	0.833	$B = -0.06 + 5.56x$
15	3.983	-3.306	4.889	-4.957	0.609	$B = 0.07 + 4.96x$
25	3.747	-3.230	4.371	-4.495	0.397	$B = 0.12 + 4.50x$
35	3.515	-3.234	4.117	-4.206	0.193	$B = 0.09 + 4.21x$
45	3.290	-3.190	3.728	-3.833	-0.006	$B = 0.105 + 3.83x$

TABLE 3—COMPARISON OF EXPERIMENTAL  $E_m^0$ -VALUES WITH THOSE COMPUTED FROM EQNS (12a-c). POTENTIALS ARE GIVEN IN MILLIVOLT

w	5° $E_m^0$		15° $E_m^0$		25° $E_m^0$		35° $E_m^0$		45° $E_m^0$	
	exp	calcd	exp	calcd	exp	calcd	exp	calcd	exp	calcd
0	234.0	234.6	228.6	228.2	222.5	221.8	215.7	215.4	208.3	209.0
10	226.7	229.0	221.2	222.4	215.1	215.8	208.2	209.3	200.9	202.7
30	215.2	217.0	209.5	209.9	203.0	202.8	195.4	195.7	187.5	188.6
50	202.8	203.9	196.5	195.8	189.6	187.8	181.0	179.7	172.3	171.7
70	186.7	187.4	178.6	177.7	168.9	168.0	159.0	158.3	148.5	148.6
90	141.5	141.4	129.8	129.4	118.3	117.5	106.4	105.6	93.7	93.6
100	46.0	46.3	34.9	34.8	23.5	23.2	11.8	11.6	-0.4	0
	$\sigma(E_m^0)$	$\pm 1.4$	$\sigma(E_m^0)$	$\pm 0.7$	$\sigma(E_m^0)$	$\pm 1.0$	$\sigma(E_m^0)$	$\pm 0.8$	$\sigma(E_m^0)$	$\pm 1.0$

the mole fraction of EG,  $x_{EG} = x$ . For each temperature three  $E_m^0$ -values are given. First of these is the experimental value, then the value computed with  $B$  given by eqn (8), with the  $b$ -value given in the heading, and in the third column results of a least squares analysis using eqn (8). The parameters found by this method and the  $\log K$ -values etc. computed using eqns (10a-c) are given in Table 2. Below the computed  $E_m^0$ -values in Table 1 the standard deviation in  $E_m^0$ ,  $\sigma(E_m^0)$ , is given,

$$\sigma(E_m^0) = \pm \sqrt{\sum (E_{m,exp}^0 - E_{m,calcd}^0)^2 / (n-1)} \quad (11)$$

$n$  = number of experimental points.

As can be seen from Table 1, the least squares fit with four constants gives a standard deviation of about  $\pm 0.5$  mV, while the fit with one empirical constant roughly doubles the standard deviation to about  $\pm 1.0$  mV.

The  $\log K$ -values in the two pure solvents as well as the constant  $b$  have been fitted to  $1/T$  with least squares methods. The expressions arrived at are

given below :

$$\log K_{H_2O} = -3.223 + 2079/T$$

$$\log K_{EG} = -5.833 + 1856/T \quad \dots (12a-c)$$

$$b = -6.31 + 3250/T$$

A comparison between computed and experimental  $E_m^0$ -values is made in Table 3.

As seen from Tables 1 and 3 the fit is about the same. A least squares fit to the constants given in Table 2 did not improve the fit and discarded in favour of eqns (12a-c).

It is evident from Tables 1 and 3 that with six constants (eqns 12a-c) it is possible to adequately fit the experimental  $E_m^0$ -values both over the whole range of concentration as well as the temperature range investigated. Of the six constants obtained two have theoretical meaning, giving an estimate of  $\Delta H$  for the reaction in question. The results presented here can be compared with the results of the authors

themselves, who fit  $E_m^0$  for each mixture studied with three constants in the expression

$$E_m^0 = \sum_0^3 a_i (t - 25)^i \quad (t = \text{temperature in degree centigrade})$$

i.e. 21 constants instead of 6 only to fit the temperature dependence. The authors claim the fit to be about  $\pm 0.3$  mV. However, to fit five experimental point with three constants leads to a large uncertainty in each constant. For that reason, the approach presented here does not only have the merit of giving a fair description of the concentration and temperature dependence of  $E_m^0$ , it also uses the minimum numbers of parameters to fit the deviations from additivity in the mixtures.

When comparing data from different authors on a certain system the agreement sometimes is rather poor. It is the intention of the present writer to use the approach outlined above to summarize data in the literature and try to give the most reasonable set of parameters, when comparing all available data on each system<sup>4</sup>.

#### References

1. E. HÖGFELDT, *Acta Chem. Scand.*, 1979, A33, 557.
2. U. SEN, K. K. KUNDU and M. N. DAS, *J. Phys. Chem.*, 1967, 71, 3665
3. E. A. GUGGENHEIM, "Mixtures", Clarendon Press, Oxford, 1952, p. 30
4. E. HÖGFELDT, to be published

---

*Note added in proof* · Since this paper was written the model has been extended to comprise the general case with B being a function of  $x$  (cf eqn 7) with all constants given a simple theoretical meaning. The application of this general approach to the data by Kundu *et al*<sup>2</sup> will be published elsewhere.

# Alkaloids of *Mitragyna parvifolia* (Roxb) Korth. and their Transformations

A. CHATTERJEE\*, K. P. DHARA and J. BANERJI

Department of Pure Chemistry, University College of Science, Calcutta-700 009

From the basic fractions of the leaves of *Mitragyna parvifolia* (Roxb) Korth. three oxindole alkaloids, mitraphylline, isomitraphylline and speciophylline  $N_2$ -oxide were isolated. A novel method has been developed for the transformation of mitraphylline, the major alkaloid of this species, to the corresponding heteroyohimbine base, ajmalicine without disturbing any chiral centre. Mitraphylline  $N_2$ -methiodide, when treated with triethyloxonium fluoroborate, was converted to its corresponding imino-ether which on reduction with sodium borohydride in acetic acid furnished ajmalicine  $N_2$ -methiodide. The latter could be transformed to ajmalicine by conventional procedure.

THE growing family of oxindole alkaloids has gained much importance on biogenetic grounds and also for the interesting chemical reactions displayed by them. These basic constituents originate from the alkaloids of secoyohimbane or heteroyohimbane series through the intermediacy of the corresponding indoleninium derivatives. The indoleninium intermediates on hydroxylation at the neighbouring carbon ( $C_8$ ) (vide Chart 1) followed by the abstraction of the proton from the hydroxyl with the concomitant migration of  $C_9$ - $C_8$  bond at  $C_7$  generate the oxindole derivatives. The key role in this transformation is played by the indolic nitrogen  $N_1$ . These alkaloids have been reported to occur in *Aspidosperma*, *Mitragyna*, *Ouroparia*, (*Uncaria*), *Rauwolfia* and *Vinca* species and bear a close structural resemblance to each other and possess the same basic framework (having  $C_8$ - $C_9$  bond cleavage) derived from tryptophan via its decarboxylation product tryptamine and secologanin, a  $C_{10}$ -unit of terpenoid origin.




Chart-1

In recent years, intensive research is being pursued in this area and this has culminated in the isolation of many new oxindoles, several of these

being stereoisomers having different configurations. Meaningful allocation of correct conformation of each configuration has been possible from spectral data (viz., pmr spectra) as spectral parameters are conformation-dependent.

The present communication is mainly concerned with the isolation of speciophylline  $N_2$ -oxide from *Mitragyna parvifolia* (Roxb) Korth. and the development of a new method for the conversion of mitraphylline, the major alkaloid of this species, to the corresponding heteroyohimbine base with the retention of chirality of the molecule. The genus *Mitragyna* is widely distributed in tropical and subtropical regions. Several *Mitragyna* species, which are large trees indigenous to South Eastern Asia, find commercial use in the timber and paper industries. The special feature of this genus is the ability to produce a large number of oxindole alkaloids having pentacyclic structures of ajmalicine type. *M. parvifolia* (Roxb) Korth. is a much investigated species and special mention may be made about the contribution of Shellard and his coworkers<sup>1-3</sup> towards systematic chemotaxonomic studies of this genus. From this particular plant occurrence of five alkaloids, viz., mitraphylline (1), pteropodine (2), isopteropodine (3), speciophylline (4) and uncariine F (5) (vide Chart 2) has been reported. It has been observed that environmental factor has a vital role to play in modifying the alkaloid content and the structure. It was therefore thought worthwhile to study the basic constituents of *M. parvifolia* which grows profusely in Bengal plain. The primary objective was to isolate mitraphylline (1), the major alkaloid of *M. parvifolia* and to evolve a new method for its conversion to pentacyclic heteroyohimbane system with the retention of configuration at the asymmetric centres as previously mentioned.

With this object, the leaves of this species were collected from the Indian Botanic Garden, Sibpur, West Bengal. The basic fractions of the alcoholic extract of the leaves yielded three oxindoles of which two were isomeric and already known

in the literature<sup>4</sup>. These were identified as mitraphylline (1)  $C_{21}H_{24}N_2O_4$  ( $M^+$  368), m.p. 265-7° and isomitraphylline (6)  $C_{21}H_{24}N_2O_4$ , m.p. 122-3° (vide Chart -), the oxindoles of normal series (D/E ring

the minor differences existing in relative peak intensities only. This observation clearly indicated that it is an  $N_b$ -oxide ( $C_{21}H_{24}N_2O_4$ ) of the base having the composition  $C_{21}H_{24}N_2O_4$ .




Chart-2

juncture being *trans*) having 15 $\alpha$ -H--20 $\beta$ -H--19 $\beta$ -H configuration. From the conformational analysis mitraphylline (1) was shown to be a stronger base than the other isomer (6). This is due to the proximity of the lactam carbonyl group to  $N_b$  which forms the ammonium ion on protonation. The protonated species has the unique advantage of undergoing stabilisation by H-bonding with the lactam carbonyl group. This situation is not permitted in isomitraphylline. The third oxindole alkaloid was found to be an  $N_b$ -oxide of specio-phylline (4) previously obtained from *Uncaria*<sup>6</sup> species only in trace amount. Thus the spectral investigations of the natural product were not possible which could only be studied with the synthetic one. In this communication we would like to report the physical properties of specio-phylline  $N_b$ -oxide isolated from *M. parvifolia*. The compound was obtained in adequate quantity, thus permitting detailed studies of the molecule. It could be isolated as an amorphous solid, m.p. 113-5° from 10% methanolic chloroform eluates. The most significant feature of this base was its highly polar character and its resistance to migration on chromatoplates [ $R_f$  0.65, developing system MeOH-Et<sub>3</sub>NH (12:1)]. It showed characteristic oxindole colour reaction—spraying chromatoplate with a solution of 0.2 M FeCl<sub>3</sub> in 85% HClO<sub>4</sub> followed by heating the plates at 90° for 1 hr when a pink spot developed. Its mass spectrum showed a ready loss of 16 mass units generating the base peak at  $m/e$  368 from the molecular ion peak at  $m/e$  384. The remaining fragmentation pattern was practically the same as that of mitraphylline and isomitraphylline,

The compound exhibited absorption maxima at  $\lambda_{max}^{EtOH}$  220, 245 and 286 nm (log  $\epsilon$ : 3.85, 4.01 and 3.23, respectively) similar to those of mitraphylline<sup>6</sup>. The ir spectrum also indicated its structural similarity with heteroyohimbine oxindole alkaloids excepting the appearance of an additional peak at 950  $cm^{-1}$  owing to the presence of aliphatic N-oxide. The 90 MHz pmr spectrum of the compound studied in  $d_6$ -DMSO showed a three proton singlet at  $\delta$  3.20 attributed to the methyl group of the carbomethoxy function. The  $C_{17}$ -H resonated as a singlet at  $\delta$  7.50 whereas  $C_{10}$ -H as a multiplet ( $J_1=6.5$  Hz and  $J_2=1.5$  Hz) at  $\delta$  4.35 with  $C_{10}$ -CH<sub>3</sub> as three proton doublet ( $J_1=6.5$  Hz) at  $\delta$  1.22.

All these data indicate the compound to be an oxindole base with a heterocyclic ring E, stereoisomeric with mitraphylline. The exact position of  $C_{10}$ -CH<sub>3</sub> signal had been used to deduce the nature of D/E ring junction. Heteroyohimbine alkaloids with a *cis* D/E ring junction normally show doublets owing to  $C_{10}$ -CH<sub>3</sub> at  $\delta$  1.32-1.42 whereas those with *trans* D/E junction exhibit the corresponding signal at  $\delta$  1.16-1.19. It appeared that a similar criterion would also be valid in the ring E hetero-oxindole series, since the alkaloids with a *cis* D/E ring junction showed the doublets at  $\delta$  1.23-1.4 while those with a *trans* D/E junction showed the corresponding signal at  $\delta$  1.1-1.16 (the  $C_{10}$ -CH<sub>3</sub> of mitraphylline appearing at  $\delta$  1.16). The coupling constant values for  $C_{10}$ -H as observed in this case clearly indicated the  $\alpha$ -orientation of  $C_{10}$ -CH<sub>3</sub> in either heterooxindole having *cis* or *trans* D/E ring junction. The four aromatic

protons in this alkaloid resonated as a multiplet around  $\delta$  6.84-7.30 indicating that the oxygen at  $N_b$  is on the opposite side of the molecule to  $C_9-H$ , otherwise the latter would have separately appeared downfield as a clear one proton doublet. All these information revealed that the compound would be an  $N_b$ -oxide of either mitraphylline (1) or speciophylline (4). Mitraphylline (1) was converted to its  $N_b$ -oxide derivative on treatment with *m*-chloroperbenzoic acid and the product was found to be different from our alkaloid. Interestingly, the natural  $N_b$ -oxide of the base when reduced with  $H_2$ -Pd/C in ethanol and also with sulphurous acid was found to be identical with speciophylline (4). The identity of our alkaloid with speciophylline  $N_b$ -oxide was subsequently established by comparison with an authentic sample.

Since mitraphylline (1) could be isolated in appreciable quantity it was intended to develop a suitable method to convert it into the corresponding indole (tetrahydro  $\beta$ -carboline) derivative, ajmalicine (7), with the retention of chirality of the molecule. The method reported in the literature<sup>6</sup> for converting the oxindoles to the corresponding tetrahydro  $\beta$ -carboline derivative was to prepare the  $N_a$ -imino-ether from the oxindole with the strong electrophile  $Et_3O^+ \cdot BF_4^-$  followed by reduction of the imino-ether with sodium borohydride in acetic acid to the corresponding indolic seco-compound. When the cyclisation of ring C occurred the process ended up with  $C_9$ -epimers. Our objective was to generate the tetrahydro  $\beta$ -carboline derivative from the imino-ether with the retention of configuration at  $C_9$ .

To fulfil this requirement it was necessary to prevent participation of lone pair of electrons on  $N_b$  leading to the formation of seco-compound. Hence the basic nitrogen of mitraphylline was quaternised with  $CH_3I$  in dry THF, when mitraphylline  $N_b$ -methiodide (8),  $C_{28}H_{37}N_2O_3I$ , d.p.  $260^\circ$  separated out as a white solid in the reaction medium. This quaternary salt was subsequently treated with dry methylene chloride solution of  $Et_3O^+ \cdot BF_4^-$  under an oxygen free dry nitrogen blanket. The imino-ether derivative (9) thus obtained, was then subjected to reduction with sodium borohydride and glacial acetic acid to yield a single product  $C_{28}H_{37}N_2O_3$  (10), d.p.  $235^\circ$ . The product showed ultraviolet absorption maxima at  $\lambda_{max}^{EtOH}$  270 and 288 nm ( $\log \epsilon$  3.9 and 3.75, respectively) similar to those of quaternary heteroyohimbinoïd alkaloid<sup>7</sup>. The identity of the compound with ajmalicine  $N_b$ -methiodide was finally established by comparing their co-tlc behaviour, ultraviolet absorption characteristics and superimposable infrared spectra. The methiodide was converted to ajmalicine (7),  $C_{23}H_{27}N_2O_2$  ( $M^+$  352), m.p.  $256^\circ$ , uv  $\lambda_{max}^{EtOH}$  226, 282 and 290 nm ( $\log \epsilon$  4.64, 3.96 and 3.88, respectively) following the procedure of Karrer<sup>7</sup>. The identity of the base was established by comparison with authentic ajmalicine following the conventional procedure. The sequence of the aforesaid reactions is displayed in Chart 3.




Chart - 3

### Experimental

The melting points were determined in a Kofler block and are uncorrected. The ultraviolet absorption spectra were recorded in a Carl-Zeiss VSU-1 Universal spectrophotometer in 95% aldehyde free ethanol and the infrared spectra in a Beckmann IR-20 spectrophotometer in KBr disc. The nmr spectra were recorded in a 90 MHz Brucker Spectrospin machine. The solvents were dried over anhydrous sodium sulphate. Column chromatography was carried out with Brockmann alumina and thin layer chromatography with silica gel G. The spots on the chromatoplates were detected by spraying Dragendorff's reagent.

**Isolation of mitraphylline, isomitraphylline and speciophylline  $N_b$ -oxide:** Finely pulverised dry leaves (10 Kg) of *Mitragyna parvifolia* (Roxb) Korth. were extracted with ethanol for three weeks. The ethanolic extract was then concentrated and churned with 5% aqueous citric acid for 72 hr. The neutral portion was separated and filtered off. The filtrate was basified with liquor ammonia in an ice-cold condition. The liberated base was taken up in chloroform, washed with water and dried. The chloroform concentrate was chromatographed over



kmann alumina and the column was eluted with eluents of increasing polarities.

The benzene-chloroform (3 : 1) and the chloroform eluates yielded mitraphylline,  $C_{21}H_{24}N_2O_4$  (M<sup>+</sup> 368), m.p. 265-7°, and isomitraphylline,  $H_{24}N_2O_4$  (M<sup>+</sup> 368), m.p. 122-3°, respectively in the 10% methanolic chloroform eluates specifically *N*<sub>6</sub>-oxide,  $C_{21}H_{24}N_2O_5$  (M<sup>+</sup> 384), m.p. 150-5° separated and crystallised as white flakes in the same solvent mixtures. UV :  $\lambda_{max}^{EtOH}$  220, 245, 286 nm (log  $\epsilon$  3.85, 4.01 and 3.23, respectively).  $\nu_{max}^{KBr}$  3400, 1710, 1610, 950 cm<sup>-1</sup>. PMR in d<sub>2</sub>-SO :  $\delta$  1.22 (3H, d,  $J_1=6.5$  Hz,  $C_{10}-CH_3$ ), 3.20 (s,  $-CO_2CH_3$ ), 4.35 (1H, dm,  $J_1=6.5$  Hz and 1.5 Hz,  $C_{10}-H$ ), 6.87-7.30 (4H, m, aromatic protons), 7.50 (1H, s,  $C_{17}-H$ ). MS: m/e 384 (M<sup>+</sup>), (M-16), 223, 222, 208, 159, 146, 145, 144, 130, 69.

**Preparation of mitraphylline *N*<sub>6</sub>-oxide** : To a solution of mitraphylline (10 mg) in dry chloroform was added a solution of *m*-chloroperbenzoic acid in the same solvent. The temperature of the reaction mixture was maintained at 0° for 3 hr. The resulting mitraphylline *N*<sub>6</sub>-oxide was isolated by preparative TLC.

**Reduction of speciophylline *N*<sub>6</sub>-oxide** : a) The natural *N*<sub>6</sub>-oxide (2 mg) was dissolved in spectral grade alcohol and hydrogenated over Pd/C for 2 hr. The reaction product on filtration and subsequent removal of the solvent furnished the parent oxindole iophylline, confirmed by co-tlc with an authentic sample. b) The natural *N*<sub>6</sub>-oxide (2 mg) treated with 5% sulphurous acid and the mixture allowed to stand for 1 hr. The tertiary base extracted with chloroform after the solution was made alkaline with ammonia, washed and dried. The chloroform was removed and the residue was found to be identical with an authentic sample of iophylline.

**Preparation of mitraphylline *N*<sub>6</sub>-methiodide** : To a solution of mitraphylline (100 mg) in dry THF (5 ml) methyl iodide (10 ml) was added and the reaction was stirred for 4 hr and kept overnight in the dark. Mitraphylline *N*<sub>6</sub>-methiodide,  $C_{21}H_{23}N_2O_4I$ , d.p. 260°, separated out as white waxy solid (90 mg). Found : C, 51.65; H, 5.40; N, 5.40.  $C_{21}H_{23}N_2O_4I$  requires C, 51.76; H, 5.29; N, 5.49%.

**Preparation of imino-ether of mitraphylline *N*<sub>6</sub>-methiodide** : To a well-stirred solution of triethylamine fluoroborate (3.5 g) in dry methylene chloride (25 ml) a solution of mitraphylline *N*<sub>6</sub>-methiodide (90 mg) in the same solvent (25 ml) was added dropwise under a completely dry and oxygen free nitrogen blanket, stirring being continued for 10 hr.

The reaction mixture was neutralised with a saturated solution of sodium bicarbonate in ice-cold condition. The methylene chloride layer was separated, washed and dried. Removal of the solvent yielded a gummy mass which on trituration with dry ether afforded the desired imino-ether of the methiodide (60 mg).  $C_{21}H_{23}N_2O_4I$ , d.p. 215°. Found : C, 53.45; H, 5.70; N, 5.25.  $C_{21}H_{23}N_2O_4I$  requires C, 53.53; H, 5.76; N, 5.20%.

**Reduction of the imino-ether of mitraphylline *N*<sub>6</sub>-methiodide to ajmalicine *N*<sub>6</sub>-methiodide** : The above imino-ether (60 mg) was dissolved in glacial acetic acid and sodium borohydride (500 mg) was added portionwise to the solution, kept at a low temperature. After the effervescence ceased, the mixture was allowed to stand at room temperature for 10 hr and later basified with liquor ammonia. The liberated base was taken up in chloroform (3 × 30 ml), washed and dried. On removal of the solvent a gummy residue was obtained. On trituration with dry ether the residue solidified (20 mg),  $C_{21}H_{27}N_2O_4I$ , d.p. 235°. UV  $\lambda_{max}^{EtOH}$  270 and 288 nm (log  $\epsilon$  3.9 and 3.75, respectively). Found : C, 53.35; H, 5.53; N, 5.75.  $C_{21}H_{27}N_2O_4I$  requires C, 53.44; H, 5.46; N, 5.66%.

**Conversion of ajmalicine *N*<sub>6</sub>-methiodide to ajmalicine** : Ajmalicine *N*<sub>6</sub>-methiodide obtained above was heated in a sealed tube under vacuum at 220-25° for 10 min. The residue was taken up in chloroform. Ajmalicine (yield 25%) crystallised from ether,  $C_{21}H_{27}N_2O_4$  (M<sup>+</sup> 352), m.p. 252°. UV :  $\lambda_{max}^{EtOH}$  226, 282 and 290 nm (log  $\epsilon$  4.64, 3.96 and 3.88, respectively). Its identity was established by comparison with an authentic sample by co-tlc, m.m.p. and superimposable infrared spectra.

#### Acknowledgement

Sincere thanks are accorded to Dr. J. D. Phillipson, the School of Pharmacy, University of London, U. K., for comparing natural speciophylline *N*<sub>6</sub>-oxide with an authentic sample and to U.G.C. (Delhi) for financial assistance.

#### References

1. E. J. SHELLARD, J. D. PHILLIPSON and D. G. GUPTA, *Planta Med.*, 1969, 17, 146.
2. E. J. SHELLARD and P. J. HOUGHTON, *Planta Med.*, 1971, 20, 32.
3. E. J. SHELLARD and P. J. HOUGHTON, *Planta Med.*, 1974, 25, 172.
4. J. L. SEXTON, "The Alkaloids" (Ed.) R. H. F. MANSKE, Academic Press, 1968, Vol. X, p. 536 and 1973, Vol. XIV, p. 123.
5. J. D. PHILLIPSON and S. R. HEMINGWAY, *Phytochemistry*, 1973, 12, 2791.
6. S. SAKAI, N. AIMI, E. YAMANAKA, J. ENDO and J. HAGINAWA, *Tetrahedron*, 1973, 29, 2015.
7. E. BACHLI, C. VAMVACAS, H. SCHMID and P. KARRER, *Helv. Chim. Acta*, 1957, 40, 1167.

# Alkaloids of *Machilus glaucescens* Wight: Machigline, A New Phenolic Oxoaporphine Alkaloid

(Mrs.) BANI TALAPATRA, SHYAMAPROSAD GOSWAMI, ARINDUM GHOSH and SUNIL K. TALAPATRA


Department of Chemistry, University College of Science, Calcutta-700 009

Machigline (I), a new phenolic oxoaporphine alkaloid, isolated along with atheroline (II) and  $\beta$ -sitosterol-O- $\beta$ -D-glucoside from the alcohol extract of the leaves of *Machilus glaucescens* Wight (Lauraceae), has been shown to be 1,2-methylenedioxy-9-hydroxy-10-methoxyoxoaporphine by spectral and chemical studies. A fatty ketol characterised as a rarely occurring *n*-hentriacontan-10-ol-16-one ( $\equiv$  10-hydroxypalmitone) (III) (first report of its occurrence in Lauraceae) has also been isolated as an aliphatic constituent from the  $\text{CHCl}_3$  extract of the plant besides the lignan and nor-lignan constituents. The mass fragmentations of I and III have been delineated. The isolation of machigline and atheroline constitutes the first report on the occurrence of oxoaporphines in *Machilus* species, and machigline adds a new name to the list of only a few phenolic oxoaporphines

THE family Lauraceae is a well-known rich source of alkaloids and some *Machilus* species are reported to elaborate benzyltetrahydroisoquinoline and aporphine alkaloids<sup>1-5</sup>. Earlier, we reported<sup>6</sup> the isolation, structure elucidation and synthesis of three new nor-lignans viz., machicendiol, machiconol and machicenin from *Machilus glaucescens*. We now report the isolation of a new phenolic oxoaporphine alkaloid designated machigline<sup>6</sup> (I) along with atheroline (II)<sup>6, 7</sup> and  $\beta$ -sitosterol-O- $\beta$ -D-glucoside from the alcohol extract of the plant material and the isolation of a rarely occurring ketol 10-hydroxypalmitone<sup>8</sup> (III) from the  $\text{CHCl}_3$  extract as the major aliphatic constituent of the plant.

The minor alkaloid machigline crystallising from chloroform-methanol as glistening red needles, m.p. 315° (d),  $\text{C}_{18}\text{H}_{11}\text{O}_8\text{N}$  ( $M^+$  321.0620),  $[\alpha]_D^{25} \pm 0^\circ$ , has been assigned structure (I) on the basis of spectral and chemical studies. Machigline is insoluble in common non-polar solvents but fairly soluble in alcohol and methanolic-chloroform and forms red solution with mineral acids. The intensity and the variation of colour of machigline in solution

from yellow to pink and to red depend on the concentration and the pH of the medium. This behaviour is reminiscent of phenolic oxoaporphine alkaloids<sup>6, 7</sup>. The presence of the phenolic hydroxyl



group is also suggested by positive  $\text{FeCl}_3$  colouration. Its solubility in  $\text{Na}_2\text{CO}_3$  solution indicates its enhanced acidity compared to simple phenols. The oxygenation sites in the oxoaporphine skeleton as


TABLE I—UV AND VISIBLE ABSORPTIONS OF MACHIGLINE AND ATHEROLINE

Compound	$\lambda_{max}$ (EtOH)		$\lambda_{max}$ (EtOH + HCl)		$\lambda_{max}$ (EtOH + NaOH)	
	nm	log $\epsilon$	nm	log $\epsilon$	nm	log $\epsilon$
Machigline	249	4.23	258	4.19	254	4.28
	272	4.12	281	4.10	304	4.26
	285	4.04	379	3.92	326	4.21
					351	3.79
	351	3.70	509	3.27	382	3.43
	385	3.22				
	430	3.18			537	3.28
Atheroline	244	4.12	257	4.10	252	4.12
	273	4.17	282	4.10	294	3.99
	292 (sh)	3.96	385	4.05	320	3.98
	355	3.90	500	3.38	390	3.74
	380	3.83			535	3.46
	435	3.60				

well as the location of the hydroxyl function was settled from a comparative study of its uv and visible spectra (Table 1) with those of the congener alkaloid atheroline<sup>6</sup> and other phenolic oxoaporphines<sup>9</sup>. Machigline displays a very characteristic 1,2-methylenedioxy phenolic oxoaporphine uv spectrum. It contains one methoxyl group (pmr and ms) and thus it appears to be a 1,2-methylenedioxy methoxy phenolic oxoaporphine. The close similarity of the uv and visible spectra of machigline and atheroline in different media and similar bathochromic shifts of  $\lambda_{max}$  values in alkali [phenolate anion from machigline is comparable in energy to that from atheroline] indicate the same location (C-9) for OH in both the alkaloids thus allowing delocalisation of the charge of the phenolate anion to nitrogen. Any other alternative position for phenolic OH group would have given rise to different uv maxima in alkali medium due to different mesomeric stabilisation of the phenolate ion<sup>6</sup>. In machigline, like atheroline, the greater mesomeric stabilisation of the phenolate ion accounts for its well-marked acidic properties compared to simple phenols. The ir spectrum ( $\nu_{max}$ ,  $cm^{-1}$ ) of machigline exhibited characteristic bands for OH (3520), conjugated CO (1635) in the highly aromatic oxoaporphine system (1575, 1522) and methylenedioxy<sup>10</sup> (962) group

The pmr spectra of machigline and atheroline show close similarity in the aromatic region suggesting the same positions of oxygenation functions in them. The pmr spectrum (80 MHz,  $d_6$ -DMSO) of machigline (Table 2) clearly shows a methylenedioxy grouping on the planar oxoaporphine ring system as a two proton singlet<sup>11,12</sup> at  $\delta$  6.48, an aromatic methoxyl at  $\delta$  3.96 (3H, s) and the five aromatic protons in  $\delta$  7.46-8.71 region and the hydroxyl proton at  $\delta$  9.9 (1H, s). The placement of methylenedioxy group is made by a comparative study of the pmr spectra of some methylenedioxy oxoaporphines in conjunction with the uv and mass spectral analysis. The chemical shifts of methylenedioxy and methoxyl protons in oxoaporphines vary with their locations. It is known that a methylenedioxy group located at 1,2 resonates at a lower field ( $\delta$  6.5-6.85) than if located at 9,10 ( $\delta$  6.2)<sup>7,13,14</sup>. The presence of an aromatic singlet at  $\delta$  7.46 due to H-3 resonating at higher field than other aromatic protons eliminates the possibility of methoxyl group

being at C-3 (moreover a C-3 methoxyl appears between  $\delta$  4.43-4.55 i.e., a comparatively lower field<sup>9</sup>). The two one proton doublets centred at  $\delta$  8.71 and 7.92 are assignable to H-5 ( $\alpha$  to N) and H-4, respectively ( $J_{4,5} = J_{5,4} = 5$  Hz) of the pyridine moiety. The appearance of the remaining two aromatic protons as two singlets indicates the adjacent positions of hydroxyl and methoxyl groups at C-9 and C-10 or vice-versa. The singlet at  $\delta$  8.03 is due to H-11 which in oxoaporphines appears more downfield<sup>9</sup> than H-3, H-8, H-9 or H-10 and that at  $\delta$  7.66 is assigned to H-8 (adjacent to 9-OH) appearing at the same field in both machigline and atheroline.



SCHEME 1 MASS FRAGMENTATION OF MACHIGLINE

The conversion of machigline to dicentrone<sup>15,16</sup> (IV) ( $\equiv$  1,2-methylenedioxy-9,10-dimethoxyoxoaporphine) by treatment with excess  $CH_3N$ , in methanolic solution confirms the skeleton and the oxygenation sites at 1,2,9 and 10 positions. The location of the hydroxyl group at C-9 has been

TABLE 2—CHEMICAL SHIFT ( $\delta$ ) OF PMR SIGNALS OF MACHIGLINE, ATHEROLINE AND THEIR ACETATES (VARIAN CFT-20, 80 MHz)

Compounds (Solvent)	-O-CH <sub>3</sub> -O	Aromatic protons					C <sub>9</sub> -OH	OCH <sub>3</sub> (1,2)	C <sub>10</sub> -OCH <sub>3</sub>	C <sub>9</sub> -O-CO-CH <sub>3</sub>
		H-3	H-4	H-5	H-8	H-11				
Machigline ( $d_6$ -DMSO)	6.48	7.46	7.92	8.71	7.66	8.03	9.9	—	3.96	—
Machigline acetate (CDCl <sub>3</sub> )	6.48	7.12	7.65	8.82	7.99	8.16	—	—	3.95	2.02
Atheroline ( $d_6$ -DMSO)	—	7.46	7.91	8.69	7.67	8.56	9.91	3.95, 3.98	3.95	—
Atheroline acetate (CDCl <sub>3</sub> )	—	7.12	7.67	8.81	8.00	8.70	—	3.96, 4.02	4.02	2.2

pmr spectrum of atheroline itself (Table 2) as it has not been reported earlier.

The major aliphatic constituent  $C_{31}H_{52}O_2$  ( $M^+$  466 4660), m.p.  $96^\circ$ , isolated from chloroform extract was characterised as 10-hydroxypalmitone (III) which was first isolated from sandal leaves<sup>6</sup>. This fatty ketol [ir peaks at  $1705$ ,  $3300$  (br)  $cm^{-1}$ ] afforded an acetate, m.p.  $43^\circ$ . No spectral details of this compound and its  $NaBH_4$  reduction product (VII) (which is not naturally or synthetically known) are available in literature and these are also reported in the present paper. The compound (III) showed pmr signals ( $CDCl_3$ , TMS) at  $\delta$  3.6 (1H, *m*,  $-CH(OH)$ ), 2.39 [*t*,  $J=7$  Hz, 4 H, two  $CH_2$  (*a* and *b*)], 1.27 [*b*, *s*, 50 H,  $(CH_2)_{24}$ ] and 0.89 [*t*,  $J=6$  Hz, 6 H, two  $CH_3$  groups]. The mass spectral analysis (Scheme 2) is quite interesting and is helpful to find the positions of carbonyl and hydroxyl groups.  $NaBH_4$  reduction of the ketonic alcohol yielded the straight chain diol,  $C_{31}H_{54}O_2$  ( $M^+$  468), *n*-hentriacontan-10,16-diol (VII) showing pmr signals at



$\delta$  3.55 [2H, *m*, two -CHOH], 1.26 [*b s*, 54 H, (CH<sub>2</sub>)<sub>17</sub>] and 0.86 [*t*, *J*=6 Hz, 6 H, two CH<sub>3</sub>]. The absence of any triplet around  $\delta$  2.39 for ketomethylenes as in III as well as the absence of any carbonyl band in the ir spectrum of VII confirms the complete conversion of III into the diol (VII). The mass spectrum of the diol (VII) showed ion peaks at *m/e* 450 (M<sup>+</sup>-H<sub>2</sub>O), 432 (*m/e* 450-H<sub>2</sub>O) indicating the presence of two hydroxyl groups and appearance of a number of other peaks due to subsequent loss of methylenes. The isolation of atheroline and machigline marks the first occurrence of oxoaporphines in a *Machilus* species and machigline adds a new name to the list of only a few natural phenolic oxoaporphines.

### Experimental

Melting points were determined in H<sub>2</sub>SO<sub>4</sub> bath and are uncorrected. The uv spectra were recorded on a Varian Techtron series 634 spectrophotometer in aldehyde free 95% ethanol. IR spectra were taken in KBr pellets with Beckmann IR-20 or Pye Unicam SP 1025 spectrometer and the optical rotations were measured on a Perkin-Elmer 241 polarimeter in CHCl<sub>3</sub> and ethanol solutions. PMR spectra of the original alkaloids were determined in d<sub>6</sub>-DMSO and those of the acetates of the alkaloids and other compounds in CDCl<sub>3</sub> using TMS as internal standard with a Varian CFT-20 spectrometer. Silica gel (60-120 mesh) was used for chromatography of main columns and silica gel (100-200 mesh) for side columns. Anhydrous Na<sub>2</sub>SO<sub>4</sub> was used for drying organic solvents. *R<sub>f</sub>* values were measured over tlc on silica gel G.

**Extraction :** The marc left after pet. ether and CHCl<sub>3</sub> extraction of the dried and powdered leaves of *Machilus glaucescens* was kept immersed in EtOH (90%) for 20 days. The gummy brown residue (15 g) obtained from the alcohol extract responded to Dragendorff test for alkaloids. A small part of the residue (4 g) was repeatedly extracted with cold 2*N* HCl (4 × 100 ml) till the fresh extract showed negative test for alkaloid. The combined acid extract (400 ml) was cooled, basified with 2*N* NH<sub>4</sub>OH solution and extracted with CHCl<sub>3</sub> (3 × 150 ml). The combined CHCl<sub>3</sub> extract (450 ml) was washed, dried and concentrated under reduced pressure. The deep brown gummy residue (residue-A) was found to be completely soluble in aqueous Na<sub>2</sub>CO<sub>3</sub> or NaOH solution showing the presence of phenolic base. The original residue was also found to be almost soluble in Na<sub>2</sub>CO<sub>3</sub> solution and negligible precipitation occurred on acidification of the alkali solution. The crude base was almost soluble in both acid and alkali. As the crude base was found to be weakly acidic (phenolic base), the direct chromatography of the crude extract was done over silica gel which effected better result without much loss compared to the case of usual acid extraction. Chromatography of the alcohol extract resulted in isolation of an uncharacterised fatty alcohol (250 mg), *m.p.* 80°,  $\nu_{max}$  3490 cm<sup>-1</sup>, from the pet. ether-benzene (1:1) eluates and  $\beta$ -sitosterol (200 mg), *m.p.* 138° from the benzene

fractions. The brown residue obtained from the CHCl<sub>3</sub>-MeOH (95:5) eluates showed three spots of which two were very close on tlc [*R<sub>f</sub>*, 0.35, 0.5, 0.53, silica gel G, CHCl<sub>3</sub>-MeOH (90:10)]. The last two spots were yellow coloured (concave shaped) and turned pinkish yellow after staining with iodine (phenolic). They showed bright pinkish red uv fluorescence. On repeated chromatography, the CHCl<sub>3</sub>-MeOH eluates on concentration showed a white amorphous solid to float on the surface of the deep wine red coloured solution. The white solid on repeated crystallisations from CHCl<sub>3</sub>-MeOH-CH<sub>3</sub>COCH<sub>3</sub> mixture afforded  $\beta$ -sitosterol-O- $\beta$ -D-glucoside, *m.p.* 265-70°d,  $\nu_{max}$  3420 (br OH), 2940, 1460, 1372, 1155, 1065 and 1020 cm<sup>-1</sup>, acetate (Py/Ac<sub>2</sub>O, 40 hr, r.t.) *m.p.* 168°, [ $\alpha$ ]<sub>D</sub>-27° (c, 1.77, CHCl<sub>3</sub>),  $\nu_{max}$  1740 and 1220 cm<sup>-1</sup>. Hydrolysis of  $\beta$ -sitosterol-O- $\beta$ -D-glucoside in 10% H<sub>2</sub>SO<sub>4</sub> in aqueous MeOH (reflux 1hr) afforded  $\beta$ -sitosterol after usual work-up and the aqueous sugar part was found to contain D-glucose identified by paper chromatography with authentic sample.

**Isolation of atheroline :** After separation of  $\beta$ -sitosterol-O- $\beta$ -D-glucoside, the wine red coloured filtrate was concentrated and found to have two yellow coloured spots, *R<sub>f</sub>* 0.50, 0.53 of varying intensity, similar to those of residue-A obtained by acid extraction of the alcohol extract. The mixed brown residue (10 g) was then chromatographed over silica gel (100-200 mesh) but as the *R<sub>f</sub>* values of both the components (phenolic alkaloids) were close, separation by chromatography alone was not possible. Repeated careful fractional crystallisations from CHCl<sub>3</sub>-MeOH-ether mixture and chromatography of the mother liquors followed by fractional crystallisations ultimately effected their separation. The major snuff coloured alkaloid (25 mg) was subsequently identified to be atheroline (comparison with an authentic sample obtained through the courtesy of Prof. M. P. Cava), *m.p.* 248-50°d, *R<sub>f</sub>* 0.54 [silica gel G, CHCl<sub>3</sub>-MeOH (90:10)],  $\nu_{max}$  3270, 1635, 1565, 1505, 1450, 1425, 1350, 1270, 1242, 1220, 1138, 1054 and 1000 cm<sup>-1</sup>; acetate (Py/Ac<sub>2</sub>O, 48 hr, r.t.), *m.p.* 190°d, crystallised from CHCl<sub>3</sub>-pet. ether as yellow needles,  $\nu_{max}$  1745, 1640, 1585, 1495, 1450, 1340, 1205, 1110 and 1010 cm<sup>-1</sup>.

**Attempted catalytic hydrogenation of atheroline :** Atheroline (8 mg) in AcOH was hydrogenated at r.t. for 2 hr using PtO<sub>2</sub> as catalyst (2 moles of H<sub>2</sub> consumed) to a pale yellow solution which turned reddish brown on exposure to air for work-up. The residue after usual work-up and chromatographic purification was found to be identical with atheroline, *m.p.* 230°d.

**Action of NaBH<sub>4</sub> on atheroline :** Atheroline (8 mg) in dry MeOH (8 ml) was treated with excess NaBH<sub>4</sub> (40 mg) and kept for 48 hr. After usual work-up, the resulting yellowish brown mass on chromatography afforded atheroline (5 mg), *m.p.* 240°d.

**Isolation of machigline :** After removal of atheroline by repeated chromatography and crystallisations, the mother liquors were mixed and

concentrated. The residue was chromatographed over neutral alumina (B.D.H.). The  $\text{CHCl}_3$ -MeOH (80 : 20) eluates on evaporation yielded machigline in poor yield (20 mg) crystallising from MeOH as glistening red needles,  $R_f$  0.5 [ $\text{CHCl}_3$ -MeOH (90 : 10)], m.p.  $315^\circ\text{d}$ , bright pink fluorescence in uv light,  $\nu_{\text{max}}$  3520, 1635, 1575, 1522, 1465, 1426, 1355, 1280, 1212, 1140, 1092, 1055, 965 and  $863\text{ cm}^{-1}$ .

**Preparation of machigline acetate:** Machigline (6 mg) was treated with pyridine (3 drops) and  $\text{Ac}_2\text{O}$  (1 ml) and warmed for 10 min on water bath and then kept for 48 hr. After usual work-up, machigline acetate was obtained as red needles, m.p.  $230^\circ\text{d}$  from  $\text{CHCl}_3$ -petrol mixture.  $\nu_{\text{max}}$  1730, 1640, 1575, 1522, 1460, 1250 and  $962\text{ cm}^{-1}$ .

**Conversion of machigline to dicentrinone:** A methanolic solution (3 ml) of machigline (5 mg) was added to an excess of ethereal diazomethane solution when a yellow solid settled down due to its insolubility in ether. It was then kept with excess of the reagent at r.t for 3 days. The yellow solid obtained after removal of ether was found to be a mixture of dicentrinone (identified by comparison of spectra of authentic dicentrinone obtained from Prof. M. P. Cava) and unreacted machigline, which was separated by chromatography. Dicentrinone ( $M^+$  335) had m.p.  $300^\circ\text{d}$ , crystallised from  $\text{CHCl}_3$ -MeOH solution,  $\nu_{\text{max}}$  1640, 1052 and  $962\text{ cm}^{-1}$ .

**Isolation of 10-hydroxypalmitone from  $\text{CHCl}_3$  extract:** Separation of lignan constituents of *M. glaucescens* has been described in an earlier communication. Analysis of its aliphatic constituents resulted in the isolation of 10-hydroxypalmitone from  $\text{CHCl}_3$  and  $\text{CHCl}_3$ -MeOH (98 : 2) eluates of the main chromatogram, crystallised from pet. ether and  $\text{CHCl}_3$  mixture as globules and from  $\text{CHCl}_3$ -MeOH mixture as flakes, m.p.  $96^\circ$ ,  $[\alpha]_D^{20} \pm 0^\circ$  ( $\text{CHCl}_3$ ),  $\nu_{\text{max}}$  3320, 2930, 2870 and  $1706\text{ cm}^{-1}$ , acetate, m.p.  $43^\circ$  (pet.ether-benzene),  $\nu_{\text{max}}$  1720 and  $1240\text{ cm}^{-1}$ .

**$\text{NaBH}_4$  reduction of 10-hydroxypalmitone to n-hentriacontan-10,16-diol:** 10-Hydroxypalmitone (15 mg) was added to an excess of  $\text{NaBH}_4$  in MeOH solution and was kept at r.t for 40 hr. The diol (VII), m.p.  $99^\circ$ , was isolated after usual work-up and crystallisation from  $\text{CHCl}_3$ -MeOH mixture,  $[\alpha]_D^{20} \pm 0^\circ$  ( $\text{CHCl}_3$ ),  $\nu_{\text{max}}$   $3300\text{ cm}^{-1}$ , m/e

(%) 450 ( $M^+ - \text{H}_2\text{O}$ , 4.5), 43 (m/e 450- $\text{H}_2\text{O}$ , 11.2), 323 (20.9), 309 (32.2), 305 (13.9), 291 (17.1), 257 (8.8), 241 (40.6), 239 (83.5), 221 (47.5), 210 (17.7), 208 (13.6), 194 (8.8), 171 (21.8), 157 (15.5), 137 (20.7), 125 (23.7), 111 (39.9), 83 (100.0) and 57 (83.5).

#### Acknowledgement

The authors thank Professor M. P. Cava for an authentic sample of atheroline and the ir and pmr spectra of dicentrinone, and also Professor F. Bholmann, Professor A. H. Jackson and Professor E. Ninomiya for the mass and pmr spectra of some compounds.

#### References

- 1 SHANG-TEH LU, *Yakugaku Zasshi*, 1963, 83, 214; 1965, 85, 588; 1967, 87, 1278.
- 2 M. TOMITA and M. KOZUKA, *Yakugaku Zasshi*, 1964, 84, 362.
- 3 S. K. BAVEYA, M. L. GORH and M. P. JONEYA, *Indian J. Pharm.*, 1968, 30, 11.
- 4 B. TALAPATRA, T. RAY and S. K. TALAPATRA, *Indian J. Chem.*, 1976, 14B, 613, *J. Indian Chem. Soc.*, 1978, 55, 1204.
- 5 S. K. TALAPATRA, S. P. GOSWAMI and B. TALAPATRA, Sixth National Symposium on Organic Chemistry (NASOC-VI), Department of Chemistry, University of Calcutta, March 22-23, Abstract, 1982, p. 28.
- 6 I. R. C. BICK and G. K. DOUGLAS, *Tetrahedron Lett.*, 1965, 2399, 4655.
- 7 M. P. CAVA, K. V. RAO, B. DOUGLAS and J. WEISBACH, *J. Org. Chem.*, 1968, 33, 2443.
- 8 A. C. CHIBNAL, S. H. PIPER, H. A. MANGOURI, E. F. WILLIAMS and A. V. V. IYENGAR, *Biochem J.*, 1937, 31, 1981.
- 9 R. H. F. MANSKE, "The Alkaloids, Chemistry and Physiology", Academic Press, New York, London, 1973, Vol. 14, p. 257.
- 10 K. NAKANISHI, "Infrared Absorption Spectroscopy", Holden-Day Inc., San Francisco, 1964, p. 36.
- 11 I. R. C. BICK and G. K. DOUGLAS, *Tetrahedron Lett.*, 1964, 1629.
- 12 W. M. HARRIS and T. A. GEISSMAN, *J. Org. Chem.*, 1965, 30, 432.
- 13 F. N. LAHFY and K. F. MAK, *Tetrahedron Lett.*, 1970, 4511.
- 14 S. K. TALAPATRA, A. PATRA and B. TALAPATRA, *Chem. and Industry*, 1969, 1056.
- 15 M. P. CAVA and A. VENKATESWARLU, *Tetrahedron*, 1971, 27, 2639.
- 16 S. T. LU, S. J. WANG, P. H. LAI, C. M. LING and C. L. LIN, *J. Pharm. Soc. Japan*, 1972, 92, 910.
- 17 I. R. C. BICK, J. H. BOWIE and G. K. DOUGLAS, *Aust. J. Chem.*, 1967, 20, 1403.
- 18 J. W. SKILES and M. P. CAVA, *J. Org. Chem.*, 1979, 44, 409.
- 19 C. H. PHOEBE, P. L. SCHIFF, J. E. KNAPP and D. J. SLATKIN, *Heterocycles*, 1980, 14, 1977.

# Structure and Synthesis of Mukoline and Mukolidine, Two New Carbazole Alkaloids from *Murraya koenigii* Spreng.

SHYAMALI ROY, LINA BHATTACHARYYA

and

D. P. CHAKRABORTY\*

Bose Institute, Calcutta-700 009


Mukoline and mukolidine, two new carbazole alkaloids from *Murraya koenigii* Spreng, have been assigned the structures 6-hydroxy-methyl-1-methoxy carbazole and 6-formyl-1-methoxy carbazole, respectively

IN continuation of our interest in the carbazole alkaloids of the genus *Murraya*<sup>1</sup>, we now report two minor alkaloids of C-13 skeleton isolated from the benzene extract of the roots of *Murraya koenigii* Spreng. The first compound,  $C_{14}H_{15}NO_2$ , mukoline (I), m.p. 115-20°, was optically inactive and gave a red picrate, m.p. 230°. The uv spectrum of I [ $\lambda_{max}^{EtOH}$  221 (4.60), 242 (4.85), 252 (4.65), 258 (4.0), 280 (3.4), 290 (3.6), 320 (3.0) nm] suggested the presence of a 1-methoxy carbazole chromophore in it. The ir spectrum showed the presence of a hydroxyl group, NH-function and aromatic residuc [ $\nu_{max}^{KBr}$  3440, 3240, 1610  $cm^{-1}$ ]. The nmr spectrum of mukoline (in  $CDCl_3$ ) indicated the presence of NH-function ( $\delta$  8.22), aromatic protons ( $\delta$  7.0-7.9), deshielded benzylic methylene protons ( $\delta$  4.75), a hydroxyl proton ( $\delta$  4.45), aromatic methoxy protons ( $\delta$  3.9) and the meta-coupled aromatic proton at C-5 ( $J=2$  cps).

The mass spectrum of I showed a molecular ion peak at m/e 227 and other significant peaks were at m/e 212 (M-15), 196 (M-31), 154 (M-15-31-28). The peak at m/e 154 could be represented by the ionic species (II) previously reported from glycozoline<sup>2</sup> and mukonine<sup>3</sup>.

Mukoline (I) on methylation with  $K_2CO_3$  in acetone furnished the N-methyl derivative  $C_{15}H_{17}NO_2$ , m.p. 140° the uv spectrum of which was very similar to that of 1-methoxy carbazole. On acetylation, mukoline (I) gave an o-acetate (III)  $C_{16}H_{17}NO_3$ , m.p. 145° [ $M^+$  269]  $\nu_{max}$  1720  $cm^{-1}$ . The uv spectrum of the acetate was similar to that of I showing that the hydroxyl group was in the side chain. These data together with the nmr spectral data of I were suggestive of the presence of a  $CH_2OH$  group on carbazole nucleus which was confirmed by oxidation of I to its formyl derivative (IV),  $C_{14}H_{13}NO_2$ , m.p. 152-55°,  $\nu_{max}$  1660  $cm^{-1}$ , [ $M^+$  225]. The uv spectrum of (IV) [ $\lambda_{max}$  238 (4.74), 248 (4.46), 275 (4.82), 290 (4.48), 330 (4.34)]

was very similar to that of 3-formyl carbazole but not super-imposable with murrayanine<sup>4</sup> (V). It (IV) was also not identical with murrayanine (V) [m.p., m.m.p., tlc]. The aldehyde (IV) on decarbonylation furnished 1-methoxy carbazole [ $\lambda_{max}$  241 (4.5), 286 (3.84), 320 (3.46)] confirming that IV is 1-methoxy-6-formyl carbazole. Therefore, mukoline could be formulated as 1-methoxy-6-hydroxy methyl carbazole. This was also substantiated by comparison of I with 1-methoxy-3-hydroxy methyl carbazole<sup>4</sup>, previously obtained by Na-borohydride reduction of murrayanine (V), when it was found that these two compounds were nonidentical.




Along with mukoline, another homogeneous, optically inactive carbazole alkaloid  $C_{14}H_{13}NO_2$ , m.p. 152-55°, [ $M^+$  225] was obtained from the same plant. The compound, named mukolidine (IV), gave a 2,4-DNPH derivative. The ir spectrum of mukolidine showed the presence of a NH-function (3185  $cm^{-1}$ ), aldehyde function (1660  $cm^{-1}$ ) in an aromatic system. The uv spectrum of IV [ $\lambda_{max}$  238, (4.74), 248 (4.46), 275 (4.82), 290 (4.48), 330 (4.34)] was very similar to that of a 3-formyl carbazole.

\* Dedicated to Professor A. K. Dey on the occasion of his 60th birth day anniversary. Part 50 in Chemical (Molecular) Taxonomy.

The nmr data of IV showed the presence of an aldehyde proton ( $\delta$  10.8, s, 1H), -NH- proton ( $\delta$  8.6, s, 1H), aromatic protons ( $\delta$  8.15, 8.08, 7.3-7.6) and an aromatic methoxy group ( $\delta$  4.05, s, 3H). The nmr data together with the mass spectral fragmentation [ $m/e$  225, 210, 182, 167] showed it to be a 3 or 6 formyl carbazole with methoxy group in it. The position of the methoxyl group was determined by decarbonylation of IV when 1-methoxy carbazole was obtained. On borohydride reduction mukolidine (IV) furnished an alcohol identical with mukoline (I) (m.m.p., ir, uv). So, it appeared that mukolidine was 1-methoxy-6-formyl carbazole and was identified with the oxidation product of mukoline as detailed above (m.m.p., ir, uv). The conclusions were supported by synthesis below.

2-Hydroxy methylene cyclohexanone (VI) was reacted with toluene diazonium chloride (VII) under Japp-Klingemann conditions when 1,2-dione-1'-(4'-methyl) phenyl hydrazone (VIII), m.p. 205° was obtained. The hydrazone (VIII) on indolization with a mixture of acetic acid and hydrochloric acid furnished 6-methyl-1-oxo-1,2,3,4-tetrahydro carbazole (IX), m.p. 190° which on dehydrogenation with Pd/C at 180° gave a 6-methyl-1-hydroxy carbazole (X). On methylation with diazomethane, the hydroxy compound (X) gave a crystalline homogeneous methoxy derivative (XI), m.p. 150°. On oxidation with DDQ, the compound (XI) gave an aldehyde which was found to be identical with mukolidine (IV) by direct comparison. The synthetic mukolidine on reduction with sodium borohydride furnished the hydroxymethyl derivative, m.p. 115-20° which was found identical with mukoline (I). Thus the structures of (I) and (IV) were confirmed by synthesis.



The oxidative functional variants of C-methyl group at 3-position\* i.e., CHO, COOH, COOMe have been encountered in carbazole alkaloids. Mukoline provides the first example of the occurrence of hydroxymethyl group, an oxidative variant of  $\text{CH}_3$ , at 6-position of carbazole alkaloids. The hydroxymethyl group of mukoline (I) has been oxidised to CHO group in mukolidine (IV).

#### Experimental

All melting points are uncorrected. Petroleum ether used had the b.p. 60-80° unless otherwise mentioned. The alumina for column chromatography and the silica gel for thin layer chromatography were supplied by Sarabhai Chemicals of India.

graph and the silica gel for thin layer chromatography were supplied by Sarabhai Chemicals of India.

**Isolation of mukoline (I) and mukolidine (IV).** Air dried finely powdered roots of *Murraya koenigii* Spreng. (1Kg) was Soxhleted for 48 hr with benzene. The extract was concentrated and chromatographed over alumina. The petroleum ether extract on evaporation gave a solid residue which on recrystallisation from benzene yielded mukolidine, m.p. 152-55°. [Found: C, 74. ; H, 4.55, N, 6.06; O, 14.4.  $\text{C}_{14}\text{H}_{11}\text{NO}_2$  requires C, 74.6; H, 4.8, N, 6.2; O, 14.2%]. It gave a 2,4-DNPH derivative melting at 300°.

The benzene, benzene-chloroform eluents from the same chromatographic column on evaporation gave an oily residue which on recrystallisation from a mixture of benzene and petroleum ether furnished homogeneous crystals of mukoline, m.p. 115-20° which on recrystallisation melted at 118°. [Found: C, 73.85; H, 5.70; N, 6.15;  $\text{C}_{14}\text{H}_{11}\text{NO}_2$  requires C, 74.0; H, 5.72; N, 6.16%]. It gave a picrate which on crystallisation from benzene melted at 230°.

**N-methyl mukoline.** A mixture of mukoline (25 mg) in dry acetone (12.5 ml), methyl iodide (0.5 ml) and potassium carbonate (250 mg) was refluxed for 6 hr. It was then filtered. On working up, the filtrate furnished crystals which after filtration and recrystallisation from benzene-pet. ether mixture gave a homogeneous compound, m.p. 140° [Found: C, 74.5; H, 6.1; N, 5.6.  $\text{C}_{15}\text{H}_{12}\text{NO}_2$  requires C, 74.6; H, 6.2; N, 5.7%].

**Acetylation of mukoline:** Mukoline (10 mg) in acetic anhydride (0.1 ml) was heated with sodium acetate on water bath for 6 hr. The reaction product on working up furnished crystals which on recrystallisation from benzene-pet. ether mixture melted at 145°. [Found: C, 78.65; H, 5.46; N, 5.15.  $\text{C}_{15}\text{H}_{12}\text{NO}_4$  requires C, 78.80; H, 5.57; N, 5.20%].

**Oxidation of mukoline with active  $\text{MnO}_2$ :** Formation of the formyl derivative (IV): To a solution of mukoline (50 mg) in dry  $\text{CCl}_4$  (30 ml), active  $\text{MnO}_2$  (500 mg) was added. The mixture was stirred for 5 hr and filtered. The filtrate after removal of the solvent yielded a solid, m.p. 152-55° which on sublimation and recrystallisation from benzene-pet ether mixture melted at 152-55°.

**Decarbonylation of the oxidation product (IV).** formation of 1-methoxy carbazole (V): The above oxidation product (40 mg) was mixed with Pd/C (20 mg) and heated in a vacuum sealed tube in presence of 1 ml of dry alcohol for 15 min at 270°. The reaction product was taken in benzene-pet ether mixture and allowed to crystallize when 1-methoxy carbazole, m.p. 69-70° was obtained and identified by thin layer chromatography, uv and m.m.p. with an authentic 1-methoxy carbazole.

**Na-borohydride reduction of mukolidine:** Sodium borohydride (25 mg) was added in cold to a solution



of mukolidine (150 mg) in dry methanol (8 ml). The solution was kept at room temperature for 2 hr. On working up the reaction mixture, and crystallisation from benzene-chloroform mixture, homogeneous crystals, m.p. 115-20° were obtained. Identification of this reduction product with natural mukoline was established by comparison of m.p., uv and ir.

**Preparation of cyclohexane-1,2-dione-1'-(4-methyl phenyl) hydrazone (VIII) :** To a solution of 2-formyl cyclohexanone (3.2 g), sodium acetate (5 g) in water was added and the mixture stirred. A diazotised solution of *p*-toluidine (3.0 g) at 0-5° was added to it gradually during 40 min. The precipitate (VIII) was filtered, washed and dried. It was crystallised from benzene-petrol mixture, m.p. 205°. [Found: C, 71.90; H, 7.21; N, 12.30.  $C_{18}H_{18}N_2O$  requires C, 72.22; H, 7.40; N, 12.49%].

**Preparation of 6-methyl-1-oxo-tetrahydro carbazole (IX) :** The above hydrazone (1.4 g) was added to boiling glacial acetic acid (13 ml). Conc. HCl (3.1 ml) was added to it through reflux condenser and the whole mixture was boiled for 3-4 min. The reaction product was poured into ice and stirred. The white crystals of the oxo-compound (IX) appeared which were filtered, washed and dried. It was recrystallized from benzene, m.p. 190°. [Found: C, 64.82; H, 6.51; N, 7.01.  $C_{18}H_{18}NO$  requires C, 65.0; H, 6.53; N, 7.03%].

**Preparation of 1-hydroxy-6-methyl carbazole (X) :** The above oxo-compound (75 mg) in dry alcohol (5 ml) was dehydrogenated at 250-70° for 4 hr in a sealed evacuated tube in presence of Pd-C catalyst (10%; 0.7 mg). The reaction product was then made free from catalyst and solvent and the only residue taken in ether. The ether solution was extracted with 2% alkali. The alkali portion was taken, acidified and again extracted with ether. On removal of ether, the residue was taken in benzene, filtered through silica gel bed for purification. Finally, an oily mass was obtained on evaporation of the solvent.

**Preparation of 1-methoxy-6-methyl carbazole (XI) :** The above hydroxy compound (X) in methanol was treated with an ethereal solution of diazomethane at 0-5° and the whole mixture was kept overnight in a refrigerator. After the removal of diazomethane and the solvent, the residue was taken in benzene and crystallised. The crystals were filtered, washed and dried, m.p. 150°. [Found: C, 79.70; H, 6.28; N, 6.42.  $C_{18}H_{18}NO$  requires C, 79.59; H, 6.20; N, 6.63%].

**Preparation of mukolidine (IV) by DDQ oxidation of 1-methoxy-6-methyl carbazole (XI) :** To a stirring solution of 1-methoxy-6-methyl carbazole (40 mg) in benzene, a solution of DDQ (20 mg) in dry benzene was added through a period of 15 min. The stirring was continued for 1/2 hr. The colour of the solution gradually changed from deep green to deep blue. The reaction product was then washed with 1% NaOH and extracted with ether. The ether solution was washed, dried and evaporated. The residue was taken in benzene and subjected to preparative thin layer chromatography in the solvent system  $C_6H_6-CHCl_3$  (1:1). The spot, identical with natural mukolidine, was scraped out from the plate, taken in alcohol, warmed and filtered. The filtrate on evaporation gave a solid which on crystallization from benzene furnished homogeneous crystals, m.p. 152-55°, identical with mukolidine in all respects (uv, ir, m.p., m.m.p.,  $R_f$ ).

#### Acknowledgement

The authors thank Prof. S. C. Bhattacharyya, Director, and Prof. A. K. Barua, Chairman, Chemistry Department, Bose Institute

#### References

1. D. P. CHAKRABORTY, *Fortschritte der Chem. Org. Natur.*, 1979, 34, 299.
2. D. P. CHAKRABORTY, *Tetrahedron Lett.*, 1966, 661.
3. D. P. CHAKRABORTY, P. BHATTACHARYYA, S. ROY, S. P. BHATTACHARYYA and A. K. BISWAS, *Phytochem.*, 1978, 17, 834.
4. D. P. CHAKRABORTY, B. K. BARMAN and P. K. BOSE, *Tetrahedron*, 1965, 21, 681.
5. D. P. CHAKRABORTY, *Planta Medica*, 1980, 59, 1929.

# Synthesis of Pyrano/Pyrido Benzothiophene Derivatives. Part—I


J. N. CHATTERJEA and RADHIKA P SAHAI

Department of Chemistry, Patna University, Patna-800 005

A synthesis of 3-methoxycarbonylbenzo[b]thiophene-2-acetate and 2-formyl-3-methoxycarbonylbenzo[b]thiophene is reported. These key compounds have been converted into condensed heterocycles by standard methods.

THE impetus of the work reported herein arose from our success in the synthesis of 1H-pyrano-[3,4-b]benzofuran-1-one derivatives and their 2-aza analogues<sup>1</sup>. Parallel exploratory studies were instituted with benzo[b]thiophene, a description of which forms the subject matter of the present paper.

Benzo[b]thiophene-2,3-dicarboxylic acid (I) which was prepared by a modified method of the earlier published method<sup>2</sup> was esterified with methanolic sulphuric acid to the dimethyl ester, which on controlled hydrolysis afforded the half-ester (II). Alternatively, the half-ester was obtained in good yield by the methanolysis of the anhydride<sup>3</sup> of I. The pmr spectrum of II showed resonances at  $\tau$  1.5-2.9 for 4 aromatic protons, and singlets at  $\tau$  5.85 (3H, COOCH<sub>3</sub>) and  $\tau$  3.1 (1H, COOH, exchangeable with D<sub>2</sub>O). Confirmation of the structure is based on the identification of its decarboxylation product (III) which, on hydrolysis, afforded the known acid<sup>4</sup> (IV). On homologation, the half-ester (II) afforded the di-ester (V) which showed absorptions at 1710 and 1740 cm<sup>-1</sup>. The related acid (VI) ( $\nu$ CO 1695, 1715 cm<sup>-1</sup>) was obtained on alkaline hydrolysis. This di-acid, on treatment with acetyl chloride gave the anhydride (IX) which showed carbonyl absorptions at 1745 and 1780 cm<sup>-1</sup> (the ir data are similar to those observed in homophthalic anhydride).




- (I) R = R<sub>1</sub> = COOH
- (II) R = COOH, R<sub>1</sub> = COOMe
- (III) R = H, R<sub>1</sub> = COOMe
- (IV) R = H, R<sub>1</sub> = COOH
- (V) R = CH<sub>2</sub>COOMe, R<sub>1</sub> = COOMe
- (VI) R = CH<sub>2</sub>COOH, R<sub>1</sub> = COOH
- (VII) R = CH<sub>2</sub>OH, R<sub>1</sub> = COOMe
- (VIII) R = CHO, R<sub>1</sub> = COOMe

The di-ester (V) on Stobbe condensation<sup>4</sup> with benzaldehyde gave the related half-ester which, without isolation, was hydrolysed to give  $\alpha$ -benzylidene-3-carboxybenzo[b]thiophene-2-acetic acid. This readily furnished the anhydride (X) ( $\nu$ CO 1725, 1759 cm<sup>-1</sup>) on treatment with acetic anhydride. The ester (V) on condensation with ethyl oxalate<sup>5</sup> followed by the cyclisation of the resulting keto-ester and preferential decarboxylation gave the pyrano


carboxylic acid (XI) ( $\nu$ CO 1700, 1730 cm<sup>-1</sup>). On account of paucity of material (XI) its conversion into XII by ammonia was not possible.

The nitrogen analogue (XII) however was secured from the half-ester (II). The related acid chloride was reduced by NaBH<sub>4</sub> in dioxane to the alcohol<sup>6</sup> (VII,  $\nu_{max}$  1710, 3420 cm<sup>-1</sup>; yield, 67%). Experiments on the oxidation of the alcohol with activated manganese dioxide<sup>7,8</sup> or chromic acid/pyridine<sup>9</sup> led to the formation of I. Dehydrogenation of the alcohol however proceeded smoothly with 2,3-dichloro-5,6-dicyanobenzoquinone (DDQ)<sup>10</sup> when the aldehyde (VIII) was secured in good yield. The aldehydic ester on treatment with hippuric acid, sodium acetate and acetic anhydride gave the related azlactone which on subsequent hydrolysis<sup>11</sup> with alkali gave the pyrido carboxylic acid (XII,  $\nu$ CO 1660, 1700 cm<sup>-1</sup>).



(IX)

(X)



(XI) x = O  
(XII) x = NH

## Experimental

All m.p.s are uncorrected. The infrared spectra were measured as KBr disc and obtained with a Perkin Elmer spectrophotometer, Model 237. The pmr spectrum was recorded in a Varian A-60 apparatus with TMS as internal standard.

**Methyl benzo[b]thiophene-2,3-dicarboxylate:** A solution of chloroacetic acid (2.84 g) was carefully neutralised with sodium carbonate solution (4 N) and added to a solution of benzo[b]thiophene-2,3-dione (4.53 g) in sodium carbonate solution (34 ml; 2 N) at 60-70° and the temperature maintained with stirring for 3 hr. On acidification, benzo[b]thiophene-2,3-

dicarboxylic acid (4.1 g), m.p. 250° separated. This was esterified with methanol (50 ml) containing sulphuric acid (2 ml) for 24 hr. The dimethyl ester crystallised from methanol in stout prisms, m.p. 91° (lit.<sup>2</sup>, m.p. 91°).

**2-Methoxycarbonylbenzo[b]thiophene-2-carboxylic acid:** The foregoing ester (0.5 g) was refluxed with methanolic potash (1.2 ml; 10%) for 25 min. Methanol was removed under reduced pressure and the residue dissolved in water. Any unchanged ester was removed with ether. On acidification and cooling, the half-ester separated as a cream coloured solid. This was collected, dried and crystallised from benzene and obtained as pale yellow needles (0.3 g), m.p. 163°. (Found: C, 55.8; H, 3.4.  $C_{11}H_6O_4S$  requires C, 55.9; H, 3.4%).

**Alternative method:** Benzo[b]thiophene-2,3-dicarboxylic anhydride (m.p. 171°;  $\nu_{CO}$  1780, 1825  $cm^{-1}$ ) (1.0 g) was refluxed with dry methanol (5 ml) for 3.5 hr. The solvent was removed under reduced pressure. The residue taken up in ether and extracted with saturated  $NaHCO_3$  solution. This on acidification furnished the half-ester, m.p. 163°, in quantitative yield.

**Benzo[b]thiophene-3-carboxylic acid:** The foregoing half-ester (0.35 g) was intimately mixed with copper bronze (0.1 g) and the mixture distilled on a metal bath. Methyl benzo[b]thiophene-3-carboxylate (0.28 g) distilled at 165–66°/17 mm. This was hydrolysed without purification by boiling under reflux with sodium hydroxide solution (0.6 ml; 10%) for 1.5 hr. On acidification, the acid was obtained as a colourless solid in quantitative yield, m.p. 175–76° (lit.<sup>2</sup>, m.p. 174–75°). (Found: C, 60.4; H, 3.4.  $C_9H_6O_4S$  requires C, 60.7; H, 3.4%).

**Methyl 3-methoxycarbonylbenzo[b]thiophene-3-acetate:** The half-ester (1.4 g) in dry benzene (6 ml) was refluxed with thionyl chloride (2 ml) for 3 hr. Benzene and excess of thionyl chloride were removed under reduced pressure and the resulting crystalline acid chloride (m.p. 61°) in dry ether was added to cooled ethereal diazomethane (from nitrosomethyl urea 6 g) and left overnight in a refrigerator. Removal of the solvent yielded the diazoketone as an oil which was taken up in dry methanol (30 ml) and heated on the water bath with a slurry of silver oxide (0.20 g) in methanol (20 ml) which was added from time to time until the evolution of nitrogen subsided (20 hr). The mixture was clarified by charcoal, filtered and solvent removed. The residue on distillation furnished a pale yellow oil (0.7 g) at 122–28°/0.3 mm which solidified. The ester crystallised from methanol in pale cream needles, m.p. 83°. (Found: C, 58.9; H, 4.5.  $C_{11}H_{10}O_4S$  requires C, 59.1; H, 4.6%).

**3-Carboxybenzo[b]thiophene-2-acetic acid:** The foregoing ester (0.25 g) was hydrolysed by boiling with NaOH solution (1 ml; 10%) for 2 hr. On acidification the related dicarboxylic acid was obtained which crystallised from alcohol in colourless needles, m.p. 235° (evolution of gas). (Found: C, 55.8; H, 3.4.  $C_{11}H_6O_4S$  requires C, 55.9; H, 3.4%).

**Anhydride. Pyrano(4,3-b)benzothiophene-1,3-(1H, 3H,4H)-dione:** This was obtained by heating the dicarboxylic acid (0.1 g) with acetyl chloride (2 ml) for 4 hr. This crystallised from dry benzene in cream coloured needles, m.p. 204–5°. (Found: C, 60.5; H, 2.7.  $C_{11}H_6O_4S$  requires C, 60.6; H, 2.8%).

**$\alpha$ -Benzylidene-3-carboxybenzo[b]thiophene-2-acetic acid:** A mixture of freshly distilled benzaldehyde (0.22 g) and methyl 3-methoxycarbonylbenzo[b]thiophene-2-acetate (0.53 g) was added to alcoholic sodium methoxide (sodium 0.05 g, methanol 4 ml) and refluxed for 6 hr. The residual mass after the removal of solvent was dissolved in water, extracted with ether to remove unchanged ester and then boiled with the addition of aqueous sodium hydroxide (3 ml, 10%) for 2 hr, cooled, and acidified. The sticky mass solidified on trituration with benzene. The compound (0.54 g) crystallised from alcohol in yellowish needles, m.p. 208° (evolution of gas). (Found: C, 66.5; H, 3.7.  $C_{18}H_{12}O_4S$  requires C, 66.7; H, 3.1%).

The anhydride was obtained by heating the dicarboxylic acid (0.1 g) with acetic anhydride (2 ml) for 10 min. This crystallised from benzene in deep yellow needles (0.06 g), m.p. 195°. (Found: C, 70.4; H, 3.2.  $C_{18}H_{10}O_4S$  requires C, 70.6; H, 3.3%).

**Condensation with ethyl oxalate:** A mixture of ethyl oxalate (0.17 g) and methyl 3-methoxycarbonylbenzo[b]thiophene-3-acetate (0.27 g) was added to alcohol free sodium ethoxide (from sodium, 0.03 g) in dry benzene when the colour turned brown. The mixture was left overnight in the refrigerator and next day, dilute sodium hydroxide solution (1 ml; 1 N) followed by ether was added to it. The alkaline solution was separated, acidified and extracted with ether. On removal of the solvent the glyoxalyl derivative separated as an oil which was dissolved in acetic acid (0.5 ml) and treated with concentrated hydrochloric acid (0.25 ml), warmed on the water bath for 30 min and cooled. After removal of volatile matter under reduced pressure, the brownish oily residuc (0.15 g) was refluxed with a mixture of acetic acid (1.5 ml) and conc. hydrochloric acid (0.8 ml) for 3 hr. A brown solid separated on cooling which was crystallised to give pyrano(4,3-b)benzothiophene-1-oxo-3(1H)-carboxylic acid which separated from alcohol in pale brown needles (0.1 g), m.p. 272°. (Found: C, 58.3; H, 2.3.  $C_{12}H_6O_4S$  requires C, 58.6; H, 2.5%).

**Methyl 2-Hydroxymethylbenzo[b]thiophene-3-carboxylate:** A solution of the half-ester (1.2 g) in dry benzene (5 ml) was refluxed with thionyl chloride (2 ml) for 3 hr. On removal of solvent, the resulting acid chloride was taken up in dry dioxane (0.8 ml) and added in instalments to a suspended mass of sodium borohydride (0.29 g) in dioxane (5 ml) with efficient stirring and left overnight with continuous stirring. Next day, the mixture was heated on a water bath for 8 hr, cooled and the complex decomposed carefully with iced dilute hydrochloric acid. The resulting oil was taken up with ether, washed with  $NaHCO_3$  solution and dried,

On removal of the solvent, the alcohol solidified. This crystallised from alcohol in colourless wooly needles (0.8 g), m.p. 193°. (Found : C, 59.5 ; H, 4.4.  $C_{11}H_{10}O_4S$  requires C, 59.5 ; H, 4.5%).

**Methyl 3-formylbenzo[b]thiophene-3-carboxylate :** The foregoing alcohol (0.66 g) in dry benzene (10 ml) was refluxed with DDQ (0.68 g) for 30 min and filtered hot. On removal of the solvent the aldehydic ester was obtained as a darkish oil. The 2,4-DNP crystallised from acetic acid as orange needles, m.p. 254-55° (decomp). (Found N, 13.9.  $C_{17}H_{14}O_6-N_4S$  requires N, 14.0%)

**Azlactone :** The foregoing aldehyde (0.45 g) was mixed with hippuric acid (0.5 g), fused sodium acetate (0.2 g) and acetic anhydride (1.2 ml). The mixture was heated on the water bath for 3 hr, cooled and filtered. The residue thus obtained was washed with alcohol affording the azlactone crystallising from acetic acid in silky yellow needles (0.35 g), m.p. 223° (Found : C, 66.0 ; H, 3.6 ; N, 3.8.  $C_{20}H_{14}O_4NS$  requires C, 66.1 ; H, 3.6 ; N, 3.9%).

**Pyrido (4,3-b)benzo[thiophene-1-oxo-3(1H, 2H)-carboxylic acid :** The foregoing oxazolone (0.25 g) was heated with potassium hydroxide solution (4 ml ; 10%) for 2 hr. The clear yellow solution was cooled and acidified. The cream coloured solid which separated was washed with hot water and dried (0.16 g). The compound crystallised from

acetic acid in creamy needles, m.p. 354° (decomp) (Found : C, 58.5 ; H, 2.7 ; N, 5.7.  $C_{23}H_{10}O_4NS$  requires C, 58.8 ; H, 2.9 ; N, 5.7%).

#### Acknowledgement

One of the authors (R.P.S) is indebted to the University Grants Commission, New Delhi for a Teacher Fellowship and to the University of Bhagalpur for grant of study leave.

#### References

1. J. N. CHATTERJEA, R. P. SAHAI, B. B. SWAROOPA, C. BHAKTA, H. C. JHA and F. ZILLIKEN, *Chem. Ber.*, 1980, 113, 3656.
2. R. WEISSGERBER and O. KRUBER, *Chem. Ber.*, 1920, 53, 1551, A. BEZDIK, P. FRIEDLANDER and P. KOENTGER, *Chem. Ber.*, 1908, 41, 227 ; C. E. DALGLIESH and F. G. MANN, *J. Chem. Soc.*, 1945, 901.
3. G. KOMPPA, *J. Prakt. Chem.*, 1929, 122, 331.
4. W. DIECKMANN, *Chem. Ber.*, 1914, 47, 1428.
5. R. D. HAWORTH, H. K. PINDRFD and P. R. JEFFERIES, *J. Chem. Soc.*, 1954, 3617.
6. S. W. CHAIKIN and W. G. BROWN, *J. Amer. Chem. Soc.*, 1949, 71, 122.
7. J. ATTENBURROW, A. F. B. CAMERON, J. H. CHAPMAN, R. M. EVANS, B. A. HENS, A. B. A. JANSEN and T. WALKER, *J. Chem. Soc.*, 1952, 1094.
8. M. Z. BARAKAT, M. F. ABDEL-WAHAB and M. M. EISADR, *J. Chem. Soc.*, 1956, 4685.
9. J. R. HOLUM, *J. Org. Chem.*, 1961, 26, 4814.
10. E. A. BRAUDE, R. P. Linstead and K. R. WOOLDRIDGE, *J. Chem. Soc.*, 1956, 3070.
11. D. BAIN, W. H. PERKIN and R. ROBINSON, *J. Chem. Soc.*, 1914, 105, 2398.

# Some Aspects of the Chemistry of Fluorinated 1,3-Diketones\*

KRISHNA C. JOSHI

Department of Chemistry, University of Rajasthan, Jaipur-302 004

Some aspects of the chemistry of fluorinated 1,3-diketones have been discussed viz., their interdisciplinary nature, analytical applications, enolic content, metal 1,3-diketonates and their quasi-aromatic character, use as laser chelates, nmr shift reagents and synthetic applications for formation of bioactive heterocycles

**T**HE chemistry of fluorinated 1,3-diketones and related compounds has received considerable attention in recent years in view of their interdisciplinary significance and diverse uses. 1,3-Diketones (or  $\beta$ -diketones) are carbonyl compounds in which the two carbonyl groups are separated by a methylene or a substituted methylene group. The introduction of perfluoro groups in such systems imparts interesting and novel properties to these compounds. Some of these are indispensable reagents in analytical chemistry and the most recent uses are in analysing lunar samples<sup>1</sup>, cobalt in vitamin B<sub>12</sub><sup>2</sup> and detection of other trace elements in blood, serum and other essential biological materials<sup>3</sup>. The fluorinated 1,3-diketones possess excellent complex forming properties and thenoyltrifluoroacetone (TTA), furoyltrifluoroacetone (FTA), thiothenoyltrifluoroacetone (STTA) and heptafluorobutanoylpivalyl methane<sup>1</sup> (FOD) are some of the well known agents.

Synthetic routes for fluorinated 1,3-diketones are similar to those for non-fluorinated diketones with certain exceptions. One review<sup>4</sup> has recently appeared on fluoro 1,3-diketones and lists the important methods. We have synthesised a number of new polyfluorinated 1,3-diketones using Claisen condensation<sup>5-7</sup>. This involves a base prompted condensation of a fluorinated ester with a ketone containing at least one  $\alpha$  hydrogen. Sodium amide and sodium hydride have been employed as condensing agents with benzene or diethyl ether as solvent. Keto-enol tautomerism is a general characteristic of these diketones. The tautomerism of 1,3-diketones has been studied in detail by deuterium exchange reaction, Raman effect, polarographic oxidation-reduction and by spectral studies, viz., ir, uv and pmr.

The effects of fluorine substitution on enolization have been studied by Park *et al.*<sup>8</sup>. Unlike the non-fluorinated 1,3-diketones (e.g. acetylacetone), hydrogen bonding is possible in both *syn* as well as in *anti* forms in fluorinated 1,3-diketones (e.g. trifluoroacetylacetone) (Fig. 1). This explains the very high enolic content of fluorinated 1,3-diketones. In fact, ir spectra of such ketones do not show characteristic

$>C=O$  absorption band ( $1725-1708\text{ cm}^{-1}$ ). Further, intramolecular as well as intermolecular




Fig 1 Hydrogen bonding in fluorinated 1,3-diketones

hydrogen bonding are observed in the regions 2700-2500 and 3000-2900  $\text{cm}^{-1}$ , respectively. In nmr spectra, the presence of  $=CH-$  resonance signal in the region  $\delta 6.2-6.1$  ppm and enolic proton resonance signal in the region  $\delta 13-26$  ppm provide substantial support for the enolization of such compounds. The role of various substituents on the degree of enolization has been studied by us<sup>9</sup>. The enolic content of our fluorinated  $\beta$ -diketones vary considerably in the range 54.73-100%. On substitution of highly electronegative groups, such as  $\text{CF}_3$  or  $\text{C}_6\text{F}_5$ , the enol content increases as the chelate is stabilized by  $\text{O}-\text{H} \cdots \text{O}$  and  $\text{O}-\text{H} \cdots \text{F}$  intramolecular bonds. Substitution of phenyl groups at 1 or 3 or both positions, in place of  $\text{CH}_3$  group, also increases the enol percentage. It is ascribed to the stabilization of the enol tautomer due to the phenyl ring being coplanar with the enol ring and thus enabling electrons to be supplied to the enol chelate ring through resonance.

## Metal 1,3-diketonates :

The chemistry of the fluorinated metal 1,3-diketonates has aroused much recent interest in laser devices<sup>9</sup>, as nmr shift reagents<sup>10</sup> and in analytical chemistry<sup>11</sup>. Under appropriate conditions, the enolic proton of a 1,3-diketone can be replaced by different metals or their salts, forming a metal derivative which is a characteristic of 1,3-diketones (Fig. 2). Several reviews have appeared on metal 1,3-diketonate complexes and only two on fluorinated 1,3-diketonates.

\*Dedicated to Prof. Arun K. Dey on the occasion of his 60th birth day.





Fig. 2. Tautomers of 1,3-diketone : (a) and (b) ; metal 1,3-diketonate : (c).

The addition of a concentrated metal salt solution to an aqueous methanolic or aqueous ethanolic solution of fluorinated 1,3-diketones results in precipitation of metal chelates.



The metal salts usually used are acetate, nitrate, oxalate, oxychloride and chloride. The other well-known methods for preparing such compounds have been reviewed by us<sup>16</sup>. Some of the metal-diketonates studied by us are those derived from  $\text{Cu}^{2+}$ ,  $\text{Cr}^{3+}$ ,  $\text{Eu}^{3+}$ ,  $\text{Sm}^{3+}$ ,  $\text{Tb}^{3+}$  and  $\text{Gd}^{3+}$ .

#### Quasi-aromatic character :

According to Collman *et al*<sup>16</sup> and other workers<sup>17</sup>, each chelate ring in metal 1,3-diketonates has a cyclic  $\pi$ -orbital, formed by the overlapping of vacant d-orbital of the central metal atom of the 1,3-diketonate. These systems have been found to undergo typical electrophilic substitution reactions of the hydrogen atom linked to  $\text{sp}^3$  hybridized carbon atom and the metal 1,3-diketonates have been termed as quasi-aromatic.


The presence of a perfluoroalkyl group, with its accompanying inductive effect, makes electrophilic substitution slower and requires forcing conditions. We have been able to accomplish this in case of fluorinated 1,3-diketonato chromium derivatives

synthesised by us and chloro-, bromo- and nitro-substituents have been introduced at the central carbon atom of the chelate ring under carefully controlled conditions<sup>18</sup> (Scheme 1)

The quasi-aromaticity of transition metal 1,3-diketonates is well established by now but the quasi-aromatic nature of lanthanide 1,3-diketonate was not investigated. We have, therefore, investigated this problem<sup>19-21</sup> and have reported that like the transition metal 1,3-diketonates, the lanthanide 1,3-diketonato system also behaves like a sensitive heterocycle possessing some aromatic character (Scheme 2).


On the basis of results obtained, it can be stated that the degree of delocalisation of  $\pi$ -electrons in lanthanide 1,3-diketonates is more pronounced than in the transition metal system leading to enhanced quasi-aromaticity.

The methine proton at the central carbon atom of the chelate ring has been subjected to nitration, chlorination and bromination. Substitution in the phenyl ring is unlikely because of ring deactivation from electron release resonance effects. The disappearance of the C-H in-plane bending vibration band from the region  $1225\text{--}1180\text{ cm}^{-1}$  in the ir spectra and the disappearance of the methine resonance signal from the region  $\delta 6.2\text{ ppm}$  in the pmr spectra provide strong evidence for electrophilic substitution at the central carbon atom.



Ar = 4- $\text{FC}_6\text{H}_4$  or a derivative, X = Cl, Br, or  $\text{NO}_2$ , R = Me, Et,  $\text{Pr}^n$ ,  $\text{CF}_3$  or Ph.

Scheme 1



Ar = Fluoroaryl group ; R =  $\text{CH}_3$ ,  $\text{C}_2\text{H}_5$ ,  $\text{CF}_3$ ,  $\text{C}_2\text{F}_5$  or  $\text{nC}_3\text{F}_7$  ; X = Cl, Br.

Scheme 2

### Laser chelates :

Since Urbain's work<sup>22</sup> on the rare earth 1,3-diketonates, the chemistry of such compounds has assumed considerable importance because of their practical use as potential laser materials. The first laser action from europium benzoylacetonate at 6130 Å was reported by Lempicki and Samelson<sup>23</sup> and Schimitschek<sup>24</sup>. Bhaumik *et al.*<sup>25</sup> have shown that laser activity is possible only with tetrakis chelates of rare earth and not with tris chelates. One of the more successful ligands, so far investigated is benzoyltrifluoroacetone. Its tetrakis derivative,  $\text{Eu}(\text{BTFA})_4\text{Q}$ , where Q is a cation (Fig. 3), has been shown to lase in acetonitrile solution from 77K to an unusually high temperature (i.e. room temperature). We have studied<sup>26,27</sup> new tetrakis rare earth chelate salts of the type piperidinium<sup>+</sup>  $[(\text{ArCOCHCOR})_4\text{M}]^-$  (where Ar = fluorophenyl or substituted fluorophenyl, R = alkyl, aryl or perfluoromethyl and M =  $\text{La}^{3+}$ ,  $\text{Pr}^{3+}$ ,  $\text{Nd}^{3+}$  and  $\text{Eu}^{3+}$ ). Some of these complexes have been examined for their fluorescence in the solid state at 77K. The  $^5\text{D}_0 \rightarrow ^7\text{F}_5$  (at 6173 Å) is by far the most intense transition in case of europium chelates accounting for approximately 95% of the total emission in all europium chelates. It may be noted that this is the first case of piperidinium tetrakis-europium-1,3-diketonates in which the  $^5\text{D}_5$  level has been observed to fluoresce.




Fig. 3. Ar = Fluoroaryl group ;  
R = Alkyl, aryl or perfluoroalkyl group .  
M =  $\text{Eu}^{3+}$ ,  $\text{Sm}^{3+}$ ,  $\text{Tb}^{3+}$ ,  $\text{Gd}^{3+}$ ,  $\text{La}^{3+}$ ,  $\text{Pr}^{3+}$  or  $\text{Nd}^{3+}$   
Q = Piperidine.

The terbium complex showed fluorescence at 5800 Å (overlapped with the transition of  $\text{Eu}^{3+}$ ) and 5440 Å, involving  $^5\text{D}_4 \rightarrow ^7\text{F}_4$  and  $^5\text{D}_4 \rightarrow ^7\text{F}_5$  transitions, respectively. In the samarium complex, fluorescence was observed at 5640 Å due to  $^6\text{F}_{9/2} \rightarrow ^6\text{H}_{7/2}$  and at 5980 Å due to  $^6\text{G}_{7/2} \rightarrow ^6\text{H}_{9/2}$ . The line emission in the samarium chelate is very faint but distinct from europium line emission. The uv absorption spectra<sup>27</sup> reveal two maxima. The first maximum is in the region of 3250-3570 Å and is a bathochromic shift of the 1,3-diketone anion absorption due to coordinated chelate ion formation. This clearly indicates that all four 1,3-diketone molecules are used in chelate formation with the metal ion. The second maximum in the region of 2440-2600 Å may be due to free 1,3-diketone anion whose formation in solution is ascribed to ionisation of the original tetrakis chelates as follows :



where L = ligand, M = rare earth metal,  $\text{HP}^+$  = piperidinium ion.

### NMR shift reagents :

In 1969, Hinckley<sup>28</sup> discovered that the addition of bis pyridine adduct of tris dipivalomethanato europium,  $\text{Eu}(\text{dpm})_3 \cdot 2\text{Py}$  to a carbon tetrachloride solution of cholesterol caused important selective downfield shifts in nmr spectrum of steroid and for obvious reasons, the europium complex was named as "shift reagent". The discovery at once suggested that it could lead to simplification of spectra by removal of signal coincidence and also characterization of nucleus in terms of its geometrical relationship with respect to one or more distant functional groups.

The paramagnetic tris-lanthanide(III) chelates of  $\text{H}(\text{fod})\text{Ln}(\text{fod})_3$  have been increasingly used as nmr shift reagents since the first report. The chemical property which permits this application is the Lewis acidity possessed by the chelates as a consequence of their coordinative unsaturation. The neutral tris-chelates dissolve in organic solvents and form labile adducts with a large variety of nucleophilic substrates. Lewis acidity of these chelates also causes two side interactions which may interfere with their usage as nmr shift reagents.

$\text{Eu}(\text{III})$  chelates of fluorinated 1,3-diketones e.g.,  $\text{H}(\text{fod})$  and  $\text{H}(\text{tfacam})$  undergo<sup>29</sup> much stronger interactions with nucleophiles (ethers, ketones, alcohols, esters and olefins) than similar non-fluorinated  $\text{Eu}(\text{III})$  chelates. This is most probably due to the increased acidity of the fluorinated chelates due to a decrease in the basicity of the fluorinated 1,3-diketones, and to increased solubility.  $\text{Eu}(\text{fod})_3$  is probably the best overall shift reagent for spectral clarification presently available.

Very recently (1974), a novel and efficient nmr shift reagent, tetrakis(1,1,1-trifluoro-4-phenylbutane-2,4-dionato) uranium,  $\text{U}(\text{btfa})_4$ , has been prepared<sup>30</sup>. It is capable of forming adducts with Lewis bases (e.g. Py and *n*-BuOH) and inducing proton shifts of a magnitude similar to those obtained with  $\text{Eu}(\text{dpm})_3$ .

We have also recently synthesised some new polyfluorinated lanthanide 1,3-diketonates<sup>30</sup> and have studied their ability to produce shifts<sup>31</sup> in *n*-hexanol, *n*-heptanol, *n*-dodecanol, *p*-fluoroaniline and *m*-trifluoromethyl aniline. The following compounds have been examined :

1. [4,4,5,5,5-Pentafluoro-1-( fluorophenyl ) 1,3-pentanedionato]holmium(III).
2. [4,4,5,5,6,6,6-Heptafluoro-1-(4'-fluorophenyl) 1,3-hexanedionato]europium(III).
3. [4,4,5,5,6,6,6-Heptafluoro-1-(4'-fluorophenyl) 1,3-hexanedionato]praseodymium(III).
4. [4,4,5,5,5-pentafluoro-1-(4'-fluorophenyl) 1,3-pentanedionato]praseodymium(III).

It was observed that europium and praseodymium 1,3-diketonates act as the best shift reagents for downfield and upfield shifts, respectively as they do not produce line broadening. Holmium 1,3-diketonates produce maximum shifts with certain nucleophiles but they are not used as shift reagents due to line broadening.

*As reaction intermediates for synthesis of bioactive heterocycles :*

Apart from the various analytical applications of the 1,3-diketones listed above, we have recently employed these compounds for synthesis of different types of bioactive heterocycles containing fluorinated groups. These heterocycles include pyrazoles, isoxazoles, pyrazolo[1,5-a]pyrimidines, 1,2,4-triazolo[4,3-b]pyridazines, 1H-pyrazolo[3,4-b]pyridines, 1,4-diazepines, 1,5-benzodiazepines, pyrazolo[5,1-c][1,2,4]triazines etc. Some of these compounds have shown promising CNS depressant, antiobesity and anticholinergic activities<sup>21</sup>.

#### Acknowledgement

The author thanks Dr. Vijai N. Pathak, Dr. (Mrs.) Sushma Bhargava and Dr. (Miss) Vineeta Grover for experimental results.

#### References

1. R. E. SIEVERS, K. J. EISENTRAUT, D. J. GRIEST, M. F. RICHARDSON, W. R. WOLF, N. M. FREW and T. L. ISENHOUR, "Second Lunar Science Conference", 1971, 2, 1451.
2. W. D. ROSS, W. G. SCRIBNER and R. E. SIEVERS, "Eighth International Symposium on Gas Chromatography", 1970, 369.
3. P. MUSHAK, M. T. GLENN and J. SAVORY, *Fluorine Chem Rev*, 1973, 6, 116, 1973, 6, 43.
4. K. C. JOSHI and V. N. PATHAK, *Indian J Chem*, 1972, 10, 485.
5. K. C. JOSHI, V. N. PATHAK and (Miss) S. BHARGAVA, *J Inorg Nuclear Chem*, 1977, 39, 803.
6. K. C. JOSHI, V. N. PATHAK and (Miss) V. GROVER, *J Fluorine Chem.*, 1980, 15, 245.
7. K. C. JOSHI, V. N. PATHAK and (Miss) V. GROVER, *J Fluorine Chem.*, 1981, 17, 555.
8. J. D. PARK, H. A. BROWN and J. R. LACHER, *J. Amer Chem. Soc.*, 1953, 75, 4753.
9. A. LEMPICKI and H. SAMELSON, *Phys. Lett.*, 1963, 4, 133.
10. C. C. HINCKLEY, *J. Amer. Chem. Soc.*, 1969, 91, 5160.
11. R. A. JAMES and W. P. BRYAN, *J. Amer. Chem. Soc.*, 1954, 76, 1982.
12. J. P. FACKLER, JR., *Progr. Inorg. Chem.*, 1966, 7, 361.
13. J. J. FORTMAN and R. E. SIEVERS, *Coord. Chem. Rev.*, 1971, 6, 331.
14. R. C. MEHROTRA, D. P. GAUR and R. BHORA, "Metal  $\beta$ -Diketonates and Allied Compounds", Academic Press, New York, 1978.
15. K. C. JOSHI and V. N. PATHAK, *Coord Chem Rev*, 1977, 22, 37 and references therein.
16. J. P. COLLMAN, R. L. MARSHALL and W. L. YOUNG (III) *Chem. Ind.*, 1962, 1380.
17. D. M. G. LLOYD and D. R. MARSHALL, *Chem. Ind.*, 1964, 1966.
18. K. C. JOSHI and V. N. PATHAK, *J Chem. Soc. Perkin I*, 1973, 57.
19. K. C. JOSHI, V. N. PATHAK and (Miss) V. GROVER, "Abstracts, IX International Symposium on Fluorine Chemistry", Avignon, France, 1979, p. 137.
20. K. C. JOSHI, V. N. PATHAK and (Miss) V. GROVER, *J Fluorine Chem.*, 1980, 15, 527.
21. K. C. JOSHI, V. N. PATHAK and (Miss) V. GROVER, *J. Nep. Chem. Soc.*, 1981, 1, 75.
22. G. URBAIN, *Bull. Soc chim Fr*, 1896, 15, 397.
23. H. SAMELSON and A. LEMPICKI, (a) *J. Chem. Phys.*, 1963, 39, 110. (b) *Phy. Lett*, 1963, 4, 133.
24. E. J. SCHMITZHECK, *Appl. Phys. Lett*, 1963, 3, 117.
25. M. L. BHAUMIK, P. C. FLETCHER, L. J. NUGENI, S. M. LEE, S. HIGH, C. I. TELK and M. WEINBERG, *J Phys. Chem*, 1964, 68, 1490.
26. K. C. JOSHI and V. N. PATHAK, *J. Inorg. Nuclear Chem*, 1973, 35, 3161.
27. K. C. JOSHI, V. N. PATHAK, (Miss) S. BHARGAVA and P. G. SEYBOLD, *J Fluorine Chem*, 1977, 9, 387.
28. R. E. SIEVERS, "NMR Shift Reagent", Academic Press, New York, 1973.
29. G. FOLCHER, J. PARU, P. PLURIEN, P. PIGNIFY and E. SOULIE, *J. Chem Soc, Chem Commun.*, 1974, 3.
30. K. C. JOSHI, V. N. PATHAK and (Miss) V. GROVER, *J. Fluorine Chem.*, 1979, 13, 261.
31. K. C. JOSHI, "Proceedings of the 1st ASPAC Congress", Singapore, 1981, p. 242.



# Restricted Rotation. Part—IV : Determination of Barrier to Rotation Around Some Crowded C-C and C-N Bonds by Dynamic Nuclear Magnetic Resonance

D. NASIPURI\*, N. P. DAW, S. BANERJEE and MITA DATTA GUPTA

Department of Chemistry, Indian Institute of Technology, Kharagpur-721 302

Temperature dependence of the nmr spectra of a few typical methyl 2-aryl-6-oxocyclohex-1-enyl-acetates (I)-(VII) has been reinvestigated. The free energy, enthalpy and entropy of activation for the restricted rotation about the arylcyclohexenone bond have been determined by line shape analysis of the spectra of the side chain methylene protons using approximate equations. The free energy of activation for conformational inversion of the molecule (VII) is now found to be appreciably higher than that reported earlier although the result is still to be rationalised. The barrier energy around C-N bond in two 1-aryl-1,4-dihydro-4,4,6-trimethyl-2-thiopyrimidones (XIII) and (XV) has also been measured by dynamic nmr taking advantage of chemical nonequivalence of the geminal methyl groups and is found to be quite high ( $\approx 98 \text{ kJ mol}^{-1}$ ).


SINCE its discovery, the high resolution nmr spectroscopy has become one of the most valuable tools of the chemists, biochemists and physicists for the determination of structures of molecules. In addition to the static aspects of the molecules (e. g., chemical shifts, coupling constants), nmr is capable of giving valuable information on many time-dependent phenomena which include a large number of exchange reactions characterised by certain rate constants<sup>1</sup>. Rotation about a single bond may be visualised as an intramolecular stereodynamic process in which the rate constant depends on the barrier energy. Previously, molecules like biphenyls with restricted rotation around the pivotal bond had to be resolved into enantiomers in order to study the barrier energy and polarimetry was the sole method of investigation. Nowadays, it is possible to study the hindered rotation by means of dynamic nmr when the energy barrier is just on the border line ( $75\text{--}96 \text{ kJ mol}^{-1}$ ), where compounds become too unstable to be isolated chemically, down to a barrier of  $21\text{--}25 \text{ kJ mol}^{-1}$  below which another powerful tool, namely, microwave spectroscopy can be applied. Moreover, unlike polarimetry, it is not necessary that the two conformers should be enantiomeric and possess a chiral centre or axis. In principle<sup>2</sup>, if a molecule by reason of restricted rotation happens to lack certain symmetry properties so that two conveniently placed groups (generally H or Me) become diastereotopic, the technique of dynamic nmr may be used to determine activation energies of the rotational process. A large number of biphenyl derivatives and their analogues have been studied using this method by various groups of workers<sup>3</sup>. In our laboratory, a dozen of 3-aryl-cyclohexenones of the type (I) have been synthesised

and the free energies of activation of restricted rotation about the arylcyclohexenone bond determined<sup>4-6</sup> from the coalescence temperature of the AB-quartet of the diastereotopic protons in the acetate side chain. In the absence of full line shape analysis<sup>1</sup>, the measurements were, however, confined to the calculation of free energies of activation ( $\Delta G^\ddagger$ ) for conformational inversion at the coalescence temperature ( $T_c$ ). The significance of the values was limited by the fact that their temperature dependence was not known. In the present communication, a few typical molecules (I)-(VII) have been re-examined by line shape analysis using approximate equations, the enthalpy and entropy of activation have been calculated and compared, and the temperature dependence of free energies of activation has been studied. The compound (VII) which behaved atypically<sup>6</sup> has been synthesised eliminating any controversy over its structure. In addition, the barrier to rotation about C-N bond in some 1-aryl-1,4-dihydro-4,4,6-trimethyl-2-thiopyrimidones<sup>7</sup> has been determined by dynamic nmr.

## Experimental

<sup>1</sup>H NMR spectra at different temperatures were taken on a Varian EM390 90 MHz machine. Temperature control was provided by a Varian variable temperature controller with an accuracy of  $\pm 2^\circ$ . Temperatures above  $50^\circ$  were calibrated using the shift difference of an ethylene glycol sample. Chemical shifts are reported in ppm relative to TMS as internal standard. IR spectra were taken in  $\text{CHCl}_3$  solution on Perkin-Elmer 237B spectrometer. Petroleum refers to a fraction, b.p.  $40\text{--}60^\circ$ . Organic solutions were dried over anhydrous  $\text{Na}_2\text{SO}_4$ . All


\*Author for correspondences.




I : R = OMe, R' = H

II : R = Me, R' = H


III : R = R' = Me




IV




V




VI




VII




VIII




IX




X



XI



XII



XIII : R = OMe

XIV : R = Me

XV : R = NO<sub>2</sub>

the melting points are corrected. TLC was done on silica-gel plates using ethyl acetate and petroleum as eluents.

Methyl 2-aryl-6-oxocyclohex-1-enylacetates (I)-(VI) were prepared by method described earlier<sup>4,5</sup>. The synthesis of compound (VII) has been carried

out with some modification as described below and the intermediates are carefully checked by tlc, glc and <sup>1</sup>H nmr for their purity.

1-Acetyl-2-methoxynaphthalene (VIII) : 1-Acetyl-2-methoxynaphthalene was prepared according to the previous method<sup>4</sup> and was rigorously purified by

column chromatography (silica gel). It crystallised from petroleum in colourless plates, m.p. 58°; <sup>1</sup>H nmr spectrum (CDCl<sub>3</sub>): δ 8.00-7.80 (3H, m, 3×ArH), 7.60-7.20 (3H, m, 3×ArH), 3.95 (3H, s, OCH<sub>3</sub>) and 2.63 (3H, s, COCH<sub>3</sub>); ν<sub>max</sub>: 1695 and 1600 cm<sup>-1</sup>. The <sup>1</sup>H nmr spectrum (CDCl<sub>3</sub>) of 1-acetyl-2-naphthol<sup>8</sup> is as follows: δ 13.55 (1H, s, exchangeable with D<sub>2</sub>O, -OH), 8.17 (1H, d, J=8 Hz, 8-H), 8.07-7.30 (4H, m, 4×ArH), 7.20 (1H, d, J=8 Hz, 3-H) and 2.87 (3H, s, COCH<sub>3</sub>); ν<sub>max</sub>: 1630 and 1580 cm<sup>-1</sup>. Each of these compounds gave a single spot and a single peak in tlc and glc (FAAP 15% column), respectively.

**Attempted preparation of 2-methoxy-1-naphthyl vinyl ketone (IX) with trifluoroacetic acid N-methylaniline salt (TAMA):** Recently, a new procedure has been developed<sup>9</sup> to synthesise α-methylene ketones using 'TAMA' and trioxymethylene. Accordingly, a mixture of 'TAMA' (2.25 g), 1-acetyl-2-methoxynaphthalene (2.00 g) and trioxymethylene (1.08 g) in dry freshly distilled dioxane (12 ml) was refluxed under N<sub>2</sub> for 2 hr followed by heating with fresh amount of trioxymethylene (0.51 g), 'TAMA' (1.2 g) and dioxane (6 ml) for 2 hr more. The ketone (VIII) was, however, recovered completely unchanged. Apparently, the method does not work with sterically hindered ketones<sup>9</sup>.

**Methyl 7-(2-methoxy-1-naphthoyl)-4-oxoheptanoate (XI):** This compound was prepared by condensing the Mannich base of 1-acetyl-2-methoxynaphthalene methiodide with ethyl β-oxo-adipate<sup>10</sup> as described in a previous paper<sup>4</sup>. 2-Methoxy-1-naphthyl β-NN-dimethylaminoethyl ketone (X), prepared in the usual way had the <sup>1</sup>H nmr spectrum (CDCl<sub>3</sub>): δ 8.05-7.70 (3H, m, 3×ArH), 7.60-7.20 (3H, m, 3×ArH), 3.97 (3H, s, OCH<sub>3</sub>), 3.13 (2H, m, COCH<sub>2</sub>), 2.83 (2H, m, CH<sub>2</sub>NMe<sub>2</sub>) and 2.27 (6H, s, NMe<sub>2</sub>); ν<sub>max</sub>: 1695 and 1610 cm<sup>-1</sup>. The dioxo-ester (XI) showed <sup>1</sup>H nmr (CDCl<sub>3</sub>): δ 8.00-7.55 (3H, m, 3×ArH), 7.50-7.20 (3H, m, 3×ArH), 3.92 (3H, s, OCH<sub>3</sub>), 3.63 (3H, s, CO<sub>2</sub>CH<sub>3</sub>), 2.92 (2H, t, J=7 Hz, 3-CH<sub>2</sub>), 2.60 (6H, m, 3×CH<sub>2</sub>CO)

and 2.06 (2H, m, 6-H<sub>2</sub>); ν<sub>max</sub>: 1735 (CO<sub>2</sub>Me), 1719 (satd. C=O), 1695 (ArCO) and 1610 cm<sup>-1</sup> (aromatic). The dioxo-ester (XI) was a viscous gum, b.p. 220-225°/0.1 mm. Found: C, 70.3; H, 6.6. C<sub>20</sub>H<sub>18</sub>O<sub>8</sub> requires C, 70.2; H, 6.4%.

**Methyl 2-(2-methoxy-1-naphthyl)-6-oxocyclohex-1-enylacetate (VII):** The above dioxo-ester (1.4 g; 4.1 mmol) was added to a solution of dry potassium t-amylate, prepared from potassium (0.16 g; 4.1 mmol), in benzene (30 ml). The solution was refluxed on a water-bath for 5 hr under N<sub>2</sub>. Some salt precipitated out. The cooled mixture was decomposed with dilute acid and the organic matter was extracted with ether. The ethereal layer was washed repeatedly with aqueous NaHCO<sub>3</sub> solution when 2-(2-methoxy-1-naphthyl)-6-oxocyclohex-1-enylacetic acid (hydrolysed from the cyclised ester by the liberated water during aldol condensation) came up completely into the alkaline layer. On acidification, a gum (0.85 g) was obtained which was esterified with diazomethane and the ester sublimed at 200°/0.1 mm. The product was mostly methyl 2-(2-methoxy-1-naphthyl)-6-oxocyclohex-1-enylacetate (VII) admixed with a little amount (ca 20% as determined from nmr) of the methyl ether of the cyclopenta-1,3-dione derivative (XII) formed as a result of internal Claisen condensation. The product was chromatographed over silica-gel when the cyclohexenylacetate (VII) was obtained in crystalline form, m.p. 102° (from benzene petroleum). Found: C, 74.4; H, 6.7. C<sub>20</sub>H<sub>18</sub>O<sub>6</sub> requires C, 74.1; H, 6.2%; <sup>1</sup>H nmr spectrum (CDCl<sub>3</sub>): δ 8.00-7.31 (7H, m, ArH), 3.90 (3H, s, OCH<sub>3</sub>), 3.42 (3H, s, CO<sub>2</sub>CH<sub>3</sub>), 3.00 (2H, AB-q, CH<sub>2</sub>CO<sub>2</sub>Me), 2.65 (4H, m, 3-H<sub>2</sub>+5-H<sub>2</sub>) and 2.26 (2H, m, 4-H<sub>2</sub>). In C<sub>6</sub>D<sub>6</sub>NO<sub>2</sub>, the side chain quartet at δ 3.00 appeared as a singlet but in CDCl<sub>3</sub> (up to 60°) and in Cl<sub>2</sub>C=CCl<sub>2</sub>, the quartet was retained.

The ester formed a red dinitrophenylhydrazone, m.p. 216° (reported<sup>4</sup> m.p. 216-217°). Found: C, 62.1; H, 5.1; N, 11.0. C<sub>22</sub>H<sub>16</sub>N<sub>2</sub>O<sub>7</sub> requires C, 61.9; H, 4.8; N, 11.1%; <sup>1</sup>H nmr spectrum

TABLE 1—NMR PARAMETERS<sup>a</sup> AND ENERGIES<sup>b</sup> OF ACTIVATION OF ROTATION ABOUT THE ARYL-CYCLOHEXENONE BOND IN COMPOUNDS (I)-(VII)

Compound	Solvent	J <sub>AB</sub> Hz	Δν <sub>AB</sub> Hz	T <sub>0</sub> °C	k <sub>0</sub>	ΔG <sub>0</sub> <sup>†</sup>	ΔG <sub>0</sub> <sup>‡</sup>	k <sub>100</sub> <sup>0</sup>	ΔG <sub>100</sub> <sup>0</sup>	k <sub>180</sub> <sup>0</sup>	ΔG <sub>180</sub> <sup>‡</sup>	ΔH <sup>‡</sup>	ΔS <sup>‡</sup> e.u.
I	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	15.00	16.10	43	89.15	66.05	67.80	630	71.90	—	—	50.24	-11
	o-C <sub>6</sub> H <sub>4</sub> Cl <sub>2</sub>	24.00	25.88	50	142.60	64.08	—	620	72.00	—	—	46.00	-13
II	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	16.50	17.43	145	97.80	87.45	88.41	—	—	700	87.60	95.14	+4
III	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	16.50	17.43	145	97.80	87.50	88.60	—	—	710	87.66	96.39	+5
IV	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	17.00	20.98	62	110.40	69.10	69.80	640	71.80	—	—	52.67	-12
V	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	16.50	19.45	184	99.70	95.85	95.30	—	—	—	—	—	—
VI	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	17.00	40.60	95	129.20	75.49	75.80	380	76.20	—	—	65.25	-6
VII	Cl <sub>2</sub> C=CCl <sub>2</sub>	17.00	10.50	80	95.50	73.15	66.00	160	74.17	—	—	51.50	-11

<sup>a</sup>The spectral changes are reversible with temperature. <sup>b</sup>Energy is expressed in kJ mol<sup>-1</sup>; the maximum errors are estimated for ΔG<sup>‡</sup> to be ±1.0 kJ mol<sup>-1</sup>; for ΔH<sup>‡</sup> to be ±4 kJ mol<sup>-1</sup>, and for ΔS<sup>‡</sup> ±4 e.u. mol<sup>-1</sup>. <sup>c</sup>Data taken from ref. 5, 6.

(CDCl<sub>3</sub>) :  $\delta$  11.2 (1H, s, ArNH), 9.23 (1H, d,  $J=3$  Hz, 3'-ArH), 1.60 (1H, 2 $\times$ d,  $J=9$  and 3 Hz, 8-ArH), 8.10-7.30 (7H, m, ArH), 3.94 (3H, s, OCH<sub>3</sub>), 3.50 (3H, s, CO<sub>2</sub>CH<sub>3</sub>), 3.17 (2H, AB-q,  $J=17$  Hz,  $\Delta\nu=10$  Hz, CH<sub>2</sub>CO<sub>2</sub>Me), 2.80 (2H, t,  $J=7$  Hz, 5-H<sub>2</sub>), 2.60 (2H, t,  $J=7$  Hz, 3-H<sub>2</sub>) and 2.24 (2H, m, 4-H<sub>2</sub>).

*1-Aryl-1,4-dihydro-4,4,6-trimethyl-2-thiopyrimidones* (XIII)-(XV): These thiones were prepared by a one step procedure from the corresponding aromatic amines, 4-methylpent-3-en-2-one (mesityl oxide), ammonium thiocyanate, water and hydrochloric acid as reported<sup>11,12</sup>. These compounds have been characterised by us (ir, nmr) elsewhere<sup>7</sup>.

## Results and Discussion

The nmr spectra of the seven arylcyclohexenones (I)-(VII) showed an AB-quartet (first three lines were clearly discernible in all the spectra) for the diastereotopic methylene protons of the acetate side chain. The  $J_{AB}$  and  $\Delta\nu$  values were calculated from the positions of the first and second, and first and third lines respectively according to standard procedure<sup>8</sup>. At coalescence temperature ( $T_c$ ), each quartet coalesced to a broad singlet which gradually sharpened with increased temperature. The approximate exchange rate,  $k_a$ , and the free energy barrier to configurational inversion,  $\Delta G_a^\ddagger$ , at  $T_c$  were calculated by using equations (1) and (2), respectively<sup>13</sup>. At several temperatures above  $T_c$ , the line widths of the coalesced singlet at its half height (W/Hz) were measured and the approximate inversion rates were obtained over a range of temperatures by equation (3)<sup>14,15</sup> where  $W_0$  is the half width of the singlet at the highest temperature attainable. When  $k$  was plotted against  $1/T$  ( $T$  in absolute scale), an approximate linear relationship

$$k_a = \pi[(\Delta\nu_a)^2 + 6 J_{AB}^2]^{1/2} \quad (1)$$

$$\Delta G_a^\ddagger = 4.57 \times T_c (10.32 - \log \frac{T_c}{k_a}) \quad (2)$$

$$k = \frac{\pi \Delta\nu_{AB}^2}{2(W - W_0)} \quad \dots (3)$$

$$\Delta H^\ddagger = E_a - RT \quad \dots (4)$$

$$\Delta S^\ddagger = \frac{\Delta H^\ddagger - \Delta G^\ddagger}{T} \quad \dots (5)$$

was observed which permitted the determination of the values of  $\Delta G^\ddagger$  at different temperatures with some degree of accuracy. Arrhenius parameter,  $E_a$ , was measured from the slope of the straight line when  $\log k$  was plotted against  $1/T$  and from  $E_a$ ,  $\Delta H^\ddagger$  and  $\Delta S^\ddagger$  were calculated using equations (4) and (5). The results are summarised in Table 1.

TABLE 2—NMR PARAMETERS<sup>a</sup> AND FREE ENERGIES OF ACTIVATION OF ROTATION ABOUT C-N IN COMPOUNDS (XIII) AND (XV)

Compound	Solvent	$\Delta\nu$ Hz	$T_c$ °C	$k_a$	$\Delta G_a^\ddagger$ kJ mol <sup>-1</sup>
XIII	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	1.5	140	3.33	97.90 $\pm$ 0.2
	<i>o</i> -C <sub>6</sub> H <sub>4</sub> Cl <sub>2</sub>	2.4	150	5.33	98.73 $\pm$ 0.2
XV	C <sub>6</sub> D <sub>6</sub> NO <sub>2</sub>	3.0	160	6.67	100.24 $\pm$ 0.2

<sup>a</sup>The spectral changes are reversible with temperature

It may, however, be noted that the enthalpy and entropy of activation derived from nmr line shape analysis using approximate equations are subject to large systematic errors<sup>16</sup>. Consequently, the significance of the values of  $\Delta H^\ddagger$ ,  $\Delta S^\ddagger$  and the observed temperature dependence of  $\Delta G^\ddagger$  are very much doubtful and no serious conclusion should be drawn therefrom. The following points are observed from the results presented in Table 1 which also contains data of our previous work<sup>8</sup> for comparison.

i) The coalescence temperature,  $T_c$ , and free energy of activation,  $\Delta G_a^\ddagger$ , of the 2-methoxy-1-naphthyl derivative (VII) have now considerably increased. The former is found to be 80° instead of 45° and the latter 73.15 instead of 66.00 kJ mol<sup>-1</sup>, determined in tetrachloroethylene. The AB-quartet remained intact in chloroform solution upto 60° which shows that the previous measurement (done in a foreign laboratory) was wrong. The  $\Delta G_a^\ddagger$  value (73.15 kJ mol<sup>-1</sup>) is still very much less than that (95.30 kJ mol<sup>-1</sup>) for the 1-naphthyl-derivative (V). We reiterate our previous explanation<sup>8</sup> that the ground state energy of the molecule (VII) is appreciably increased by the *o*-methoxy substituent while that of the transition state may have been reduced by a combined effect of conjugation and out-of-plane bending of the pivotal bond both assisted by methoxyl group<sup>17,18</sup>. It must be understood that unlike the biphenyl derivatives, where both the rings are planar, the cyclohexenone moiety in VII is nonplanar and may have different conformations in the ground and the transition states leading to different steric interactions. The  $\Delta G_a^\ddagger$  values of the rest of the compounds agreed with those previously reported<sup>8</sup>.

ii) Although the measurement of  $\Delta H^\ddagger$  and  $\Delta S^\ddagger$  values are very much unreliable for reasons stated earlier, there is an unmistakable trend towards high negative entropy of activation (-11 e.u.) and low  $\Delta H^\ddagger$  values for compounds (I), (IV) and (VII) which contain an *ortho*-methoxyl group. On the other hand, the three compounds (II), (III) and (V) having no methoxyl substituent show very small (almost negligible) positive entropy of activation and their  $\Delta H^\ddagger$  values are comparable with those of  $\Delta G^\ddagger$ . It is risky to draw any firm conclusion based on this very uncertain ground; we can only conjecture that the rotation of the methoxyl group *ortho* to the pivotal bond is much more restricted (and therefore more orderly) in the transition state than in the ground

state, which explains this negative entropy of activation. Alternatively, one can argue that for compounds having relatively low coalescence temperatures, the systematic error for the determination of the enthalpy and entropy of activation is much greater than for compounds having high coalescence temperatures. This is, however, not borne out from the experiments of Oki *et al.*<sup>14</sup> on 5,7-dihydrobenzo-[c,e] thiopins having low coalescence temperatures.

iii) The temperature dependence of  $\Delta G^\ddagger$  also presents some inconsistency between the two series of compounds. Thus while for the non-methoxylated compounds (II), (III) and (VI), the  $\Delta G^\ddagger$  values at  $T_0$ , 100° and 180° are fairly constant, for the methoxylated compounds (I), (IV) and (VII), the  $\Delta G^\ddagger$  values vary appreciably with temperature. This is, of course, expected from the difference in the entropy of activation in the two series. Comparison of the  $\Delta G^\ddagger$  values at coalescence temperatures, therefore, may not be a true index of the relative restricted rotation in this series. The values are to be taken qualitatively rather than quantitatively.

Three 1-aryl-1,4-dihydro-4,4,6-trimethyl-2-thiopyrimidones (XIII)-(XV) were studied by dynamic nmr technique. The two rings connected by a C-N bond are dissymmetrically substituted and so if the rotation about this bond is sufficiently restricted by *ortho*-substitution in the phenyl ring, the two geminal methyl groups at C-4 might be chemically nonequivalent and would appear as a doublet. This happens to be the case for compounds (XIII) and (XV), the two 4-methyl groups giving two signals around  $\delta$  1.40 with small  $\Delta\nu$  values (1.5-3.0 Hz) depending to some extent on the solvents used (see Table 2). In these two cases, the inversion rate,  $k_0$ , at  $T_0$  was determined by equation (6)<sup>18</sup> and then the free energy of activation was obtained by substituting the value of  $k_0$  in equation (2). The  $\Delta G^\ddagger$  values range between 97.90 and 100.24 kJ mol<sup>-1</sup> which are little higher than the energy barriers to rotation about C-N bond in 1-arylhydantoin<sup>20</sup> and N-arylsuccinimides<sup>21</sup> in which six-membered thiopyrimidone ring is replaced by similarly constituted five-membered one.

$$k_0 = \frac{\pi \Delta\nu}{\sqrt{2}} \quad \dots (6)$$

The almost equal values of  $\Delta G^\ddagger$  for the compounds (XIII) and (XV), in spite of the fact that nitro group is much bulkier than methoxyl, is certainly due to resonance stabilisation of the transition state in the latter. Since the chemical shift difference is very small, the line shape analysis by taking the spectra at different temperatures would not have helped much. In the case of *o*-methyl compound (XIV) and of a few more similar com-

pounds<sup>7</sup>, the differential aromatic ring anisotropy is not strong enough to cause any chemical shift difference in the geminal methyl groups situated at the other end of the molecule.

#### Acknowledgement

One of the authors (S. B.) is thankful to the Council of Scientific and Industrial Research, New Delhi for a Fellowship.

#### References

1. G. BINSCH, "Topics in Stereochemistry", (Eds.) F. L. ELLIOT and N. L. ALLINGER, Interscience, New York, 1968, Vol. 3, p. 97.
2. For a review, see W. B. JENNINGS, *Chem. Rev.*, 1975, 75, 307.
3. R. J. KURLAND, M. B. RUBIN and W. B. WISE, *J. Chem. Phys.*, 1964, 40, 2426; W. L. MEYER and R. B. MEYER, *J. Amer. Chem. Soc.*, 1963, 85, 2170; M. OKI, H. IWAMURA and N. HAYAKAWA, *Bull. Chem. Soc. Japan*, 1964, 37, 1865; I. O. SUTHERLAND and M. V. J. RAMSAY, *Tetrahedron*, 1965, 21, 3401; M. OKI and H. IWAMURA, *Tetrahedron*, 1967, 24, 2377; for a review, see, S. STERNIPLI, "Dynamic Nuclear Magnetic Resonance Spectroscopy", (Eds.) L. M. JACKMAN and F. A. COTTON, Academic Press, New York, 1975, p. 163.
4. D. NASIPURI and P. R. MUKHERJEE, *J. Chem. Soc. Perkin Trans. II*, 1975, 464.
5. D. NASIPURI, P. K. BHATTACHARYA and G. T. FURST, *J. Chem. Soc. Perkin Trans. II*, 1977, 356.
6. D. NASIPURI and S. K. KONAR, *J. Chem. Soc. Perkin Trans. II*, 1979, 269.
7. D. NASIPURI, S. BANERJEE, B. V. ALAKA and N. P. DAW, *Synthesis*, 1982, 1073.
8. K. FRITS, *Ber.*, 1921, 54B, 709.
9. JIAN-LOUIS GRAS, *Tetrahedron Lett.*, 1979, 2111, 2955.
10. C. M. GUHA and D. NASIPURI, *Org. Synth. Coll. Vol.*, 5, 384.
11. R. A. MATHIS, F. D. STEWART and F. SWEDISH, *J. Amer. Chem. Soc.* 1948, 70, 1452.
12. R. A. MATHIS, *J. Amer. Chem. Soc.*, 1951, 75, 1747.
13. J. A. POPE, W. G. SCHNIEDER and H. I. BENNISTEIN, "High Resolution Nuclear Magnetic Resonance", McGraw-Hill, New York, 1959, see also ref. 3.
14. M. OKI, H. IWAMURA and G. YAMAMOTO, *Bull. Chem. Soc. Japan*, 1971, 44, 262.
15. M. OKI and G. YAMAMOTO, *Bull. Chem. Soc. Japan*, 1971, 44, 266.
16. A. ALLERHAND, H. S. GUTOWSKY, J. JONES and R. A. MINTZER, *J. Amer. Chem. Soc.*, 1966, 88, 3185.
17. M. M. HARRIS and C. CHEUNG KING LING, *J. Chem. Soc.*, 1964, 1825.
18. R. D. CROSS, V. A. FASSEL and M. MARGOSHES, *J. Amer. Chem. Soc.*, 1956, 78, 1332.
19. H. S. GUTOWSKY and C. H. HOIM, *J. Chem. Phys.*, 1956, 25, 1228.
20. I. D. COLFERROOK, H. G. GILLS, A. GRANTA and S. ICLY, *Cand. J. Chem.*, 1973, 51, 3635.
21. A. FOUCAUD, R. ROUDAUT and C. FAYAT, *Bull. Soc. chim. France*, 1972, 5, 1915.

# Polymerization of Methacrylamide Initiated by Ceric Ion-Malic Acid Redox System

G. S. MISRA\* and J. I. KHATIB

Department of Chemistry, University of Jammu, Jammu-180 001

The homogeneous polymerization of methacrylamide (M) was studied in aqueous sulphuric acid medium at  $35 \pm 0.2^\circ$  under a nitrogen atmosphere. The rate of monomer disappearance was proportional to  $[MA]^1 [Ce(IV)]^1 [M]^{1.5}$  and the rate of ceric ion disappearance was directly proportional to  $[Ce(IV)]$  but independent of  $[M]$ . The rate increased very slowly upto a certain range of malic acid (MA) concentration above which it remained constant. A very stable complex was revealed by Lineweaver-Burk plot of  $rate^{-1}$  vs  $[MA]^{-1}$ . Increasing reaction temperature increased the rate from 25 to  $45^\circ$ . The activation energy was found to be  $15.25 \text{ k cal mol}^{-1}$ . By decreasing pH of the medium the rate of polymerization decreased.

SEVERAL papers have appeared on the polymerization of acrylamide initiated by various redox systems<sup>1-3</sup>. However, the polymerization of methacrylamide has not been attended to so much. Misra *et al* have investigated the polymerization of methacrylamide initiated by persulphate-thiomalic acid<sup>4</sup> and persulphate-ascorbic acid<sup>5</sup> redox systems. Burfield and Ng<sup>6</sup> studied the polymerization of methacrylamide initiated by persulphate alone. The present investigation has been carried out with a view to throw light on the mechanism of polymerization of methacrylamide.

## Experimental

Methacrylamide (E. Merck) was purified by two recrystallizations from acetone and dried under vacuum over calcium chloride. Malic acid (Reidal), ceric ammonium sulphate (Loba Chemie) and sulphuric acid (all AR or equivalent grade) were used as such. Double distilled water was used as solvent in all the experiments. The polymerization apparatus and procedure adopted was similar to that used by Misra *et al*<sup>5</sup>. The ceric ion concentration in the reaction system was determined by cerimetry. The reaction mixture was quenched by the addition of excess of standard ferrous ammonium sulphate and the excess of Fe(II) was determined by titrating it against standard ceric solution using ferroin as indicator.

## Results and Discussion

### Rate of monomer disappearance :

**Malic acid dependence :** The initial rate and maximum conversion increased with increasing  $[MA]$  from  $11.25 \times 10^{-3}$  to  $72.00 \times 10^{-3} \text{ mol/l}$  at constant  $[M]$ ,  $[Ce(IV)]$  and  $[H_2SO_4]$ . However, below  $6.00 \times 10^{-3} \text{ mol/l}$  of  $[MA]$  the polymerization was negligibly small. At lower  $[MA]$  the production of primary radicals is very low, hence initial rate and maximum conversion are at the lowest. As  $[MA]$  increases the production of primary free

radicals by interactions with ceric ion increases and hence initial rate and maximum conversion also




Fig 1. Polymerization of methacrylamide with varying initial concentrations of malic acid at constant  $[M] = 0.044 \text{ mol/l}$ ;  $[Ce(IV)] = 0.002 \text{ mol/l}$ ,  $[H_2SO_4] = 0.125 \text{ mol/l}$ ; Temp.  $35 \pm 0.2^\circ$ .

- =  $11.25 \times 10^{-3} \text{ mol/l}$ ;
- =  $22.50 \times 10^{-3} \text{ mol/l}$ ;
- =  $36.00 \times 10^{-3} \text{ mol/l}$ ;
- =  $72.00 \times 10^{-3} \text{ mol/l}$ ;
- =  $15.75 \times 10^{-3} \text{ mol/l}$ ;
- =  $29.25 \times 10^{-3} \text{ mol/l}$ ;
- =  $54.00 \times 10^{-3} \text{ mol/l}$ .

increase (Fig. 1). The malic acid exponent was found to be unity which indicated a unimolecular termination mechanism.

**Ceric ion dependence:** The initial rate and maximum conversion increased with increasing ceric ion concentration from  $2.5 \times 10^{-4}$  to  $50 \times 10^{-4}$  mol/l at fixed [M], [MA] and  $[H_2SO_4]$ . However, above  $50 \times 10^{-4}$  mol/l concentration of ceric ion the initial rate and maximum conversion decreased. At any fixed [MA] an increase in  $[Ce(IV)]$  increases the rate of production of active free radicals from malic acid by oxidation, hence rate and maximum conversion increased. Above  $50 \times 10^{-4}$  mol/l of  $[Ce(IV)]$  the initial rate decreased showing that at higher  $[Ce(IV)]$  the metal ion may get involved in termination reaction as well. The ceric ion exponent of unity confirmed the unimolecular termination mechanism. Several workers have reported the unimolecular termination mechanism<sup>3,7,8</sup>. Dainton proposed that the unimolecular termination mechanism of growing chains in aqueous phase is due to the dissolved metal ions. On the other hand Palit and Konar<sup>9</sup> suggested that unimolecular chain termination in heterogeneous media may be due to degradative chain transfer, or by dissolved metal ions or by the occlusion of the growing radicals in the cage of polymer coils.

**Monomer dependence:** Increasing [M] from  $7.03 \times 10^{-3}$  to  $42.19 \times 10^{-3}$  mol/l increased the initial rate and maximum conversion at fixed [MA],  $[Ce(IV)]$  and  $[H_2SO_4]$ . The more the concentration of monomer the more are the chances of initiation, higher the propagation magnitude and hence higher the initial rate and maximum conversion. The monomer exponent of near unity (1.2) rules out the possibility of primary radical termination. The samples of the polymethacrylamide formed became insoluble due to which the degree of polymerization could not be determined. The insolubility of the polymer samples is probably due to the intermolecular imidization or due to crosslinking in the polymer chains.

**Temperature dependence:** The effect of temperature on the rate was studied within the range 25 to 45°. As the temperature increases the initial rate and maximum conversion increased which is due to the increased frequency of initiation that enhances the rate and maximum conversion. The activation energy was found to be 15.25 k cal mol<sup>-1</sup>.

**Sulphuric acid dependence:** Increasing sulphuric acid concentration decreased the rate of polymerization at fixed [M], [MA] and  $[Ce(IV)]$ . This is possibly due to the formation of a highly sulphated complex of ceric ion that predominates at higher  $[H_2SO_4]$ . This highly sulphated complex of ceric ion has been suggested to be less reactive<sup>10</sup>. This was also proved in our laboratory by carrying out reactions with ceric ion in aqueous and sulphuric acid solutions. The rate in case of freshly prepared aqueous solutions of ceric ion are always higher than the rates observed in case of same concentration of ceric ion in sulphuric acid. By postulating  $Ce(SO_4)_2$  to be the reactive species it is evident that as

$[H_2SO_4]$  is increased the  $HSO_4^-$  ions produced will compete with the malic acid molecules by acting as ligands, and hence initial rate and maximum conversion should decrease. Further, it is known that ceric ion associates successively with one, two, three and four sulphate ions to form complexes which render the ceric ion almost inactive.





Fig. 2 Plot of  $-\frac{d[Ce(IV)]}{dt} \times 10^6$  mol/l/s vs (A)-[MA], (B)-[Ce(IV)]

For (A):  $[M] = 7.03 \times 10^{-3}$  mol/l,  $[Ce(IV)] = 2.05 \times 10^{-4}$  mol/l,  $[H_2SO_4] = 6.83 \times 10^{-3}$  mol/l; Temp. 35 ± 0.2°.

For (B):  $[M] = 4.22 \times 10^{-3}$  mol/l;  $[MA] = 11.06 \times 10^{-3}$  mol/l,  $[H_2SO_4] = 16.39 \times 10^{-3}$  mol/l; Temp. 35 ± 0.2°.

**Rate of ceric ion disappearance:** The rate of ceric ion disappearance increased with increasing  $[Ce(IV)]$ . Plot of rate vs  $[Ce(IV)]$  gave a straight line passing through the origin (Fig. 2B). The rate was found to be independent of [M]. Both these observations suggest that ceric ion participates only in the redox reaction but not in initiation or termination reactions. The rate increased slightly with increasing [MA] upto a certain range above which it remained constant (Fig. 2A). This shows a strong complex formation between ceric ion and malic acid in the reaction system that decomposes in presence of sulphuric acid to give free radicals (R<sup>•</sup>).



where K and  $k_r$  are the formation and decomposition constants of the complex. The complex formation was confirmed by Lineweaver-Burk plot of rate<sup>-1</sup> vs  $[MA]^{-1}$  which left a considerable intercept

on the ordinate. pH studies revealed a 1:1 complex formation between ceric ion and malic acid. The ir spectra of the complex gave a peak at  $1550\text{ cm}^{-1}$  (a shift). No peak appeared at  $1725\text{ cm}^{-1}$  which was observed in malic acid spectrum. This shift in the peak and a peak at  $560\text{ cm}^{-1}$  show the possible presence of metal-oxygen bonding in the complex.

#### Acknowledgement

The authors thank Dr. H. Narita of Kyoto University, Japan for valuable help and also the University Grants Commission, India for financial assistance to one of them (J.I.K.).

#### References

1. G. S. MISRA and J. J. REBELLO, *Makromol. Chem.*, 1975, **176**, 2203
2. G. S. MISRA and J. J. REBELLO, *Makromol. Chem.*, 1976, **177**, 21.
3. G. S. SUR and S. K. CHOI, *J. Macromol. Sci. Chem.*, 1981, **A15**, 671.
4. G. S. MISRA and S. L. DUBEY, *Colloid and Polym. Sci.*, 1979, **257**, 156.
5. G. S. MISRA and C. V. GUPTA, *Makromol. Chem.*, 1973, **165**, 205.
6. D. R. BURFIELD and S. C. NAG, *Eur. Polym. J.*, 1976, **12**, 873.
7. M. WATANABE and H. KIUCHI, *J. Polym. Sci.*, 1962, **58**, 103.
8. J. S. SHUKLA and D. C. MISRA, *Makromol. Chem.*, 1973, **173**, 91.
9. S. R. PALIT and R. S. KONAR, *J. Polym. Sci.*, 1964, **A-2**, 1731.
10. A. A. KATAI, V. K. KULSHRESTHA and R. H. MERCHES-SAULT, *J. Polym. Sci.*, 1963, **C-2**, 403.
11. a) F. S. DAINTON, *J. Polym. Sci.*, 1959, **34**, 227.  
b) F. S. DAINTON and D. G. L. JAMES, *Trans. Faraday Soc.*, 1958, **54**, 649.



# Formylcamphor Condensed with Diamines : The Structure in Solution as Obtained from UV Absorption and Circular Dichroism Spectroscopy

HANS PETER JENSEN

Chemistry Department A, Building 207, The Technical University of Denmark, DK-2800 Lyngby, Denmark

The condensation products of the stereoisomers of 1,2-diamino-1,2-diphenylethane with two molecules of formylcamphor have been investigated by means of uv absorption and circular dichroism spectroscopy. In chloroform such compounds take on a *syn* configuration with hydrogen bonding within an  $\alpha$ -(N-alkylaminoethylene) camphor group, and the intense  $\pi \rightarrow \pi^*$  transitions of the chromophore will couple in dimers provided the chromophores are near to each other. It is demonstrated how information about the relative orientation of the two formylcamphor groups may be obtained using the signs and envelopes of the  $\pi \rightarrow \pi^*$  transition bands.

SCHIFF base condensation products of formylcamphor and various 1,2-diamines have been rather thoroughly investigated and quite different conclusions have been reached concerning the stereochemistry of these compounds in various solvents<sup>1-3</sup>.

With the purpose of studying further the rotational conformations around substituted ethylene bridges showing that the stereochemistry of these rather complicated compounds can be understood within an exciton formalism, the condensation products between formylcamphor and the stereoisomers of 1,2-diamino-1,2-diphenylethane (stilbenediamine) have been investigated.

It has been the conclusion of previous papers in this subject<sup>1,2</sup> that minimum potential energy even for closely related molecules can be achieved in quite different ways e.g. in R-chxn(fmch)<sub>2</sub> and S-chxn(fmch)<sub>2</sub>, the rigidity of the cyclohexane ring is a dominating factor which forces the two diastereoisomers to take  $\Delta$  and  $\Lambda$  configurations, respectively. The configuration<sup>4</sup> is given in terms of handedness of the pair of lines connecting N and O of each aminomethylenecamphor group, and thus simultaneously representing the  $\pi \rightarrow \pi^*$  transition dipole moment of the chromophores.

In contrast to this it was shown that when the barrier towards rotation around the C-C bond of the diamine is low, the stereochemistry of the compounds is determined by the asymmetric bulkiness of the camphor skeleton as e.g. R-pn(fmch)<sub>2</sub> and S-pn(fmch)<sub>2</sub> have the same absolute configuration of the above mentioned pair of lines ( $\Delta$ )<sup>1,2</sup>.

Finally, it was demonstrated that *meso* compounds, e.g. R,S-chxn(fmch)<sub>2</sub> and R,S-2,3-bn(fmch)<sub>2</sub>, exhibit co-existence of the two possible forms (*e,a*) and (*a,e*) and that equivalence exists in the behaviour between *meso* compounds and compounds with an optically inactive ethylene bridge, e.g. en(fmch)<sub>2</sub> and ibn(fmch)<sub>2</sub><sup>3</sup>; spectra of the latter compound have not been published earlier,

but are quite analogous to those of en(fmch)<sub>2</sub>. Therefore at room temperature and in aged chloroform solutions two *gauche* rotamers of the ethylene bridge exist in equilibrium with the *trans* form. The equilibrium, however, may be displaced at lower temperatures, and judged from the CD spectrum of ibn(fmch)<sub>2</sub> in CHCl<sub>3</sub> at -60° (compare Table 2 of Ref 1) this should be towards the opposite absolute configuration of R-chxn(fmch)<sub>2</sub>. A consequence of the difference in configuration between R-pn(fmch)<sub>2</sub> and S-pn(fmch)<sub>2</sub>, on one hand and the *meso* and optically inactive compounds on the other is that, although it looks that the camphor groups are the stereochemically determining factors as soon as the rotation around the ethylene bridge is reasonably free, asymmetric methyl groups on the ethylene bridge are also involved in defining the minimum potential energy. Certainly, it is demonstrated from the above argumentation that formylcamphor Schiff base condensates with 1,2-diamines are compounds where the different substituents are heavily embedded into each other.

## Experimental

Racemic stilbenediamine was prepared and resolved according to Williams and Bailar<sup>5</sup> and Ugo *et al.*<sup>6</sup>, respectively, *meso*-stilbenediamine was prepared according to Irving and Parkins<sup>6</sup>, and formylcamphor was prepared from natural (+)-camphor according to Bishop *et al.*<sup>7</sup>. The identity of the compounds was established through chemical analyses.

Assignments of absolute configuration of optical active diamines have been done according to Gillard<sup>8</sup>.

Ultraviolet absorption spectra were measured with a Cary 14 spectrophotometer and circular dichroism spectra with a Roussel-Jouan micrograph II.




Fig 1. Molar absorptions and circular dichroisms of [various condensates dissolved and aged in  $\text{CHCl}_3$ ]. Full lines : room temperatures ; Broken lines :  $-60^\circ$ . In cases with broken lines in the CD-spectra no changes occur with temperature. All dipole strengths are  $\sim 2.10^{-18} \text{ cm}^2 \text{ cm}^{-1}$ .

**Abbreviations :**

R-stien = (+) $_D$ -(R,R)-1,2-diamino-1,2-diphenyl-ethane  
 S-stien = (-) $_D$ -(S,S)-1,2-diamino-1,2-diphenyl-ethane  
 R,S-stien = meso-(R,S)-1,2-diamino-1,2-diphenyl-ethane

R-chxn = (-) $_D$ -trans-(R,R)-1,2-cyclohexane-diamine  
 S-chxn = (+) $_D$ -trans-(S,S)-1,2-cyclohexane-diamine  
 R,S-chxn = meso-(R,S)-1,2-cyclohexanediamine  
 R-2,3-bn = (-) $_D$ -(R,R)-2,3-butanediamine  
 S-2,3-bn = (+) $_D$ -(S,S)-2,3-butanediamine

R,S-2,3-bn = *meso*-(R,S)-2,3-butanediamine  
 R-pn = (-)<sub>D</sub>-(R)-1,2-propanediamine  
 S-pn = (+)<sub>D</sub>-(S)-1,2-propanediamine  
 en = 1,2-ethanediamine  
 ibn = 2-methyl-1,2-propanediamine  
 fmcH = formylcamphor

R-pn(fmcH), etc. symbolize the "Schiff base" condensates formed from one molecule of diamine and two molecules of diketones

## Results and Discussion

The Schiff base condensates of stilbenediamine and formylcamphor show the same kind of *syn/anti* tautomerisation depending on the ability of the solvent to form hydrogen bonds, as was demonstrated earlier for similar compounds<sup>1</sup>, and accordingly we will, in what follows, only refer to the spectra of aged chloroform solutions. In such solution it is possible by <sup>1</sup>H nmr spectroscopy to confirm that the *syn* configuration of the chromophore is the dominating species. The reason why we wish to be certain that we work with the *syn* configuration is that we want to discuss spectral behaviour in an exciton formalism with reference to the acetylacetone chromophore<sup>2</sup>, which independent of solvent is found in a *syn* configuration.

The spectra of R-stien(fmcH)<sub>2</sub>, S-stien(fmcH)<sub>2</sub> and R,S-stien(fmcH)<sub>2</sub> are given in Fig. 1.

The spectra are measured approximately 2 hr after dissolution, at which time *syn/anti* ratio from nmr is estimated to ~10/1. Prolonged dissolution in CHCl<sub>3</sub> seems to accelerate a destruction as the  $\pi \rightarrow \pi^*$  transition intensity falls off markedly after 5 hr. The destruction products have not been investigated.

If one considers absorption and circular dichroism spectra of the two diastereoisomers R- and S-stien(fmcH)<sub>2</sub>, it is seen that these fit nicely with expectations based on the order pn < 2,3-bn < stien with respect to increasing barrier towards rotation around the substituted ethylene bridge. This is to say that while R- and S-pn(fmcH)<sub>2</sub> and R- and S-2,3-bn(fmcH)<sub>2</sub> choose the same absolute configuration of the diastereoisomers, this is not the case with R- and S-stien(fmcH)<sub>2</sub>, which has a mirror image relationship. A mirror image relation-

ship was also seen with R- and S-chxn(fmcH)<sub>2</sub>, and in that case was a consequence of an infinitely great barrier towards rotation around the substituted ethylene bridge. Cooling to -60° does not accentuate the CD-spectra very much and although the absorption spectra do not show a marked exciton splitting there cannot be very much *trans* rotamer present in solution, because of the magnitudes of the Cotton effects

Turning our attention towards the spectral behaviour of R,S-stien(fmcH)<sub>2</sub>, it is seen that the exciton splitting in the absorption band is even less marked than with the active compounds discussed. This means that the distribution between the *gauche* and *trans* rotamers at room temperature is probably placed rather much towards the *trans* form. This conclusion is confirmed by the CD spectrum which is not characteristic of exciton coupling at room temperature, whereas cooling enforces such a behaviour, thereby meaning that this species like the rest of the investigated *meso* and optically inactive diamine condensates with formylcamphor, has the  $\Lambda$  configuration of the chromophores as the low energy one. This set of information supports the conclusion that asymmetric substituents on the ethylene bridge in the condensates of formylcamphor and 1,2-diamines do not directly determine but do influence seriously the way in which minimum potential energy is achieved.

## Acknowledgement

The author thanks Mrs. L. Penzien for valuable assistance.

## References

1. H. P. JENSEN and E. LARSEN, *Acta Chem. Scand.*, 1975, 85, 157.
2. H. P. JENSEN and E. LARSEN, *Gazz. Chim. Ital.*, 1977, 107, 143.
3. M. GULLOTTI, A. PASINI, P. FANTUCCI, R. UGO and R. D. GILLARD, *Gazz. Chim. Ital.*, 1972, 102, 853.
4. I. U. P. A. C., *Inorg. Chem.*, 1970, 1, 9.
5. O. F. WILLIAMS and J. C. BAILAR, *J. Amer. Chem. Soc.*, 1959, 81, 4464.
6. M. N. IRVING and R. M. PARKINS, *J. Inorg. Nuclear Chem.*, 1965, 27, 270.
7. A. W. BISHOP, L. CLAISEN and W. SINCLAIR, *Justus Liebigs Ann. Chem.*, 1894, 281, 314.
8. R. D. GILLARD, *Tetrahedron*, 1965, 21, 503.
9. E. LARSEN, *Acta Chem. Scand.*, 1969, 23, 2158.

# Thermodynamics of Ferrous-1,10-Phenanthroline in *t*-Butanol-Water and Glycerol-Water Media at 25°

A. K. MANDAL, S. BANDYOPADHYAY and S. ADITYA

Department of Applied Chemistry, University of Calcutta, Calcutta-700 009

The enthalpies of formation of ferrous-1,10-phenanthroline in *t*-BuOH-water and glycerol-water mixtures at 25° have been determined by calorimetry. The stability constants of the complex in the above mixed solvents have been determined spectrophotometrically. The entropy-changes have been evaluated combining the enthalpy values with the corresponding free energy changes calculated from  $pK$  values. The role of solvents on the thermodynamic parameters has been discussed.

1,10-Phenanthroline and its Fe(II) complex are well known for their use in analytical chemistry and also in view of their possible use as corrosion-inhibitors in boilers<sup>1</sup>. Since the first determination of the stability constants of phenanthroline ion and its ferrous complex by Dwyer and Nyholm<sup>2</sup>, different workers<sup>3-11</sup> have studied these systems. Lahiri and Aditya<sup>12</sup> made a detailed spectrophotometric study and reported on the thermodynamic properties of phenanthroline ion, ferroin and ferriin in aqueous medium. The dissociation constants as well as the enthalpies of the reactions in methanol-water medium were studied in this laboratory by Biswas and Aditya<sup>13</sup>. We also presented in an earlier communication<sup>14</sup> the thermodynamics of 2,2'-dipyridinium ion and 1,10-phenanthroline ion in *t*-butanol-water and glycerol-water media at 25°. In this communication we report the enthalpies of formation of  $FePh_3^{2+}$  in different *t*-butanol- and glycerol-water mixtures at 25° determined by calorimetry and the dissociation constants by spectrophotometry.  $\Delta G^\circ$  and  $\Delta S^\circ$  values were calculated from these experimental results.

## Experimental

The solutions were prepared as reported earlier<sup>14,15</sup>. Purification of solvents was described in an earlier communication<sup>16</sup>.

For the measurement of enthalpy change we used a microcalorimeter fabricated in this laboratory<sup>17,18</sup>. Experimental determinations were carried out in the same way as described in the case of  $Fe(dipy)_3^{2+}$  reported earlier<sup>15</sup>. In the present case also we note that the addition of a small volume of Mohr solution to a large excess of 1,10-phenanthroline gives a constant value of  $\Delta H$  in the pH-range used. The heat change due to the formation of  $PhH^+$  ion was taken into account. For the purpose, blank experiment with no Mohr salt (5 ml of solution containing  $HClO_4$  and 250 ml of Ph) was done. The concentration of Ph was always more than 30 times the concentration of  $Fe^{2+}$  ion. The stability constants of  $FePh_3^{2+}$  were determined in *t*-butanol- and glycerol-water mixtures spectrophotometrically

at 25° with a Beckmann DU spectrophotometer as reported in detail earlier<sup>19</sup>.

## Results and Discussion

From the measured heat liberated, enthalpy change per mole for the reaction  $Fe^{2+} + 3 Ph \rightleftharpoons FePh_3^{2+}$  was calculated, using the relation  $\Delta H = -\frac{Q}{x}$ , where  $Q$  represents the heat liberated in Joules for  $x$  moles of  $FePh_3^{2+}$  formed. The reaction is iso-electric and as such ionic strength has very little effect. So the experimentally determined  $\Delta H$ s have been taken as  $\Delta H^\circ$ s. The dissociation constants and the  $\Delta H^\circ$ s for  $FePh_3^{2+} \rightleftharpoons Fe^{2+} + 3Ph$ , in *t*-butanol- and glycerol-water have been presented in columns 2 and 3 of Table 2 and in columns 6 and 7 of Table 3, respectively.

TABLE 1—THERMODYNAMICS OF  $FePh_3^{2+}$  IN AQUEOUS MEDIUM AT 25°

Reaction	$\Delta G^\circ$ (kJ mole <sup>-1</sup> )	$\Delta H^\circ$ (kJ mole <sup>-1</sup> )	$\Delta S^\circ$ (kJ mole <sup>-1</sup> )
$FePh_3^{2+} \rightleftharpoons Fe^{2+} + 3Ph$	116.90	131.04 <sup>a</sup>	47.28
	119.24	138.07 <sup>b</sup>	64.43
	117.70	129.70 <sup>c</sup>	40.27

a = Spectrophotometric value<sup>11</sup>.

b = Calorimetric value<sup>15</sup>.

c = Our values extrapolated from lower percentages of organic solvent.

TABLE 2—THERMODYNAMICS OF  $FePh_3^{2+} \rightleftharpoons Fe^{2+} + 3Ph$  IN *t*-BUTANOL AND GLYCEROL-WATER MEDIA AT 25°

Wt % of solvent	$pK_a$ s	
	Glycerol-water	<i>t</i> -butanol-water
0 <sup>b</sup>	20.70 ( $\pm 0.48$ ) <sup>a</sup>	20.70 ( $\pm 0.48$ )
10	20.52	20.20
20	20.66	19.70
30	19.70	19.10
40	19.92 ( $\pm 1.10$ )	17.50
50	—	17.00 ( $\pm 0.81$ )

<sup>a</sup> Values in parentheses indicate maximum errors.

The thermodynamic parameters  $\Delta G^\circ$ ,  $\Delta H^\circ$  and  $T\Delta S^\circ$  for the above reaction in *t*-butanol- and glycerol-water have been compiled in columns

TABLE 3—THERMODYNAMICS OF  $\text{FePh}_3^{2+} \rightleftharpoons \text{Fe}^{2+} + 3\text{Ph}$  IN DIFFERENT SOLVENT MEDIA AT 25°



Wt % of solvent	$\Delta G^\circ$ (kJ mole <sup>-1</sup> )				$\Delta H^\circ$ (kJ mole <sup>-1</sup> )				$T\Delta S^\circ$ (kJ mole <sup>-1</sup> )			
	Glycerol	<i>t</i> -BuOH	EtOH	MeOH	Glycerol	<i>t</i> -BuOH	EtOH	MeOH	Glycerol	<i>t</i> -BuOH	EtOH	MeOH
0	117.70	117.70	117.12	116.90	129.70	129.70	129.91	131.40	12.00	12.00	12.79	14.14
10	116.65	114.85	113.00	114.22	136.10	137.48	130.87	148.53	19.45	22.63	17.87	34.31
20	117.44	112.01	109.00	111.71	149.07	153.22	133.22	166.94	31.63	41.21	24.22	55.23
30	112.00	108.57	104.90	109.20	145.73	172.13	128.45	167.78	33.73	63.56	23.55	58.58
40	113.35	99.50	100.05	106.69	142.42	156.32	—	156.90	29.07	56.82	—	50.21
50	—	96.65	96.50	104.18	139.95	150.58	—	148.11	—	53.93	—	43.93

Values of  $\Delta G^\circ$  at 15% and 25% for glycerol-water media are 116.10 and 114.60 kJ mole<sup>-1</sup>, and for *t*-BuOH-water media are 117.90 and 109.20 kJ mole<sup>-1</sup>, respectively.

Values  $\Delta H^\circ$  at 2.5% and 5% for glycerol-water media are 131.00 ( $\pm 0.02$ ) and 132.67 ( $\pm 0.04$ ) kJ mole<sup>-1</sup> and for *t*-BuOH-water media are 131.54 ( $\pm 0.03$ ) and 133.51 ( $\pm 0.04$ ) kJ mole<sup>-1</sup>, respectively.

2, 3, 6, 7, 10, 11 of Table 3 along with the same in EtOH<sup>17, 20</sup> and MeOH-water<sup>18</sup> (reported earlier) in columns 4, 5, 8, 9, 12, 13 of the same table. The Figs. 1, 2 and 3 indicate the nature of the plots of  $\Delta H^\circ$ ,  $\Delta G^\circ$  and  $T\Delta S^\circ$  against wt %, mole-fraction of organic solvent and reciprocal of the dielectric constant of aqueo-organic solvents, respectively. The dielectric constant values necessary are taken from Conway<sup>21</sup> and Akerlof<sup>22</sup>. We have also determined the same parameters in water from the extrapolation of the  $\Delta H^\circ$  and  $\Delta G^\circ$  values in the region of lower percentages of organic components in water. The values of the thermodynamic parameters of  $\text{FePh}_3^{2+}$  in water in literature along with ours are presented in Table 1. The present values are in good agreement with those of Anderegg<sup>11</sup> and Lahiri and Aditya<sup>12</sup>.

In the Figs. 1 and 2 it is seen that  $\Delta G^\circ$  changes linearly upto 30% of *t*-BuOH (which corresponds to


Fig. 1. Plot of  $\Delta G^\circ$ ,  $\Delta H^\circ$  and  $T\Delta S^\circ$  vs wt % of organic component.

Fig. 2. Plot of  $\Delta G^\circ$ ,  $\Delta H^\circ$  and  $T\Delta S^\circ$  vs mole fraction of organic component

a mole-fraction of 0.09) and 20% of glycerol (corresponding to a mole-fraction of 0.04) and deviates at higher percentages. The variation of  $\Delta H^\circ$  and  $T\Delta S^\circ$  values with solvent composition is not linear. The values at first increase with increasing organic solvent and pass through a maximum at about 30% in case of *t*-BuOH and 20% in case of glycerol in the respective solvent mixtures. Similar behaviour has been observed by us in case of  $\text{PhH}^+$  in *t*-BuOH- and glycerol-water mixtures<sup>14</sup> and also in case of  $\text{dipyH}^+$  and  $\text{Fe(II)-dipy}$  complexes<sup>23</sup>. Such type of maximum structuration was also supported by Mishchenko *et al.*<sup>24</sup>, Krestov and Klopov<sup>24</sup>, Pointud *et al.*<sup>25</sup>.

The interpretation of the thermodynamic data in mixed solvents is extremely difficult as it involves a knowledge of the structure of the liquid mixture and structure modification of the media when an ionic




Fig. 3. Plot of  $\Delta G^\circ$ ,  $\Delta H^\circ$  and  $T\Delta S^\circ$  vs  $1/D$  of solvent mixture ( $D$  = dielectric constant).

system is introduced in the media, in addition to ionic solvation effects.

The free energy change of transfer,  $\Delta G^\circ$ , which consists of electric and non-electric contributions [ $\Delta G^\circ = \Delta G^\circ_{(el)} + \Delta G^\circ_{(non-el)}$ ], in the present case will be mainly due to ion solvent and solvent-solvent interactions (non-electric part). Since the reaction is iso-electric,  $\Delta G^\circ_{(el)}$  will be negligible due to the small difference in the ionic ratio of  $FePh_2^{2+}$  and  $Fe(H_2O)_6^{2+}$  which is always solvated.  $\Delta G^\circ$  indicates that the reaction is favoured in mixed solvents. This is possibly because of (i) higher solubility of Ph' in the mixed solvents, (ii) the difference in the solvational properties of  $Fe(H_2O)_6^{2+}$  and  $FePh_2^{2+}$  in the media, and (iii) the solvent-solvent interaction.

The entropy change of transfer of different ionic species participating in the reaction will depend on difference in entropy of the solvent media. As discussed in our earlier communication<sup>25</sup> for  $Fe(dipy)_3^{2+}$ , we have for the entropy change of  $FePh_2^{2+}$

$$T\Delta S^\circ = T\Delta S_{(Fe^{2+})} + 3T\Delta S_{(Ph)} - T\Delta S_{(FePh_2^{2+})}$$

The value of  $T\Delta S^\circ$  passes through a maximum based on the models by Franks and Reid<sup>26</sup>, Kundu et al<sup>27</sup> and other workers<sup>28-30</sup>.

The variation of  $\Delta H^\circ$  with solvent composition in case of  $Fe(Ph)_2^{2+}$  is found to be similar to that observed in case of  $Fe(dipy)_3^{2+}$ . The models have been discussed in details<sup>24,31</sup>. The thermodynamic parameters for  $Fe(II)$ -1,10-phenanthroline complex in general vary with composition of the solvent in the same manner as the  $Fe(II)$ -dipy complex.

#### Acknowledgement

One of the authors (S.B.) thanks the Council of Scientific and Industrial Research, New Delhi for the award of a Senior Research Fellowship.

#### References

1. A. WEISSTUCK, D. A. CARTER and C. C. NATHAN, "Proc. 26th Conf. Nat. Assoc. Corrosion", Eng., 1970, 536.
2. F. P. DWYER and R. S. NYHOLM, *J. Proc. Roy. Soc., New South Wales*, 1946, 80, 28.
3. R. D. ALEXANDER, A. W. L. DUDENEY and R. J. IRVING, *J. Chem. Soc., Faraday Trans. 1*, 1978, 5, 1075.
4. T. S. LEE, I. M. KOLTHOFF and D. L. LEUSSING, *J. Amer. Chem. Soc.*, 1948, 70, 2348, 3595.
5. C. H. COOK and F. A. LONG, *J. Amer. Chem. Soc.*, 1951, 73, 4119.
6. C. J. HAWKINS, H. DWELL and W. F. PICKERING, *Analyt. Chem. Acta*, 1961, 25, 257.
7. H. IRVING and D. H. MELLOR, *J. Chem. Soc.*, 1962, 5222.
8. R. RICCARDI and P. FRANZOSINI, *Bull. Sci. Fac. Chim. Ind. Bologna*, 1957, 15, 25.
9. R. NASANEN and E. U. UUSITALO, *Suomen Kemistilehti*, 1956, 29B, 11.
10. P. GEORGE, G. I. H. HANANIA and D. H. IRVING, *J. Chem. Soc.*, 1959, 2548.
11. G. ANDEREGG, *Helv. Chim. Acta*, 1963, 46, 2397, 2813.
12. S. C. LAHIRI and S. ADITYA, *Z. Physik. Chem.*, 1964, 41, 173.
13. G. BISWAS, S. C. LAHIRI and S. ADITYA, *Thermochim. Acta*, 1977, 19, 55.
14. S. BANDYOPADHYAY, A. K. MANDAL and S. ADITYA, *J. Indian Chem. Soc.*, 1981, 58, 467.
15. S. BANDYOPADHYAY, A. K. MANDAL and S. ADITYA, *Thermochim. Acta*, 1982, 52, 204.
16. S. BANDYOPADHYAY and S. C. LAHIRI, *J. Indian Chem. Soc.*, 1978, 55, 1286.
17. A. K. ROY, S. C. LAHIRI and S. ADITYA, *Thermochim. Acta*, 1976, 16, 277.
18. S. BANDYOPADHYAY and S. ADITYA, *J. Indian Chem. Soc.*, 1980, 57, 76.
19. D. K. HAZRA and S. C. LAHIRI, *Anal. Chim. Acta*, 1975, 79, 335.
20. A. BHATTACHARYA and S. C. LAHIRI, *J. Indian Chem. Soc.*, 1978, 55, 607.
21. B. E. CONWAY, "Electrochemical Data", Elsevier Publishing Company, Amsterdam, Houston, London, 1952.
22. G. AKERLOF, *J. Amer. Chem. Soc.*, 1932, 54, 4125.
23. K. P. MISHCHENKO and G. M. POLTORATSKY, "Examination of the Thermodynamics and Structure of Aqueous and Non-aqueous Electrolytic Solutions", Chemical Publisher, Leningrad Division, 1968.
24. G. A. KRESTOV and V. I. KLOPOV, *Zh. Strukt. Khim.*, 1964, 5, 829.
25. Y. POINTUD, J. P. MOREL and J. JUILLARD, *J. Phys. Chem.*, 1976, 80, 2381.
26. F. FRANKS and D. S. REID, *J. Phys. Chem.*, 1969, 73, 3152.
27. K. K. KUNDU and K. BOSE, *Cand. J. Chem.*, 1977, 55, 3961.

# Photocorrosion

K. L. CHENG

Department of Chemistry, University of Missouri-Kansas City, Kansas City, Missouri 64110, U. S. A.

Semiconductors are often decomposed by anodic oxidation or cathodic reduction upon illumination when they are in contact with electrolytes. Examples of semiconductor corrosion are described. The mechanisms of photocorrosion for various materials are reviewed. Stabilization of semiconductor surface against photocorrosion has been discussed and the ways to prevent, to suppress, and to minimize photocorrosion are suggested. Modern analytical techniques are useful tools for future photocorrosion research.

## I Electrochemical Principles of Corrosion

### A. Corrosion of metals and alloys :

**C**ORROSION is the interaction of a metal or alloy with its non-metallic environment. Since metals and alloys are conductors and are built up of cations and electrons that are more or less easily dissociable, and the environment usually contains ionically conducting species, most corrosion reactions are electrochemical. The stability of metals has been reviewed in detail<sup>1</sup>.

### B. Corrosion of semiconductors :

Semiconductors are often decomposed by anodic oxidation or cathodic reduction if they are illuminated in contact with electrolytes<sup>2</sup>. The mechanism of these reactions has been analyzed and studied in some detail<sup>3</sup>. It appears that the anodic decomposition may be described as a weakening of chemical bonds at the surface of a semiconductor due to the presence of holes, that means a deficiency of electrons in bonding orbitals. The cathodic decomposition may be analogously described as caused by the presence of electrons in the surface, occupying non-bonding or antibonding orbitals. As a result, the weakening of the bonding of surface atoms in both cases facilitates the attack by nucleophilic or electrophilic reactants which are always present in the electrolyte.

In recent years, considerable attention had been given to the properties of semiconductors in contact with electrolytic solutions<sup>4-6</sup>, and theories had been formulated explaining many of the results. There was a critical problem of corrosion encountered with all of the materials tested, particularly the photocorrosion<sup>7-9</sup>. In some cases the semiconductors corrode spontaneously in the dark (forming mainly a battery), while in most instances corrosion occurs on illumination. Instead of reduced species in the aqueous electrolyte, holes in the n-type semiconductor valence band were found to oxidize the electrode itself. Holes in such an n-type semiconductor are broken bonds, while electrons in a p-type semiconductor represent excess bonds, so that in either case accumulation of the photogenerated carriers at the semiconductor surface can lead

to a rupturing of the lattice. With n-type CdS, for example, the reaction on illumination is



the two electrons can reduce  $\text{Cd}^{2+}$  at a counter electrode. The coating of elemental S covers the electrode surface in a few minutes and the reaction stops

Of course, if an electrode would remain stable under illumination, then it could be applied to generate useful chemical products in a solution, while itself only acting as a photocatalyst. Therefore, photoelectrochemical decomposition of water with semiconductors as catalysts has been extensively studied. In 1972, Fujishima and Honda<sup>7</sup> showed that it is possible to use the semiconductor  $\text{TiO}_2$  (rutile) in contact with water to generate both  $\text{H}_2$  and  $\text{O}_2$  under illumination, and claimed that the material suffered no degradation. This report soon created great enthusiasm in the field of semiconductor-electrolyte interfaces<sup>8</sup>.

We know the corrosion phenomena, we recognize its serious problems, and we have limited knowledge about it. We are actively searching for its solutions.

## II. Examples of Semiconductor Corrosion

### A. Photocorrosion of $\text{TiO}_2$ :

Even though the  $\text{TiO}_2$  photoanodes have been shown by many investigators to be stable, evidence indicates that they actually undergo slow dissolution in acidic solutions<sup>9,10</sup>. Upon exposure to an 1N  $\text{H}_2\text{SO}_4$  solution, the  $\text{TiO}_2$  electrode turns velvety black in contrast to the unexposed glassy surface of the crystal. Scanning electron microscopy (SEM) reveals the presence of square tapered pits on the exposed surfaces of the crystal. This process is not a simple chemical dissolution because of its absence in the dark. Addition of 1.0 M  $\text{CoSO}_4$  or 1.0 M  $\text{Co}(\text{ClO}_4)_2$  to 1N  $\text{H}_2\text{SO}_4$  suppresses the anodic photodissolution of  $\text{TiO}_2$  as evidenced by the absence of apparent changes or weight loss of the photoanode.

Some evidence of photoanodic dissolution of  $\text{TiO}_2$  in alkaline solutions (5.0–7.0 M NaOH) at very high light intensities was also observed; a small depression in the electrode surface after about 1 hr of irradiation appeared<sup>11</sup>.

#### B. Stability of titanates :

(a)  $\text{SrTiO}_3$  electrodes, before and after the passage of electricity in the photolysis of water with 9.5 M NaOH in  $\text{H}_2^{18}\text{O}/\text{H}_2\text{O}$ , were examined by Wrighton *et al.* They concluded that the  $\text{SrTiO}_3$  was stable under conditions where the electrolysis of water was photo assisted. This is the first report to show the photolysis of water without any external bias. Ohashi, McCann and Bockris<sup>12</sup> also found it to be stable when they combined n- $\text{SrTiO}_3$ -p-CdTe and n- $\text{SrTiO}_3$ -p-GaP as stable photoelectric cells.

(b)  $\text{FeTiO}_3$ ,  $\text{Fe}_2\text{TiO}_4$  and  $\text{Fe}_3\text{TiO}_8$  : Iron titanate systems have been studied as possible candidates for semiconductor electrodes in PEC cells by Ginley and Baughman<sup>14</sup>. These authors observed the electrochemical degradation of the titanates with leaching of iron out of the surface. This poses a serious problem in spite of the reasonable chemical stability of these materials.

(c)  $\text{BaTiO}_3$  : Photolysis of water using  $\text{BaTiO}_3$  electrodes has been studied by Nasby and Quinn<sup>15</sup>. No apparent electrode degradation has been observed for solutions in the pH range 1.1 to 13.6

#### C. Acid dissolution of $\text{Fe}_2\text{O}_3$ :

The possibility of using  $\text{Fe}_2\text{O}_3$  as semiconductor electrodes in photoelectrochemical cells has been investigated. Hardee and Bond<sup>16</sup> observed gas evolution with the anodic current which they attribute to the photo assisted oxidation of water to produce  $\text{O}_2$ . They found that the potential for the onset of the photocurrent shifts to more negative values with increasing pH of the solution. The  $\text{Fe}_2\text{O}_3$  films are seen to be stable at open circuit in basic solutions up to 1 M NaOH. On the other hand, acid solutions (pH < 4.5) slowly dissolve the  $\text{Fe}_2\text{O}_3$  coating<sup>17</sup>.

The acid dissolution of  $\text{Fe}_2\text{O}_3$  seems to be not related to photocorrosion. It may be simply the increasing solubility of  $\text{Fe}_2\text{O}_3$  in an acidic solution.

But Yeh and Hackerman<sup>18</sup> reported no noticeable corrosion problems with  $\text{Fe}_2\text{O}_3$  in pH 4.0 acetate buffer to 5.5 M KOH solutions.

#### D. $\text{SnO}_2$ :

Photo effects at polycrystalline  $\text{SnO}_2$  electrodes have been demonstrated by Kim and Laitinen<sup>19</sup>. The photo assisted electrolysis of water by uv irradiation of a Sb-doped  $\text{SnO}_2$  electrode has been studied by Wrighton<sup>20</sup>. In acidic or weakly alkaline solutions, small amounts of  $\text{H}_2\text{O}_2$  are also formed<sup>21</sup>.


#### E. $\text{ZnO}$ and $\text{Cu}_2\text{O}$ :

Gerischer<sup>21</sup> states that the reduction of ZnO can occur at high cathodic polarization where the surface degenerates. Thermodynamic considerations by Gerscher<sup>21</sup> also show that the cathodic and anodic


decomposition potentials are close together and both are far inside the band gap of the  $\text{Cu}_2\text{O}$ . This system is therefore very unstable and unsuitable as a photo electrode in a PEC cell.

#### F. $\text{GaP}$ , $\text{GaAs}$ , $\text{CdTe}$ , $\text{CdS}$ , $\text{ZnSe}$ and $\text{ZnTe}$ :

According to Memming and Schwandt<sup>22</sup>, irradiation of an n-GaP electrode in alkaline solutions yields electron flow from GaP to the counter electrode, resulting in photoanodic dissolution of GaP according to the reaction




At higher current densities (10 mA/cm<sup>2</sup>), the following reaction takes place<sup>23</sup>




In acidic solutions, these studies have shown that Ga and P are dissolved in the trivalent and pentavalent states, respectively with the consumption of 6 positive holes.

Analytical studies of the photoanodic dissolution of GaAs have been reported<sup>24</sup>. In alkaline solutions, GaAs dissolution takes place according to the reaction




The photoanodic dissolution of CdS electrodes has been described<sup>25,26</sup> according to the reactions



Despite of anodic dissolution of CdTe, the combinations of n- $\text{TiO}_2$  and n- $\text{SrTiO}_3$  with p-CdTe and p-GaP have been reported to form separate, stable self-driven PEC cells<sup>12</sup>. Ohashi *et al.*<sup>26</sup> have investigated ZnTe and CdTe as possible candidates for photo cathodes in PEC cells. Their studies show that CdTe can be used as stable photocathode in a PEC cell consisting of CdTe/NaOH/ $\text{TiO}_2$  but ZnTe is unstable and has unfavourable photo response characteristics.

The photodecomposition of ZnSe illustrates a common property of binary compound semiconductors<sup>27</sup>. Very stable semiconductors decompose rapidly in an electrolyte solution on illumination. When an electrode of conducting n-type ZnSe and a piece of Pt wire are immersed in an inert aqueous electrolyte solution and the external leads are short-circuited, nothing happens in the dark. However, if the electrode is illuminated, a remarkably efficient reaction starts. The ZnSe has a band gap of 2.7 eV and is normally pale yellow in colour. After a few minutes of irradiation, its surface turns dark red due to the oxidation of  $\text{Se}^{2-}$  to  $\text{Se}^0$ . Analysis of the solution also shows the dissolution of  $\text{Zn}^{2+}$  ion. Two electrons pass through the external circuit from the ZnSe electrode to the Pt electrode according to the overall reaction



To understand the relation between the conductivity type and the chemical reaction rate, we may consider that in an ionic compound, the conduction band can be associated with the cations and the valence band with the anions. This may be partially



valid for partially ionic compounds such as ZnSe. Based on the relative thermodynamic properties of the ions, there is a tendency towards a symmetric dissolution. A  $\text{Zn}^{2+}$  ion in the crystal goes into solution, leaving behind two negative charges on a  $\text{Se}^{2-}$  ion that remains bound to the solid. For electrostatic reasons, the dissolution soon ceases unless the negative charges on the  $\text{Se}^{2-}$  can move out of the crystal passing through the external circuit. This is difficult in an n-type semiconductor. In order to move charges out of the crystal it must get to the conduction band, because this is where charge moves in an n-type semiconductor. For getting to the conduction band, it requires 2.7 eV excitation energy which cannot be supplied by thermal excitation at room temperature. As a result, there is no decomposition in the dark. On illumination, holes become available. These flow to the surface and so neutralize the negative charges. At the same time the electrons excited by the radiation flow in the opposite direction through the conduction band and into the external circuit to complete the charge balance. The dissolution of ZnSe crystal continues until it is blocked by the coating of a layer of slightly soluble material on its surface. Theoretically, if the ZnSe had been p-type, the charge neutralization required for the dissolution could have been supplied by the flow of thermally excited holes through the valence band. The dark dissolution should take place. No experiment with the p-type ZnSe was reported<sup>48</sup>.

#### G $\text{WO}_3$ :

$\text{WO}_3$  shows no weight changes after prolonged passage of electricity under strong irradiation.

#### H. Si :

Another kind of reaction that consumes the electrode material is the anodic oxidation of covalent semiconductors requiring a supply of holes to the surface<sup>49</sup>. An important example that requires a supply of holes is the anodic oxidation of Si. For an n-type crystal there is a Schottky barrier at its surface with the usual rectifying i-V behaviour. The overall reaction is



the experimentally obtained values for  $z$  vary from 2 to 4 depending on the reaction conditions.

### III. Stabilization of Semiconductor Surface against Photocorrosion

Recently, impressive progress has been made in the development of photoelectrochemical solar cells. However, a major difficulty remains, that is, the photocorrosion of desirable anode materials such as GaAs and n-Si. Ultimately, the goal is to make photoelectric cells using polycrystalline materials<sup>57,58</sup>, which will contain different defects. Simple theory suggests that defective areas of the crystal surface will be more difficult to stabilize<sup>59</sup>. Experimentally speaking, it is unclear what effects these defects will have on the photoelectrochemical corrosion processes.

A great number of efforts have been made in the past to prevent, to suppress, or to minimize photocorrosion. These efforts may be summarized as follows.

#### A. Electrode coating :

The approach to the dissolution problem has been the use of inert coatings on the photoanode surface. Gourgand and Elliott<sup>59</sup> have described the use of a  $\text{MoO}_3$  coating to prevent the electrolytic corrosion of n-GaAs under irradiation. Nakato *et al*<sup>30</sup> have reported the coating of a thin transparent gold film to the n-GaP surface.

Coating or deposition of a wide band-gap stable semiconductor on the surface of the unstable semiconductor has been attempted in an effort to reduce the extent of anodic photodecomposition. Tomkiewicz *et al*<sup>61</sup> describe the sputtering of  $\text{TiO}_2$ ,  $\text{SnO}_2$ ,  $\text{Nb}_2\text{O}_5$ ,  $\text{Al}_2\text{O}_3$ , and  $\text{Si}_3\text{N}_4$  on GaAs and GaAlAs. Single crystalline semiconductors, such as n-Si, p-Si, n-GaAs, p-GaAs, n-GaP, n-InP and n-CdS have been coated with n- $\text{TiO}_2$  resulting in unfavourable results<sup>62</sup>. However, Bockris and Uosaki<sup>63</sup> have reported the chemical vapour deposition of  $\text{TiO}_2$  on CdS single crystals. The efficiency of this electrode is reported to be four times greater than a  $\text{TiO}_2$  single crystal in contrast to the results of Kohl *et al*<sup>64</sup>. Ghosh and Maruska<sup>65</sup> have reported the reduced photocorrosion by the use of  $\text{TiO}_2$  film on CdSe.

In the investigation of electrocatalysis or inhibition of electrode processes of a reactant (R) at the metal electrode (M) in the presence of surface layer (S), Schultze and Habib<sup>66</sup> conclude that electrocatalysis and inhibition by electrosorbates and protective layers is a three-parameter problem. It depends on (a) the type of layer (ionic, covalent, neutral oxide, salt), (b) the type of reaction, and (c) the type of influence (chemical, electrostatic, geometric, etc.).

Electrodes covered with thin permeable polymer films have been studied by Doblhofer<sup>67</sup>. The films prepared on the anode of the glow discharge act as semi-permeable membranes. Hydrogen can be oxidized on the Pt-polymer interface of these polymer covered electrodes at rates comparable to uncovered Pt, while the films were impermeable to iron ions.

#### B. Use of redox system :

The stability problems associated with the use of  $\text{CdX}$  ( $\text{X}=\text{S}, \text{Se}, \text{Te}$ ) and  $\text{GaY}$  ( $\text{Y}=\text{P}, \text{As}$ ) as photoanodes in PEC cells have led some investigators to suppress anodic dissolution by the use of suitable redox systems in the electrolyte.  $\text{Fe(II)-EDTA}$  is a good stabilizing agent at pH 3 for n-GaAs<sup>68</sup>.

The use of wide-gap semiconductors in PEC systems is hampered by the fact that these electrodes utilize only a small portion of the solar spectrum for efficient energy conversion. The dye sensitization approach restricts light absorption to the order of 1-2% since only monolayers of dyes are active

for electron transfer. Therefore, efforts should be made on the achievement of good stability with low band gap semiconductors like GaP, GaAs, etc. by incorporation of suitable redox couples in the electrolyte<sup>17</sup>. The stability of common semiconductors used as photoanodes with values of their band gap, flatbands and quantum efficiency is listed in Table 1.

TABLE 1—STABILITY OF SEMICONDUCTOR ELECTRODES FOR PHOTOCATALYTIC DISCOMPOSITION OF WATER\*

Material	$E_{H_2}$ eV	$E_{F/B}$ eV	Highest quantum efficiency %	Stability
TiO <sub>2</sub>	3.0	0.05	100	Stable
SrTiO <sub>3</sub>	3.2	-0.2	100	Stable
BaTiO <sub>3</sub>	3.3	0.1	30	Stable
KTaO <sub>3</sub>	3.5	-0.2	6	Stable
FeTO <sub>3</sub>	2.2	1.1	15	Leaching of Fe noted
Fe <sub>2</sub> TiO <sub>4</sub>	2.2	1.2	15	Leaching of Fe noted
Fe <sub>2</sub> TiO <sub>3</sub>	2.2	1.5	15	Stable
Fe <sub>2</sub> O <sub>3</sub>	2.2	0.7	40	Stable at pH > 4.5
Cu <sub>2</sub> O	2.2	—	—	Corrodes
CuO	1.7	1.0	—	Corrodes
WO <sub>3</sub>	2.7	0.5	100	Stable in acid
ZnO	3.2	0	—	Corrodes
SnO <sub>2</sub>	3.5	0.5	100	Stable
SiC	3.0	-1.3	—	Corrodes
V <sub>2</sub> O <sub>5</sub>	2.75	1.2	—	Corrodes
Si	1.1	-0.7	—	Corrodes
InP	1.3	-0.2	—	Corrodes
GaAs	1.4	-0.5	—	Corrodes
GaP	2.2	-1.0	—	p-type stable
CdS	2.4	-0.5	—	Corrodes
CdSe	1.7	-0.2	—	Corrodes
ZrO <sub>2</sub>	5.0	-1.0	—	Stable
Cr <sub>2</sub> O <sub>3</sub>	1.4	—	—	Corrodes, poor response
CoO	0.5	0.8	—	Corrodes, poor response

\* Abstracted from Table 1 in Ref. 9.

#### C. Non-aqueous solvent system :

The corrosion problems exhibited by so many of the small band gap semiconductors will be relieved in a non-aqueous electrolyte. For example, Kohl and Bard<sup>18</sup> report the photocorrosion of the semiconductors (n- and p-GaAs) electrodes in acetonitrile solutions is suppressed and does not occur until potentials were well positive of the flat band potential.

#### IV. Future Research of Photocorrosion

In the photoelectrochemistry, there are two challenging problems facing us, namely, (i) efficient and readily available electrode materials<sup>19</sup> and (ii) photocorrosion. For the long range research on photocorrosion the following recommendations may be suggested.

A. For better theoretical understanding of the photocorrosion of materials, particularly semiconductors, to study the electrode surfaces with modern surface techniques<sup>20,21</sup>.

(a) Auger electron spectroscopy (AES) has, since its inception as a commercially available surface chemical analytical technique, enjoyed a strong interaction with the field of material science. Corrosion is primarily concerned with

the interaction of materials with their environments. AES is sensitive to all elements except H and He, and the relative sensitivities for most elements varies by only about one order of magnitude. Each element has relatively few strong Auger peaks, which limits peak overlap, and most elements do not show strong peak energy shifts, making elemental identification easy.

(b) X-ray photoelectron spectroscopy (XPS, ESCA) offers the researcher a unique capability for detecting chemical species in thin (1-2 nm) surface films, with only minor perturbation from the exciting radiation. This technique is important for the identification of corrosion imitators and for determining the nature of the first films formed in corrosion process. XPS is useful for (i) oxide-metal differentiation, (ii) differentiation of oxidation states, and (iii) identifying other chemical changes. It can provide more structural information as more is learned about its spectra of corrosion elements. The use of synergistic analytical technique such as scanning Auger microscopy, secondary ion mass spectroscopy, and ion micro probe, will provide some measure of spatial definition when combined with XPS.

B. To continue the current efforts to find ways to stabilize the electrodes such as coatings, doping, and combinations of electrodes<sup>40,41</sup>. It seems that the glow discharge polymer coating deserves more research efforts<sup>42</sup>.

C. To stabilize the electrode surfaces with ion implantation. The ion implantation in semiconductors has been known for sometime<sup>43</sup>; however, little is known about its study in photocorrosion

#### Acknowledgement

This work was supported by the Gas Research Institute and the Research Administration, University of Missouri-Kansas City.

#### References

1. J. O'M. BOCKRIS and D. M. DRAZIC, "Electrochemical Science", Barnes & Noble Books, New York, 1972, p. 239.
2. R. WILLIAMS, *J. Chem. Phys.*, 1969, 32.
3. H. GERISCHER and W. MINDT, *Electrochim. Acta*, 1968, 13, 1329.
4. H. P. MARUSDA and A. K. GHOSH, *Sol. Energy*, 1978, 20, 443.
5. A. D. FRANKLIN, NBS. Spec. Publ., 1976, 455, U. S. National Bureau of Standards.
6. J. D. E. MCINTYRE, S. SRINIVASAN and F. G. WILL, "Proc. of Symp. on Electrode Materials and Processes for Energy Conversion and Storage", *The Electrochem. Soc.*, 1977, 71-6, 1-1033.
7. A. FUJISHIMA and K. HONDA, *Nature*, 1972, 238, 37.
8. E. YEAGER, *Surf. Sci.*, 1980, 101, 1.
9. L. A. HARRIS, D. R. CROSS and M. E. GERSTNER *J. Electrochem. Soc.*, 1977, 124, 839.
10. L. A. HARRIS and R. H. WILSON, *J. Electrochem. Soc.*, 1976, 123, 1010.
11. A. B. BACARELY, J. M. BOLTS, P. G. CUMMINS and M. S. WRIGHTON, *Appl. Phys. Lett.*, 1977, 31, 568.

12. M. S. WRIGHTON, A. B. ELLIS, P. T. WOLCZANSKI, D. I. MORSE, H. B. ABRAMHAMSON and D. S. GINLEY, *J. Amer. Chem. Soc.*, 1976 **98**, 2774
13. K. OHASHI, J. McCANN and J. O'M. BOCKRIS, *Nature*, 1977, **266**, 610.
14. D. S. GINLEY and R. J. BAUGHMAN, *Mat. Res. Bull.*, 1976, **11**, 1539
15. R. D. NASBY and R. K. QUINN, *Mat. Res. Bull.*, 1976, **11**, 985.
16. K. L. HARDEF and A. J. BARD, *J. Electrochem. Soc.*, 1976, **123**, 1024.
17. K. RAJESHWAR, P. SINGH and J. DuBOW, *Electrochim. Acta*, 1978, **23**, 1117
18. L-S. R. YEH and N. HACKERMAN, *J. Electrochem. Soc.*, 1977, **124**, 833.
19. H. KIM and H. A. LAITINEN, *J. Electrochem. Soc.*, 1975, **122**, 53.
20. M. S. WRIGHTON, D. L. MORSE, A. B. ELLIS, D. S. GINLEY and H. B. ANDERSON, *J. Amer. Chem. Soc.*, 1976, **98**, 44.
21. H. GERISCHER, *J. Electroanal. Chem.*, 1977, **82**, 133.
22. R. MEMMING and G. SCHWAND, *Electrochim. Acta*, 1968, **13**, 1299.
23. R. L. MEEK and N. E. SCHMUCKER, *J. Electrochem. Soc.*, 1972, **119**, 1148.
24. A. YAMAMOTO and S. YANO, *J. Electrochem. Soc.*, 1975, **122**, 260
25. H. GERSCHER, *J. Electroanal. Chem.*, 1975, **58**, 263
26. K. OHASHI, K. UOSAKI and J. O'M. BOCKRIS, *Int. J. Energy Res.*, 1977, **1**, 25
27. A. HELLER, B. MILLER, S. S. CHU and Y. T. LEE, *J. Amer. Chem. Soc.*, 1979, **101**, 7633.
28. M. J. MADON, K. W. FRESF, Jr and S. R. MORRISON, *J. Electrochem. Soc.*, 1980, **127**, 87.
29. S. GOURGUAD and D. ELLIOTT, *J. Electrochem. Soc.*, 1977, **124**, 102
30. Y. NAKATO, T. OHNISHI and H. TSUBOMURA, *Chem. Lett.*, 1975, 883.
31. M. TOMKIEWICZ and J. M. WOODALL, *J. Electrochem. Soc.*, 1977, **124**, 1436.
32. P. A. KOHL, S. N. FRANK and A. J. BARD, *J. Electrochem. Soc.*, 1977, **124**, 225.
33. J. O'M. BOCKRIS and K. UOSAKI, *Energy*, 1976, **1**, 95.
34. A. K. GHOSH and H. P. MARUSKA, Final Progress Report NSF Grant ERP 75-13901 (June 1976), See also Ref (17)
35. J. W. SCHULTZ and M. A. HABIB, *J. Appl. Electrochem.*, 1979, **9**, 255.
36. K. DOBLHOFFER, *Electrochim. Acta*, 1980, **25**, 871.
37. P. A. KOHL and A. J. BOND, *J. Electrochem. Soc.*, 1979, **126**, 59
38. A. J. NOZIK, *J. Crystal Growth*, 1977, **39**, 200.
39. H. GERISCHER, Proc. of Symp. on Electrode Materials and Processes for Energy Conversion and Storage, *The Electrochem. Soc.*, 1977, **77-6**, 8-29.
40. A. HELLER, *Accs. Chem. Res.*, 1981, **14**, 154
41. A. HELLER and R. G. VADINSKY, *Phys. Rev. Lett.*, 1981, **46**, 1153
42. S. NAMBA, Proc. of the U. S.-Japan Seminar on Ion Implantation in Semiconductors, Japan Soc. for the promotion of Sci., 1972.
43. R. WILLIAMS, *J. Vac. Soc. Technol.*, 1975, **13**, 12.
44. R. WILLIAMS, *Wu Li (Physics in Chinese)*, 1981, **10**, 650.

# Spectrophotometric Study of the Reaction of Chromium(VI) with Fluphenazine Hydrochloride

H. SANKE GOWDA and J. B. RAJ

Department of Post-graduate Studies and Research in Chemistry,  
Manasagangotri, Mysore-570 006

Fluphenazine hydrochloride forms a red coloured species with chromium(VI) instantaneously at room temperature in 2.5 M phosphoric acid medium. A 29-fold molar excess of the reagent is necessary for maximum development of colour intensity. The red coloured species exhibits maximum absorbance at 500 nm with molar absorptivity of  $2.616 \times 10^4$  litre mole<sup>-1</sup> cm<sup>-1</sup>. Beer's law is valid over the concentration range of 0.05-1.85 ppm of chromium(VI). The method offers the advantages of simplicity, rapidity and sensitivity without the need for heating or extraction.

**T**HE colour reaction between chromium(VI) and fluphenazine hydrochloride (FPH) has not been previously studied. We have now studied this coloured reaction and developed FPH as a sensitive reagent for the spectrophotometric determination of chromium(VI).

## Experimental

**Apparatus:** Absorbance measurements were recorded with a Beckman DB spectrophotometer with matched 1 cm silica cells.

**Reagents:** *Chromium (VI) solution:* A stock solution of chromium(VI) was prepared from AnalaR potassium dichromate crystals in double distilled water to give a standard solution of  $1 \times 10^{-3}$  M. The stock solution was further diluted as needed.

**FPH solution:** A 0.5% (w/v) aqueous solution of FPH was prepared and stored in an amber bottle in a refrigerator.

**Diverse ions:** Solutions of diverse ions of suitable concentrations were prepared using analytical grade reagents.

**Procedure:** An aliquot of the stock solution containing 0.05-1.85 ppm of chromium(VI), 10 ml of 10 M phosphoric acid and 1 ml of 0.5% FPH solution were diluted to 25 ml in a volumetric flask with double distilled water, mixed well and the absorbance measured at 500 nm against a corresponding reagent blank. The amount of chromium in the sample solution was deduced from a standard calibration curve.

## Results and Discussion

FPH reacts with chromium(VI) to form a red coloured species in hydrochloric, sulphuric or phosphoric acid medium at room temperature. The study of the reaction in hydrochloric or sulphuric acid medium is not recommended because the reaction is less stable and many foreign ions interfere in the determination of chromium(VI). Hence, phosphoric acid medium has been selected.

The maximum colour intensity is observed in 2-5.5 M phosphoric acid. Below and above this acid range the absorbance is not maximum. A 29-fold molar excess of the reagent is necessary for full development of colour intensity. The red coloured species, which is thought to be a radical cation<sup>1,2</sup>, exhibits absorption maximum at 498-502 nm at which the reagent does not absorb. The absorbance readings remain constant for 45 min and are insensitive to temperature in the range 5-45°. The order of addition of the reagents is not critical.

Beer's law is valid over the concentration range of 0.05-1.85 ppm of chromium(VI). The optimum concentration range evaluated by Ringbom's method<sup>3,4</sup> is 0.18-1.55 ppm. The sensitivity of the reaction is 1.9 ng cm<sup>-2</sup> and the molar absorptivity is  $2.616 \times 10^4$  litre mole<sup>-1</sup> cm<sup>-1</sup>.

TABLE 1—EFFECT OF DIVERSE IONS  
Amount of chromium taken = 1 ppm

Ion added	Tolerance limit (ppm)	Ion added	Tolerance limit (ppm)
Fe(III)	3000	Cd(II)	2500
Co(II)	150	V(V)	0.3
Ni(II)	500	Fluoride	1100
Cu(II)	1700	Chloride	2000
Mn(II)	1500	Bromide	1300
Mo(VI)	300	Iodide	0.2
W(VI)	150	Nitrate	2000
U(VI)	200	Sulphate	1800
Pb(II)	120	Nitrite	0.3
Ca(II)	1200	Acetate	1300
Al(III)	3000	Tartrate	500
Ba(III)	5000	Oxalate	1000
Zn(II)	2000	Citrate	2200
Sr(III)	5500	EDTA	8000
Zr(IV)	150		

**Effect of diverse ions:** In order to assess the possible analytical applications of the method, the effect of some ions which often accompany chromium was studied by adding different amounts

of the diverse ions to 1 ppm of chromium(VI) which gave less than 2% error in absorbance readings (Table 1). The major advantage of this method is that FPH can be used as a selective reagent for the determination of chromium in presence of a large amount of iron(III).

*Determination of chromium in chromium steels:*  
Simulated samples containing chromium corresponding to chromal steel, AISI-A 4320 and AISI-

ES 2100 were prepared and the chromium content was determined. There is a good agreement between the amounts of chromium taken and found.

#### References

1. P. C. DWIVEDI, K. GURUDATH RAO, S. N. BHAT and C. N. R. RAO, *Spectrochim Acta*, 1975, 31A, 129.
2. V. MARIA STAN, DORNEANU and G. H. GHIMICESCU, *Talanta*, 1977, 24, 140.
3. G. H. AYRES, *Analyt Chem.*, 1949, 21, 652.
4. A. RINGBOM, *Z. analyt Chem.*, 1939, 115, 332.

# Spectral Studies of Polymeric Metal Complexes with Schiff Bases of Terephthalaldehyde and Hydrazides

P. L. MAURYA\*, C. P. DUBE and B. V. AGARWALA\*

Chemical Laboratories, University of Allahabad, Allahabad-211 002

Polymerization reactions involving the formation of Schiff base metal complexes by condensation have been described. The Schiff bases formed are terephthalaldehyde bis-(benzoic acid hydrazone) (TBH) and terephthalaldehyde bis-(nicotinic acid hydrazone) (TNH). The IR spectra indicate that chelation occurs through their enolic form. Both hydrazones act as tetradentate ligands and a polymeric structure is proposed for 1:1 complexes. All complexes except Zn(II) are paramagnetic which along with calculated values of ligand field parameters,  $\nu_2/\nu_1$ ,  $10 Dq$ ,  $B'$ ,  $\beta$  and  $\beta''$ , obtained from electronic spectral data support an octahedral geometry.

METAL complexes<sup>1-5</sup> of Schiff bases of hydrazides with aldehydes and ketones have been of special interest in recent years, particularly in the context of therapeutic value of hydrazide and hydrazone. The coordination occurs both in keto<sup>2-5</sup> as well as enolic form<sup>2,4</sup> of the ligands with the metal ions. Larsen *et al.*<sup>6</sup> have made an extensive study on molecular and electronic structure in metal complexes with Schiff bases of  $\beta$ -diketones and diamines by absorption and circular dichroism spectra. The results have been interpreted by means of molecular exciton theory to rationalize the observations on the dimeric Schiff bases. Formation of oxygen bridged bi- and trinuclear complexes have also been described in a review by Sinn and Harris<sup>7</sup>.

The present paper describes the synthesis and characterisation of Schiff bases viz., terephthalaldehyde bis-(benzoic acid hydrazone) (TBH) and terephthalaldehyde bis-(nicotinic acid hydrazone) (TNH) and their complexes with Mn(II), Co(II), Ni(II), Cu(II) and Zn(II). The results are discussed with the aid of infrared and electronic spectra and magnetic and thermal data. These complexes are similar to several coordination polymers of Schiff bases with other terephthalaldehyde derivatives, which had been initiated by Prof. A. K. De<sup>10-12</sup>.

## Experimental

### Materials :

Terephthalaldehyde (Koch Light), and nicotinic acid hydrazide and benzoic acid hydrazide were used to synthesize the Schiff bases.  $Mn(CH_3COO)_2 \cdot 4H_2O$ ,  $Cu(CH_3COO)_2 \cdot H_2O$ ,  $Zn(CH_3COO)_2 \cdot 2H_2O$  (all BDH, AnalaR),  $Co(CH_3COO)_2 \cdot 4H_2O$  (Srirabhai M.),  $Ni(CH_3COO)_2 \cdot 4H_2O$  (Veb Laborchemie) were used and the solvents were of reagent grade.

**Preparation of Schiff bases :** Benzoic acid hydrazide (13.6 g ; 0.1 mol) or nicotinic acid hydrazide (13.7 g ; 0.1 mol) and terephthalaldehyde (6.7 g ; 0.05 mol) dissolved in ethanol were mixed and refluxed on a water bath for 2 hr. The precipi-

tated white crystalline solids were filtered, washed successively with water, ethanol, diethylether, and dried (yield ca 80%). The Schiff bases obtained are insoluble in water, ethanol, chloroform, benzene, acetone, toluene, xylene, but soluble in DMF and DMSO. Found : C, 72.3 ; H, 4.82 ; N, 16.05. Calcd. for  $C_{22}H_{16}N_4O_2$  ; C, 71.35 ; H, 4.86 ; N, 15.14% and C, 64.32 ; H, 4.45 ; N, 22.94. Calcd. for  $C_{20}H_{14}N_4O_2$  ; C, 64.51 ; H, 4.30 ; N, 22.58%.

**Synthesis of Schiff base-metal complexes :** TBH or TNH (0.1 mol) dissolved in DMF was gradually added to a solution of the metal salt (0.01 mol) in DMF- $H_2O$  media. The mixture was refluxed at ca 120° for 2 to 3 hr as necessary and left overnight. The precipitated mass was filtered, washed with DMF, ethanol and ether and dried (yield 80-85%).

The complexes are air stable, powdery and insoluble in water and common organic solvents viz., ethanol, acetone, benzene, chloroform, nitrobenzene, THF, DMF and DMSO.

**Analytical data :** Microanalytical methods were used for the determination of carbon, hydrogen and nitrogen. The complexes were decomposed by fuming  $HNO_3$  and the metal contents estimated titrimetrically against EDTA.

**Magnetic susceptibility :** The magnetic susceptibility of the complexes were determined at 298 K by Faraday's method.

**Spectral studies :** IR spectra were recorded on Beckman Infrared spectrophotometer using KBr pellets in the range of 4000-400  $cm^{-1}$ . DRS were obtained in the range 200-1000 nm using Carl-Zeiss spectrophotometer VSU-2.

**Thermogravimetry :** TG was done by heating the complexes upto 800° at a rate of 10°  $min^{-1}$  in air.

## Results and Discussion

The analytical data of the complexes (Table I) agree with the general formula  $(ML_2H_2O)_n$  where

\*Present address : Leningrad, U.S.S.R.

M=Mn(II), Co(II), Ni(II), Cu(II), or Zn(II),  
L=C<sub>8</sub>H<sub>8</sub>N<sub>2</sub>O<sub>2</sub> or C<sub>8</sub>H<sub>8</sub>N<sub>2</sub>O<sub>4</sub>.

TABLE 1—COLOUR AND ANALYTICAL DATA OF THE COMPLEXES

Complex	Colour	Analyses %			
		Found (Calcd.)			
		M	C	H	N
MnL <sub>2</sub> H <sub>2</sub> O	Brown	11.64 (11.97)	56.92 (57.52)	4.32 (4.35)	13.04 (12.20)
CoL <sub>2</sub> H <sub>2</sub> O	Reddish brown	12.26 (12.73)	57.42 (57.02)	4.30 (4.32)	12.82 (12.09)
NiL <sub>2</sub> H <sub>2</sub> O	Greenish yellow	12.16 (12.68)	56.96 (57.05)	4.42 (4.32)	12.69 (12.10)
CuL <sub>2</sub> H <sub>2</sub> O	Brown	13.05 (13.58)	56.92 (56.46)	4.35 (4.27)	12.02 (11.97)
ZnL <sub>2</sub> H <sub>2</sub> O	Yellow	13.21 (13.92)	56.52 (56.24)	4.48 (4.26)	12.43 (11.93)
MnL'.2H <sub>2</sub> O	Brown	11.54 (11.91)	52.84 (52.02)	3.86 (3.90)	18.94 (18.22)
CoL'.2H <sub>2</sub> O	Brown	12.42 (12.67)	51.48 (51.61)	3.92 (3.87)	18.76 (18.06)
NiL'.2H <sub>2</sub> O	Yellow	12.16 (12.63)	52.04 (51.64)	3.82 (3.87)	18.99 (18.06)
CuL'.2H <sub>2</sub> O	Brown	13.16 (13.53)	51.41 (51.11)	3.94 (3.83)	17.81 (17.88)
ZnL'.2H <sub>2</sub> O	Yellow	13.34 (13.86)	51.02 (50.91)	3.89 (3.81)	17.95 (17.82)

L=C<sub>8</sub>H<sub>8</sub>N<sub>2</sub>O<sub>2</sub>, L'=C<sub>8</sub>H<sub>8</sub>N<sub>2</sub>O<sub>4</sub>

characteristic bands near 3250, 1650, 1300, 750 and 670 assigned to N-H stretching, C=O stretching, N-H in-plane bending, C=O in-plane deformation and C=O out-of-plane deformation, respectively<sup>10</sup>. The bands near 1630 and 1600 are assigned to C=N and C=C stretching, respectively. The bands at 1485 and 1050 in TNH are due to pyridine ring

TABLE 3B—IR SPECTRA\* OF TNH AND ITS COMPLEXES

TNH	Mn(II)	Co(II)	Ni(II)	Cu(II)	Zn(II)	Assignment
...	3500	3505	3510	3500	3510	ν OH(H <sub>2</sub> O)
3250	...	...	...	...	...	ν NH
1655	...	...	...	...	...	ν C=O
1630	1620	1620	1615	1615	1510	ν C=N
1600	1600	1610	1600	1610	1610	ν C=C and ν H <sub>2</sub> O
...	1560	1565	1560	1560	1565	ν C=N-N=C
1485	1485	1480	1485	1485	1485	ν N=N-(pyridine)
1305	...	...	...	...	...	δ NH
...	1290	1285	1285	1290	1290	ν C-O
1050	1050	1050	1045	1050	1050	ν N=N-(pyridine)
910	920	925	925	930	930	ν N-N
750	...	...	...	...	...	C=O in-plane
670	...	...	...	...	...	C=O out-of-plane deformation
...	525	520	515	520	520	ν M-O
...	450	455	460	450	450	ν M-N

\* Wave numbers are in cm<sup>-1</sup>.

TABLE 2—MAGNETIC MOMENT, ELECTRONIC SPECTRAL DATA AND LIGAND FIELD PARAMETERS OF TBH AND TNH\* COMPLEXES

Complex with	Magnetic moment	Electronic spectra		ν <sub>1</sub> /ν <sub>2</sub>	10 Dq	B'	β	β°	Geometry
		Band cm <sup>-1</sup>	Assignment						
Mn(II)	5.92 (5.80)	17500	*A <sub>1g</sub> → T <sub>1g</sub> (G)	...	...	...	...	...	Octahedral
		21240	→ T <sub>2g</sub> (G)						
		23450	→ E <sub>g</sub> (G)						
		26520	→ T <sub>2g</sub> (D)						
		28750	→ E <sub>g</sub> (D)						
Co(II)	4.89 (4.91)	10200	*T <sub>1g</sub> → *T <sub>1g</sub> (F)	2.1 (2.1)	11150 (11450)	893 (893)	0.919 (0.920)	800 (8.00)	Octahedral
		21350	→ *A <sub>1g</sub> (F)						
		22300	→ *T <sub>1g</sub> (F)						
		22300	→ *T <sub>2g</sub> (F)						
Ni(II)	2.96 (3.02)	10150	*A <sub>1g</sub> → *T <sub>1g</sub> (F)	1.5 (1.5)	10150 (10200)	922 (911)	0.873 (0.863)	12.68 (13.65)	Octahedral
		15200	→ *T <sub>1g</sub> (F)						
		27750	→ *T <sub>2g</sub> (F)						
		27750	→ *T <sub>2g</sub> (P)						
Cu(II)	1.95 (1.98)	10100	*B <sub>1g</sub> → *A <sub>1g</sub>	...	10100 (10000)	...	...	...	Octahedral
		11150	→ *B <sub>2g</sub>						
		15200	→ *E <sub>g</sub>						

\* Values within the parentheses are for TNH complexes.


TABLE 3A—IR SPECTRA\* OF TBH AND ITS COMPLEXES

TBH	Mn(II)	Co(II)	Ni(II)	Cu(II)	Zn(II)	Assignment
...	3510	3500	3510	3510	3500	ν OH(H <sub>2</sub> O)
3250	...	...	...	...	...	ν NH
1650	...	...	...	...	...	ν C=O
1630	1615	1620	1620	1620	1620	ν C=N
1600	1610	1600	1600	1610	1610	ν (H <sub>2</sub> O) + ν C=C
...	1570	1560	1560	1560	1565	ν C=N-N=C
1300	...	...	...	...	...	δ NH
...	1290	1290	1285	1290	1290	ν C-O
915	935	935	940	940	935	ν N-N
750	...	...	...	...	...	C=O in-plane
670	...	...	...	...	...	C=O out-of-plane deformation
...	520	520	510	510	520	ν M-O
...	450	460	460	450	455	ν M-N


\* Wave numbers are in cm<sup>-1</sup>.

The ir spectra (Tables 3A and 3B, wave numbers expressed in cm<sup>-1</sup>) of TBH and TNH show chara-

nitrogen. All these bands in the spectra of TBH and TNH indicate that these are present in keto form, and the proposed structures I and II for the Schiff bases are as follows :



I TBH




II TNH

However, the chelation occurs through enolic form which finds support from the fact that (i) C=O stretching bands disappear and (ii) new bands

appear near 1570-50 and 1290-85 which may be assigned to C=N-N=C stretching and C-O stretching at C-O-M site, respectively. The involvement of azomethine nitrogens for coordination is indicated by (i) a negative shift in the stretching frequency of C=N group and (ii) a positive shift in the stretching vibrations of N-N group<sup>14</sup> in the spectra of the complexes. Coordination through oxygen and nitrogen are further supported by the occurrence of new bands at ~520-510 and ~460-450 which may be assigned to M-O and M-N stretching frequencies, respectively. The ring nitrogens in the case of TNH do not take part in coordination as the bands observed at 1485 and 1050 due to >N=N-(pyridine) remain unchanged on chelation.

Thus, both the Schiff bases act as tetradentate ligands as each metal ion is coordinated with two nitrogen and two oxygen atoms. Coordination polymerization takes place since all the four donors in one ligand molecule can not coordinate to the same metal ion due to steric factors. Two water molecules are attached to satisfy the coordination number. The presence of water molecule is indicated by the observance of strong bands at 3500 and 1600 in the ir spectra which may be assigned to  $\nu_{OH}$  and  $\delta H_2O$ , respectively. The percentage weight loss observed between 100-200° by TG analysis correspond to the elimination of 2 H<sub>2</sub>O, thus supporting the above assumption.



III. TBH complexes

Mn(II), Co(II), Ni(II) and Cu(II) complexes are paramagnetic and the magnetic moment values at 298 K are found to be : 5.92, 4.89, 2.96, 1.95 and 5.90, 4.91, 3.02 and 1.98 B.M. for the two series of complexes, respectively. Various ligand field parameters viz.,  $\nu_2/\nu_1$ , 10 Dq, B',  $\beta$  and  $\beta^*$  have

been calculated (Table 2) from electronic spectral data. Both these data show octahedral geometry of the complexes<sup>16-20</sup>. The geometry, composition, insolubility and high thermal stability of the complexes indicate their polymeric nature<sup>1,2,9,21</sup>.

#### Acknowledgement

The authors thank the Council of Scientific and Industrial Research, New Delhi for awarding a Post-doctoral Fellowship to (P.L.M)

#### References

1. I. I. GEORGESCU, D. CIOMARTAN, G. TEODORESCU, M. HLEVCA and M. ZAHARESU, *Riv. Roum. Chim.*, 1973, 18, 1195.
2. A. P. NARIMANIDZE, A. M. MAMULASHVILI and T. K. DZHASHASHVILI, *Tr. Gruz. Politekh. Inst.*, 1975, 4, 34.
3. K. K. NARANG and A. AGARWAL, *Indian J. Chem.*, 1975, 13, 1072.
4. R. C. AGGARWAL, L. PRASAD and N. K. SINGH, *Indian J. Chem.*, 1976, 14A, 181.
5. R. C. AGGARWAL and T. R. RAO, *Trans. Metal Chem.*, 1977, 2, 201; *Curr. Sci.*, 1977, 46, 625.
6. K. K. KHAKIMOV, A. A. SHABILALOV and M. A. AZIZOV, *Russ. J. Inorg. Chem.*, 1970, 15, 1022.
7. E. LARSEN, *Acta Chem. Scand.*, 1969, 23, 2158.
8. E. LARSEN and K. SCHAUMBERG, *Acta Chem. Scand.*, 1971, 25, 962.
9. E. SINN and C. M. HARRIS, *Coord. Chem. Revs.*, 1969, 4, 391.
10. P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *Polymer Bull.*, 1979, 1, 631; *J. Indian Chem. Soc.*, 1980, 57, 275.
11. B. SINGH, V. BANERJEE, B. V. AGARWALA and A. K. DEY, *J. Indian Chem. Soc.*, 1980, 57, 365.
12. B. SINGH, P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *J. Indian Chem. Soc.*, 1981, 58, 541.
13. T. MIYAZAWA, T. SHIMANOCHI and S. MIZUSHIMA, *J. Chem. Phys.*, 1956, 24, 408; 1958, 29, 611.
14. P. A. GIURE and I. D. LIN, *J. Chem. Phys.*, 1952, 20, 136.
15. K. NAKAMOTO, "Infrared and Raman Spectra of Coordination Compounds", Wiley, New York, 1978.
16. J. W. STAUT, *J. Chem. Phys.*, 1959, 31, 709.
17. A. B. P. LEVER, "Inorganic Electronic Spectroscopy" Elsevier, Amsterdam, 1968.
18. C. J. BALLHAUSEN, "Introduction to Ligand Field Theory", McGraw-Hill, New York, 1962.
19. R. S. DRAGO, "Physical Methods in Inorganic Chemistry", Reinhold, New York, 1965.
20. L. SACCONI, *Transition Metal Chemistry*, 1968, 4, 199.
21. P. L. MAURYA, B. V. AGARWALA and A. K. DEY, *Polymer Bull.*, 1980, 3, 253; *Makromol. Chem.*, 1982, 183, 511.



## Peptide Models for the Metal-Binding Sites of Proteins and Enzymes

BIBUDHENDRA SARKAR

The Research Institute of the Hospital for Sick Children, Toronto, M5G 1X8  
and  
The Department of Biochemistry, University of Toronto, Toronto, M5S 1A8,  
Ontario, Canada

A series of peptide models were utilized to probe the metal-binding sites of proteins and enzymes. Studies with three peptide analogues, GlyGly-L-His, GlyGly-L-His-NHCH<sub>3</sub>, and L-Asp-L-Ala-L-His-NHCH<sub>3</sub>, representing the Cu(II)-transport site of human serum albumin revealed that the Cu(II)-binding site is located at the NH<sub>2</sub>-terminal of the protein involving the  $\alpha$ -NH<sub>2</sub>, imidazole, and two deprotonated peptide nitrogens and the COO<sup>-</sup> of the Asp residue forming a pentacoordinated structure. Similarly, the investigation of the Ni(II)-transport site of human serum albumin using peptide models revealed the structure of the Ni(II)-binding site of albumin. A cyclic octapeptide, cyclo(Gly-L-Glu-Gly-Gly-L-His-Gly-L-His-Gly), was designed to mimic the Zn(II)-binding site of carboxypeptidase. Structural studies with the cyclic octapeptide showed that the Zn(II) binding took place with the imidazoles of the two histidine residues and the carboxyl side chain of the glutamic acid residue, a finding similar to what is known about the Zn(II)-binding sites of carboxypeptidase. Furthermore, a cyclic heptapeptide, cyclo(Gly-L-His-L-Gly-L-His-Gly-L-His-Gly), was designed to mimic the Zn(II)-binding site of carbonic anhydrase. Detailed studies with the cyclic heptapeptide showed that Zn(II) bound to this peptide involving imidazoles from all the three histidine residues as is known to be the case for the Zn(II)-binding site of carbonic anhydrase. Considerations for successful design of peptide models as well as its limitations are discussed.

**I**MPORTANT advances have been made in recent years in the investigations of metal protein interactions in which the peptide models have played a very significant role. Small peptide molecules designed to mimic the metal binding sites of proteins and enzymes can provide valuable information which is otherwise difficult to obtain from the studies of the native molecules. Models for metal binding sites which are located on a short polypeptide chain may be designed using a linear peptide molecule with suitable side chains positioned in strategic locations. However, models to mimic the metal-binding sites originating from different parts of the polypeptide chain such as those found in most metalloenzymes and metalloproteins are difficult to design. In this case, a linear peptide may not be suitable. Cyclic peptides with side chains suitably positioned for the purpose of metal binding may provide both the rigidity and the ligand binding geometry of the native proteins and enzymes.

We have designed peptide models mimicking both types of metal-binding sites discussed above. In this article, I shall discuss some of our results with Cu(II) and Ni(II)-transport sites of human serum albumin and the Zn(II)-binding sites of two metalloenzymes: carboxypeptidase and carbonic anhydrase.

*Copper(II)-transport site of human serum albumin:*

Copper(II) bound to albumin is considered to be the transport form of Cu(II) in blood. It has

long been known that bovine serum albumin has one strong binding site for Cu(II)<sup>1,2</sup>. The stoichiometry of Cu(II) binding to HSA\* was established by us later<sup>3</sup>. The involvement of  $\alpha$ -NH<sub>2</sub> at the strong Cu(II)-binding site was shown by blocking the reaction of the  $\alpha$ -NH<sub>2</sub> group with 2,4-dinitrofluorobenzene by Cu(II)<sup>4</sup>. Titrimetric studies indicated that one of the coordinating groups at the binding site had a  $pK_a$  near 8<sup>5</sup>. The 525 nm absorption band of the 1:1 Cu(II)-albumin complex and the displacement of two protons by the first Cu(II) at pH 9 suggested that two peptide bond nitrogens and a possible fourth coordinating atom such as an imidazole nitrogen participated along with the  $\alpha$ -NH<sub>2</sub> at the strong site<sup>6</sup>. Subsequently, we found that dog serum albumin failed to exhibit the characteristics of a specific first binding site for Cu(II)<sup>7</sup>. Amino acid sequence analysis of the NH<sub>2</sub>-terminal region of DSA showed that the third residue histidine, critical to the binding of Cu(II), has been replaced with a tyrosine residue<sup>8</sup>. This finding confirmed the involvement of the imidazole nitrogen in the coordination of Cu(II) in the case of HSA and BSA.

On the basis of the proposed Cu(II)-binding site of albumin involving the  $\alpha$ -amino nitrogen, two intervening peptide nitrogens and the imidazole nitrogen of the histidine residue in the third position, three peptide analogues were designed and synthesized. The peptide glycylglycyl-L-histidine was synthesized by active ester method<sup>9,10</sup>. Another

\*Abbreviations used: HSA, human serum albumin; BSA, bovine serum albumin; DSA, dog serum albumin; GGH, glycylglycyl-L-histidine; GGHNMA, glycylglycyl-L-histidine-N-methyl amide; AAHNMA, L-aspartyl-L-alanyl-L-histidine-N-methyl amide.

peptide analogue was prepared by derivatizing the carboxyl group to N-methyl amide to more closely resemble the protein molecule<sup>11</sup>. Finally, the native sequence peptide, L-aspartyl-L-alanyl-L-histidine-N-methyl amide, representing the Cu(II) transport site of HSA, was synthesized employing the N-hydroxysuccinimide ester method<sup>12</sup>.

TABLE 1—COMPARISON OF LOG STABILITY CONSTANTS (LOG  $\beta_{pqr}$ , LOG  $\beta'_{pqr}$  AND LOG  $\beta''_{pqr}$ ) OF THE COMPLEX SPECIES  $M_pH_qA_r$  [ $M$ —Cu(II),  $A$ —GLYGLY-L-HIS-N-METHYLAMIDE,  $A'$ —GLYGLY-L-HIS,  $A''$ —L-ASP-L-ALA-L-HIS-N-METHYLAMIDE] IN 0.15 M NaCl AT 25°

p	q	r	log $\beta_{pqr}$ ( $M_pH_qA_r$ )	log $\beta'_{pqr}$ ( $M_pH_qA'$ )	log $\beta''_{pqr}$ ( $M_pH_qA''$ )
0	3	1	—	17.50	17.267
0	2	1	14.47	14.78	14.286
0	1	1	8.00	8.04	7.731
1	-2	1	-0.479	-1.99	-0.55

TABLE 2—SPECTRAL PROPERTIES OF THE Cu(II)-TRANSPORT SITE OF HUMAN SERUM ALBUMIN, Cu(II)-COMPLEXES OF THE NATIVE SEQUENCE PEPTIDE, AND THE DESIGNED PEPTIDES

Cu(II) complex	$\lambda_{max}$ (nm)	$\epsilon_{max}$ (liter mol <sup>-1</sup> cm <sup>-1</sup> )
Human serum albumin-Cu(II)	525	101
GlyGly-L-His-Cu(II) (MH <sub>2</sub> A)	525	103
GlyGly-L-His-NHMe-Cu(II) (MH <sub>2</sub> A)	525	103
L-Asp-L-Ala-L-His-NHMe-Cu(II) (MH <sub>2</sub> A)	525	103

TABLE 3—PARAMAGNETIC RESONANCE PARAMETERS OF Cu(II) ION FOR ITS FIRST COMPLEX WITH HUMAN SERUM ALBUMIN, GLY-GLY-L-HIS-NHCH<sub>3</sub>, AND L-ASP-L-ALA-L-HIS-NHCH<sub>3</sub> AT 77K

Ligand compound	pH	$g_{  }$	$g_{\perp}$	$A_{  }$ (gauss)	$A_{\perp}$ (mk)
Human serum albumin	6.5	2.166	2.051	214	21.6
Human serum albumin	9.2	2.169	2.049	214	21.6
Gly-Gly-L-His-NHCH <sub>3</sub>	6.4	2.17	2.051	211	21.3
Gly-Gly-L-His-NHCH <sub>3</sub>	11.2	2.163	2.051	209	21.1
L-Asp-L-Ala-L-His-NHCH <sub>3</sub>	6.5	2.167	2.050	211	21.4
L-Asp-L-Ala-L-His-NHCH <sub>3</sub>	11.1	2.166	2.049	209	21.1

$$^a A \text{ (mk)} = 0.046686 g A \text{ (gauss)}$$

The Cu(II) complex equilibria in the systems containing Cu(II) and the peptides were studied by analytical potentiometry<sup>13,14</sup>. The species and their stability constants are presented in Table 1. In all the systems studied, there is one major species (MH<sub>2</sub>A) existing in physiological pH. The spectral properties of the major Cu(II)-peptide species are almost identical to HSA-Cu(II) (Table 2). The crystal of Cu(II)-GGHNMA was prepared at physiological pH and its molecular structure was determined. It is shown in Fig. 1 that Cu(II) is tetradentately chelated by amino-terminal nitrogen, the next two peptide nitrogens and the histidyl nitrogen of a single tripeptide molecule in a slightly distorted square-planar arrangement<sup>15</sup>. Electron paramagnetic resonance (EPR) spectra of the synthetic peptides correspond very well with those

for the Cu(II)-HSA complex<sup>16</sup>. The results are shown in Table 3. At 77 K, the epr spectra of Cu(II) complex of HSA exhibited only one form of epr signal between pH 6.5 and 9.5. The presence of equally spaced nine-line superhyperfine structure with spacing ~15 gauss indicated considerable covalent bonding between Cu(II) and four nitrogen atoms derived from the protein. In the pH range between 6 and 11, the epr spectra of Cu(II) complexes of AAHNMA and GGHNMA also exhibited well resolved nine-line superhyperfine structure.




Fig. 1 Structure of the Cu(II)-complex of the designed peptide glycyglycyl-L-histidine-N-methyl amide by X-ray crystallographic analysis<sup>15</sup>

All the above studies showed a considerable similarity between AAHNMA and GGHNMA. However, the native sequence peptide AAHNMA resembled closer to the protein HSA as far as their Cu(II)-binding affinity and dissociation are concerned<sup>17</sup>. This raised the question as to whether the Cu(II)-binding site indeed involved the side chain carboxyl group in addition to the four nitrogen ligands already proposed. In order to solve this question, a detailed investigation was undertaken with <sup>13</sup>C-nmr technique<sup>18</sup>.

The consequences of the binding of a paramagnetic metal such as Cu(II) by a ligand molecule are alterations of the chemical shifts and linewidths of the nuclear resonances of the ligand. But Cu(II) has a long electron spin relaxation time ( $T_1 \sim 10^{-8}$  s<sup>-1</sup>). Because of this, its dominant effect is line broadening. The broadening of line is caused by the considerable decrease of the relaxation time due to the localized magnetic field of species bearing an unpaired electron in the proximity of the nmr active nucleus. The dipolar term is usually dominant in many cases. But the scalar term which corresponds to the transfers of unpaired spin density from the metal ion to the carbon is also quite significant. If the dipolar term dominates the line broadening, the ratio of  $T_1/T_2 = 7/6$ . If, however, the scalar mechanism is important,  $T_1/T_2 > 7/6$ . In this

instance, it is possible to interpret the data in terms of actual binding of paramagnetic metal with the ligand from the line broadening results.

TABLE 4—CARBON-13 SPIN-LATTICE AND TRANSVERSE RELAXATION TIMES IN PRESENCE OF Cu(II)

[Cu(II)]/peptide molar ratio 1 : 50, pH = 7.0,  $\omega_1 = 25.16$  MHz,  $\omega_2 = 90.54$  MHz.

	$T_1$ 1p s <sup>-1</sup>	$T_1$ 2p s <sup>-1</sup>	$T_{1p}/T_{2p}$	$T_{2p}/T_{2p+1}$
Asp COO <sup>-</sup>		31		1.5
C <sub>2</sub>	0.26	375	1440	1.6
C <sub>4</sub>		280		1.6
C <sub>6</sub>	0.30	230	770	1.8
Asp C $\alpha$	0.37	22	60	1.3
Asp C $\beta$	0.40	67	170	2.3
His C $\beta$	0.28	31	110	1.9

The observed  $T_1$  and  $T_2$  values for AAHNMA-Cu(II) are given in Table 4 at pH 7.0 for a Cu(II)/peptide molar ratio of 1 : 50. For all of the carbon atoms which are affected by Cu(II), the ratio  $T_1/T_2 \gg 7/6$  indicates predominant scalar interactions. The lack of any frequency dependencies of the linewidth in Cu(II)-containing solution

indicated that fast exchange limit was obtained in all the cases. Coordination of Cu(II) with the peptide showed a large line broadening for several  $^{13}\text{C}$  resonances, especially C<sub>2</sub>, C<sub>4</sub> and C<sub>6</sub> of the His, Asp C $\beta$ , Asp COO<sup>-</sup>, and His C $\beta$  (Fig. 2). The results suggest that in addition to four nitrogen ligands (one amino, two peptide and one imidazole nitrogen) in a square-planar coordination, there is the involvement of the side chain carboxyl group forming a pentacoordinated structure (Fig. 3). Further investigation of Cu(II) interaction of the NH<sub>2</sub>-terminal 24-residue peptide fragment of HSA by  $^{13}\text{C}$ -nmr technique confirmed the proposed structure<sup>19-22</sup>.




Fig. 3 Structure of the Cu(II)-transport site<sup>19</sup>.




Fig. 2.  $^{13}\text{C}$ -NMR spectra (25.16 MHz) of  $\text{D}_2\text{O}$  solution containing 0.27 M L-aspartyl-L-alanyl-L-histidine-N-methyl amide and  $5.41 \times 10^{-3}$  M Cu(II). The pH of solutions was (a) 2.0, (b) 7.0 and (c) 10.0 (\*corresponds to Asp COO<sup>-</sup>)<sup>19</sup>.

#### Nickel-transport site of human serum albumin :

Nickel(II) in human serum is mainly associated with albumin and L-histidine<sup>23</sup>. Nickel(II), like Cu(II), blocks the reaction of 1-fluoro-2,4-dinitrobenzene with the  $\alpha$ -amino group at the NH<sub>2</sub>-terminus of BSA. It has also been shown in preliminary tests that increasing amounts of Ni(II) caused the characteristic purple colour of the 1 : 1 Cu(II)-BSA complex to fade and change to yellow<sup>6</sup>. These results suggest that Ni(II) binds at the NH<sub>2</sub>-terminal region of albumin. Further experiments in this laboratory showed that HSA possesses a strong binding site for Ni(II)<sup>24</sup>.

In order to investigate the nature of the Ni(II)-binding site of HSA, detailed studies were undertaken with the synthetic native sequence peptide AAHNMA. In studying the Cu(II) binding to AAHNMA, it was found that the proton-liberation




Fig. 4. Species distribution for the Ni(II)-L-aspartyl-L-alanyl-L-histidine-N-methyl amide system as a function of pH. [Ni(II)] =  $1.09 \times 10^{-4}$  M; [Peptide] =  $4.474 \times 10^{-4}$  M. Curve 1, MA ( $\log \beta_{101} = 5.50$ ); Curve 2, MA<sub>2</sub> ( $\log \beta_{102} = 11.56$ ); Curve 3, MH<sub>2</sub>A ( $\log \beta_{1-21} = 5.94$ ); Curve 4, MH<sub>1</sub>A<sub>2</sub> ( $\log \beta_{1-21} = 4.75$ )<sup>25</sup>.

reaction begins at a pH slightly above 5 and a rapid increase in  $\delta H^+/\delta C_M$  occurs to a maximum of almost 3.5 at pH 6.4. This rapid displacement is attributed to the formation of the major species  $MH_{-1}A$  (Fig. 4). At pH 9.5-10.0,  $\delta H^+/\delta C_M$  is steady at a value of 2, where the species  $MH_{-2}A$  is present exclusively. Since in this pH range the  $\beta$ -carboxyl, imidazole and amino groups are already titrated, the protons liberated can be attributed to complex formation by the two peptide amide groups.

The visible spectra of Ni(II) complexes of HSA and AAHNMA are very similar. Analysis of the spectra of HSA as a function of pH, in the presence of 1 equivalent of Ni(II), showed that the spectrum of hexaquo-Ni(II) with absorption maxima at 395 and at 650-720 nm (broad doublet) changes rapidly with increasing pH to a highly absorbing peak at 420 nm, indicative of a square-planar or square-pyramidal geometry about the metal ion (Fig. 5). By pH 6.9, the peak has developed well with a shoulder in the region of 450-480 nm. At higher pH, the increases in absorption are less, but a small peak develops at 340 nm.




Fig 5 Visible absorption spectra as a function of pH for the Ni(II)-human serum albumin system. [Ni(II)-HSA] = 1.01 mM in 0.15M NaCl, 1 cm cell path with protein as reference at 25°C.

The visible absorption spectra of Ni(II)-AAHNMA are shown in Fig. 6. At pH 3.5, a spectrum of hexaquo-Ni(II) is observed. When the pH is increased to approximately 5.1, the spectrum is shifted to a  $\lambda_{max}$  of 385 nm and a broad peak at about 640 nm. It is possible that some initial carboxylate interaction with Ni(II) before proton liberation may be taking place, yielding a complex of octahedral symmetry. By pH 5.4, the peak maximum has shifted to 415 nm and the solution is a mixture of octahedral Ni(II) and mainly the highly absorbing MA complex ( $\lambda_{max}=428$  nm,  $\epsilon_{max}=202$ ). As the pH is increased, the absorption at 420 nm increases sharply, coinciding with the increases in the species  $MH_{-1}A$  ( $\lambda_{max}=420$ ,  $\epsilon_{max}=135$ ) as shown in the species distribution. A shoulder in the region 450-480 nm is also present on the high

wavelength side of the 420 nm peak. The results are very similar to those observed with Ni(II)-HSA




Fig. 6 Visible absorption spectra as a function of pH for the Ni(II)-L-aspartyl-L-alanyl-L-histidyl-N-methyl amide system. [Ni(II)] = 10.97 mM; [Peptide] = 50 mM in 0.15M NaCl at 25°C.

These results strongly suggest that the Ni(II)-binding site is located in the  $NH_2$ -terminal tripeptide segment of HSA. Further studies with Ni(II)-binding to DSA and its  $NH_2$ -terminal model peptide glycylglycyl-L-tyrosine-N-methyl amide showed a lack of binding specificity<sup>28</sup>. There is a histidine residue in the third position of HSA as has been discussed before and it has a greater specificity for Ni(II)-binding. Hence, it appears that the imidazole group is involved in the Ni(II)-binding

To further characterize this site, detailed  $^1H$ - and  $^{13}C$ -nmr experiments were undertaken with Ni(II)-binding to AAHNMA<sup>29</sup>. The individual chemical shifts ( $\Delta = \delta_{1/2 \text{ complex}} - \delta_{free \text{ peptide}}$ ) for carbons and protons are shown in Fig. 7. The Asp  $COO^-$  carbon is affected most of all by Ni(II) binding ( $\Delta = 8.32$  ppm at pH=9.1) which is consistent with carboxylate-Ni(II) coordination. The imidazole ring system also shows large variations [C(5),  $\Delta = -2.45$  ppm]. Upon complexation, the Ni(II)-binding to the  $NH_2$ -terminal and  $COO^-$  group affects the  $\alpha$  carbon (4.69 ppm) more strongly while in the case of  $\beta$  carbon, we observed a shielding effect (-1.73 ppm) at pH 9.1. In the proton nmr spectra, many upfield chemical shifts are observed for imidazole residue. Most significantly, in DMSO- $d_6$  solution containing Ni(II)-AAHNMA, there is a complete disappearance of Ala and His N-H protons, which confirms the coordination of these two peptide nitrogens. The above results suggest that Ni(II) forms complex with this peptide involving the  $\alpha$ - $NH_2$ , N(3) imidazole, two deprotonated peptide nitrogens, and the  $COO^-$  group in a pentacoordinated structure as shown by the arrows in Fig. 7. Subsequent studies of Ni(II)-binding to the  $NH_2$ -terminal 24-residue peptide fragment of HSA by  $^{13}C$ -nmr technique confirmed the above structure<sup>30</sup>.




Fig. 7. Chemical shift ( $\Delta\delta_{1/1}$  complexed-peptide) for the 1/1 Ni(II)-L-aspartyl-L-alanyl-L-histidine-N-methyl amide complex in  $D_2O$  at pH 9.1. Underlined numbers represent  $^1H$  values and numbers without underline show  $^{13}C$  values in ppm. Arrows are directed toward the proposed site of Ni(II)-binding to the peptide<sup>22</sup>.

#### Zinc(II)-binding site of carboxypeptidase .

Carboxypeptidase is a Zn(II)-metalloenzyme which catalyzes the hydrolysis of the carboxyl terminal of peptides and esters. Upon removal of Zn(II), a catalytically inactive apoenzyme results. The role of Zn(II) and other transition metals in the enzymatic activity of carboxypeptidase has been the subject of many investigations<sup>27,28</sup>. The Zn(II)-binding ligands involved in the binding have been identified as His (69), Glu(72) and His(196)<sup>29,30</sup>.

Initially, we designed a linear hexapeptide, Gly-L-His-L-Ser-L-Arg-L-Glu-Gly, containing the native sequence 69-72 of carboxypeptidase with glycine on two termini<sup>31</sup>. But the peptide did not show any specificity for Zn(II)-binding. It was thought that a suitable model should include all the three native Zn(II) ligands. A critical survey of several metalloenzymes, whose crystal structures have been elucidated, revealed the natural occurrence of one to three amino acid residues in between two ligands for the metal-binding. Other ligands originate from a distant part of the molecule. With this consideration, a linear octapeptide containing the three native Zn(II)-ligands with the sequence, Gly-L-Glu-Gly-Gly-L-His-Gly-L-His-Gly, was designed and synthesized<sup>32</sup>. But this peptide also did not show significant specificity for Zn(II)-binding.

At this stage, it was thought that a linear peptide has considerable conformational flexibility. The ligands in the native enzyme are somewhat fixed because of the folding of the protein. Thus, it was thought that the cyclization of the linear peptide may be a means by which binding residues can be brought close to each other. In this manner,

certain rigidity can also be introduced in the molecule. Model building by both CPK and Kendrew models showed that the cyclic octapeptide of the same sequence, cyclo(Gly-L-Glu-Gly-Gly-L-His-Gly-L-His-Gly) provide the satisfactory requirements for the Zn(II)-binding geometry. This model retains the native Zn(II)-ligands interspaced by glycine residues. The two imidazole residues and the  $\gamma$ -carboxyl moiety of the glutamyl residue in the model seemed to interact well with the tetrahedral Zn(II).

The cyclic octapeptide was synthesized by high dilution technique from the corresponding linear octapeptide, N-Boc-Gly- $\gamma$ -OBu<sup>t</sup>-L-Glu-Gly-Gly-L-His-Gly-L-His-Gly-OBzINO<sub>2</sub>, via the azide method<sup>33</sup>. The linear octapeptide was obtained by coupling of the two tetrapeptide fragments : N-Boc-Gly- $\gamma$ -OBu<sup>t</sup>-L-Glu-Gly-Gly-ONp and L-His-Gly-L-His-Gly-OBzINO<sub>2</sub>. The cyclic peptide was purified to homogeneity. The product obtained was ninhydrin negative and Pauli's reagent positive. Further confirmation of this material was obtained by the proton magnetic resonance spectrum in which the various kinds of protons of this peptide were accounted for.

A detailed  $^{13}C$ - and  $^1H$ -nmr investigation was undertaken to determine the Zn(II)-binding ligands of the cyclic octapeptide. The details of the  $^{13}C$ - and  $^1H$ -nmr spectra are shown in Figs. 8 and 9




Fig. 8.  $^{13}C$ -NMR spectra (25.16 MHz) of cyclo(Gly-L-Glu-Gly-Gly-L-His-Gly-L-His-Gly) in  $DMSO-d_6$ . The upper spectrum is of the free peptide, the lower of octapeptide in presence of Zn(II) (1 : 1)<sup>34</sup>.

The effect of increasing concentrations of Zn(II) on the octapeptide in  $DMSO-d_6$  in the range Zn(II)/peptide = 1 : 4 to 2 : 1 shows that the Zn(II)-complex is in fast exchange on the nmr time scale. The important observation was the increasing or decreasing shifts with increasing Zn(II) from ratio 1 : 4 to 1 : 1 ; beyond this ratio, the shift is unaffected.

Under these circumstances, the results suggest a 1 : 1 complex (Fig. 10).




Fig. 9.  $^1\text{H}$ -NMR spectra (220 MHz) of cyclo-(Gly-L-Glu-Gly-Gly-L-His-Gly-L-His-Gly) in  $\text{DMSO}-d_6$ . The upper spectrum is of the free peptide, the lower of octapeptide in presence of  $\text{Zn(II)}$  (1 : 1). The scale is downfield from  $\text{TMS}^{22}$ .




Fig. 10 The variation of the  $^{13}\text{C}$  chemical shift as a function of the relative concentration of  $\text{Zn(II)}$  present. The data were obtained in  $\text{DMSO}-d_6^{22}$ .

In Table 5, the chemical shifts of  $^1\text{H}$  and  $^{13}\text{C}$  resonances in cyclo-octapeptide are compared with the corresponding resonances observed in the 1 : 1 complex. In the case of protons, the largest chemical shift changes are observed for the proton resonances of the histidine residues and more particularly  $\text{C(2)H}$  protons. All the  $\text{NH}$  resonances are unaffected. Thus, the peptide  $-\text{NH}_2$  group does

not participate in coordination. The chemical shift induced on glutamic acid residue are about 0.1 ppm or less. In the case of  $^{13}\text{C}$  resonances, the most dramatic changes in chemical shift occur in the histidine residues and especially in the imidazole ring. The three carbon of the imidazole ring,  $\text{C(2)}$ ,  $\text{C(4)}$  and  $\text{C(5)}$ , show a large change in chemical shift upon binding to  $\text{Zn(II)}$ . The two methylene of the glutamic residue show a large change in chemical shift upon ligating to the metal ion. Both carbons are shifted downfield ( $\text{Glu C}_\gamma = 0.88 \text{ ppm}$

TABLE 5— $^{13}\text{C}$ - AND  $^1\text{H}$ -NMR SHIFTS FOR CYCLO-OCTAPEPTIDE AND 1 : 1  $\text{Zn(II)}$ -CYCLO-OCTAPEPTIDE IN  $\text{DMSO}-d_6$

	$^{13}\text{C}$		$^1\text{H}$	
	cP8 <sup>a</sup>	cP8-Zn(II)	cP8	cP8-Zn(II)
Glu $\text{CH}_2^\beta$	31.38	32.07	1.89	1.87
His $\text{CH}_2^\beta$	33.72	32.07	2.89	2.97
	34.03		3.02	3.15
Glu $\text{CH}_2^\gamma$	35.23	36.11	2.22	2.32
Gly $\text{CH}_2$	47.88	47.89	3.86	3.86
			3.82	3.82
			3.67	3.67
			3.62	
Glu $\text{CH}^\alpha$	57.81	56.81	4.16	4.21
His $\text{CH}^\alpha$	58.80	57.89	4.30	4.43
			4.46	4.66
$\text{C(5)-H}$	121.36	125.02 <sup>b</sup>	6.92	7.02
$\text{C(4)-H}$	121.80			
$\text{C(2)-H}$	138.98	135.49 <sup>b</sup>	—	—
	140.11	141.31	7.65	8.08
			7.70	
Gly CO	174.55	174.43	—	—
	175.00	174.70		
		174.90		
His CO	176.80	175.76	—	—
	177.41	176.64		
Glu CO	177.66	177.53	—	—
Glu $\text{COO}^-$	179.08	181.09	—	—

<sup>a</sup> cP8 : cyclo-octapeptide.

<sup>b</sup> Linewidth at half-height 60 Hz [ $\text{C(4)-H}$ ] and 36 Hz [ $\text{C(5)-H}$ ].

$\text{Glu C}_\beta = 0.69 \text{ ppm}$ ). The carboxyl resonances of glycine are essentially unaffected upon  $\text{Zn(II)}$  binding. But the carbonyl atoms of glutamic at the two histidine residues shift upfield  $-0.13$ ,  $-1.0$  and  $-0.77 \text{ ppm}$ , respectively, upon complexation. The most significant observation is the deshielding effect ( $\Delta = 2.01 \text{ ppm}$ ). From these observations it is clear that the largest chemical shifts occur for the two imidazole rings and for the glutam




Fig. 11. Structure of the  $\text{Zn(II)}$ -binding to the designed cyclo-octapeptide as deduced from the NMR studies<sup>22</sup>.

carboxyl group. The results demonstrate that both the imidazoles of the two histidine residues and the carboxyl side chain of the glutamic acid residue of the cyclo-octapeptide are coordinated to Zn(II) as shown in Fig. 11.

#### Zinc(II)-binding site of carbonic anhydrase :

Carbonic anhydrase is a Zn(II) containing metalloenzyme and the catalytic activity of the enzyme is linked to the presence of Zn(II) ion<sup>24</sup>. The biologically relevant activity of the enzyme is the reversible hydration of carbon dioxide although it is known to catalyze a variety of hydration reactions, such as the hydration of various aldehydes, and carboxylic, sulfonic and carbonic esters. Zinc(II) in the enzyme is bound to the histidine residues, which in human B isozyme are : His-94, His-96, and His-119<sup>24</sup>. The coordination geometry about the Zn(II) is distorted tetrahedral with the fourth position occupied by a water molecule.

Considering the known structure of the Zn(II)-binding site of carbonic anhydrase, the simplest possible peptide model which may be proposed for this metal binding site is one which contains three histidyl residues linked in a manner that would enable formation of the base of a tetrahedron when Zn(II) complexation occurs. Similar considerations as those followed in the design of carboxypeptidase Zn(II)-binding model resulted in the designing of a cyclic heptapeptide molecule : cyclo(Gly-L-His-Gly-L-His-Gly-L-His-Gly)<sup>25</sup>. Model building by both CPK and Kendrew models indicated that the three histidines of the above cyclic heptapeptide have the ability to interact with the Zn(II) to form a tetrahedral complex.

The cyclic heptapeptide was synthesized from the linear heptapeptide, Gly-L-His-Gly-L-His-Gly-L-His-Gly-OH, which in turn was obtained by coupling of the fragments, viz., BOC-Gly-L-His-Gly-N<sub>3</sub> and L-His-Gly-L-His-Gly-OBzlNO<sub>2</sub>, followed by deblocking of amino and carboxyl protecting groups. Conversion of the linear heptapeptide to the azide by treatment with diphenylphosphoryl azide was followed by cyclization in high dilution. The homogeneous material was found to be ninhydrin negative. The nmr spectrum of the material upon integration indicated the proper ratios of various kinds of protons to be expected of the cyclic heptapeptide<sup>26</sup>.

The metal titration studies show that the magnitude of the chemical shift perturbations induced by Zn(II) increases in increasing metal ion concentration from Zn(II)/peptide ratio 1 : 4 to 1 : 1 ; beyond this ratio, the shift is unaffected. Thus, the cyclic heptapeptide forms a 1 : 1 complex with Zn(II). Similar studies were undertaken by <sup>13</sup>C-nmr technique. Fig. 12 shows the relationship between the ratio of Zn(II)-peptide to the change in chemical shift of the C(2), C(4) and C(5) imidazole carbons of the cyclic peptide. The change in chemical shift for all the carbons is linear to a ratio of 1 : 1, following which it seems to level off. This result is consistent with a 1 : 1 complex of Zn(II)-cyclopeptide.




Fig. 12. The variations of the <sup>13</sup>C chemical shift in DMSO-d<sub>6</sub> as a function of the cyclic heptapeptide/Zn ratio<sup>26</sup>.

The <sup>1</sup>H- and <sup>13</sup>C-nmr spectra of free cyclic heptapeptide and Zn(II)-bound peptide are shown in Figs 13 and 14. The chemical shifts of <sup>1</sup>H and <sup>13</sup>C resonances in cyclopeptide are compared with the




Fig. 13. A portion of the <sup>1</sup>H-nmr spectrum obtained in DMSO-d<sub>6</sub> at 250 MHz showing the resonances of the exchangeable N-H protons and imidazole protons of cyclic heptapeptide (a) and its 1 : 1 complex with Zn(II) (b)<sup>26</sup>.




Fig. 14.  $^{13}\text{C}$ -NMR spectra (22.63 MHz) of cyclo(Gly-L-His-Gly-L-His-Gly-L-His-Gly) in  $\text{DMSO-d}_6$ , in the (a) absence and (b) presence of 1:1  $\text{Zn(II)}$ <sup>a</sup>

corresponding resonances observed in the 1 : 1 complex in Table 6. The changes in the chemical shift of the proton of imidazole are relatively large, indicating that this ring is involved in the complexation. The largest downfield shift occurs for the imidazole N(1)-H proton ( $\Delta=1.34$  ppm). The peptide -NH- resonances are clearly observable and almost unaffected. Consequently, none of these nitrogens can serve as a ligand.

TABLE 6— $^{13}\text{C}$ - AND  $^1\text{H}$ -NMR CHEMICAL SHIFTS FOR CYCLO-HEPTAPEPTIDE AND 1 : 1  $\text{Zn(II)}$ -CYCLO-HEPTAPEPTIDE IN  $\text{DMSO-d}_6$

	$^{13}\text{C}$		$^1\text{H}$	
	cP7 <sup>a</sup>	$\text{Zn(II)}$ -cP7	cP7	$\text{Zn(II)}$ -cP7
His $\text{CH}_\beta$	32.25	31.40	2.93	3.11
Gly $\text{CH}_\alpha$	46.81	46.87	2.97	
	47.00	47.04	3.47	3.55
			3.60	
His $\text{CH}_\alpha$	57.21	56.30	3.74	
	57.67	57.02	4.36	4.52
C(5)-H	121.45	123.41	4.48	
		123.99	6.79	6.90
C(4)-H	136.67	135.04	6.88	7.16
	137.25	135.40	—	—
C(2)-H	138.49	140.20	7.54	8.16
			7.59	8.28
N(1)-H	—	—	11.88	13.22
			—	—
Gly CO	173.63	173.80		
	173.93	173.90		
		174.06		
His CO	175.42	175.10		
	176.13	175.42		
		175.87		

<sup>a</sup> cP7, cyclo-heptapeptide.

By addition of one equivalent of  $\text{Zn(II)}$  to the peptide, the imidazole residue is the most affected as shown by the  $^{13}\text{C}$ -nmr spectra. The C(2), C(4) and C(5) carbon resonances of this group are dramatically affected and show a very large change in chemical shift after complexation. In fact, all

three imidazole residues are affected in the same way and suggest that these residues of cyclo-heptapeptide are ligands. Both C(2) and C(5) carbons move downfield ( $\Delta=1.71$  and  $1.96$ ,  $2.54$  ppm, respectively) while C(4) moves upfield upon complexation ( $\Delta=-1.63$  and  $-1.85$  ppm). Shifts of similar magnitude and sign have been observed for the imidazole residue of histidine when this amino acid residue in a peptide binds to  $\text{Zn(II)}$ <sup>8,87</sup>. There are changes in His  $\text{C}_\alpha$  and His  $\text{C}_\beta$ , which are all neighbours of the imidazole ring. The Gly  $\text{C}_\alpha$  carbon signals and the Gly carbonyl resonances appear to be unaffected by metal complexation whereas the carbonyl carbon atoms of the three histidine residues move  $\sim 0.50$  ppm upfield on complexation. From these results, we can conclude that the designed cyclic heptapeptide binds a single  $\text{Zn(II)}$  ion in 1 : 1 complex and that the binding site for  $\text{Zn(II)}$  is the N(3) nitrogen of the three imidazole residues as shown in Fig. 15.




Fig. 15. Structure of the  $\text{Zn(II)}$ -binding to the designed cyclic heptapeptide as deduced from the nmr studies.



### Conclusion :

The results discussed above confirm the concept of molecular design to mimic the metal-binding sites of biological macromolecules<sup>20</sup>. However, several interesting facts have emerged from these studies. In the investigations of the Cu(II)-transport site of HSA, we initially designed two peptides, GGH and GGHNMA. Both the peptides demonstrated a remarkable similarity with the Cu(II)-transport site of HSA. But it was not until the native sequence peptide AAHNMA was synthesized and the Cu(II)-binding studies were carried out did we recognize the full implication of the carboxyl side chain of the NH<sub>2</sub>-terminal aspartyl residue of HSA. Extensive chemical and physical studies with the native HSA molecule failed to detect the involvement of the carboxyl group in the coordination of Cu(II). The same holds true with the Ni(II)-transport site of HSA. Although these experiments helped in the structural elucidation of the Cu(II)-transport site of HSA, the functional aspects of this site are still unclear. It is possible that some residues which may not be directly bonded to the metal, yet close enough, could influence the dynamics of the Cu(II)-transport. In designing models for the Zn(II) binding sites of carboxypeptidase and carbonic anhydrase, it is clear that the cyclic peptides afforded both the rigidity and the ligand binding geometry of the native metal binding sites. In these models, too, the functional aspects of the metal binding sites are not considered and hence no catalytic activity of the enzyme can be expected in these molecules. One should also bear in mind that in none of these models does the native microenvironment around the metal binding site appear. Thus, one must use caution to interpret the model studies in relation to defining the native metal binding sites. However, peptide molecules belong to an important class of models to probe the metal binding sites and a careful analysis of the results should provide critical information about the structure of the metal-binding sites of proteins and enzymes.

### Acknowledgement

This research was supported by the Medical Research Council of Canada. The author wishes to acknowledge the encouragement and enthusiastic support of all his co-workers whose names appear in the references. Thanks are due to Miss Janet Denton who patiently and carefully typed the manuscript.

### References

1. I. M. KLOTZ and H. G. CURME, *J. Amer. Chem. Soc.*, 1948, 70, 939.
2. I. M. KOLTHOFF and B. R. WILLEFORD, Jr., *J. Amer. Chem. Soc.*, 1958, 80, 5673.
3. B. SARKAR and Y. WIGFIELD, *Can. J. Biochem.*, 1968, 46, 601.
4. T. PETERS, Jr., *Biochim. Biophys. Acta*, 1960, 39, 546.
5. E. BRESLOW, *J. Biol. Chem.*, 1964, 239, 3252.
6. T. PETERS, Jr. and F. A. BLUMENSTOCK, *J. Biol. Chem.*, 1967, 242, 1574.
7. D. W. APPLETON and B. SARKAR, *J. Biol. Chem.*, 1971, 246, 5040.
8. J. W. DIXON and B. SARKAR, *J. Biol. Chem.*, 1974, 249, 5872.
9. S. LAU, T. P. A. KRUCK and B. SARKAR, *J. Biol. Chem.*, 1974, 249, 5878.
10. S. LAU and B. SARKAR, *J. Chem. Soc. Dalton*, 1981, 491.
11. T. P. A. KRUCK, S. LAU and B. SARKAR, *Can. J. Chem.*, 1976, 54, 1300.
12. K. S. N. IYER, S. LAU, S. H. LAURIE and B. SARKAR, *Biochem. J.*, 1978, 169, 61.
13. B. SARKAR and T. P. A. KRUCK, *Can. J. Chem.*, 1973, 51, 3541.
14. B. SARKAR, *J. Indian Chem. Soc.*, 1977, 54, 117.
15. N. CAMERMAN, A. CAMERMAN and B. SARKAR, *Can. J. Chem.*, 1976, 54, 1309.
16. G. RAKHIT and B. SARKAR, *J. Inorganic Biochem.*, 1981, 15, 233.
17. B. SARKAR, V. RENUGOPALAKRISHNAM, T. P. A. KRUCK and S. LAU in "Environmental Effects on Molecular Structure and Properties", (Ed.) B. PULLMAN, D. Reidel Publishing Co., Dordrecht-Holland, 1976, p. 165.
18. J.-P. LAUSSAC and B. SARKAR, *J. Biol. Chem.*, 1980, 255, 7563.
19. B. SARKAR, J.-P. LAUSSAC and S. LAU in "Biological Aspects of Metals and Metal-Related Diseases", (Ed.) B. SARKAR, Raven Press, New York, 1983, in press.
20. B. SARKAR, "Proceedings of the Nobel Symposium on Inorganic Biochemistry", Sweden, 1982, p. 26.
21. B. SARKAR, "Life Chemistry Reports", Oxford, 1983, in press.
22. B. SARKAR and J.-P. LAUSSAC, "Proceedings of the International Conference on Coordination Chemistry", Hungary, 1982, p. 53.
23. M. LUCASSEN and B. SARKAR, *J. Toxicol. & Environ. Hlth.*, 1979, 5, 897.
24. J. D. GLENNON and B. SARKAR, *Biochem. J.*, 1982, 203, 15.
25. J. D. GLENNON and B. SARKAR, *Biochem. J.*, 1982, 203, 25.
26. J.-P. LAUSSAC and B. SARKAR, *Can. J. Chem.*, 1980, 58, 2055.
27. R. PIRAS and B. L. VALLEE, *Biochemistry*, 1967, 6, 348.
28. B. L. VALLEE and J. F. RIORDAN, "Brookhaven Symposium in Biology", 1968, 21, 91.
29. W. N. LIPSCOMB, J. A. HARTSUCH, G. N. REEKS, JR., F. A. QUICHO, P. H. BETHGE, M. L. LUDWIG, T. A. STEITZ, H. MUIRHEAD and J. A. COPPOLA, "Brookhaven Symposium in Biology", 1968, 21, 24.
30. R. A. BRADSHAW, L. H. ERICSON, K. A. WALSH and H. NEURATH, *Proc. Natl. Acad. Sci. USA*, 1969, 63, 406.
31. S. LAU and B. SARKAR, *Proc. Can. Fed.*, 1971, 14, 33.
32. S. LAU and B. SARKAR, *Proc. Can. Fed.*, 1973, 16, 97.
33. K. S. IYER, J.-P. LAUSSAC, S. LAU and B. SARKAR, *Intl. J. Peptide and Protein Res.*, 1981, 17, 549.
34. D. KEILIN and T. MANN, *Biochem. J.*, 1940, 34, 1163.
35. K. K. KANNAN, B. NOTSTRAND, K. FRIDBERG, S. LÖVGREN, A. OHLSSON and M. PETEF, *Proc. Natl. Acad. Sci. USA*, 1975, 72, 51.
36. K. S. IYER, J.-P. LAUSSAC and B. SARKAR, *Intl. J. Peptide and Protein Res.*, 1981, 18, 468.
37. H. LAKUSTA, C. M. DEBER and B. SARKAR, *Can. J. Chem.*, 1980, 58, 757.
38. B. SARKAR in "Metal Ligand Interaction in Organic and Biochemistry", (Ed.) B. PULLMAN, D. Reidel, Dordrecht-Holland, 1977, p. 193.

## Separation of Th(IV) in Aqueous Glycine Medium by Cation Exchange Chromatography

LALIT C. T. EUSEBIUS†, ASHOK MAHAN and ANIMESH K. GHOSE\*

Chemical Laboratories, University of Allahabad, Allahabad-211 002

Through cation exchange column chromatography using Dowex 50W-X8 (Na<sup>+</sup> form, 100-200 mesh) in aqueous 0.20 M glycine media, analytical conditions predicted from the distribution coefficient (*K*), have enabled the separation of a wide concentration of Th(IV) from U(VI), Al(III), Cr(III), Fe(III), La(III), Ce(III), Ca(II), Sr(II), Ba(II), Mn(II), Co(II), Ni(II), Zn(II), Cd(II), Pb(II), Ag(I), Cu(II) or Hg(II). The following ternary mixtures were also resolved: Th(IV)-Cu(II)-Hg(II)-U(VI)/Al(III)/Cr(III)/Fe(III)/La(III)/Ce(III)/Ca(II)/Sr(II)/Ba(II)/Mn(II)/Co(II)/Ni(II)/Zn(II)/Cd(II)/Pb(II)/Ag(I). In all the separations column kinetics was found to be favourable, though the separation of Th(IV) was almost but not quite quantitative. Values of *K*, elution characteristics of metal ions, elution curves and results of the resolution of a number of mixtures are presented

**M**OST of the reported methods<sup>7</sup> for the separation of thorium by ion exchange in HCl, HNO<sub>3</sub> or H<sub>2</sub>SO<sub>4</sub> media suffer from disadvantages rendering the resolution of mixtures containing a number of metal ions difficult. The slow kinetics of ion exchange in the mineral acids is perhaps a serious drawback, which results in tailing in the chromatograms. For example, anion exchange chromatography in 5-6 M HNO<sub>3</sub> is highly selective for Th(IV)<sup>1,2</sup> but tailing of U(VI) and a few other metal ions limits the application of this method. Considerably better kinetics, though not excellent, was obtained in 0.60 M HNO<sub>3</sub> containing 55% acetone<sup>7,8</sup>. Also, in the case of cation exchange separations of Th(IV), eluting agents such as 3 M H<sub>2</sub>SO<sub>4</sub><sup>9,12</sup> or 0.50 M oxalic acid<sup>11</sup> are inefficient because kinetics is slow and for the quantitative recovery of Th(IV), the resin must be ignited to ash<sup>14,15,16</sup> and Th(IV) determined in the residue. However, Strelow *et al.*<sup>17</sup> were able to devise a method for the separation of Th(IV), which does not require ashing.

Glycine is a versatile complexant<sup>18</sup> and among the separations described using glycine, are those of Zn(II)-Cd(II)<sup>19</sup> and of Cu(II)-Co(II)<sup>4</sup>. A chelating exchanger was used by Hering<sup>5</sup> for studying the ion exchange behaviours of Fe(III), Cu(II), Ni(II), Co(II), Mg(II) and K(I). Glycine and other amino acids along with other complexants were used as retaining agents for the separation of several less familiar elements on NH<sub>4</sub><sup>+</sup>-form nuclear sulphonic acid exchanger at 85-90°C<sup>21</sup>. Jercan and Dinouiu<sup>6</sup> reported the concentration and separation of U(VI) from diverse ions using Dowex 2X-8 and Vionite AT-1 anion exchanger in glycine (pH > 3.4 to < 6) solution containing α,α'-bipyridyl.

In this work, a systematic study has been done on the possibility of concentration and separation of Th(IV) in aqueous glycine medium. The

following metal ions, U(VI), Al(III), Cr(III), Fe(III), La(III), Ce(III), Ca(II), Sr(II), Ba(II), Mn(II), Co(II), Ni(II), Cu(II), Zn(II), Cd(II), Hg(II), Pb(II) and Ag(I) were also studied for obtaining the analytical conditions under which Th(IV) may be separated from mixtures. The resin used was strongly acidic Dowex 50W-X8. On the basis of the *K* values, specific separation of Th(IV) from 18 other metal ions was achieved by column chromatography. A wide range of concentrations of glycine and Th(IV) were studied for the separation but only one typical set is included here. Better recovery of Th(IV) occurs when glycine is below 0.4 M, while the recovery shows a fall if the concentration of glycine is higher. *K* values, elution behaviour of metal ions, elution curves and results of the resolution of various mixtures are reported in this communication.

### Experimental

#### Material :

(a) *Water* : De-ionised distilled water was used in all the experiments.

(b) *Metal ion solution* : Aqueous 0.06-0.20 M solutions of U(VI), Al(III), Cr(III), La(III), Ca(II), Sr(II), Ba(II), Mn(II), Co(II), Ni(II), Cu(II), Zn(II), Cd(II), Pb(II) and Ag(I) were prepared from reagent grade nitrate samples (BDH AnalaR or Johnson Mathey). Solutions of Hg(II), 0.10 M in 0.10 M glycine, and of Th(IV), 0.05 M in 0.05 M glycine were prepared from their nitrate samples (BDH AnalaR) directly in glycine solution. Fe(III) solution, 0.06 M in 0.06 M glycine was prepared from ammonium iron(III) sulphate directly in aqueous glycine solution. Cerous chloride (Johnson Mathey) was used to prepare aqueous solution of Ce(III). The solutions were standardised by determining the metal contents<sup>8,19,20</sup>.

†Present Address : Department of Chemistry, Ewing Christian College, Allahabad-211 003.

(c) *Glycine solution* : 2.0 M stock solution of glycine (E. Merck, G.R.) was prepared in water. Freshly prepared solutions were used.

(d) *Ion exchange resin* : Strongly acidic polystyrene based sulphonic acid Dowex 59W-X8 (Na<sup>+</sup>-form, 100-200 mesh) was washed in a column with ca 0.2 M EDTA solution (pH 8-10) and then with water. The resin in the Na<sup>+</sup>-form was obtained by passing a large excess of ca 10% NaCl solution through the column and then washing with water until free from chloride ions. The resin in the Na<sup>+</sup>-form was air dried on a sintered bed by applying suction and was stored in an air tight bottle. The capacity and water content were found to be 3.04 meq/g and about 21%, respectively

#### Apparatus :

(a) *Equilibration studies* : A wrist motion microid flask shaker (Griffin & George), operating on 220 V/50 cycles A.C. mains was used for shaking the solutions with the resin in 100 ml pyrex flasks

(b) *pH measurements* : A Leeds and Northrup pH meter was used for pH measurements.

#### Distribution studies :

An appropriate amount of metal ion (about 30% of the total exchange capacity of resin) solution and aqueous glycine of the desired concentration (0.04 to 1.60 M) were mixed and 1 g of resin was added. This was shaken for 1 hr and the resin was filtered off. The metal content was determined in the solution phase. Glycine did not interfere in the estimation of metal ions. *K* was determined using the relationship,  $K = \text{meq metal per g of resin/meq metal per ml of solution}$ .

All experiments were performed at least in duplicate, at  $30 \pm 2^\circ$ , and the average values are recorded (Table I). The relative experimental error in the determination of *K* values was usually  $\pm 5$  to 10%.

#### Results and Discussion

In general, *K* values of most of the metal ions studied decrease with an increase in glycine concentration from 0.04 to 1.60 M (Table I). Complexation with glycinate ion is, perhaps, the dominant factor which governs the trend and magnitude of the sorption. The cation exchange sorption of a metal ion decreases as the charge on the species formed changes from a small positive value to zero and finally becomes negative. Previous studies<sup>2,3</sup> has confirmed that an effective decrease in the sorption is not necessarily accompanied by the formation of a negatively charged species.

Water molecules coordinated with metal ions are generally replaced by glycine as its concentration is increased, resulting in the formation of small positive charged or neutral species in most of the cases, leading to the decrease of *K* values. Further increase of glycine concentration perhaps favours the formation of neutral species as indicated by appreciably high values of *K*. The high values of *K* even at higher concentrations of glycine, in almost all metal ions except Th(IV), Cu(II) and Hg(II), suggest that metal ions or complex ions with a low charge have higher affinity for cation exchanger than glycine in aqueous medium.

Though Th (IV) has the highest positive charge amongst the metal ions, it shows the lowest affinity

TABLE I—DISTRIBUTION COEFFICIENTS IN AQUEOUS GLYCINE

Metal Ion	Distribution coefficients ( <i>K</i> )						
	Conc. of aqueous glycine (M)						
	0.04	0.12	0.20	0.40	0.64	1.00	1.60
Al(III)	(a)	(a)	(a)	(a)	(a)	(a)	(a)
Ca(II)	1290	1080	1060	1220	1290	1080	1220
Cr(III)	1620	1240	1800	2460	—	890	800
Mn(II)	2270	2530	2270	1970	1740	1890	1890
Fe(III)	2580	2010	1850	1150	670	560	480
Co(II)	3260	1820	2080	1200	680	420	270
Ni(II)	2600	1050	690	320	190	110	60
Cu(II)	340	90	49	28	8.8	4.9	2.2
Zn(II)	1040	950	760	560	400	310	240
Sr(II)	1720	1600	—	1410	—	—	4050
Ag(I)	280	280	280	260	240	200	170
Cd(II)	1250	1050	1050	1050	1050	780	780
Ba(II)	1120	1040	—	1690	—	—	2370
La(III)	(a)	(a)	(a)	(a)	(a)	(a)	(a)
Hg(II)	1690	230	80	25	12	6.0	3.4
Pb(II)	1440	1360	1360	1760	2750	8310	12400
Ce(III)	(a)	(a)	(a)	(a)	(a)	(a)	(a)
Th(IV)	3.2	3.0	3.2	2.9	4.2	15.2	6.3
U(VI)	(a)	(a)	(a)	(a)	(a)	(a)	630

a = Very high value.

for cation exchanger as the amount of glycine is increased. In the case of Cu(II) and Hg(II) the  $K$  values decrease appreciably with the increase in glycine concentration and at 1.60  $M$  glycine the  $K$  values are even lower than that for Th(IV). This behaviour shown by Cu(II) and Hg(II) metal ions is due to their pronounced complexing tendency with glycine, resulting in the formation of perhaps negatively charged species<sup>10</sup>.

#### Prediction of separation possibilities :

$K$  values suggest the utility of glycine for the separation of Th(IV) from other metal cations. Th(IV) should follow the feed effluent because of low affinity for the exchanger and other metal ions should be retained onto the resin bed due to higher affinity. The separation of Th(IV) from Cu(II) or

the column at the controlled flow rate of  $1.0 \pm 0.5$  ml/min. Feed effluent was collected from the beginning of the sorption.

**Elution:** The sorption was followed by the quantitative elution of the components of the binary mixtures. The very weakly held Th(IV) was eluted with 40 ml of 0.20  $M$  glycine (including 25 ml of feed effluent). The break-through of strongly sorbed other metal ions [except Cu(II) and Hg(II)] were not observed even after the passage of 125 ml of 1.0  $M$  glycine (Table 2). Cu(II) or Hg(II) was recovered with 105 and 95 ml of 1.6  $M$  glycine while other ions were stripped off with the help of other eluents. Al(III), Cr(III), Mn(II), Fe(III), Co(II), Ni(II), Zn(II), Cd(II) and Ce(III) were eluted with about 80 ml of 2.5  $M$  HCl, Ag(I) with 65 ml of 2.5  $M$

TABLE 2—ELUTION CHARACTERISTICS OF METAL IONS ON DOWEX 50W-X8 COLUMN

Metal	BTV(ml)	VEP (ml)	TEV (ml)	Eluting agent
Th(IV)	5	~20	40	0.20M Glycine
Cu(II)	15	45	105	1.6M Glycine
Hg(II)	5	30	95	—do—
Al(III)	> 125	—	—	2.5M HCl
Cr(III)	> 125	—	—	—do—
Fe(III)	> 125	—	—	—do—
La(III)	> 125	—	—	—do—
Co(III)	> 125	—	—	—do—
Co(II)	> 125	—	—	—do—
Ni(II)	> 125	—	—	—do—
Zn(II)	> 125	—	—	—do—
Cd(II)	> 125	—	—	—do—
Mn(II)	> 125	—	—	—do—
Ca(II)	> 125	—	—	3M NH <sub>4</sub> OAc
Sr(II)	> 125	—	—	2M NH <sub>4</sub> OAc
Ba(II)	> 125	—	—	4M NH <sub>4</sub> OAc
U(VI)	> 125	—	—	1M NH <sub>4</sub> OAc
Pb(II)	> 125	—	—	4M NH <sub>4</sub> OAc
Ag(I)	> 125	—	—	2.5M HNO <sub>3</sub>

BTV = Breakthrough volume.

VEP = Volume elution peak

TEV = Total elution volume.

Hg(II) is noteworthy, since these cannot be achieved at higher glycine concentrations ( $>0.64 M$ ) because of almost identical  $K$  values. Below 0.64  $M$  glycine, Th(IV) should follow the feed effluent and the strongly retained Cu(II) or Hg(II) may thereafter be removed with higher amounts of glycine.

#### Separation of binary and ternary mixture :

Column chromatographic separations of Th(IV) from other metal ions were achieved under the conditions predicted from batch experimentation. The following procedure was adopted :

**Preparation and pretreatment of resin bed :** The resin slurry (~5 g) was prepared in water from pre-purified and washed Na<sup>+</sup>-resin. It was transferred to the graduated column (~65 cm long with internal diameter ~0.85 cm). The height of the resin bed was about 8.0 cm. It was then treated with 0.10  $M$  or 0.20  $M$  glycine solution, as the case is.

**Preparation of feed and sorption :** The feed, 25 ml in 0.20  $M$  glycine, was prepared in duplicate by mixing known amounts of Th(IV) and one of the other cations studied. The feed was passed through

TABLE 3—RESULTS OF THE SEPARATION OF Th(IV) FROM A NUMBER OF METAL IONS

Th(IV) taken = 59.17 mg

Other Metal Ions*	Taken mg	Number of Determinations	Recovery of Th (IV) in (%)
Ag(I)	56.63	6	96.20
Mn(II)	27.42	6	95.90
Co(II)	29.46	6	96.01
Ni(II)	27.80	6	96.10
Cu(II)	31.77	8	96.00
Zn(II)	32.84	6	96.20
Ca(II)	20.10	6	96.30
Cd(II)	56.76	6	96.04
Hg(II)	100.80	8	96.08
Pb(II)	104.63	8	96.16
Sr(II)	25.66	6	96.12
Ba(II)	63.59	6	96.20
La(III)	45.70	6	95.98
Ce(III)	32.07	6	96.04
Al(III)	8.97	6	96.15
Fe(III)	17.51	8	96.20
Cr(III)	17.19	6	96.06
U(VI)	120.17	6	96.06

\*The recovery of these were ~100%.

$\text{HNO}_3$ , Ca(II) with 75 ml of 3 M  $\text{NH}_4\text{OAc}$  and Pb(II) with 75 ml of 4.0 M  $\text{NH}_4\text{OAc}$ . The results of the separations are reported in Table 3.

Th(IV) can also be separated from other metal ions [except Cu(II) and Hg(II)] at higher concentration ( $>1.0$  M) of glycine. But the recovery of Th(IV) has been found to be only about 80-85%. The recovery may be enhanced upto 96% if the separation is done at lower ( $\leq 0.20$  M) concentration of glycine and hence all separations were achieved in 0.20 M glycine. In all the separations column kinetics is highly favourable, the recovery is good but not quite quantitative perhaps due to very slow ligand exchange rates.

**Elution curves:** Figs. 1 and 2 represent the elution curves for the resolution of the following mixtures: Th(IV)-Fe(III)/Ce(III)/Pb(II) and Th(IV)-Cu(II)/Hg(II), respectively. The concentration is represented in terms of ml of 0.01 M EDTA. Volume of the effluent in the figures also include the volume passing out of the resin bed from the feed




Fig. 1. Elution curves: Th(IV)-Fe(III)/Ce(III)/Pb(II)




Fig. 2. Elution curves: Th(IV)-Hg(II)/Cu(II).

The separation between Th(IV) and Cu(II) or Hg(II) along with other cations at lower glycine

concentration (0.04-0.20 M) and of these three from other cations at higher glycine concentration (1.0-1.6 M) indicated the possibility of a number of ternary separations: Al(III)/Ca(II)/Cr(III)/Mn(II)/Fe(III)/Co(II)/Ni(II)/Zn(II)/Sr(II)/Ag(I)/Cd(II)/Ba(II)/Pb(II)/U(VI)/La(III)/Ce(III)-Cu(II)/Hg(II)-Th(IV).

For chromatographic separations of ternary mixtures, the feed was prepared in 0.1 M glycine by mixing any three of the above mentioned cations. Th(IV) followed the feed effluent whereas other metal ions were held onto the resin bed with considerable variation in sorption. Recovery of Th(IV) was achieved with 0.10 M glycine. Th(IV) exhibits almost similar behaviour as in 0.20 M glycine because it has almost identical  $K$  values in 0.04 to 0.20 M glycine. After the complete elution of Th(IV), not too strongly held Cu(II) or Hg(II) was eluted with 1.60 M glycine and finally the most strongly retained metal ions were desorbed with HCl,  $\text{HNO}_3$  or  $\text{HN}_4\text{OAc}$ , as the case may be.

#### References

1. D. J. CORSEWELL, *J. Inorg. Nuclear Chem.*, 1957, 3, 384.
2. J. DANON, *J. Amer. Chem. Soc.*, 1956, 78, 5953.
3. R. GHOSH, A. MAHAN and A. K. DEY, *Indian J. Chem.*, 1976, 14A, 518.
4. R. N. GOLOVATYI and V. V. OSHCHAPOVSKII, *Ukr. Khim. Zh.*, 1963, 29, 187; *Chem. Abs.*, 1963, 59, 3294b.
5. R. HIRING, *Proc. Conf. Appl. Phys. Chem. Methods, Chem. Anal.*, Budapest, 1966, 2, 35; *Chem. Abs.*, 1968, 68, 119018f.
6. E. JERCAN and L. DINOIU, *Anal. Chim. Acta*, 1970, 50, 166.
7. J. KORKISCH, "Modern Methods for the Separation of Rare Metal Ions", Pergamon Press, Oxford, 1969.
8. J. KORKISCH and S. S. AHLUWALIA, *Anal. Chim. Acta*, 1964, 31, 552.
9. J. KORKISCH and P. ANTAL, *Z. anal. Chem.*, 1960, 173, 126.
10. I. A. KORSHUNOV and G. M. SERGEV, *Radio Khimiya*, 1971, 13, 901; *Chem. Abs.*, 1972, 77, 27860g.
11. O. A. NIFTZEL, B. W. WESSING and M. A. DE SESA, *Anal. Chem.*, 1958, 30, 1182.
12. B. P. RADHAKRISHNA, *Anal. Chim. Acta*, 1952, 6, 351.
13. L. G. SILLEN and A. K. MARTFELL, "Stability Constants of Metal Ion Complexes", Spl. Pub. No. 17 (1964), Spl. Pub. No. 25 (1971), The Chemical Society, London.
14. F. W. E. STRELOW, *Anal. Chem.*, 1959, 31, 1201.
15. F. W. E. STRELOW, *Anal. Chem.*, 1961, 33, 1648.
16. F. W. E. STRELOW, *Anal. Chem.*, 1967, 39, 1454.
17. F. W. E. STRELOW and M. D. BOSHOFF, *Anal. Chim. Acta*, 1972, 62, 351.
18. V. F. TOROPOVA and Y. M. AZIZOVA, *Zh. Neorg. Khim.*, 1966, 11, 531; *Chem. Abs.*, 1966, 64, 18498a.
19. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", ELBS, Lowe & Brydone, London, 1968.
20. F. J. WELCHER, "The Analytical Uses of EDTA", D. Van Nostrand Co., N. J., 1967.
21. J. O. WINGET and R. E. LINDSTROM, U. S. Bur. Mines, Rep. Invest. No. 7175, 1968; *Chem. Abs.*, 1969, 70 25259z.
22. M. N. ZVEREVA, N. K. GORNOVSKAYA and L. T. KOCHURINA, *Vest. Leningr. Gos. Univ.* 1974, *Fiz. Khim.*, 153; *Anal. Abs.*, 1974, 27, 2464.
23. L. C. T. EUSEBIUS, A. MAHAN, A. K. GHOSH and A. K. DEY, *Indian J. Chem.*, 1977, 15A, 438.

# Effect of Substituents on the Relative Stabilities of Fe(III) Complexes of Substituted Salicylic Acids

M. C. CHATTOPADHYAYA

Chemical Laboratories, University of Allahabad, Allahabad-211 002

The stability constants of Fe(III) complexes of salicylic acid (SA) and ten of its substituted derivatives were determined at constant ionic strength using spectrophotometric measurements. Fe(III)-SA system was taken as a reference for comparing the difference in the acid dissociation constants ( $\Delta pK$ ) and stability constant values ( $\Delta \log K$ ). A parallelism is observed, though the magnitude of  $\Delta \log K$  is less than  $\Delta pK$ . While the substitution of an electron donor group increases the stability constant, it decreases the value of the apparent equilibrium constant. Similarly, the electron withdrawing groups have opposite effect on these two parameters. A hypsochromic shift in the absorption maximum ( $\lambda_{max}$ ) of 1:1 complex is observed when an electron withdrawing group is substituted in the nucleus of the reference ligand, whereas other groups (or an atom like Hg) give a bathochromic shift. However, exact correlation between  $\Delta \lambda_{max}$  and  $\Delta \log K$  or  $\Delta pK$  was not observed.

**IRON(III)**, due to its pronounced affinity for ligands containing oxygen, forms several coloured complexes with salicylic acids<sup>1-14</sup>. Thus, salicylic acid and sulphosalicylic acid have extensively been used as colorimetric reagent<sup>10-12</sup> for iron(III). Similar to Fe(III)-phenol complexes<sup>10-10</sup>, the colour of Fe(III)-salicylates depends on the various substituent groups attached to salicylates. The substitution effect influences the dissociation constants<sup>21</sup> and consequently the metal ligand stability constants. Hence, it was thought of interest to study the influence of substitution on the stability constants and on the absorption spectra of Fe(III)-salicylates. For this purpose, salicylic acid and ten of its substituted derivatives were chosen as ligands.

## Experimental

### Methods :


Reagent grade samples of the following salicylic acids were employed : (i) 2-Hydroxy benzoic acid (SA), (B.D.H.), (ii) 2-Hydroxy 3-methyl benzoic acid (oCA), (B.D.H.), (iii) 2-Hydroxy 4-methyl benzoic acid (mCA), (K and K Lab), (iv) 2-Hydroxy 5-methyl benzoic acid (pCA), (K and K Lab), (v) 2-Hydroxy 5-nitro benzoic acid (NSA), (Fluka), (vi) 2-Hydroxy 5-chloro benzoic acid (CSA), (Fluka), (vii) 2-Hydroxy 5-sulpho benzoic acid (SSA), (E. Merck), (viii) 2-Hydroxy 3-methyl 5-sulpho benzoic acid (SoCA), (ix) 2-Hydroxy 4-methyl 5-sulpho benzoic acid (SmCA), (x) 2-Hydroxy 3-sulpho 5-methyl benzoic acid (SpCA) and (xi) 2-Hydroxy 3-mercury 5-sulpho benzoic acid (HgSSA). The acids (viii) to (xi) were prepared as described earlier<sup>22</sup>.

All the acids were purified by several recrystallizations before use. Aqueous solutions were prepared by direct weighing, using CO<sub>2</sub>-free water. A stock solution of ferric chloride in dilute HClO<sub>4</sub>

was prepared and standardised titrimetrically against standard dichromate solution. CO<sub>2</sub>-free NaOH and HClO<sub>4</sub> solutions were used for bringing the pH at the desired value. Solutions of acids and alkalis were standardised by conventional titrimetric methods. NaClO<sub>4</sub> was used as a background electrolyte.

### Procedure :

In the pH range 1-3.5, the reaction between Fe(III) ion and salicylic acids (H<sub>2</sub>L) takes place as follows :



Charges are omitted for simplicity.

At constant pH, the apparent equilibrium constant can be expressed as :

$$K'_1 = \frac{[\text{FeL}]}{(\text{Fe}^0 - [\text{FeL}]) (\text{L}^0 - [\text{FeL}])} \quad \dots (2)$$

Fe<sup>0</sup> and L<sup>0</sup> being the initial concentration of iron(III) and ligand, respectively.

The stability constant is defined as

$$K_1 = \frac{[\text{FeL}]}{[\text{F}][\text{L}]} = K'_1 \phi \quad \dots (3)$$

where

$$\phi = 1 + \frac{[\text{H}]}{K_2^H} + \frac{[\text{H}]^2}{K_1^H K_2^H} \quad \dots (4)$$

K<sub>1</sub><sup>H</sup> and K<sub>2</sub><sup>H</sup> are the dissociation constants (concentration quotient) of ligand for carboxyl and phenolic groups, respectively. Knowing the values of K<sub>1</sub><sup>H</sup>, K<sub>2</sub><sup>H</sup> and [H], K<sub>1</sub> can be calculated from equation (3) at a particular ionic strength.

To find out K<sub>1</sub>' at a definite pH value (2.35 ± 0.05), the molar absorptivity,  $\epsilon$ , for ML species at

$\lambda_{max}$  was determined by elimination method<sup>22</sup>. Taking average value of  $\epsilon$ ,  $K'_1$  was calculated at ionic strength of 0.1 from

$$K'_1 = \frac{\epsilon A}{(\epsilon M^\circ - A)(\epsilon L^\circ - A)} \quad \dots (5)$$

where A is absorbance value at  $\lambda_{max}$ .

Using  $K'_1$  and  $K'_2$  at  $I=0.1$ , determined by the method as described earlier<sup>21</sup>,  $\log K_1$  was calculated. The relevant data of each system are summarised in Table 1.



0.1, the pH of the solution was varied in the range 1.4-3.2 by adding different amounts of HClO<sub>4</sub> and  $K_1$  values were determined. It is observed that there is no appreciable change in  $K_1$  values in the pH range 1.4-2.0, but above pH 2.0, the value decreases, probably due to the hydrolysis of the uncomplexed Fe(III). The effect due to hydrolysis can be accounted for by multiplying the right hand side of equation (3) by the correction factor<sup>24</sup>  $(1 + K_h/[H])$ , where  $K_h$  is the first stage hydrolysis constant for Fe(III), the value<sup>25</sup> of  $K_h$  being  $2.34 \times 10^{-4}$  at  $I=0.1$ . Consistency is then observed in

TABLE 1—DISSOCIATION CONSTANTS OF LIGANDS AND STABILITY CONSTANT OF Fe(III)-COMPLEX AT IONIC STRENGTH OF 0.1

Ligand	$pK_1^H$	$pK_2^H$	$\lambda_{max}$	$\epsilon_{max}$	$\log K'_1$	$\log K_1$	$\Delta pK$	$\Delta \log K'_1$	$\Delta \log K_1$	$\Delta \lambda_{max}$
SA	2.81	13.24	530	1660	4.70	16.19 (16.37)*	—	—	—	—
oCA	2.84	14.14	556	1660	4.34	16.75 (16.93)	-0.93	+0.36	-0.56	-26
mCA	2.94	13.54	534	1663	4.61	16.49 (16.67)	-0.43	+0.09	-0.30	-04
pCA	2.87	13.74	560	1852	4.62	16.05 (16.83)	-0.56	+0.08	-0.46	-30
NSA	1.90	9.89	496	2097	5.09	12.76 (12.94)	+4.26	-0.39	+3.43	+34
CSA	2.43	12.50	536	1909	4.76	15.25 (15.43)	+1.12	-0.06	+0.94	+06
SSA	2.44	11.90	506	1931	5.00	14.60 (14.78)	+1.71	-0.30	+1.59	+24
SoCA	2.54	12.58	530	2116	4.70	15.34 (15.52)	+0.93	0.0	+0.85	0
SmCA	2.67	12.33	510	2177	4.76	15.23 (15.41)	+1.05	-0.06	+0.96	+20
SpCA	2.52	13.47	546	2213	4.83	16.34 (16.52)	+0.06	-0.13	-0.15	-16
HgSA	2.43	12.03	514	2038	5.08	15.10 (15.28)	+1.50	-0.38	+1.09	+16

\*Values within parentheses include correction factor for hydrolysis of Fe(III)

At higher pH values (above 3.5), higher species of the complex are formed as evident from the study of isobestic points on absorption spectra at different pH values. The formation of higher species takes place as follows :



At pH 4 and above, considerable hydrolysis of Fe(III) takes place and consequently the stability constant values for higher species were not determined.

All pH measurements were made with a Universal pH meter (Redekis OP-204, Hungary) with glass and calomel electrodes. The absorption spectra were recorded on Perkin-Elmer 137 UV-Vis or SF-4 USSR spectrophotometers. Measurements were done at room temperature at  $25 \pm 1^\circ$

## Results and Discussions

To study the effect of pH on the stability constant of ML species, solutions of Fe(III) ion and the ligand were prepared by mixing them in a 1 : 1 ratio. While the ionic strength was maintained at

the values of  $K_1$  (the corrected values are shown within the parenthesis in Table 1).

For examining the effect of substitution, Fe(III)-SA system was taken as reference for comparison with other systems. The difference in the values of  $pK_1^H$ ,  $pK_2^H$ ,  $\log K'_1$ ,  $\log K_1$  and  $\lambda_{max}$  were expressed as  $\Delta pK$ ,  $\Delta \log K'_1$ ,  $\Delta \log K_1$  and  $\Delta \lambda$ , respectively (Table 1). It is noted that the sign (+ or -) of  $pK$  and the corresponding  $\Delta \log K_1$  is identical. However,  $\Delta \log K_1$  value is smaller in magnitude when compared to  $\Delta pK$ . A linear plot of  $\log K_1$  vs  $pK_1^H$ ,  $pK_2^H$  with a positive slope ( $< 1$ ) is obtained. However, a small departure is observed in the case of Fe(III)-SpCA systems.

Equation (3) can be written as :

$$\log K_1 = \log K'_1 + \log \phi \quad \dots (8)$$

$\phi$  is a function of  $K_1^H$  and  $K_2^H$  and hence at a particular pH the value of  $\log \phi$  increases with the increase in  $pK_1^H$ ,  $pK_2^H$  value. The value of  $\log K'_1$ , however, decreases with the increase in  $pK_1^H$ ,  $pK_2^H$ . Due to this opposing influence, the net increase (or decrease) in  $\log K_1$  value is significantly less than that of  $\Delta pK_1^H$ ,  $\Delta pK_2^H$ .

In equilibrium (1), both hydrogen as well as the metal compete for L. If the dissociation constant is large (smaller value of  $pK_1^H K_2^H$ ), [L] available for Fe(III) to form the complex is also more. Consequently at a given pH,  $\log K_1'$  is higher.  $\log K_1'$  not only indicates the stability of the complex, but includes the term which is competitive with (and appreciably so at lower pH) complex formation, whereas  $\log K_1$  is proportional to the free energy change for the reaction  $M+L=ML$ .

In the absorption spectra studies of 1 : 1 complex, with SA as the reference ligand, the following substitution effects can be noted.

Hypsochromic shift :  $-\text{NO}_2, -\text{SO}_3\text{H}$

Bathochromic shift :  $-\text{CH}_3, -\text{Hg}, -\text{Cl}$

Similar observations were made by Ackerman and Hesse<sup>30</sup> in the case of Fe(III)-phenol complexes. However, the extent of the effect decreases with the increasing number of substituents. For example, the substitution of methyl group in *meta* position shifts the  $\lambda_{\text{max}}$  of Fe(III)-phenol complex<sup>30</sup> by 15 nm, while in the case of Fe(III)-SA complex it is only 4 nm.

Since the electron acceptor groups shift the  $\lambda_{\text{max}}$  to shorter wavelengths and electron donating groups to longer wavelengths, an apparent correlation between  $\lambda_{\text{max}}$  and stability constant is expected. Table I also shows that  $\Delta\lambda$  and  $\Delta\log K_1$  values have the same sign. But in the case of Fe(III)-phenol complexes the stability has been regarded as the function of the electron density of phenolate oxygen while the  $\lambda_{\text{max}}$  depends on the difference in energy between anion and radical<sup>30</sup>. Similar may be the case with Fe(III)-salicylates and hence any exact correlation between  $\lambda_{\text{max}}$  and stability constant is unlikely. This is obvious from the fact that  $\text{CH}_3$  group acts as the strongest donor at *ortho* position while considering the  $pK_1^H$  and  $\log K_1$  values but the  $\lambda_{\text{max}}$  of Fe(III)-PCA complex is more than that of Fe(III)-oCA complex. Further the  $\lambda_{\text{max}}$  of Fe(III)-SA complex and Fe(III)-SoCA complex is the same but their stability constants differ considerably.

## Acknowledgement

The author is thankful to Professor W. A. E. McBryde, Department of Chemistry, University of Waterloo, Ontario, Canada for valuable suggestions.

## References

1. A. K. BANKO, *Zhur. Obshchei Khim. (U.S.S.R.)*, 1945, 15, 745, 748.
2. R. T. FOLEY and R. C. ANDERSON, *J. Amer. Chem. Soc.*, 1948, 70, 1195; 1950, 72, 5609.
3. A. AGREN, *Acta Chem. Scand.*, 1954, 8, 266, 1059, 1955, 9, 39.
4. A. AGREN, *Svensk. Kem. Tidskr.*, 1956, 68, 181, 185, 189.
5. D. D. PERRIN, *Nature*, 1958, 182, 74.
6. S. C. TRIPATHI and S. PRAKASH, *Z. Phy. Chem.*, 1958, 204, 326.
7. J. C. COLLECTER, *Ann. Chim. (Paris)*, 1960, 5, 415.
8. K. J. DIVEKAR, *J. Sci. Ind. Research*, 1962, 21B, 309.
9. S. S. KATYAR and V. B. S. CHAUHAN, *Indian J. Chem.*, 1963, 1, 94.
10. Z. L. ERNST and J. MENASHI, *Trans. Faraday Soc.*, 1963, 59, 1794.
11. M. V. PARK, *J. Chem. Soc. (A)*, 1966, 816.
12. K. OGAWA and M. TOBE, *Bull. Chem. Soc. Japan*, 1966, 39, 223, 227.
13. S. S. KATYAR and V. B. S. CHAUHAN, *J. Indian Chem. Soc.*, 1970, 47, 796.
14. W. A. E. MCBRYDE, J. L. ROHR, J. S. FENCINER and J. A. PAGE, *Can. J. Chem.*, 1970, 48, 2574.
15. M. C. CHATTOPADHYAYA, *J. Inorg. Nuclear Chem.*, 1976, 38, 569.
16. R. O. SCOTT, *Analyst*, 1941, 66, 142.
17. E. B. SANDEL, "Colorimetric Determination of Trace Metals", Interscience Publishers, New York, 1959.
18. Z. MARCZENKO, "Spectrophotometric Determination of Elements", Ellis Harwood Ltd., Chichester, 1976, p. 313.
19. E. F. W. WESS and W. R. BRODE, *J. Amer. Chem. Soc.*, 1934, 56, 1037.
20. V. G. ACKERMANN and D. HESSE, *Z. anorg. allg. Chem.*, 1970, 375, 77.
21. M. C. CHATTOPADHYAYA and R. S. SINGH, *Indian J. Chem.*, 1980, 19A, 141.
22. M. C. CHATTOPADHYAYA and R. S. SINGH, *Indian J. Chem.*, 1970, 8, 1126.
23. M. C. CHATTOPADHYAYA and R. S. SINGH, *Anal. Chim. Acta*, 1974, 70, 49.
24. H. S. FRANK and R. L. OSWALT, *J. Amer. Chem. Soc.*, 1947, 69, 1321.
25. L. G. SILLEN and A. R. MARTELL, "Stability Constant", Special Publication No. 17, The Chemical Society, London, 1964, p. 54.



# Computations of Apparent Formation Constants and Free Metal Ions in EGTA or EDTA Buffer Systems.

## Part—I : Effects of pH and Metal Concentration with Respect to Ligand

S. D. BISWAS and F. S. CHEBIB

Department of Oral Biology, Faculty of Dentistry, University of Manitoba,  
Winnipeg, Manitoba Canada R3E 0W3

Thermodynamic formation constants, ( $\log K$ ) (Bjerrum, Schwarzenbach and Sillen, 1957) for each of four hydrogen and metal bound with ethylene glycol-bis ( $\beta$ -amino ethyl ether) N,N'-tetra-acetic acid (EGTA) or metal bound with ethylenediamine tetra-acetic acid (EDTA) were used to compute the following apparent formation constants:  $K'_{M\cdot HEGETA}$ ,  $K'_{M\cdot HEDTA}$ ,  $K'_{M\cdot EGTA}$ , and  $K'_{M\cdot EDTA}$ . A computer program was developed to calculate these four apparent formation constants for any metal, given its thermodynamic constants, for the full pH range (0.1 to 14.0 at increments of 0.1). A more expanded computer program was developed to calculate, for the same pH range and for any given metal: ligand ratio, the free metal concentration in the solution, given the metal's thermodynamic constants. The program was utilized to calculate for Ca, Mn, Mg, etc. the exact amount of free metal ion for the full pH range and for metal to ligand ratios ranging from 0.01 to 0.1 at 0.01 intervals, for 0.10 to 0.90 at 0.10 intervals and for 0.90 to 0.99 at 0.01 intervals. It was possible to show that the free calcium increased by nearly two-fold when the pH increased by one-tenth order magnitude, i.e. 0.1 pH unit.

**C**ALCIUM is involved in several physiological processes viz., excitation-contraction coupling, action potential of muscle fibre membrane, regulation of enzyme action, etc.<sup>1-4</sup>. Highly selective calcium chelating agents e.g. ethylene glycol bis ( $\beta$ -amino ethyl ether) N,N'-tetra acetic acid (EGTA) or ethylenediaminetetraacetic acid (EDTA) are frequently used to regulate free calcium ion concentration in the reaction medium. To determine the calcium ion concentration accurately, the applications of exact conditional or apparent formation constants denoted by  $\log K'$  between the metal ion and the ligand are essential because the value of  $\log K'$  appears to change as a function of pH. These apparent formation constants are derived from a true or thermodynamic value which, for some metal ions, have been already determined by a number of different methods viz., radioactive tracer<sup>5</sup>, chelex partitions<sup>6,7</sup>, murexides<sup>8</sup>, arsenazo III<sup>9</sup>, membrane electrode<sup>10</sup> and more commonly by the pH titrations<sup>11</sup>. However, the use of selective membrane electrode is not very uncommon and this is carried out in the presence of varieties of buffer, e.g. imidazole, tris-maleate, phosphate, etc. The value of the true formation constant as determined by the later method agrees reasonably well with that of pH titration value as previously determined by Bjerrum *et al*<sup>12</sup>.

The apparent formation constants ( $K'_{Ca\cdot HEGETA}$ ,  $K'_{Ca\cdot HEDTA}$ ) are shown to be dependent on  $pH^{11-13}$ . For greater accuracy, both these constants have

simultaneously been used to calculate the free calcium ions in this buffer system. Similar calculations were carried out with the EDTA system as well

In the present investigation, the various formation constants, e.g.  $K'_{Ca\cdot EGTA}$ ,  $K'_{Ca\cdot HEGETA}$ ,  $K'_{Ca\cdot EDTA}$  and  $K'_{Ca\cdot HEDTA}$  have been calculated for the full pH range at 0.1 pH increments and used in computing the amount of free calcium ion concentration in solution of EGTA or EDTA buffer system.

A computer program was developed to calculate free metal ion concentration in a solution at varying pH increments (0.1 to 14.0 at 0.1) and for a given range of metal to ligand ratio. The listing of the source statements of the computer program is presented and the program was coded in Fortran and may be run on most medium to large computers\*. The theoretical background used for the program is explained in the next section.

### Procedures :


#### Theoretical background :

The reaction parameters involved in the calculation of free metal ions in Me-EGTA or Me-EDTA buffer system are dealt in two different sections :

(a) Determination of conditional or apparent formation constants ( $K'_{M\cdot HEGETA}$ ,  $K'_{M\cdot EGTA}$ ,  $K'_{M\cdot EDTA}$ )

\*Detailed program is available on request.

and  $K'_{MeHL}$ ) from respective thermodynamic constants, which have been determined earlier at known ionic strengths of 0.1 M KCl (20°)<sup>1,6,7</sup>. The conditional constants are pH-dependent. The EGTA or EDTA ligand is a tetrabasic acid and has four dissociable H ions, being able to associate with the ligand stepwise as shown in the following equations :



where  $L^{4-}$ ,  $HL^{3-}$ ,  $H_2L^{2-}$ ,  $H_3L^{-}$  and  $H_4L^0$  are different ionic species, L being the ligand (EGTA or EDTA) and  $K_{a1}$ ,  $K_{a2}$ ,  $K_{a3}$  and  $K_{a4}$  are formation (thermodynamic) constants. The formation constants have been determined under thermodynamic conditions where ionic strength is kept constant in the presence of 0.1 M KCl at 20° (see Table 1).

TABLE 1

Abbreviation for the constant in the text	Cation	Ligand	Thermodynamic EGTA $\log_{10}K$	EDTA $\log_{10}K$
$K_{a1}$	H <sup>+</sup>	$L^{4-}$	9.46	10.26
$K_{a2}$	H <sup>+</sup>	$HL^{3-}$	8.85	6.16
$K_{a3}$	H <sup>+</sup>	$H_2L^{2-}$	2.68	2.67
$K_{a4}$	H <sup>+</sup>	$H_3L^{-}$	~2.00	1.99
$K_{MeHL}$	Ca <sup>2+</sup>	$HL^{3-}$	5.33	3.51
$K_{MeL}$	Ca <sup>2+</sup>	$L^{4-}$	11.00	10.70


From Bjerrum, Schwarzenbach and Sillen (1957).

Applying the law of mass action, the above equation can be presented as follows :

$$\begin{aligned} [H_4L^0] &= K_{a4} [H_3L^{-}] \times [H^+] \\ [H_3L^{-}] &= K_{a3} [H_2L^{2-}] \times [H^+] \quad \dots (2) \\ [H_2L^{2-}] &= K_{a2} [HL^{3-}] \times [H^+] \end{aligned}$$

and  $[HL^{3-}] = K_{a1} [L^{4-}] \times [H^+]$

When bivalent metal such as calcium ligands with different ionic species, several calcium complexes are formed. They are shown as follows :



Hence,

$$[MeH_3L^{+}] = K_{MeH_3L} [H_3L^{-}] \times [Me^{2+}] \quad \dots (4)$$

$$[MeH_2L^0] = K_{MeH_2L} [H_2L^{2-}] \times [Me^{2+}] \quad \dots (5)$$

$$[MeHL^{-}] = K_{MeHL} [HL^{3-}] \times [Me^{2+}] \quad \dots (6)$$

$$\text{and } [MeL^{2-}] = K_{MeL} [L^{4-}] \times [Me^{2+}] \quad \dots (7)$$

where four different types of complexes ( $MeH_3L^{+}$ ), ( $MeH_2L^0$ ), etc. are likely to be formed and each complex will have corresponding formation constants.

The last two formation constants are used to compute conditional formation constants (Table 1), because the charge acquired by the plex is pH dependent and the metal-ligand complex with a positive charge or with a zero charge exists in negligible quantities at the physiological pH. Therefore, only conditional formation constants ( $K'_{MeHL}$  and  $K'_{MeL}$ ) have been used. ( $HL^{3-}$ ) and ( $L^{4-}$ ) are the ionic species prevalent at the physiological pH range. These have been calculated and will be published elsewhere.

The logarithms of the thermodynamic formation constants for the interaction of EGTA and EDTA with H ions and calcium as calculated by Bjerrum *et al.*<sup>10</sup> are given in Table 1.

(b). Calculation of free calcium ions in the EGTA and EDTA systems :

From equations (6) and (7), we have :

$$K_{MeHL} = [MeHL^{-}] / [HL^{3-}] \times [Me^{2+}] \quad \text{and } K_{MeL} = [MeL^{2-}] / [L^{4-}] \times [Me^{2+}]$$

At a given pH condition the conditional formation constants  $K'_{MeHL}$  and  $K'_{MeL}$  can be defined as follows :

$$\begin{aligned} K'_{MeHL} &= [MeHL^{-}] / [L_{total}] \times [Me^{2+}] \quad \text{and } K'_{MeL} = [MeL^{2-}] / [L_{total}] \times [Me^{2+}] \\ \text{where } L_{total} &= H_4L^0 + H_3L^{-} + H_2L^{2-} + HL^{3-} + L^{4-} \end{aligned}$$

$$\begin{aligned} \text{Now, } R_1 &= K_{MeHL} / K'_{MeHL} \\ &= \frac{[MeHL^{-}] \times [Me^{2+}] \times [L_{total}]}{[MeHL^{-}] \times [Me^{2+}] \times [HL^{3-}]} \end{aligned}$$

(where,  $K_{MeHL}$  is a thermodynamic constant and  $K'_{MeHL}$  is an apparent formation constant).

$$R_1 = \frac{[L_{total}]}{[HL^{3-}]}$$

Therefore,

$$\begin{aligned} R_1 &= \frac{[H_4L^0] + [H_3L^{-}] + [H_2L^{2-}] + [HL^{3-}] + [L^{4-}]}{[HL^{3-}]} \\ &= \frac{[H_4L^0]}{[HL^{3-}]} + \frac{[H_3L^{-}]}{[HL^{3-}]} + \frac{[H_2L^{2-}]}{[HL^{3-}]} + \frac{[L^{4-}]}{[HL^{3-}]} + \frac{[L^{4-}]}{[HL^{3-}]} \\ &= K_{a2} \cdot K_{a3} \cdot K_{a4} \cdot [H^+]^3 + K_{a2} \cdot K_{a3} [H^+]^2 + K_{a2} [H^+] + 1 + 1/[K_{a1} \cdot H^+] \quad \dots \end{aligned}$$

Similarly,

$$R_2 = K_{MeL} / K'_{MeL} = K_{a1} \cdot K_{a2} \cdot K_{a3} \cdot K_{a4} [H^+]^4 + K_{a1} \cdot K_{a2} \cdot K_{a3} [H^+]^3 + K_{a1} \cdot K_{a2} [H^+]^2 + K_{a1} [H^+] + 1 \quad \dots$$

Since,  $Me^{2+} + L_{total} = MeL_{total}$ , where  $K'_{MeL_{total}}$  is the conditional formation constant, therefore,

$$[K'_{MeHL} + K'_{MeL}] = K'_{MeL_{total}} = \frac{[MeL_{total}]}{[Me^{2+}] \times [L_{total}]} \quad \dots$$

$MeL_{total}$  is taken as approximately equal to

total cations present and the free ligand,  $L_{\text{total}}$ , as approximately equal to the total ligand minus  $\text{MeL}_{\text{total}}$ .

Equation (14) has been written as a quadratic equation to avoid the necessity of successive calculation of the free metal ions. Hence,

$$\text{Me}^{2+}[\text{free}] = -b \pm \sqrt{b^2 + 4K'_{\text{MeL}_{\text{total}}} [\text{MeL}_{\text{total}}]} \quad (15)$$

$$2K'_{\text{MeL}_{\text{total}}}$$

where,  $b = 1 + K'_{\text{MeL}_{\text{total}}} [L_{\text{total}} - \text{MeL}_{\text{total}}]$

### Results and Discussion

The conditional or apparent formation constants for calcium computed as a function of pH, are listed in Appendix II<sup>17</sup>.




Fig. 1a.




Fig. 1b.

The effects of both pH and the concentration of EGTA on free calcium ions are shown in Figs. 1a and 1b; similar effects with EDTA, another strong chelator of calcium, are shown in Figs. 2a and 2b. Although these studies have been carried out over the full range of pH, in the present graphs only effects are shown between a selected pH range [5.0-8.5], the range over which the pH of the reaction medium could vary physiologically, and at three different ratios of calcium to ligand [Me: EGTA or EDTA, 0.1, 0.5 and 0.9]. Results other than these are listed in Appendix II<sup>17</sup>.




Fig. 2a.




Fig. 2b.

From the Figs. 1a and 2a, it is quite evident that as calcium to ligand ratios increase, the free calcium ion concentration concomitantly increase as shown by the fall in  $p\text{Me}$  values. When Figs.

1a and 2a are compared as an effect of pH, the ligand EDTA seems to behave more effectively as a calcium chelator at least at pH 6.0 than at pH 8.0 and the effect is quite opposite when EGTA is used. Although, one would prefer to use EGTA over EDTA, when magnesium is also present as a part of the reactant, in addition to the presence of a large quantity of calcium ion; in such situations EGTA is more effectively used as a buffer<sup>14</sup>, since the magnesium ions could hardly shift the sigmoidal curves (see Figs. 1a or 2a), thus effecting the free calcium ion concentrations in solution significantly. However, in the presence of equally large amounts of magnesium ions one might expect a shift in the sigmoidal curve significant enough to cause a substantial change in the free calcium ion concentrations. One could replot the curve as an effect of magnesium by successive calculations, alternating with calcium and magnesium until a constant free calcium concentration is obtained. Of course, the prevalence of binding of either calcium or magnesium to the ligand will depend upon their respective formation constants. At least for the EGTA, the formation constants for calcium and magnesium are several magnitudes apart and this makes the EGTA a better buffer to be used when calcium and magnesium are both present in solution.

In EGTA, the effect of pH on free pCa is linear within a certain range of pH (between 5.0 and 8.0) as shown in Fig. 1a. However, in EDTA buffer it is slightly curved within the same pH range (see Fig. 2a). The ratio between calcium and ligand does not affect linearity.

Table 2 lists pCa values as computed by the present method, where different values for the formation constants for EGTA were used. These formation constants had been obtained through different techniques using several types of buffers at a constant ionic strength. What is important at this point is to emphasize that the method described by Owen<sup>9</sup> gave the same value of the formation constant [ $K_{CaEGTA}$ ] to the magnitude of  $10^{11.00}$ , as

previously obtained by the potentiometric titration (Schwarzenbach *et al.*, 1957). However, other techniques produced formation constants somewhat lower than those reported in the present table. This change in the formation constant will obviously affect the free pCa in solution. If the pCa values are compared with two different constants, one with  $10^{11.00}$  and the other with  $10^{10.81}$ , a substantial difference in the free calcium ions will be obtained. The difference between these two values could go as high as 50-70%.

Weber and Winicur<sup>10</sup> have used dissociation constant rather than the formation constant to calculate the free calcium in solution ( $K_{CaEGTA}$  being  $1.2 \times 10^{-6} M^{-1}$  at pH 6.6). This value was slightly less than what we have calculated with our system i.e., the value at pH 6.6 was  $1.29 \times 10^{-6} M^{-1}$ . This minor difference in the formation constant would lead to a fair amount of free calcium ion difference. It would be safer to use formation constant of the same pH, the pH at which the reaction is supposed to be carried out. Hence, it was essential to compute the formation constants for each of 0.1 pH-unit change. However, the larger the difference as one might conceivably see between the two values of pH 6.8 and 7.4, a much larger difference in the free calcium is likely to be obtained.

Owen<sup>9</sup> reported that the formation constant was independent of the buffer solution (e.g. imidazole, tris-maleate or phosphate), in agreement with the findings of Schwarzenbach *et al.*<sup>12</sup>, but he did not agree with the viewpoint of Ogawa<sup>2</sup> and Godt<sup>3</sup>, who stated that the formation constant somehow depended upon the type of the buffer used.

The effect of pH on the free calcium is quite substantial and this can be ascertained if free calcium ions are calculated at two different pH values. For example, at pH 7.0, the free calcium ions is in the order of  $2.301 \times 10^{-8} M^{-1}$ , whereas at pH 6.5, a 0.5 pH-unit less than the former, the free calcium concentration becomes of the order of

TABLE 2—COMPARISON OF THE FREE pCa AT DIFFERENT  $K_{CaEGTA}$  VALUES

Source	Method	KCl (M)	Buffer	MgCl (mM)	ATP (mM)	pH	$K_{CaEGTA} (M^{-1})$	$K_{CaHREGTA} (M^{-1})$	pCa
Schwarzenbach <i>et al</i> (1957)	pH/potentiometric titration	0.1	Phosphate	—	—	varying	$10^{11.00}$	$10^{10.81}$	7.475
Schwarzenbach <i>et al</i> (1957)	pH/potentiometric titration	0.1	Phosphate	—	—	varying	$10^{11.00}$	—	—
Ebaashi (1961)	Radioactive tracer	0.14	10 mM Tris-maleate	10	—	6.8	$10^{10.81}$	—	6.785
Briggs and Fleischman (1965)	Chelex partition	0.05	30 mM Imidazole	4	4	6.7	$10^{10.81}$	—	6.805
Ogawa (1968)	Murexide	0.1	20 mM Imidazole	0 or 10	—	6.8	$10^{10.81}$	—	6.825
Godt (1974)	Chelex partition	0.1 to 0.3	22.2 mM Imidazole	5	5	7.0	$10^{10.81}$	—	6.895
Dipolo <i>et al</i> (1976)	Arsenazo III	0.1	2mM TES	25	—	7.0	$10^{10.81}$	—	7.435
Owen (1976)	Ca-membrane electrode	—	Imidazole Tris-maleate or phosphate	—	—	—	$10^{11.00}$	—	7.475

TES, N-tris (hydroxymethyl) methyl-2-aminomethane sulfonic acid.

$2.28 \times 10^{-9} M^{-1}$ . At pH 7.5, the value further decreases by an order of magnitude ( $2.31 \times 10^{-9} M^{-1}$ ). Therefore, it is quite conceivable that the application of a more accurate formation constant for the calculation of the free calcium ions is important. Otherwise, a slight difference in the values of the formation constants may add a significant error in the determination of free calcium ions in solution. With a 0.2 pH-unit difference the calcium ions in solution could vary as high as 3 fold. To maintain a required amount of calcium ions in solution for carrying out a specific reaction, the use of Appendix II<sup>17</sup> is recommended to avoid error due to the pH difference.

The added advantage of the present determination is that both the formation constants ( $K'_{M+HL}$  and  $K'_{M+L}$ ) have been simultaneously plugged in the calculation and this will enable the calculation of the free calcium ions to a much greater degree of accuracy. In some instances the effect may not be very large where the pH is low (below pH 7.0), but the effect of the last constant might be pronounced when the pH reaches as high as 8.0 or above.

#### References

1. S. IMAI and K. TAKEDA, *J. Physiol.*, 1967, 190, 155.
2. Y. OGAWA, *J. Biochem.*, 1968, 64, 255.
3. S. EASASHI and M. ENDO, in "Progress in Biophysics and Molecular Biology", J. A. V. BUTLER and D. NOBLE, (Eds.), 1968, Vol. 18, p. 123, Pergamon Press, London.
4. C. CAPUTO, *J. Gen. Physiol.*, 1968, 51, 180.
5. R. E. GODT, *J. Gen. Physiol.*, 1974, 63, 722.
6. S. EASASHI, *J. Biochem.*, 1961, 50, 236.
7. F. N. BRIGGS and M. FLEISHMAN, *J. Gen. Physiol.*, 1965, 49, 131.
8. R. DIPOLO, J. REQUENA, F. J. BRINLEY, Jr., L. J. MULLINS, A. SCARPA and T. TUFFERT, *J. Gen. Physiol.*, 1976, 67, 433.
9. J. D. OWEN, *Biochim. Biophys. Acta*, 1976, 451, 321.
10. J. BJERRUM, G. SCHWARZENBACH and L. G. SILLEN, "Stability Constants, Part I. Organic Ligands", The Chemical Society, London, 1957, p. 76, 90.
11. H. PORTZEHL, P. C. CALDWELL and J. C. RUEGG, *Biochim. Biophys. Acta*, 1964, 79, 581.
12. L. G. SILLEN and A. E. MARTELL, "Stability Constants of Metal-Ion Complexes", Chemical Society Publication, 17, 1964, London.
13. A. RINGBOM, "Complexation in Analytical Chemistry, Chemical Analysis", 1963, Vol. 16, p. 334, Interscience Publications, New York.
14. C. C. ASHLEY and D. G. MOISESCU, *Proc. Physiological Soc.*, 1974, 112P.
15. G. SCHWARZENBACH, H. SPINN and G. ANDREGG, *Helv. Chim. Acta*, 1957, 40, 1886.
16. A. WEBER and S. WINICUR, *J. Biol. Chem.*, 1961, 236, 3198.
17. Appendix II is omitted to economize space; and can be obtained from the author (S.D.B.).

# Fe(III), Co(III), Cu(II) and Ni(II) Derivatives of Some New Monothio- $\beta$ -Diketones<sup>†</sup>

S. K. SAINI\*, V. D. GUPTA\*\* and R. C. MEHROTRA

Chemical Laboratories, University of Rajasthan, Jaipur-302 004

A few new monothio- $\beta$ -diketones, [RCSCH<sub>2</sub>COR', where R = Ph, Me; R' = C<sub>6</sub>H<sub>4</sub>Cl(p), C<sub>6</sub>H<sub>4</sub>Br(p), C<sub>6</sub>H<sub>4</sub>Me(p), C<sub>6</sub>H<sub>4</sub>OCH<sub>3</sub>(p)] have been synthesized and their metal complexes with Cu(II), Ni(II), Co(III) and Fe(III) were prepared. These were characterized by elemental analysis, IR, magnetic measurements, electronic spectra. Molecular weight determination in refluxing chloroform showed them to be monomeric.

**R**EPLACEMENT of an oxygen by a sulphur atom in  $\beta$ -diketones brings about considerable deviation in the properties of derived transition metal complexes<sup>1,2</sup>. This has led to considerable activity in the field of monothio- $\beta$ -diketonate derivatives<sup>3-5</sup>. We have synthesized a few new monothio- $\beta$ -diketones [RCSCH<sub>2</sub>COC<sub>6</sub>H<sub>4</sub>X(p); X = Cl, Br, Me or OMe] having chloro, bromo, methyl and methoxy substituents in the phenyl ring. The present paper deals with a number of their transition metal complexes of Fe(III), Co(III), Ni(II), Cu(II).

## Experimental

Diethyl ether (Alembic), methanol (BDH) and acetonitrile (BDH) were dried by the standard methods. Benzonitrile and acetophenones were distilled before use. Sodamide (May and Baker) was used as such. Sulphur was estimated gravimetrically as barium sulphate. Nickel, cobalt, copper and iron were estimated by standard methods<sup>6</sup>. Molecular weight was determined by semimicro Gallenkamp Ebulliometer using thermometer sensing in refluxing chloroform. Magnetic measurements were carried out with Gouy's balance at room temperature (308 K). Infrared spectra were recorded in the region 4000-200 cm<sup>-1</sup> on Perkin-Elmer Model 577 in nujol mulls using cesium iodide window. Electronic spectra were taken on Beckman DU-26 spectrophotometer in chloroform.

**Preparation of monothio- $\beta$ -diketones<sup>6</sup>:** 0.1 mole of substituted acetophenone was added to a stirred ethereal suspension of sodamide (0.2 mole) in a three necked round bottom flask (500 ml) fitted with a dropping funnel, mechanical stirrer and a condenser. After half an hour, an ethereal solution of ethyl thio ester (0.1 mole) was added dropwise with stirring at 0°. The reaction mixture was then stirred for 3-4 hr and was left overnight. The sodium salt of monothio- $\beta$ -diketone formed was poured in ice-cold water and extracted with solvent ether. The extract was treated with CO<sub>2</sub> to precipitate the monothio- $\beta$ -diketones. The solid red to yellow product was


filtered, washed with water and then crystallized from ether or ethanol.

**Preparation of nickel(II), copper(II) and cobalt(III) monothio- $\beta$ -diketonate derivatives:** A solution of Ni(II) or Cu(II) acetate in aqueous methanol (20 ml) was mixed with aqueous solution of monothio- $\beta$ -diketone in 1:2 molar ratio. The precipitated complex was filtered, washed with water and crystallized from dry methanol or acetonitrile. For the preparation of Co(III) complexes, Co(II) acetate was reacted with the ligand in acetonitrile (Table 2).


**Preparation of iron(III) monothio- $\beta$ -diketonate derivatives:** On addition of aqueous solution of iron(III) chloride to a hot solution of monothio- $\beta$ -diketones in methanol (1:3 molar ratio), a dark brown compound was precipitated which was filtered, washed with water and crystallized from dry methanol (Table 2).

## Results and Discussion

The new monothio- $\beta$ -diketones were prepared by the following route:



The thione ester can be easily prepared from the corresponding nitrile:



[R = Me or Ph; R' = C<sub>6</sub>H<sub>4</sub>X(p);  
X = Cl, Br, Me or OMe]

All these ligands were prepared in good yields as red and orange solids (Table 1) and were characterized.

<sup>†</sup> Dedicated to Prof. A. K. Dey on his sixtieth birthday.


Present Address: \* Scientist, Defence Material & Stores Research & Development Estt., Post Box No. 320, Kanpur-208 013.  
\*\* Chemistry Department, Faculty of Science, Banaras Hindu University, Varanasi.

TABLE 1—MONOTHIO- $\beta$ -DIKETONES,  $\text{RCSCH}_2\text{COC}_6\text{H}_4\text{X}(p)$  USED IN THE PRESENT WORK


R	X	m.p. (°C)	Yield (%)	S% Found (Calcd.)
Ph	Cl	115	62	11.4 (11.6)
Ph	Br*	129-30	58	9.9 (10.0)
Ph	Me*	124-25	61	12.6 (12.6)
Ph	OMe	121	62	11.8 (11.8)
Me	Cl	38-39	54	15.1 (15.0)
Me	Br	88-89	42	12.4 (12.4)
Me	Me*	67-68	48	16.6 (16.7)
Me	OMe*	56-57	50	15.5 (15.4)

\*Reported earlier; ref. 7.

The ir spectra of these monothio- $\beta$ -diketones<sup>1-3</sup> display characteristic absorptions in the ranges 1585-1600, 1550-1570 and 1240-1260  $\text{cm}^{-1}$  due to  $\nu\text{C}=\text{O}$ ,  $\nu\text{C}=\text{C}$  and  $\nu\text{C}-\text{S}$ , respectively. In analogy with other thio- $\beta$ -diketones<sup>1-3</sup>, these may exist as an equilibrium mixture of tautomeric enol and enethiol forms which interconvert rapidly by the intramolecular chelate proton transfer<sup>4</sup>.



A few latter transition metal complexes of the type  $\text{M}(\text{RCSCHCOC}_6\text{H}_4\text{X}-p)_n$ . ( $\text{M}=\text{Fe, Co, n}=3$ ;  $\text{M}=\text{Cu, Ni}$ ;  $n=2$ ) were synthesized from the corresponding acetate or chloride in methanol or acetonitrile and crystallized from these solvents:



A similar reaction of cobalt(II) acetate led to the synthesis of the *tris* derivatives only due to the oxidation of cobalt(II) to cobalt(III) in aqueous media by the atmospheric oxygen. All the metal complexes were from dark brown to dark red solids with sharp melting points, soluble in chloroform and benzene. Molecular weight determinations, carried out in a few representative cases showed them to be monomeric in refluxing chloroform (Table 2).

The ir spectral characteristics of the transition metal monothio- $\beta$ -diketonates were consistent with the conjugated chelate structure, in harmony with the observation of previous workers<sup>1-3</sup>. Of the more significant bands, these metal complexes had two characteristic bands above the 1480  $\text{cm}^{-1}$ . The band of higher frequency at 1595-1555  $\text{cm}^{-1}$  has been assigned to  $\nu\text{C}-\text{O}$  vibrations, while the band of lower frequency at 1516-1490  $\text{cm}^{-1}$  was due to  $\nu\text{C}-\text{C}$  vibration of phenyl ring. The  $\nu\text{C}-\text{S}$  vibration was observed in the region 1235-1255  $\text{cm}^{-1}$ . The metal-oxygen and metal-sulphur frequencies could be noted at 440-490 and 345-290  $\text{cm}^{-1}$  regions, respectively.

Magnetic susceptibilities of some of the complexes were measured with Gouy's balance (Table 3).

 TABLE 2—ANALYTICAL DATA AND PROPERTIES OF THE TRANSITION METALS MONOTHIO- $\beta$ -DIKETONATE DERIVATIVES

Metal	R	$\text{C}_6\text{H}_4\text{X}-p$	n	Nature	m.p. (°C)	Metal % Found (Calcd.)	Sulphur % Found (Calcd.)	Mol. Wt. Found (Calcd.)
Ni	Me	$\text{CH}_3$	2	Dark brown solid	216	13.2 (13.3)	14.9 (14.5)	—
Ni	Me	Br	2	Brown solid	224	10.9 (10.3)	11.9 (11.2)	540 (571)
Ni	Ph	OMe	2	Brown solid	208	9.7 (9.8)	10.0 (10.7)	—
Cu	Me	Cl	2	Red brown solid	176	13.3 (13.1)	13.3 (13.2)	460 (487)
Cu	Ph	$\text{CH}_3$	2	Brown solid	193	11.8 (11.15)	11.5 (11.2)	—
Cu	Ph	Br	2	Brown solid	164	9.1 (9.1)	9.6 (9.1)	688 (699)
Cu	Ph	OMe	2	Brown solid	182	10.0 (10.6)	10.8 (10.6)	—
Co	Ph	Br	3	Red brown solid	214	5.5 (5.8)	9.3 (9.5)	1002 (1013)
Co	Ph	Cl	3	Red brown solid	156	6.6 (6.7)	10.8 (10.9)	—
Co	Me	Cl	3	Red solid	164	8.2 (8.5)	13.7 (13.8)	688 (693)
Fe	Ph	Br	3	Dark green solid	178	5.8 (5.5)	9.8 (9.5)	—
Fe	Me	Br	3	Green solid	157	6.2 (6.8)	12.0 (11.7)	—
Fe	Me	Cl	3	Green solid	210	8.3 (8.1)	14.1 (13.9)	692 (690)

TABLE 3—MAGNETIC MOMENTS OF THE METAL COMPLEXES;  
M(RCSCHCOR)<sub>n</sub>

Metal	R	R'	$\mu_{eff}$ B.M.
Fe(III)	Me	C <sub>6</sub> H <sub>5</sub> Br- <i>p</i>	5.20
Fe(III)	Ph	C <sub>6</sub> H <sub>5</sub> OCH <sub>3</sub> - <i>p</i>	5.15
Cu(II)	Ph	C <sub>6</sub> H <sub>5</sub> Cl- <i>p</i>	2.08
Cu(II)	Me	C <sub>6</sub> H <sub>5</sub> Cl- <i>p</i>	1.97
Cu(II)	Ph	C <sub>6</sub> H <sub>5</sub> Br- <i>p</i>	1.95
Cu(II)	Ph	C <sub>6</sub> H <sub>5</sub> CH <sub>3</sub> - <i>p</i>	1.80

The complexes of nickel(II) with these monothio- $\beta$ -diketones are found to be diamagnetic like other nickel complexes of other monothio- $\beta$ -diketones<sup>9</sup>. Replacement of one oxygen atom in  $\beta$ -diketone by sulphur causes a change in bond type of the respective nickel(II) complexes from spin free to spin paired. Attempts to prepare cobalt(II) complexes which would be spin paired were unsuccessful. The quick oxidation of cobalt(II) to cobalt(III) also occurs with certain soft bases such as NO<sub>2</sub><sup>-</sup>, CN<sup>-</sup>, etc<sup>10</sup>. It is of interest to observe that iron(III) complexes with these ligands are spin free like those with other monothio-diketonates. The thio- $\beta$ -diketonate complexes of copper(II) were found to have magnetic moments of 1.8-2.0 B.M. indicating the presence of one unpaired electron.

Most of the published work on the electronic spectra of metal complexes of monothio- $\beta$ -diketones has been reported on the nickel(II) chelates. In the case of nickel complexes reported here, the positions and intensity of the bands [630-640 nm (M<sub>d</sub>-M<sub>d</sub>); 520-530 nm (M<sub>d</sub>-L <sub>$\pi$</sub> ); 405-430 nm (L <sub>$\pi$</sub> -M<sub>d</sub>); 300-338 nm (L <sub>$\pi$</sub> -L <sub>$\pi$</sub> )] are in good agreement with the values of other nickel complexes reported in the literature<sup>9</sup>.

#### Acknowledgement

One of the authors (S.K.S.) is thankful to the C.S.I.R., New Delhi for a Research Fellowship.

#### References

1. S. E. LIVINGSTONE, *Coord. Chem. Rev.*, 1971, 7, 59
2. M. COX and J. DARKEN, *Coord. Chem. Rev.*, 1971, 7, 29.
3. R. L. MARTIN, *Prog. Inorg. Chem.*, 1980, 27, 213.
4. E. UHLEMANN and H. MÜLLER, *Angew. Chem. Intern. Ed., Eng.*, 1965, 4, 154.
5. A. I. VOGEL, "Text Book of Quantitative Inorganic Analysis", ELBS, 1979.
6. E. UHLEMANN and PH. THOMAS, *J. Prakt. Chem.*, 1966, 34, 180.
7. L. CARLSEN and F. DUUS, *Synthesis*, 1977, 256
8. L. CARLSEN and F. DUUS, *J. Amer. Chem. Soc.*, 1978, 100, 281.
9. S. H. H. CHASTON, S. E. LIVINGSTONE, T. N. LOCKEYER, V. A. PICKLES and I. S. SHANNON, *Aust. J. Chem.*, 1965, 18, 673.
10. S. E. LIVINGSTONE, *Quart. Rev.*, 1965, 19, 386.



# Formation Constants and Thermodynamic Parameters of 2-Amino-3-hydroxypyridine with Some Bivalent Metal Ions

H. L. KALRA\*, J. S. MALIK and (Miss) VERSHA GERA

Department of Chemistry, Kurukshetra University, Kurukshetra-132 119

The proton-ligand stability constants of 2-amino-3-hydroxypyridine (AHP) and formation constants of its chelates with Cd(II), Co(II), Ni(II), Zn(II) and Cu(II) have been determined, using Calvin-Bjerrum pH titration technique as modified by Irving and Rossotti, in aqueous media at different ionic strengths and temperatures. The stability constants of the complexes follow the order  $\text{Cu(II)} > \text{Zn(II)} > \text{Ni(II)} > \text{Co(II)} > \text{Cd(II)}$ , which is in accordance with Irving Williams order.

Thermodynamic stability constants ( $\log K_{\text{st}}^{\text{H}^+}$ ) of these metal complexes have been obtained by extrapolating the experimental values to zero ionic strength. The values of overall changes in  $\Delta G^\circ$ ,  $\Delta H^\circ$  and  $\Delta S^\circ$  accompanying complexation reactions have also been calculated.

THE stability constants of metal complexes with *o*-aminophenol have been determined<sup>1</sup>. It was of interest to determine the stability constants of corresponding heterocyclic analogue of *o*-aminophenol, viz., 2-amino-3-hydroxypyridine (AHP). Moreover, survey of literature reveals that no work has been reported on the stability constants of this ligand with bivalent metal ions.

In the present investigation, stability constants and thermodynamic parameters of some bivalent metal complexes with AHP have been determined in aqueous media at different ionic strengths and temperatures by potentiometric method.

## Materials and methods :

A pure sample of 2-amino-3-hydroxypyridine (AHP) was obtained from Aldrich Chemical Co., USA and its solution was prepared in double distilled water without further purification. Solutions of bivalent metal ions Cu(II), Ni(II) and Co(II) were prepared by dissolving their nitrates while those of Zn(II) and Cd(II) were prepared from corresponding sulphate salts. All the solutions were standardised by gravimetric methods<sup>2</sup>. Potassium nitrate (2 M) was used to maintain the appropriate ionic strengths (0.05 M, 0.10 M, 0.15 M and 0.2 M). KOH solution was prepared by washing KOH pellets with boiling conductivity water and finally dissolving it in  $\text{CO}_2$ -free conductivity water. It was standardised against oxalic acid potentiometrically. Nitric acid solution was prepared by diluting a calculated amount of the acid with conductivity water and standardisation against KOH solution.

## Apparatus :

A digital pH meter (model pH 5651) manufactured by Electronic Corporation of India Limited, Hyderabad, with combination electrode CA-11

(0-14 pH range) was used for pH measurements. The pH meter was standardised with buffer solutions of pH 4.00 and pH 9.20. The temperature was maintained by running water with the help of water circulating pump from a thermostat through a double walled beaker.

## Procedure :

The experimental technique of Bjerrum and Calvin<sup>3-4</sup> as modified by Irving and Rossotti<sup>5</sup> was used to determine  $\bar{n}$  and  $pL$  values.

Three solutions, A :  $4 \times 10^{-3} M \text{ HNO}_3$ , B :  $4 \times 10^{-3} M \text{ HNO}_3 + 3 \times 10^{-3} M$  ligand, C :  $4 \times 10^{-3} M \text{ HNO}_3 + 3 \times 10^{-3} M$  ligand +  $5 \times 10^{-4} M$  metal (total-volume 50 ml in each case), were prepared.

The concentration of the common ingredients were the same in all the cases. An appropriate quantity of  $\text{KNO}_3$  (2.0 M) was added to maintain the desired ionic strength.

The mixtures A, B and C were individually titrated against standard KOH solution (0.4 M). The pH measurements were done in an atmosphere of oxygen-free nitrogen at different ionic strengths and temperature. A graph between pH and the volume of alkali added was plotted. The three titration curves so obtained were referred to as (i) acid, (ii) ligand and (iii) complex titration curves, respectively.

## Results and Discussion

To calculate the proton-ligand stability constants, the values of  $\bar{n}_A$  were calculated at different pH values by noting  $v'$  from acid titration curve and  $v''$  from ligand titration curve for the same pH using the following equation :

$$\bar{n}_A = \left\{ \gamma^{\text{H}^+} C_L + \frac{(v' - v'')(N^0 + E^0)}{(V^0 + v'')} \right\} / \gamma^{\text{H}^+} C_L \dots (1)$$

\* Author for correspondence.

TABLE 1—PROTONATION CONSTANT OF THE LIGAND AND STEPWISE AND OVERALL METAL-LIGAND STABILITY CONSTANTS AT VARIOUS IONIC STRENGTHS AND TEMPERATURES

Metal ion	$\log K_n^H / \log K_n$	Temp. 20°					Temp. 30°	Temp. 40°
		$\mu = 0.0$	$\mu = 0.05$	$\mu = 0.1$	$\mu = 0.15$	$\mu = 0.20$	$\mu = 0.10$	$\mu = 0.10$
Cd <sup>2+</sup>	$\log K_n^H$	—	9.50	9.35	9.24	9.15	9.21	9.07
	$\log K_n^H$	—	6.01	5.89	5.79	5.71	5.74	5.62
	$\log \beta_n^H$	—	15.51	15.24	15.03	14.86	14.95	14.69
	$\log K_1$	3.48	3.28	3.19	3.13	3.06	3.12	3.01
	$\log K_2$	3.18	3.04	2.97	2.93	2.89	2.87	2.74
Co <sup>2+</sup>	$\log \beta_2$	6.66	6.32	6.16	6.06	5.95	5.99	5.75
	$\log K_1$	3.58	3.37	3.26	3.19	3.12	3.16	3.05
	$\log K_2$	3.12	2.92	2.87	2.83	2.79	2.80	2.71
Ni <sup>2+</sup>	$\log \beta_2$	6.70	6.29	6.13	6.02	5.91	5.96	5.76
	$\log K_1$	3.66	3.44	3.32	3.25	3.18	3.21	3.10
	$\log K_2$	3.04	2.98	2.89	2.84	2.80	2.82	2.75
Zn <sup>2+</sup>	$\log \beta_2$	6.70	6.42	6.21	6.09	5.98	6.03	5.85
	$\log K_1$	4.36	4.05	3.90	3.80	3.71	3.77	3.64
	$\log K_2$	3.95	3.63	3.48	3.37	3.29	3.36	3.26
Cu <sup>2+</sup>	$\log \beta_2$	8.31	7.68	7.38	7.17	7.00	7.13	6.90
	$\log K_1$	6.85	6.44	6.23	6.16	5.95	6.02	5.74
	$\log K_2$	5.08	4.57	4.38	4.21	4.02	4.20	4.06
	$\log \beta_2$	11.93	11.01	10.61	10.37	9.97	10.22	9.80

The proton-ligand stability constants were obtained from the formation curves so obtained and refined by various computational techniques<sup>6</sup>.

The following equations (2) and (3) were used to calculate the average number of ligands attached per metal ion ( $\bar{n}$ ) and the negative logarithms of the free ligand concentration ( $pL$ ) at a particular  $pH$ .

$$\bar{n} = \frac{(v'' - v') (N^0 + E^0)}{(V^0 + v') \cdot \bar{n}_A \cdot T^0 C_M} \quad (2)$$

$$pL = \log_{10} \left[ \frac{\sum_{n=0}^{\infty} \beta_n^H \left( \frac{1}{\text{anti log } pH} \right)^n}{T^0 C_L - \bar{n} T^0 C_M} \times \frac{V^0 + v''}{V^0} \right] \quad (3)$$

The terms used in equations (1), (2) and (3) have their usual meanings.

Metal-ligand formation constants were calculated from the formation curves obtained by plotting  $\bar{n}$  against  $pL$ . The formation constants thus obtained were refined using various computational techniques<sup>6</sup> viz. (1) correction term method, (2) pointwise calculation method, (3) least squares treatment (simultaneous equations method), and (4) least squares treatment (curve fitting method) and are given in Table 1.

The thermodynamic formation constants were obtained by the extrapolation to zero ionic concentration from the plots of  $\log K$  versus  $\sqrt{\mu}$  and are given in Table 1.

#### Thermodynamic parameters :

The values of overall change in free energy ( $\Delta G^\circ$ ), enthalpy ( $\Delta H^\circ$ ) and entropy ( $\Delta S^\circ$ ) accompanying complexation reactions have been determined using the temperature coefficient and Gibbs-Helmholtz<sup>7</sup> equation.

The value of  $\Delta G^\circ$  was obtained from the expression  $\Delta G^\circ = -RT \ln \beta$  and  $\Delta H^\circ$  was determined

with the help of an isobar equation

$$\frac{d \ln \beta}{dT} = \frac{\Delta H^\circ}{RT^2}$$

which may be rewritten as

$$\frac{d(\log \beta)}{d(1/T)} = \frac{-\Delta H^\circ}{4.57}$$

The values of  $\log \beta$  obtained at different temperatures were plotted as a function of  $1/T$ . The gradient of the tangent drawn at the point corresponding to 30° was determined and equated to  $\frac{-\Delta H^\circ}{4.57}$ . The value of  $\Delta H^\circ$  was thus obtained.  $\Delta S^\circ$  was then evaluated from the relation

$$\Delta S^\circ = \frac{\Delta H^\circ - \Delta G^\circ}{T}$$


The values of  $\Delta G^\circ$ ,  $\Delta H^\circ$  and  $\Delta S^\circ$  are given in Table 2.

TABLE 2—THERMODYNAMIC PARAMETERS OF BIVALENT METAL COMPLEXES WITH AHP  $\mu = 0.1M$ 

Metal ion	$-\Delta G^\circ$ kcal/mol <sup>-1</sup> (20°)	$-\Delta H^\circ$ kcal/mol <sup>-1</sup>	$\Delta S^\circ$ cal/deg <sup>-1</sup> mol <sup>-1</sup> (30°)
Cd <sup>2+</sup>	8.21	8.39	-0.26
Co <sup>2+</sup>	8.26	8.39	-0.54
Ni <sup>2+</sup>	8.41	8.39	-0.096
Zn <sup>2+</sup>	9.87	9.65	0.86
Cu <sup>2+</sup>	14.27	14.26	-0.36

In the initial stages of the titration, the ligand curve is shifted to the left (or above) of the acid curve due to the basic properties of the amino group which accepts a proton from the strongly acidic medium.

The protonated species formed dissociates in two steps as shown below :



Both 1 : 1 and 1 : 2 complexes could be studied in all the cases. It is evident from Table I that  $\log K_1$  and  $\log K_2$  values at 20° are higher than their values at 30 and 40° with all the metals indicating that low temperature is favourable for complex formation. The stability constants follow the trend  $Cu^{2+} > Zn^{2+} > Ni^{2+} > Co^{2+} > Cd^{2+}$  at all the ionic strengths and temperatures. This is in accordance with the Irving Williams' order.

All the complexes were found to be enthalpy stabilized. The negative value of  $\Delta H^\circ$  in the systems ensure that the reactions are exothermic. The entropy factor has been found to be favourable only in the case of  $Zn^{2+}$  complex.

#### Acknowledgement

The authors thank Professor V. Yativrajam, Chairman, Department of Chemistry, Kurukshetra

University, Kurukshetra for facilities. One of them (J.S.M.) is thankful to the U.G.C., New Delhi for the award of a Teacher-Fellowship under FIP and to the Jat Education Society, Rohtak for grant of leave.

#### References


1. "Stability Constants of Metal-Ion Complexes", compiled by A. E. MARTIN (Organic ligands), and L. G. SILLEN (Inorganic ligands). The Chemical Society, Special Publication No 17, London, 1964.
2. A. I. VOGEL, "A Text Book of Quantitative Inorganic Analysis", Longman Green, London, 1962.
3. J. BJERRUM, "Metal Ammine Formation in Aqueous Solution", P. Haase & Sons, Copenhagen, 1941.
4. M. CALVIN and K. W. WILSON, *J. Amer. Chem. Soc.*, 1945, 67, 2003.
5. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1954, 2904.
6. H. M. IRVING and H. S. ROSSOTTI, *J. Chem. Soc.*, 1953, 3397.
7. K. B. YATSIMIRSKII and V. P. VASILEV, "Instability Constants of Complex Compounds", Pergamon Press, Oxford, 1960.
8. H. IRVING and R. J. P. WILLIAMS, *J. Chem. Soc.*, 1953, 3192.

# Tetravalent Manganese as an Oxidising Agent

S. B. RAO and B. R. SANT\*

Regional Research Laboratory, Bhubaneswar-751 013

**T**ETRAVALENT manganese in the form of manganese dioxide is known as an oxidising agent for the oxidation of hydrochloric acid to chlorine, Fe(II) to Fe(III) and oxalic acid to carbon dioxide and water.  $MnO_2$  by itself does not dissolve easily in sulphuric acid but in the presence of reductants it can be rapidly brought into solution. Stauter and Um<sup>1</sup> in a recent patent suggested the possibility of employing manganese dioxide ores for converting Cr(III) of the chrome ore to Cr(VI). However, there are no reports on the use of Mn(IV) solution as an oxidimetric reagent till recently<sup>2</sup>, due to the difficulties in the preparation of a fairly stable solution. During the study of the kinetics of the decomposition of permanganate in sulphuric acid by spectrophotometric methods, Mandal and Sant<sup>3</sup> reported that in 8-11 M sulphuric acid, Mn(IV) is formed according to the equation :



The manganese(IV) solution thus formed is reasonably stable, and the change in normality of a 0.1 N solution is only 0.1-0.2 percent per day at 25°. Such a solution is a powerful oxidising agent and the standard potential of the redox system  $Mn(IV) + 2 e \rightleftharpoons Mn(II)$  is 1.577 V.

*Manganese(IV) sulphate as an oxidimetric reagent :*

This reagent has been used for the titrimetric determination of a number of reducing agents. For instance Fe(II), V(IV), U(IV) and Mo(V)<sup>4</sup> are quantitatively oxidised respectively to Fe(III), V(V), U(VI) and Mo(VI) in 1-2 M sulphuric acid and titrations can be performed using ferroin as the indicator. Oxalate is oxidised to carbon dioxide and water in 1-2 M sulphuric acid and titrations with Mn(IV) are possible at 70°. Arsenite is quantitatively oxidised to arsenate by Mn(IV) in hydrochloric acid medium with iodide ion as the catalyst. Mandal<sup>5</sup> reported the use of iodide or iodate as a catalyst, with Mn(IV) colour itself indicating the end point. It has been found by the present authors that with iodine monochloride as a catalyst methyl orange could be used as an indicator.

Manganese(IV) sulphate solution quantitatively oxidises antimony(III) to antimony(V) in the presence of an halogen acid and titrations can be carried out using methyl orange as an indicator. Methyl orange is a better indicator than ferroin<sup>6</sup> in a semiaqueous solution containing hydrochloric acid and iodine monochloride. Further, ferroin end points are not reliable due to the fact that ferroin forms insoluble complex with Sb(V)<sup>7</sup>. In sulphuric acid medium and in the absence of chloride, both As(III) and Sb(III) reduce manganese(IV) to manganese(III) and indirect titrations by adding excess manganese(IV) and back titrations with iron(III) show good agreement with those of direct titrations.

*Manganese dioxide as an oxidation-decomposition agent :*

It has been observed that  $MnO_2$  can be conveniently used as a decomposition agent for the analysis of refractory ores like chromite and sulphide ores like chalcopyrite. Either the synthetically<sup>8</sup> prepared  $MnO_2$  or the naturally occurring manganese ore can be employed for the purpose.

## Acknowledgement

The authors are thankful to the Director, Regional Research Laboratory, Bhubaneswar, for permission to publish the paper.

## References

1. J. C. STAUTER and R. T. UM, *U. S. Patent*, No. 4029734 (Cl. 423-54 C 01 G 37/00), 14 June 1977.
2. S. K. MANDAL and B. R. SANT, *Talanta*, 1976, 23, 485.
3. S. K. MANDAL and B. R. SANT, *J. Inorg. Nuclear Chem.*, 1977, 39, 2233.
4. O. GRAUBE and K. HUBERICH, *Z. Elektrochem.*, 1923, 29, 8.
5. S. K. MANDAL and B. R. SANT, *Indian J. Chem.*, 1980, 19A, 389.
6. N. RUKMINI, V. S. N. P. KAVITHA and K. RAMA RAO, *The Analyst*, 1979, 104, 1201.
7. G. G. RAO and S. G. VISWANATH, *Anal. Chim. Acta*, 1977, 94, 174.
8. P. W. SELWOOD, R. P. EISCHENS, M. ELLIS and K. WETHINGTON, *J. Amer. Chem. Soc.*, 1949, 71, 3039.

## ERRATA

JICS, LIX, September 1982, pp. 1044-1046

Paper entitled: "Studies in Triethylamine-Water. Part—IV: Predicting the Solubilities of Triethylamine and Water" by S Thangavel and Mathew J Moollel

The figures on page 1045 were not correct. The correct figures are as follows.




Fig. 1. Variation of the terms A, B, C and D of equation (III) with temperature.





Fig. 2. Variation of  $g^M$  with solvent composition  $(X)$ .



\*F. Kohler and O. K. Rice, *J. Chem. Phys.*, 1957, 26, 1614

Fig. 3. Solubility curve of  $\text{Et}_3\text{N}-\text{H}_2\text{O}$  system.

# Journal of the Indian Chemical Society

Vol. 59, 1982

## AUTHOR INDEX

### "A"

- Abdel-Rahman, A. E. *See* A. M. Mahmoud 675
- Abou-Taleb, Salah A. *See* M. A. Zayed .. 1013
- Aboul-Enein, M. N. *See* A. M. El-Naggar . 783
- Adewuyi, Victoria *See* Lilitana Ilcheva 1352
- Adhikari, M. *See* Saroj Kumar Sanyal 460
- Aditya, S. *See* A. K. Mandal 1390
- Aditya, S. *See* Ansuman Roy . 585
- Agarwal, Anita *See* W. U. Malik 1316
- Agarwal, Kanchan *See* J. S. Shukla 779
- Agarwal, (Miss) S. *See* Wahid U Malik . 1060
- Agarwal, S. C. *See* N. Prasad .. 980
- Agarwal, Vipin Kumar *See* Y. D. Kulkarni 380
- Agarwala, B. V. *See* Bhagwat Singh 29, 1130
- Agarwala, B. V. *See* P. L. Maurya 1400
- Aggarwal, Anita Rani *See* Harish Kumar Arora . 347
- Aggarwal, R. C. ; B. Singh and M. K. Singh—  
Preparative and Structural Studies on  
Bimetallic Tetradiithiocarbamates of Some  
Bivalent 3d-Metal Ions 269
- Agnihotri, P. W. ; V. R. Pasarkar and G.  
Bagavant—Synthesis of Pericarbonyl  
Lignans and Their Analogues 869
- Agrawal, S. *See* R. Sahai 853, 1121
- Agrawal, Sushma *See* Ajay K. Jain ... 106
- Ahmad, Iqbal *See* Mohd. Kamil 1199
- Ahmad, N. *See* Syed A. Nabi . 1200
- Ahmed, M. G. ; S. A. Ahmed and M. K.  
Alam—Reaction of Ninhydrin with  
Aromatic Amines and Ureas 806
- Ahmed, S. A. *See* M. G. Ahmed 806
- Ahmed, Shakti Rais *See* Anila Thusoo 1007
- Alaka, B. V. ; D. Patnaik and M. K. Rout—  
Preparation, Synthesis and Mass Spectral  
Studies of 3-(*p*-Nitrophenyl)-thiazolo-  
[2, 3, *c*] [1, 2, 4]-triazepine Derivatives .. 1168
- Alam, M. K. *See* M. G. Ahmed 806
- Al-Dhahir, Adnan A. Karim—Yield of Mole-  
cular Hydrogen as a Criterion for the  
Radiation Stability of Organic Com-  
pounds ... 632
- Al-Dhahir, Adnan A. Karim and Idris M.  
Swan—Gas-liquid Chromatographic Study  
of Molar Heats of Evaporation : Effect of  
Molecular Structure ... 645
- Ali, Akhtar and R. K. Saksena—Biologically  
Active New 1-Substituted-2-mercapto-  
benzoyl-4-phenylimidazoles ... 420
- Ali, Mohd *See* Naseem H. Khan 1077
- Ali, Mohammad Ramzan ; R. Singh and  
V. K. Verma—A Novel Route to the  
Synthesis of 3-Arylimino-5-*p*-Methoxy-  
phenyl-1, 2, 4-Dithiazoles. Part—III ... 663
- Ali, Mohammad Ramzan and V. K. Verma—  
Synthesis of Some 3-Arylimino-5-(*N*-  
Methylanilino)-1,2,4- $\Delta^4$ -Dithiazolines ... 1165
- Aljančić, Ljerka J. *See* Milenko B. Čelap ... 1255
- Allam, M. G. *See* H. A. Dessoki ... 1063
- Ambardekar, A. B. *See* R. T. Sane 1201
- Ambekar, (Miss) Manik W. *See* P. P. Pathe ... 670
- Ambhore, D P. ; S. Q. R. Ilyas and A. P.  
Joshi—Phenoxy Acetyl Acetophenone as  
an Analytical Reagent for Iron ... 691
- Andhiwal, C. K. and Kamal Kishore—High  
Content of Cholesterol in the Lipid of  
*Acacia farnesiana* Leaves ... 1079
- Anjaneyulu, Y. ; R. Prabhakara Rao, R. Y.  
Swamy, A. Eknath and K. Narasimha  
Rao—Isolation, Characterisation and  
Antimicrobial Activity Studies of the  
Mixed Ligand Complexes of Cd(II) with  
8-Hydroxyquinoline and Various Salicylic  
Acids .. 1024

- Annappurna, D.; Y. D. Reddy and V. V. Somayajulu—Synthesis of 3-Heteraryl Coumarins as Optical Brighteners ... 977
- Ansari, M. N.; M. C. Jain, R. D. Kaushik and Wahid U. Malik—pH-Metric Studies on the Copper Benzamidothiosemicarbazide Complex 414
- Arora, Harish Kumar; Anita Rani Aggarwal and R. P. Singh—Acid Dissociation Constants in Ethanol Water Mixture: Some Hydroxy Coumarins 347
- Arora, O. P. and Sudhindra N. Misra—Synthesis and Characterisation of Mixed Ligand Complexes of Divalent Nickel ... 98
- Arora, O. P. and Sudhindra N. Misra—Synthesis and Characterization of Some Mixed Ligand Complexes of Ni(II) Ethylacetoacetate with Schiff Bases 32
- Ashby, E. C. and A. B. Goel—Redistribution Reactions Involving Lithium Aluminium Hydride and Lithium Tetraphenylaluminate 134
- Astik, R. R. See N. C. Desai 771
- Athar, M. See Syed A. Nabi 1200
- Atre, Vasudha See V. J. Tyaga Raju 199
- Awasthi, V. K.; S. N. Bhattacharya and (Mrs.) Mahima Verma (in part)—Tricyclohexyl Tin Halides and Pseudohalides: Structural and Biocidal Activity 264
- "B"
- Bachlas, B. P. See A. Kumar 280
- Badr, M. Z. A. See A. M. Osman 763
- Bag, S. P.; A. B. Chatterjee, A. K. Chakrabarti and P. R. Chakraborty—Complex Formation of Vanadium(V) with Salicylhydroxamic Acid in MIBK Photometric Methods of Determination of Vanadium in Alloy Steel and Ores .. 1085
- Bag, S. P.; A. B. Chatterjee, A. K. Chakrabarti and P. R. Chakraborty—Ternary Extraction and Photometric Estimation of Vanadium(V) with N Cinnamoyl-N-Phenyl Hydroxylamine (N-CPHAMine) and Thiocyanate in Chloroform .. 630
- Bag, S. P.; A. K. Chakrabarti and J. P. Goswami—A New Sensitive and Selective Reagent for Extraction of Trace Amount Molybdenum in iso-Amyl Alcohol and Photometric Determination ... 713
- Bag, S. P.; Amarjyoti Basu and A. B. Chatterjee—Spectrophotometric Determination of Vanadium with 2:2'-Diaminodiphenyl-Disulphide in Strong Acid Solution 787
- Bag, S. P. and C. R. Chanda—Spectrophotometric Determination of Rhenium with N-(4-Methoxyphenyl)- $\alpha$ -thiopicolinamide and Evaluation of the Stability Constant of the Complex Involved Therein 688
- Bagavant, G. See P. W. Agnihotri 869
- Bagchi, B. N.; S. N. Ghosh, S. K. Ghosh and S. P. Dhua—Movement and Transformation of Anhydrous Ammonia in Field Soil ... 453
- Bahadur, Krishna and S. Ranganayaki—Functional Approach to the Problem of Origin of Life - Photochemical Splitting of Water and Reduction of Nitrogen and Carbon dioxide ... 480
- Bahel, S. C.; B. L. Dubey, N. Nath, A. Tripathi and J. K. Srivastava—Synthesis and Structural Studies of the Complexes of Zn(II), Ni(II), Cu(II) and Co(II) with 3-Aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazoles ... 1127
- Bahel, S. C. See R. B. Pathak 776
- Bahel, S. C. See R. S. Sharma 877
- Bahl, O. P.; T. L. Dhami, R. L. Seth, L. M. Manocha and R. B. Mathur—Application of Coordination Compounds of Silicon and Copper in Fiber and Fiber Reinforced Plastic Materials ... 1306
- Bai, L. J.; Z. F. Wang and Y. T. Chen—ESR Study of Cu(II)-N-Aryl Glycinates 1280
- Bailar, Jr., John C.—Some Interesting Aspects of the Chemistry of Platinum ... 1214
- Baishya, N. K. and G. Baruah—Spectrophotometric Determination of Chromium in Steel by Extraction of its Ion Association Complex with Tetraphenylarsonium Chloride ... 389



Bajaj, P. and D. C. Gupta—Copolymerization of Acrylonitrile with [(2-Methacryloyloxy) alkoxy] Trimethyl Silanes ...	228	Hydrofuramide on Sulphenamide Acceleration System ...	403
Bajpai, Beena See K. K. Bajpai ...	1090	Banerjee, S. See D. Nasipuri ...	1379
Bajpai, S. K. and G. N. Shukla - Screening of Metal Complexes for Biological Activity. Part-IV : Synthesis of Pharmacologically and Microbiologically Active Thiocyanato and Oxalato Complexes of Fe <sup>3+</sup> , Co <sup>3+</sup> , Ni <sup>2+</sup> and Cu <sup>2+</sup> with 3-Phenylaminomethyl benzoxazolinone-2 ...	343	Banerjee, Sadhana ; Sushanta Dutta and S. K. Chakraborti—Synthesis of 9-Alkyl-6-Mercapto-purine Analogues ...	417
Bajpai, S. K. See S. R. Tewari ...	891	Banerjee, Vishwanath and Arun K. Dey—Polymeric Metal Complexes of 5,5'-( <i>p</i> -phenylene-bis azo)-diquinolin-8-ol ..	991
Bajpai, K. K. and Beena Bajpai—Interaction Products of Triphenylphosphine Oxide with Some Organotin Halides ...	1090	Banerji, Avijit and Arup K. Siddhanta—3,4-Bond Cleavage of Tetrahydro- $\beta$ -Carboline Alkaloids · Transformation of Venenatine and Rhazine to the Corresponding 2-Acylindole Derivatives ...	542
Baker, L. C. W. ; H. G. Mukherjee and B. K. Chaudhuri—Studies on Triortho-periodate Tetracobaltic(III) Acid. Part-II ...	930	Banerji, J. ; (Mrs.) A. Chatterjee, N. Ghoshal, A. Das, S. Sarkar, S. Bhattacharya (in part) and J. N. Shoolery—Studies on Rutaceae. Part-III : Reactions and Rearrangements of Prenyl and Prenyloxy Coumarins ...	145
Balfour, Lady E. B.—Some Reflections on Ways to Bring About a Permanently Sustainable World Agriculture ...	431	Banerji, J. See A. Chatterjee ...	1360
Bandyopadhyay, S. See A. K. Mandal ...	1390	Banerji, Kalyan K. See Anandi L. Jain ...	654
Bandyopadhyay, T. K. See S. Ghosh ...	1034	Banerji, Samir K. See B. G. Saha ...	927
Banerjee, A. K. ; Dharmbir Prasad and S. K. Roy—Metal Complexes as Ligands : Binuclear Alkali Metal Complexes with Copper(II)- and Nickel(II)-Salicylaldehydes ...	1303	Bansal, R. K. and G. Bhagchandani—Synthesis and Mass Spectral Studies of Some New 1,3,4-Oxadiazoles ...	277
Banerjee, A. K. ; Sailendra K. Sinha, Monojit K. Ghosh and S. K. Roy—Alkaline Earth Metal Complexes. Mixed Ligand Complexes of Some Organic Compounds of Magnesium with Nitrogen Donor Ligands ..	1020	Bansal, S. P. See R. S. Saxena ...	702
Banerjee, A. K. ; Tarkeshwar Singh and S. K. Roy—Azo Complexes : Complexes of Alkali Metal Salts of Some Organic Acids with <i>o</i> -Hydroxybenzeneazo-2-Naphthal ...	1186	Barua, A. K. See T. K. Chatterjee ...	418
Banerjee, A. K. ; Tarkeshwar Singh and S. K. Roy—Azo Complexes : Complexes of Alkali Metal Salts of Some Organic Acids with <i>o</i> -Hydroxybenzene-Azo-2-Naphthyl Amine ...	1089	Baruah, G. See N. K. Baisya ...	389
Banerjee, Amalendu See Haraprasad Samaddar ...	905	Basolo, F. See P. N. Venkatasubramanian ...	1218
Banerjee, B. and S. N. Chakravarty—Vulcanization of Natural Rubber : Influence of		Bassi, P. S. ; N. K. Sharma and K. N. Goswami—Structure of Faceted Naphthalene-Benzic Acid Eutectic ...	968
		Basu, Amarjyoti See S. P. Bag ...	787
		Basu, P. K. See P. Vishnu Kamath ...	153
		Basu, R. See J. Lahiri ...	941
		Basu, Sekhar ; A. K. Gupta and K. K. Rohatgi-Mukherjee—Concentration Depolarization, Energy Transfer and Kinetics of Concentration Quenching of Fluorescence of Anthracene Sulfonates ...	578
		Baveja, Anil K. and V. K. Gupta - Oxalyldihydrazide : A New Reagent for Rapid Gravimetric Determination of Selenium ...	1111
		Baweja, R. K. See S. N. Dubey ...	1133
		Bera, A. K. See M. C. Chakravorti ...	990
		Bhaduri, (Mrs.) I. See R. G. Bhattacharyya ...	919

- Bhagchandani, G. *See* R. K. Bansal ... 277
- Bhagwat, W. V.—The Relation Between Intensity and Velocity of Photochemical Reactions ... 575
- Bhakta, C. *See* J. N. Chatterjea ... 707
- Bharadwaj, P. K. *See* M. C. Chakravorti ... 990
- Bhardwaj, P. N. and G. Srivastava—Triphenylsiloxy and Diphenylsiladioxy Derivatives of Boron ... 300
- Bhargava, Jayant *See* (Mrs.) P. R. Shukla ... 620
- Bhargava, P. N. ; Ram Lakhan and Ramacharya Tripathi—Local Anaesthetics. Part-II : Synthesis of 2-(N,N-Disubstituted Aminoacetamido)-4-*p*-Fluorophenyl and -*m*-Methoxyphenyl Thiazoles ... 773
- Bhargava, P. N. *See* Ram Lakhan ... 804
- Bhat, K. C. *See* H. V. Keer ... 740
- Bhatia, V. K. *See* (Miss) S. Chakraborty ... 1158
- Bhatnagar, R. P. and F. A. K. Yusufi—Electromigration of Some Metal Ions on Filter Paper using Aqueous Glycolate Buffer Media ... 410
- Bhatnagar, R. P. *See* B. G. Saha ... 927
- Bhatt, (Miss) A. and V. K. Gupta—A New Reagent System for Photometric Analysis of Selenium in Complex Materials ... 888
- Bhattacharjee, S. *See* M. S. Mayadeo .. 800, 896, 1189
- Bhattacharjya, U. and Partha Mukhopadhyay—Carbon, Nitrogen and Sulphur Mineralisation in a Soil from Three Decomposing Plant Materials of Varying C/N, C/S and N/S Ratios ... 68
- Bhattacharya, A. K.—About the Nature of M-S Bond in Complex Compounds ... 515
- Bhattacharya, Debasis *See* Ansuman Roy ... 585
- Bhattacharya, P. K.—Antiferromagnetic Interaction in Binuclear Copper(II) Complexes Involving Tetradentate Schiff Bases ... 505
- Bhattacharya, P. K. and P. J. Patel—A New Approach to Astatistical Stabilisation of Cu(II) Ternary Complexes Containing Tertiary Amines and O—O— Co-ordinating Ligands ... 310
- Bhattacharya, P. K. and V. K. Patel—A New Parameter in Astatistical Stabilization of Ternary Complexes ... 1244
- Bhattacharyya, R. G. and (Mrs.) I. Bhaduri—Metal Ion Interactions with the Constituents of Nucleic Acid. Part-I : Metal-Adenine Complexes ... 919
- Bhattacharya, S. *See* J. Banerji ... 145
- Bhattacharya, S. N. *See* V. K. Awasthi ... 264
- Bhattacharyya, Lina *See* Shyamali Roy ... 1369
- Bhave, Narayan S. and R. B. Kharat—Studies of ESR Spectra of some Cu(II) Complexes ... 994
- Bhoon, Y. K. *See* K. Mukkanti ... 830
- Bhushan, Himanshu *See* L. K. Mishra ... 1092
- Bhushan, R. *See* W. U. Malik ... 1316
- Biswas, S. D. and F. S. Chebib—Computations of Apparent Formation Constants and Free Metal Ions in EGTA or EDTA Buffer Systems. Part-I : Effects of pH and Metal Concentration with Respect to Ligand ... 1419
- Bjerrum, Jannik and Predrag Djurdjevic—Metal Ammine Formation in Solution. Part-XXIII : The Nickel(II)-Mono- and Diethanolamine Systems ... 1229
- Blokhra, R. L. ; S. Chand and R. Sidhu—Flow Through Porous Medium. Part-VI : Permeability Studies of Water and Ammonium Salt Solutions Through Soil Membrane ... 63
- Bommannavar, A. S. *See* H. V. Kiran ... 1310
- Boparai, K. S. *See* Jyoti Talegaonkar ... 108, 109
- Boparai, K. S. *See* Suman Mukhija ... 427
- Bozadziev, Pesho *See* Liliana Ilcheva ... 1352
- Brar, A. S. *See* S. S. Sandhu ... 173
- Brown, D. A. ; H. J. Lyons, F. M. Hussen and C. Munir—Substitution of  $\eta_5$ -Cyclopentadienyl Iron Carbonyl Halides by Diphenylcyclopropanone ... 139
- Brown, D. A. ; J. P. Chester and N. J. Fitzpatrick—Molecular Orbital Study of  $[\text{BFe}(\text{CO})_3]^+$ ,  $\text{B}=(\text{C}_6\text{H}_5)$ ,  $(\text{C}_6\text{H}_7)$  and  $(\text{C}_7\text{H}_9)$  ... 1273
- Butail, Jagmohan *See* Balbir Chand Verma ... 811

# "C"

- Ćelap Milenko B. ; Ljerka J. Aljančić and Tomislav J. Janjić—Optical Inversion of the *cis* ( $\text{NO}_2$ ), *trans* (N), *cis*(O)-*bis*(Amino carboxylato)Dinitrocobaltate(III) Ion ... 1255

Chadha, Rita and Naba K. Ray—MNDO Study of Reaction Paths: Hydroboration of Organic Nitriles	204	Chatterjea, J. N.; Sanat K. Mukherjee and C. Bhakta—Syntheses of 2-Hydroxyisocarbostyrils	707
Chakrabarti, A. K. See S. P. Bag	630, 713, 1085	Chatterjea, J. N. See N. Prasad	980
Chakrabarti, Anil K.—Ternary Complex—Influence of Oxalic Acid on Vanadium(V) Determination with 4-Sulpho-2-Aminobenzenethiol in Aqueous Solution	627	Chatterjee, (Mrs.) A. See J. Banerji	145
Chakrabarty, D. K. See H. V. Kiran	1310	Chatterjee, A.; K. P. Dhara and J. Banerji—Alkaloids of <i>Mitragyna parvifolia</i> (Roxb) Korth. and their Transformations	1360
Chakraborti, S. K. See Sadhana Banerjee	417	Chatterjee, (Mrs.) Asima; Uttam Kumar Pandit, Suvra Sarkar and J. N. Shoolery—Electrophilic Substitution in Indoles. Part-I: Reaction of 3-Methyl Indole with Sulphuryl Chloride	523
Chakraborty, D. P. See Shyamali Roy	1369	Chatterjee, A. B. See S. P. Bag	630, 787, 1085
Chakraborty, K. R.—Introduction to Science Based on Symmetry	1	Chatterjee, Basanta G. See Sitaram Sharma	536
Chakraborty, P. R. See S. P. Bag	630, 1085	Chatterjee, S. K. See G. N. Mukherjee	1117
Chakraborty, (Miss) S. and V. K. Bhatia—Behaviour of Vanadyl Porphyrin Complexes of TLC	1158	Chatterjee, T. K.; A. Nagar, A. K. Barua and K. Mukherjee—Chemical Investigation of the Steam Bark of <i>Canthium dicoccum</i>	418
Chakraborty, A. K. See M. B. Saha	1109	Chattopadhyaya, M. C.—Effect of Substituents on the Relative Stabilities of Fe(III) Complexes of Substituted Salicylic Acids	1416
Chakravarty, S. N. See B. Banerjee	403	Chattopadhyaya, M. C. See Uma Shankar Lal	493
Chakravorti, M. C.; A. K. Bera and P. K. Bharadwaj—Binuclear Oxofluoro Complex of Quinquevalent Molybdenum	990	Chattopadhyay, T. K. See B. Majee	219
Chakrawarti, Purushottam B.; B. L. Vijayvargiya and H. N. Sharma—Thermodynamic Study of M <sup>2+</sup> -Noradrenaline Systems in Aqueous Solutions	734	Chaturvedi, U. S. and R. C. Kapoor—Polarographic Studies on Acidic Aminoacid Imines (N-Salicylidene-L-aspartic Acid and N-Salicylidene-L-glutamic Acid)	210
Chakrawarti, Purushottam B. and Pramila Khanna—Physicochemical Study of Some Transition Metal Complexes of Vanillin-sulphanilate	828	Chaubal, A. M. See M. S. Mayadeo	949
Chamoli, R. P.; S. J. Rai and P. C. Gupta—Synthesis and Studies of Some New Phthal-as-Eins	863	Chaube, (Miss) Abha and V. K. Gupta—A Field Test for the Detection and Semi-quantitative Determination of Sulphur dioxide in Air and Water	1106
Chand, Lal; R. Maurya and A. B. Ray—Selective Methylation of Quercetin and Myricetin	1001	Chaudhry, S. C. See K. C. Malhotra	922
Chand, S. See R. L. Blokhra	63	Chaudhuri, B. K. See L. C. W. Baker	930
Chand, Trilok See W. U. Malik	1053	Chaudhury, A. K. and N. Kole—Equilibrium and Formation Constants of Co(II), Ni(II) and Zn(II) Complexes of N-Benzoyl Phenyl Hydroxyl Amine in Various Mixed Aqueous Solvents	934
Chanda, C. R. See S. P. Bag	688	Chaurasia, M. R. and Surendra K. Sharma—Synthesis of Some New 4(3H) Quinazolinones as Potential Fungicides	370
Chandra, Kailash See Ashok Kumar	843	Chebib, F. S. See S. D. Biswas	1419
Chandra, Kailash See Purshotam Soni	913	Cheema, H. S. See T. S. Lobana	799
Chandrasekharan, K. See P. Mathur	970		
Chang, A. C. See Gene D. Schaumberg	150		
Chatterjea, J. N. and K. R. R. P. Singh—Rearrangement in Furyl-2-Keto-Oximes	527		
Chatterjea, J. N. and Radhika P. Sahai—Synthesis of Pyrano/Pyrido Benzothiophene Derivatives. Part-I	1372		

- Chen, Y. T. *See* L. J. Bai ... 1280
- Cheng, K. L.—Photocorrosion ... 1393
- Chester, J. P. *See* D. A. Brown ... 1273
- Chiranjeevi, A. *See* Bipin B. Mahapatra 988, 1022
- Chokkalingam, S. *See* V. Krishnasamy ... 641
- Choudhary, C. K. and B. Prasad—Standard Electrode Potential of Mercury-Mercurous Electrode at a Number of Temperatures .. 555
- Choudhary, Jitendra and Sukhnandan Prasad—Kinetics of Oxidation of Glycollic Acid by Quinequevalent Vanadium in Sulphuric Acid Medium ... 638
- “D”
- Dagani, Doron *See* Dietmar Seyferth . 111
- Dan, (Mrs) S. ; S. S. Dan and P. Mukhopadhyay—Chemical Examination of Three Indigenous Plants 419
- Dan, S. S. *See* (Mrs.) S. Dan 419
- Darji, R. R. and A. Shah—Photochemical and Thermal Transformations of S-Benzoyl-O-alkyl Xanthates 657
- Das, A. *See* J. Banerji ... 145
- Das, H. R. *See* J. Pramanik . 397
- Das, (Miss) K. ; S. K. Gupta, U. S. Prasad and L. K. Mishra—Complexes of 2-(*o*-Hydroxyphenyl) Benzthiazoline with Some Bivalent Metal Ions . 334
- Das, P. B. *See* (Miss) S. Mohanty . 1190
- Das, Ram ; Girish Dixit and (Miss) Kamala Zutshi—Determination of Stability Constant of Copper(II) Complexes with Ethylenediamine and Acetyl Salicylate (Aspirinate) by Electrochemical Methods . 700
- Das, T. N. ; P. N. Moorthy and K. N. Rao—Chemiluminescent Method for Determination of Low Concentration of Hydrogen Peroxide .. 85
- Datta, Krishna M. *See* Nityananda Saha 728
- Datta Gupta, Mita *See* D. Nasipuri .. 1379
- Dave, L. D. and H. M. Trivedi—Ion-Exchange Equilibria of  $\text{Na}^{2+}$ – $\text{Ca}^{2+}/\text{Cl}^-$  and  $\text{Na}^+$ – $\text{Mg}^{2+}/\text{Cl}^-$  from Concentrated Solution 1136
- Davis, Reg and Desmond J. O'Reardon—Mass Spectrometry of Transition Metal  $\pi$ -Complexes. Part-VII : A Study of the Behaviour of Some Ruthenocene Derivatives ... 1270
- Daw, N. P. *See* D. Nasipuri ... 1379
- Dayal, Rameshwar—Chemical Constituents of *Eucalyptus citriodora* Roots ... 1008
- De, Anil K. ; Uday S. Ray and Narahari Parhi—Extraction of Zinc(II) as Chloride by High Molecular Weight Amine, Amberlite LA-1 . 1334
- De, K. S. and K. Gadgil—Chemisorption Kinetic Studies of Oxygen on  $\text{V}_2\text{O}_5$ – $\text{Ti}_2\text{O}_3$  846
- De, S. K. and Deepali Laloraya—Post-harvest Changes in the Status of Nitrogen and Organic Carbon in Soil Treated with Fertilizers and Pesticides for Growing *Raphanus sativus* . 470
- De, T. K. *See* C. L. Sharma 101
- Debi, (Miss) Aloka *See* H. G. Mukherjee 907, 908
- Deenadas, C. *See* H. V. Keer . 740
- Dehuri, S. N. and A. Nayak—Studies on Heterocyclic Compounds. Part-V : Synthesis and Antimicrobial Activities of N-Bridged Thiazole and Imidazole Derivatives ... 1170
- Desai, N. C. ; R. R. Astik and K. A. Thaker—Thiazolidinones as Potential Antibacterial Compound. Part-I . 771
- Desai, N. C. *See* H. K. Shukla 1101
- Deshmukh, B. K.—Extraction and Photometric Determination of Silver(I) with 4-S-Benzyl-1-*p*-Chlorophenyl-5-Phenyl-2,4-Isodithiobiuret (BPPTB) . 401
- Deshmukh, B. K.—Stability Constant of Fe(II), Co(II), Ni(II), Cu(II) and Cd(II) Complexes of 2,2'-Dipyridyl-2-Pyrimidyl-hydrazone 105
- Deshpande, D. S. *See* R. T. Sane 1201
- Dessoki, H. A. ; M. G. Allam and A. M. Hammam—The Reaction of Potassium Permanganate with Potassium Ferrocyanide and Some Binary Mixtures in Presence of Fluoride Ions ... 1063
- Devi, (Miss) Aloka *See* H. G. Mukherjee ... 984
- Dey, Arun K. *See* Bhagwat Singh . 29, 1130
- Dey, Arun K. *See* Hari Kishor Gupta . 216
- Dey, Arun K. *See* Uma Shankar Lal . 493
- Dey, Arun K. *See* Vishwanath Banerjee ... 991
- Dey, B. P. *See* S. Dutta ... 902



Gaur, Chandra Pal Singh <i>See</i> Bharat Singh ...	59	Gijare, A. S. <i>See</i> R. T. Sane ...	1201
Gaur, H. C. <i>See</i> R. K. Gupta ...	176	Giri, S.; Nizamuddin and H. C. Gupta— Synthesis of Some Aryl Fluorobenzene Sulphonates and Hydroxy Diaryl Sulpho- nes as Potential Fungicides ...	365
Gaur, R. C. <i>See</i> T. S. Waraich ...	103, 213	Goel, A. B. <i>See</i> E. C. Ashby ...	134
Gautam, R. K.; S. Kannan and G. S. Saharia—Studies in the Cycloheptane Series. Part-XXXI: Friedel-Crafts Reac- tion of the Anhydride of $\alpha\alpha$ -Dimethylglu- taric Acid with Different Aromatic Hydrocarbons and Synthesis of 1,1- Dimethyl-3,4-benzo/substituted benzocy- cloheptanes and 1,1-Dimethylthieno [3,4-b] Cycloheptane ...	378	Goel, Anil B. and Sarala Goel—Chemistry of Metal-Diene Complexes: $^{31}\text{P}$ NMR Studies of the Reaction of (COD) $\text{PtCl}_2$ with Tertiary Phosphines in Methanol ...	141
Gera, (Miss) Versha <i>See</i> H. L. Kalra ...	1427	Goel, Sarala <i>See</i> Anil B. Goel ...	141
Ghildyal, B. P.—Maximizing Crop Yields ..	445	Gogoi, P. K. <i>See</i> R. N. Mukherjee ...	170
Ghorai, P. C. <i>See</i> H. K. Saha ...	1124	Goswami, J. P. <i>See</i> S. P. Bag ...	713
Ghose, Animesh K. <i>See</i> Lalit C T. Eusebius ..	1412	Goswami, K. N. <i>See</i> P. S. Bassi ..	968
Ghosh, A. K. and J. C. Ghosh—First Disso- ciation Constant of Phosphoric Acid at a Number of Temperatures ...	745	Goswami, Shyamaprosad <i>See</i> Bani Tala- patra ...	1364
Ghosh, B. N.—Evaluation of the Mean Activity Coefficient of the Ions of Strong Electrolytes in Solutions whose Concen- tration Varied from 0.001 <i>M</i> to 4 <i>M</i> ...	737	Govardhan, Ch. <i>See</i> T. Sundara Ramaiah ...	975
Ghosh, G. and S. S. Rathi—Action of Electrolytes on Lyophobic Sols ...	567	Govil, Girjesh and Anil Saran—Biochemical Fuel Cells ...	1226
Ghosh, Guru Prasanna—Physico-chemical Studies on Phosphorylation ...	599	Gowda, A. Thimme <i>See</i> H. Sanke Gowda ...	1201
Ghosh, J. C. <i>See</i> A. K. Ghosh ...	745	Gowda, H. Sanke and A. Thimme Gowda— Spectrophotometric Determination of Ruthenium with Prochlorperazine Bisme- thanesulphonate ...	120
Ghosh, Monojit K. <i>See</i> A. K. Banerjee ...	1020	Gowda, H. Sanke and J. B. Raj—Spectro- photometric Study of the Reaction of Chromium(VI) with Fluphenazine Hydro- chloride ...	1391
Ghosh, R. <i>See</i> B. R. Singh ..	939	Grover, (Miss) Vineeta <i>See</i> Krishna C. Joshi ..	293, 107
Ghosh, S.; S. K. Ray, P. K. Ray and T. K. Bandyopadhyay—A Study on Solid State Thermal Decomposition Characteristics of Some Metallo-organic Compounds. Part-I: Dehydration and Decarboxylation of Hydrated Calcium Salts of Pyridine Monocarboxylic Acids ...	1034	Guha, Dipak <i>See</i> K. D. Gupta ..	99
Ghosh, S. K.—Role of Phosphate and Organic Matter in the Management of Lateritic Soils for Increasing Productivity ...	457	Gunjkar, V. G.; N. Ramachandran and H. V. Keer—Heat Capacity and Thermo- dynamic Properties of $\text{Sr}_2\text{MoCoO}_6$ and $\text{Sr}_2\text{MoNiO}_6$ ...	74
Ghosh, S. K. <i>See</i> B. N. Bagchi ...	453	Gupta, A. and B. S. Pannu—Stability of Complexes of Co(II), Ni(II) and Cu(II) with Esters of Salicylic Acid ..	93
Ghosh, Subhalakshmi and (Late) Santi R. Palit—Studies in Electrolysis in a W-tube with Reference to Non-Faradaic Beha- viour ...	1047	Gupta, (Km.) Achla <i>See</i> S. K. Srivastava ...	92
Ghosh, Subhalakshmi <i>See</i> Santi R. Palit ...	759	Gupta, A. K. <i>See</i> Sekhar Basu ...	57
Ghoshal, N. <i>See</i> J. Banerji ...	145	Gupta, B. K. <i>See</i> A. Syamal ...	69
		Gupta, D. C. <i>See</i> P. Bajaj ...	22
		Gupta, H. C. <i>See</i> S. Giri ..	36
		Gupta, Hari Kishor; Pyare Lal Maurya and Arun K. Dey—Mannich Bases as Potential Polydentate Ligands: 2,5-Bis(benzylamino- methyl) Hydroquinone Complexes ...	21

- Gupta, K. D. ; Swapan Nandi, Mukhdeo and Dipak Guha—Studies on the Flow and Sedimentation Characteristics of Sodium Bentonite Suspensions in Presence of Electrolytes and Humic Acids 998
- Gupta, K. S. See (Mrs.) S. Mittal 595
- Gupta, (Miss) Kiran Bala See M. Imtiaz Husain 1193
- Gupta, P. C. See R. P. Chamoli 863
- Gupta, R. K. ; K. W. D. Verma and H. C. Gaur—Complex Formation in Molten Salts: Thermodynamics of Association Equilibria of Single and Mixed Ligand Complexes: A Review ... 176
- Gupta, S. K. See (Miss) K. Das .. 334
- Gupta, Shashi Bhushan See H. K. Gakhar 666, 900
- Gupta, V. D. See B. Singh ... 244, 793
- Gupta, V. D. See S. K. Saini 1424
- Gupta, V. K. See (Miss) A. Bhatt . 888
- Gupta, V. K. See (Miss) Abha Chaube 1106
- Gupta, V. K. See Anil K. Baveja . 1111
- Gupta, Y. K. See (Mrs.) S. Mittal .. 595
- Guru, S. See Rajendra P. Misra . 987
- Gutmann, V. See G. Resch .. 130
- Gutmann, V. See W. Linert . 1284
- "H"
- Haas, Carol K. See Dietmar Seyferth 111
- Halim, F. M. Abdel See I. M. Sidahmed ... 1139
- Halli, M. B. See N. V. Huggi . 1017
- Hammam, A. M. See H. A. Dessoki 1063
- Hassan, A. Abou El-Ela See M. A. El-Maghraby . 867
- Hernando, V. and M. E. Garcia Lopez De Sa—Effects of P and Fe Concentrations in the Medium on the Uptake and Distribution of Fe in Maize Plants (*Zea Mays L.*) . 429
- Hezien, Z. A. See A. M. Osman . 763
- Hiremath, A. C. See N. V. Huggi 1017
- Högfeltdt, Erik—A Simple Derivation Function to Summarize Data in Solvent Mixtures. Part-2: The Standard Oxidation Potential of the Silver Chloride Electrode in Water-Ethylene Glycol Mixtures 1357
- Huggi, N. V. ; M. B. Halli and A. C. Hiremath—Study of Transition and Non-Transition Metal Complexes with 3-Amino-2-Benzoylbenzofuran . 1017
- Husain, M. Imtiaz ; (Miss) Kiran Bala Gupta and R. C. Srivastava—Search for New Hypoglycemic Agents. Part-VII: Coumarinylsulphonyl Ureas, Semicarbazides and Semicarbazones ... 1193
- Hussain, S. H. See M. S. Mayadeo 894, 949, 952
- Hussein, F. M. See D. A. Brown .. 139
- "I"
- Ilicheva, Lilianna ; Maria Polianova, Victoria Adewuyi and Pesho Bozadziev—Determination of Zinc with Cupric Ion-Selective Electrode and its Analytical Application in Fertilizers 1352
- Ilyas, Mohd. See Mohd. Kamil 1199
- Ilyas, S. Q. R. See D. P. Ambhore ... 691
- Ingle, D. B. See V. H. Patil 1000
- Iyer, Venkataraman N. ; (Miss) Gecta N. Sheth and V. V. R. Subrahmanyam—Melting Behaviour of Some Pure N-Acyl Amino Acids and Peptides .. 856
- "J"
- Jadhav, R. T. and M. G. Paranjpe—Heterocyclic Compounds. Sulphur as a Potential Oxidant. Preparation of 5-Alkyl/aryl-imino-2,4-dialkyl/aryl-3-thio-oxo-1,2,4-thiadiazolidines .. 71
- Jadhav, R. T. and M. G. Paranjpe—Some Interesting Reactions of N-Phenyl-S-Chloro isothiocarbamoyl Chloride ... 1004
- Jadhav, R. T. and M. G. Paranjpe—Thiocarbamide as Dealkylating Agent: Debenzylation of Certain 2-S-Benzyl-1,5-diaryl-2,4-isodithiobiurets with Thiocarbamide .. 1003
- Jagdale, M. H. ; M. M. Salunkhe and S. S. Swami—Kinetics of Nickel(II) Ion and Cobalt(II) Ion Catalysed Hydroxamic Acid Formation from Formic Acid 355
- Jain, (Miss) A. See R. A. Misra ... 289
- Jain, Ajay K. ; Raj Pal Singh and Sushma Agrawal—Selectivity of Heterogeneous Ion-Exchange Membrane Discs with Reference to their Water Content, Porosity, Swelling, Electrolyte Absorption and Electrical Conductance ... 106
- Jain, Anandi L. and Kalyan K. Banerji—Kinetics and Mechanism of Oxidation of Substituted Mandelic Acids by Sodium N-Chlorobenzenesulphonamide ... 654

Jain, Anju <i>See</i> H. K. Gakhar	...	900	the Coordination Sphere of Lanthanone Ions	...	1247
Jain, D. C. <i>See</i> I. P. Varshney	...	884	Kalinowski, K. <i>See</i> Z. Marczenko	...	1354
Jain, M. C. <i>See</i> M. N. Ansari	..	414	Kalra, H. L. ; J. S. Malik and (Miss) Versha Gera—Formation Constants and Thermodynamic Parameters of 2-Amino-3-hydroxypyridine with Some Bivalent Metal Ions	...	1427
Jain, Rajeev <i>See</i> Wahid U. Malik	...	191, 558, 962, 1057, 1060	Kalsi, P. S. <i>See</i> M. R. Manrao	...	901
Jain, S. L. <i>See</i> R. C. Kapoor		510	Kamath, P. Vishnu ; S. Yashonath, A. Srinivasan, P. K. Basu and C. N. R. Rao—Electron Spectroscopic Investigations of Carbon Monoxide, Nitrogen and Oxygen Adsorbed on Transition Metals	.	153
James, C. <i>See</i> S. M. K. Nair	...	1147	Kamil, Mohd. ; Noor Ahmad Khan, Iqbal Ahmad, Mohd. Ilyas and Wasir Rahman—Chemical Constituents of <i>Cephalotaxus griffithii</i>		1199
Janjić, Tomislav J. <i>See</i> Milenko B. Čelap		1255	Kannan, S. <i>See</i> R. K. Gautam	...	378
Jensen, Hans Peter—Formylcamphor Condensed with Diamines : The Structure in Solution as Obtained from UV Absorption and Circular Dichroism Spectroscopy		1387	Kantam, (Miss) M. Lakshmi <i>See</i> V. Yattirajam	...	1287
Jha, Abha Rani and Rajendra Kumar Mishra—Selective Extraction and Spectrophotometric Determination of Iron(III) as Thiocyanato and Azido Mixed-Complexes with Hydroxy-amidine	..	694	Kantak, U. N. <i>See</i> S. R. Patil	...	1300
Jha, (Miss) Abha Rani and Rajendra Kumar Mishra—Extraction and Spectrophotometric Determination of Vanadium(V) as Mixed Ligand Complexes of Various Hydroxyamidines and Thiocyanate		1177	Kanungo, B. K. ; B. Pradhan and D. V. Ramana Rao—Mixed Chelate Complexes of Iron(III) Containing Dithiocarbamate and Acetylacetonate, Oxinate or Glycinate	...	329
Jha, N. K. <i>See</i> L. K. Mishra		1092	Kanungo, J. L. Das <i>See</i> G. N. Sarkar		358
Jha, N. K. <i>See</i> R. S. Prasad		207	Kapoor, P. N. <i>See</i> A. K. Narula		195
Jha, P. P. <i>See</i> S. K. Roy		1096	Kapoor, R. C. <i>See</i> R. S. Sindal	.	1313
Jindal, A. K. <i>See</i> W. U. Malik	...	1053	Kapoor, R. C. and S. L. Jain—Polarographic Reduction of In(III)	..	510
Joshi, A. P. <i>See</i> D. P. Ambhore		691	Kapoor, R. C. <i>See</i> U. S. Chaturvedi	.	210
Joshi, Krishna C.—Some Aspects of the Chemistry of Fluorinated 1,3-Diketones		1375	Kapoor, R. N. <i>See</i> A. K. Narula	195, 1296	
Joshi, Krishna C. ; Vijai N. Pathak and (Miss) Vineeta Grover—Studies in Fluorinated 1,3-Diketones and Related Compounds. Part-XIII : Synthetic and Spectral Studies of Some New Fluorinated <i>Tris</i> Europium 1,3-Diketonates	...	293	Katyál, M. <i>See</i> A. K. Singh	..	625
Joshi, Krishna C. ; Vijai N. Pathak and (Miss) Vineeta Grover—Studies in Fluorinated 1,3-Diketones and Related Compounds. Part-XIV : Search for New NMR Shift Reagents	...	1072	Kaur, (Miss) Baljit <i>See</i> Mangat Rai	416, 1197	
Joshi, R. C. <i>See</i> K. A. Thakar	...	77	Kaur, (Miss) Baljit <i>See</i> Ajit Singh	..	673
			Kaushik, R. D. <i>See</i> M. N. Ansari		414
			Keer, H. V. ; C. Deenadas and K. C. Bhat—Heat Capacity and Thermodynamic Properties of Some Mixed Fluorides	..	740
			Keer, H. V. <i>See</i> V. G. Gunjkar		743
			Khan, A. A. <i>See</i> S. Zaman Rao	.	375
			Khan, Farid and A. V. Mahajani—Stability Constants and Thermodynamic Parameters of Neodymium(III) Complexes with Mandelic, Cinnamic and Phenylacetic Acids : A Polarographic Study	..	996

# "K"

Kadian, R. K. ; B. S. Garg and R. P. Singh—Compatibility of Nitrilotriacetic Acid and 3-Acetyl-4-Hydroxy-6-Methyl-2-Pyrone in



Khan, M. U. See P. P. Singh	35	Kotecha, (Miss) C. C. ; (Mrs.) J. A. Oza and D. N. Vyas—Effect of Chemicals on Protein Hydrolysate Amino Acids of Pumpkin ( <i>Curcubita pepo</i> ) Seeds During Germination	82
Khan, Naseen H. ; Mohd. Ali, H. Panda and (Miss) Rakhshinda—Synthesis of $\alpha$ -Amino-adipic Acid	1077	Kratzer, K. See J. Stary	1329
Khan, Noor Ahmad See Mohd. Kamil	1199	Krishan, Kewal See Mangat Rai	80
Khan, S. A. See P. P. Singh	35	Krishnan, M. S. See S. M. K. Nair	1147
Khandual, N. C. See R. C. Mohapatra	1162	Krischner, Stanley and Joanne Gabay—The Deuterium Isotope Effect on the Pfeiffer Effect in Optically Labile Coordination Compounds	1259
Khanna, Parmila See Purushottam B. Chakrawarti	828	Krishnasamy, V. See P. Mathur	970
Kharat, R. B. See Narayan S Bhawe	994	Krishnasamy, V. and P. Ratnasamy—Isomerization of $\beta$ -Pinene in the Vapour Phase over Alumina Catalyst: Influence of Partial Pressure of Nitrogen and Pyridine	1151
Khasnis, D. V. and V. M. Shinde—Extractive Spectrophotometry of Palladium(II) and Ruthenium(III) with Phenanthraquinone Monothiosemicarbazone	93	Krishnasamy, V. and P. Ratnasamy—Characterization of Alumina—A Versatile Catalyst	839
Khasnis, D. V. and V. M. Shinde—Determination of Copper in Steel, Brass, Gun-metal, Nickel-Silver and Aluminium Alloy by Extraction with Phenanthraquinone Monothiosemicarbazone	812	Krishnasamy, V. and S. Chokkalingam—Decomposition of Propan-2-ol over Chromite Spinel—Kinetic Studies	641
Khatib, J. I. See G. S. Misra	1334	Krishnasamy, V. ; T. V. Subramaniam and S. Soundararajan—Methylation of Phenol over Alumina in the Vapour Phase: Influence of Copper Sulphate	1067
Khatrri, J. C. and Mukhtar Singh—Electrode Kinetics of the Polarographic Reduction of Ni(II) in the Presence of Increasing Concentrations of L-4-Hydroxyproline and L-Tryptophan	897	Kulkarni, Y. D. and Vipin Kumar Agarwal—Studies on the Amine Exchange Reactions in C-Mannich Bases	380
Khetrapal, C. L.—NMR Spectroscopy of Oriented Molecules and its Applications to Inorganic Chemistry	164	Kulshrestha, S. K. See A. G. Fadnis	411
Khetrapal, C. L.—NMR Spectroscopy of Oriented Organo-selenium Compounds	1276	Kumar, A. ; H. Sharma, V. Sharma and B. P. Bachlas—Physico-chemical Studies of 1,5-Dimethyl- and 1,5-Diphenyl-1,3,5-pentanetriones with VO(II), Cr(III), Mn(II), Co(II), Ni(II), Cu(II) and UO <sub>2</sub> (III)	280
Khopkar, S. M. See A. G. Gaikwad	1346	Kumar, Arvind See (Miss) Gunjan Srivastava	958
King, R. Bruce and K. Tanaka—Reactions of Allylmetal Carbonyls of Rhodium and Cobalt with Carbon Monoxide and Hydrogen: New Catalytic Intermediates in Homogeneous Hydroformylation Reactions	124	Kumar, Ashok ; Kailash Chandra and Mukhtar Singh—Studies on the Suppression of Polarographic Maximum of Mn(II) by Some uni- and poly-valent Cations vis-a-vis Their Influence on the Kinetics of the Electrode Reaction of Mn(II)	843
Kiran, H. V. ; A. S. Bommanavar, D. K. Chakrabarty and A. B. Biswas—Mössbauer Spectra of Copper Nickel Ferrites	1310	Kumar, D. See A. Syamal	96
Kiran, Sushma See H. K. Gakhar	666	Kumar, N. See Sangeeta Wadhwa	247
Kishore, Kamal See C. K. Andhiwal	1079		
Kolandaivelu, P. See A. Natarajan	1155		
Kole, N. See A. K. Chaudhury	934		
Korkisch, J. ; I. Steffan and H. Staniek—Separation of Nickel by Solvent Extraction and Cation-Exchange Determination of Nickel in Mineral Waters	1331		

Kumar, Pradeep ; R. S. Shukla, A. K. Ram-rakhyani, A. K. Sengupta and O. P. Srivastava—Synthesis of New Dithiocarbamates as Potential Anthelmintic Antimicrobial and Insecticidal Agents	681	Langalia, N. A. and K. A. Thaker—Studies on Antitubercular Agents. Part-III : Preparation of Some <i>p</i> -(2,4-Diaryl-amino-6- <i>S</i> -Triazinylamino)-Benzaldehyde/ Acetophenone Thiosemicarbazones as Potential Tuberculostatic Agents	1099
Kumar, Rakesh <i>See</i> T. N. Srivastava	186	Langalia, N. A. <i>See</i> H. K. Shukla	1101
Kumar, Surinder <i>See</i> Ajit Singh	673	Lavale, S. C. <i>See</i> K. S. Pitre	1081
Kumar, Surinder <i>See</i> Mangat Rai	80	Lavale, S. C. and K. S. Pitre—4-(2-Pyridyl-azo) Resorcinol, A Sensitive Amperometric Reagent for Ultramicro Determination of $\text{Pr}^{3+}$ and $\text{Nd}^{3+}$	965
Kumar, Swatantar <i>See</i> Balbir Chand Verma	811	Levesque-Madore, C. S. <i>See</i> Gene D. Schaumberg	150
Kumar, Virendra <i>See</i> V. K. Mahesh	1192	Limaye, S. N. and M. C. Saxena—Some Ligational Aspects of Tartrazine : Its Binary and Ternary Lanthanide Complexes	698
Kumari, Amrita <i>See</i> R. S. Prasad	207	Limaye, S. N. and M. C. Saxena—Some Lanthanide—EDTA Ternary Complexes with Catechol, Resorcinol and Phloroglucinol	910
Kushwaha, S. S. S. <i>See</i> R. Sahai	853, 1121	Linert, W. and V. Gutmann—Infrared Spectra of Iron(II) Complexes with <i>N,N</i> -Dimethylformamide and <i>N,N</i> -Dimethylthioformamide	128

### "L"

Laha, (Miss) Swapna <i>See</i> P. L. Majumder	281	Lobana, T. S. ; H. S. Cheema and S. S. Sandhu—Donor Properties of Ditertiary-phosphine Dioxides towards Iron(III)	79
Laha, S. <i>See</i> P. L. Majumder	548	Lyons, H. J. <i>See</i> D. A. Brown	13
Lahiri, J. and R. Basu—Molecular Complexes of Tetracycline and Oxytetracycline Drugs with Nucleic Acid Bases and Aromatic Amino Acids	941		
Lahiri, S. C. <i>See</i> S. Dutta	902		
Lajunen, Lauri H. J.—Coordination of Al(III), Be(II) and Cu(II) Ions with 1,7-Dihydroxy-4-Sulfo-2-Naphthoic and 3,5-Dihydroxy-7-Sulfo-2-Naphthoic Acids in Aqueous Sodium Perchlorate Medium	1238		
Lakhan, Ram <i>See</i> P. N. Bhargava	773		
Lakhan, Ram ; P. N. Bhargava and Salik Prasad—The Reaction of Isatin with Active Methylene Group. Part-I : Formation of 5-(2-Oxo-3-Indolinyldene)-3-Aryl-2,4-Thiazolidindiones—A new Class of Thioindigoid Dyes	804		
Lakhani, S. U. ; G. S. Thakur and S. P. Sangal—A Potentiometric Study on the Complexes of Gadolinium, Erbium and Ytterbium in Aqueous Solution	801		
Lal, K. B. <i>See</i> Vinita Srivastava	497		
Lal, Uma Shankar, M. C. Chattopadhyaya and Arun K. Dey—Heterogeneous Ion-Selective Electrodes Based on Electro-neutral Ion-Carriers : Barium(II) and Nickel(II) Electrodes	493		
Laloraya, Deepali <i>See</i> S. K. De	470		

### "M"

Mahajan, J. P. <i>See</i> A. K. Dwivedi	45
Mahajan, K. C. <i>See</i> K. C. Malhotra	92
Mahajani, A. V. <i>See</i> Farid Khan	99
Mahan, Ashok <i>See</i> Lalit C. T. Eusebius	141
Mahapatra, Bipin B. and S. K. Pujari—Mixed Ligand Complexes of Cobalt(II) and Cadmium(II) with Oxine as Primary Ligand and Heterocyclic and Aromatic Amines as Secondary Ligands	118
Mahapatra, Bipin B. ; D. Panda, S. K. Pujari and A. Chiranjeevi—Mixed Ligand Anionic Complexes of Cadmium(II)	102
Mahapatra, Bipin B. ; S. M. Mahapatra, S. K. Pujari and A. Chiranjeevi—Complexes of	

Co(II), Ni(II), Cu(II), Zn(II), Cd(II) and Hg(II) with Chelating Bidentate Schiff's Base	988	Malik, Wahid U. and Rajeev Jain—On the Polarographic Reduction Mechanism of Some Heterocyclic Compounds	191
Mahapatra, S. M. See Bipin B. Mahapatra	988	Malik, Wahid U. and Rajeev Jain—On the Polarographic Reduction of 2-Aminobenzothiazoles	558
Mahesh, V. K. See Mahendra Pal Sharma	810	Malik, Wahid U. and Rajeev Jain—Polarographic Studies on the Effect of Some Ionic and Non-ionic Surfactants on the Kinetics of Irreversible Electrode Processes of Arylazopyrimidine and Arylazopyrazole	962
Mahesh, V. K.; Virendra Kumar and Om Prakash—Synthesis of Some 5-Arylazopyrimidine Derivatives	1192	Malik, Wahid U.; J. S. Tyagi and Aditya Prakash Mittal—Hydrogen Ion Equilibria on <i>p</i> -Toluenesulphonylated Casein	423
Mahmoud, A. M. See A. M. Osman	763	Malik, Wahid U.; J. S. Upadhyaya, Rajeev Jain and M. P. Sharma—Polarographic Studies on the Reduction of the Azomethine Bond in Aryl Thiosemicarbazides and the Determination of Hammett Parameters	1057
Mahmoud, A. M.; A. E. Abdel-Rahman and H. A. El-Sherief—Synthesis and Biological Activity of Some New 2-(N-Substituted Carboxamidomethyl Thio) Naphth [1,2-d] Oxazoles. Part-V	675	Malik, Wahid U.; (Miss) S. Agarwal and Rajeev Jain—Polarographic Reduction of Some 5,5-Dimethylcyclohexane-2-Benzothiazolylhydrazono-1,3-Diones and its 2-Methyl, 4-Methyl, 4-Methoxy, 4-Ethoxy Derivatives	1060
Maizwal, U. C. and K. Srinivasulu—Titrimetric Determination of Thorium(IV) using N-(2-Hydroxyethyl)ethylene diamine-triacetic Acid as Titrant and Pyrocatechol Violet as an Indicator	395	Malik, Wahid U. See M. N. Ansari	414
Majee, B. and T. K. Chattopadhyay—Formation of Unusual Molecular Complexes by Some Organotin-(Aryl Azo) Benzoates	219	Mallik, Asok K. See Sunil K. Talapatra	534
Majumdar, M. K. See R. N. Sen Sarma	790	Mandal, A. K.; S. Bandyopadhyay and S. Aditya—Thermodynamics of Ferrous-1,10-Phenanthroline in <i>t</i> -Butanol-Water and Glycerol-Water Media at 25°	1390
Majumder, P. L. and (Miss) Swapna Laha—Chemical Constituents of <i>Launaea nudicaulis</i> . C-13 Nuclear Magnetic Resonance Spectroscopy of Taraxasterenes and Pseudo-Taraxasterenes	881	Mandal, S. K. and S. K. Sanyal—Viscosity B Coefficient of Phenols and Benzyl Alcohol	803
Majumder, P. L. and S. Laha—Steric Effects on Oxymercuration-Demercuration of Taraxasteryl, Pseudo-Taraxasteryl, and 19-Epi-Taraxasteryl Acetates	548	Mandal, S. S. See H. K. Saha	1124
Makhlouf, A. A. See A. M. El-Naggar	783	Manglik, (Km.) Anita and S. K. Sharma—A Kinetic Study of Oxidation of Isobutyl Alcohol with Aqueous Iodine	352
Malhotra, K. C.; (Miss) Geeta Mathur, K. C. Mahajan and S. C. Chaudhury—Preparation and Characterization of Naphthoxides of Niobium(V) and Tantalum(V)	922	Manhas, B. S. and T. K. Tripathi—Relationships Between the Direction of Shifts in the Carbon-Oxygen Stretching Frequencies of Carboxylate Complexes and the Type of Carboxylate Coordination	315
Malik, J. S. See H. L. Kalra	1427	Manna, Pravash Chandra See M. K. Pal	409
Malik, W. U.; R. Bhushan and Anita Agarwal—Hydrogen Ion Equilibria and Metal Binding Studies on Arachin	1316	Manocha, L. M. See O. P. Bahl	1306
Malik, W. U.; S. K. Srivastava, Trilok Chand and A. K. Jindal—Studies on the Interfacial Tension and Electrical Conductance of Oil/Water Emulsions Stabilized by Lignosulphonate of <i>Eucalyptus teriticornis</i>	1053		

- Manrao, M. R. *See* Ajit Singh ... 673
- Manrao, M. R. ; R. C. Sharma, B. S. Dhir and P. S. Kalsi—Synthesis and Antifungal Activity of Oxazolones .. 901
- Marathe, D. G. and K. N. Munshi—Physicochemical Studies of Some Mixed Ligand Complexes of Samarium(III) and Holmium(III) . 617
- Marczenko, Z. and K. Kalinowski—Floatable Ion Associates Formed in the System Iridium(III)-Tin(II)-Chloride-Basic Dye 1354
- Martin, Dean F.; Therald Moeller and William J. Randall—The Rare Earths. Part-XCII: Chelating Tendencies of 1-Methoxy-2,4-pentanedione ... 1232
- Mathur, (Miss) Geeta *See* K. C. Malhotra .. 922
- Mathur, P ; V. Krishnasamy and K. Chandrasekharan—Transformations of  $\beta$ -Pinene Over Platinum-Alumina Catalyst. Part-I: Influence of Contact Time, Temperature and Platinum Concentration ... 970
- Mathur, R. B. *See* O. P. Bahl ... 1306
- Mathur, K. C. K. *See* R. S. Sindal 1313
- Mathur, P. B.—Some Thoughts on the Mechanism of Biochemical Reproduction Reactions and Drug Actions 603
- Mathur, R. C. *See* D. S. Sankhla ... 893
- Matteson, Donald S. *See* Rahul Ray ... 119
- Mattey, S. K. *See* N. K. Sharma .. 385
- Maurya, P. L. *See* Bhagwat Singh 29, 1130
- Maurya, P. L. ; C. P. Dube and B. V. Agarwala—Spectral Studies of Polymeric Metal Complexes with Schiff Bases of Terephthalaldehyde and Hydrazides 1400
- Maurya, Pyare Lal *See* Hari Kishor Gupta .. 216
- Maurya, R. *See* Lal Chand .. 1001
- Maurya, R. C. and R. K. Shukla—Thiocyanato Substituted Nitrosyl Chromium(I) Complexes ... 340
- Mayadeo, M. S. , A. M. Chaubal and S. H. Hussain—Formation Constants of the Chelates of 2-Hydroxy-1-Naphthalidene-*ortho*-Fluoroaniline with Some Bivalent Metal Ions ... 949
- Mayadeo, M. S. and S. Bhattacharjee—Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-Sulphamethoxazole Complexes with  $\text{Cu}^{2+}$ ,  $\text{Ni}^{2+}$ ,  $\text{Co}^{2+}$ ,  $\text{Zn}^{2+}$  and  $\text{Mg}^{2+}$  ... 896
- Mayadeo, M. S. and S. Bhattacharjee—Determination of Stability Constants of 2-hydroxy-1-naphthalidene-sulphafurazole Complexes with  $\text{La}^{3+}$ ,  $\text{Y}^{3+}$ ,  $\text{Pr}^{3+}$ ,  $\text{Nd}^{3+}$ ,  $\text{Gd}^{3+}$ ,  $\text{Dy}^{3+}$  1189
- Mayadeo, M. S. and S. Bhattacharjee—Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-sulphaphenazole Complexes with  $\text{La}^{3+}$ ,  $\text{Y}^{3+}$ ,  $\text{Pr}^{3+}$ ,  $\text{Nd}^{3+}$ ,  $\text{Gd}^{3+}$ ,  $\text{Dy}^{3+}$  800
- Mayadeo, M. S. *See* S. D. Samant 383
- Mayadeo, M. S. ; S. S. Purohit and S. H. Hussain—Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-2', 6'-Dimethylaniline Complexes with  $\text{La}^{3+}$ ,  $\text{Y}^{3+}$ ,  $\text{Pr}^{3+}$ ,  $\text{Nd}^{3+}$ ,  $\text{Dy}^{3+}$  and  $\text{Gd}^{3+}$  952
- Mayadeo, M. S. ; S. S. Purohit and S. H. Hussain—Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Chloro-2'-Methoxyaniline Complexes with  $\text{La}^{3+}$ ,  $\text{Y}^{3+}$ ,  $\text{Nd}^{3+}$ ,  $\text{Dy}^{3+}$  and  $\text{Gd}^{3+}$  . 894
- Mayadeo, M. S. and S. S. Purohit—Determination of Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Hydroxyaniline Complexes with  $\text{Mg}^{2+}$ ,  $\text{Co}^{2+}$ ,  $\text{Ni}^{2+}$  and  $\text{Cu}^{2+}$  955
- Mehra, S. C. *See* S. Zaman Rao 375
- Mehrotra, R. C. ; P. C. Vyas and C. K. Oza—Complex Polymetaphosphates of Strongly Electropositive Elements 486
- Mehrotra, R. C. *See* S. K. Saini . 1424
- Mehrotra, R. C.—Recent Advances in the Chemistry of Simple and Bimetallic Alkoxides of Later Transition Elements (with Particular reference to the '3d' series) ... 715
- Mehrotra, R. C.—Training and Research in Analytical Chemistry: An Interdisciplinary Science ... 1209
- Mishra, A. ; M. P. Singh and V. K. Singh—Nitrato-Complexes of Y(III), La(III), Ce(III), Pr(III), Nd(III), Sm(III), Gd(III), Tb(III), Dy(III) and Ho(III) with 2-(2'-Pyridyl) Benzimidazole .. 622
- Mishra, A. K. *See* K. N. Tandon ... 283

- Mishra, H. C. ; S. K. Roy and A. N. Ojha—  
Studied on Heteropoly 6-Ammonium  
Molybdochromate 792
- Mishra, H. P. *See* K. C. Satpathy 40
- Mishra, L. K.—Complexes of 5-Nitrobenzi-  
midazole with Some Metal Ions ... 795
- Mishra, L. K.—Complexes of Pd(II) and  
Pt(II) with Some Organic Ligands ... 408
- Mishra, L. K. ; Himanshu Bhushan and N. K.  
Jha—Mixed Ligand Cobalt(III) Complexes  
Containing Benzotriazole or 5-Nitrobenzo-  
triazole ... 1092
- Mishra, L. K. *See* (Miss) K. Das 334
- Mishra, L. K. *See* K. K. Roy 'Anil' ... 797
- Mishra, M. N. *See* G. D. Tiwari 362
- Mishra, R. C. ; B. K. Mohapatra and D.  
Panda—Studies on Hydrazones, Semicar-  
bazones, Thiosemicarbazones and Oximes  
as Ligands. Part-III : Some Divalent Metal  
Complexes of Benzil Semicarbazone 836
- Mishra, R. G. *See* K. N. Tandon 283
- Mishra, Rajendra Kumar *See* (Miss) Abha  
Rani Jha 694, 1177
- Mishra, S. B. *See* R. N. Roy 1094
- Misra, G. S. and J. I. Khatib—Polymerization  
of Methacrylamide Initiated by Ceric Ion-  
Malic Acid Redox System ... 1384
- Misra, R. A. ; (Miss) A. Jain and A. Yadava—  
Reductive Alkylation of 2-Methyl-1,4-  
Naphthaquinone (Menadione) at Mercury  
Pool Cathode 289
- Misra, Ranjana *See* J. S. Shukla 1196
- Misra, Rajendra P. and S. Guru—Nickel(II)  
Complexes with Substituted Amino Benzo-  
thiazoles 987
- Misra, S. G. and S. P. Pathak—Phosphate  
Fertilization in Alluvial Soils of Allahabad  
Division. Interrelation in Water Soluble  
P, Adsorbed P and Olsen's P ... 466
- Misra, S. K. *See* S. R. Tewari 891
- Misra, Sudhindra N. *See* D. S. Sankhla 893
- Misra, Sudhindra N. *See* O. P. Arora 32, 98
- Misra, Sudhindra N.—Synthesis and Spectral  
Studies of Lanthanide Complexes with  
Fluoro- $\beta$ -diketones ... 99
- Misra, V. N. *See* S. R. Tewari ... 891
- Misra, V. S. ; V. K. Saxena and Rashmi  
Srivastava—Synthesis and Amoebicidal  
Activity of Some 2-Methyl-6(8)-alkyl-4  
(arylsulphonylhydrazino) quinolines ... 781
- Misra, Vinay S. , Pramila Saha and V. K.  
Saxena—Synthesis of Some New Benzimi-  
dazoles as Antiamoebic Agents 1074
- Mitra, Alok K. *See* Amarendra Patra ... 660
- Mitra, G. K. and B. C. Pathak—Synthesis of  
4-Imidazolyl-2-Methyl-5-Nitro-8-Hydroxy  
Quinolines as Possible Antiprotozoal  
Agents 367
- Mitra, (Miss) P. , A. Nayak and A. S. Mitra—  
Studies on 2-Pyrazolin-5-one Derivatives  
... 1005
- Mittal, A. K. and O. P. Singhal—Some New  
Coumarins and Schiff's Bases as Possible  
Antibacterial and Antifungal Agents 373
- Mittal, A. K. and O. P. Singhal—Synthesis of  
Some New 1-phenyl-3-methyl/phenyl-4-  
(*o/m/p*-substituted benzeneazo)-5-pyrazolo-  
lones, 1-phenyl-3-(*o/m/p*-substituted anilic)-  
5-pyrazolones and 3-methyl/phenyl-4-  
(*o/m/p*-substituted benzeneazo)-5-isoxazo-  
lones as Possible Biological Agents 711
- Mittal, Aditya Prakash *See* Wahid U. Malik. 423
- Mittal, (Mrs.) S. ; K. S. Gupta and Y. K.  
Gupta—Kinetics of the Acid Catalysed  
Hydrolysis of Formamide in Binary-  
Aqueous Mixtures ... 595
- Mitra, A. S. *See* (Miss) P. Mitra 1005
- Modak, S. C. *See* Uday Sankar Ray 392
- Modak, Sagar Chandra *See* Uday Sankar  
Ray ... 911
- Mody, M. K. , A. R. Prasad, T. Ramalingam  
and P. B. Sattur—Synthesis and Pharma-  
cology of 2-Aryl-5-Aryloxyalkyl-S-Triazolo  
[3,4-*b*]-1,3,4-Thiadiazoles 769
- Moeller, Thera'd *See* Dean F. Martin 1232
- Mohanty, (Miss) S. and P. B. Das—Conduc-  
tance of KCl and NaCl Sucrose+Water,  
Glucose+Water and Urea+Water Mix-  
tures at Different Temperatures 1190
- Mohapatra, B. K. *See* B. K. Sahu ... 732
- Mohapatra, B. K. *See* R. C. Mishra .. 836
- Mohapatra, B. K. *See* R. N. Roy ... 1094
- Mohapatra, R. C. and N. C. Khandual—  
Kinetics of Chromic Acid Oxidation of

<b>Phenacyl Bromides (<math>\omega</math>-Bromoacetophenones)</b>	... 1162	Munir, C. See D. A. Brown	... 139
<b>Moolal, Mathew J. See S. Thangavel</b>	.. 1044	Munshi, K. N. See D. G. Marathe	... 617
<b>Moorthy, P. N. See T. N. Das</b>	.. 85	Munshi, K. N. See (Miss) N. R. Gandhi	... 1290
<b>Mouli, G. V. P. Chandra See M. Sadasiva Shankar</b>	. 1104	Murty, H. V. N.; V. M. Rao and M. N. Sastri—The Extraction of Chromium(VI) from Mineral Acid Solutions by Trilauryl-amine-Oxide	... 1343
<b>Mukhdeo See K. D. Gupta</b>	... 998	Murthy, J. Venu Gopalakrishna See Satya Prakash	.. 591
<b>Mukhedkar, A. J. See V. A. Mukhedkar</b>	... 295	Murthy, K. V. S. S. See C. S. Prakasa Sastry	. 1107
<b>Mukhedkar, V. A.; R. L. Rajgolkar and A. J. Mukhedkar—Role of Metal Ions in Reactions of dl-Camphorquinone with Monoamines</b>	. 295	Murty, N. Krishna and A. V. Suryanarayana—Detection and Determination of Phosphate Using Monomethyl-p-Aminophenol as Reagent	.. 1113
<b>Mukherjee, G. N.; (Miss) S. Sarkar and S. K. Chatterjee—Metal Complexes of Some Model Peptides. Part-I : Complex Formation of Cu(II) with N-Salicyloyl Glycine</b>	.. 1117	"N"	
<b>Mukherjee, H. G. and (Miss) Aloka Debi—Determination of Equilibrium Constant of Ferric Formate Complex by Paper Electrophoresis</b>	.. 907	Nabi, Syed A.; Ahsan R. Siddiqui, M. Athar and N. Ahmad—Selective Microgram Detection of Iron(III) on Ion Exchange Resin Beads	. 1200
<b>Mukherjee, H. G. and (Miss) Aloka Debi—Relative Stability of Formate Complexes by Paper Electrophoresis</b>	. 908	Nagar, A. See T. K. Chatterjee	418
<b>Mukherjee, H. G. and (Miss) Aloka Devi—Paper Electrophoretic Separation and Estimation of the Constituents of Pyrolusite and Indian Coin (Cupro-nickel)</b>	. 984	Nair, S. M. K.; M. S. Krishnan and C. James—Thermal Decomposition of Irradiated Strontium Nitrate	.. 1147
<b>Mukherjee, H. G. See L. C. W. Baker</b>	... 930	Nair, T. D. Radhakrishnan; P. Sreeman and N. Thankarajan—A Dynamic TG Study of Bis(acetylacetonato) Copper(II)	... 415
<b>Mukherjee, K. See T. K. Chatterjee</b>	418	Nandi, Swapn See K. D. Gupta	... 998
<b>Mukherjee, R. N.; M. S. Venkateshan, V. S. Vijaya and P. K. Gogoi—Dithiophosphinates of Some First Row Transition Metals</b>	. 170	Narain, Gopal See (Mrs.) P. R. Shukla	620, 1180
<b>Mukherjee, Samir Kumar See B. B. Roy</b>	440	Narula, A. K.; B. Singh, P. N. Kapoor and R. N. Kapoor—Benzilic Acid Complexes of Niobium(V) and Tantalum(V)	195
<b>Mukherjee, Sanat K. See J. N. Chatterjea</b>	707	Narula, A. K.; B. Singh and R. N. Kapoor—Anthranilic Acid Hydrazide Complexes of Aluminium(III) and Titanium(IV)	... 1296
<b>Mukherjee, Sushmita See Suresh K. Garg</b>	. 1038	Norula, J. L. See N. K. Sharma	385
<b>Mukhiya, Suman; Jyoti Talegaonkar and K. S. Boparai—Determination of Sodium Carboxylates by Reaction with <math>\omega</math>-Bromoacetophenone</b>	. 427	Nasipuri, D.; N. P. Daw, S. Banerjee and Mita Datta Gupta—Restricted Rotation. Part-IV: Determination of Barrier to Rotation Around Some Crowded C-C and C-N Bonds by Dynamic Nuclear Magnetic Resonance	.. 1379
<b>Mukhopadhyay, Apurba K. See Amarendra Patra</b>	660	Natarajan, A.; P. Kolandaivelu and A. Savarianandam—Vibrational Analysis of Gloxal— $h_2-d_2$ and hd	... 1155
<b>Mukhopadhyay, P. See (Mrs.) S. Dan</b>	419	Nath, D. See A. K. Singh	... 625
<b>Mukhopadhyay, Partha See U. Bhattacharjya</b>	.. 68		
<b>Mukkanti, K.; Y. K. Bhoon, K. B. Pandeya and R. P. Singh—Studies on Some Polydentate Ligands. I</b>	. 830		
<b>Muktawat, K. P. Singh See J. P. Rawat</b>	... 1011		

Nath, N. <i>See</i> S. C. Bahel	... 1127	Palit, Santi R. <i>See</i> Nita Vidyarthi( <i>nee</i> Das)	748, 753
Nayak, A. <i>See</i> (Miss) P. Mitra	... 1005	Palit, Santi R. <i>See</i> Subhalakshmi Ghosh	1047
Nayak, A. <i>See</i> S. N. Dehuri	1170	Palta, (Miss) Neelam; S. N. Dubey and D. M. Puri—Organophosphonic Acids as Complexes. Part-II: Interaction of Ethylenediphosphonic Acid with Some Divalent Metal Ions	.. 261
Nayak, P. L. <i>See</i> B. C. Singh	.. 349	Panda, D. <i>See</i> Bipin B. Mahapatra	1022
Nerenberg, S. T. <i>See</i> R. Prasad	1220	Panda, D. <i>See</i> R. C. Mishra	.. 836
Nigam, H. L. <i>See</i> Vinita Srivastava	... 251, 497	Panda, H. <i>See</i> Naseem H. Khan	.. 1077
Nigam, S. C.; G. S. Saharia and H. R. Sharma—Studies in Heterocyclic Compounds. Part-XXXI. Synthesis of Some 4-Methyl-5-(methyl/ <i>p</i> -methylphenyl)-5-(ary-lazo/ <i>N</i> -Substituted <i>p</i> -sulphamylbenzene-azo)-pyrimidin-2-ols as Potential Anti-bacterials	709	Pandey, Ashok and K. P. Tiwari—Effects of Ultraviolet Radiation on Amino Acid Composition of Single Cell Protein	686
Nigam, S. S. <i>See</i> S. P. Shrivastava	1198	Pandey, D. P. <i>See</i> S. C. Tripathi	238
Nimdeokar, N. M. <i>See</i> P. P. Pathe	670	Pandey, Ganesh D., Kamala P. Tiwari and Sant P. Tandon—A Novel Synthesis of Yohimbane Skeleton—Synthesis of 17,18-Dimethoxy-15,16,17,18,19,20-hexadehydro-yohimbane by Condensation of an Indolylethylamide with 3(2H)-isoquinoline	.. 532
Niranjan, G. S. <i>See</i> B. C. Sikoria	.. 905	Pandey, Rajnish K. <i>See</i> Rajendra S. Varma	1174
Nizamuddin <i>See</i> S. Giri	365	Pandeya, K. B. <i>See</i> Indra Rani	235
"O"			
Ojha, A. N. <i>See</i> H. C. Mishra	792	Pandeya, K. B. <i>See</i> K. Mukkanti	830
O'Reardon, Desmond J. <i>See</i> Reg Davis	1270	Pandeya, K. B. <i>See</i> R. S. Sindhu	... 895
Osman, A. M., M. Z. A. Badr, A. M. Mahmoud and Z. A. Hezien—Cyclocondensation and Cycloaddition Reactions on the Unsaturated Centre of Arylidene-2-amino-benzoxazole	763	Pandeya, K. B. <i>See</i> T. S. Waraich	103, 213
Oza, C. K. <i>See</i> R. C. Mehrotra	486	Pandit, Uttam Kumar <i>See</i> (Mrs.) Asima Chatterjee	... 523
Oza, Chandra K. <i>See</i> Prakash C. Vyas	305	Pannu, B. S. <i>See</i> A. Gupta	937
Oza, (Mrs.) J. A. <i>See</i> (Miss) C. C. Kotecha	.. 82	Paranjpe, M. G. <i>See</i> P. P. Pathe	.. 670
"P"			
Padhi, N. P. <i>See</i> B. C. Singh	349	Paranjpe, M. G. <i>See</i> R. T. Iadhave ...	71, 1003, 1004
Padhy, P. C. and R. N. Patel—Mixed Ligand Complexes of Zinc(II)	992	Pardeshi, (Miss) Leela G.—Study of Dielectric Properties and Dipole Moments of Mn(II) Salts of Some Fatty Acids in Benzene Solutions	.. 1050
Padhy, P. C. and R. N. Patel—Mixed Ligand Complexes of Zinc(II) with Dibasic Acids and Nitrogen Donor Ligands	1182	Parhi, Narahari <i>See</i> Anil K. De	... 1334
Pal, A. <i>See</i> S. Dutta	902	Parikh, A. R. <i>See</i> V. H. Shah	.. 678
Pal, Anang <i>See</i> H. S. Verma	1184	Pasarkar, V. R. <i>See</i> P. W. Agnihotri	869
Pal, M. K. and Pravash Chandra Manna—Molecular Complex of 8-Hydroxyquinoline and Potassium Hexacyanoferrate(II) in Acid Medium	409	Patel, B. N. <i>See</i> K. C. Satpathy	40
Palit, Santi R. and Subhalakshmi Ghosh—Transition of Non-Faradaic Electrolysis to Faradaic Electrolysis by Change of Conditions	.. 759	Patel, H. H. <i>See</i> V. H. Shah	... 678
		Patel, Kanti <i>See</i> Ramesh Patel	... 1145
		Patel, P. J. <i>See</i> P. K. Bhattacharya	310
		Patel, R. B. <i>See</i> J. K. Verma	... 43
		Patel, R. N. <i>See</i> P. C. Padhy	992, 1182
		Patel, Rajani <i>See</i> Ramesh Patel	... 1145
		Patel, Ramesh; Rajani Patel and Kanti Patel	

—Thermal Degradation of <i>p</i> -Anisic Acid—		Determination of Palladium(II) and Platinum(IV) with Dibenzylidenethiocarbonylhydrazide	
Formaldehyde Condensation Product	1145	Prasad, A. R. See M. K. Mody	769
Patel, V. K. See P. K. Bhattacharya	1244	Prasad, B. See C. K. Choudhary	555
Pateria, M. G. and R. M. Verma—An Indirect Method for the Iodometric Microdetermination of Certain Organic Acids	1203	Prasad, Dharmbir See A. K. Banerjee	1303
Pathak, B. C. See G. K. Mitra	367	Prasad, N. ; S. C. Agarwal, J. N. Chatterjea and S. C. Sengupta—Free Acids in Lac Resin	980
Pathak, D. N.—Reactivity of Indian Rock Phosphates in Presence of Oxidative Degradation Products of Coal	899	Prasad, R. and S. T. Nerenberg—Chaotropic Ions and Acid Buffers as Eluents in Ligand Purification Using Semiautomated Affinity Chromatography	1220
Pathak, R. B. ; (Miss) U. Srivastava and S. C. Bahel—Synthesis of 5-Aryl/Aryloxyalkyl-1,3,4-Oxadiazoles-2-Thiones and Related Compounds as Possible Fungicides	776	Prasad, R. S. ; Amrita Kumari and N. K. Jha —Disothiocyanatodihalonitric acidates(II)	207
Pathak, S. P. See S. G. Misra	466	Prasad, Salik See Ram Lakhan	804
Pathak, Vijai N. See Krishna C. Joshi	293, 1072	Prasad, Sukhmandan See Jitendra Choudhary	638
Pathe, P. P. ; (Miss) Manik W. Ambekar, N. M. Nimdeokar and M. G. Paranjpe—On 1,3,5-Triazines. Part-II : Synthesis of 2,4-Dithio-3,5-Diaryl-6-Phenylimino-Hexahydro-1,3,5-Triazines and 2,6-Dithio-3,5-Diaryl-4-Phenylimino-Hexahydro-1,3,5-Triazines	670	Prasad, U. S. See (Miss) K. Das	334
Patil, S. R. ; U. N. Kantak and D. N. Sen—Phenyl-Tin Cleavage by Some Ferrocenyl Hydrazones	1300	Prášilová, J. See J. Stary	1329
Patil, V. H. and D. B. Ingle—2-Aryl amino-4-[4'-(benzene sulphonamido)-phenyl]-thiazoles	1000	Pujari, S. K. See Bipin B. Mahapatra	98, 1022, 1183
Patnaik, D. See B. V. Alaka	1168	Puri, D. M. See (Miss) Neelam Palta	261
Patra, Amarendra ; Alok K. Mitra and Apurba K. Mukhopadhyay—Carbon-13 NMR Signals of Some Phenothiazine Derivatives	660	Puri, D. M. See Hemant K. Sharma	1031
Pitre, K. S. and S. C. Lavale—Amperometric Estimation of La <sup>3+</sup> and Ce <sup>3+</sup> with Cupferron using d. m. e.	1081	Puri, D. M. See S. N. Dubey	1133
Pitre, K. S. See S. C. Lavale	965	Purohit, S. S. See M. S. Mayadeo	894, 952, 955
Polianova, Maria See Liliana Ilcheva	1352	"R"	
Pradhan, B. See B. K. Kanungo	329		
Prakash, Om See V. K. Mahesh	1192	Rahman, Wasiur See Mohd. Kamil	1199
Prakash, Satya and J. Venu Gopalakrishna Murthy—Ultrasonic Study of the Elastic Constants of Some Ancient and Mediaeval Indian Coins	591	Rai, A. K. See Y. P. Singh	273
Pramanik, J. and H. R. Das—Extraction and Photometric Method for the Simultaneous		Rai, Mangat ; (Miss) Baljit Kaur and B. S. Dhir—Studies on Schiff Bases of Veratraldehyde	416
		Rai, Mangat and (Miss) Baljit Kaur—Synthesis of 1,2,4-Oxadiazolines Having Antifungal Activity	1197
		Rai, Mangat ; Surinder Kumar, Baldev Singh, Kewal Krishan and Ajit Singh—Synthesis and Reduction of Nitrones of Vanillin	80
		Rai, S. J. See R. P. Chamoli	863
		Raina, Nancy See Anila Thusoo	1007
		Raj, J. B. See H. Sanke Gowda	1398
		Rajgolkar, R. L. See V. A. Mukhedkar	295
		Rakhshinda, (Miss) See Naseem H. Khan	1077
		Ramachandran, N. See V. G. Gunjkar	743



Ramaiah, T. Sundara ; S. K. Ramraj, Ch. Govardhan and V. Vishwanath Rao—Aza Triterpenes-III : Action of Excess Hydrazoic Acid-Boron Trifluoride Etherate on 3-Oxo-Penta Cyclic Triterpenes ...	975	Manganese as an Oxidising and Decomposing Agent ...	1430
Ramalingam, T. See M. K. Mody	769	Rao, S. Zaman ; A. A. Khan and S. C. Mehra—Synthesis of N-Benzoyl-N'-2-(4-Aryl-5-Arylazothiazolyl) Thiocarbamides as Potential Antineoplastics ...	375
Ramana, Karri V. See S. R. Sagi	336	Rao, T. Navaneeth See M. Anand Rao	1040
Ramraj, S. K. See T. Sundara Ramaiah	975	Rao, V. M. See H. V. N. Murty	1343
Ramrakhyani, A. K. See Pradeep Kumar	681	Rao, V. Vishwanath See T. Sundara Ramaiah	975
Ranbaore, Vilas See V. J. Tyaga Raju	199	Rastogi, Anita See Anil K. Sen Gupta	1102
Randall, William J. See Dean F. Martin	1232	Rastogi, Renu See J. S. Shukla	779
Ranganathan, T. N. See G. S. Rao	518	Rathi, S. S. See S. Ghosh	567
Ranganayaki, S. See Krishna Bahadur	480	Ratnasamy, P. See V. Krishnasamy	839, 1151
Rani, Indra ; K. B. Pandeya and R. P. Singh—Reactions of Coordinated Oximes. Part-V. Reactions of Aluminium Isopropoxide on Some Cobalt(II) Bis-Chelates of o-Hydroxy Oximes ..	235	Rawat, J. P. ; K. P. Singh Muktaawat and Onkar Singh—Detection and Chromatographic Separation of Phenols on Papers Impregnated with Ferric Hydroxide ...	1011
Rao, A. L. J. and Makhan Singh—Polarographic Determination of Stannous (tin) with Acrylic Acid	1083	Ray, A. B. See Lax Chand	1001
Rao, B. G. See C. S. Prakasa Sastry	1107	Ray, J. K. See Sitaram Sharma	536
Rao, B. Rajeshwara See M. Sadasiva Shankar	1104	Ray, Naba K. See Rita Chadha	204
Rao, C. N. R. See P. Vishnu Kamath	153	Ray, P. K. See S. Ghosh	1034
Rao, D. V. Ramana See B. K. Kanungo	329	Ray, Rahul and Donald S. Matteson—A Highly Efficient Osmium Tetraoxide Catalyzed Oxidation of Sterically Hindered Olefins to Diols	119
Rao, G. N. and A. Varadarajulu—Systematic Study of the Solvent Extraction of Metal-Tridentate Schiff Base Complexes	1009	Ray, S. K. See S. Ghosh	1034
Rao, G. S. and T. N. Ranganathan—High Purity and Special Materials for Electronics	518	Ray, Uday S. See Anil K. De	1334
Rao, K. N. See T. N. Das	85	Ray, Uday Sankar and S. C. Modak—Extraction of Cerium(IV) by Liquid Cation Exchanger (Versatic 10) and its Separation from Lanthanide Elements ...	392
Rao, K. Narasimha See Y. Anjaneyulu	1024	Ray, Uday Sankar and Sagar Chandra Modak—Solvent Extraction of Thorium with Liquid Cation Exchanger (Versatic 10) ...	911
Rao, M. Anand ; B. Sethuram and T. Navaneeth Rao—Oxidation Studies. Part-XV : Ag(I)—Catalysis in Oxidation of Amines by Ce(IV) in Nitric Acid, A Kinetic Study	1040	Raychaudhuri, S. P.—Integrated Nutrient to Soil for Soil Productivity ...	435
Rao, M. S. Prasada See S. R. Sagi	336	Raychaudhuri, T. K. See H. K. Saha	723
Rao, N. Prabhakara See Y. Anjaneyulu	1024	Reddy, K. Adinarayana See K. Raja Reddy	422
Rao, P. Nageswara See K. Raja Reddy	422	Reddy, K. Raja ; P. Nageswara Rao and K. Adinarayana Reddy—Spectrophotometric Study of the Complexation Reaction between Oxovanadium(IV) and Gallacetophenoneoxime ...	422
Rao, P. Raghunatha and E. V. Sundaram—Kinetics of Oxidation of Substituted Benzaldehydes by KMnO <sub>4</sub> in Buffer Medium	704	Reddy, Y. D. See D. Annapurna	977
Rao, S. B. and B. R. Sant—Tetravalent		Reddy, Y. D. See M. Sadasiva Shankar	1104

Resch, G. ; V. Gutmann and H. Schauer— The "Shaking Effect" on the Conductivities of Liquids ..	130	Saha, H. K. ; S. S. Mandal and P. C. Ghorai— Stabilisation of Molybdenyl Cations with 4,4'-Dimethyl 2,2'-Bipyridyl in Different Salt and Non-electrolytic Complexes ...	112
Richards, P. See S. C. Srivastava	1262	Saha, M. B. and A. K. Chakraburty— Spectrophotometric Determination of Palladium with Rubeanic Acid in Presence of Piperidine, Quinoline, $\alpha$ -Picoline and Collidine ..	110
Rohatgi-Mukherjee, K. K. See Sekhar Basu	578	Saha, Nityananda and Krishna M. Datta— Cobalt(II) Complexes of 5(3)-Methyl pyrazole-3(5)-Carboxamide ...	7
Rout, M. K. See B. C. Singh	349	Sahai, R. ; S. Agrawal and S. S. S. Kushwaha —Complexation of Salicylanilide with Some Metal Ions of Biological Interest	8
Rout, M. K. See B. V. Alaka	1168	Sahai, R. ; S. Agrawal and S. S. S. Kushwaha —Stacked Ternary Complexes of Salicyla- nilide, Dithionon and Tryptophan with Co(II), Ni(II) and Cu(II)	11
Roy 'Anil', K. K. and L. K. Mishra—Com- plexes of Some Platinum Metals with 4-Amino-3,5-Dimercapto-1,2,4-Triazole	797	Sahai, R. ; V. Singh and Rekha Verma— Differential Refractometric and Conducto- metric Studies on the Charge-Transfer Interaction of Some Metal $\beta$ -Diketonates with Iodine	
Roy, Ansuman ; Debasis Bhattacharya and S. Aditya—Photo-Chemistry of Aqueous Anthraquinone-2-Sulfonate Solution	585	Sahai, Radhika P. See J. N. Chatterjea	13
Roy, B. B. and Samir Kumar Mukherjee—A Study of Iron Concretions in Lateritic Soil of West Bengal	440	Saharia, G. S. See R. K. Gautam	3
Roy, R. N. ; S. B. Mishra and B. K. Moha- patra—Mixed Ligand Complexes of Co(II), Ni(II), Cu(II) and Zn Salts with <i>o</i> -Hy- droxy Propiophenone and Quinoline ...	1094	Saharia, G. S. See S. C. Nigam	7
Roy, S. K. See A. K. Banerjee	1020, 1089, 1186, 1303	Sahu, B. K. and B. K. Mohapatra— $\gamma$ -Carbon Bonded Acetylacetonato Complexes of Pd(II)	7
Roy, S. K. See H. C. Mishra	792	Saini, S. K. ; V. D. Gupta and R. C. Mehrotra —Fe(III), Co(III), Cu(II) and Ni(II) Derivatives of Some New Monothio- $\beta$ - Diketones	14
Roy, S. K. and P. P. Jha—Infrared Spectra and Thermal Studies of Some Reported Heteropoly Complexes	1096	Saksena, R. K. See Akhtar Ali	4
Roy, Shyamali ; Lina Bhattacharyya and D. P. Chakraborty—Structure and Syn- thesis of Mukoline and Mukolidine, Two New Carbazole Alkaloids from <i>Murraya</i> <i>koenigii</i> Spreng	1369	Salemn, S. M. See I. M. Sidahmed	11
		Saluja, M. P. See Mahendra Pal Sharma	8
		Salunkhe, M. M. See M. H. Jagdale	3
		Samaddar, Haraprasad and Amalendu Banerjee—Use of Potassium Bromate : Oxidation of Aldehydes	9
		Samant, S. D. and M. S. Mayadeo—Electron Impact Induced Fragmentation of Schiff Bases of 2-hydroxy-5-methylbenzaldehyde	3
		Sandhu, S. S. ; M. S. Sidhu and A. S. Brar— Photochemical Reduction of Uranyl Ion with Tri- <i>p</i> -Tolylphosphine	1

# "S"

Sagi, S. R. ; Karri V. Ramana and M. S. Prasada Rao—Some Studies on Thallium Oxalates-VIII : Barium <i>Bis</i> -Oxalato Diaquo Thallate(III) Monohydrate ...	336
Saha, B. G. ; R. P. Bhatnagar and Samir K. Banerji—Synthesis and Characterization of Complexes of Co(II), Cu(II), Cd(II), Mg(II) with Disubstituted Thioureas	927
Saha, H. K. ; B. K. Sikdar and T. K. Ray- chaudhuri—Studies on Reactivity of Molybdenyl(V) Cation in the Environment of Diverse Anions in Presence of 5-Nitro 1,10-Phenanthroline as an Organic Base .	723

- Sandhu, S. S. *See* T. S. Lobana 799
- Sane, R. T. ; A. S. Gijare, A. B. Ambardekar and D. S. Deshpande—Colorimetric Estimation of Ce(IV) by Phenothiazines 1201
- Sangal, S. P. *See* S. U. Lakhan 801
- Sankhla, D. S. ; R. C. Mathur and Sudhindra N. Misra—Spectral and Magnetic Studies of Some Mixed Ligand Complexes of High-Spin Cobalt(II) 893
- Sant, B. R. *See* S. B. Rao 1430
- Santappa, M.—Carbon Fibres 321
- Sanyal, S. K. *See* S. K. Mandal 803
- Sanyal, Saroj Kumar and M. Adhikari—Thermosmosis in Membranes 460
- Saran, Anil *See* Girjesh Govil 1226
- Sarkar, Bibudhendra—Peptide Models for the Metal-Binding Sites of Proteins and Enzymes 1403
- Sarkar, G. N. and J. L. Das Kanungo—Ion Exchange Selectivity of Monovalent Ions in Aqueous and 50% Ethanol-Water Media towards *Tris*-Trimethylene Diamine Co(III) Exchanged Amberlite-IRC-50 358
- Sarkar, (Miss) S. *See* G. N. Mukherjee 1117
- Sarkar, S. *See* J. Banerji 145
- Sarkar, Suvra *See* (Mrs) Asima Chatterjee 523
- Sastri, M. N. *See* H. V. N. Murty 1343
- Sastry, C. S. Prakasa, B. G. Rao and K. V. S. S. Murthy—Spectrophotometric Determination of Aromatic Amines Using Catechol and Iodine 1107
- Satapathi, S. K. *See* R. L. Dutta ... 332
- Satpathy, K. C. ; H. P. Mishra and B. N. Patel—Complexes of *p-p'*-bis (benzoyl thiourea) Benzene with Cu(II), Ni(II) and Co(II) Salts and Their Biological Activity 40
- Sattur, P. B. *See* M. K. Mody 769
- Savarianandam, A. *See* A. Natarajan ... 1155
- Saxena, B. B. L. *See* Bharat Singh 59
- Saxena, J. P. *See* R. P. Soni ... 668
- Saxena, M. C. *See* S. N. Limaye .. 698, 916
- Saxena, R. C. *See* H. S. Verma . 1184
- Saxena, R. S. and G. L. Sharma—Physico-Chemical Studies on the Composition and Stability Constants of Zn(II), Cd(II) and Hg(II) DL-Valine Complexes ... 635
- Saxena, R. S. and G. L. Sharma—Potentiometric Determination of Dissociation Constants of DL-Tryptophan in Different Aquo-Organic Solvents ... 413
- Saxena, R. S. and S. P. Bansal—Polarographic Study of Thorium(IV) and Uranyl(II) Complexes with DL-Ornithine Hydrochloride ... 702
- Saxena, Sanjiv *See* Y. P. Singh 273
- Saxena, Shradha *See* J. S. Shukla 1196
- Saxena, V. K. *See* V. S. Misra 781
- Saxena, V. K. *See* Vinay S. Misra . 1074
- Schauer, H. *See* G. Resch 130
- Schaumberg, Gene D., C. S. Levesque-Madore, Garrison Sposito and A. C. Chang—Infrared Spectroscopic Study of Saturation Extracts from Arid-Zone Field Soils Amended with Sewage Sludge 150
- Sen, A. K.—Role of Toxic Aromatic Compounds in Nitrogen Enrichment 476
- Sen, D. N. *See* S. R. Patil 1300
- Sen Gupta, A. K. *See* Pradeep Kumar 681
- Sen Gupta, Anil K. and Anita Rastogi—Synthesis of Some New 1-Substituted 5-bromo-3-aryloxy acetyl hydrazono-2-indolinones as Potential Antibacterial Agents 1102
- Sengupta, S. C. *See* N. Prasad 980
- Sen Sarma, R. N. and M. K. Majumdar—Determination of Aluminium in Iron Ores . 790
- Seth, R. L. *See* O. P. Bahl 1306
- Sethuram, B. *See* M. Anand Rao 1040
- Seyferth, Dietmar ; Carol K. Haas and Doron Dagan—*Bis*(iodomethyl) Mercury as a CH<sub>3</sub> Transfer Reagent 111
- Shah, A. *See* R. R. Darji . 657
- Shah, Pramila *See* Vinay S. Misra ... 1074
- Shah, V. H. ; H. H. Patel and A. R. Parikh—Studies on Acetamide Derivatives: Preparation and Antimicrobial Activity of 2- $\alpha$ -Arylaminoacetamido/ $\alpha$ -carbamoyl benzylamino/Arylcarbamoylmethylamino-5-*o*-Nitrophenyl/Benzoylaminoethyl-1,3,4-Thiadiazoles ... 678
- Shankar, M. Sadasiva ; B. Rajeshwara Rao, G. V. P. Chandra Mouli and Y. D. Reddy—

Synthesis of Substituted 6-Pyrazolo and 6-Isoxazolo-Benzoxazoles and Their Physiological Activity .	1104	Sharma, S. K. See (Km.) Anita Manglik ...	352
Shanmuganathan, Sp.; V Durai and T. Sundaravelu—Physico-Chemical Studies on Some Alkylmercapto- and Alkylsulphonyl Phenols ..	52	Sharma, Sitaram; J. K. Ray and Basanta G. Chatterjee—Synthesis of Some Novel $\beta$ -lactam Derivatives ..	536
Sharda, (Miss) Pushpa and G. C. Shivahare—Potentiometric Determination of Niobium(V) in Presence of Tantalum in Non-Aqueous Media	906	Sharma, Surendra K. See M. R. Chaurasia .	370
Sharda, (Miss) Pushpa See G. C. Shivahare	242	Sharma, Uma Shankar Prasad See B. Singh ..	1187
Sharma, C. L. and T. K. De—Polyamino Chelates of Co(II), Ni(II), Cu(II), Zn(II) and Pd(II) using Cysteine as a Secondary Ligand .	101	Sharma, V. See A. Kumar	280
Sharma, C. P. See Sangeeta Wadhwa	247	Shelke, D. N.—Equilibrium Study of the Mixed Complexes of Uranyl Ion with 3,5-Dinitrosalicylic as Primary and Some Substituted Carboxylic Acids as Secondary Ligands ...	833
Sharma, D. K. See B. Singh	1187	Sheth, (Miss) Geeta N. and V. V. R. Subrahmanyam—Properties of Pure Sodium Soaps of Saturated Fatty Acids ...	860
Sharma, G. L. See R. S. Saxena	413, 635	Sheth, (Miss) Geeta N. See Venkataraman N. Iyer	856
Sharma, H. See A. Kumar	280	Shinde, V. M. See D. V. Khasnis	93, 812
Sharma, H. N. See Purushottam B. Chakraborti .	734	Shivahare, G. C. and (Miss) Pushpa Sharda—Studies on the Coordination of Niobium(V) with 1,6-Dihydroxyphenazine ...	242
Sharma, H. R. See S. C. Nigam	709	Shivahare, G. C. See (Miss) Pushpa Sharda ..	906
Sharma, Hemant K.; S. N. Dubey and D. M. Puri—Metal Derivatives of Organoantimony Compounds: Reactions of Anhydrous Chlorides of B(III), V(III) and Sn(IV) with Arylantimony Compounds .	1031	Shoolery, J. N. See (Mrs.) Asima Chatterjee	523
Sharma, J. C. See Mahendra Pal Sharma	810	Shoolery, J. N. See J. Banerji	145
Sharma, M. P. See Wahid U Malik	1057	Shrivastava, S. P. and S. S. Nigam—Chemical Examination of <i>Medicago sativa</i> Seeds	1198
Sharma, Mahendra Pal; S. P. Srivastava, V. K. Mahesh, M. P. Saluja and J. C. Sharma—Chemical Investigation of <i>Wrightia mollissima</i> ..	810	Shukla, G. N. See S. K. Bajpai	343
Sharma, N. K.; J. L. Norula and S. K. Mathey—Transformation of Sucrose: An Alternative Route for Amination	385	Shukla, G. N. See S. R. Tewari	891
Sharma, N. K. See P. S. Bassi	968	Shukla, H. K.; N. A. Langalia, N. C. Desai and K. A. Thaker—Studies on Antitubercular Agents. Preparation of 2-Arylamino-4-(4-Carbethoxyaniline)-6-Isonicotinylhydrazino-1,3,5-Triazine .	1101
Sharma, R. C. See M. R. Manrao	901	Shukla, J. S.; Kanchan Agarwal and Renu Rastogi—Studies on Synthesis and Anthelmintic Activity of N-(Substituted Phenoxy Acetamido) Phthalimides	779
Sharma, (Late) R. D. See J. S. Upadhyaya	1097	Shukla, J. S.; Shradha Saxena and Ranjana Misra—Studies on Some Biologically Active Quinazolones. Synthesis of 2-Phenoxy methyl-3-N-substituted Amino Carbonyl methyl-8-substituted 4(3H) quinazolones as Anticonvulsant Agents ..	1196
Sharma, R. S. and S. C. Bahel—Synthesis of Aryloxy/Aryl Acetyl Thiosemicarbazides, Substituted 1,3,4-Oxadiazoles, 1,3,4-Thiadiazoles, 1,2,4-Triazoles and Related Compounds as Potential Fungicides ...	877	Shukla, (Mrs.) P. R.; Chandreshwari Srivastava, V. K. Singh and Gopal Narain—A Study of the Decomposition Patterns of Some Transition Metal Complexes Derived	
Sharma, Rajendra K. See Purshotam Soni	913		
Sharma, Ravi S. See Prakash C. Vyas	305		

- mainly from the Heterocyclic Ligands viz., Furan-2-Carboxaldoxime and 3-methyl-4-arylazopyrazole-5-one using Thermogravimetric Analysis . 1180
- Shukla, (Mrs.) P. R. ; V. K. Singh, Jayant Bhargava and Gopal Narain—Characterisation of Some Solid Products Obtained by Carrying Out the Replacement Reactions on the Hydrated Sulphates of Copper(II), Nickel(II) and Cobalt(II) Using Two Different Heterocyclic Ligands Viz., Antifuran-2-carboxaldoxime and 2-Pyrrolidone . 620
- Shukla, R. K. See R. C. Maurya 340
- Shukla, R. S. See Pradeep Kumar 681
- Sid Ahmed, I. M. ; S. M. Salem and F. M. Abdel Halim—The Alkaline and Acid Hydrolysis of *n*-Butylacetate in Methanol-Water Mixtures 1139
- Siddhanta, Arup K See Avijit Banerji 542
- Siddiqui, Ahsan R See Syed A. Nabi 1200
- Sidhu, M. S. See S. S. Sandhu 173
- Sidhu, R. See R. L. Blokhra 63
- Sikdar, B. K. See H. K. Saha ... 723
- Sikoria, B. C. ; S. J. Srivastava and G. S. Niranjan—Phytochemical Studies on *Eclipta alba* .. 905
- Sindal, R. S. ; K. C. K. Mathur and R. C. Kapoor—Cyclic Voltammetry of Thallium(I) in Different Supporting Electrolytes 1313
- Sindhu, R. S. ; K. B. Pandeya and R. P. Singh—Polarographic Reduction of Uranyl(II) in Presence of Some Disubstituted Pyridines 895
- Singh, A. K. ; D. Nath, M. Katyal and R. P. Singh—Cu(I), Ag(I), Tl(I), Zn(II), Cd(II) and Hg(II) Complexes of 1-Amino-4,4,6-trimethyl-1H, 4H-Pyrimidine-2-thiol 625
- Singh, Ajit ; Surinder Kumar, M. R. Manrao and (Miss) Baljit Kaur—Addition of Sulphene to Substituted Benzalanilines 673
- Singh, Ajit See Mangat Rai 80
- Singh, B. See A. K. Narula 195, 1296
- Singh, B. See R. C. Aggarwal . 269
- Singh, B. and V. D. Gupta—Metal Complexes of Sulfur-Nitrogen Chelating Agents .
- Organotin(IV) Derivatives of Diethylaminomethyl Ester of 2-Amino-1-cyclopentene-1-carbodithioic Acid .. 793
- Singh, B. and V. D. Gupta—Metal Complexes of Sulphur-Nitrogen Chelating Agents : Transition Metal Complexes of the Esters of 2-Amino-1-cyclopentene-1-dithiocarboxylic Acid 244
- Singh, B. C. ; P. L. Nayak, M. K. Rout and N. P. Padhi—Oxidation of Methyl Group : Kinetics of Cerium(IV) Oxidation of 2-Methyl Benzthiazole, Benzoxazole and Benzimidazole in Acetic-Perchloric Acid Mixture 349
- Singh, B. , Uma Shankar Prasad Sharma and D. K. Sharma—Conductometric and Spectrometric Studies on Complex of Ag(I) and Hg(II) Ions with N, N'-Diphenyl Thiourea . 1187
- Singh, B. R. and R. Ghosh—Spectrophotometric Determination of Dissociation Constants of Violuric Acid and Stability Constant of its Cu(II) Complex .. 939
- Singh, Baldev See Mangat Rai .. 80
- Singh, Bhagwat ; P. L. Maurya, B. V. Agarwala and Arun K. Dey—Coordination Polymers of Terephthaldehyde bis-(semicarbazone) with Some Bipositive Cations ... 1130
- Singh, Bharat, Chandra Pal Singh Gaur, Ras Bihari Singh and B. B. L. Saxena—Kinetic Study of Ag(I) Catalysed Oxidation of Glycine by Ce(IV) in Perchloric Acid Medium 59
- Singh, Bhagwat ; P. L. Maurya, B. V. Agarwala and Arun K. Dey—Polymeric Bipositive Metal Ion Complexes of Terephthaldehyde bis-(isonicotinic acid hydrazone) 29
- Singh, Devendra, O. V. Singh and S. N. Tandon—Solvent Extraction Studies on Thiocyanate Complexes of Zinc(II), Cadmium(II) and Mercury(II) 1338
- Singh, K. R. R. P. See J. N. Chatterjee 527
- Singh, M. K. See R. C. Aggarwal ... 269
- Singh, M. P. See A. Sharma 622
- Singh, Makhan See A. L. J. Rao . . 1083
- Singh, Malkiat See Balbir Chand Verma . 811

Singh, Mukhtar <i>See</i> Ashok Kumar	...	843	sence of Salicylic and Substituted Salicylic	
Singh, Mukhtar <i>See</i> J. C. Khatri	...	897	Acids in Dilute Perchloric Acid Medium	55
Singh, Mukhtar <i>See</i> Mahesh Chandra Dubey		706	Srinivasan, A. <i>See</i> P. Vishnu Kamath	153
Singh, O. V. <i>See</i> Devendra Singh		1338	Srinivasulu, K. <i>See</i> U. C. Maiwal	395
Singh, Onkar <i>See</i> J. P. Rawat		1011	Srivastava, C. P. <i>See</i> A. S. Tyagi	823
Singh, P. P. ; S. A. Khan and M. U. Khan— Synthesis and Structural Studies of Some Mixed Ligand Bimetallic Tetrathiocyanato Complexes		35	Srivastava, Chandreshwari <i>See</i> (Mrs.) P. R. Shukla	1180
Singh, R. <i>See</i> Mohammad Ramzan Ali		663	Srivastava, G. <i>See</i> P. N. Bhardwaj	300
Singh, R. P. <i>See</i> A. K. Singh	..	625	Srivastava, (Miss) Gunjan and Arvind Kumar —Studies on the Polarographic Reduction of Progesterone	958
Singh, R. P. <i>See</i> Harish Kumar Arora		347	Srivastava, H. C. <i>See</i> I. P. Varshney	884
Singh, R. P. <i>See</i> Indra Rani		235	Srivastava, J. K. <i>See</i> S. C. Bahel	1127
Singh, R. P. <i>See</i> K. Mukkanti		830	Srivastava, (Miss) M. <i>See</i> T. N. Srivastava	1028
Singh, R. P. <i>See</i> R. K. Kadian	..	1247	Srivastava, O. P. <i>See</i> Pradeep Kumar	681
Singh, R. P. <i>See</i> R. S. Sindhu	...	895	Srivastava, P. C. <i>See</i> T. N. Srivastava	186
Singh, R. P. <i>See</i> Suresh K. Garg	...	1038	Srivastava, P. K. <i>See</i> J. S. Upadhyaya	683, 767, 808, 1097
Singh, R. P. <i>See</i> T. S. Waraich	...	103, 213	Srivastava, P. K. <i>See</i> S. C. Tripathi	238
Singh, Raj Pal <i>See</i> Ajay K. Jain		106	Srivastava, R. C. <i>See</i> M. Imtiaz Husain	1193
Singh, Ras Bihari <i>See</i> Bharat Singh		59	Srivastava, R. C. <i>See</i> T. N. Srivastava	1028
Singh, Tarkeshwar <i>See</i> A. K. Banerjee		1089, 1186	Srivastava, Rashmi <i>See</i> V. S. Misra	781
Singh, V. <i>See</i> R. Sahai		46	Srivastava, S. C. <i>See</i> S. C. Tripathi	238
Singh, V. K. <i>See</i> A. Mishra		622	Srivastava, S. C. and P. Richards—Coordina- tion Chemistry of Technetium as Related to Nuclear Medicine	126
Singh, V. K. <i>See</i> (Mrs.) P. R. Shukla		620, 1180	Srivastava, S. J. <i>See</i> B. C. Sikronia	90
Singh, Y. P. ; Sanjiv Saxena and A. K. Rai— Some New $\beta$ -Diketonates of Boron : Their Synthesis and Characterisation		273	Srivastava, S. K. <i>See</i> W. U. Malik	105
Singhal, O. P. <i>See</i> A. K. Mittal		373, 711	Srivastava, S. K. , (Km.) Anita Verman and (Km.) Achla Gupta—Complexing Beha- viour of N-cyclo Hexyl Benzothiazole Sul- phonamide with Cu(II), Mn(II), Ni(II), Co(II) and Fe(III)	92
Sinha, K. S. <i>See</i> R. D. Tiwari		526	Srivastava, S. P. <i>See</i> Mahendra Pal Sharma	81
Sinha, S. B. <i>See</i> A. K. Dwivedi		450	Srivastava, T. N. ; P. C. Srivastava and Rakesh Kumar—Reactions of Benzotellu- racyclopentane Diiodide	18
Sinha, Sailendra K. <i>See</i> A. K. Banerjee		1020	Srivastava, T. N. ; R. C. Srivastava and (Miss) M. Srivastava—Some Anionic Organotellurium Complexes	102
Somayajulu, V. V. <i>See</i> D. Annapurna		977	Srivastava, (Miss) U. <i>See</i> R. B. Pathak	77
Soni, Purshotam ; Kailash Chandra, Rajendra K. Sharma and Bhagawan S. Garg—Effect of Different Groups on Cyclopentadienyl Ring on the Stability of Titanium-Cyclo- pentadienyl Bond		913	Srivastava, Vinita and H. L. Nigam—Plaro- graphic Study of Ternary Complexes in Solution : Complex Formation Between Copper(II) 2,2'-bipyridyl 1 : 1 Complex and Ligands Containing Oxygen and or Nitrogen Donor Atoms as Secondary Ligands	2
Soni, R. P. and J. P. Saxena—Heterocyclic Quinones. Part-III : Synthesis of Dialkyl- benzodipyrrocolinequinones		668		
Soundararajan, S. <i>See</i> V. Krishnasamy		1067		
Sposito, Garrison <i>See</i> Gene D. Schaumberg		150		
Sreeman, P. <i>See</i> T. D. Radhakrishnan Nair		415		
Srinivas, K. ; K. V. Subbaiah and P. V. Subba Rao—Kinetics and Mechanism of Oxida- tion of <i>m</i> -Cresol by Vanadium(V) in Pre-				

- Srivastava, Vinita ; K. B. Lal and H. L. Nigam—Correlation of Electrode Behaviour and Spectral Properties of Some Mixed-Ligand Complexes of Copper(II) . 497
- Staniek, H. See J. Korkisch 1331
- Stary J. ; K. Kratzer and J. Prasilová—The Cumulation of Methylmercury and Phenylmercury Species on Alga 1329
- Steffan, I. See J. Korkisch 1331
- Steyermark, Al—Teaching Microchemistry in Industry Versus Teaching in a University 1213
- Subba Rao, P. V. See K. Srinivas 55
- Subbaiah, K. V. See K. Srinivas 55
- Subrahmanyam, V. V. R. See (Miss) Geeta N. Sheth 860
- Subrahmanyam, V. V. R. See Venkataraman N. Iyer 856
- Subramaniam, T. V See V Krishnasamy 1067
- Sundaram, E. V. See P. Raghunatha Rao 704
- Sundaramaiah, T. and V Viswanath Rao—Oxidative Decarboxylation. Partial Synthesis of Aegiceradienol (*nor* Echinocystadienol) 74
- Sundaravelu, T. See Sp Shanmuganathan 52
- Suryanarayana, A. V See N Krishna Murty 1113
- Suryanarayana, C. V—New Conceptions on the Equilibrium Properties of Electrolyte Solutions 562
- Swami, S. S. See M H. Jagdale . 355
- Swamy, R. Y. See Y. Anjaneyulu 1024
- Swan, Idris M. See Adnan A Karim Al-Dhahir 645
- Syamal, A. and B. K. Gupta—Cobalt(II) Complexes with ONO Donor Tridentate Schiff Bases Derived from Salicylaldehyde, Substituted Salicylaldehyde and Orthohydroxybenzylamine 697
- Syamal, A. and D. Kumar—Dioxouranium(VI) Heterochelates ... 96
- "T"
- Talapatra, Bani ; Shyamaprosad Goswami and Sunil K. Talapatra—Alkaloids of *Machilus glaucescens* Wight. Machigline A New Phenolic Oxoaporphine Alkaloid ... 1364
- Talapatra, Bani See Sunil K. Talapatra . 534
- Talapatra, Sunil K. ; Mallik, Ashok K. and Bani Talapatra—Carbon-13 NMR Spectra of Angular and Linear Furanoflavones . 534
- Talapatra, Sunil K. See Bani Talapatra ... 1364
- Talegaonkar, Jyoti and K. S. Boparai—Determination of Sodium-*N*-Alkyl/Dialkyl Dithiocarbamates by Reaction with 2,4-Dinitrobenzenesulphenyl Chloride and Alkalimetric Determination of Ammonium-*N*-Aryl Dithiocarbamates . 108
- Talegaonkar, Jyoti and K. S. Boparai—Determination of Xanthates by Reaction with 2,4-Dinitrobenzenesulphenyl Chloride ... 109
- Talegaonkar, Jyoti See Suman Mukhija ... 427
- Tanaka, K See R Bruce King 124
- Tandon, K. N ; A. K. Mishra and R. G. Mishra—Some Reactions of Nickel Chloride in *N,N*-Dimethylformamide (DMF) .. 283
- Tandon, S N See Devendra Singh ... 1368
- Tandon, Sant P. See Ganesh D. Pandey 532
- Taqi Khan, M M—Dioxygen Complexes of the Heavier 4d and 5d Transition Metal Ions . 160
- Tewari, S R ; S K Bajpai, S K. Misra, G. N. Shukla and V N. Misra—Inorganic Coordination Complexes. Part-V : Complexes of Divalent Zinc, Cadmium and Mercury with Substituted Salicyl Hydrazines ... 891
- Thaker, K. A. and R. C. Joshi—Synthesis of 3-Hydroxy-2-(3'-pyridyl) Chromones and -2-(3'-pyridyl) Chromones ... 77
- Thaker, K. A See H. K. Shukla 1101
- Thaker, K. A. See N. A. Lingalia 1099
- Thaker, K. A. See N. C. Desai ... 771
- Thakur, G. S See S. U. Lakhani 801
- Thangavel, S. and Mathew J. Moolel—Studies in Triethylamine-Water. Part-IV : Predicting the Solubilities of Triethylamine and Water ... 1044
- Thankarajan, N. See T. D. Radhakrishnan Nair . 415
- Thomas, J D. R.—Metal-Polyalkoxylate Complexes and their Applications in Analytical Potentiometry ... 1323
- Thusoo, Anila ; Nancy Raina and Shakti 1457

- Rais Ahmed—Flavonoids and other Constituents of *Indigofera hetrantha* ... 1007
- Tilak, B. D.—Synthesis on Sulphur and Nitrogen Heterocyclics Involving Rearrangement via Small Rings ... 815
- Tiwari, G. D. and M. N. Mishra—Studies on Metal Chelates of 5-Iodo-8-Hydroxyquinolino-4-(*p*-Tolyl) sulphonamide and 5-Iodo-7-Chloro-8-Hydroxyquinolino-4-(*p*-Tolyl) sulphonamide as Potential Drugs 362
- Tiwari, K. P. See Ashok Pandey .. 686
- Tiwari, Kamala P. See Ganesh D. Pandey 532
- Tiwari, R. D. and K. S. Sinha—Structural Studies of a New Flavone Glycoside from the Seeds of *Cassia nodosa* . 526
- Tripathi, T. K. See B. S. Manhas 315
- Tripathi, A. See S. C. Bahel 1127
- Tripathi, Ramacharya See P. N. Bhargava 773
- Tripathi, S. C. ; S. C. Srivastava, D. P. Pandey and P. K. Srivastava—Halogen Oxidation and Nitrosylation of Mixed Ligand Molybdenum and Tungsten Tricarbonyls 238
- Trivedi, H. M. See L. D. Dave 1136
- Tyaga Raju, V. J. ; Vilas Ranbaore, Vasudha Atre and M. C. Ganorkar—Structural Studies of Cu(II) and Ni(II) Complexes with Physiologically Active Ligands ... 199
- Tyagi, A. S. and C. P. Srivastava—FIR Studies of Copper(II) Monohaloacetates : Molecular Structure Based on Cu—O Vibrations 823
- Tyagi, J. S. See Wahid U. Malik .. 423
- “U”
- Upadhyaya, J. S. See Wahid U. Malik 1057
- Upadhyaya, J. S. and P. K. Srivastava—Potential Antineoplastic Agents : Synthetic and Pharmacological Studies on Some N-Aryl-N'-2(4-phenyl-5-arylazothiazolyl) thiocarbamides ... 683
- Upadhyaya, J. S. and P. K. Srivastava—Potential Antithyroid Agents. Part-II : Synthetic and Pharmacological Studies on Some N-Aryl-N'-2(benzimidazolyl)thiocarbamides and N-aryl-N'-benzenesulphonylthiocarbamides . ... 808
- Upadhyaya, J. S. and P. K. Srivastava—Potential Antithyroid Agents. Part-V : Synthetic and Pharmacological Studies on Some N-aryl-N'-benzoylthiocarbamides .. 767
- Upadhyaya, J. S. ; P. K. Srivastava and (Late) R. D. Sharma—Potential Local Anaesthetic Agents. Part-III : Alkylaryl aminoacetyl-2-aminothiazoles and Benzimidazoles . 1097
- “V”
- Varadarajulu, A. See G. N. Rao ... 1009
- Varma, Rajendra S. and Rajnish K. Pandey—Synthesis of 3-(*p*-Fluoro)benzoylhydrazono-5-substituted-2-indolinones as Potential Biologically Active Agents 1174
- Varshney, I. P. ; D. C. Jain and H. C. Srivastava—Study of Saponins from *Albizia lebbek* Benth Flowers 884
- Vats, J. L. See H. S. Verma 1184
- Venkatasubramaniam, P. N. and F. Basolo—Intramolecular  $\pi$ - $\pi$  Interactions in Metal “Capped” Porphyrins 1218
- Venkateshan, M. S. See R. N. Mukherjee 170
- Verma, Balbir Chand ; Swatantar Kumar, Jagmohan Butail and Malkiat Singh—Mercurimetric Determination of Organotrithiocarbonates and A Method for the Analysis of Mercaptans 811
- Verma, H. S. ; Anang Pal, R. C. Saxena and J. L. Vats—Complexes of Co(II), Ni(II), Cr(III), Mn(III) and Fe(III) with Schiff Base Derived from *Bis-p*(Aminophenyl) Sulphide and 2-Acetyl Thiophene Glyoxal 1184
- Verma, J. K. and R. B. Patel—Protonation Constants and Thermodynamic Parameters of 3-Bromo-2-Hydroxy-5-Methylacetophenone, Its Oxime and *n*-Propylimine 43
- Verma, K. W. D. See R. K. Gupta 176
- Verma (in part), (Mrs.) Mahima See V. K. Awasthi . 264
- Verma, M. M.—Retarding Influence of Phosphates and Wheat-straw on Nitrogen Loss in Soils Treated with Ammonium Sulphate and Ammonium Nitrate ... 473
- Verma, R. M. See M. G. Pateria . 1203
- Verma, Rekha See R. Sahai .. 46
- Verma, V. K. See Mohammad Ramzan Ali . . 663, 1165



Verman, (Km) Anita See S. K. Srivastava	925	Wang, Z. F. See L. J. Bai	1280
Vidyardhi (nee Das), Nita and Santi R. Palit— Cosolvency Studies of Polyethylene. Part-I : Lowering of Cloud Temperature in Cosol- vent Mixtures	743	Waraich, T. S. ; R. C. Gaur, K. B. Pandeya and R. P. Singh—Infrared Spectra of Some New Dithio Carbamates	103
Vidyardhi (nee Das), Nita and Santi R. Palit— Cosolvency Studies of Polyethylene. Part II : Viscometric Studies in Different Cosolvent Media	753	Waraich, T. S. ; R. C. Gaur, K. B. Pandeya and R. P. Singh—Oxomolybdenum(V) and Oxomolybdenum(VI) Complexes of Some New Dithiocarbamates	213
Vig, O. P.—Syntheses of Some Terpenoids via Nickel Tetracarbonyl Induced Cycli- sation	609	"Y"	
Vijaya, V. S. See R. N. Mukherjee	170	*Yadava, A. See R. A. Misra	289
Vijayvargiya, B. L. See Purushottam B. Chakrawarti	734	Yamasaki, Kazuo See Yuzo Yoshikawa	1250
Vishwanath Rao, V. See T. Sundararamiah	74	Yashonath, S. See P. Vishnu Kamath	153
Vyas, D. N. See (Miss) C. C. Kotecha	82	Yatirajam, V. and (Miss) M. Lakshmi Kantam—Synthesis and Characterisation of $\mu$ -Oxobis [Oxotetrachlororhenates(VI)]	1287
Vyas, P. C. See R. C. Mehrotra	486	Yoshikawa, Yuzo and Kazuo Yamasaki— The Oxidation of Optically Active 3,4-Dihydroxyphenylalanine by Optically Active Cobalt(III) Complexes	1250
Vyas, Prakash C. ; Chandra K. Oza and Ravi S. Sharma—Characterization and Mole- cular Weight Determination of Some Organo Poly (aminium phosphate)s- Part V	305	Yusufi, F. A. K. See R. P. Bhatnagar	410
"W"		"Z"	
Wadhwa, Sangeeta, B. S. Garg, C. P. Sharma and N. Kumar—Preparation and Characterization of <i>Bis</i> -Dithiocarbamate di- <i>p</i> -Tolyl Tin(IV)	247	Zayed, M. A., Salah A. Abou-Galeb and M. M. S. El-Morsy—Studies on 3-Oxo- Glutaric Acid Dianilide Part-I Acid- Base Properties	1013
		Zutshi, (Miss) Kamala See Ram Das	700

# SUBJECT INDEX

## "A"

- Acacia farnesiana* Leaves, High Content of Cholesterol in the Lipid of (Andhiwal and Kishore) . 1079
- Acetamide Derivatives, Studies on : Preparation and Antimicrobial Activity of 2- $\alpha$ -Arylaminoacetamido/ $\alpha$ -Carbamoyl benzyl-amino/Arylcarbamoylmethylamino-5-*o*-Nitrophenyl/Benzoylaminoethyl-1, 3, 4-Thiadiazole (Shah, Patel and Parikh) 678
- 3-Acetyl-4-hydroxy-6-methyl-2-pyrone and Nitrilotriacetic Acid, Compatability of, in the Coordination Sphere of Lanthanum Ions (Kadınan, Garg and Singh) 1247
- Bis* (Acetylacetonato) Copper(II), A Dynamic TG Study of (Nair, Sreeman and Thankarajan) 415
- Acid-Base Properties. Studies on 3-Oxo-Glutaric Acid Dianilide. Part-I (Zayed, Abou-Taleb and El-Morsy) 1013
- Acid Buffers and Chaotropic Ions as Eluents in Ligand Purification Using Semiautomated Affinity Chromatography (Prasad and Nerenberg) ... 1220
- Acid Catalysed Hydrolysis, Kinetics of the, of Formamide in Binary—Aqueous Mixtures (Mittal, Gupta and Gupta) . 595
- Acid Dissociation Constants in Ethanol Water Mixture : Some Hydroxy Coumarins (Arora, Aggarwal and Singh) ... 347
- Acid Hydrolysis and Alkaline of *n*-Butylacetate in Methanol-Water Mixtures (Sidahmed, Salem and Halim) 1139
- Acidic Aminoacid Imines (N-Salicylidene-I-aspartic Acid and N-Salicylidene-I-glutamic Acid), Polarographic Studies on (Chaturvedi and Kapoor) . 210
- Acrylonitrile, Copolymerization of, with [(2-Methacryloyloxy) alkoxy] Trimethyl Silanes (Bajaj and Gupta) .. 228
- N-Acyl Amino Acids and Peptides, Melting Behaviour of Some Pure (Iyer, Sheth and Subrahmanyam) ... 856
- Aegiceradienol (*nor* Echinocystadienol), Partial Synthesis of : Oxidative Decarboxylation (Sundararamaiah and Rao) .. 7
- Ag(I)-Catalysis in Oxidation of Amines by Ce(IV) in Nitric Acid, A Kinetic Study. Oxidation Studies. Part—XV (Rao, Sethuram and Rao) . 104
- Ag(I) and Hg(II) Ions, Conductometric and Spectrometric Studies on Complex of, with N,N'-Diphenyl Thiourea (Singh, Sharma and Sharma) . 118
- Ag(I), Kinetic Study of, Catalysed Oxidation of Glycine by Ce(IV) in Perchloric Acid Medium (Singh, Gaur, Singh and Saxena) 5
- Al(III), Be(II) and Cu(II) Ions, Coordination of, with 1,7-Dihydroxy-4-Sulfo-2-Naphthoic and 3,5-Dihydroxy-7-Sulfo-2-Naphthoic Acids in Aqueous Sodium Perchlorate Medium (Lajunen) ... 123
- Aldehydes, Oxidation of : Use of Potassium Bromate (Samaddar and Banerjee) . 90
- Alkali Metal Salts, Complexes of, of Some Organic Acids with *o*-Hydroxybenzeneazo-2-Naphthol. Azo Complexes (Banerjee, Singh and Roy) 118
- Alkali Metal Salts, Complexes of, of Some Organic Acids with *o*-Hydroxybenzene-Azo-2-Naphthyl Amine : Azo Complexes (Banerjee, Singh and Roy) . 108
- Alkaline and Acid Hydrolysis of *n*-Butylacetate in Methanol-Water Mixtures (Sidahmed, Salem and Halim) . 113
- Alkaline Earth Metal Complexes : Mixed Ligand Complexes of Some Organic Compounds of Magnesium with Nitrogen Donor Ligands (Banerjee, Sinha, Ghosh and Roy) . 102
- Alkaloids of *Machilus glaucescens* Wight : Machigline A New Phenolic Oxoaporphine Alkaloid (Talapatra, Goswami and Talapatra) . 136
- Alkaloids of *Mitragyna parvifolia* (Roxb) Korth. and their Transformations (Chatterjee, Dhara and Banerji) ... 136

Alkoxides, Recent Advances in the Chemistry of Simple and Bimetallic, of Later Transition Elements (with particular reference to the '3d' series) (Mehrotra)	715	violet Radiation on, of Single Cell Protein (Pandey and Tiwari)	686
Alkylarylaminoacetyl-2-aminothiazoles and Benzimidazoles. Potential Local Anaesthetic Agents. Part—III (Upadhyaya, Srivastava and Sharma)	1097	Amino Acids, Effects of Chemicals on Protein Hydrolysate, of Pumpkin ( <i>Cucurbita pepo</i> ) Seeds During Germination (Kotecha, Oza and Vyas)	82
5-Alkyl/arylimino-2,4-dialkyl/aryl-3-thio/oxo-1,2,4-thiadiazolidines, Preparation of (Jadhav and Paranjpe)	71	Amino Acids, The Effect of Some, on the Corrosion of Aluminium in HCl Solution (Fouda and El-Semongy)	89
Alkylmercapto and Alkylsulphonyl Phenols, Physico-Chemical Studies on Some (Shanmuganathan, Durai and Sundaravelu)	52	$\alpha$ -Aminoadipic Acid, Synthesis of (Khan, Ali, Panda and Rakhshinda)	1077
9-Alkyl-6-Mercaptopurine Analogues, Synthesis of (Banerjee, Dutta and Chakraborti)	417	1-Amino-4,4,6-Trimethyl-1H,4H-Pyrimidine-2-thiol, Cu(I), Ag(I), Tl(I), Zn(II), Cd(II) and Hg(II) Complexes of (Singh, Nath, Katyal and Singh)	625
Alluvial Soils, Phosphate Fertilization in, of Allahabad Division, Interrelation in Water Soluble P, Adsorbed P and Olsen's P (Misra and Pathak)	466	2-Aminobenzothiazoles, On the Polarographic Reduction of (Malik and Jain)	558
Allylmetal Carbonyls of Rhodium and Cobalt, Reactions of, with Carbon Monoxide and Hydrogen : New Catalytic Intermediates in Homogeneous Hydroformylation Reactions (King and Tanaka)	124	2-Amino-1-Cyclopenten-1-dithiocarboxylic Acid, Transition Metal Complexes of the Esters of : (Metal Complexes of Sulphur-Nitrogen Chelating Agents) (Singh and Gupta)	244
Alumina, Characterization of—A Versatile Catalyst (Krishnasamy and Ratnasamy)	839	2-Amino-3-hydroxypyridine, Formation Constants and Thermodynamic Parameters of, with Some Bivalent Metal Ions (Kalra, Malik and Gera)	1427
Aluminium(III) and Titanium(IV), Anthranilic Acid Hydrazide Complexes of (Narula, Singh and Kapoor)	1296	Ammonium-N-Aryl Dithiocarbamates, Alkalimetric Determination of (Talegaonkar and Boparai)	108
Aluminium, Determination of, in Iron Ores (Sen Sarma and Majumdar)	790	Amoebicidal Activity of Some 2-Methyl-6(8)-alkyl-4-(arylsulphonyl hydrazino)quinolines, Synthesis and (Misra, Saxena and Srivastava)	781
Aluminium Isopropoxide, Reactions of, on Some Cobalt(II) <i>Bis</i> -Chelates of <i>o</i> -Hydroxy Oximes. Reactions of Coordinated Oximes. Part—V : (Rani, Pandeya and Singh)	235	Amoebicidal Testing of Drugs. Use of Goat Serum as a Substitute for Horse Serum for Growing <i>Entamoeba histolytica</i> (Dutta, Pal, Dey and Lahiri)	902
Aluminium in HCl Solution, The Effect of Some Amino Acids on the Corrosion of (Fouda and El-Semongy)	89	Amperometric Estimation of $\text{La}^{3+}$ and $\text{Ce}^{4+}$ with Cupferron using d.m.e (Pitre and Lavale)	1081
Amination, An Alternative Route For : Transformation of Sucrose (Sharma, Norula and Matthey)	385	Analytical Chemistry, Training and Research in : An Interdisciplinary Science (Mehrotra)	1209
Amine Exchange Reactions, Studies on the, in C-Mannich Bases (Kulkarni and Agarwal)	380	Analytical Reagent for Iron, Phenoxy Acetyl Acetophenone as an (Ambhore, Ilyas and Joshi)	691
Amino Acid Composition, Effects of Ultra-		Angular and Linear Furanoflavones, Carbon-13	

NMR Spectra of (Talapatra, Mallik and Talapatra)	534	Aromatic Amines, Spectrophotometric Determination of, Using Catechol and Iodine (Sastry, Rao and Murthy)	1107
Anhydrous Ammonia, Movement and Transformation of, in Field Soil (Bagchi, Ghosh, Ghosh and Dhua)	453	2- $\alpha$ -Arylaminoacetamido/ $\alpha$ -Carbamoylbenzylamino / Arylcarbamoylmethylamino - 5 - <i>o</i> -Nitrophenyl / Benzoylamino methyl - 1, 3, 4-Thiadiazole, Preparation and Antimicrobial Activity. Studies on Acetamide Derivatives (Shah, Patel and Parikh)	678
Anhydrous Chlorides of B(III), V(III) and Sn(IV), Reactions of, with Arylantimony Compounds. Metal Derivatives of Organoantimony Compounds (Sharma, Dubey and Puri)	1031	2-Aryl amino-4-[4'(benzene sulphonamido)-phenyl]thiazoles (Patil and Ingle)	1000
Anionic Organotellurium Complexes, Some (Srivastava, Srivastava and Srivastava)	1028	N-Aryl-N'-benzenesulphonylthiocarbamides and N-Aryl-N'-2(benzimidazolyl) thiocarbamides, Synthetic and Pharmacological Studies on Some. Potential Antithyroid Agents. Part-II (Upadhyaya and Srivastava)	808
<i>p</i> -Anisic Acid-Formaldehyde Condensation Product, Thermal Degradation of (Patel, Patel and Patel)	1145	2-Arylamino-4-(4-Carbethoxyaniline)-6-Isonicotinylhydrazino-1,3,5-Triazine, Preparation of. Studies on Antitubercular Agents (Shukla, Langalia, Desai and Thaker)	1101
Anthelmintic Activity of N-(Substituted Phenoxy Acetamido) Phthalimides, Studies on Synthesis and (Shukla, Agarwal and Rastogi)	779	5-Aryl / Aryloxyalkyl-1, 3, 4, - Oxadiazoles - 2-Thiones and Related Compounds as Possible Fungicides, Synthesis of (Pathak, Srivastava and Bahel)	776
Anthracene Sulfonates, Concentration, Depolarization, Energy Transfer and Kinetics of Concentration Quenching of Fluorescence of (Basu, Gupta and Rohatgi-Mukherjee)	578	2-Aryl-5-Aryloxyalkyl-S-Triazolo[3,4-b]-1,3,4-Thiadiazoles, Synthesis and Pharmacology of (Mody, Prasad, Ramalingam and Sattur)	769
Anthranilic Acid Hydrazide Complexes of Aluminium(III) and Titanium(IV) (Narula, Singh and Kapoor)	1296	Arylazopyrimidine and Arylazopyrazole, Polarographic Studies on the Effect of Some Ionic and Non-ionic Surfactants on the Kinetics of Irreversible Electrode Processes of (Malik and Jain)	962
Anthraquinone-2-Sulfonate Solution, Photochemistry of Aqueous (Roy, Bhattacharya and Aditya)	585	5-Arylazopyrimidine Derivatives, Synthesis of Some (Mahesh, Kumar and Prakash)	1192
Antiferromagnetic Interaction in Binuclear Copper(II) Complexes Involving Tetradentate Schiff Bases (Bhattacharya)	505	N-Aryl-N'-2-(benzimidazolyl) thiocarbamides and N-aryl-N'-benzenesulphonylthiocarbamides, Synthetic and Pharmacological Studies on Some. Potential Antithyroid Agents. Part-II (Upadhyaya and Srivastava)	808
Antitubercular Agents, Studies on. Preparation of 2-Arylamino-4-(4-Carbethoxyaniline)-6-Isonicotinylhydrazino-1,3,5-Triazine (Shukla, Langalia, Desai and Thaker)	1101	N-Aryl-N'-benzoylthiocarbamides, Synthetic and Pharmacological Studies on Some. Potential Antithyroid Agents. Part-V (Upadhyaya and Srivastava)	767
Antitubercular Agents, Studies on. Part-III: Preparation of Some <i>p</i> -(2,4-Diaryl-amino-6-S-Triazinylamino) Benzaldehyde/Acetophenone Thiosemicarbazones as Potential Tuberculostatic Agents (Langalia and Thaker)	1099	Aryl Fluorobenzene Sulphonates and	
Arachin, Hydrogen Ion Equilibria and Metal Binding Studies on (Malik, Bhushan and Agarwal)	1316		

Hydroxy Diaryl Sulphones, Synthesis of Some, as Potential Fungicides (Giri, Nizamuddin and Gupta)	365	Hydroxybenzene-Azo-2-Naphthyl Amine (Banerjee, Singh and Roy)	1089
Arylidene-2-aminobenzoxazole, Cyclocondensation and Cycloaddition Reactions on the Unsaturated Centre of (Osman, Badr, Mahmoud and Hezien)	763	Azomethine Bond, Polarographic Studies on the Reduction of the, in Aryl Thiosemicarbazides and the Determination of Hammett Parameters (Malik, Upadhyaya, Jain and Sharma)	1057
3-Arylimino-5- <i>p</i> -Methoxyphenyl-1,2,4-Dithiazoles, A Novel Route to the Synthesis of. Part-III (Ali, Singh and Verma)	663	"B"	
3-Arylimino-5-( <i>N</i> -Methylanilino)-1,2,4- $\Delta^4$ -Dithiazolines, Synthesis of Some (Ali and Verma)	1165	Barrier to Rotation, Determination of. Around Some Crowded C-C and C-N Bonds by Dynamic Nuclear Magnetic Resonance Restricted Rotation. Part-IV (Nasipuri, Daw, Banerjee and Datta-Gupta)	1379
Aryloxy/Aryl Acetyl Thiosemicarbazides, Substituted 1,3,4-Oxadiazoles, 1,3,4-Thiadiazoles, 1,2,4-Triazoles and Related Compounds, Synthesis of, as Potential Fungicides (Sharma and Bahel)	877	Barium(II) and Nickel(II) Electrodes Heterogeneous Ion-Selective Electrodes Based on Electroneutral Ion-Carriers (Lal, Chattopadhyaya and Dey)	493
<i>N</i> -Aryl- <i>N'</i> -2-(4-phenyl-5-arylazothiazolyl)thiocarbamides, Synthetic and Pharmacological Studies on Some Potential Antineoplastic Agents (Upadhyaya and Srivastava)	683	Barium Bis-Oxalato Diaquo Thallate(III) Monohydrate (Some Studies on Oxalates -VIII) (Sagi, Ramana and Rao)	336
Association Equilibria, Thermodynamics of, of Single and Mixed Ligand Complexes of. A Review (Complex Formation in Molten Salts)(Gupta, Verma and Gaur)	176	Benzalanilines, Addition of Sulphene to Substituted (Singh, Kumar, Manrao and Kaur)	673
Astatical Stabilization of Ternary Complexes, A New Parameter in (Bhattacharya and Patel)	1244	Benzaldehydes, Kinetics of Oxidation of Substituted, by KMnO <sub>4</sub> in Buffer Medium (Rao and Sundaram)	704
Astatistical Stabilisation of Cu(II) Ternary Complexes, A New Approach to, Containing Tertiary Amines and O-O <sup>-</sup> Co-ordinating Ligands (Bhattacharya and Patel)	310	Benzil Semicarbazone, Some Divalent Metal Complexes of. Studies on Hydrazones, Semicarbazones, Thiosemicarbazones and Oximes as Ligands. Part-III (Mishra, Mohapatra and Panda)	836
Aza Triterpenes-III: Action of Excess Hydrazoic Acid-Boron Trifluoride Etherate on 3-Oxo-Penta Cyclic Triterpenes (Ramalah, Ramraj, Govardhan and Rao)	975	Benzilic Acid Complexes of Niobium(V) and Tantalum(V) (Narula, Singh, Kapoor and Kapoor)	195
Az lactone (Part-I), Synthesis of Some New Derivatives of (El-Maghraby and Hassan)	867	Benzimidazoles, Synthesis of Some New, as Antiamoebic Agents (Misra, Shah and Saxena)	1074
Azo Complexes: Complexes of Alkali Metal Salts of Some Organic Acids with <i>o</i> -Hydroxybenzeneazo-2-Naphthol (Banerjee, Singh and Roy)	1186	Benzotelluracyclopentane Diiodide, Reactions of (Srivastava, Srivastava and Kumar)	186
Azo Complexes: Complexes of Alkali Metal Salts of Some Organic Acids with <i>o</i> -		<i>S</i> -Benzoyl-O-alkyl Xanthates, Photochemical and Thermal Transformations of (Darji and Shah)	657
		<i>N</i> -Benzoyl- <i>N'</i> -2-(4-Aryl-5-Arylazothiazolyl) Thiocarbamides, Synthesis of, as Potential Antineoplastics (Rao, Khan and Mehra)	375

N-Benzoyl Phenyl Hydroxyl Amine, Equilibrium and Formation Constants of Co(II), Ni(II) and Zn(II) Complexes of, in Various Mixed Aqueous Solvents (Chaudhury and Kole) ...	934	Biologically Active New 1-Substituted-2-Mercaptobenzoyl-4-Phenylimidazoles ( Ali and Saxena) ...	420
<i>p-p'</i> -bis (Benzoyl thiourea) Benzene, Complexes of, with Cu(II), Ni(II) and Co(II) Salts and Their Biological Activity (Satpathy, Mishra and Patel )	40	Boron, Triphenylsiloxy and Diphenylsiloxy Derivatives of (Bhardwaj and Srivastava)...	300
2-S-Benzyl-1,5-diaryl-2,4-isodithiobiurets, Debenzylation of, with Thiocarbamide. Thiocarbamide as Dealkylating Agent (Jadhav and Paranjpe) ...	1003	N-Bridged Thiazole and Imidazole Derivatives, Synthesis and Antimicrobial Activities of. Studies on Heterocyclic Compounds. Part—V (Dehuri and Nayak) ..	1170
2,5-Bis (Benzylaminomethyl) Hydroquinone Complexes (Mannich Bases as Potential Polydentate Ligands) (Gupta, Maurya and Dey ) ...	216	3-Bromo- 2-Hydroxy- 5-Methylacetophenone, Protonation Constants and Thermodynamic Parameters of, Its Oxime and <i>n</i> -Propylimine (Verma and Patel)	43
[BFe(CO) <sub>5</sub> ] <sup>+</sup> , B = (C <sub>8</sub> H <sub>8</sub> ), (C <sub>8</sub> H <sub>7</sub> ) and (C <sub>7</sub> H <sub>9</sub> ), Molecular Orbital Study of (Brown, Chester and Fitzpatrick) ...	1273	<i>n</i> -Butylacetate, The Alkaline and Acid Hydrolysis of, in Methanol-Water (Sidahmed, Salem and Halim) ..	1139
Bimetallic Tetrathiocarbamates, Preparative and Structural Studies on, of Some Bivalent 3d-Metal Ions (Aggarwal, Singh and Singh)	269	“C”	
Bimetallic Tetrathiocyanato Complexes, Synthesis and Structural Studies of Some Mixed Ligand ( Singh, Khan and Khan)	35	Cadmium(II) and Cobalt(II), Mixed Ligand Complexes of, with Oxine as Primary Ligand and Heterocyclic and Aromatic Amines as Secondary Ligands (Mahapatra and Pujari)	1183
Binary Mixtures in Presence of Fluoride Ions, The Reaction of Potassium Permanganate with Potassium Ferrocyanide and (Dessoki, Allam and Hammam) ...	1063	Cadmium(II), Mixed Ligand Anionic Complexes of (Mahapatra, Panda, Pujari and Chiranjeevi) ..	1022
Binuclear Alkali Metal Complexes with Copper(II) and Nickel(II)-Salicylaldimines: Metal Complexes as Ligands (Banerjee, Prasad and Roy)	1303	dl-Camphorquinone, Role of Metal Ions in Reactions of, with Monoamines (Mukhedkar, Rajgolkar and Mukhedkar) ..	295
Binuclear Copper(II) Complexes, Antiferromagnetic Interaction in, Involving Tetradentate Schiff Bases (Bhattacharya) ...	505	<i>Canthium dicoccum</i> , Chemical Investigation of the Steam Bark of (Chatterjee, Nagar, Barua and Mukherjee) ...	418
Binuclear Oxofluoro Complex of Quinquevalent Molybdenum (Chakravorti, Bera and Bharadwaj) ...	990	Carbazole Alkaloids, Structure and Synthesis of Mukoline Mukolidine, two New, from <i>Murraya koenigii</i> Spreng (Ray, Bhattacharya and Chakraborty)	1369
Biochemical Fuel Cells (Govil and Saran) .	1226	$\gamma$ -Carbon Bonded Acetylacetonato Complexes of Pd(II) (Sahu and Mohapatra) ...	732
Biochemical Reproduction Reactions and Drug Actions, Some Thoughts on the Mechanism of (Mathur) ...	603	Carbon Fibres (Santappa) ...	321
		Carbon Monoxide, Nitrogen and Oxygen, Electron Spectroscopic Investigations of, Adsorbed on Transition Metals (Kamath, Yashonath, Srinivisan, Basu and Rao) ..	153
		Carbon, Nitrogen and Sulphur Mineralisation in a Soil from Three Decomposing Plant	

Materials of Varying C/N, C/S and N/S Ratios (Bhattacharjya and Mukhopadhyay) ...	68	Benzimidazole in Acetic-Perchloric Acid Mixture (Oxidation of Methyl Group) (Singh, Nayak, Rout and Padhi) ...	349
Carbon-Oxygen Stretching Frequencies of Carboxylato Complexes, Relationships Between the direction of Shifts in the, and the type of Carboxylate Coordination (Manhas and Trikha) ...	315	CH <sub>3</sub> Transfer Reagent, <i>Bis</i> (Iodomethyl) Mercury as a (Seyferth, Haas and Dagani) ...	111
Carbon-13 NMR Signals of Some Phenothiazine Derivatives (Patra, Mitra and Mukhopadhyay) ...	660	Chaotropic Ions and Acid Buffers as Eluents in Ligand Purification Using Semiautomated Affinity Chromatography (Prasad and Nerenberg) ...	1220
Carbon-13 NMR Spectra of Angular and Linear Furanoflavones (Talapatra, Mallik and Talapatra) ...	534	Characterisation of Some Solid Products Obtained by Carrying Out the Replacement Reactions on the Hydrated Sulphates of Copper(II), Nickel(II) and Cobalt(II) Using Two Different Heterocyclic Ligands viz., Antifuran-2-Carboxaldoxime and 2-Pyrrolidone (Shukla, Singh, Bhargava and Narain) ...	620
Carboxylato Complexes, Relationships Between the Direction of Shifts in the Carbon-Oxygen Stretching Frequencies of, and the Type of Carboxylate Coordination (Manhas and Trikha) ...	315	Charge Transfer Interaction, Differential Refractometric and Conductometric Studies on the, of Some Metal $\beta$ -Diketonates with Iodine (Sahai, Singh and Verma) ...	46
<i>Cassia nodosa</i> , Structural Studies of a New Flavone Glycoside from the Seeds of (Tiwari and Sinha) ...	526	Chelating Tendencies of 1-Methoxy-2,4-Pentanedione. The Rare Earths. Part-XCII (Martin Moeller and Randall) ...	1232
Catalytic Intermediates, New, in Homogeneous Hydroformylation Reactions: Reactions of Allylmetal Carbonyls of Rhodium and Cobalt with Carbon Monoxide and Hydrogen (King and Tanaka) ...	124	Chemical Constituents of <i>Cephalotaxus griffithii</i> (Kamil, Khan, Ahmad, Ilyas and Rahman) ...	1199
Cation Exchange Chromatographic Separation of Manganese in Mixed Solvent Systems (Gaikwad and Khopkar) ...	1346	Chemical Examination of <i>Medicago savita</i> Seeds (Shrivastava and Nigam) ...	1198
Cd(II), Isolation, Characterisation and Antimicrobial Activity Studies of the Mixed Ligand Complexes of, with 8-Hydroxyquinoline and Various Salicylic Acids (Anjaneyulu, Rao, Swamy, Eknath and Rao) ...	1024	Chemical Examination of Three Indigenous Plants (Dan, Dan and Mukhopadhyay) ...	419
Ce(IV), Colorimetric Estimation of, by Phenothiazines (Sane, Gijare, Ambardekar and Deshpande) ...	1201	Chemical Investigation of the Steam Bark of <i>Canthium dicoccum</i> (Chatterjee, Nagar, Barua and Mukherjee) ...	418
<i>Cephalotaxus griffithii</i> , Chemical Constituents of (Kamil, Khan, Ahmad, Ilyas and Rahman) ...	1199	Chemisorption Kinetic Studies of Oxygen on V <sub>2</sub> O <sub>5</sub> -Ti <sub>2</sub> O <sub>3</sub> (De and Gadgil) ...	846
Cerium(IV), Extraction of, by Liquid Cation Exchanger (Versatic 10) and its Separation from Lanthanide Elements (Ray and Modak) ...	392	Cholesterol, High Content, in the Lipid of <i>Acacia farnesiana</i> Leaves (Andhiwal and Kishore) ...	1079
Cerium(IV) Oxidation, Kinetics of, of 2-Methyl Benzthiazole, Benzoxazole and		Chromic Acid Oxidation of Phenacyl Bromides ( $\omega$ -Bromoacetophenones), Kinetics of (Mohapatra and Khandual) ...	1162
		Chromium, Spectrophotometric Determination of, in Steel by Extraction of its Ion Association Complex with Tetraphenylarsonium Chloride (Baishya and Baruah) ...	389
			1465

Chromium(VI), Spectrophotometric Study of the Reaction of, with Fluphenazine Hydrochloride (Gowda and Raj)	1398	droxy Oximes (Reactions of Coordinated Oximes-Part V) (Rani, Pandeya and Singh)	235
Chromium(VI), The Extraction of, from Mineral Acid Solutions by Trilaurylamine-Oxide (Murty, Rao and Sastri)	1343	Cobalt(II) Complexes of 5(3)-Methyl Pyrazole-3(5)-Carboxamide (Saba and Datta)	728
Cloud Temperature, Lowering of, in Cosolvent Mixtures. Cosolvency Studies of Polyethylene. Part I (Vidyarthi and Palit)	748	Cobalt(III) Complexes, Mixed Ligand, Containing Benzotriazole or 5-Nitrobenzotriazole (Mishra, Bhushan and Jha)	1092
Coal, Reactivity of Indian Rock Phosphates in Presence of Oxidative Degradation Products of (Pathak)	899	Cobalt(II) Complexes with ONO Donor Tridentate Schiff Bases Derived from Salicylaldehyde, Substituted Salicylaldehydes and Orthohydroxybenzylamine (Syamal and Gupta)	697
Co(II), Ni(II) and Cu(II), Stability of Complexes of, with Esters of Salicylic Acid (Gupta and Pannu)	937	Cobalt(II), Spectral and Magnetic Studies of Some Mixed Ligand Complexes of High Spin (Sankhla, Mathur and Misra)	893
Co(II), Ni(II) and Zn(II) Complexes of N-Benzoyl Phenyl Hydroxyl Amine, Equilibrium and Formation Constants of, in Various Mixed Aqueous Solvents (Chaudhury and Kole)	934	(COD)PtCl <sub>2</sub> , <sup>31</sup> P NMR Studies of the Reaction of, with Tertiary Phosphines in Methanol (Goel and Goel)	141
Co(II), Ni(II), Cr(III), Mn(III) and Fe(III), Complexes of, with Schiff Base Derived from <i>Bis-p</i> (Aminophenyl) Sulphide and 2-Acetyl Thiophene Glyoxal (Verma, Pal, Saxena and Vats)	1184	Colorimetric Estimation of Ce(IV) by Phenothiazines (Sane, Gijare, Ambardekar and Deshpande)	1201
Co(II), Ni(II), Cu(II) and Zn Salts, Mixed Ligand Complexes of, with <i>o</i> -Hydroxy Propiophenone and Quinoline (Roy, Mishra and Mohapatra)	1094	Compatibility of Nitrilotriacetic Acid and 3-Acetyl-4-Hydroxy-6-Methyl-2-Pyrone in the Coordination Sphere of Lanthanum Ions (Kadian, Garg and Singh)	1247
Co(II), Cu(II), Cd(II), Mg(II), Synthesis and Characterization of Complexes of, with Disubstituted Thioureas (Saha, Bhatnagar and Banerji)	927	Complex Formation Between Copper(II) 2,2'-bipyridyl 1 : 1 Complex and Ligands Containing Oxygen and/or Nitrogen Donor Atoms as Secondary Ligands: Polarographic Study of Ternary Complexes in Solution (Srivastava and Nigam)	251
Co(II), Ni(II), Cu(II), Zn(II) and Pd(II), Polyamino Chelates of, using Cysteine as a Secondary Ligand (Sharma and De)	101	Complex Formation in Molten Salts: Thermodynamics of Association Equilibria of Single and Mixed Ligand Complexes: A Review (Gupta, Verma and Gaur)	176
Co(II), Ni(II), Cu(II), Zn(II), Cd(II) and Hg(II), Complexes of, with Chelating Bidentate Schiff's Base (Mahapatra, Mahapatra, Pujari and Chiranjeevi)	988	Complex Formation of Cu(II) with N-Salicyloyl Glycine. Metal Complexes of Some Model Peptides. Part-I (Mukherjee, Sarkar and Chatterjee)	1117
Cobalt(II) and Cadmium(II), Mixed Ligand Complexes of, with Oxine as Primary Ligand and Heterocyclic and Aromatic Amines as Secondary Ligands (Mahapatra and Pujari)	1183	Complexation Reaction, Spectrophotometric Study of the, Between Oxovanadium(IV) and Gallacetophenoneoxime (Reddy, Rao and Reddy)	422



Complexing Behaviour of N-Cyclo Hexyl Benzothiazole Sulphonamide with Cu(II), Mn(II), Ni(II), Co(II) and Fe(III) (Srivastava, Verman and Gupta) ..	925	Silanes (Bajaj and Gupta)	228
Computations of Apparent Formation Constants and Free Metal Ions in EGTA or EDTA Buffer Systems. Part-I: Effects of pH and Metal Concentration with Respect to Ligand (Biswas and Chebib)	1419	Copper and Silicon, Application of Coordination Compounds of, in Fiber and Fiber Reinforced Plastic Materials (Bahl, Dharmi, Seth, Manocha and Mathur) ..	1306
Concentration Depolarization, Energy Transfer and Kinetics of Concentration Quenching of Fluorescence of Anthracene Sulphonates (Basu, Gupta, Rohatgi-Mukherjee)	578	Copper Benzanidothiosemicarbazide Complex, pH-Metric Studies on the (Ansari, Jain, Kaushik and Malik) ..	414
Concentration Quenching of Fluorescence of Anthracene Sulfonates, Concentration Depolarization, Energy Transfer and Kinetics of (Basu, Gupta and Rohatgi-Mukherjee) ..	578	Copper(II) Complexes, Determination of Stability Constant of, with Ethylenediamine and Acetyl Salicylate (Aspirinate) by Electrochemical Methods (Das, Dixit and Zutshi) ...	700
Conductance of KCl and NaCl in Sucrose+ Water, Glucose+ Water and Urea+ Water Mixtures at Different Temperatures (Mohanty and Das) ...	1190	Copper in Steel, Brass, Gunmetal, Nickel-Silver and Aluminium Alloy, Determination of, by Extraction with Phenanthraquinone Monothiosemicarbazones (Khasnis and Shinde)	812
Conductometric and Spectrometric Studies on Complex of Ag(I) and Hg(II) Ions with N,N'-Diphenyl Thiourea (Singh, Sharma and Sharma)	1187	Copper(II), Mixed Ligand Complexes of, Correlation of Electrode Behaviour and Spectral Properties of Some (Srivastava, Lal and Nigam) ...	497
Coordination Chemistry of Technetium as Related to Nuclear Medicine (Srivastava and Richards)	1262	Copper(II) Monohaloacetates, FIR Studies of Molecular Structure Based on Cu-O Vibrations (Tyagi and Srivastava) ...	823
Coordination Compounds of Silicon and Copper, Application of, in Fiber and Fiber Reinforced Plastic Materials (Bahl, Dharmi, Seth, Manocha and Mathur) ..	1306	Copper Nickel Ferrites, Mossbauer Spectra of (Kiran, Bommannavar and Chakrabarty)	1310
Coordination Polymer, Studies on the, of Niobium(V) with 1,6-Dihydroxyphenazine (Shivahare and Sharda)	242	Corrosion, of Aluminium in HCl Solution, The Effect of Some Amino Acids on the (Fouda and El-Semongy)	89
Coordination Polymers of Terephthalaldehyde bis-(semicarbazone) with Some Bipositive Cations (Singh, Maruya, Agarwala and Dey) ...	1130	Cosolvency Studies of Polyethylene. Part-I: Lowering of Cloud Temperature in Cosolvent Mixtures (Vidyarthi and Palit) ...	748
Coordination of Al(III), Be(II) and Cu(II) Ions with 1,7-Dihydroxy-4-sulfo-2-naphthoic and 3,5-Dihydroxy-7-sulfo-2-naphthoic Acids in Aqueous Sodium Perchlorate Medium (Lajunen)	1238	Cosolvency Studies of Polyethylene Part-II: Viscometric Studies in Different Cosolvent Media (Vidyarthi and Palit)	753
Copolymerization of Acrylonitrile with [(2-Methacryloyloxy) alkoxy] Trimethyl		Coumarins and Schiff's Bases, Some New, as Possible Antibacterial and Antifungal Agents (Mittal and Singhal) ...	373
		Coumarinylsulphonyl Ureas, Semicarbazides and Semicarbazones. Search for New Hypoglycemic Agents. Part-VII (Husain, Gupta and Srivastava) ...	1193
		m-Cresol, Kinetics and Mechanism of Oxidation of, by Vanadium(V) in Presence of Salicylic and Substituted Salicylic Acids	

in Dilute Perchloric Acid Medium (Srinivas, Subbaiah and Subba Rao) ...	55	Cyclopentadienyl Bond (Soni, Chandra, Sharma and Garg) ...	913
Cu(I), Ag(I), Tl(I), Zn(II), Cd(II) and Hg(II) Complexes of 1-Amino-4,4,6-trimethyl-1H, 4H-pyrimidine-2-thiol (Singh, Nath, Katyal and Singh)	625	"D"	
Cu(II)-N-Aryl Glycinates, ESR Study of (Bai, Wang and Chen)	1280	4d and 5d Transition Metal Ions, Dioxygen Complexes of the Heavier (Taqui Khan)	160
Cu(II), Complex Formation of, with N-Sali- cyloyl Glycine-Metal Complexes of Some Model Peptides. Part-I (Mukherjee, Sarkar and Chatterjee)	1117	Debenzylation of Certain 2-S-Benzyl-1,5- diaryl-2,4-isodithiobiurets with Thiocarpa- mide: Thiocarbamide as Dealkylating Agent (Jadhav and Paranjpe) ...	1003
Cu(II) Complexes, Studies of ESR Spectra of Some (Bhave and Kharat)	994	Decarboxylation and Dehydration of Hydrat- ed Calcium Salts of Pyridine Monocarbo- xylic Acids. A Study on Solid State Thermal Decomposition Characteristics of Some Metallo-organic Compounds. Part-I (Ghosh, Ray, Ray and Bandyopadhyay) . .	1034
Cu(II) Ternary Complexes, A New Approach to Astatistical Stabilisation of, Contain- ing Tertiary Amines and O-O <sup>-</sup> Co-ordi- nating Ligands (Bhattacharya and Patel)...	310	Decomposition Patterns, A Study of the, of Some Transition Metal Complexes Derived mainly from the Heterocyclic Ligands viz., Furan-2-Carboxaldoxime and 3- Methyl-4-arylazopyrazole-5-one using Thermogravimetric Analysis (Shukla, Srivastava and Singh) ...	1180
Cu(II) and Ni(II) Complexes, Structural Studies of, with Physiologically Active Ligands (Raju, Ranbaore, Atre and Ganorkar)	199	Decomposition of Propan-2-ol over Chromite Spinel-Kinetic Studies (Krishnasamy and Chokkalingam)	641
Cyclic Voltammetry of Thallium(I) in Different Supporting Electrolytes (Sindal, Mathur and Kapoor)	1313	Dehydration and Decarboxylation of Hydrat- ed Calcium Salts of Pyridine Monocarbo- xylic Acids. A Study on Solid State Thermal Decomposition Characteristics of Some Metallo-organic Compounds Part-I (Ghosh, Ray, Ray and Bandyopadhyay) ...	1034
N-Cyclo Hexyl Benzothiazole Sulphonamide, Complexing Behaviour of, with Cu(II), Mn(II), Ni(II), Co(II) and Fe(III) (Srivastava, Verman and Gupta)	925	Detection and Determination of Phosphate Using Monomethyl- <i>p</i> -Amidophenol as Reagent (Murty and Suryanarayana) ...	1113
Cyclocondensation and Cycloaddition Reac- tions on the Unsaturated Centre of Aryli- dene-2-aminobenzoxazole (Osman, Badr, Mahmoud and Hezien) ...	763	Deuterium Isotope Effect on the Pfeiffer Effect in Optically Labile Coordination Com- pounds (Krischner and Gabay)	1259
Cycloheptane Series, Studies in the Part- XXXI: Friedel-Crafts Reaction of the Anhydride of $\alpha\alpha$ -Dimethylglutaric Acid with Different Aromatic Hydrocarbons and Synthesis of 1,1-Dimethyl-3,4-benzo/ substituted benzocycloheptanes and 1,1- Dimethylthieno[3,4-b]Cycloheptane (Gau- tam, Kannan and Saharia) ...	378	Deviation Function, A Simple, to Summa- rize Data in Solvent Mixtures. The Standard Oxidation Potential of the Silver Chloride Electrode in Water- Ethylene Glycol Mixtures (Högfeldt) ...	1357
$\eta_5$ -Cyclopentadienyl Iron Carbonyl Halides, Substitution of, by Diphenylcycloprope- none (Brown, Lyons, Hussein and Munir)	139	Dialkylbenzodipyrrocolinequinones, Synthesis of: Heterocyclic Quinones—Part III (Soni and Saxena) ...	668
Cyclopentadienyl Ring, Effect of Different Groups on, on the Stability of Titanium-			

<i>p</i> -( 2,4-Diarylamino-6- <i>S</i> -Triazinylamino )—Benzaldehyde Acetophenone Thiosemicarbazones, Preparation of Some, as Potential Tuberculostatic Agents. Studies on Antitubercular Agents. Part—III (Langalia and Thaker)	1099	$\alpha\alpha$ -Dimethylglutaric Acid, Friedel-Crafts Reaction of the Anhydride of, with Different Aromatic Hydrocarbons and Synthesis of 1,1-Dimethyl-3,4-benzo/substituted benzocycloheptanes and 1,1-Dimethylthieno [3,4- <i>b</i> ] Cycloheptane (Studies in the Cycloheptane Series Part-XXXI) (Gautam, Kannan and Saharia)	378
Dielectric Properties and Dipole Moments of Mn(II) Salts, Study of, of Some Fatty Acids in Benzene Solutions (Pardeshi)	1050	1,1-Dimethyl-3,4-benzo/substituted benzocycloheptanes and 1,1-Dimethylthieno [3,4- <i>b</i> ] Cycloheptane, Friedel-Crafts Reaction of the Anhydride of $\alpha\alpha$ -Dimethylglutaric Acid with Different Aromatic Hydrocarbons and Synthesis of Studies in the Cycloheptane Series. Part-XXXI (Gautam, Kannan and Saharia)	378
Diethylaminomethyl Ester, Organotin(IV) Derivatives of, of 2-Amino-1-Cyclopentene-1-Carbodithioic Acid. Metal Complexes of Sulfur-Nitrogen Chelating Agents (Singh and Gupta)	793	1,1-Dimethylthieno [3,4- <i>b</i> ] Cycloheptane and 1,1-Dimethyl-3,4-benzo/substituted benzocycloheptanes, Friedel-Crafts Reaction of the Anhydride of $\alpha\alpha$ -Dimethylglutaric Acid with Different Aromatic Hydrocarbons and Synthesis of. Studies in the Cycloheptane Series. Part-XXXI (Gautam, Kannan and Saharia)	378
Differential Refractometric and Conductometric Studies on the Charge-Transfer Interaction of Some Metal $\beta$ -Diketonates (Sahai, Singh and Verma)	46	Dioxouranium(VI) Heterochelates (Syamal and Kumar)	96
3,4-Dihydroxyphenylalanine, The Oxidation of Optically Active, by Optically Active Cobalt(III) Complexes (Yoshikawa and Yamasaki)	1250	Dioxygen Complexes of the Heavier 4d and 5d Transition Metal Ions (Taqui Khan)	160
Disothiocyanatodihalonickelates(II) (Prasad, Kumari and Jha)	207	Diphenylsiladioxo and Triphenylsiloxo Derivatives of Boron (Bharadwaj and Srivastava)	300
$\beta$ -Diketonates, Differential Refractometric and Conductometric Studies on the Charge-Transfer Interaction of Some Metal, with Iodine (Sahai, Singh and Verma)	46	Dipole Moments and Dielectric Properties of Mn(II) Salts, Study of, of Some Fatty Acids in Benzene Solutions (Pardeshi)	1050
$\beta$ -Diketones of Boron, Some New Their Synthesis and Characterisation (Singh, Saxena and Rai)	273	2,2'-Dipyridyl-2-Pyrimidylhydrazones, Stability Constants of Fe(II), Co(II), Ni(II) Cu(II) and Cd(II) Complexes of (Deshmukh)	105
17,18-Dimethoxy-15,16,17,18,19,20-hexadecahydroyohimbane, Synthesis of, by Condensation of an Indolylethylbromide with 3(2H)-isoquinolone (Pandey, Tiwari and Tandon)	532	Dissociation Constants of DL-Tryptophan, Potentiometric Determination of, in Different Aquo-organic Solvents (Saxena and Sharma)	413
1,5-Dimethyl- and 1,5-Diphenyl-1,3,5-Pentatrienes, Physico-Chemical Studies of, with V(II), Cr(III), Mn(II), Co(II), Ni(II), Cu(II) and UO <sub>2</sub> (II) (Kumar, Sharma, Sharma and Bachlas)	280	Dissociation Constants of Violuric Acid, Spectrophotometric Determination of, and Stability Constant of its Cu(II) Complex (Singh and Ghosh)	939
5,5-Dimethylcyclohexane-2-Benzothiazolylhydrazono-1,3-Diones and its 2-Methyl, 4-Methyl, 4-Methoxy, 4-Ethoxy Derivatives, Polarographic Reduction of Some (Malik, Agarwal and Jain)	1060		

2-(N,N-Disubstituted Aminoacetamido)-4- <i>p</i> -Fluorophenyl and - <i>m</i> -Methoxyphenyl Thiazoles, Synthesis of Local Anaesthetics. Part-II (Bhargava, Lakhan and Tripathi) ...	773	on the, Stabilized by Lignosulphonate of <i>Eucalyptus teriticornis</i> (Malik, Srivastava, Chand and Jindal) ..	1053
Ditertiaryphosphine, Dioxides, Donor Properties of, towards Iron(III) (Lobana, Cheema and Sandhu) ..	799	Electrode Behaviour and Spectral Properties, Correlation of, of Some Mixed Ligand Complexes of Copper(II) (Srivastava, Lal and Nigam) ..	497
2,4-Dithio-3,5-Diaryl-6-Phenylimino-Hexahydro-1,3,5-Triazines and 2,6-Dithio-3,5-Diaryl-4-Phenylimino-Hexahydro-1,3,5-Triazines, Synthesis of. on 1,3,5-Triazines. Part-II (Pathe, Ambekar, Nimdeokar and Paranjpe) ...	670	Electrode Kinetics of the Polarographic Reduction of Ni(II) in the Presence of Increasing Concentrations of L-4-Hydroxyproline and L-Tryptophan (Khatri and Singh) ...	897
Dithiocarbamates, Infrared Spectra of Some New (Waraich, Gaur, Pandeya and Singh) ..	103	Electrolysis, Studies on, in a W-tube with Reference to Non-Faradaic Behaviour (Ghosh and Palit) ...	1047
Dithiocarbamates, Synthesis of New, as Potential Anthelmintic Antimicrobial and Insecticidal Agents (Kumar, Shukla, Ramrakhyani, Sen Gupta and Srivastava) ...	681	Electrolyte Solutions, New Conceptions on the Equilibrium Properties of (Suryanarayana) ...	562
<i>Bis</i> -Dithiocarbamate di- <i>p</i> -Tolyl Tin(IV), Preparation and Characterization of (Wadhwa, Garg, Sharma and Kumar) ..	247	Electrolytes on Lyophobic Sols, Action of (Ghosh and Rathi) ..	567
Dithionon, Salicylanilide and Tryptophan, Stacked Ternary Complexes of, with Co(II), Ni(II) and Cu(II) (Sahai, Agrawal and Kushwaha) ..	1121	Electromigration of Some Metal Ions on Filter Paper Using Aqueous Glycolate Buffer Media (Bhatnagar and Yusufi) ...	410
Dithiophosphinates of Some First Row Transition Metals (Mukherjee, Venkateshan, Vijaya and Gogoi) ..	170	Electron Impact Induced Fragmentation of Schiff Bases of 2-hydroxy-5-methylbenzaldehyde (Samant and Mayadeo) ...	383
Divalent Metal Complexes of Benzil Semicarbazone, Studies on Hydrazones, Semicarbazones, Thiosemicarbazones and Oximes as Ligands. Part-III (Mishra, Mohapatra and Panda) ...	836	Electron Spectroscopic Investigations of Carbon Monoxide, Nitrogen and Oxygen Adsorbed on Transition Metals (Kamath, Yashonath, Srinivisan, Basu and Rao) ...	153
Donor Properties of Ditertiaryphosphine Dioxides towards Iron(III) (Lobana, Cheema and Sandhu) ...	799	Electronics, High Purity and Special Materials for (Rao and Ranganathan) ...	518
		Electrophilic Substitution in Indoles. Part-I: Reaction of 3-Methyl Indole with Sulphuryl Chloride (Chatterjee, Pandit, Sarkar and Shoolery) ...	523
		Electropositive Elements, Complex Polymetaphosphates of Strongly (Mehrotra, Vyas and Oza) ...	486
		Energy Transfer, Concentration Depolarization and Kinetics of Concentration Quenching of Fluorescence of Anthracene Sulfonates (Basu, Gupt and Rohatgi-Mukherjee) ...	578
		Equilibrium and Formation Constants of Co(II), Ni(II) and Zn(II) Complexes of <i>N</i> -Benzoyl Phenyl Hydroxyl Amine in	

"E"

<i>Eclipta alba</i> , Phytochemical Studies on (Sikoria, Srivastava and Niranjana) ...	905
Elastic Constants, Ultrasonic Study of the, of Some Ancient and Mediaeval Indian Coins (Prakash and Murthy) ...	591
Electrical Conductance and Interfacial Tension of Oil/Water Emulsions, Studies	

Various Mixed Aqueous Solvents (Chaudhury and Kole)	934	plexes of, with 3-Phenylaminomethyl benzoxazolinone-2 (Screening of Metal Complexes for Biological Activity. Part-IV) (Bajpai and Shukla)	343
Equilibrium Constants of Ferric Formate Complex, Determination of, by Paper Electrophoresis (Mukherjee and Debi)	907	Fe(II), Co(II), Ni(II), Cu(II) and Cd(II), Stability Constants of, Complexes of 2,2'-Dipyridyl-2-pyrimidylhydrazone (Deshmukh)	105
Equilibrium Properties of Electrolyte Solutions, New Conceptions on the (Suryanarayana)	562	Fe(III), Co(III), Cu(II) and Ni(II) Derivatives of Some New Monothio- $\beta$ -Diketones (Saini, Gupta and Mehrotra)	1424
Equilibrium Study of the Mixed Complexes of Uranyl Ion with 3,5-Dinitrosalicylic as Primary and Some Substituted Carboxylic Acids as Secondary Ligands (Shelke)	833	Fe(II) Complexes, Effect of Substitution on the Relative Stabilities of, of Substituted Salicylic Acid (Chattopadhyaya)	1416
ESR Spectra, Studies of, of Some Cu(II) Complexes (Bhave and Kharat)	994	Ferric Formate Complex, Determination of Equilibrium Constant of, by Paper Electrophoresis (Mukherjee and Debi)	907
ESR Study of Cu(II)-N-Aryl Glycinates (Bai, Wang and Chen)	1280	Ferrocenyl Hydrazones, Phenyl-Tin Cleavage by Some (Pittel, Kantak and Sen)	1300
Ethylenediphosphonic Acid, Interaction of, with Some Divalent Metal Ions (Organophosphonic Acids as Complexes. Part-II) (Palta, Dubey and Puri)	261	Ferrous-1,10-Phenanthroline, Thermodynamics of, in <i>t</i> -Butanol-Water and Glycerol-Water Media at 25° (Mandal, Bandyopadhyay and Aditya)	1390
<i>Eucalyptus citriodora</i> Roots, Chemical Constituents of (Dayal)	1008	Field Soil, Movement and Transformation of Anhydrous Ammonia (Bagchi, Ghosh, Ghosh and Dhua)	453
<i>Eucalyptus teriticornis</i> , Studies on the Interfacial Tension and Electrical Conductance of Oil/Water Emulsions Stabilized by Lignosulphonate of (Malik, Srivastava, Chand and Jindal)	1053	FIR Studies of Copper(II) Monohaloacetates: Molecular Structure Based on Cu-O Vibrations (Tyagi and Srivastava)	823
Evaluation of the Mean Activity Coefficient of the Ions of Strong Electrolytes in Solutions whose Concentration Varied from 0.001 M to 4 M (Ghosh)	737	First Dissociation Constant of Phosphoric Acid at a Number of Temperature (Ghosh and Ghosh)	745
Extraction and Spectrophotometric Determination of Vanadium(V) as Mixed Ligand Complexes of Various Hydroxyamides and Thiocyanate (Jha and Mishra)	1177	Flavone Glycoside, Structural Studies of a New, from the Seeds of <i>Cassia nodosa</i> (Tiwari and Sinha)	526
"F"		Flavonoids and Other Constituents of <i>Indigofera hetrantha</i> (Thusoo, Raina and Ahmed)	1007
Fatty Acids in Benzene Solutions, Study of Dielectric Properties and Dipole Moments of Mn(II) Salts of Some (Pardeshi)	1050	Floatable Ion Associates Formed in the System Iridium(III) - Tin(II) - Chloride-Basic Dye (Marczenko and Kalinowski)	1354
Fatty Acids, Properties of Pure Sodium Soaps of Saturated (Sheth and Subrahmanyam)	860	Fluorides, Heat Capacity and Thermodynamic Properties of Some Mixed (Keer, Deenadas and Bhat)	740
Fe <sup>2+</sup> , Co <sup>2+</sup> , Ni <sup>2+</sup> and Cu <sup>2+</sup> , Synthesis of Pharmacologically and Microbiologically Active Thiocyanato and Oxalato Com-		Fluorinated 1,3-Diketones, Some Aspects of the Chemistry of (Joshi)	1375

Fluorinated 1,3-Diketones, Studies in and Related Compounds. Part-XIII : Synthetic and Spectral Studies of Some New Fluorinated <i>Tris</i> Europium 1,3-Diketonates (Joshi, Pathak and Grover)	293
Fluorinated 1,3-Diketones, Studies in and Related Compounds. Part-XIV : Search for New NMR Shift Reagents (Joshi, Pathak and Grover)	... 1072
Fluorinated <i>Tris</i> Europium 1,3-Diketonates, Synthetic and Spectral Studies of Some New (Studies in Fluorinated 1,3-Diketonates and Related Compounds Part-XIII) (Joshi, Pathak and Grover)	293
3-( <i>p</i> -Fluoro)benzoylhydrazono-5-substituted-2-indolinones, Synthesis of, as Potential Biologically Active Agents (Varma and Pandey)	1174
Formamide, Kinetics of the Acid Catalysed Hydrolysis of, in Binary Aqueous Mixtures (Mittal, Gupta and Gupta)	595
Formation Constants of the Chelates of 2-Hydroxy-1-Naphthalidene- <i>ortho</i> -Fluoro-aniline with Some Bivalent Metal Ions (Mayadeo, Chaubal and Hussain)	949
Formate Complexes, Relative Stability of, by Paper Electrophoresis (Mukherjee and Debi)	... 908
Formylcamphor Condensed with Diamines : The Structure in Solution as Obtained from UV Absorption and Circular Dichroism Spectroscopy (Jensen)	... 1387
Free Acids in Lac Resin (Prasad, Agarwal, Chatterjea and Sengupta)	.. 980
Free Metal Ions and Formation Constants, Computations of Apparent, in EGTA or EDTA Buffer Systems. Part-I : Effects of pH and Metal Concentration with Respect to Ligand (Biswas and Chebib)	... 1419
Friedel-Crafts Reaction of the Anhydried of $\alpha\alpha$ -Dimethylglutaric Acid with Different Aromatic Hydrocarbons and Synthesis of 1,1-Dimethyl-3,4-benzo/substituted benzocycloheptanes and 1,1-Dimethylthieno [3,4-b] Cycloheptane (Studies in the Cycloheptane Series. Part-XXXI) (Gautam Kannan and Saharia)	... 378

Fuel Cells, Bio-Chemical (Govil and Saran)	... 1226
Fumaryl- <i>bis</i> -N-Phenyl (FPHA), <i>p</i> -Phenylene-di-Acrylyl- <i>bis</i> -N-Phenyl (PAPHA), Isophthalyl- <i>bis</i> -N-Phenyl (IPHA) Hydroxamic Acids, Synthesis of, and Spectral and Magnetic Studies of their Polymers with Mn(II), Fe(II), Co(II), Ni(II), Cu(II) and Zn(II) (Gandhi and Munshi)	1290
Functional Approach to the Problem of Origin in Life—Photochemical Splitting of Water and Reduction of Nitrogen and Carbon Dioxide (Bahadur and Ranganayaki)	480
Furan-2-carboxaldoxime and 3-Methyl-4-aryl-azopyrazole-5-one using Thermogravimetric Analysis, A Study of the Decomposition Patterns of Some Transition Metal Complexes Derived Mainly from the Heterocyclic Ligands viz., (Shukla, Srivastava and Singh)	.. 1180
Furyl-2-Keto-Oximes, Rearrangement in (Chatterjea and Singh)	527
"G"	
Ga(III), In(III) and Ge(IV), Influence of Some Ionic and Non-ionic Surfactants on the Electrode Reactions of (Dubey and Singh)	706
Gadolinium, Erbium and Ytterbium, A Potentiometric Study on the Complexes of, in Aqueous Solution (Lakhani, Thakur and Sangal)	801
Gas-liquid Chromatographic Study of Molar Heats of Evaporation. Effect of Molecular Structure (Al-Dhahir and Swan)	.. 645
Gloxal— $h_2$ - $d_2$ and $hd$ , Vibrational Analysis of (Natarajan, Kolandaivelu and Savariannandam)	1155
Glycolic Acid, Kinetics of Oxidation of, by Quinquevalent Vanadium in Sulphuric Acid Medium (Choudhary and Prasad)	... 638
Goat Serum, Use of, as a Substitute for Horse Serum for Growing <i>Entamoeba histolytica</i> . Amoebicidal Testing of Drugs (Dutta, Pal, Dey and Lahiri)	... 902

Halogen Oxidation and Nitrosylation of Mixed Ligand Molybdenum and Tungsten Tricarbonyls (Tripathi, Srivastava, Pandey and Srivastava) ..	238	on Electroneutral Ion-Carriers : Barium(II) and Nickel(II) Electrodes (Lal, Chattopadhyaya and Dey) ...	493
Hammett Parameters, Polarographic Studies on the Reduction of the Azomethine Bond in Aryl Thiosemicarbazides and the Determination of (Malik, Upadhyaya, Jain and Sharma)	1057	Heteropoly 6-Ammonium Molybdochromate, Studied in (Mishra, Roy and Ojha) ...	792
Heat Capacity and Thermodynamic Properties of Some Mixed Fluorides (Keer, Deenadas and Bhat)	740	Heteropoly Complexes, Infrared Spectra and Thermal Studies of Some Reported (Roy and Jha)	1096
Heat Capacity and Thermodynamic Properties of $\text{Sr}_2\text{MoCoO}_8$ and $\text{Sr}_2\text{MoNiO}_8$ (Gunjkar, Ramachandran and Keer)	743	High Content of Cholesterol in the Lipid of <i>Acacia farnesiana</i> Leaves (Andhiwal and Kishore)	1079
3-Heteraryl Coumarins, Synthesis of, as Optical Brighteners (Annapurna, Reddy and Somayajulu)	977	High Purity and Special Materials for Electronics (Rao and Ranganathan)	518
Heterocyclic Compounds, On the Polarographic Reduction Mechanism of Some (Malik and Jain)	191	High Spin Cobalt(II), Spectral and Magnetic Studies of Some Mixed Ligand Complexes of (Sankhla, Mathur and Misra) ...	893
Heterocyclic Compounds, Studies on Part-V Synthesis and Antimicrobial Activities of N-Bridged Thiazole and Imidazole Derivatives (Dehuri and Nayak)	1170	Hydrated Calcium Salts, Dehydration and Decarboxylation of, of Pyridine Monocarboxylic Acids. A Study on Solid State Thermal Decomposition Characteristics of Some Metallo-organic Compounds. Part-I (Ghosh, Ray, Ray and Bandyopadhyay)	1034
Heterocyclic Compounds, Studies in. Part-XXXI: Synthesis of Some 4-Methyl-5 (Methyl/ <i>p</i> -methylphenyl )-5-(arylozo/N-substituted <i>p</i> -sulphamylbenzeneazo)-pyrimidin-2-ols as Potential Antibacterials (Nigam, Saharia and Sharma) ...	709	Hydrated Sulphates of Copper(II), Nickel(II) and Cobalt(II), Characterisation of Some Solid Products Obtained by Carrying Out the Replacement Reactions on the, Using Two Different Heterocyclic Ligands viz., Antifuran-2-Carboxaldoxime and 2-Pyrrolidone (Shukla, Singh, Bhargava and Narain) ...	620
Heterocyclic Compounds. Sulphur as a Potential Oxidant: Preparation of 5-Alkyl/arylimino-2,4-dialkyl/aryl-3-thio/oxo-1,2,4-thiadiazolidines (Jadhav and Paranjpe)	71	Hydrazoic Acid-Boron Trifluoride Etherate, Action of Excess, on 3-Oxo-Penta Cyclic Triterpenes. Aza Triterpenes—III (Ramaiah, Ramraj, Govardhan and Rao) ..	975
Heterocyclic Quinones—Part-III Synthesis of Dialkylbenzodipyrrocolinequinones (Soni and Saxena) ...	668	Hydrazones, Semicarbazones, Thiosemicarbazones and Oximes, Studies on, as Ligands. Part-III: Some Divalent Metal Complexes of Benzil Semicarbazone (Mishra, Mohapatra and Panda) ...	836
Heterogeneous Ion Exchange Membrane Disc, Selectivity of, with Reference to their Water Content, Porosity, Swelling, Electrolyte Absorption and Electrical Conductance (Jain, Singh and Agrawal)	106	Hydroboration of Organic Nitriles. MNDO Study of Reaction Paths (Chadha and Ray) ...	204
Heterogeneous Ion-Selective Electrodes Based		Hydroformylation Reactions, New Catalytic Intermediates in Homogeneous: Reactions of Allylmetal Carbonyls of Rhodium	1473

and Cobalt with Carbon Monoxide and Hydrogen (King and Tanaka)	124	Constants of, with $Mg^{2+}$ , $Co^{2+}$ , $Ni^{2+}$ and $Cu^{2+}$ (Mayadeo and Purohit)	... 955
Hydrofuramide, Influence of, on Sulphenamide Acceleration System: Vulcanization of Natural Rubber (Banerjee and Chakravarty)	... 403	2-Hydroxy-1-Naphthalidene-Sulphamethoxazole Complexes, Determination of Stability Constants of, with $Cu^{2+}$ , $Ni^{2+}$ , $Zn^{2+}$ and $Mg^{2+}$ (Mayadeo and Bhattacharjee)	.. 896
Hydrogen Ion Equilibria and Metal Binding Studies on Arachin (Malik, Bhushan and Agarwal)	... 1316	2-Hydroxy-1-Naphthalidenesulphafurazole Complexes, Determination of Stability Constants of, with $La^{3+}$ , $Y^{3+}$ , $Pr^{3+}$ , $Nd^{3+}$ , $Gd^{3+}$ , $Dy^{3+}$ (Mayadeo and Bhattacharjee)	... 1189
Hydrogen Ion Equilibria on <i>p</i> -Toluene-sulphonylated Casein (Malik, Tyagi and Mittal)	423	2-Hydroxy-1-Naphthalidene-Sulphaphenazole Complexes, Determination of Stability Constants of, with $La^{3+}$ , $Y^{3+}$ , $Pr^{3+}$ , $Nd^{3+}$ , $Gd^{3+}$ , $Dy^{3+}$ (Mayadeo and Bhattacharjee)	800
Hydrogen Peroxide, Chemiluminescent Method for Determination of Low Concentration of (Das, Moorthy and Rao)	85	2-( <i>o</i> -Hydroxyphenyl) Benzthiazoline, Complexes of, with Some Bivalent Metal Ions (Das, Gupta, Prasad and Mishra)	.. 334
Hydroxamic Acid Formation, Kinetics of Nickel(II) Ion and Cobalt(II) Ion Catalysed, from Formic Acid (Jagdale, Salunkhe and Swami)	355	3-Hydroxy-2-(3'-pyridyl) Chromones and -2-(3'-pyridyl) Chromones, Synthesis of (Thakar and Joshi)	77
Hydroxy Coumarins, Some . Acid Dissociation Constants in Ethanol Water Mixture (Arora, Aggarwal and Singh)	347	8-Hydroxyquinoline and Potassium Hexacyanoferrate(II), Molecular Complexes of, in Acid Medium (Pal and Manna)	409
Hydroxy Diaryl Sulphones and Aryl Fluorobenzene Sulphonates, Synthesis of Some, as Potential Fungicides (Giri, Nizamuddin and Gupta)	365	Hypoglycemic Agents, New, Search for. Part-VII: Coumarinylsulphonyl Ureas, Semicarbazides and Semicarbazones (Husain, Gupta and Srivastava)	. 1193
2-Hydroxyisocarbostyrils, Synthesis of Chatterjea, Mukherjee and Bhakta)	.. 707	"I"	
2-Hydroxy-5-methylbenzaldehyde, Electron Impact Induced Fragmentation of Schiff Bases of (Samant and Mayadeo)	383	4-Imidazolyl-2-Methyl-5-Nitro- <sup>2</sup> -Hydroxyquinolines, Synthesis of, as Possible Antiprotozoal Agents (Mitra and Pathak)	367
2-Hydroxy-1-Naphthalidene-4'-Chloro-2'-Methoxyaniline Complexes, Determination of Stability Constants of, with $La^{3+}$ , $Y^{3+}$ , $Pr^{3+}$ , $Nd^{3+}$ , $Dy^{3+}$ and $Gd^{3+}$ (Mayadeo, Purohit and Hussain)	894	In(III), Polarographic Reduction of (Kapoor and Jain)	510
2-Hydroxy-1-Naphthalidene-2',6'-Dimethylaniline Complexes, Determination of Stability Constants of, with $La^{3+}$ , $Y^{3+}$ , $Pr^{3+}$ , $Nd^{3+}$ , $Dy^{3+}$ and $Gd^{3+}$ (Mayadeo, Purohit and Hussain)	. 952	Indian Coins, Ancient and Mediaeval, Ultrasonic Study of the Elastic Constants of Some (Prakash and Murthy)	. 591
2-Hydroxy-1-Naphthalidine- <i>ortho</i> -Fluoroaniline, Formation Constants of the Chelates of, with Some Bivalent Metal Ions (Mayadeo, Chaubal and Hussain)	... 949	Indian Coin (Cupro-nickel) and Pyrolusite, Paper Electrophoretic Separation and Estimation of the Constituents of (Mukherjee and Debi)	... 984
2-Hydroxy-1-Naphthalidene-4'-Hydroxyaniline Complexes, Determination of Stability		Indian Rock Phosphates, Reactivity of, in Presence of Oxidative Degradation Products of Coal (Pathak)	899
		Indigenous Plants, Chemical Examination of Three (Dan, Dan and Mukhopadhyay)	... 419



<i>Indigofera hetrantha</i> , Flavonoids and other Constituents of (Thusoo, Ratna and Ahmed)	1007	5-Iodo-8-Hydroxyquinolino-4-( <i>p</i> -Tolyl) sulphonamide and 5-Iodo-7-Chloro-8-Hydroxyquinolino-4-( <i>p</i> -Tolyl) sulphonamide, Studies on Metal Chelates of (Tiwari and Mishra)	362
Indirect Method for the Iodometric Microdetermination of Certain Organic Acids (Pateria and Verma)	1203	<i>Bis</i> (Iodomethyl) Mercury as a $\text{CH}_3$ Transfer Reagent (Seyferth, Haas and Dagan)	111
Infrared Spectra and Thermal Studies of Some Reported Heteropoly Complexes (Roy and Jha)	1096	Iodometric Microdetermination, An Indirect Method for the, of Certain Organic Acids (Pateria and Verma)	1203
Infrared Spectra of Iron(II) Complexes with N,N-Dimethylformamide and N,N-Dimethylthioformamide (Linert and Gutmann)	1284	Ion-Exchange Equilibria of $\text{Na}^{2+} - \text{Ca}^{2+}/\text{Cl}^-$ and $\text{Na}^{2+} - \text{Mg}^{2+}/\text{Cl}^-$ from Concentrated Solution (Dave and Trivedi)	1136
Infrared Spectra of Some New Dithiocarbamates (Waraich, Gaur, Pandeya and Singh)	103	Ion Exchange Selectivity of Monovalent Ions in Aqueous and 50% Ethanol-Water Media towards <i>Tris</i> -Trimethylene Diamine Co(III) Exchanged Amberlite-IRC-50 (Sarkar and Das Kanungo)	358
Infrared Spectroscopic Study of Saturation Extracts from Arid-Zone Field Soils Amended with Sewage Sludge (Schaumberg, LeVésque-Madore, Sposito and Chang)	150	Ionic and Non-ionic Surfactants, Influence of Some, on the Electrode Reactions of Ga(III), In(III) and Ge(IV) (Dubey and Singh)	706
Inorganic Coordination Complexes. Part-V Complexes of Divalent Zinc, Cadmium and Mercury with Substituted Salicyl Hydrazines (Tewari, Bajpai, Misra, Shukla and Misra)	891	Ionic and Non-ionic Surfactants, Polarographic Studies on the Effect of Some, on the Kinetics of Irreversible Electrode Processes of Arylazopyrimidine and Arylazopyrazole (Malik and Jain)	962
Integrated Nutrient Supply to Soil for Productivity (Raychaudhuri)	435	Iridium(III) - Tin(II) - Chloride - Basic Dye, Floatable Ion Associates Formed in the System (Marczenko and Kalinowski)	1354
Intensity and Velocity, The Relation Between, of Photochemical Reactions (Bhagwat)	575	Iron(II) Complexes, Infrared Spectra of, with N,N-Dimethylformamide and N,N-Dimethylthioformamide (Linert and Gutmann)	1284
Interaction Products of Triphenylphosphine Oxide with Some Organotin Halides (Bajpai and Bajpai)	1090	Iron Concretions, A Study of, in Lateritic Soil of West Bengal (Roy and Mukherjee)	440
Interdisciplinary Science, Training and Research in Analytical Chemistry (Mehrotra)	1209	Iron, Phenoxy Acetyl Acetophenone as an Analytical Reagent for (Ambhore, Ilyas Joshi)	691
Interfacial Tension and Electrical Conductance of Oil/Water Emulsions, Studies on the, Stabilized by Lignosulphonate of <i>Eucalyptus teriticornis</i> (Malik, Srivastava, Chand and Jindal)	1053	Iron(III), Mixed Chelate Complexes of, Containing Dithiocarbamate and Acetyl-acetate, Oxinate or Glycinate (Kanungo, Pradhan and Rao)	329
Interrelation in Water Soluble P, Adsorbed P and Olsen's P, Phosphate Fertilization in Alluvial Soils of Allahabad Division (Misra and Pathak)	466	Iron(III), Selective Extraction and Spectrophotometric Determination of, as Thiocyanato and Azido Mixed-Complexes with Hydroxy-amidine (Jha and Mishra)	694
Intramolecular $\pi$ - $\pi$ Interactions in Metal "Capped" Porphyrins (Venkatasubramanian and Basolo)	1218		

Iron(III), Selective Microgram Detection of, on Ion Exchange Resin Beads (Nabi, Siddiqui, Athar and Ahmad) ...	1200	Lanthanide Complexes, Its Binary and Ternary: Some Ligational Aspects of Tartrazine (Limaye and Saxena) ...	698
Isatin, The Reaction of, with Active Methylene Group. Part-I: Formation of 5-(2-Oxo-3-Indolinylidene)-3-Aryl-2,4-Thiazolidindiones—A New Class of Thioindigoid Dyes (Lakhan, Bhargava and Prasad) ..	804	Lanthanide Complexes, Synthesis and Spectral Studies of, with Fluoro $\beta$ -diketones (Misra) ...	99
Isobutyl Alcohol, A Kinetic Study of Oxidation of, with Aqueous Iodine (Manglik and Sharma)	352	Lanthanide-EDTA Ternary Complexes, Some, with Catechol, Resorcinol and Phloroglucinol (Limaye and Saxena)	916
Isomerization of $\beta$ -Pinene in the Vapour Phase Over Alumina Catalyst · Influence of Partial Pressure of Nitrogen and Pyridine (Krishnasamy and Ratnasamy)	1151	Lateritic Soil of West Bengal, A Study of Iron Concretions (Roy and Mukherjee)	440
Isophthalyl-bis-N-Phenyl (IPHA) Hydroxamic Acids, <i>p</i> -Phenylene-di-Acrylyl-bis-N-Phenyl (PAPHA), Fumaryl-bis-Phenyl (FPHA), Synthesis of, and Spectral and Magnetic Studies of Their Polymers with Mn(II), Fe(II), Co(II), Ni(II), Cu(II) and Zn(II) (Gandhi and Patel)	1290	Lateritic Soils, Role of Phosphate and Organic Matter in the Management of, for Increasing Productivity (Ghosh)	457

#### "K"

KCl and NaCl Sucrose+Water, Glucose+Water and Urea+Water Mixtures, Conductance of, at Different Temperatures (Mohanty and Das) ..	1190	<i>Launaea nudicaulis</i> , Chemical Constituents of: C-13 Nuclear Magnetic Resonance Spectroscopy of Taraxasterenes and Pseudo-Taraxasterenes (Majumder and Laha)	881
Kinetics and Mechanism of Oxidation of Substituted Mandelic Acids by Sodium N-Chlorobenzenesulphonamide (Jain and Banerji)	654	Linear and Angular Furanoflavones, Carbon-13 NMR Spectra of (Talapatra, Mallik and Talapatra)	534
Kinetics of Oxidation of Glycollic Acid by Quinquevalent Vanadium in Sulphuric Acid Medium (Choudhary and Prasad) ..	638	Lipid of <i>Acacia farnesiana</i> Leaves, High Content of Cholesterol in the (Andhiwal and Kishore)	1079
Kinetics of Oxidation of L-Rhamnose by Vanadium(V) (Fadnis and Kulshrestha)	411	Lithium Aluminium Hydride and Lithium Tetraphenylaluminate, Redistribution Reactions Involving (Ashby and Goel) ..	134
		Local Anaesthetics. Part-II: Synthesis of 2-(N,N-Disubstituted Aminoacetamido) 4- <i>p</i> -Fluorophenyl and - <i>m</i> -Methoxyphenyl Thiazoles (Bhargava, Lakhan and Tripathi) ...	77
		Low Concentration of Hydrogen Peroxide, Chemiluminescent Method for Determination of (Das, Moorthy and Rao) ...	8
		Lyophobic Sols, Action of Electrolytes on (Ghosh and Rath)	56

#### "L"

La <sup>3+</sup> and Ce <sup>3+</sup> , Amperometric Estimation of, with Cupferron using d. m. e (Pitre and Lavale) ...	1081
Lac Resin, Free Acids in (Prasad, Agarwal, Chatterjea and Sengupta) ...	980
$\beta$ -Lactam Derivatives, Synthesis of Some Novel (Sharma, Ray and Chatterjee) ...	536

#### "M"

<i>Machilus glaucescens</i> Wight, Alkaloids of: Machigline A New Phenolic Oxoaporphine Alkaloid (Talapatra, Goswami and Talapatra) ...	136
Magnesium, Mixed Ligand Complexes of Some Organic Compounds of, with Nitrogen Donor Ligand Alkaline Earth	

Metal Complexes (Banarjee, Sinha, Ghosh and Roy)	1020	$\pi$ - $\pi$ Interactions in (Venkatasubramanian and Basola)	... 1218
Mandelic Acids, Kinetics and Mechanism of Oxidation of Substituted, by Sodium N-Chlorobenzenesulphonamide (Jain and Banerji)	654	Metal Complexes, A Study of the Decomposition Patterns of Some Transition, Derived mainly from the Heterocyclic Ligands viz, furan-2-carboxaldoxime and 3-Methyl-4-arylazopyrazole-5-one using Thermogravimetric Analysis (Shukla, Srivastava, Singh and Narain)	1180
Manganese, Cation Exchange Chromatographic Separation of, in Mixed Solvent Systems (Gaikwad and Khopkar)	1346	Metal Complexes, Screening of, for Biological Activity. Part—IV : Synthesis of Pharmacologically and Microbiologically Active Thiocyanato and Oxalato Complexes of Fe <sup>3+</sup> , Co <sup>3+</sup> , Ni <sup>3+</sup> and Cu <sup>3+</sup> with 3-Phenylaminomethyl benzoxazolinone-2 (Bajpai and Shukla)	343
Mannich Bases as Potential Polydentate Ligands: 2,5-Bis (benzylaminomethyl) Hydroquinone Complexes (Gupta, Maurya and Dey)	216	Metal Complexes as Ligands : Binuclear Alkali Metal Complexes with Copper(II)- and Nickel(II)-Salicylaldehydes (Banerjee, Prasad and Roy)	1303
Mass Spectrometry of Transitions Metal $\pi$ -Complexes. Part-VII : A Study of the Behaviour of Some Ruthenocene Derivatives (Davis and O'Reardon)	1270	Metal Complexes of Some Model Peptides. Part—I : Complex Formation of Cu(II) with N-Salicyloyl Glycine (Mukherjee, Sarkar and Chatterjee)	1117
Maximizing Crop Yields (Ghildyal)	445	Metal Complexes, Study of Transition and Non-Transition, with 3-Amino-2-Benzoyl-benzofuran (Huggi, Halli and Hiremath)	1017
Mean Activity Coefficient of the Ions, Evaluation of the, of Strong Electrolytes in Solutions whose Concentration Varied from 0.001 M to 4 M (Ghosh)	737	Metal Complexes of Sulfur-Nitrogen Chelating Agents : Organotin(IV) Derivatives of Diethylaminomethyl Ester of 2-Amino-1-Cyclopentene-1-Carboxithioic Acid (Singh and Gupta)	793
Medicago sativa Seeds, Chemical Examination of (Shrivastava and Nigam)	1198	Metal-Diene Complexes, Chemistry of : <sup>31</sup> P NMR Studies of the Reaction of (COD)-PtCl <sub>2</sub> with Tertiary Phosphines in Methanol (Goel and Goel)	141
Melting Behaviour of Some Pure N-Acyl Amino Acids and Peptides (Iyer, Sheth and Subrahmanyam)	856	Metal Ion Interactions with the Constituents of Nucleic Acid. Part-I : Metal-Adenine Complexes (Bhattacharyya and Bhaduri)	919
Mercaptans, A Method for the Analysis of, Mercurimetric Determination of Organotrithiocarbonates and (Verma, Kumar, Butail and Singh)	811	Metal Ions, Electromigration of Some, on Filter Paper using Aqueous Glycolate Buffer Media (Bhatnagar and Yusufi)	410
Mercurimetric Determination of Organotrithiocarbonates and A Method for the Analysis of Mercaptans (Verma, Kumar, Butail and Singh)	811	Metal-Polyalkoxylate Complexes and their Applications in Analytical Potentiometry (Thomas)	1323
Mercury—Mercurous Electrode, Standard Electrode Potential of, at a Number of Temperatures (Choudhary and Prasad)	555	Metal Tridentate Schiff Base Complex, System	1477
Metal—Adenine Complexes. Metal Ion Interactions with the Constituents of Nucleic Acid. Part—I (Bhattacharyya and Bhaduri)	919		
Metal Ammine Formation in Solution. Part-XXIII : The Nickel(II)-Mono- and Diethanolamine Systems (Bjerrum and Djurdjevic)	1229		
Metal "Capped" Porphyrins, Intermolecular			

- matic Study of the Solvent Extraction (Rao and Varadarajulu) 1009
- Metallo-organic Compounds, A Study on Solid State Thermal Decomposition Characterists of Some. Part—I: Dehydration and Decarboxylation of Hydrated Calcium Salts of Pyridine Monocarboxylic Acids (Ghosh, Ray, Ray and Bandyopadhyay) 1034
- Methacrylamide, Polymerization of, Initiated by Ceric Ion-Malic Acid Redox System (Misra and Khatib) 1384
- 1-Methoxy-2,4-Pentanedione, Chelating Tendencies of. The Rare Earths. Part-XXII (Martin, Moeller and Randall) 1232
- 2-Methyl-6(8)-alkyl-4-(arylsulphonylhydrazino) quinolines, Synthesis and Amoebicidal Activity of Some (Misra, Saxena and Srivastava) 781
- Methyl Group Oxidation: Kinetics of Cerium (IV) Oxidation of 2-Methyl Benzthiazole, Benzoxazole and Benzimidazole in Acetic-Perchloric Acid Mixture (Singh, Nayak, Rout and Padhi) 349
- 3-Methyl Indole, Reaction of, with Sulphuryl Chloride Part-I Electrophilic Substitution in Indoles (Chatterjee, Pandit, Sarkar and Shoolery) 523
- 4-Methyl-5(methyl/p-methylphenyl)-5-(arylaazo/N-substituted p-sulphamylbenzeneazo)pyrimidin-2-ols, Synthesis of Some, as Potential Antibacterials. Studies in Heterocyclic Compounds. Part-XXXI (Nigam, Saharia and Sharma) 709
- 2-Methyl-1,4-Naphthaquinone (Menadione), Reductive Alkylation of, at Mercury Pool Cathode (Misra, Jain and Yadava) 289
- 3-Methyl/Phenyl-4-(o/m/p-substituted benzeneazo)-5-isoxazolones, I-Phenyl-3-methyl/phenyl-4-(o/m/p-substituted benzeneazo)-5-pyrazolones and I-phenyl-3-(o/m/p-substituted anilic)-5-Pyrazolones, Synthesis of Some New, as Possible Biological Agents (Mittal and Singhal) ... 711
- 3-Methyl Pyrazole-3(5)-Carboxamide, Cobalt(II) Complexes of (Saha and Datta) ... 728
- Methylation of Phenol over Alumina in the Vapour Phase: Influence of Copper Sulphate (Krishnasamy, Subramaniam and Soundararajan) .. 1067
- Methylation of Quercetin and Myricetin, Selective (Chand, Maurya and Ray) ... 1001
- Methylmercury and Phenylmercury Species on Alga, The Cumulation of (Stary', Kratzer and Prasilova') 1329
- Microchemistry Teaching in Industry Versus Teaching in a University (Steyermark) .. 1213
- Mineralisation, Carbon, Nitrogen and Sulphur, in a Soil from Three Decomposing Plant Materials of Varying C/N, C/S and N/S Ratios (Bhattacharjya and Mukhopadhyay) ... 68
- Mitragyna parvifolia* (Roxb.) Korth. and their Transformations, Alkaloids of (Chatterjee, Dhara and Banerji) 1360
- Mixed Chelate Complexes of Iron(III) Containing Dithiocarbamate and Acetylacetonate, Oxinate or Glycinate (Kanungo, Pradhan and Rao) ... 329
- Mixed Ligand Anionic Complexes of Cadmium(II) (Mahapatra, Panda, Pujari and Chiranjeevi) 1022
- Mixed Ligand Bimetallic Tetrathiocyanato Complexes, Synthesis and Structural Studies of Some (Singh, Khan and Khan) 35
- Mixed Ligand Complexes of Cd(II), Isolation, Characterisation and Antimicrobial Activity Studies of the, with 8-Hydroxyquinoline and Various Salicylic Acids (Anjaneyulu, Rao, Swamy, Eknath and Rao) 1024
- Mixed Ligand Complexes of Cobalt(II) and Cadmium(II) with Oxime as Primary Ligand and Heterocyclic and Aromatic Amines as Secondary Ligands (Mahapatra and Pujari) 1183
- Mixed Ligand Complexes of Divalent Nickel, Synthesis and Characterization of (Arora and Misra) 98
- Mixed Ligand Complexes of Ni(II) Ethylacetoacetate with Schiff Bases, Synthesis and Characterization (Arora and Misra) ... 32
- Mixed Ligand Complexes of Zinc(II) (Padhy and Patel) ... 992

Mixed Ligand Complexes of Zinc(II) with Dibasic Acids and Nitrogen Donor Ligands (Padhy and Patel)	1182	Molybdenum(V) Cation, Studies on Reactivity of, in the Environment of Diverse Anions in Presence of 5-Nitro 1,10-Phenanthroline as an Organic Base (Saha, Sikdar and Raychaudhuri)	723
Mn(II) Salts, Study of Dielectric Properties and Dipole Moments of, of Some Fatty Acids in Benzene Solutions ( Pardeshi)	1050	Molybdenyl Cations, Stabilisation of, with 4,4'-Dimethyl 2,2'-Bipyridyl in Different Salt and Nonelectrolytic Complexes (Saha, Mandal and Ghorai)	1124
Mn(II), Studies on the Suppression of Polarographic Maximum of, by Some Uni- and Poly-valent Cations vis-a-vis Their Influence on the Kinetics of the Electrode Reaction of Mn(II) (Kumar, Chandra and Singh)	843	Monothio- $\beta$ -Diketones, Fe(III), Co(III), Cu(II) and Ni(II) Derivatives of Some New (Saini, Gupta and Mehrotra)	1424
MNDO Study of Reaction Paths : Hydroboration of Organic Nitriles (Chadha and Ray)	204	Mossbauer Spectra of Copper Nickel Ferrites (Kiran, Bommanavar and Chakrabarty)...	1310
Molar Heats of Evaporation, Gas-Liquid Chromatographic Study of : Effect of Molecular Structure (Al-Dhahir and Swan)	645	Movement and Transformation of Anhydrous Ammonia in Field Soil (Bagechi, Ghosh, Ghosh and Dhua)	453
Molecular Complexes of Tetracycline and Oxytetracycline Drugs with Nucleic Acid Bases and Aromatic Amino Acids (Lahiri and Basu)	941	M-S Bond, About the Nature of, in Complex Compounds (Bhattacharya)	515
Molecular Hydrogen, Yield of, as a Criterion for the Radiation Stability of Organic Compounds (Al-Dhahir)	632	Mukoline and Mukolidine, Two New Carbazole Alkaloids, Structure and Synthesis of, from <i>Murraya koenigii</i> Spreng (Roy, Bhattacharyya and Chakraborty)	1369
Molecular Orbital Study of $[\text{BFe}(\text{CO})_5]^+$ , $\text{B} = (\text{C}_6\text{H}_5)$ , $(\text{C}_6\text{H}_7)$ and $(\text{C}_7\text{H}_9)$ (Brown, Chester and Fitzpatrick)	1273	"N"	
Molecular Structure Based on Cu-O Vibrations : FIR Studies of Copper(II) Monohaloacetates (Tyagi and Srivastava)	823	$\text{Na}^{2+} - \text{Ca}^{2+}/\text{Cl}^-$ and $\text{Na}^{2+} - \text{Mg}^{2+}/\text{Cl}^-$ , Ion-Exchange Equilibria of, from Concentrated Solution (Dave and Trivedi)	1136
Molecular Structure, Effect of . Gas-Liquid Chromatographic Study of Molar Heats of Evaporation (Al-Dhahir and Swan)	645	$\text{Na}^+ - \text{Mg}^{2+}/\text{Cl}^-$ and $\text{Na}^+ - \text{Ca}^{2+}/\text{Cl}^-$ , Ion-Exchange Equilibria of, from Concentrated Solution (Dave and Trivedi)	1136
Molten Salts, Complex Formation in : Thermodynamics of Association Equilibria of Single and Mixed Ligand Complexes : A Review (Gupta, Verma and Gaur)	176	NaCl and KCl, Conductance of, in Sucrose + Water, Glucose + Water and Urea + Water Mixtures at Different Temperatures (Mohanty and Das)	1190
Molybdenum, A New Sensitive and Selective Reagent for Extraction of Trace Amount, in iso-Amyl Alcohol and Photometric Determination (Bag, Chakrabarti and Goswami)	713	Naphthalene-Benzonic Acid Eutectic, Structure of Faceted (Bassi, Sharma and Goswami)	968
Molybdenum, Binuclear Oxofluoro Complex of Quinquevalent (Chakravarti, Bera and Bharadwaj)	990	Neodymium(III) Complexes, Stability Constants and Thermodynamic Parameters of, with Mandelic, Cinnamic and Phenylacetic Acids : A Polarographic Study (Khan and Mahajan)	996
		Ni(II), Electrode Kinetics of the Polarographic Reduction of, in the Presence of Increasing Concentrations of L-4-Hydroxyproline and L-Tryptophan (Khatri and Singh)	897

Ni(II) Ethylacetoacetate, Mixed Ligand Complexes of, with Schiff Bases, Synthesis and Characterization (Arora and Misra) ..	32	Benzimidazole (Mishra, Singh and Singh) ...	622
Nickel Chloride, Some Reactions of, in N, N-Dimethylformamide (DMF) (Tandon, Mishra and Mishra) ...	283	Nitrilotriacetic Acid and 3-Acetyl-4-hydroxy-6-methyl-2-pyrone, Compatability of, in the Coordination Sphere of Lanthanone Ions (Kadinan, Garg and Sing) ..	1247
Nickel(II) Complexes with Substituted Amino Benzothiazoles (Misra and Guru)	987	5-Nitrobenzimidazole, Complexes of, with Some Metal Ions (Mishra) ...	795
Nickel(II) Ion and Cobalt(II) Ion Catalysed, Kinetics of, Hydroxamic Acid Formation from Formic Acid (Jagdale, Salunkhe and Swami) ..	355	Nitrogen Enrichment, Role of Toxic Aromatic Compounds (Sen)	476
Nickel in Mineral Waters, Determination of: Separation of Nickel by Solvent Extraction and Cation-Exchange (Korkisch, Steffan and Staniek)	1331	Nitrogen Loss in Soils, Retarding Influence of Phosphates and Wheat-straw on, Treated with Ammonium Sulphate and Ammonium Nitrate (Verma)	473
Nickel(II)-Mono- and Diethanolamine Systems. Metal Ammine Formation in Solution. Part-XXIII (Bjerrum and Djurdjevic) .	1229	Nitrogen and Organic Carbon, Post-harvest Changes in the States of, in Soil Treated with Fertilizers and Pesticides for Growing <i>Raphanus sativas</i> (De and Laloraya)	470
Nickel, Separation of, by Solvent Extraction and Cation-Exchange Determination of Nickel in Mineral Waters (Korkisch, Steffan and Staniek) .	1331	Nitrones of Vanillin, Synthesis and Reduction of (Rai, Kumar, Singh, Krishan and Singh)	80
Nickel, Synthesis and Characterization of Mixed Ligand Complexes of (Arora and Misra)	98	3-( <i>p</i> -Nitrophenyl)-thiazolo-[2,3, <i>c</i> ][1,2,4]-triazepine Derivatives, Preparation, Synthesis and Mass Spectral Studies of (Alaka, Patnaik and Rout) ...	1168
Ninhydrin, Reaction of, with Aromatic Amines and Ureas (Ahmed, Ahmed and Alam) ...	806	Nitrosyl Chromium(I) Complexes, Thiocyanato Substituted (Maurya and Shukla) ...	340
Niobium(V), Potentiometric Determination of, in Presence of Tantalum in Non-Aqueous Media (Sharda and Shivahare) ..	906	Nitrosylation, Halogen Oxidation and, of Mixed Ligand Molybdenum and Tungsten Tricarbonyls (Tripathi, Srivastava, Pandey and Srivastava)	238
Niobium(V), Studies on the Coordination Polymer of, with 1,6-Dihydroxyphenazine (Shivahare and Sharda)	242	NMR Reagents, Search for New. Studies in Fluorinated 1,3-Diketones and Related Compounds. Part-XIV (Joshi, Pathak and Grover)	1072
Niobium(V) and Tantalum(V), Benzoic Acid Complexes of (Narula, Singh, Kapoor and Kapoor)	195	NMR Spectroscopy of Oriented Molecules and its Applications to Inorganic Chemistry (Khetrapal)	164
Niobium(V) and Tantalum(V), Preparation and Characterization of Naphthoxides of (Malhotra, Mathur, Mahajan and Chaudhry)	922	NMR Spectroscopy of Oriented Organoselenium Compounds (Khetrapal)	1276
Nitrato-Complexes of Y(III), La(III), Ce(III), Pr(III), Nd(III), Sm(III), Gd(III), Tb(III), Dy(III) and Ho(III) with 2-(2'-Pyridyl)		<sup>31</sup> P NMR Studies of the Reaction of (COD)-PtCl <sub>2</sub> with Tertiary Phosphines in Methanol (Goel and Goel) ...	141
		<i>cis</i> (NO <sub>2</sub> ), <i>trans</i> (N), <i>cis</i> (O) <i>bis</i> (aminocarboxylato) dinitrocobaltate(III) Ion, Optically Inversion of the (Ćelap, Aljancić and Janjić)	1255

Non-Faradaic Electrolysis to Faradaic Electrolysis, Transition of, by Change of Conditions (Palit and Ghosh) ...	759	Sulfur-Nitrogen Chelating Agents (Singh and Gupta) ...	793
M <sup>3+</sup> -Noradrenaline Systems, Thermodynamic Study of, in Aqueous Solutions (Chakrawarti, Vijayvargiya and Sharma) ..	734	Organotrithiocarbonates, Mercurimetric Determination of, and A Method for the Analysis of Mercaptans (Verma, Kumar, Butail and Singh) ...	811
Nucleic Acid, Metal Ion Interactions with the Constituents of. Part-I: Metal-Adenine Complexes (Bhattacharyya and Bhaduri) ..	919	Oriented Molecules, NMR Spectroscopy of, and its Applications to Inorganic Chemistry (Khetrapal) ..	164
"O"			
Oil/Water Emulsion Stabilized, Studies on the Interfacial Tension and Electrical Conductance of, by Lignosulphonate of <i>Eucalyptus teriticornis</i> (Malik, Srivastava, Chand and Jindal)	1053	Osmium Tetraoxide Catalyzed Oxidation, A Highly Efficient, of Sterically Hindered Olefins to Diols (Ray and Matteson) .	119
Optical Inversion of the <i>cis</i> (NO <sub>2</sub> ), <i>trans</i> (N), <i>cis</i> (O)- <i>bis</i> (Aminocarboxylato) Dinitrocobaltate(III) Ion (Čelap, Aljancić and Janjić)	1255	1,3,4-Oxadiazoles, Synthesis and Mass Spectral Studies of Some New (Bansal and Bhagchandani) ...	277
Organic Acids, An Indirect Method for the Iodometric Microdetermination of (Pateria and Verma)	1203	1,2,4-Oxadiazolines, Synthesis of, Having Antifungal Activity (Rai and Kaur) ..	1197
Organo Poly (aminium Phosphate)s, Characterization and Molecular Weight Determination of Some. Part V (Vyas, Oza and Sharma)	305	Oxalyldihydrazide : A New Reagent for Rapid Gravimetric Determination of Selenium (Baveja and Gupta) ...	1111
Organoantimony Compounds, Metal Derivatives of : Reactions of Anhydrous Chloride of B(III), V(III) and Sn(IV) with Aryl-antimony Compounds (Sharma, Dubey and Puri)	1031	Oxaporphine Alkaloid, A New Phenolic : Alkaloids of <i>Machilus glaucescens</i> Wight (Talapatra, Goswami and Talapatra)	1364
Organophosphonic Acids as Complexes. Part-II. Interaction of Ethylenediphosphonic Acid with Some Divalent Metal Ions (Palta, Dubey and Puri)	261	Oxazolones, Synthesis and Antifungal Activity of (Manrao, Sharma, Dhir and Kalsi)	901
Organoselenium Compounds, NMR Spectroscopy of Oriented (Khetrapal)	1276	Oxidation of <i>m</i> -Cresol, Kinetics and Mechanism of, by Vanadium(V) in Presence of Salicylic and Substituted Salicylic Acids in Dilute Perchloric Acid Medium (Srinivas, Subbaiah and Rao)	55
Organotellurium Complexes, Some Anionic (Srivastava and Srivastava) ...	1028	Oxidation of Glycollic Acid, Kinetics of, by Quinquevalent Vanadium in Sulphuric Acid Medium (Choudhary and Prasad) ...	638
Organotin (Aryl Azo) Benzoates, Formation of Unusual Molecular Complexes by Some (Majee and Chattopadhyay)	219	Oxidation of Isobutyl Alcohol, A Kinetic Study of, with Aqueous Iodine (Manglik and Sharma)	352
Organotin(IV) Derivatives of Diethylamino-methyl Ester of 2-Amino-1-cyclopentene-1-carbodithioic Acid : Metal Complexes of		Oxidation of Optically Active 3,4-Dihydroxy-phenylalanine by Optically Active Cobalt-(III) Complexes (Yoshikawa and Yamasaki)	1250
		Oxidation Potential of the Silver Chloride Electrode, The Standard, in Water-Ethylene Glycol Mixtures. A Simple Deviation Function to Summarize Data in Solvent Mixtures. Part-2 (Högfeldt) ...	1357
		Oxidation Studies. Part-XV : Ag(I)-Catalysis	

in Oxidation of Amines by Ce(IV) in Nitric Acid. A Kinetic Study (Rao, Sethuram and Rao) ...	1040	P and Fe Concentrations, Effects of, in the Medium on the Uptake and Distribution of Fe in Maize Plants ( <i>Zea Mays</i> L.) (Hernando and Garcia Lopez De Sa) ..	4
Oxidation of Substituted Benzaldehydes, Kinetics of, by $\text{KMnO}_4$ in Buffer Medium (Rao and Sundaram) ..	704	$^{32}\text{P}$ Tracer Investigation on Phosphorus Utilization by Soybean in Vertisol (Dwivedi, Sinha and Mahajan)	4
Oxidation of Substituted Mandelic Acids, Kinetics and Mechanism of, by Sodium N-Chlorobenzenesulphonamide (Jain and Banerji) ...	654	Palladium(II) and Platinum(IV), Extraction and Photometric Method for the Simultaneous Determination of, with Dibenzylidenethiocarbohydrazide (Pramanik and Das) ..	4
Oxidative Decarboxylation : Partial Synthesis of Aegiceradienol ( <i>nor</i> Echinocystadienol) (Sundaramaiah and Rao) ...	74	Palladium(II) and Ruthenium(III), Extractive Spectrophotometry of, with Phenanthraquinone Monothiosemicarbazone (Khasnis and Shinde)	
Oxidising Agent, Tetravalent Manganese as an (Rao and Sant) ...	1430	Palladium, Spectrophotometric Determination of, with Rubeanic Acid in Presence of Piperidine, Quinoline, $\alpha$ -Picoline and Collidine (Saha and Chakraborty) ..	11
Oximes, Hydrazones, Semicarbazones and Thiosemicarbazones, Studies on, as Ligands. Part-III : Some Divalent Metal Complexes of Benzil Semicarbazone (Mishra, Mohapatra and Panda) ...	836	Paper Electrophoretic Separation and Estimation of the Constituents of Pyrolusite and Indian Coin (Cupro-nickel) (Mukherjee and Devi) ..	5
Oximes, Reactions of Coordinated. Part-V : Reactions of Aluminium Isopropoxide on Some Cobalt(II) <i>Bis</i> -Chelates of <i>o</i> -Hydroxy Oximes (Rani, Pandeya and Singh) ..	235	Pd(II) and Pt(II) Complexes of, with Some Organic Ligands (Mishra) ..	4
3-Oxo-Glutaric Acid Dianilide, Studies on, Part-I : Acid-Base Properties (Zayed, Abou-Taleb and El-Morsy) ..	1013	Pd(II), $\gamma$ -Carbon Bonded Acetylacetonato Complexes of (Sahu and Mohapatra) ...	7
5-(2-Oxo-3-Indolinylidene)-3-Aryl-2,4-Thiazolidindiones—A New Class of Thioindigoid Dyes, Formation of. The Reaction of Isatin with Active Methylene Group (Lakhan, Bhargava and Prasad) ..	804	Peptide Models for the Metal-Binding Sites of Proteins and Enzymes (Sarkar) ..	14
Oxomolybdenum(V) and Oxomolybdenum Complexes of Some New Dithiocarbamates (Waraich, Gaur, Pandeya and Singh) ..	213	Pericarbonyl Lignans and Their Analogues, Synthesis of (Agnihotri, Pasarkar and Bagavant) ..	8
$\mu$ -Oxo <i>bis</i> [Oxoterachlororhenates(VI)], Synthesis and Characterisation of (Yatirajam and Kantam) ..	1287	Permeability Studies of Water and Ammonium Salt Solutions Through Soil Membrane (Blokhra, Chand and Sidhu) ...	
Oxovanadium(IV) and Gallacetophenone-oxime, Spectrophotometric Study of the Complexation Reaction between (Reddy, Rao and Reddy) ..	422	Pfeiffer Effect, the Deuterium Isotope Effect on, in Optically Lable Coordination Compounds (Kirschner and Gabay) ...	12
Oxygen, Chemisorption Kinetic Studies of, on $\text{V}_2\text{O}_5$ - $\text{Ti}_2\text{O}_3$ (De and Gadgil) ..	846	pH-Metric Studies on the Cooper Benzamido-thiosemicarbazide Complex (Ansari, Jain, Kaushik and Malik) ..	4
Oxymercuration, Steric Effects of : Oxymercuration-Demercuration of Taraxasteryl, Pseudo-Taraxasteryl and 19- <i>Epi</i> -Taraxasteryl Acetates (Majumder and Laha) ...	548	Pharmacologically and Microbiologically Active Thiocyanato and Oxalato Complexes, Synthesis of, of $\text{Fe}^{3+}$ , $\text{Co}^{3+}$ , $\text{Ni}^{2+}$ and $\text{Cu}^{2+}$ with 3-Phenylaminomethyl	



benzoxazolinone-2. Screening of Metal Complexes for Biological Activity. Part—IV (Bajpai and Shukla)	343	5,5'-( <i>p</i> -Phenylene- <i>bis</i> azo)-di-quinolin-8-ol, Polymeric Metal Complexes of (Banerjee and Dey)	991
Phenacyl Bromides ( <i>o</i> -Bromoacetophenones), Kinetics of Chromic Acid Oxidation of (Mohapatra and Khandual)	1162	<i>p</i> -Phenylene-di-Acrylyl- <i>Bis</i> -N-Phenyl (PAP-HA), Fumaryl- <i>Bis</i> -N-Phenyl (FPHA), Iso-phthalyl- <i>Bis</i> -N-Phenyl (IDHA) Hydroxamic Acids and Spectral and Magnetic Studies of Their Polymers with Mn(II), Fe(II), Co(II), Ni(II), Cu(II) and Zn(II) (Gandhi and Munshi)	1290
Phenols and Benzyl Alcohol, Viscosity B Coefficient of (Mandal and Sanyal)	803	Phenylmercury and Methylmercury Species, The Commulation of, on Alga (Stary, Kratzen and Prašilová)	1329
Phenols, Detection and Chromatographic Separation of, on Papers Impregnated with Ferric Hydroxide (Rawat, Muktawat and Singh)	1011	Phenylmercury(II) Compounds—II. Some Novel Three-Coordinate Phenylmercury(II) Complexes with Triazene-1-Oxides (Dutta and Satapathi)	332
Phenol, Methylation of, over Alumina in the Vapour Phase: Influence of Copper Sulphate (Krishnasamy, Subramaniam and Soundararajan)	1067	Phosphate and Organic Matter, Role of, in the Management of Lateritic Soils for Increasing Productivity (Ghosh)	457
Phenothiazine Derivatives, Carbon-13 NMR Signals of Some (Patra, Mitra and Mukhopadhyay)	660	Phosphate, Detection and Determination of, Using Monomethyl- <i>p</i> -Amidophenol as Reagent (Murty and Suryanarayana)	1113
Phenoxy Acetyl Acetophenone as an Analytical Reagent for Iron (Ambhore, Ilyas and Joshi)	691	Phosphate Fertilization in Alluvial Soils of Allahabad Division. Interrelation in Water Soluble P, Adsorbed P and Olsen's P (Misra and Pathak)	466
2-Phenoxy methyl-3-N-substituted Amino Carbonyl methyl-8-substituted 4(3H) quinoxalones, Synthesis of, as Anticonvulsant Agents. Studies on some Biologically Active quinoxalones (Shukla, Saxena and Misra)	1196	Phosphates and Wheat-straw, Retarding Influence of, on Nitrogen Loss in Soils Treated with Ammonium Sulphate and Ammonium Nitrate (Verma)	473
N-Phenyl-S-Chloro isothiocarbamoyl Chloride, Some Interesting Reactions of (Jadhav and Paranjpe)	1004	Phosphoric Acid, First Dissociation Constant of, at a Number of Temperatures (Ghosh and Ghosh)	745
I-Phenyl-3-methyl/phenyl-4-( <i>o</i> / <i>m</i> / <i>p</i> -substituted benzeneazo)-5-pyrazolones, I-Phenyl-3-( <i>o</i> / <i>m</i> / <i>p</i> -substituted anilic)-5-pyrazolones and 3-Methyl/phenyl-4-( <i>o</i> / <i>m</i> / <i>p</i> -substituted benzeneazo)-5-isoxazolones, Synthesis of Some New, as Possible Biological Agents (Mittal and Singhal)	711	Phosphorus Utilization by Soybean in Vertisol, <sup>32</sup> P Tracer Investigation on (Dwivedi, Sinha and Mahajan)	450
I-Phenyl-3-( <i>o</i> / <i>m</i> / <i>p</i> -substituted anilic)-5-pyrazolones, I-Phenyl-3-methyl/phenyl-4-( <i>o</i> / <i>m</i> / <i>p</i> -substituted benzeneazo)-5-pyrazolones and 3-Methyl/phenyl-4-( <i>o</i> / <i>m</i> / <i>p</i> -substituted benzeneazo)-5-isoxazolones, Synthesis of Some New, as Possible Biological Agents (Mittal and Singhal)	711	Phosphorylation, Physico-chemical Studies on (Ghosh)	599
Phenyl-Tin Cleavage by Some Ferrocenyl Hydrazones (Patil, Kantak and Sen)	1300	Photochemical and Thermal Transformations of S-Benzoyl-O-alkyl Xanthates (Darji and Shah)	657
		Photochemical Reactions, The Relation Between Intensity and Velocity of (Bhagwat)	575
		Photochemical Reduction of Uranyl Ion with	

Tri- <i>p</i> -Tolylphosphine (Sandhu, Sidhu and Brar)	173	Platinum, Some Interesting Aspects of the Chemistry of (Bailar)	... 1214
Photochemical Splitting of Water and Reduction of Nitrogen and Carbon dioxide—Functional Approach to the Problem of Origin of Life (Bahadur and Ranganayaki)	480	Polarographic Determination of Stannous (tin) with Acrylic Acid (Rao and Singh)	... 1083
Photochemistry of Aqueous Anthraquinone-2-Sulfonate Solution (Roy, Bhattacharya and Aditya)	... 585	Polarographic Reduction Mechanism, on the, of Some Heterocyclic Compounds (Malik and Jain)	... 191
Photocorrosion (Cheng)	1393	Polarographic Reduction of 2-Aminobenzothiazoles (Malik and Jain)	... 558
Phthal-as-Eins, Synthesis and Studies of Some New (Chamoli, Rai and Gupta)	... 863	Polarographic Reduction of In(III) (Kapoor and Jain)	... 510
Physico-Chemical Studies of 1,5-Dimethyl- and 1,5-Diphenyl-1,3,5-pentanetriones with VO(II), Cr(III), Mn(II), Co(II), Ni(II), Cu(II) and UO <sub>2</sub> (II) (Kumar, Sharma, Sharma and Bachlas)	... 280	Polarographic Reduction of Ni(II), Electrode Kinetics of the, in the Presence of Increasing Concentrations of L-4-Hydroxyproline and L-Tryptophan (Khatri and Singh)	... 897
Physico-Chemical Studies of Some Mixed Ligand Complexes of Samarium(III) and Holmium(III) (Marathe and Munshi)	... 617	Polarographic Reduction of Progesterone, Studies on the (Srivastava and Kumar)	... 958
Physico-Chemical Studies on Phosphorylation (Ghosh)	... 599	Polarographic Reduction of Some 5,5-Dimethylcyclohexane-2-Benzothiazolylhydrazono-1,3-Diones and its 2-Methyl, 4-Methyl, 4-Methoxy, 4-Ethoxy Derivatives (Malik, Agrawal and Jain)	... 1060
Physico-Chemical Studies on Some Alkylmercapto and Alkylsulphonyl Phenols (Shanmuganathan, Durai and Sundaravelu)	... 52	Polarographic Reduction of Uranyl(II) in Presence of Some Disubstituted Pyridines (Sindhu, Pandeya and Singh)	... 895
Phytochemical Studies on <i>Eclipta alba</i> (Sikroria, Srivastava and Niranjana)	... 905	Polarographic Studies on Acidic Aminoacid Imines (N-Salicylidene-1-aspartic Acid and N-Salicylidene-1-glutamic Acid) (Chaturvedi and Kapoor)	... 210
Physico-chemical Studies on the Composition and Stability Constants of Zn(II), Cd(II) and Hg(II) DL-Valine Complexes (Saxena and Sharma)	... 635	Polarographic Study of Ternary Complexes in Solution : Complex Formation Between Copper(II) 2,2'-bipyridyl 1:1 Complex and Ligands Containing Oxygen and/or Nitrogen Donor Atoms as Secondary Ligands (Srivastava and Nigam)	... 251
Physicochemical Study of Some Transition Metal Complexes of Vanillin-Sulphanilate (Chakrawarti and Khanna)	... 828	Polarographic Study of Thorium(IV) and Uranyl(II) Complexes with DL-Ornithine Hydrochloride (Saxena and Bansal)	... 702
$\beta$ -Pinene, Isomerization of, in the Vapour Phase Over Alumina Catalyst : Influence of Partial Pressure of Nitrogen and Pyridine (Krishnasamy and Ratnasamy)	... 1151	Polyamino Chelates of Co(II), Ni(II), Cu(II), Zn(II) and Pd(II) using Cysteine as a Secondary Ligand (Sharma and De)	... 101
$\beta$ -Pinene, Transformations of, over Platinum-Alumina Catalyst. Part-I : Influence of Contact Time, Temperature and Platinum Concentration (Mathur, Krishnasamy and Chandrasekharan)	... 970	Polyethylene, Cosolvency Studies of. Part-I : Lowering of Cloud Temperature in Cosolvent Mixtures (Vidyarthi and Palit)	... 748
Platinum Metals, Complexes of Some, with 4-Amino-3,5-Dimercapto-1,2,4-Triazole (Roy and Mishra)	... 797	Polydentate Ligands. I, Studies on Some (Mukkanti, Bhoon, Pandeya and Singh)	... 830

Polyethylene, Cosolvency Studies of. Part-II : Viscometric Studies in Different Cosolvent Media (Vidyarthi and Palit) ...	753	Alkylarylaminoacetyl-2-aminothiazoles and Benzimidazoles (Upadhyaya, Srivastava and Sharma) ...	1097
Polymeric Bipositive Metal Ion Complexes of Terephthalaldehyde <i>bis</i> -(isonicotinic acid hydrazone) (Singh, Maurya, Agarwala and Dey) ...	29	Pr <sup>3+</sup> and Nd <sup>3+</sup> , 4-(2-Pyridylazo) Resorcinol, A Sensitive Amperometric Reagent for Ultamicro Determination of (Lavale and Pitre) ...	965
Polymeric Metal Complexes of 5,5'-( <i>p</i> -Pheny- lene- <i>bis</i> azo)-di-quinolin-8-ol (Banerjee and Dey) ...	991	Prenyl and Prenyloxy Coumarins, Reactions and Rearrangements of. (Studies on Ruta- ceae. Part-III) (Banerji, Chatterjee, Ghoshal, Das, Sarkar, Bhattacharya and Shoolery) ...	145
Polymeric Metal Complexes, Spectral Studies of, with Schiff Bases of Terephthalalde- hyde and Hydrazides (Maurya, Dube and Agarwala) ...	1400	Progesterone, Studies on the Polarographic Reduction of (Srivastava and Kumar) ...	958
Polymerization of Methacrylamide Initiated by Ceric Ion-Malic Acid Redox System (Misra and Khatib) ...	1384	Propan-2-ol, Decomposition of, Over Chro- mite Spinel—Kinetic Studies (Krishnas- amy and Chokkalingam) ...	641
Polymetaphosphates Complex, of Strongly Electropositive Elements (Mehrotra, Vyas and Oza) ...	486	Proteins and Enzymes, Peptide Models for the Metal-Binding Sites of (Sarkar) ...	1400
Post-harvest Changes in the Status of Nitro- gen and Organic Carbon in Soil Treated with Fertilizers and Pesticides for Growing <i>Raphanus sativus</i> (De and Laloraya) ...	470	Protonation Constants and Thermodynamic Parameters of 3-Bromo-2-Hydroxy-5- Methylacetophenone, Its Oxime and <i>n</i> - Propylimine (Verma and Patel) ...	43
Potassium Bromate, Use of: Oxidation of Aldehydes (Samaddar and Banerjee) ...	905	Pyrano/Pyrido Benzothiophene Derivatives, Synthesis of. Part-I (Chatterjee and Sahai) ...	1372
Potassium Permanganate with Potassium Ferrocyanoide, The Reaction of, and Some Binary Mixtures in Presence of Fluoride Ions (Dessoki, Allam and Hammam) ...	1063	2-Pyrazolin-5-one Derivatives, Studies on (Mitra, Nayak and Mittra) ...	1005
Potential Antithyroid Agents. Part-II : Synthetic and Pharmacological Studies on Some N-Aryl-N'-2 (benzimidazolyl) thio- carbarnides and N-aryl-N'-benzenesulphonyl- thiocarbarnides (Upadhyaya and Srivas- tava) ...	808	6-Pyrazolo and 6-Isoxazolo-Benzoxazoles, Synthesis of Substituted, and Their Physiological Activity (Shankar, Rao, Mouli and Reddy) ...	1104
Potential Antithyroid Agents. Part-V : Syn- thetic and Pharmacological Studies on Some N-aryl-N'-benzoylthiocarbarnides (Upadhyaya and Srivastava) ...	767	-2-(3'-Pyridyl) Chromones and 3-Hydroxy-2- (3'-Pyridyl) Chromones, Synthesis of (Thakar and Joshi) ...	77
Potential Antineoplastic Agents: Synthetic and Pharmacological Studies on Some N-Aryl-N'-2(4-Phenyl-5-arylazothiazolyl) thiocarbarnides (Upadhyaya and Srivas- tava) ...	683	4-(2-Pyridylazo) Resorcinol, A Sensitive Amperometric Reagent for Ultramicro Determination of Pr <sup>3+</sup> and Nd <sup>3+</sup> (Lavale and Pitre) ...	965
Potential Local Anaesthetic Agents. Part-III :		Pyrolusite and Indian Coin (Cupro-nickel), Paper Electrophoretic Separation and Esti- mation of the Constituents of (Mukherjee and Devi) ...	984

"Q"

Quercetin and Myricetin, Selective Methyl- ation of (Chand, Maurya and Ray) ..	1001
---	------

4(3H) Quinazolinones, Synthesis of Some, as Potential Fungicides (Chaurasia and Sharma) ...	370
Quinazolones, Studies on Some Biologically Active. Synthesis of 2-Phenoxy methyl-3-N-substituted Amino Carbonyl methyl-8-substituted 4(3H) quinazolones as Anti-convulsant Agents (Shukla, Saxena and Misra) ...	1196

#### "R"

Radiation Stability of Organic Compounds, Yield of Molecular Hydrogen as a Criterion for the (Al-Dhahir) ...	632
<i>Raphanus sativas</i> , Post-harvest Changes in the Status of Nitrogen and Organic Carbon in Soil Treated with Fertilizers and Pesticides for (De and Laloraya) ...	470
Rare-Earth Metal Complexes of Sodium 2-[4-Amino-3(1,2,4-Triazolylazo)] Naphthol-4-Sulphonate, Stability Constants and Related Thermodynamic Functions of Some (Garg, Mukherjee, Garg and Singh) ..	1038
Rare Earths. Part—XCII: Chelating Tendencies of 1-Methoxy-2,4-Pentanedione (Martin, Moeller and Randall) ...	1232
Reactions Paths, MNDO Study of: Hydroboration of Organic Nitriles (Chadha and Ray) ...	204
Reactivity of Indian Rock Phosphates in Presence of Oxidative Degradation Products of Coal (Pathak) ..	899
Reactivity of Molybdenyl(V) Cation, Studies on, in the Environment of Diverse Anions in Presence of 5-Nitro 1,10-Phenanthroline as an Organic Base (Saha, Sikdar and Raychaudhuri) ...	723
Reagent for Rapid Gravimetric Determination of Selenium, A New: Oxaldihydrazide (Baveja and Gupta) ...	1111
Recent Advances in the Chemistry of Simple and Bi-metallic Alkoxides of Later Transition Elements (with particular reference to the '3d' series) (Mehrotra) ...	715
Redistribution Reactions Involving Lithium Aluminium Hydride and Lithium Tetraphenylaluminate (Ashby and Goel) ...	134

Reduction of the Azomethine Bond, Polarographic Studies on the, in Aryl Thiosemicarbazides and the Determination of Hammett Parameters (Malik, Upadhyaya, Jain and Sharma) ...	1057
Reductive Alkylation of 2-Methyl-1,4-Naphthaquinone (Menadione) at Mercury Pool Cathode (Misra, Jain and Yadava) ...	289
Relationships Between the Direction of Shifts in the Carbon-Oxygen Stretching Frequencies of Carboxylate Complexes and the Type of Carboxylate Coordination (Manhas and Trikha) ...	315
Relative Stability of Formate Complexes by Paper Electrophoresis (Mukherjee and Debi) ...	908
Relative Stabilities of Fe(III) Complexes, Effect of Substituents on the, of Substituted Salicylic Acids (Chattopadhyaya) ...	1416
Replacement Reactions on the Hydrated Sulphates, Characterisation of Some Solid Products Obtained by Carrying Out the, of Copper(II), Nickel(II) and Cobalt(II) Using Two Different Heterocyclic Ligands viz. Antifuran-2-Carboxaldoxime and 2-Pyrrolidone (Shukla, Singh, Bhargava and Narain) ...	620
Restricted Rotation. Part-IV: Determination of Barrier to Rotation Around Some Crowded C-C and C-N Bonds by Dynamic Nuclear Magnetic Resonance (Nasipuri, Daw, Banerjee and Gupta) ...	1379
Retarding Influence of Phosphates and Wheat-straw on Nitrogen Loss in Soils Treated with Ammonium Sulphate and Ammonium Nitrate (Verma) ...	473
L-Rhamnose, Kinetics of Oxidation of, by Vanadium(V) (Fadnis and Kulshrestha) ...	411
Rhenium, Spectrophotometric Determination of, with N-(4-Methoxy-Phenyl)- $\alpha$ -thiopicolinamide and Evaluation of the Stability Constant of the Complex Involved Therein (Bag and Chanda) ...	688
Role of Metal Ions in Reactions of dl-Camphorquinone with Monoamines (Mukhedkar, Rajgolkar and Mukhedkar) ...	295

Rutdecac, Studies on. Part-III : Reactions and Rearrangements of Prenyl and Prenyloxy Coumarins (Banerji, Chatterjee, Ghoshal, Das, Sarkar, Bhattacharya and Shoolery)

145

Ruthenium, Spectrophotometric Determination of, with Prochlorperazine Bismethanesulphonate (Gowda and Gowda)

1201

Ruthenocene Derivatives, A Study of the Behaviour of Some. Spectrometry of Transition Metal  $\pi$ -Complexes. Part-VII (Davis and O'Reardon)

... 1270

### "S"

Salicylanilide, Complexation of, with Some Metal Ions of Biological Interest (Sahai, Agrawal and Kushwaha)

853

Salicylanilide, Dithionon and Tryptophan, Stacked Ternary Complexes of, with Co(II), Ni(II) and Cu(II) (Sahai, Agrawal and Kushwaha)

.. 1121

Salicylic Acid, Stability of Complexes of Co(II), Ni(II) and Cu(II) with Esters of (Gupta and Pannu)

937

Samarium(III) and Holmium(III), Physico-Chemical Studies of Some Mixed Ligand Complexes of (Marathe and Munshi)

617

Saponins, Study of, from *Albizia lebbek* Benth Flowers (Varshney, Jain and Srivastava)

. 884

Saturation Extracts from Arid-Zone Field Soils Amended with Sewage Sludge, Infrared Spectroscopic Study of (Schaumberg, LeVesque-Madore, Sposito and Chang)

150

Schiff Bases of Veratraldehyde, Studies on (Rai, Kaur and Bhir)

. 416

Science Based on Symmetry (Chakraborty)

1

Sedimentation Characteristics of Sodium Bentonite Suspensions, Studies on the Flow and, in Presence of Electrolytes and Humic Acids (Gupta, Nandi, Mukhdeo and Guha)

998

Selective Microgram Detection of Iron(III) on Ion Exchange Resin Beads (Nabi, Siddiqui, Athar and Ahmad)

1200

Selenium, A New Reagent for Rapid Gravimetric Determination of. Oxalyldihydrazide (Baveja and Gupta)

1111

Selenium, A New Reagent System for Photometric Analysis of, in Complex Materials (Bhatt and Gupta)

888

Semicarbazones, Thiosemicarbazones, Hydrazones and Oximes, Studies on, as Ligands. Part-III : Some Divalent Metal Complexes of Benzil Semicarbazone (Mishra, Mohapatra and Panda)

836

Sensitive and Selective Reagent, A New, for Extraction of Trace Amount Molybdenum in iso-Amyl Alcohol and Photometric Determination (Bag, Chakrabarti and Goswami)

713

"Shaking Effect" on the Conductivities of Liquids (Resch, Gutman and Schauer)

130

Silicon and Copper, Application of Coordination Compounds of, in Fiber and Fiber Reinforced Plastic Materials (Bahl, Dhami, Seth, Manocha and Mathur)

1306

Silver(I), Extraction and Spectrophotometric Determination of, with 4-S-Benzyl-1-p-Chlorophenyl-5-Phenyl-2,4-Isothiobiuret (BPPTB) (Deshmukh)

401

Simple and Bimetallic Alkoxides, Recent Advances in the Chemistry of, of Later Transition Elements (with particular reference to the '3d' series) (Mehrotra)

715

Sodium-N-Alkyl/Dialkyl Dithiocarbamates, Determination of, by Reaction with 2,4-Dinitrobenzenesulphenyl Chloride and Alkalimetric Determination of Ammonium-N-Aryl Dithiocarbamates (Talegaonkar and Boparai)

108

Sodium 2-[4-Amino-3-(1,2,4-Triazolylazo)] Naphthol-4-Sulphonate, Stability Constants and Related Thermodynamic Functions of Some Rare-Earth Metal Complexes of (Garg, Mukherjee, Garg and Singh)

1038

Sodium Bentonite Suspensions, Studies on the Flow and Sedimentation Characteristics of, in Presence of Electrolytes and Humic Acids (Gupta, Nandi, Mukhdeo and Guha)

. 998

Sodium Carboxylates, Determination of, by Reaction with $\omega$ -Bromoacetophenone (Mukhiya, Talegaonkar and Boparai) ..	427	Spectrophotometric Determination of Ruthenium with Prochlorperazine Bis methanesulphonate (Gowda and Gowda) ...	1201
Sodium Soaps, Properties of Pure, of Saturated Fatty Acids (Sheth and Subrahmanyam) ...	860	Spectrophotometric Study of the Reaction of Chromium(VI) with Fluphenazine Hydrochloride (Gowda and Raj) .	1398
Soil Productivity, Integrated Nutrient Supply to Soil for (Raychaudhuri) ...	435	$\text{Sr}_2\text{MoCoO}_6$ and $\text{Sr}_2\text{MoNiO}_6$ , Heat Capacity and Thermodynamic Properties of (Gunjekar, Ramachandran and Keer)	743
Solid Products, Characterisation of Some, Obtained by Carrying Out the Replacement Reactions on the Hydrated Sulphates of Copper(II), Nickel(II) and Cobalt(II) Using Two Different Heterocyclic Ligands viz., Antifuran-2-Carboxaldoxime and 2-Pyrrolidone (Shukla, Singh, Bhargava and Narain) .	620	$\text{Sr}_2\text{MoNiO}_6$ and $\text{Sr}_2\text{MoCoO}_6$ , Heat Capacity and Thermodynamic Properties of (Gunjekar, Ramachandran and Keer) . .	743
Solid State Thermal Decomposition Characteristics of Some Metallo-Organic Compounds, A Study on. Part-I : Dehydration and Decarboxylation of Hydrated Calcium Salts of Pyridine Monocarboxylic Acids (Ghosh, Ray, Ray and Bandyopadhyay)	1034	Stabilisation of Molybdenyl Cations with 4,4'-Dimethyl 2,2'-Bipyridyl in Different Salt and Non-electrolytic Complexes (Saha, Mandal and Ghorai) ..	1124
Solubilities of Triethylamine and Water, Predicting the. Studies in Triethylamine-Water. Part-IV (Thangavel and Moolel) .	1044	Stability Constants and Related Thermodynamic Functions of Some Rare-Earth Metal Complexes of Sodium 2-[4-Amino-3-(1,2,4-Triazolylazo)] Naphthol-4-Sulphonate (Garg, Mukherjee, Garg and Singh)	1038
Solvent Extraction Studies on Thiocyanate Complexes of Zinc(II), Cadmium(II) and Mercury(II) (Singh, Singh and Tandon)	1338	Stability Constants of Copper(II) Complexes, Determination of, with Ethylenediamine and Acetyl Salicylate (Aspirinate) by Electrochemical Methods (Das, Dixit and Zutshi) .	700
Spectral and Magnetic Studies of Some Mixed Ligand Complexes of High Spin Cobalt(II) (Sankhla, Mathur and Misra)	893	Stability Constants of Fe(II), Co(II), Ni(II), Cu(II) and Cd(II) Complexes of 2,2'-Dipyridyl-2-Pyrimidylhydrazone (Deshmukh)	105
Spectral Studies of Polymeric Metal Complexes with Terephthalaldehyde and Hydrazides (Maurya, Dube and Agarwala) ...	1400	Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Chloro-2'-Methoxyaniline Complexes, Determination of, with $\text{La}^{3+}$ , $\text{Y}^{3+}$ , $\text{Nd}^{3+}$ , $\text{Dy}^{3+}$ and $\text{Gd}^{3+}$ (Mayadeo, Purohit and Hussain) ...	894
Spectrophotometric Determination of Aromatic Amines Using Catechol and Iodine (Sastry, Rao and Murthy)	1107	Stability Constants of 2-Hydroxy-1-Naphthalidene-2',6'-Dimethylaniline Complexes, Determination of, with $\text{La}^{3+}$ , $\text{Y}^{3+}$ , $\text{Pr}^{3+}$ , $\text{Nd}^{3+}$ , $\text{Dy}^{3+}$ and $\text{Gd}^{3+}$ (Mayadeo, Purohit and Hussain)	952
Spectrophotometric Determination of Dissociation Constants of Violuric Acid and Stability Constant of its Cu(II) Complex (Singh and Ghosh) .	939	Stability Constants of 2-Hydroxy-1-Naphthalidene-4'-Hydroxyaniline Complexes, Determination of, with $\text{Mg}^{2+}$ , $\text{Co}^{2+}$ , $\text{Ni}^{2+}$ and $\text{Cu}^{2+}$ (Mayadeo and Purohit) ..	955
Spectrophotometric Determination of Rhenium with N-(4-Methoxy-Phenyl)- $\alpha$ -thiopicolinamide and Evaluation of the Stability Constant of the Complex Involved Therein (Bag and Chanda) ...	688	Stability Constants of 2-Hydroxy-1-Naphthalidene-Sulphamethoxazole Complexes, Determination of, with $\text{Cu}^{2+}$ , $\text{Ni}^{2+}$ , $\text{Co}^{2+}$ , $\text{Zn}^{2+}$ and $\text{Mg}^{2+}$ (Mayadeo and Bhattacharjee) ...	896

Stability Constants of 2-Hydroxy-1-Naphthalidene-Sulphaphenazole Complexes, Determination of, with $\text{La}^{3+}$ , $\text{Y}^{3+}$ , $\text{Pr}^{3+}$ , $\text{Nd}^{3+}$ , $\text{Gd}^{3+}$ , $\text{Dy}^{3+}$ (Mayadeo and Bhattacharjee)	800	Sucrose, Transformation of: An Alternative Route for Amination (Sharma, Norula and Matthey)	385
Stability Constants of 2-Hydroxy-1-Naphthalidene-Sulphafurazole Complexes, Determination of, with $\text{La}^{3+}$ , $\text{Y}^{3+}$ , $\text{Pr}^{3+}$ , $\text{Nd}^{3+}$ , $\text{Gd}^{3+}$ , $\text{Dy}^{3+}$ (Mayadeo and Bhattacharjee)	1189	Sulfur-Nitrogen Chelating Agents, Metal Complexes of: Organotin(IV) Derivatives of Diethylaminomethyl Ester of 2-Amino-1-cyclopentene-1-carbodithioic Acid (Singh and Gupta)	793
Stability and Related Thermodynamics of Chelation of $\text{Zn(II)}$ with Thiodiacetic Acid (TDAA), Thiodipropionic Acid (TDPA), Iminodiacetic Acid (IDAA), Dithiodiacetic Acid (DTDAA) and Diglycollic Acid (DGA) (Dubey, Baweja and Puri)	1133	Sulphene, addition of, to Substituted Benzal-anilines (Singh, Kumar, Manrao and Kaur)	673
Stability of Complexes of $\text{Co(II)}$ , $\text{Ni(II)}$ and $\text{Cu(II)}$ with Esters of Salicylic Acid (Gupta and Pannu)	937	Sulphur and Nitrogen Heterocyclics, Synthesis on, Involving Rearrangement via Small Rings (Tilak)	815
Stannous (tin), Polarographic Determination of, with Acrylic Acid (Rao and Singh)	1083	Sulphurdioxide, A Field Test for the Detection and Semiquantitative Determination of, in Air and Water (Chaube and Gupta)	1106
Strontium Nitrate, Thermal Decomposition of Irradiated (Nair, Krishnan and James)	1147	Sulphur-Nitrogen Chelating Agents, Metal Complexes of: Transition Metal Complexes of the Esters of 2-Amino-1-cyclopentene-1-dithiocarboxylic Acid (Singh and Gupta)	244
Structure and Synthesis of Mukoline Mukalidine, Two New Carbazole Alkaloids from <i>Murraya koenigii</i> Spreng. (Ray, Bhattacharya and Chakraborty)	1369	Sustainable World Agriculture, Some Reflections on Ways to Bring About a Permanently (Balfour)	431
Structure in Solution as Obtained from UV Absorption and Circular Dichroism Spectroscopy: Formylcamphor Condensed with Diamines (Jensen)	1387		
1-Substituted 5-bromo-3-aryloxy acetyl hydrazono-2-indolinones, Synthesis of Some New, as Potential Antibacterial Agents (Sen Gupta and Rastogi)	1102	"T"	
2-(N-Substituted Carboxamidomethyl Thio)-Naphth [1,2-d] Oxazoles, Synthesis and Biological Activity of Some New. Part-V (Mahmoud, Abdel-Rahman and El-Sherief)	675	Taraxasterenes and Pseudo-Taraxasterenes, C-13 Nuclear Magnetic Resonance Spectroscopy of. Chemical Constituents of <i>Launaea nudicaulis</i> (Majumder and Laha)	881
1-Substituted-2-mercaptobenzoyl-4-phenylimidazoles, Biologically Active New (Ali and Saksena)	420	Taraxasteryl, Pseudo-Taraxasteryl and 19-Epi-Taraxasteryl Acetates, Oxymercuration-Demercuration of (Majumder and Laha).	548
N-(Substituted Phenoxy Acetamido) Phthalimides, Studies on Synthesis and Anthelmintic Activity of (Shukla, Agarwal and Rastogi)	779	Tartrazine, Some Ligational Aspects of: Its Binary and Ternary Lanthanide Complexes (Limaye and Saxena)	698
		Teaching Microchemistry in Industry versus Teaching in a University (Steyermark)	1213
		Technetium, Coordination Chemistry of, as Related to Nuclear Medicine (Srivastava and Richards)	1262
		Terephthalaldehyde bis-(isonicotinic acid hydrazone), Polymeric Bipositive Metal Ion Complexes of (Singh, Maurya, Agarwala and Dey)	29

Terephthaldehyde bis-(semicarbazone), Coordination Polymers of, with Some Bipositive Cations (Singh, Maurya, Agarwala and Dey) ...	1130	Barium Bis-Oxalato Diaquo Thallate(III) Monohydrate (Sagi, Ramana and Rao) ...	336
Ternary Complexes, A New Parameter is Astatistical Stabilization of (Bhattacharya and Patel) ...	1244	2-Thenoyl-, 5-Bromo-2-thenoyl- and 5-Nitro-2-thenoylamino Acid Derivatives and Their Antimicrobial Activity, Synthesis of Some (El-Naggar, Aboul-Enein and Makhlouf)...	783
Ternary Complexes-Influence of Oxalic Acid on Vanadium(V) Determination with 4-Sulpho-2-Aminobenzenethiol in Aqueous Solution (Chakrabarti) .	627	Thermal Decomposition of Irradiated Strontium Nitrate (Nair, Krishnan and James) ...	1147
Ternary Complexes, Polarographic Study of, in Solution : Complex Formation Between Copper(II) 2,2'-bipyridyl 1 : 1 Complex and Ligands Containing Oxygen and/or Nitrogen Donor Atoms as Secondary Ligands (Srivastava and Nigam) ...	251	Thermal Degradation of <i>p</i> -Anisic Acid-Formaldehyde Condensation Product (Patel, Patel and Patel) ...	1145
Ternary Complexes, Stacked, of Salicylanilide, Dithionon and Tryptophan with Co(II), Ni(II) and Cu(II) (Sahai, Agrawal and Kushwaha) ...	1121	Thermodynamic and Protonation Constants Parameters of 3-Bromo-2-Hydroxy-5-Methylacetophenone, Its Oxime and <i>n</i> -Propylimine (Verma and Patel) ...	43
Ternary Extraction and Photometric Estimation of Vanadium(V) with N-Cinnamoyl-N-Phenyl Hydroxylamine (N-CPHAmine) and Thiocyanate in Chloroform (Bag, Chatterjee, Chakrabarti and Chakraborty) ..	630	Thermodynamic Study of M <sup>+</sup> -Noradrenaline Systems in Aqueous Solutions (Chakrawarti, Vijayvargiya and Sharma)...	734
Terpenoids via Nickel Tetracarbonyl Induced Cyclisation, Synthesis of Some (Vig) ...	609	Thermodynamics of Ferrous-1,10-Phenanthroline in <i>t</i> -Butanol-Water and Glycerol-Water Media at 25° (Mandal, Bandyopadhyay and Aditya) ...	1390
Tetracycline and Oxytetracycline Drugs, Molecular Complexes of, with Nucleic Acid Bases and Aromatic Amino Acids (Lahiri and Basu) ...	941	Thermoosmosis in Membranes (Sanyal and Adhikari) ...	460
Tetrahydro- $\beta$ -Carboline Alkaloids, 3,4-Bond Cleavage of : Transformation of Venenatine and Rhazine to the Corresponding 2-Acylindole Derivatives (Banerji and Siddhanta) ...	542	Thiazolidinones as Potential Antibacterial Compound. Part-I (Desai, Astik and Thaker) ..	771
Tetravalent Manganese as an Oxidising and Decomposing Agent (Rao and Sant) ..	1430	Thiazolo[3,2- <i>a</i> ]quinazolines, Synthesis of Substituted (Gakhar, Kiran and Gupta) ...	666
Th(IV), Separation of, in Aqueous Glycine Medium by Cation Exchange Chromatography (Eusebius, Mahan and Ghose) ...	1412	Thiocarbamide as Dealkylating Agent : Debenzylation of Certain 2-S-Benzyl-1,5-diaryl-2,4-isodithiobiurets with Thiocarbamide (Jadhav and Paranjpe) ...	1003
Thallium(I), Cyclic Voltammetry of, in Different Supporting Electrolytes (Sindal, Mathur and Kapoor) ...	1313	Thiocyanate Complexes of Zinc(II), Cadmium(II) and Mercury(II), Solvent Extraction Studies on (Singh, Singh and Tandon) ...	1323
Thallium Oxalates, Some Studies on-VIII :		Thiocyanato and Oxalato Complexes, Synthesis of Pharmacologically and Microbiologically Active, of Fe <sup>+</sup> , Co <sup>+</sup> , Ni <sup>+</sup> and Cu <sup>+</sup> with 3-Phenylaminomethyl benzoxazolinone-2. Screening of Metal Complexes for Biological Activity. Part-IV (Bajpai and Shukla) ...	343
		Thiocyanato Substituted Nitrosyl Chromium(I) Complexes (Maurya and Shukla) ...	340
		Thioindigold Dyes, A new Class of—The	



Reaction of Isatin with Active Methylene Group. Part-I : Formation of 5-(2-Oxo-3-Indolinylidene)-3-Aryl-2,4-Thiazolidindiones (Lakhan, Bhargava and Prasad)	804	Transition Metal Complexes, Physicochemical Study of Some, of Vanillin-sulphanilate (Chakrawarti and Khanna)	828
Thiosemicarbazones, Hydrazones, Semicarbazones and Oximes, Studies on, as Ligands. Part-III : Some Divalent Metal Complexes of Benzil Semicarbazone (Mishra, Mohapatra and Panda)	836	Transition of Non-Faradaic Electrolysis to Faradaic Electrolysis by Change of Conditions (Palit and Ghosh)	759
Thorium(IV) and Uranyl(II) Complexes, Polarographic Study of, with DL-Ornithine Hydrochloride (Saxena and Bansal)	702	1,3,5-Triazines, On. Part-II. Synthesis of 2,4-Dithio-3,5-Diaryl-6-Phenylimino-Hexahydro-1,3,5-Triazines and 2,6-Dithio-3,5-Diaryl-4-Phenylimino-Hexahydro-1,3,5-Triazines (Pathe, Ambekar, Nimdeokar and Paranjpe)	670
Thorium, Solvent Extraction of, with Liquid Cation Exchanger (Versatic 10) (Ray and Modak)	911	Triazolo[3,4-b][1,3,4]thiadiazoles (Gakhar, Jain and Gupta)	900
Thorium(IV), Titrimetric Determination of, using N-(2-Hydroxyethyl ethylenediamine-triacetic Acid as Titrant and Pyrocatechol Violet as an Indicator (Maiwal and Srinivasulu)	395	Tricyclohexyl Tin Halides and Pseudohalides. Structural and Biocidal Activity (Awasthi, Bhattacharya and Verma)	264
Three Coordinate Phenylmercury(II) Complexes, Some Novel, with Triazene-1-Oxides. Phenylmercury(II) Compound -II (Dutta and Satapathi)	332	Triethylamine-Water, Studies in. Part-IV : Predicting the Solubilities of Triethylamine and Water (Ihangavel and Moolal)	1044
Titanium-Cyclopentadienyl Bond, Effect of Different Groups on Cyclopentadienyl Ring on the Stability of (Soni, Chanda, Sharma and Garg)	913	Tris-Trimethylene Diamine Co(III) Exchanged Amberlite-IRC-50, Ion Exchange Selectivity of Monovalent Ions in Aqueous and 50% Ethanol-Water Media towards (Sarkar and Das Kanungo)	358
p-Toluenesulphonylated Casein, Hydrogen Ion Equilibria on (Malik, Tyagi and Mittal)	423	Triortho-periodate Tetracobaltic(III) Acid, Studies on. Part-II (Baker, Mukherjee and Chaudhuri)	930
Toxic Aromatic Compounds, Role of, in Nitrogen Enrichment (Sen)	476	Triphenylphosphine Oxide, Interaction Products of, with Some Organotin Halides (Bajpai and Bajpai)	1090
Training and Research in Analytical Chemistry : An Interdisciplinary Science (Mehrotra)	1209	Triphenylsiloxy and Diphenylsiloxy Derivatives of Boron (Bhardwaj and Srivastava)	300
Transformations of $\beta$ -Pinene Over Platinum-Alumina Catalyst. Part-I : Influence of Contact Time, Temperature and Platinum Concentration (Mathur, Krishnasamy and Chandrasekharan)	970	DL-Tryptophan, Potentiometric Determination of Dissociation Constants of, in Different Aquo-Organic Solvents (Saxena and Sharma)	413
Transition and Non-Transition Metal Complexes, Study of, with 3-Amino-2-Benzoyl-benzofuran (Huggi, Halli and Hiremath)	1017	Tryptophan, Salicylanilide and Dithionon, Stacked Ternary Complexes of, with Co(II), Ni(II) and Cu(II) (Sahai, Agrawal and Kushwaha)	1121
Transition Metal $\pi$ -Complexes, Mass Spectrometry of. Part-VII : A Study of the Behaviour of Some Ruthenocene Derivatives (Davis and O'Reardon)	1270		

"U"

Ultrasonic Study of the Elastic Constants of Some Ancient and Mediaeval Indian Coins (Prakash and Murthy)	591
---	-----

Ultraviolet Radiation, Effects of, on Amino Acid Composition of Single Cell Protein (Pandey and Tiwari) ...	686	Vanadium(V), Ternary Extraction and Photometric Estimation of, with N-Cinnamoyl-N-Phenyl Hydroxylamine (N-CPHAMine) and Thiocyanate in Chloroform (Bag, Chatterjee, Chakrabarti and Chakraborty) ...	63
Unsaturated Centre of Arylidene-2-amino-benzoxazole, Cyclocondensation and Cyclo-addition Reactions on the (Osman, Badar, Mahmoud and Hezien) ..	763	Vanadyl Porphyrin Complexes of TLC, Behaviour of (Chakraborty and Bhatia) ...	115
Unusual Molecular Complexes, Formation of, by Some Organotin (Aryl Azo) Benzoates (Majee and Chattopadhyay) ...	219	Vanillin-sulphanilate, Physicochemical Study of Some Transition Metal Complexes (Chakrawarti and Khanna) ...	82
Uranyl Ion, Equilibrium Study of the Mixed Complexes of, with 3,5-Dinitrosalicylic as Primary and Some Substituted Carboxylic Acids as Secondary Ligands (Shelke) ..	833	Venenatine and Rhazine, Transformation of, to the Corresponding 2-Acylindole Derivatives. 3,4-Bond Cleavage of Tetrahydro- $\beta$ -Carboline Alkaloids (Banerji and Siddhanta) ...	54
Uranyl Ion, Photochemical Reduction of, with Tri- <i>p</i> -Tolylphosphine (Sandhu, Sidhu and Brar) ..	173	Veratraldehyde, Studies on Schiff Bases of (Rai, Kaur and Dhir) ...	41
Uranyl(II), Polarographic Reduction of, in Presence of Some Disubstituted Pyridines (Sindhu, Pandeya and Singh) ...	895	Versatile Catalyst—Characterization of Alumina (Krishnasamy and Ratnasamy) .	83
“V”		Vibrational Analysis of Glyoxal- $\text{h}_2$ - $\text{d}_2$ and $\text{hd}$ (Natarajan, Kolandaivelu and Savariannandam) ...	115
Vanadium in Alloy Steel and Ores, Photometric Methods of Determination of: Complex Formation of Vanadium(V) with Salicylhydroxamic Acid in MIBK (Bag, Chatterjee, Chakrabarti and Chakraborty) ...	1085	Violuric Acid and Stability Constant of its Cu(II) Complex, Spectrophotometric Determination of Dissociation Constants of (Singh and Ghosh) ...	93
Vanadium(V), Complex Formation of, with Salicylhydroxamic Acid in MIBK. Photometric Methods of Determination of Vanadium in Alloy Steel and Ores (Bag, Chatterjee, Chakrabarti and Chakraborty) ...	1085	Viscometric Studies in Different Cosolvent Media. Cosolvency Studies of Polyethylene. Part-II (Vidarthi and Palit) ...	75
Vanadium(V) Determination, Ternary Complexes-Influence of Oxalic Acid on, with 4-Sulpho-2-Aminobenzenethiol in Aqueous Solution (Chakrabarti) ..	627	Viscosity $\beta$ Coefficient of Phenols and Benzyl Alcohol (Mandal and Sanyal) .	80
Vanadium(V), Extraction and Spectrophotometric Determination of, as Mixed Ligand Complexes of Various Hydroxyamides and Thiocyanate (Jha and Mishra) ..	1177	Vulcanization of Natural Rubber. Influence of Hydrofuramide on Sulphenamide Acceleration System (Banerjee and Chakravarty) .	40
Vanadium, Spectrophotometric Determination of, with 2:2'-Diamino-Diphenyl-Disulphide in Strong Acid Solution (Bag, Basu and Chatterjee) ...	787	“W”	
		Water and Ammonium Salt Solutions, Permeability Studies of, Through Soil Membrane (Blokhra, Chand and Sidhu) ...	63
		Ways to bring About a Permanently Sustainable World Agriculture, Some Reflections on (Balfour) ...	431
		World Agriculture, Some Reflections on Ways to Bring About a Permanently Sustainable (Balfour) ...	431

<i>Wrightia mollissima</i> , Chemical Investigation of (Sharma, Srivastava, Mahesh, Saluja and Sharma) ..	810	Acid (TDAA), Thiodipropionic Acid (TDPA), Iminodiacetic Acid (IDAA), Dithiodiacetic Acid (DTDAA) and Diglycollic Acid (DGA) (Dubey, Baweja and Puri) ..	1133
"X"			
Xanthates, Determination of, by Reaction with 2,4-Dinitrobenzenesulphenyl Chloride (Talegaonkar and Bopara) ...	109	Zinc, Cadmium and Mercury, Complexes of Divalent, with Substituted Salicyl Hydrazines. Inorganic Coordination Complexes. Part-V (Tewari, Bajpai, Misra, Shukla and Misra) ...	891
"Y"			
Y(III), La(III), Ce(III), Pr(III), Nd(III), Sm(III), Gd(III), Tb(III), Dy(III) and Ho(III), Nitrate-Complexes of, with 2-(2'-Pyridyl) Benzimidazole (Mishra, Singh and Singh) ...	622	Zinc(II), Cadmium(II) and Mercury(II), Solvent Extraction Studies on Thiocyanate Complexes of (Singh, Singh and Tandon) ..	1338
Yield of Molecular Hydrogen as a Criterion for the Radiation Stability of Organic Compounds (Al-Dhahir) ..	632	Zinc, Determination of, with Cupric Ion-Selective Electrode and its Analytical Application in Fertilizers (Ilcheva, Polianova, Adewuyi and Bozadziev) ..	1352
Yohimbane Skeleton, A Novel Synthesis of: Synthesis of 17,18-Dimethoxy-15,16,17,18,19,20-hexadehydroyohimbane by Condensation of an Indolylethylbromide with 3(2H)-isoquinolone (Pandey, Tiwari and Tandon) ...	532	Zinc(II), Extraction of, as Chloride by High Molecular Weight Amine, Amberlite LA-1 (De, Ray and Parhi) ..	1334
"Z"			
Zn(II), Cd(II) and Hg(II) DL-Valine Complexes, Physico-Chemical Studies on the Composition and Stability Constants of (Saxena and Sharma) ..	635	Zinc(II), Mixed Ligand Complexes of (Padhy and Patel) ...	992
Zn(II), Ni(II), Cu(II) and Co(II), Synthesis and Structural Studies of the Complexes of, with 3-Aryloxymethyl-4-aryl-5-mercapto-1,2,4-triazoles (Bahel, Dubey, Nath, Tripathi and Srivastava) ...	1127	Zinc(II), Mixed Ligand Complexes of, with Dibasic Acids and Nitrogen Donor Ligands (Padhy and Patel) ...	1182
Zn(II), Stability and Related Thermodynamics of Chelation of, with Thiodiacetic Acid (TDAA), Thiodipropionic Acid (TDPA), Iminodiacetic Acid (IDAA), Dithiodiacetic Acid (DTDAA) and Diglycollic Acid (DGA) (Dubey, Baweja and Puri) ..	1133		
		Book Review	
		Experimental Organic Chemistry by P. R. Singh, D. S. Gupta and K. S. Bajpai, Tata McGraw-Hill, 1981, vol. 1, xvii+267 (Rs. 27.00); vol. 2, xix+378 (Rs. 27.00) R. K. Bansal ..	
		1115	
		Obituary	
		Obituary of Prof. Priyadarshan Ray D. Banerjee ...	
		1205	

Access. No. 85240 1493  
 Date 12.2.87

## **ESSAY CONTEST ON "SYNTHETIC FOOD"**

An essay contest on "Synthetic Food" is being organized under the auspices of the Indian Society of Agricultural Chemists for the undergraduate and postgraduate (including Research Scholars) students.

Candidates desirous of participating in the contest should send two copies of their article in English with a certificate from their respective Head of the Department/Institution that he is a bonafide student of the Department/Institution. The cash prizes that will be awarded to the successful students will be financed by Dr. A. T. McPherson, Maryland, U.S.A., a renowned Food Scientist and will be as follows .

Ist Prize (one)	:	Rs. 500/-
IInd Prize (two)	:	Rs. 200/- each
IIInd Prize (three)	:	Rs. 100/- each

Copies of the essay not exceeding 2000 words in duplicate should reach **Dr. S. K. De, Hony. General Secretary, Indian Society of Agricultural Chemists, Department of Chemistry, University of Allahabad, Allahabad-211 002** by August 31, 1983 along with an entry fee of Rs. 5/- in the form of I.P.O. payable to the Indian Society of Agricultural Chemists, Allahabad.

# The Indian Chemical Society

## Office-bearers (1981)

### President

S. M. Mukherji, D.Sc., Ph.D., F.N.A.

### Vice-Presidents

( Who have filled the office of the President )

P. K. Bose, D.Sc., F.N.A.  
R. N. Chakravarti, D.Sc., F.R.S.C., F.A.S., F.N.A.  
R. D. Desai, D.Sc., F.R.S.C., F.I.Sc., F.N.A.  
Sukh Dev, M.Sc., Ph.D., F.N.A.  
N. R. Dhar, D.Sc., Dres.Sc., F.R.S.C., F.N.A.  
T. R. Govindachari, Ph.D., F.N.A.

R. C. Mehrotra, D.Phil., Ph.D., D.Sc.(Lond.),  
F.R.S.C., F.N.A.  
J. N. Mukherjee, C.B.E., D.Sc., F.A.S.B., F.N.A.  
P. Ray, D.Sc., F.N.A.  
Jagdish Shankar, M.S., Ph.D., A.R.S.C., F.N.A.

### Vice-Presidents

D. Banerjee, Ph.D., D.Sc., F.N.A.Sc., C.Chem.,  
F.R.S.C. (Lond.)  
Arun K. Dey, M.Sc., D.Phil., D.Sc., F.N.A.Sc.

(Mrs) K. K. Rohatgi-Mukherjee, M.Sc., D.Phil.  
M. N. Sastri, D.Sc., Ph.D.  
President of the Waltair Branch(Ex-officio)

### Hony. Secretary

S. K. Talapatra, M.Sc., Ph.D., P.R.S., C.Chem., F.R.S.C.

### Hony. Treasurer

D. P. Chakraborty, Ph.D., D.Sc.

### Hony Editors

M. M. Chakrabarty, Ph.D. (L'pool), F.R.S.C.

K. C. Joshi, M.S., Ph.D., F.R.S.C.

H. L. Nigam, Ph.D. (Lond.), F.N.A.

### Members of the Council

R. P. Agarwala, M.Sc., Ph.D (Lond.), D.I.C (Lond.)  
A. K. Banerjee, Ph.D.  
Avijit Banerji, M.Sc., Ph.D., P.R.S.  
H. L. Bhatnagar, M.Sc., Ph.D.  
P. K. Bhattacharya, M.Sc., Ph.D.  
D. K. Chattoraj, Ph.D., D.Sc.  
Jyotirmoy Das, M.Sc., Ph.D.  
S. K. De, M.Sc., M.Sc. (Bot.), D.Phil., D.Sc.,  
F.N.A.Sc., F.I.S.A.C.  
N. S. Gnanapragasam, M.A., M.Sc., Ph.D.  
Y. K. Gupta, M.Sc., D.Phil., F.N.A.Sc.  
R. C. Kapoor, D.Phil., D.Sc.  
P. L. Majumdar, M.Sc., Ph.D., P.R.S.  
H. C. Mishra, M.Sc., Ph.D., F.R.S.C.  
J. P. Mittal, M.Sc., Ph.D.

Harigopal Mukherjee, M.Sc., Ph.D.  
K. N. Munshi, M.Sc., D.Phil., D.Sc.  
U. Muralikrishna, M.Sc., Ph.D.  
N. S. Narasimhan, B.Sc., Ph.D.  
T. Navaneeth Rao, M.Sc., Ph.D.  
H. K. Saha, M.Sc., P.R.S., Ph.D., D.Sc., F.R.S.C.  
Anil K. Sengupta, M.Sc., Ph.D.  
Pasupati Sengupta, M.Sc., Ph.D., F.N.A.  
Sp. Shanmuganathan, M.Sc., Ph.D., C.Chem.,  
F.R.S.C., M.A.C.S., F.C.S., F.T.N.A.Sc.  
V. R. Shastry, M.Sc., Ph.D.  
N. N. Siddhanta, M.Sc., Ph.D.  
A. Syamal, M.Sc., Ph.D., D.Sc., F.R.S.C., F.I.C.  
S. C. Tripathi, Ph.D.  
I. P. Varshney, M.Sc., Ph.D., D.Sc., F.R.S.C.

### Board of Associate Editors

Samir K. Banerji, M.Sc., D.Phil., F.N.A.Sc.  
(Mrs.) Rama Basu, M.Sc., D.Phil.  
J. N. Chatterjee, D.Sc., D.Phil., F.R.S.C., F.N.A.Sc.,  
F.N.A.

Pijush Kanti Das, M.Sc., D.Phil.  
Ashok G. Datta, M.Sc., D.Phil.  
S. K. De, M.Sc., M.Sc. (Bot.), D.Phil., D.Sc.,  
F.N.A.Sc., F.I.S.A.C.

S. M. Khopkar, M.Sc., Ph.D.  
Samir C. Lahiri, M.Sc. (Tech.), D.Phil.  
Sujit C. Lahiri, M.Sc., Ph.D., D.Sc., P.R.S.  
P. L. Majumdar, M.Sc., Ph.D., P.R.S.  
Guru Nath Mukherjee, M.Sc., Ph.D.  
Harigopal Mukherjee, M.Sc., Ph.D.  
Bidyut Baran Nath, M.Sc., D.Phil.

S. K. Patil, M.Sc., Ph.D.  
T. Navaneeth Rao, M.Sc., Ph.D.  
M. N. Sastri, D.Sc., Ph.D.  
Sp. Shanmuganathan, M.Sc., Ph.D., C.Chem.,  
F.R.S.C., M.A.C.S., F.C.S., F.T.N.A.Sc.  
M. P. Singh, M.Sc., D.Phil., D.Sc.  
Prithwi Raj Singh, M.Sc., Ph.D.  
Rajendra Pal Singh, M.Sc., Ph.D.  
Ramesh Pratap Singh, M.Sc., M.Tech., Ph.D.  
T. N. Srivastava, M.Sc., Ph.D., D.Sc., F.N.A.Sc.  
R. K. Suri, M.Sc., A.I.C.  
A. Syamal, M.Sc., Ph.D., D.Sc., F.R.S.C., F.I.C.  
(Mrs.) Bani Talapatra, D.Sc.  
S. C. Tripathi, Ph.D.  
K. V. Viswanathan, M.Sc., Ph.D.

### Executive Secretary

I. Kar, Ph.D.

### Executive Editor

S. K. Roy, Ph.D., D.I.C.

### Auditor

S. Mitra, B. Com., F.C.A., A.C.I.S (Lond.)

# INDIAN CHEMICAL SOCIETY

92, ACHARYA PRAFULLA CHANDRA ROAD

CALCUTTA-700 009.

## Price of Publications :

1. Catalogue of Physical-Chemical Standard Substances ;  
Reprinted from Pure and Applied Chemistry, Vol. 29(4), 601-16 (1972)  
(With the kind permission of the International Union of Pure and Applied Chemistry.)  
Price : Rs. 4 (Inland, inclusive of postage)  
Rs. 8 (Foreign, inclusive of postage by Surface Mail).
2. Acharya Prafulla Chandra Ray : Life and Achievements  
by Prof. N. R. Dhar :  
Price : Rs. 5 (Inland, inclusive of postage)  
Rs. 10 (Foreign, inclusive of postage by Surface Mail).
3. Reflections on Chemical Education by Prof. N. R. Dhar :  
Price : Rs. 12.50 (Inland, inclusive of postage)  
Rs. 25.00 (Foreign, inclusive of postage by Surface Mail).
4. History of Chemistry in Ancient & Medieval India  
Edited by Prof. P. Ray :  
Price : Rs. 30.00 (Inland, inclusive of postage)  
Rs. 75.00 (Foreign, inclusive of postage by Surface Mail).
5. Abstracts of XX-ICCC (held at Calcutta in December 1979)  
Price : Inland : Rs. 325.00 (Inclusive of Regd. postage  
by Surface Mail)  
Foreign : Rs. 425.00 or U. S. \$ 50.00 (Inclusive of Regd.  
Air Mail postage).
6. Calcutta (A Tourist Guide Book)  
Price : Inland : Rs. 15.00 (Inclusive of postage)  
Foreign : Rs. 25.00 (Inclusive of postage by Surface Mail).

Annual Subscription (inclusive of postage) for the Journal of the Indian Chemical Society (for Non-Fellows) for 1983 :

Rs. 400.00 (Inland) ; U.S. \$ 125.00 (Foreign)

Air Postage Extra. (May be paid in equivalent Indian Rupee)

Back issues of the Journal of the Indian Chemical Society and Indian Journal of Applied Chemistry (upto 1972 ; discontinued from January, 1973) may be available, for which separate enquiries are to be made for availability and rates.

I. Kar  
Executive Secretary







**INDIAN CHEMICAL SOCIETY**  
**92, ACHARYA PRAFULLA CHANDRA ROAD**  
**CALCUTTA-700 009.**

**Price of Publications :**

1. **Catalogue of Physical and Chemical Standard Substances ;**  
**Reprinted from Pure and Applied Chemistry, Vol. 29(4), 601-16 (1972)**  
**(With the kind permission of the International Union of Pure and Applied Chemistry.)**  
Price : Rs. 4 (Inland, inclusive of postage)  
Rs. 8 (Foreign, inclusive of postage by Surface Mail).
2. **Acharya Prafulla Chandra Ray : Life and Achievements**  
**by Prof. N. R. Dhar :**  
Price : Rs. 5 (Inland, inclusive of postage)  
Rs. 10 (Foreign, inclusive of postage by Surface Mail).
3. **Reflections on Chemical Education by Prof. N. R. Dhar :**  
Price : Rs. 12.50 (Inland, inclusive of postage)  
Rs. 25.00 (Foreign, inclusive of postage by Surface Mail).
4. **History of Chemistry in Ancient & Medieval India**  
**Edited by Prof. P. Ray :**  
Price : Rs. 30.00 (Inland, inclusive of postage)  
Rs. 75.00 (Foreign, inclusive of postage by Surface Mail).
5. **Abstracts of XX-ICCC (held at Calcutta in December 1979)**  
Price : Inland : Rs. 325.00 (Inclusive of Regd. postage  
by Surface Mail)  
Foreign : Rs. 425.00 or U. S. \$ 50.00 (Inclusive of Regd.  
Air Mail postage).
6. **Calcutta (A Tourist Guide Book)**  
Price : Inland : Rs. 15.00 (Inclusive of postage)  
Foreign : Rs. 25.00 (Inclusive of postage by Surface Mail).

**Annual Subscription (inclusive of postage) for the Journal of the Indian Chemical Society (for Non-Fellows) for 1983 :**

**Rs. 400.00 (Inland) ; U.S. \$ 125.00 (Foreign)**

**Air Postage Extra. (May be paid in equivalent Indian Rupee)**

**Back issues of the Journal of the Indian Chemical Society and Indian Journal of Applied Chemistry (upto 1972 ; discontinued from January, 1973) may be available, for which separate enquiries are to be made for availability and rates.**

**I. Kar**  
**Executive Secretary**